

# Geotechnical Engineering Report

## Sub-District H Water Main Extension Project – Phase 2

Creektrace, Indian Trace, and John Miller Roads, and Lauren and Joann Lanes  
Alexandria, Campbell County, Kentucky

Project No. N1095342

May 21, 2010 (revised)

March 4, 2010 (original)

### Prepared for:

Northern Kentucky Water District  
Erlanger, Kentucky

### Prepared by:



A Terracon COMPANY

Cincinnati, Ohio

Offices Nationwide  
Employee-Owned

Established in 1965  
terracon.com

# Terracon

Geotechnical ■ Environmental ■ Construction Materials ■ Facilities



May 21, 2010 (revised)  
March 4, 2010 (original)

Northern Kentucky Water District  
2835 Crescent Springs Road  
P.O. Box 18640  
Erlanger, Kentucky 41018

Attn: Mr. John Scheben  
Design Supervisor  
TEL: 859-426-2717  
FAX: 859-578-7893  
Email: jscheben@nkywater.org


**Re: Geotechnical Engineering Report  
Proposed Sub-District H Water Main Extension Project – Phase 2  
Creektrace, Indian Trace, and John Miller Roads, and Lauren and Joann Lanes  
Aelxandria, Campbell County, Kentucky  
HCN/Terracon Project Number: N1095342**


Dear Mr. Scheben:

H.C. Nutting, A Terracon Company (HCN) has completed the geotechnical engineering services for the above referenced project. This study was performed in general accordance with our proposal number PN1090210, dated March 10, 2009. This report presents the findings of the subsurface exploration and provides geotechnical recommendations concerning earthwork during the installation of water main. This report has been prepared as requested by NKWD and Viox & Viox to more specifically address the geotechnical aspects along the waterline alignment for incorporation onto the project plans.

We appreciate the opportunity to be of service to you on this project. If you have any questions concerning this report, or if we may be of further service, please contact us.

Sincerely,  
**H.C. NUTTING, A TERRACON COMPANY**

  
Bobby Daita, P.E.  
Senior Staff Engineer

  
Jess A. Schroeder, P.E.  
Senior Principal - Office Manager

H.C. Nutting, a Terracon Company 611 Lunken Park Drive Cincinnati, Ohio 45226  
P [513] 321 5816 F [513] 321 0294 www.terracon.com

## TABLE OF CONTENTS

	Page
EXECUTIVE SUMMARY .....	I
1.0 INTRODUCTION.....	1
2.0 PROJECT INFORMATION.....	1
3.0 SUBSURFACE CONDITIONS .....	2
3.1 TYPICAL PROFILE .....	2
3.2 GROUNDWATER .....	3
4.0 RECOMMENDATIONS FOR DESIGN AND CONSTRUCTION.....	3
4.1 GEOTECHNICAL CONSIDERATIONS.....	3
4.2 CONSTRUCTION ASSESSMENT .....	4
4.3 TRENCH EXCAVATIONS.....	6
4.4 UNDERCUT AND REPLACEMENT.....	7
4.5 BEDDING AND BACKFILL.....	8
4.6 DRAINAGE AND GROUNDWATER CONSIDERATIONS.....	10
4.7 CREEK CROSSINGS .....	10
4.7.1 OPEN CUT EXCAVATIONS .....	11
4.7.2 HORIZONTAL DIRECTIONAL DRILLING.....	11
4.8 SLOPE STABILITY CONSIDERATIONS .....	12
4.7 THRUST BLOCK RECOMMENDATIONS.....	12
5.0 GENERAL COMMENTS .....	16

### Appendix A – Field Exploration

- Exhibit A-1 Site Vicinity Maps
- Exhibit A-2 through A-18 Test Boring Location Plans
- Exhibit A-20 through A-44 Test Boring Logs
- Exhibit A-45 Field Exploration Description

### Appendix B – Supporting Information

- Exhibit B-1 - Laboratory Testing
- Exhibit B-2 through B-4 - Laboratory Plots

### Appendix C – Supporting Documents

- Exhibit C-1 - General Notes
- Exhibit C-2 - Unified Soil Classification
- Exhibit C-3 - General Notes – Rock Properties

## Geotechnical Engineering Report

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY  
May 21, 2010 ■ HCN/Terracon Project No. N1095342



### EXECUTIVE SUMMARY

A geotechnical study was performed for the Phase 2 portion of the proposed sub-district H water main extension project in Campbell County, Kentucky. The project involves installation of an 8-inch water main along Creektrace Road, Indian Trace Road, Joann Lane, John Miller Road, and Lauren Lane in Alexandria, Campbell County, Kentucky. Based on a review of provided plan and profile drawings the proposed water main invert elevations are generally about 4 to 14 feet below existing site grade, with the typical depth being about 4 to 8 feet.

A total of 25 test borings were performed as part of the exploration program. The typical subsurface profile at the test borings consisted of existing fill and/or natural cohesive soils underlain by weathered shale and limestone bedrock.

The following key geotechnical related items are identified:

- Open cut excavations will penetrate a variety of materials ranging from medium stiff cohesive soil to very stiff to hard cohesive soil and weathered shale bedrock. The shale bedrock is typically soft to very soft in bedrock classification terms. There are also hard limestone layers within the bedrock formation and in residual soil zones above the bedrock.
- Materials anticipated at pipe invert elevation are generally expected to be compact cohesive materials and occasionally, bedrock. One boring (CR-1) found fill to extend below design invert elevation. A small undercut/replacement scheme is recommended there to improve pipe support conditions (and uniformity). Based on review of the project plans, the use of pipe restraints and thrust blocks along portions of the alignment is proposed.
- The planned creek crossings can be performed by open cut or trenchless methods. These installations will most likely penetrate into weathered bedrock at most if not all locations.

Close monitoring of the construction operations discussed herein will be critical in achieving the design subgrade support. We recommend that HCN/Terracon be retained to perform construction testing and inspection for this project.

This summary should be used in conjunction with the entire report for design purposes. It should be recognized that details were not included or fully developed in this section, and the report must be read in its entirety for a comprehensive understanding of the items contained herein. The section titled **GENERAL COMMENTS** should be read for an understanding of the report limitations.

**GEOTECHNICAL ENGINEERING REPORT  
SUB-DISTRICT H WATER MAIN EXTENSION PROJECT- PHASE 2  
CREEKTRACE, INDIAN TRACE, AND JOHN MILLER ROADS AND  
LAUREN AND JOANN LANE  
ALEXANDRIA, CAMPBELL COUNTY, KENTUCKY  
HCN/TERRACON PROJECT NO. N1095342  
MAY 21, 2010 (REVISED)  
MARCH 4, 2010 (ORIGINAL)**

**1.0 INTRODUCTION**

A geotechnical engineering report has been completed for the Phase 2 portion of the proposed Sub-District H Water Main Extension project in Alexandria, Campbell County, Kentucky (Exhibit 1). A total of twenty five borings including twelve borings along Creektrace Road (designated at CR-1 to CR-12), six borings along Indian Trace Road (designated as IR-1 to IR-6), two borings along John Miller Road (designated as JM-1 to JM-2), three borings along Joann Lane (designated as JL-1 to JL-2), and two borings along Lauren Lane (LL-1 and LL-2) were drilled to approximate depths of 3.3 to 14 feet below existing grades. Logs of the borings along with site vicinity map, boring location plans are included in Appendix A of this report.

The purpose of these services is to provide information and geotechnical engineering recommendations related to:

- subsurface soil conditions
- groundwater conditions
- earthwork recommendations
- slope stability considerations
- pipe subgrade recommendations

**2.0 PROJECT INFORMATION**

Item	Description
Project Purpose	Water main extension – Phase 2
Project Alignment	Creektrace Road, Indian Trace Road, Joann Lane, John Miller Road, and Lauren Lane
Total Project Length	24,848 feet (12167+ 7892 +789 +2100+1900)
Pipe Invert Elevations	Creektrace Road – 4.5 to 10 feet Indian Trace Road – 4 to 11 feet John Miller Road – 4 to 14 feet Joann Lane – 4 to 8 feet Lauren Lane – 6 to 8 feet
Creek Crossings	Creektrace Road – near Sta. 81+00 (Pond Creek) Indian Trace Road – near Sta. 1+50, near Sta.31+00 (Pond Creek)

## Geotechnical Engineering Report

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY

May 21, 2010 ■ HCN/Terracon Project No. N1095342



Existing Grades	<ul style="list-style-type: none"><li>• Grades generally slope down along Creektrace Road and vary approximately between El. 670 and El. 525 feet</li><li>• Indian Trace Road has rolling terrain with grades approximately varying between El. 525 and El. 490 feet</li><li>• Grades generally increase along Joann Lane and vary between El. 500 and El. 585 feet</li><li>• Grades along John Miller Road vary between El. 525 and El. 565 feet</li><li>• Lauren Lane has grades varying between El. 525 and El. 535 feet.</li></ul>
-----------------	--

### 3.0 SUBSURFACE CONDITIONS

#### 3.1 Typical Profile

The surficial material at test borings consisted of topsoil, asphalt or concrete pavement with granular base, existing fill, and natural soils. Topsoil with thickness varying between 3 and 12 inches was encountered at the surface of five test borings. Asphalt pavement with thickness varying between 4 and 6 inches was encountered at four test borings and concrete pavement with thickness varying approximately between 3 and 7 inches was encountered at three test borings. The thickness of granular base underlying the asphalt/concrete pavement varied between 3 and 6 inches. Existing fill was encountered at surface at eight test boring locations. Underlying these surficial materials were the natural overburden soils. Weathered shale and limestone bedrock was encountered below the overburden soils at eight test borings. The following table summarizes the encountered subsurface conditions:

Description	Approximate Depth to Bottom of Stratum (feet)	Material Encountered	Consistency/Density
Existing Fill <sup>1</sup>	1 to 14	Sandy lean clay, Lean Clay, Fat Clay, Poorly Graded Gravel, Sandy Silt	Soft to Very Stiff (cohesive) Loose to Medium Dense (granular)
Natural Overburden Soils	2.5 to 12.5	Sandy Lean Clay, Silty Clay, Lean Clay, Fat Clay	Medium Stiff to Hard
Bedrock <sup>2</sup>	Bottom of Boring	Weathered Brown Shale with Limestone	Soft (rock hardness)

## Geotechnical Engineering Report

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY  
May 21, 2010 ■ HCN/Terracon Project No. N1095342



1. Test boring CR-1 was terminated within existing fill at 14 feet. At all other borings, fill thickness was less than 5 feet. It appears that the existing fill was placed with some compactive effort. However, we have not reviewed any records showing its controlled placement as structural fill.
2. Bedrock was encountered at seven test borings between depths of 1 and 12.5 feet. Based on the elevation at which bedrock was encountered, a review of published literature suggests that Ordovician Age bedrock along the various roads within Phase 2 of the project are the Southgate and McMicken members which belong to the Latonia formation under the Kope group. In general Kope bedrock members are rich in shale containing up to 80 percent of shale and 20 percent of limestone.

Conditions encountered at each boring location are indicated on the individual boring logs. Stratification boundaries on the boring logs represent the approximate location of changes in soil types; the transition between materials may be gradual. Details for each of the borings can be found on the boring logs in Appendix A of this report.

### 3.2 Groundwater

Groundwater conditions were noted during and after drilling operations at each of the test boring locations. During drilling, groundwater was encountered at three test boring locations (CR-7, IR-2, and JL-3) between depths of 0.5 and 7.5 feet below existing grades. The shallow groundwater was generally perched water within existing fill. No groundwater or “dry” conditions were reported during and after drilling operations at the remaining of the test boring locations. A “dry” condition is reported when no water is observed in the borehole or on the sampling tools. Boreholes were backfilled immediately upon completion and patched at the roadway surface for safety reasons. Therefore, long-term groundwater conditions at the site were not obtained.

Perched water may be encountered at shallow depths within the existing fill, at the fill/natural soil interface or near the soil/bedrock interface, etc. Groundwater level fluctuations occur due to seasonal variations in the amount of rainfall, runoff and other factors not evident at the time the borings were performed. Therefore, groundwater levels during construction or later may be higher or lower than the levels indicated on the boring logs. The possibility of groundwater level fluctuations should be considered when developing the design and construction plans for the project.

## 4.0 RECOMMENDATIONS FOR DESIGN AND CONSTRUCTION

### 4.1 Geotechnical Considerations

Based on the provided water main alignment plans prepared by Viox & Viox, the proposed water main inverts are generally about 4 to 8 feet below existing site grades along the various roads planned within Phase 2. Deeper invert elevations of up to 14 feet are planned near creek

## Geotechnical Engineering Report

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY  
May 21, 2010 ■ HCN/Terracon Project No. N1095342



crossings. Based on the results of the test borings and the anticipated water main subgrade elevations, we anticipate that trench excavations in the area of the test boring locations will typically penetrate a combination of existing fill or medium stiff to hard natural cohesive residual soils. Weathered shale and limestone bedrock may be encountered at pipe subgrade elevation at some locations along Creektrace Road, Indian Trace Road, and John Miller Road. Based on the project plans, the use of pipe restraints and thrust blocks along portions of the alignment is proposed. The use of thrust blocks/restraints are typically shown where horizontal and/or vertical grade changes cannot be accommodated by the inherent flex of the waterline. Recommendations for the use of thrust blocks/restraints or lowering the waterline into bedrock where stability is a concern has been provided for evaluation by the waterline designer and NKWD. Additional details regarding general water main construction are provided in the following sections, followed by a station-by-station overview of our recommendations.

### 4.2 Construction Assessment

We anticipate excavations could likely be completed using conventional trench box support or conventional trench box support incorporated with laid-back slopes (open-cut and cover). Open-cut and cover techniques (with/without trench box support) can be considered, provided that precautions are taken to protect any existing utilities, structures, roadways, or creeks within the construction area. The following table shows the proposed invert elevations and anticipated bearing materials at the soil test boring locations.

Boring Number	Approx. Ground Elevation (ft.)	Estimated Depth to Bedrock below Existing Grade (ft.)	Approx. Invert Elev. / Depth (ft.)	Anticipated Material @ Pipe Invert (approx.)
<b>Creektrace Road</b>				
CR-1	668	>9	663 / 5	Very Stiff Existing Fill
CR-2	648	>9	638 / 2	Very Stiff Lean Clay
CR-3	624	2.5 <sup>1</sup>	619 / 5	Weathered Shale
CR-4	596	>9	592 / 4	Very Stiff Lean Clay
CR-5	580	>9	576 / 4	Very Stiff Lean Clay
CR-6	564	>9	558 / 6	Stiff Lean Clay
CR-7	548	>9	542 / 6	Stiff Lean Clay/ Very Stiff Fat Clay
CR-8 <sup>2</sup>	528	12.5 <sup>1</sup>	524 / 4	Very Stiff Lean Clay
CR-9	538	1	533 / 5	Weathered Shale
CR-10	527	>10	521 / 6	Stiff Lean Clay
CR-11	557	>9	553 / 4	Very Stiff Lean Clay
CR-12	558	>9	549 / 9	Very Stiff Lean Clay
<b>Indian Trace Road</b>				
IR-1 <sup>2</sup>	520	>9	515 / 5	Very Stiff Fat Clay
IR-2	500	>9	495 / 5	Very Stiff Fat Clay



**Geotechnical Engineering Report**

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY  
 May 21, 2010 ■ HCN/Terracon Project No. N1095342



Boring Number	Approx. Ground Elevation (ft.)	Estimated Depth to Bedrock below Existing Grade (ft.)	Approx. Invert Elev. / Depth (ft.)	Anticipated Material @ Pipe Invert (approx.)
IR-3 <sup>2</sup>	493	7.5 <sup>1</sup>	485 / 8	Weathered Shale
IR-4	512	>9	506 / 6	Stiff to Very Stiff Fat Clay
IR-5	507	>9	503 / 4	Very Stiff Lean Clay
IR-6	526	5 <sup>1</sup>	520 / 6	Weathered Shale

**Joann Lane**

JL-1	501	7.5 <sup>1</sup>	495 / 6	Hard Lean Clay
JL-2	534	>9	530 / 4	Medium Stiff to Very Stiff Lean Clay
JL-3	584	>9	580 / 4	Very Stiff Lean Clay

**John Miller Road**

JM-1 <sup>2</sup>	524	>9 <sup>1</sup>	515 / 9	Stiff to Very Stiff Lean Clay
JM-2	562	2.5 <sup>1</sup>	556 / 6	Weathered Shale

**Lauren Lane**

LL-1	528	>9	525 / 3	Very Stiff Fat Clay
LL-2	534	>9	529 / 5	Very Stiff Lean Clay

1. Residuum with limestone fragments and layers may be encountered above this bedrock depth
2. Near creek crossing.

In general, the placement of the water main, hydrants, and valves within the soil profile will not add significant load on the underlying bearing material. However, it is important to have uniform and proper support, and to maintain proper line and grade of the pipe to prevent the pipe from becoming over-stressed in hoop compression or bending. Based on the proposed invert elevations and subsurface conditions encountered at the test borings, we anticipate the bearing material at invert elevations should generally consist of stiff to very stiff cohesive soils and/or weathered shale and limestone bedrock. Some of the cohesive materials within excavation limits may comprise "residuum" which can contain hard limestone fragments and layers.

Very stiff existing cohesive fill soils were encountered near the pipe invert elevation at test boring CR-1 along Creektrace Road. The test boring extended to a boring termination depth of 14 feet which is approximately 9 feet below the pipe invert elevation. Based on a review of the obtained fill samples, it is our opinion that the existing fill was placed with some compactive effort. However, we have not reviewed any records showing the fill placement and compaction in a controlled manner (with QA/QC testing). It is therefore recommended that at least one foot of existing fill below the pipe invert elevation be undercut and replaced with engineered fill (or flowable fill if within the roadway easement).

In general, we anticipate stiff to very stiff natural cohesive soils at proposed pipe invert elevations. The highly plastic fat clays encountered at test borings are moisture sensitive and can be subjected to significant strength loss upon wetting. During construction, any soft to medium stiff soils encountered at pipe subgrade elevation (due to their exposure to inclement weather) may need

## Geotechnical Engineering Report

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY  
May 21, 2010 ■ HCN/Terracon Project No. N1095342



undercutting to expose suitable stiff to very stiff bearing materials. The undercut area may be brought up to design bearing levels with engineered fill as discussed in the Bedding and Backfill section of this report. The contractor should adhere to all installation specifications provided by the water main manufacturer. Thrust blocks and pipe restraints should also be provided along the water main alignment in accordance with manufacturer's specifications.

Pavement rehabilitation consisting of asphalt pavement patching and installation of soldier beams along the edge of the road on the downslope side was observed near Sta. 11+00 along Creektrace Road. Test boring CR-2 performed in the vicinity of this rehabilitated area encountered very stiff natural cohesive soils to the explored boring depth of 9 feet below existing grade. Considering the encountered soil conditions and observed rehabilitation of the apparent instability, it is our opinion that the proposed water main should be installed along upslope side of the road as currently shown on the plans in this area of the alignment. We have not identified any obvious areas of potential instability along the roadways within other portions of this phase of the project; however, we recommend that the water main generally be installed along the upslope side of the road when feasible.

The water main alignment is generally located within the roadways or adjacent to the roadways within Phase 2 except near creek crossings, where the alignment juts out away from the road. In general, it is recommended that the alignment of the water main always be along the upslope side of the road.

### 4.3 Trench Excavations

All temporary cut slopes required for water main installation should be made in accordance with OSHA Safety Regulations. It is anticipated that the depths of excavation will range between about 4 and 14 feet below existing grades. We anticipate that trench boxes or other types of temporary shoring will be utilized within the existing roadway and in close proximity to existing physical features.

Where sufficient space is available, the excavation slope can be laid back, in accordance with OSHA criteria. It is recommended that temporary excavation slopes be examined periodically to evaluate any potential destabilizing effects.

Trench excavations can be as deep as 14 feet below existing grade. It is our opinion that the overburden soils/weathered shale bedrock encountered in the test borings can typically be excavated using conventional rubber tired backhoes and/or trackhoes. If excavations penetrate into bedrock (such as along Creektrace Road, Indian Trace Road, and John Miller Road), the rock formation could include hard limestone layers in perhaps 20 to 25% (+/-) of the mass. Hard limestone layers can also be encountered with residual clay overlying the weathered shale zone. No rock coring was performed as part of this study. The weathered bedrock typically breaks along the natural horizontal bedding planes. Excavation of narrow trenches in the shale and limestone can be difficult. A rock trencher or line drilling may be used to define the edge of the

## Geotechnical Engineering Report

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY  
May 21, 2010 ■ HCN/Terracon Project No. N1095342



trench, with the rock being excavated with a large hydraulic hoe. Breaking with percussion tools will likely be advantageous to excavate some zones of limestone. The Contractor's "responsible person" should also establish a minimum lateral distance from the crest of the slope or excavation for all spoil piles and vehicles. Likewise, the contractor's "responsible person" should establish protective measures for exposed slope faces.

We recommend that the engineering specifications state that the contractor will be responsible for the temporary shoring, bracing, and sheeting design, if required, and the protection of roadways, utilities, and any other structures. We recommend that a pre-condition survey of all-adjacent structures and roadways be performed prior to the start of construction.

Unless visually apparent, the location of private underground utilities and other manmade physical features cannot be easily identified during our site reconnaissance. Oftentimes, the subsurface soils adjacent to these underground features, whether in-use or abandoned, may not represent the subsurface conditions encountered in the soil test borings. Unless notified in advance, identifying and/or locating the presence of underground manmade features such as leach fields, septic systems, irrigation piping, drainage tile, vaults, privies, cisterns, wells, shelters, private utilities, etc. is beyond our scope of services. Interviewing individual home and property owners for the purposes of identifying/locating known underground physical features is also outside the range of our site reconnaissance activities.

These manmade features are often used to collect, store, and/or provide an avenue for transporting water/ liquid waste. Similarly, underground utilities bedded in granular soils and utility trenches that may be inadequately backfilled tend to "hold" water. As a result, the soils in the area of the underground features tend to be saturated or near saturation, resulting in "weakening" of the soil structure and increased susceptibility to failure if exposed and/or disturbed. Due to the proposed construction being within a developed area where manmade disturbances are likely, we recommend that the contractor carefully evaluate their excavation methods so that properly laid back slopes or sheeting/shoring/trench boxes can be readily utilized during construction. Additionally, if any suspicious surficial features (i.e., depressions, mounds, etc.) and/or seepage within the excavation are observed, further excavation should stop and the owner and geotechnical engineer should be notified.

### 4.4 Undercut and Replacement

The bottom of the excavations for the water main pipes and valves/hydrants must be stable so that no excessive settlement will occur. In some of the proposed pipe subgrade areas where existing fill or soft to medium stiff natural soils may be encountered or if excessive water seepage is encountered during excavation, the on-site cohesive fill or natural soil is highly susceptible to strength loss when wet and disturbed. Therefore, a limited undercut and replacement (or other stabilizing measures) could be required. The undercut depth or other stabilization measures can be decided in field during construction based on the encountered conditions. The undercut of existing fill or soft to medium stiff natural soils should expose at least stiff to very stiff natural

## Geotechnical Engineering Report

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY

May 21, 2010 ■ HCN/Terracon Project No. N1095342



cohesive soils. However, in the vicinity of test boring CR-1, due to the relatively deep existing fill it is recommended that a partial undercut of existing fill extending to one foot below the pipe should be performed. The partial undercut of existing fill along Creektrace Road (near CR-1) should be replaced with engineered granular fill like Dense Graded Aggregate (DGA) or with flowable fill if the pipeline is within the roadway easement; however, this does not preclude the use of proper bedding below and around the pipe. Soft to medium stiff soils may be encountered at pipe subgrade due to weather conditions during construction. Any such soft soils should be undercut to expose at least stiff to very stiff material. It is anticipated that these undercuts will be shallow (up to 1 to 2 feet). The shallow undercuts can be replaced with new engineered fill. Granular fill is recommended for its ease of compaction in narrow trenches using a vibratory compactor.

### 4.5 Bedding and Backfill

It is recommended that pipe bedding material be used and consist of a “shaped” surface of well-graded sand and/or gravel (with a maximum size less than 1 inch) with no more than 10 percent passing the No. 200 sieve. This granular material should not be less than 3 inches in thickness below the bottom of the pipe and should extend to a height of at least 12 inches above the top of the pipe. This material should be placed in 4 to 6 inch thick lifts and be uniformly compacted to at least 95 percent (in non-pavement areas) of the Standard Proctor maximum dry density (ASTM D 698) at 2 percent below to 3 percent above of the optimum moisture content. Some pipe manufacturers provide backfill requirements pertaining to their particular brand or type of pipe. If this is the case for this project, the manufacturer's specifications could be adopted. If the manufacturer's specifications vary significantly from those provided herein, HCN/Terracon should be contacted to evaluate the appropriateness of the compaction specifications.

Within the roadway right-of-way, the trench backfill above the bedding fill should be in compliance with Northern Kentucky Water District and current KTC specifications. Flowable concrete fill (low strength mortar) should be used within roadway easements to reduce construction time and minimize the risk of future trench settlement. It is our experience that reduced labor costs associated with flowable concrete backfill make the use of this material an attractive alternative. Flowable concrete is a semi-rigid backfill, typically stronger than the soil that was removed.

In areas that are not within the roadway right-of-way, the remaining backfill above the granular zone previously described, can consist of on-site cohesive soils or high quality granular material unless specified otherwise. Excavated overburden soils from the water main alignment areas appear to be suitable for reuse as trench backfill, though likely wet of optimum. Some moisture adjustment may be necessary to achieve specified compaction. Material classifying as fat clay, such as the cohesive material encountered in majority of the test borings, should be placed wet of optimum to reduce swell potential. Any proposed backfill material (on-site or imported) should be properly tested to determine its optimum moisture content and moisture-density characteristics and pre-approved before use. All backfill material should be free of organics, topsoil, debris and other deleterious substances. Maximum solid particle size (rock fragments, etc.) should be less than about 4 inches in any dimension. If utility trenches are backfilled with relatively clean granular

**Geotechnical Engineering Report**

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY  
 May 21, 2010 ■ HCN/Terracon Project No. N1095342



material, they should be capped with at least 18 inches of cohesive fill in non-pavement areas to reduce the infiltration and conveyance of surface water through the trench backfill. The following table provides property requirements for structural fill:

Fill Type <sup>1</sup>	USCS Classification	Acceptable Location for Placement
Lean clay	CL (LL < 40)	All locations and elevations
Fat clay <sup>2</sup>	CH (LL > 50)	In non-structural fill areas
Well graded granular	GW <sup>3</sup>	All locations and elevations
On-site soils	Varies	The on-site soils, including the existing uncontrolled fill material, typically appear suitable for use as fill. Appropriate moisture conditioning may be needed.

1. New structural fill should consist of approved materials that are free of organic matter and debris. Frozen material should not be used, and fill should not be placed on a frozen subgrade. A sample of each material type should be submitted to the geotechnical engineer for evaluation.
2. Delineation of fat clays should be performed in the field by a qualified geotechnical engineer or their representative.
3. Similar to KTC DGA stone or crushed limestone aggregate or granular material such as sand, gravel or crushed stone containing less than 8% low plasticity fines.

**Compaction Requirements for Backfill**

Fill Lift Thickness	8-inches or less in loose thickness 6-inches or less if hand compaction equipment used
Compaction Requirements <sup>1</sup> (Pavement Areas)	Top 12" beneath pavement areas, 100% of the materials maximum Standard Proctor dry density (ASTM D 698); structural fill beneath the top 12" should be compacted to at least 98% of the materials maximum Standard Proctor dry density (ASTM D 698)
Compaction Requirements (Landscape Areas)	95% of maximum Standard Proctor dry density (ASTM D 698) provided long-term plans do not include paving or a structure in these areas
Moisture Content - Cohesive Soil (Low Plasticity)	Within ±3% of optimum moisture content (OMC) as determined by the Standard Proctor test at the time of placement and compaction

## Geotechnical Engineering Report

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY

May 21, 2010 ■ HCN/Terracon Project No. N1095342



---

Moisture Content - Granular Material<sup>2</sup>

Within  $\pm 2\%$  of OMC

---

1. Should the results of the in-place density tests indicate the specified moisture or compaction limits have not been met, the area represented by the test should be reworked and retested as required until the specified moisture and compaction requirements are achieved.
2. Specifically, moisture levels should be maintained low enough to allow for satisfactory compaction to be achieved without the cohesionless fill material pumping when proofrolled.

---

All materials to be used as structural fill should be tested in the laboratory to determine their suitability and compaction characteristics.

### 4.6 Drainage and Groundwater Considerations

Water should not be allowed to collect in the bottom of excavation or on prepared subgrades of the construction area. Undercut or excavated areas should be sloped toward one corner to facilitate removal of any collected rainwater, groundwater, or surface runoff.

Three existing ponds are identified along the west side of Joann Lane. The proposed waterline alignment along Joann Lane is along the east side of the road. The invert elevation of the pipeline is generally at or below the pool elevations of these ponds. However, based on the presence of relatively impermeable cohesive soils at test borings and observed groundwater conditions during drilling, we do not anticipate significant seepage within the excavations (away from creek crossings). Any encountered water can most likely be removed with typical sump and pump methods. The presence and handling of groundwater should be further evaluated at the time of construction.

### 4.7 Creek Crossings

A total of three creek crossings are identified within Phase 2 of the project. The proposed water main alignment along Creektrace Road and Indian Trace Road crosses Pond Creek at Sta. 81+00 and Sta. 31+00, respectively. John Miller Road and Joann Lane intersect Creektrace Road and Indian Trace Road near the Pond Creek crossing, respectively. Additionally, Indian Trace Road crosses an existing creek at Sta. 1+50. At creek crossings, the water main alignment deviates from the roadway alignment and traverses the creek away from the roadway.

The invert elevations of the water main near the creek crossings are up to 10 feet below the existing grade at El. 507 near Creektrace Road and El. 480 near Indian Trace Road. Test borings CR-8, IR-3, JM-1, and JL-1 were drilled near the Pond Creek crossings along Creektrace Road and Indian Trace Road. Based on our test borings, highly weathered shale bedrock with limestone (or stiff clay soil) is anticipated at the proposed invert elevations. The water main near the creek crossing can be installed either by open cut excavations or directional drilling construction techniques. Additional details are provided below.

## Geotechnical Engineering Report

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY  
May 21, 2010 ■ HCN/Terracon Project No. N1095342



### 4.7.1 Open Cut Excavations

Based on the offset of the water main alignment near the creek, open cut excavations should be feasible. Based on the channel width and depth of Pond Creek, it is our opinion that dewatering using cofferdams and sandbags will be required to provide a relatively dry construction environment during the installation of the water main. We recommend that the contractor be required to perform dewatering inside of the cofferdams and sandbags using conventional sump and pump methods in cohesive soils, or deep well system in sandy soils during excavation. Deep wells should consist of pumps set in individual casings or sono tubes, and generally include 12 to 18 inches of crushed aggregate at the bottom of well for stability. Proper dewatering operations could also facilitate the excavation and fill placement activities for water main installation across Pond Creek.

We recommend that the dewatering contractor be given the entire responsibility for designing and implementing the dewatering system on a performance specification basis. Selection and design of means and methods to control groundwater should be the sole responsibility of the specialty contractor. However, the hydraulic efficiency of each dewatering well, if used, should be demonstrated to be no less than 90 percent at the time it is accepted by the engineer. The contractor should obtain additional subsurface data to assist their design, as deemed necessary.

### 4.7.2 Horizontal Directional Drilling

The horizontal directional drilling (HDD) method is a process of boring a pilot hole with a drill head suitable for the soil conditions. Once the initial pilot hole is complete, a reamer, slightly larger than the pilot hole is attached to the drill stem and pulled back. The reamer enlarges the borehole to accommodate the pipe that is then pulled into place.

Control of tunnel alignment and elevation is typically more easily achieved in uniform material. Based on test borings drilled in the vicinity of Pond Creek, we anticipate that the encountered materials will generally consist of completely weathered shale bedrock with limestone. Based on the elevation at which bedrock was encountered, published literature suggests that bedrock belongs to the McMicken and Southgate Formation under Kope group which is rich in shale. Hard limestone layers may be encountered within the shale formation as well as within residual clay zones occasionally found above the weathered bedrock. The contractor selected to perform the HDD should have equipment and proof of experience appropriate for such construction. The contractor should have experience with similar soil geology and installation type (size and length) for the project.

Care should be taken when using HDD methods below any existing pavements. For example, excess fluid pressure during backreaming can cause ground heave.

## Geotechnical Engineering Report

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY  
May 21, 2010 ■ HCN/Terracon Project No. N1095342



### 4.8 Slope Stability Considerations

Based on the relatively very stiff to hard cohesive overburden soils and relatively shallow brown shale bedrock in some areas, deep-seated (global) slope failure does not appear to be a concern (although detailed slope stability analyses were not performed). During our site visit, one area along Creektrace Road near Sta. 11+00 was observed to be asphalt patched on the downhill traffic lane. Additionally, the downhill slope was observed to be rehabilitated with a row of soldier beams installed along the edge of the road. We are not aware of the cause of these repairs, but they are likely to be the result of slope creep and subsequent pavement distress. Based on the provided plans, the water main alignment in this area is along the upslope side of the road. Test boring CR-2 performed in the vicinity of this rehabilitated area encountered very stiff natural cohesive soils to the explored test boring depth of 9 feet below existing grade. Considering the encountered soil conditions and observed rehabilitation of the apparent instability, it is our opinion that the proposed water main should be installed along upslope side of the road as currently shown on the plans in this area of the alignment.

We have not identified any obvious areas of potential instability along the roadways within other portions of this phase of the project; however, we recommend that the water main generally be installed along the upslope side of the road when feasible. Due to the long-term nature of creep, slope movement may become evident in this area and along other portions of the alignment in the future. Therefore, we recommend that monitoring along the alignment be performed on a regular basis due to the potential for creep movement.

### 4.7 Thrust Block Recommendations

Thrust block or restrained joints are used to resist thrust forces that occur in waterlines when the pipeline changes directions, changes sizes, or stops. A thrust block may be constructed between the fitting and the undisturbed side or bottom of the trench. The base of the thrust block is designed to support the anticipated thrust loads by providing a bearing area through which the thrust forces can be transferred to the soil without exceeding the bearing capacity of the soil.

An alternative method of providing thrust restraint is the use of restrained joints. A restrained joint is a special type of push-on or mechanical joint that is designed to provide longitudinal restraint. Restrained joint systems function in a manner similar to thrust blocks; as the reaction of the entire restrained unit of piping with the soil balances the thrust forces. The objective in designing a restrained joint thrust restraint system is to determine the length of pipe that must be restrained on each side of the focus of a thrust force. This will be a function of the pipe size, the internal pressure, depth of cover, the characteristics of the soil surrounding the pipe, and whether the pipe is polyethylene encased.

The provided plans depicting the water main alignment shows several bends where thrust blocks are anticipated. Based on the invert elevations of the water main pipeline, existing fill and natural cohesive soils and/or weathered shale bedrock are anticipated in the vicinity of the thrust blocks.



**Geotechnical Engineering Report**

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY  
 May 21, 2010 ■ HCN/Terracon Project No. N1095342



Two areas of instability were identified in this study where long-term creep of the slopes is likely. Consideration should be given to using restrained joints from station 45+00 to 55+00 where the slope instability was observed.

The following soil parameters can be used in sizing the thrust blocks and restrained joints:

Interface Material	Coefficient of Friction
Stiff to Very Stiff Existing Fill	0.30
Stiff to Very Stiff Natural Cohesive soils	0.35
Weathered Shale Bedrock	0.50

The following earth pressure coefficients can be used in sizing the thrust blocks for horizontal and vertical bends.

Material	Angle of Internal Friction ( $\phi$ )	Total Unit Weight ( $\gamma$ , pcf)	$K_o$ (At-rest)	$K_p$ (Passive)
Stiff to Very Stiff Existing Fill	23	120	0.61	2.28
Stiff to Very Stiff Natural Cohesive Soil	26	125	0.56	2.56
Weathered Shale Bedrock	36	135	0.41	3.85

The following allowable bearing capacities can be used in sizing the thrust block for downward directed thrust

Bearing Material	Allowable Bearing Capacity
New Engineered Granular Fill (placed over stiff to very stiff natural soils)	3,000 psf
Stiff to Very Stiff Natural Cohesive soils	3,000 psf
Weathered Shale Bedrock	8,000 psf

The following table summarizes the recommended coefficient of friction values for the interface of thrust block concrete and in-situ soil. These are ultimate values (no safety factors applied).

Interface Material	Coefficient of Friction
Stiff to Very Stiff Existing Fill	0.30
Stiff to Very Stiff Natural Cohesive soils	0.35
Weathered Shale Bedrock	0.50

**Geotechnical Engineering Report**

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY

May 21, 2010 ■ HCN/Terracon Project No. N1095342



It is recommended that the trench backfill in the areas of thrust blocks and restrained joints consist of granular backfill.

**4.8 Overview of Geotechnical Recommendations**

The following table is being provided for use by the NKWD and the waterline designer to aid in waterline design, and development of the project plans. The table generally outlines our recommendations along the alignment in consideration of the geotechnical aspects outlined above and based on review of the plan and profile information provided to us. The actual design of the waterline and design methodology is the responsibility of the designer. We have not considered flowrates, pressures, valve/hydrant placement, etc., along the waterline, which may require the further use of thrust blocks/restraints, grade change, waterline relocation, in addition to the recommendations provided below. We request the opportunity to review such changes and/or meet with the NKWD/designer to discuss any of our recommendations, as deemed necessary. It should be further acknowledged that our test borings provide limited, widely-spaced information and that “ground truth” is only obtained in the field during construction at the time of excavation. Adjustments in the field at the time of construction based on actual field conditions should be anticipated. Additional exploration and/or long-term monitoring may be required.

Alignment	Approximate Station	Applicable Test Boring(s)	Geotechnical Consideration(s)	Remarks <sup>(3)</sup>
Creektrace Road	0+00 to 0+50	CR-1 <sup>(1)</sup>	Minimum 1-foot undercut of existing fill	Within road; Likely existing fill; Use thrust blocks/restraints
	0+50 to 16+50	CR-1 & 2 <sup>(2)</sup>	Minimum 1-foot undercut where existing fill present	Likely existing fill; Possible rock excavation approaching Sta. 16+50
	16+50 to 27+00	CR-3	None anticipated	Likely rock excavation
	27+00 to 27+75	CR-3 <sup>(1)</sup>	None anticipated	Pipe bend; Use thrust blocks/restraints; Likely rock excavation
Creektrace Road	27+75 to 78+50	CR-4, 5, 6, 7, & 8	Existing fill near Sta. 66+00 (minimum 1-foot undercut)	Portions within road; Likely existing fill along alignment
	78+50 to 83+25	CR-8 <sup>(1)</sup> , JM-1	Dewatering required	Creek crossing; Use thrust blocks/restraints
	83+25 to 101+75	CR-9	None anticipated	Likely rock excavation

**Geotechnical Engineering Report**

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY

May 21, 2010 ■ HCN/Terracon Project No. N1095342



Alignment	Approximate Station	Applicable Test Boring(s)	Geotechnical Consideration(s)	Remarks <sup>(3)</sup>
	101+75 to 103+00	CR-10 <sup>(1)</sup>	Dewatering likely required	Drainage structure crossing; Use thrust blocks/restraints
	103+00 to 118+50	CR-10 & 11	Existing fill near Sta. 103+00 (minimum 1-foot undercut)	Likely existing fill along alignment
	118+50 to 119+50	CR-12 <sup>(1)</sup>	None Anticipated	Jack and bore; Use thrust blocks/restraints
	119+50 to 121+40	CR-12	None anticipated	(none)
Indian Trace Road	0+00 to 2+00	IR-1 <sup>(1)</sup>	None anticipated	Bend in alignment; Use thrust blocks/restraints
	2+00 to 5+25	IR-1	None anticipated	(none)
	5+25 to 6+25	IR-1 <sup>(1)</sup>	None anticipated	Bend in alignment; Use thrust blocks/restraints
	6+25 to 8+75	IR-1 <sup>(1)</sup>	None anticipated	(none)
	8+75 to 9+25	IR-1 <sup>(1)</sup>	None anticipated	Bend in alignment; Use thrust blocks/restraints
	9+25 to 13+00	IR-1 <sup>(1)</sup> & 2 <sup>(1)</sup>	None anticipated	Within road
	13+00 to 14+25	IR-2 <sup>(1)</sup>	None anticipated	Bend in alignment; Use thrust blocks/restraints
	14+25 to 17+50	IR-2	None anticipated	(none)
	17+50 to 18+50	IR-2 <sup>(1)</sup>	None anticipated	Bend in alignment; Use thrust blocks/restraints
	18+50 to 20+25	IR-2 <sup>(1)</sup>	None anticipated	(none)
	20+25 to 21+00	IR-2 <sup>(1)</sup>	None anticipated	Bend in alignment; Use thrust blocks/restraints
21+00 to 29+25	IR-2 <sup>(1)</sup> & IR-3 <sup>(1)</sup>	None anticipated	Within road	
Indian Trace Road	29+25 to 32+50	IR-3	Dewatering required	Creek crossing; Likely rock excavation; Use thrust blocks/restraints
	32+50 to 40+75	IR-3 <sup>(1)</sup> & 4 <sup>(1)</sup>	None anticipated	Portions within road
	40+75 to 41+75	IR-4 <sup>(1)</sup>	None Anticipated	Bend in alignment; Use thrust blocks/restraints
	41+75 to 47+50	IR-4	None anticipated	(none)

**Geotechnical Engineering Report**

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY

May 21, 2010 ■ HCN/Terracon Project No. N1095342



Alignment	Approximate Station	Applicable Test Boring(s)	Geotechnical Consideration(s)	Remarks <sup>(3)</sup>
	47+50 to 48+75	IR-4 <sup>(1)</sup>	Likely dewatering	Drainage structure crossing; Use thrust blocks/restraints
	48+75 to 77+75	IR-5 & 6	None anticipated	Likely rock excavation beyond Sta. 70+00
Joanne Lane	0+00 to 1+25	JL-1	None anticipated	Possible rock excavation near Sta. 0+00
	1+25 to 2+00	JL-1	Existing fill (minimum 1-foot undercut)	Bend in alignment; Use thrust blocks/restraints
	2+00 to 20+76	JL-2 & JL-3	None anticipated	(none)
John Miller Road	0+00 to 1+75	JM-1	None anticipated	Creek Trace Road Crossing; bend in road; Use thrust blocks/restraints
	1+75 to 7+89	JM-1 <sup>(1)</sup> , 2	None anticipated	Likely rock excavation beyond Sta. 3+50
Lauren Lane	0+00 to 0+50	LL-1	None anticipated	Bend in alignment; Use thrust blocks/restraints
	0+50 to 2+25	LL-1 <sup>(1)</sup>	None anticipated	(none)
	2+25 to 2+75	LL-1 <sup>(1)</sup>	None anticipated	Bend in alignment; Use thrust blocks/restraints
	2+75 to 18+00	LL-1 <sup>(1)</sup> & 2	None anticipated	(none)

(1) Boring drilled outside of station range.

(2) Considers waterline alignment on upslope side of road. Otherwise embed waterline in bedrock.

(3) Thrust block/restraint use based on project plans.

**5.0 GENERAL COMMENTS**

HCN/Terracon should be retained to review the final design plans and specifications so comments can be made regarding interpretation and implementation of our geotechnical recommendations in the design and specifications. HCN/Terracon also should be retained to provide observation and testing services during grading, excavation, foundation construction and other earth-related construction phases of the project.

## **Geotechnical Engineering Report**


Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY  
May 21, 2010 ■ HCN/Terracon Project No. N1095342




The analysis and recommendations presented in this report are based upon the data obtained from the borings performed at the indicated locations and from other information discussed in this report. This report does not reflect variations that may occur between borings, across the site, or due to the modifying effects of weather. The nature and extent of such variations may not become evident until during or after construction. If variations appear, we should be immediately notified so that further evaluation and supplemental recommendations can be provided.

The scope of services for this project does not include either specifically or by implication any environmental or biological (e.g., mold, fungi, and bacteria) assessment of the site or identification or prevention of pollutants, hazardous materials or conditions. If the owner is concerned about the potential for such contamination or pollution, other studies should be undertaken.

This report has been prepared for the exclusive use of our client for specific application to the project discussed and has been prepared in accordance with generally accepted geotechnical engineering practices. No warranties, either express or implied, are intended or made. Site safety, excavation support, and dewatering requirements are the responsibility of others. In the event that changes in the nature, design, or location of the project as outlined in this report are planned, the conclusions and recommendations contained in this report shall not be considered valid unless HCN/Terracon reviews the changes and either verifies or modifies the conclusions of this report in writing.



SCALE 1:24 000



CONTOUR INTERVAL FEET FEET  
NATIONAL GEODETIC VERTICAL DATUM OF 1929


MAP OF ALEXANDRIA, KENTUCKY 1983

7.5 MINUTE SERIES (TOPOGRAPHIC)



Note: Joann Lane is a side street off Indian Trace Road and John Miller Road and Lauren Lane are side streets off Creektrace Road.

Project Mngr: AJM	Project No: N1095342	<p>Consulting Engineers and Scientists</p> <p>611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45228 PH. (513) 321-5316 FAX. (513) 321-4540</p>	<p>SITE VICINITY MAP</p> <p>SUBDISTRICT H WATER MAIN EXTENSION – PHASE 2</p> <p>NORTHERN KENTUCKY WATER DISTRICT</p> <p>CREEKTRACE, INDIAN TRACE, JOHN MILLER RD., JOANN &amp; LAUREN LN., ALEXANDRIA, CAMPBELL COUNTY KENTUCKY</p>	<p>EXHIBIT</p> <p>A-1</p>
Drawn By: DRK	Scale: AS SHOWN			
Checked By: AJM	File No: FIGURE 1A			
Approved By: JAS	Date: 2/2/2010			



REV.	DATE	BY	DESCRIPTION


  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226  
 PH. (513) 321-5816 FAX. (513) 321-4540

APPROXIMATE TEST BORING LOCATION PLAN  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
 NORTHERN KENTUCKY WATER DISTRICT  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY

**APPROXIMATE TEST BORING LOCATION PLAN**  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
 NORTHERN KENTUCKY WATER DISTRICT  
 PHASE 2  
 KENTUCKY

**EXHIBIT A-2**

DESIGNED BY:	BD
DRAWN BY:	KU
APPROVED BY:	BD
SCALE:	1" = 100'
DATE:	01/23/18
JOB NO.:	N1805312
ACAD NO.:	NKWD CTR BLDWG
SHEET NO.:	A-2



REV.	DATE	BY	DESCRIPTION


  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE      CINCINNATI, OHIO 45226  
 PH. (513) 321-5816      FAX. (513) 321-4540




**APPROXIMATE TEST BORING LOCATION PLAN**  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
**NORTHERN KENTUCKY WATER DISTRICT**  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY      KENTUCKY


EXHIBIT A-3	
DESIGNED BY:	BD
DRAWN BY:	KM
CHECKED BY:	BD
SCALE:	1" = 10'
DATE:	01/29/2010
JOB NO.:	11055342
ACAD NO.:	HKWD_CTR_BLDWG
SHEET NO.:	A-3






REV.	DATE	BY	DESCRIPTION

  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226  
 PH. (513) 321-5816 FAX. (513) 321-4540



**APPROXIMATE TEST BORING LOCATION PLAN**  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
**NORTHERN KENTUCKY WATER DISTRICT**  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY KENTUCKY

EXHIBIT A-4	
DESIGNED BY:	BD
DRAWN BY:	KM
APP'D. BY:	BD
SCALE:	1" = 100'
DATE:	01/23/2010
JOB NO.:	N1095342
ACAD NO.:	NKWD CTR BL DWG
SHEET NO.:	A-4




REV.	DATE	BY	DESCRIPTION

  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE      CINCINNATI, OHIO 45226  
 PH. (513) 321-5816      FAX. (513) 321-4540



**APPROXIMATE TEST BORING LOCATION PLAN**  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
**NORTHERN KENTUCKY WATER DISTRICT**  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY      KENTUCKY

EXHIBIT A-5	
DESIGNED BY:	BD
DRAWN BY:	KM
APPROVED BY:	BD
SCALE:	1" = 100'
DATE:	01/29/2010
JOB NO.:	11095342
ACAD NO.:	NKYWD_CTR_EL_DWG
SHEET NO.:	A-5




REV.	DATE	BY	DESCRIPTION

  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226  
 PH. (513) 321-5816 FAX. (513) 321-4540

**APPROXIMATE TEST BORING LOCATION PLAN**  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
**NORTHERN KENTUCKY WATER DISTRICT**  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY KENTUCKY

EXHIBIT A-6	
DESIGNED BY:	BD
DRAWN BY:	KM
APP'D. BY:	SP
SCALE:	1" = 100'
DATE:	01/29/2010
JOB NO.:	N1025342
ACAD NO.:	NKWD CTR BL DWG
SHEET NO.:	A-6




REV.	DATE	BY	DESCRIPTION

  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226  
 PH. (513) 321-5816 FAX. (513) 321-4540

**APPROXIMATE TEST BORING LOCATION PLAN**  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
**NORTHERN KENTUCKY WATER DISTRICT**  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY KENTUCKY

**EXHIBIT A-7**

DESIGNED BY:	BD
DRAWN BY:	KM
APPROV. BY:	BD
SCALE:	1" = 100'
DATE:	01/29/2010
JOB NO.:	111095342
ACAD NO.:	NKYWD_CTR_EL_DWG
SHEET NO.:	A-7



REV.	DATE	BY	DESCRIPTION

  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226  
 PH. (513) 321-5816 FAX. (513) 321-4540

APPROXIMATE TEST BORING LOCATION PLAN  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
 NORTHERN KENTUCKY WATER DISTRICT  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY KENTUCKY

**EXHIBIT A-8**  
 DESIGNED BY: BD  
 DRAWN BY: KJM  
 APPVD. BY: BD  
 SCALE: 1" = 100'  
 DATE: 01/29/2010  
 X39 NO. 11085332  
 ACAD. NO. HKWD CTR. PL. DWG.  
 SHEET NO. A-8



REV.	DATE	BY	DESCRIPTION



  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE  
 PH. (513) 321-5816

CINCINNATI, OHIO 45226  
 FAX. (513) 321-4540

**APPROXIMATE TEST BORING LOCATION PLAN**  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
**NORTHERN KENTUCKY WATER DISTRICT**  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY      KENTUCKY


**EXHIBIT A-9**

DESIGNED BY:	BD
DRAWN BY:	KJ
CHECKED BY:	BD
SCALE:	1" = 100'
DATE:	01/25/2010
JOB NO.:	N1095342
ACAD NO.:	NKWD_CTR_BLDWG
SHEET NO.:	A-9




REV.	DATE	BY	DESCRIPTION

  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226  
 PH. (513) 321-5816 FAX. (513) 321-4540




**APPROXIMATE TEST BORING LOCATION PLAN**  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
**NORTHERN KENTUCKY WATER DISTRICT**  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY KENTUCKY

EXHIBIT A-10	
DESIGNED BY:	BD
DRAWN BY:	KM
APPROV. BY:	BD
SCALE:	1" = 100'
DATE:	01/15/2010
JOB NO.:	W1095342
ACAD NO.:	NKWD IT BL DWG
SHEET NO.:	A-10



REV.	DATE	BY	DESCRIPTION

  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE      CINCINNATI, OHIO 45226  
 PH. (513) 321-5816      FAX. (513) 321-4540



**APPROXIMATE TEST BORING LOCATION PLAN**  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
**NORTHERN KENTUCKY WATER DISTRICT**  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY      KENTUCKY

**EXHIBIT A-11**


DESIGNED BY:	BD
DRAWN BY:	KJA
APPVD BY:	BD
SCALE:	1" = 100'
DATE:	01/19/2010
JOB NO.:	N1095342
ACAD NO.:	NRWD IT BLDWG
SHEET NO.:	A-11





REV	DATE	BY	DESCRIPTION

  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE      CINCINNATI, OHIO 45226  
 PH. (513) 321-5816      FAX. (513) 321-4540



**APPROXIMATE TEST BORING LOCATION PLAN**  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
**NORTHERN KENTUCKY WATER DISTRICT**  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY      KENTUCKY


**EXHIBIT A-12**

DESIGNED BY:	BD
DRAWN BY:	KM
APP'D. BY:	BD
SCALE:	1" = 100'
DATE:	01/19/2010
JOB NO.:	11055342
ACAD NO.:	NKWD.IT.EL.DWG
SHEET NO.:	A-12




REV.	DATE	BY	DESCRIPTION

  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45228  
 PH. (513) 321-5816 FAX. (513) 321-4540




**APPROXIMATE TEST BORING LOCATION PLAN**  
**SUB-DISTRICT H. PROPOSED 8" WATER MAIN EXTENSION**  
**NORTHERN KENTUCKY WATER DISTRICT**  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY KENTUCKY

EXHIBIT A-13	
DESIGNED BY:	BD
DRAWN BY:	KM
APPROV. BY:	BD
SCALE:	1" = 100'
DATE:	01/19/2010
JOB NO.:	11195342
ACAD NO.:	NRWD IT BL DWG
SHEET NO.:	A-13




REV.	DATE	BY	DESCRIPTION

  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE      CINCINNATI, OHIO 45226  
 PH. (513) 321-5816      FAX. (513) 321-4540




**APPROXIMATE TEST BORING LOCATION PLAN**  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
**NORTHERN KENTUCKY WATER DISTRICT**  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY      KENTUCKY

EXHIBIT A-14	
DESIGNED BY:	BD
DRAWN BY:	KM
APPROV. BY:	BD
SCALE:	1" = 100'
DATE:	01/18/2010
JOB NO.:	N1625342
ACAD NO.:	NKWD IT BLDWG
SHEET NO.:	A-14



REV.	DATE	BY	DESCRIPTION



  
**Terracon** COMPANY  
 611 LUNKEN PARK DRIVE      CINCINNATI, OHIO 45226  
 PH. (513) 321-5818      FAX. (513) 321-4540



**APPROXIMATE TEST BORING LOCATION PLAN**  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
**NORTHERN KENTUCKY WATER DISTRICT**  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY      KENTUCKY

**EXHIBIT A-15**

DESIGNED BY:	BD
DRAWN BY:	KM
APPROV. BY:	BD
SCALE:	1" = 100'
DATE:	01/15/2010
JOB NO.:	H1095342
DRAWING NO.:	NKYWD JL BL DWG
SHEET NO.:	A-15





REV.	DATE	BY	DESCRIPTION

  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE      CINCINNATI, OHIO 45226  
 PH. (513) 321-5816      FAX. (513) 321-4540



**APPROXIMATE TEST BORING LOCATION PLAN**  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
**NORTHERN KENTUCKY WATER DISTRICT**  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY      KENTUCKY

EXHIBIT A-16	
DESIGNED BY:	BD
DRAWN BY:	K24
APPVD. BY:	BD
SCALE:	1" = 100'
DATE:	01/19/2010
JOB NO.:	N1055342
ACAD NO.:	NKWD_JL_BLDWG
SHEET NO.:	A-16




REV.	DATE	BY	DESCRIPTION

  
**Terracon** COMPANY  
 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226  
 PH. (513) 321-5816 FAX. (513) 321-4540

APPROXIMATE TEST BORING LOCATION PLAN  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
**NORTHERN KENTUCKY WATER DISTRICT**  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY KENTUCKY

EXHIBIT A-17	
DESIGNED BY:	BD
DRAWN BY:	KM
APP'D BY:	BD
SCALE:	1" = 100'
DATE:	01/29/2010
JOB NO.:	N195342
ACAD NO.:	NKWD_JMR_BLDWG
SHEET NO.:	A-17




REV.	DATE	BY	DESCRIPTION


  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226  
 PH. (513) 321-5816 FAX. (513) 321-4340


APPROXIMATE TEST BORING LOCATION PLAN  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
 NORTHERN KENTUCKY WATER DISTRICT  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY KENTUCKY

**EXHIBIT A-18**  
 DESIGNED BY: BD  
 DRAWN BY: KM  
 APP'D BY: BD  
 SCALE: 1" = 100'  
 DATE: 01/29/2010  
 JOB NO. 11023342  
 ACAD NO. NKWD LL BL DWG  
 SHEET NO. A-18



REV.	DATE	BY	DESCRIPTION

  
**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE      CINCINNATI, OHIO 45226  
 PH. (513) 321-5816      FAX. (513) 321-4540



**APPROXIMATE TEST BORING LOCATION PLAN**  
 SUB-DISTRICT H, PROPOSED 8" WATER MAIN EXTENSION  
**NORTHERN KENTUCKY WATER DISTRICT**  
 PHASE 2  
 ALEXANDRIA, CAMPBELL COUNTY      KENTUCKY

EXHIBIT A-19	
DESIGNED BY:	BD
DRAWN BY:	KM
APPVD. BY:	BD
SCALE:	1" = 100'
DATE:	01/22/2010
JOB NO.:	N1095342
ACAD NO.:	NKWD.LL.BLDWG
SHEET NO.:	A-19



# LOG OF BORING NO. CR-1

CLIENT <b>Northern Kentucky Water District</b>		ELEVATION REFERENCE <b>Interpolated from Site Topographic Plans</b>							
SITE <b>Alexandria, Kentucky</b>		PROJECT <b>Proposed Sub-District H Water Main Ext. Ph. 2</b>							
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan	DEPTH, ft.	SAMPLES			TESTS			
	DESCRIPTION		USCS SYMBOL	NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf
	Approx. Surface Elev.: 668 ft								
5	663	5	1	SS	100	2-2-2 (4)	26		2000*
	<b>FILL</b> , lean clay, little silt, brown, medium stiff		2	SS	100	4-4-5 (9)	25		3147
10	658		3	SS	100	2-1-3 (4)	21		4000*
	<b>FILL</b> , lean clay, some silt, trace shale and brown fragments, brown, trace gray, stiff to very stiff		4	SS	100	4-5-5 (10)	17		8000*
12.5	655.5	10	5	SS	100	5-6-7 (13)	26		8000*
	<b>FILL</b> , fat clay, trace sand or silt, shale fragments, brown, very stiff		6	SS	100	9-9-8 (17)			8000*
14	654								
	<b>FILL</b> , lean clay, trace root matter and sand, brown and gray, very stiff								
	Boring Completed at 14 ft.								

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual.

\*Calibrated Hand Penetrometer  
Exhibit A-20

**WATER LEVEL OBSERVATIONS, ft**

WL	▽ N/E	WD	▽
WL	▽ N/E	AB	▽
WL			



BORING STARTED		2-2-10	
BORING COMPLETED		2-2-10	
RIG	Truck	FOREMAN	JG
LOGGED	DRK	JOB #	N1095342

# LOG OF BORING NO. CR-2

<b>CLIENT</b> Northern Kentucky Water District		<b>ELEVATION REFERENCE</b> Interpolated from Site Topographic Plans	
<b>SITE</b> Alexandria, Kentucky		<b>PROJECT</b> Proposed Sub-District H Water Main Ext. Ph. 2	
<b>GRAPHIC LOG</b>	Boring Location: As Shown on Test Boring Location Plan	<b>SAMPLES</b>	
	<b>DESCRIPTION</b>	<b>TESTS</b>	
	Approx. Surface Elev.: 648 ft	<b>DEPTH, ft.</b>	<b>USCS SYMBOL</b>
		<b>NUMBER</b>	<b>TYPE</b>
		<b>RECOVERY, %</b>	<b>BLOWS / 6in. (SPT - N)</b>
		<b>WATER CONTENT, %</b>	<b>DRY UNIT WT pcf</b>
		<b>UNCONFINED STRENGTH, psf</b>	
	<b>LEAN CLAY</b> , little sand, trace silt, brown and dark brown, very stiff 2.5 <span style="float: right;">645.5</span>	CL 1	SS 100
	<b>LEAN CLAY</b> , trace to little limestone fragments, brown, very stiff	CL 2	SS 100
		CL 3	SS 78
		CL 4	SS 100
	9 <span style="float: right;">639</span> Boring Completed at 9 ft.		

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual. \*Calibrated Hand Penetrometer Exhibit A-21

WATER LEVEL OBSERVATIONS, ft			
WL	▽ N/E	WD	▼
WL	▽ N/E	AB	▼
WL			



BORING STARTED		2-1-10	
BORING COMPLETED		2-1-10	
RIG	Truck	FOREMAN	JG
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT 3/4/10

# LOG OF BORING NO. CR-3

<b>CLIENT</b> Northern Kentucky Water District	<b>ELEVATION REFERENCE</b> Interpolated from Site Topographic Plans
<b>SITE</b> Alexandria, Kentucky	<b>PROJECT</b> Proposed Sub-District H Water Main Ext. Ph. 2

GRAPHIC LOG	DESCRIPTION	DEPTH, ft.	USCS SYMBOL	SAMPLES				TESTS	
				NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf
	Boring Location: As Shown on Test Boring Location Plan  Approx. Surface Elev.: 624 ft								
2.5	<b>LEAN CLAY</b> , trace limestone fragments, some silt (RESIDUUM), brown, very stiff	621.5	CL	1	SS	100	8-4-5 (9)	19	6000*
3.3	<b>COMPLETELY WEATHERED SHALE</b> , with limestone fragments Boring Completed at 3.3 ft.	620.7		2	SS	100	18-50/4"	22	

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual. \*Calibrated Hand Penetrometer Exhibit A-22

WATER LEVEL OBSERVATIONS, ft			
WL	▽ N/E	WD	▽
WL	▽ N/E	AB	▽
WL			



BORING STARTED	2-2-10
BORING COMPLETED	2-2-10
RIG	Truck
LOGGED	DRK
FOREMAN	JG
JOB #	N1095342

BOREHOLE 99 BORING LOGS PH.2.GPJ TERRACON TEST.GDT. 3/4/10

# LOG OF BORING NO. CR-4

CLIENT <b>Northern Kentucky Water District</b>		ELEVATION REFERENCE <b>Interpolated from Site Topographic Plans</b>									
SITE <b>Alexandria, Kentucky</b>		PROJECT <b>Proposed Sub-District H Water Main Ext. Ph. 2</b>									
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan	DEPTH, ft.	SAMPLES				TESTS				
	DESCRIPTION		USCS SYMBOL	NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf	UNCONFINED STRENGTH, psf	
	Approx. Surface Elev.: 596 ft										
	2.5		593.5	CL	2	SS	100	2-2-4 (6)	21		6000*
	7.5		588.5	CL	3	SS	100	9-12-10 (22)	15		8000*
9	587	CL ML	4	SS	100	9-11-12 (23)	20		8000*		
Boring Completed at 9 ft.											

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual. \*Calibrated Hand Penetrometer Exhibit A-23

WATER LEVEL OBSERVATIONS, ft			
WL	▽ N/E	WD	▼
WL	▽ N/E	AB	▼
WL			



BORING STARTED		2-2-10	
BORING COMPLETED		2-2-10	
RIG	Truck	FOREMAN	JG
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH.2.GPJ TERRACON TEST.GDT 3/4/10

# LOG OF BORING NO. CR-5

<b>CLIENT</b> Northern Kentucky Water District	<b>ELEVATION REFERENCE</b> Interpolated from Site Topographic Plans
---	--

<b>SITE</b> Alexandria, Kentucky	<b>PROJECT</b> Proposed Sub-District H Water Main Ext. Ph. 2
-------------------------------------	---

GRAPHIC LOG	DESCRIPTION	DEPTH, ft.	SAMPLES				TESTS		
			USCS SYMBOL	NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf
Boring Location: As Shown on Test Boring Location Plan									
Approx. Surface Elev.: 580 ft									
9	LEAN CLAY, little silt, trace sand and root matter, dark brown, very stiff	5	CL	1	SS	100	2-3-6 (9)	23	8000*
			CL	2	SS	100	11-15-13 (28)	24	8000*
			CL	3	SS	100	6-10-13 (23)	21	8000*
			CL	4	SS	100	13-19-20 (39)	20	8000*
	Boring Completed at 9 ft.	571							

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual. \*Calibrated Hand Penetrometer Exhibit A-24

WATER LEVEL OBSERVATIONS, ft			
WL	N/E	WD	▼
WL	N/E	AB	▼
WL			



BORING STARTED	2-1-10
BORING COMPLETED	2-1-10
RIG	Truck FOREMAN JG
LOGGED	DRK JOB # N1095342

BOREHOLE 99 BORING LOGS PH.2.GPJ TERRACON TEST.GDT 3/4/10

# LOG OF BORING NO. CR-6

CLIENT <b>Northern Kentucky Water District</b>		ELEVATION REFERENCE <b>Interpolated from Site Topographic Plans</b>									
SITE <b>Alexandria, Kentucky</b>		PROJECT <b>Proposed Sub-District H Water Main Ext. Ph. 2</b>									
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan	DEPTH, ft.	SAMPLES				TESTS				
	DESCRIPTION		USCS SYMBOL	NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf	UNCONFINED STRENGTH, psf	
	Approx. Surface Elev.: 564 ft										
	2.5		<b>LEAN CLAY</b> , some limestone fragments, brown, stiff	CL	1	SS	44	1-2-9 (11)	19		4000*
	561.5		<b>LEAN CLAY</b> , little shale fragments, brown, stiff	CL	2	SS	100	15-13-13 (26)	12		4000*
7.5	<b>LEAN CLAY</b> , little shale fragments, brown, stiff	CL	3	SS	100	6-4-2 (6)	20		4000*		
556.5	<b>FAT CLAY</b> , trace shale fragments, brown, very stiff	CH	4	SS	100	6-9-13 (22)	20		8000*		
9	<b>FAT CLAY</b> , trace shale fragments, brown, very stiff										
	Boring Completed at 9 ft.										

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual.

\*Calibrated Hand Penetrometer  
Exhibit A-25

**WATER LEVEL OBSERVATIONS, ft**

WL	N/E	WD	▼
WL	N/E	AB	▼
WL			



BORING STARTED		2-1-10	
BORING COMPLETED		2-1-10	
RIG	Truck	FOREMAN	JG
LOGGED	DRK	JOB #	N1095342

# LOG OF BORING NO. CR-7

CLIENT <b>Northern Kentucky Water District</b>		ELEVATION REFERENCE <b>Interpolated from Site Topographic Plans</b>					
SITE <b>Alexandria, Kentucky</b>		PROJECT <b>Proposed Sub-District H Water Main Ext. Ph. 2</b>					
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan		SAMPLES				
	DESCRIPTION	TESTS					
	Approx. Surface Elev.: 548 ft	DEPTH, ft.	USCS SYMBOL	NUMBER			
		RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %			
		DRY UNIT WT pcf	UNCONFINED STRENGTH, psf				
5	543	1	SS	100	2-2-2 (4)	28	3000*
7.5	540.5	2	SS	100	7-11-8 (19)	24	4000*
7.8	540.2	3	CH	100	19-12-10 (22)	20	5000*
		4	CL	100	50/4"	19	



The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual.

\*Calibrated Hand Penetrometer Exhibit A-26

WATER LEVEL OBSERVATIONS, ft			
WL	▽ 0.5	WD	▽
WL	▽ N/E	AB	▽
WL			



BORING STARTED		2-2-10	
BORING COMPLETED		2-2-10	
RIG	Truck	FOREMAN	JG
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT 3/4/10

# LOG OF BORING NO. CR-8

CLIENT <b>Northern Kentucky Water District</b>		ELEVATION REFERENCE <b>Interpolated from Site Topographic Plans</b>	
SITE <b>Alexandria, Kentucky</b>		PROJECT <b>Proposed Sub-District H Water Main Ext. Ph. 2</b>	
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan		SAMPLES
	DESCRIPTION	TESTS	
	Approx. Surface Elev.: 528 ft	DEPTH, ft.	USCS SYMBOL
2.5	525.5	1	CL
<b>LEAN CLAY</b> , trace sand and root matter, brown, very stiff		1	SS
		100	1-2-2 (4)
		2	CL
<b>LEAN CLAY</b> , trace sand and limestone fragments, dark brown, very stiff		2	SS
		100	3-5-5 (10)
5		3	CL
<b>LEAN CLAY</b> , some limestone fragments, brown, stiff		3	SS
		100	3-5-9 (14)
10	518	4	CL
<b>LEAN CLAY</b> , some limestone fragments, brown, stiff		4	SS
		0	50/0"
12.5	515.5	5	CL
<b>LEAN CLAY</b> , some limestone fragments, brown, stiff		5	SS
		100	29-18-17 (35)
13.2	514.8	6	SS
<b>WEATHERED SHALE</b> , trace limestone fragments, brown, soft Boring Completed at 14 ft.		6	SS
		100	31-50/3"

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual. \*Calibrated Hand Penetrometer Exhibit A-27

WATER LEVEL OBSERVATIONS, ft			
WL	▽	N/E	WD
WL	▽	N/E	AB
WL			



BORING STARTED		2-2-10	
BORING COMPLETED		2-2-10	
RIG	Truck	FOREMAN	JG
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT 3/4/10



# LOG OF BORING NO. CR-9

<b>CLIENT</b> Northern Kentucky Water District	<b>ELEVATION REFERENCE</b> Interpolated from Site Topographic Plans
---	--

<b>SITE</b> Alexandria, Kentucky	<b>PROJECT</b> Proposed Sub-District H Water Main Ext. Ph. 2
-------------------------------------	---

GRAPHIC LOG	DESCRIPTION	DEPTH, ft.	USCS SYMBOL	SAMPLES				TESTS	
				NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf
Boring Location: As Shown on Test Boring Location Plan									
Approx. Surface Elev.: 538 ft									
1	<b>FILL</b> , lean clay, trace root matter, soft	537		1	SS	100	2-9	41	1000*
1A	<b>WEATHERED SHALE</b> , some limestone fragments, brown, soft			1A	SS	100	19	13	
4		534		2	SS	100	29-50/5"	20	
Boring Completed at 4 ft.									

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual.

\*Calibrated Hand Penetrometer  
Exhibit A-28

**WATER LEVEL OBSERVATIONS, ft**

WL	▽ N/E	WD	▽
WL	▽ N/E	AB	▽
WL			



BORING STARTED		2-2-10	
BORING COMPLETED		2-2-10	
RIG	Truck	FOREMAN	JG
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT 3/4/10

# LOG OF BORING NO. CR-10

CLIENT <b>Northern Kentucky Water District</b>		ELEVATION REFERENCE <b>Interpolated from Site Topographic Plans</b>								
SITE <b>Alexandria, Kentucky</b>		PROJECT <b>Proposed Sub-District H Water Main Ext. Ph. 2</b>								
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan	DEPTH, ft.	SAMPLES				TESTS			
	DESCRIPTION		USCS SYMBOL	NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf	UNCONFINED STRENGTH, psf
	Approx. Surface Elev.: 527 ft									
0.5	<b>TOPSOIL</b> 526.5									
2.5	<b>FILL</b> , fat clay, trace root matter, brown, very stiff 524.5		1A	SS	100	2-3 (5)	27		8000*	
5	<b>FILL</b> , poorly graded gravel, some sand and asphalt fragments, trace limestone fragments, dense 522		2	SS	100	11-17-23 (40)	8			
10	<b>LEAN CLAY</b> , little silt, gray, stiff 517	5	CL	3	SS	100	3-4-5 (9)	30		4000*
			CL	4	SS	100	5-5-8 (13)	26		4000*
	Boring Completed at 10 ft.	10								

LL=45%  
PI=24%

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual. \*Calibrated Hand Penetrometer Exhibit A-29

WATER LEVEL OBSERVATIONS, ft			
WL	▽ N/E	WD	▽
WL	▽ N/E	AB	▽
WL			



BORING STARTED		2-2-10	
BORING COMPLETED		2-2-10	
RIG	Truck	FOREMAN	JG
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH.2.GPJ TERRACON TEST.GDT 3/4/10

# LOG OF BORING NO. CR-11

<b>CLIENT</b> Northern Kentucky Water District	<b>ELEVATION REFERENCE</b> Interpolated from Site Topographic Plans
---	--

<b>SITE</b> Alexandria, Kentucky	<b>PROJECT</b> Proposed Sub-District H Water Main Ext. Ph. 2
-------------------------------------	---

GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan	DESCRIPTION	DEPTH, ft.	USCS SYMBOL	SAMPLES				TESTS		
					NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf	UNCONFINED STRENGTH, psf
Approx. Surface Elev.: 557 ft											
0.2	556.8	TOPSOIL		CL	1	SS	100	1-1-1 (2)	14		8000*
		<b>LEAN CLAY</b> , trace root matter, brown, very stiff									
5	552			CL	2	SS	100	5-5-7 (12)	18		8000*
		<b>FAT CLAY</b> , trace sand, brown and gray, very stiff									
9	548		5	CH	3	SS	100	5-5-6 (11)	29		8000*
				CH	4	SS	100	12-13-15 (28)	25		8000*
		Boring Completed at 9 ft.									

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual.

\*Calibrated Hand Penetrometer Exhibit A-30

WATER LEVEL OBSERVATIONS, ft			
WL	∇ N/E	WD	∇
WL	∇ N/E	AB	∇
WL			



BORING STARTED		2-2-10	
BORING COMPLETED		2-2-10	
RIG	Truck	FOREMAN	JG
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT 3/4/10

# LOG OF BORING NO. CR-12

CLIENT <b>Northern Kentucky Water District</b>		ELEVATION REFERENCE <b>Interpolated from Site Topographic Plans</b>	
SITE <b>Alexandria, Kentucky</b>		PROJECT <b>Proposed Sub-District H Water Main Ext. Ph. 2</b>	
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan		SAMPLES
	DESCRIPTION	TESTS	
	Approx. Surface Elev.: 558 ft	DEPTH, ft.	USCS SYMBOL
		NUMBER	TYPE
		RECOVERY, %	BLOWS / 6in. (SPT - N)
		WATER CONTENT, %	DRY UNIT WT pcf
		UNCONFINED STRENGTH, psf	
2.5	555.5	1	SS
<b>FILL</b> , sandy silt, little gravel, trace asphalt fragments, dark brown, loose		100	3-3-3 (6)
		11	
7.5	550.5	2	SS
<b>LEAN CLAY</b> , little silt, trace limestone fragments, brown, very stiff		100	8-10-11 (21)
		19	8000*
9	549	3	SS
<b>LEAN CLAY</b> , some silt, brown, very stiff		100	6-6-9 (15)
		17	6000*
		4	SS
<b>LEAN CLAY</b> , some silt, brown, very stiff		100	11-12-18 (30)
		20	8000*
Boring Completed at 9 ft.			

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual. \*Calibrated Hand Penetrometer Exhibit A-31

WATER LEVEL OBSERVATIONS, ft			
WL	▽ N/E	WD	▽
WL	▽ N/E	AB	▽
WL			



BORING STARTED		2-1-10	
BORING COMPLETED		2-1-10	
RIG	Truck	FOREMAN	JG
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT 3/4/10

# LOG OF BORING NO. IR-1

CLIENT <b>Northern Kentucky Water District</b>		ELEVATION REFERENCE <b>Interpolated from Site Topographic Plans</b>	
SITE <b>Alexandria, Kentucky</b>		PROJECT <b>Proposed Sub-District H Water Main Ext. Ph. 2</b>	
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan		SAMPLES
	DESCRIPTION	TESTS	
	Approx. Surface Elev.: 520 ft	DEPTH, ft.	
0.5	ASPHALT PAVEMENT	519.5	
1	GRANULAR BASE	519	1 SS 100 21-7-7 (14) 9 4000*
2.5	FILL, lean clay, little sand and gravel, dark brown and brown, stiff	517.5	CL 2 SS 100 2-3-2 (5) 29 2000*
5	LEAN CLAY, some silt, dark brown, medium stiff	515	CH 3 SS 67 3-6-10 (16) 26 5000*
7.5	FAT CLAY, trace shale fragments, brown, very stiff	512.5	4 SS 67 16-16-16 (32)
9	LIMESTONE FRAGMENTS, trace lean clay, dense	511	
	Boring Completed at 9 ft.		

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual.

\*Calibrated Hand Penetrometer  
Exhibit A-32

**WATER LEVEL OBSERVATIONS, ft**

WL	▽ N/E	WD	▽
WL	▽ N/E	AB	▽
WL			



BORING STARTED		1-23-10	
BORING COMPLETED		1-23-10	
RIG	Truck	FOREMAN	JJ
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT 3/4/10

# LOG OF BORING NO. IR-2

<b>CLIENT</b> Northern Kentucky Water District		<b>ELEVATION REFERENCE</b> Interpolated from Site Topographic Plans																																																																		
<b>SITE</b> Alexandria, Kentucky		<b>PROJECT</b> Proposed Sub-District H Water Main Ext. Ph. 2																																																																		
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan  DESCRIPTION  Approx. Surface Elev.: 500 ft	DEPTH, ft.	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th colspan="2">USCS SYMBOL</th> <th colspan="4">SAMPLES</th> <th colspan="3">TESTS</th> </tr> <tr> <th>NUMBER</th> <th>TYPE</th> <th>RECOVERY, %</th> <th>BLOWS / 6in. (SPT - N)</th> <th>WATER CONTENT, %</th> <th>DRY UNIT WT pcf</th> <th colspan="2">UNCONFINED STRENGTH, psf</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>SS</td> <td>100</td> <td>7</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>1A</td> <td>SS</td> <td>100</td> <td>4</td> <td></td> <td></td> <td>4000*</td> <td></td> </tr> <tr> <td>1B</td> <td>SS</td> <td>100</td> <td>3</td> <td></td> <td></td> <td>6000*</td> <td></td> </tr> <tr> <td>CL 2</td> <td>SS</td> <td>100</td> <td>6-5-5 (10)</td> <td>24</td> <td></td> <td>5000*</td> <td></td> </tr> <tr> <td>5</td> <td>CH 3</td> <td>SS</td> <td>100</td> <td>4-3-3 (6)</td> <td>23</td> <td>7000*</td> <td></td> </tr> <tr> <td>9</td> <td>CH 4</td> <td>SS</td> <td>100</td> <td>5-7-9 (16)</td> <td>22</td> <td>5000*</td> <td></td> </tr> </tbody> </table>	USCS SYMBOL		SAMPLES				TESTS			NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf	UNCONFINED STRENGTH, psf		1	SS	100	7					1A	SS	100	4			4000*		1B	SS	100	3			6000*		CL 2	SS	100	6-5-5 (10)	24		5000*		5	CH 3	SS	100	4-3-3 (6)	23	7000*		9	CH 4	SS	100	5-7-9 (16)	22	5000*	
	USCS SYMBOL		SAMPLES				TESTS																																																													
NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf	UNCONFINED STRENGTH, psf																																																														
1	SS	100	7																																																																	
1A	SS	100	4			4000*																																																														
1B	SS	100	3			6000*																																																														
CL 2	SS	100	6-5-5 (10)	24		5000*																																																														
5	CH 3	SS	100	4-3-3 (6)	23	7000*																																																														
9	CH 4	SS	100	5-7-9 (16)	22	5000*																																																														
	0.5 ASPHALT PAVEMENT 499.5 1 GRANULAR BASE 499 1.5 <b>FILL</b> , lean clay, little silt and sand, gray, stiff 498.5 <b>LEAN CLAY</b> , little silt, brown, very stiff 5 495 <b>FAT CLAY</b> , trace gravel, dark brown and gray, very stiff ∇ 7.5 492.5 <b>FAT CLAY</b> , little silt, brown and gray, very stiff 9 491 Boring Completed at 9 ft.																																																																			

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual.

\*Calibrated Hand Penetrometer  
Exhibit A-33

**WATER LEVEL OBSERVATIONS, ft**

WL	∇ 7.5	WD	∇
WL	∇ 6.0	AB	∇
WL			



BORING STARTED		1-23-10	
BORING COMPLETED		1-23-10	
RIG	Truck	FOREMAN	JJ
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT 3/4/10

# LOG OF BORING NO. IR-3

CLIENT <b>Northern Kentucky Water District</b>		ELEVATION REFERENCE <b>Interpolated from Site Topographic Plans</b>					
SITE <b>Alexandria, Kentucky</b>		PROJECT <b>Proposed Sub-District H Water Main Ext. Ph. 2</b>					
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan	SAMPLES					
	DESCRIPTION	TESTS					
	Approx. Surface Elev.: 493 ft	DEPTH, ft.	USCS SYMBOL	NUMBER			
			TYPE	RECOVERY, %			
			BLOWS / 6in. (SPT - N)	WATER CONTENT, %			
			DRY UNIT WT pcf	UNCONFINED STRENGTH, psf			
2.5	<b>FILL</b> , lean clay, trace root matter and limestone fragments, dark brown, medium stiff	1	SS	100	2-3-3 (6)	25	2000*
5	<b>LEAN CLAY</b> , little silt, trace sand and gravel, brown, stiff	CL	2	SS	100	2-3-4 (7)	4000*
7.5	<b>LEAN CLAY</b> , little silt, trace shale and limestone fragments, brown, very stiff	CL	3	SS	56	6-9-11 (20)	8000*
10	<b>HIGHLY WEATHERED SHALE</b> with limestone fragments, soft	4	SS	100	11-19-27 (46)		
	Boring Completed at 10 ft.	5 AUGER					

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual.

\*Calibrated Hand Penetrometer  
Exhibit A-34

WATER LEVEL OBSERVATIONS, ft			
WL	▽ N/E	WD	▽
WL	▽ N/E	AB	▽
WL			



BORING STARTED	1-23-10
BORING COMPLETED	1-23-10
RIG	Truck FOREMAN JJ
LOGGED	DRK JOB # N1095342

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT 3/4/10

# LOG OF BORING NO. IR-4

CLIENT <b>Northern Kentucky Water District</b>		ELEVATION REFERENCE <b>Interpolated from Site Topographic Plans</b>								
SITE <b>Alexandria, Kentucky</b>		PROJECT <b>Proposed Sub-District H Water Main Ext. Ph. 2</b>								
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan		SAMPLES			TESTS				
	DESCRIPTION	DEPTH, ft.	USCS SYMBOL	NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf	UNCONFINED STRENGTH, psf
	Approx. Surface Elev.: 512 ft									
	0.3 ASPHALT PAVEMENT 511.7									
	1 GRANULAR BASE 511			1	SS	100	6-5-4 (9)	26		8000*
	2.5 FILL, lean clay, trace gravel, gray, very stiff 509.5									
	5 FAT CLAY, little sand, trace gravel, brown, very stiff 507			CH	2	SS	100	5-6-9 (15)	24	6000*
	5 FAT CLAY, brown and gray, very stiff to stiff 507			CH	3	SS	100	7-4-6 (10)	42	5000*
	9 Boring Completed at 9 ft. 503			CH	4	SS	100	6-6-5 (11)	46	4000*

LL=83%  
PI=56%

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual.

\*Calibrated Hand Penetrometer  
Exhibit A-35

WATER LEVEL OBSERVATIONS, ft			
WL	∇ N/E	WD	∇
WL	∇ N/E	AB	∇
WL			



BORING STARTED		1-23-10	
BORING COMPLETED		1-23-10	
RIG	Truck	FOREMAN	JJ
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT. 3/4/10



# LOG OF BORING NO. IR-5

<b>CLIENT</b> Northern Kentucky Water District		<b>ELEVATION REFERENCE</b> Interpolated from Site Topographic Plans							
<b>SITE</b> Alexandria, Kentucky		<b>PROJECT</b> Proposed Sub-District H Water Main Ext. Ph. 2							
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan  DESCRIPTION  Approx. Surface Elev.: 507 ft								
	0.5 — 506.5 ASPHALT PAVEMENT <u>FILL</u> , lean clay, trace gravel, little silt, gray, very stiff to stiff  3.5 — 503.5 <u>LEAN CLAY</u> , trace silt and sand, dark brown, very stiff  5 — 502 <u>LEAN CLAY</u> , some silt, brown, very stiff  9 — 498 Boring Completed at 9 ft.	DEPTH, ft.  5          — — — — — — — — — —	SAMPLES  TESTS  UNCONFINED STRENGTH, psf						
		USCS SYMBOL	NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf	UNCONFINED STRENGTH, psf
			1	SS	100	5-6-13 (19)	23		6000*
			2	SS	100	5-5	34		3000*
		CL	2A	SS	100	7	24		8000*
		CL	3	SS	100	5-8-11 (19)	21		8000*
		CL	4	SS	100	12-17-16 (33)	20		8000*

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual. \*Calibrated Hand Penetrometer Exhibit A-36

<b>WATER LEVEL OBSERVATIONS, ft</b>			<b>BORING STARTED</b> 1-23-10		
WL	▽ N/E		WD	▽	<b>BORING COMPLETED</b> 1-23-10
WL	▽ N/E		AB	▽	<b>RIG</b> Truck <b>FOREMAN</b> JJ
WL					<b>LOGGED</b> DRK <b>JOB #</b> N1095342
WL					

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT 3/4/10

# LOG OF BORING NO. IR-6

<b>CLIENT</b> Northern Kentucky Water District	<b>ELEVATION REFERENCE</b> Interpolated from Site Topographic Plans
<b>SITE</b> Alexandria, Kentucky	<b>PROJECT</b> Proposed Sub-District H Water Main Ext. Ph. 2

GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan	DESCRIPTION	DEPTH, ft.	USCS SYMBOL	SAMPLES				TESTS	
					NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf
	Approx. Surface Elev.: 526 ft									
0.5	525.5	<b>FILL</b> , sandy silt, trace gravel, black, loose			1	SS	100	4	17	
1	525	<b>FILL</b> , lean clay, little sand and gravel, brown, very stiff			1A	SS	100	5	8	6000*
2.5	523.5	<b>FILL</b> , lean clay, little sand and gravel, brown, very stiff			1B	SS	100	4	20	7000*
5	521	<b>LEAN CLAY</b> , little silt, dark brown, very stiff			2	SS	100	12-13-14 (27)	18	8000*
5		<b>LEAN CLAY</b> , little silt and sand, brown, very stiff								
9	517	<b>HIGHLY WEATHERED SHALE</b> , with limestone fragments, brown, soft			3	SS	67	9-18-21 (39)	14	
					4	SS	100	23-17-17 (34)	15	
	Boring Completed at 9 ft.									

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual. \*Calibrated Hand Penetrometer Exhibit A-37

WATER LEVEL OBSERVATIONS, ft			
WL	▽ N/E	WD	▽
WL	▽ N/E	AB	▽
WL			



BORING STARTED		1-23-10	
BORING COMPLETED		1-23-10	
RIG	Truck	FOREMAN	JJ
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT 3/4/10

# LOG OF BORING NO. JL-1

<b>CLIENT</b> Northern Kentucky Water District		<b>ELEVATION REFERENCE</b> Interpolated from Site Topographic Plans							
<b>SITE</b> Alexandria, Kentucky		<b>PROJECT</b> Proposed Sub-District H Water Main Ext. Ph. 2							
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan  DESCRIPTION  Approx. Surface Elev.: 501 ft	DEPTH, ft.	SAMPLES		TESTS				
			USCS SYMBOL	NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf
	0.6 CONCRETE PAVEMENT 500.4								
	0.8 GRANULAR BASE 500.2		1	SS	67	3-27-7 (34)	14		8000*
	2.5 FILL, sandy lean clay, trace to little gravel, brown and gray, very stiff 498.5		2	SS	67	5-61-6 (67)	20		
	5 FILL, lean clay, some gravel and limestone fragments, brown, stiff 496								
	LEAN CLAY, little silt, trace sand, dark brown, hard 493.5	5	CL	SS	83	6-41-50/0	22		9000*
	7.5 HIGHLY WEATHERED SHALE, and limestone fragments, brown, soft 492		4	SS	67	19-40-29 (69)	14		
	9 Boring Completed at 9 ft.								

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual.

\*Calibrated Hand Penetrometer  
Exhibit A-38

**WATER LEVEL OBSERVATIONS, ft**

WL	N/E	WD	▼
WL	N/E	AB	▼
WL			



BORING STARTED		1-23-10	
BORING COMPLETED		1-23-10	
RIG	Truck	FOREMAN	JJ
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT 3/4/10

# LOG OF BORING NO. JL-2

CLIENT <b>Northern Kentucky Water District</b>		ELEVATION REFERENCE <b>Interpolated from Site Topographic Plans</b>									
SITE <b>Alexandria, Kentucky</b>		PROJECT <b>Proposed Sub-District H Water Main Ext. Ph. 2</b>									
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan		SAMPLES				TESTS				
	DESCRIPTION		DEPTH, ft.	USCS SYMBOL	NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf	UNCONFINED STRENGTH, psf
	Approx. Surface Elev.: 534 ft										
	0.5	CONCRETE PAVEMENT	533.5								
	0.7	GRANULAR BASE	533.3		1	SS	72	2-3-5 (8)	29		3000*
2.5	POSSIBLE FILL, fat clay, brown, stiff	531.5									
5	LEAN CLAY, trace sand and silt, dark brown and brown, medium stiff	529	5	CL	2	SS	100	8-5-6 (11)	19	2000*	
9	LEAN CLAY, some silt, little to some sand, trace iron concretions, brown, very stiff	525		CL	3	SS	100	4-4-7 (11)	19	7000*	
9	Boring Completed at 9 ft.	525		CL	4	SS	100	16-14-14 (28)	17	8000*	

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual.

\*Calibrated Hand Penetrometer  
Exhibit A-39

WATER LEVEL OBSERVATIONS, ft			
WL	▽	N/E	WD
WL	▽	N/E	AB
WL			



BORING STARTED	1-23-10
BORING COMPLETED	1-23-10
RIG	Truck
LOGGED	DRK
FOREMAN	JJ
JOB #	N1095342

BOREHOLE 99 BORING LOGS PH.2.GPJ TERRACON TEST.GDT 3/4/10

# LOG OF BORING NO. JL-3

CLIENT <b>Northern Kentucky Water District</b>		ELEVATION REFERENCE <b>Interpolated from Site Topographic Plans</b>									
SITE <b>Alexandria, Kentucky</b>		PROJECT <b>Proposed Sub-District H Water Main Ext. Ph. 2</b>									
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan		SAMPLES			TESTS					
	DESCRIPTION		DEPTH, ft.	USCS SYMBOL	NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf	UNCONFINED STRENGTH, psf
	Approx. Surface Elev.: 584 ft										
	0.3	CONCRETE PAVEMENT	583.7								
	0.5	GRANULAR BASE	583.5		1	SS	89	2-3-2 (5)	10		2000*
	2.5	FILL, fat clay, brown, medium stiff	581.5								
	3.5	FILL, fat clay, trace root matter, brown and gray, stiff	580.5		2	SS	100	3-3	29		4000*
	5	LEAN CLAY, trace silt, brown, very stiff	579		CL	2A	SS	100	4	25	6000*
	5	FAT CLAY, brown and gray, very stiff to stiff	579	5	CH	3	SS	100	5-7-10 (17)	24	13543
	9	Boring Completed at 9 ft.	575		CH	4	SS	100	7-7-10 (17)	26	4000*

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual.

\*Calibrated Hand Penetrometer  
Exhibit A-40

WATER LEVEL OBSERVATIONS, ft				 A Terracon COMPANY	BORING STARTED		1-23-10
WL	▽ 0.5	WD	▽		BORING COMPLETED		1-23-10
WL	▽ N/E	AB	▽		RIG	Truck	FOREMAN JJ
WL					LOGGED	DRK	JOB # N1095342

# LOG OF BORING NO. JM-1

CLIENT <b>Northern Kentucky Water District</b>		ELEVATION REFERENCE <b>Interpolated from Site Topographic Plans</b>	
SITE <b>Alexandria, Kentucky</b>		PROJECT <b>Proposed Sub-District H Water Main Ext. Ph. 2</b>	
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan		SAMPLES
	DESCRIPTION	TESTS	
	Approx. Surface Elev.: 524 ft	DEPTH, ft.	USCS SYMBOL
		NUMBER	TYPE
		RECOVERY, %	BLOWS / 6in. (SPT - N)
		WATER CONTENT, %	DRY UNIT WT pcf
		UNCONFINED STRENGTH, psf	
1	TOPSOIL 523	1	SS 100
2.5	<u>LEAN CLAY</u> , trace sand, gravel and shale fragments, brown 521.5	1A	SS 100
5	<u>LEAN CLAY</u> , trace sand, dark brown, very stiff 519	2	SS 100
5	<u>LEAN CLAY</u> , trace to little shale and limestone fragments, brown, stiff to very stiff 519	3	SS 100
9	<u>LEAN CLAY</u> , trace to little shale and limestone fragments, brown, stiff to very stiff 515	4	SS 100
	Boring Completed at 9 ft.		

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual. \*Calibrated Hand Penetrometer Exhibit A-41

WATER LEVEL OBSERVATIONS, ft			
WL	∇ N/E	WD	∇
WL	∇ N/E	AB	∇
WL			



BORING STARTED		2-1-10	
BORING COMPLETED		2-1-10	
RIG	Truck	FOREMAN	JG
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT. 3/4/10

# LOG OF BORING NO. JM-2

<b>CLIENT</b> Northern Kentucky Water District	<b>ELEVATION REFERENCE</b> Interpolated from Site Topographic Plans
---	--

<b>SITE</b> Alexandria, Kentucky	<b>PROJECT</b> Proposed Sub-District H Water Main Ext. Ph. 2
-------------------------------------	---

GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan	DESCRIPTION	DEPTH, ft.	USCS SYMBOL	SAMPLES				TESTS	
					NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf
Approx. Surface Elev.: 562 ft										
2.5	559.5	<b>FAT CLAY</b> , trace shale fragments, brown, stiff	1	CH	SS	100	2-4-4 (8)	29		4000*
4	558	<b>WEATHERED SHALE</b> , some limestone fragments, brown, soft	2		SS	100	50/5"	19		
		Boring Completed at 4 ft.								

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual.

\*Calibrated Hand Penetrometer Exhibit A-42

**WATER LEVEL OBSERVATIONS, ft**

WL	▽ N/E	WD	▼
WL	▽ N/E	AB	▽
WL			



BORING STARTED		2-2-10	
BORING COMPLETED		2-2-10	
RIG	Truck	FOREMAN	JG
LOGGED	DRK	JOB #	N1095342

# LOG OF BORING NO. LL-1

CLIENT <b>Northern Kentucky Water District</b>		ELEVATION REFERENCE <b>Interpolated from Site Topographic Plans</b>						
SITE <b>Alexandria, Kentucky</b>		PROJECT <b>Proposed Sub-District H Water Main Ext. Ph. 2</b>						
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan	SAMPLES						
	DESCRIPTION	TESTS						
	Approx. Surface Elev.: 528 ft	DEPTH, ft.	USCS SYMBOL	NUMBER				
			TYPE	RECOVERY, %				
			BLOWS / 6in. (SPT - N)	WATER CONTENT, %				
		DRY UNIT WT pcf	UNCONFINED STRENGTH, psf					
2.5	525.5	1	SS	22	2-1-2 (3)	40	1000*	
7.5	520.5	CH	2	SS	100	7-7-7 (14)	29	4760
9	519	CH	3	SS	100	4-6-7 (13)	31	6000*
		CL	4	SS	100	8-10-10 (20)	18	8000*
Boring Completed at 9 ft.								

LL=78%  
PI=52%

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual. \*Calibrated Hand Penetrometer Exhibit A-43

WATER LEVEL OBSERVATIONS, ft			
WL	▽ N/E	WD	▽
WL	▽ N/E	AB	▽
WL			



BORING STARTED		2-1-10	
BORING COMPLETED		2-1-10	
RIG	Truck	FOREMAN	JG
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT 3/4/10



# LOG OF BORING NO. LL-2

<b>CLIENT</b> Northern Kentucky Water District		<b>ELEVATION REFERENCE</b> Interpolated from Site Topographic Plans																																																				
<b>SITE</b> Alexandria, Kentucky		<b>PROJECT</b> Proposed Sub-District H Water Main Ext. Ph. 2																																																				
GRAPHIC LOG	Boring Location: As Shown on Test Boring Location Plan  DESCRIPTION  Approx. Surface Elev.: 534 ft	DEPTH, ft.	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th colspan="3">SAMPLES</th> <th colspan="4">TESTS</th> </tr> <tr> <th>USCS SYMBOL</th> <th>NUMBER</th> <th>TYPE</th> <th>RECOVERY, %</th> <th>BLOWS / 6in. (SPT - N)</th> <th>WATER CONTENT, %</th> <th>DRY UNIT WT pcf</th> <th>UNCONFINED STRENGTH, psf</th> </tr> </thead> <tbody> <tr> <td rowspan="2">CL</td> <td>1</td> <td>SS</td> <td>100</td> <td>1</td> <td rowspan="2">31</td> <td rowspan="2"></td> <td rowspan="2">8000*</td> </tr> <tr> <td>1A</td> <td>SS</td> <td>100</td> <td>2-5 (7)</td> </tr> <tr> <td>CL</td> <td>2</td> <td>SS</td> <td>100</td> <td>6-7-13 (20)</td> <td>20</td> <td></td> <td>6000*</td> </tr> <tr> <td>CL</td> <td>3</td> <td>SS</td> <td>100</td> <td>6-6-8 (14)</td> <td>17</td> <td></td> <td>8000*</td> </tr> <tr> <td>CL</td> <td>4</td> <td>SS</td> <td>100</td> <td>7-9-9 (18)</td> <td>17</td> <td></td> <td>6000*</td> </tr> </tbody> </table>	SAMPLES			TESTS				USCS SYMBOL	NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf	UNCONFINED STRENGTH, psf	CL	1	SS	100	1	31		8000*	1A	SS	100	2-5 (7)	CL	2	SS	100	6-7-13 (20)	20		6000*	CL	3	SS	100	6-6-8 (14)	17		8000*	CL	4	SS	100	7-9-9 (18)	17		6000*
	SAMPLES			TESTS																																																		
	USCS SYMBOL	NUMBER	TYPE	RECOVERY, %	BLOWS / 6in. (SPT - N)	WATER CONTENT, %	DRY UNIT WT pcf	UNCONFINED STRENGTH, psf																																														
	CL	1	SS	100	1	31		8000*																																														
		1A	SS	100	2-5 (7)																																																	
CL	2	SS	100	6-7-13 (20)	20		6000*																																															
CL	3	SS	100	6-6-8 (14)	17		8000*																																															
CL	4	SS	100	7-9-9 (18)	17		6000*																																															
0.5	533.5	5																																																				
7.5	526.5																																																					
9	525																																																					
Boring Completed at 9 ft.																																																						

The stratification lines represent the approximate boundary lines between soil and rock types: in-situ, the transition may be gradual.

\*Calibrated Hand Penetrometer Exhibit A-44

**WATER LEVEL OBSERVATIONS, ft**

WL	∇ N/E	WD	∇
WL	∇ N/E	AB	∇
WL			



BORING STARTED		2-1-10	
BORING COMPLETED		2-1-10	
RIG	Truck	FOREMAN	JG
LOGGED	DRK	JOB #	N1095342

BOREHOLE 99 BORING LOGS PH 2.GPJ TERRACON TEST.GDT 3/4/10

**APPENDIX A**  
**FIELD EXPLORATION**

## Geotechnical Engineering Report

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY  
May 21, 2010 ■ HCN/Terracon Project No. N1095342



### Field Exploration Description

The boring locations were laid out on the site by HCN/Terracon personnel using water main alignment plans provided by Viox & Viox Inc., (undated). Ground surface elevations at test boring locations were interpolated from the water main alignment plan drawings. The borings were drilled with truck-mounted rotary drill rig using continuous flight hollow-stem augers to advance the boreholes. Samples of the soil encountered in the borings were obtained using the split-barrel sampling procedures.

In the split barrel sampling procedure, the number of blows required to advance a standard 2 inch O.D. split barrel sampler the last 12 inches of the typical total 18 inch penetration by means of a rope and cathead manual safety hammer with a free fall of 30 inches, is the standard penetration resistance value (SPT-N). This value is used to estimate the in-situ relative density of cohesionless soils and consistency of cohesive soils.

An automatic SPT hammer was used to advance the split-barrel sampler in the borings performed on this site. A greater efficiency is typically achieved with the automatic hammer compared to the conventional safety hammer operated with a cathead and rope. Published correlations between the SPT values and soil properties are based on the lower efficiency cathead and rope method. This higher efficiency affects the standard penetration resistance blow count (N) value by increasing the penetration per hammer blow over what would be obtained using the cathead and rope method. The effect of the automatic hammer's efficiency has been considered in the interpretation and analysis of the subsurface information for this report.

The samples were tagged for identification, sealed to reduce moisture loss, and taken to our laboratory for further examination, testing, and classification. Information provided on the boring logs attached to this report includes soil descriptions, consistency evaluations, boring depths, sampling intervals, and groundwater conditions. The borings were backfilled with auger cuttings prior to the drill crew leaving the site.

A field log of each boring was prepared by the drill crew. These logs included visual classifications of the materials encountered during drilling as well as the driller's interpretation of the subsurface conditions between samples. Final boring logs included with this report represent the engineer's review of obtained soil samples, driller's field logs and include modifications based on laboratory tests of the samples.

**APPENDIX B**  
**SUPPORTING INFORMATION**

**Geotechnical Engineering Report**

Sub-District H Water Main Extension – Phase 2 ■ Campbell County, KY  
May 21, 2010 ■ HCN/Terracon Project No. N1095342




**Laboratory Testing**

Selected soil samples were tested in the laboratory to measure natural water content and Atterberg Limits. Three unconfined compression strength tests were also performed on selected natural cohesive soil samples. A calibrated hand penetrometer was used to estimate the approximate unconfined compressive strength of some samples. The calibrated hand penetrometer has been correlated with unconfined compression tests and provides a better estimate of soil consistency than visual examination alone. The test results are provided on the boring logs included in Appendix A.

Descriptive classifications of the soils indicated on the boring logs are in accordance with the enclosed General Notes and the Unified Soil Classification System. Also shown are estimated Unified Soil Classification Symbols. A brief description of this classification system is attached to this report. All classification was by visual manual procedures. Selected samples were further classified using the results of Atterberg limit testing. The Atterberg limit test results are also provided on the boring logs.

## UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	3146.8			
Undrained shear strength, psf	1573.4			
Failure strain,	10.8			
Strain rate, in./min.	0.027			
Water content, %	24.5			
Wet density, pcf	122.9			
Dry density, pcf	98.7			
Saturation, %	93.5			
Void ratio	0.7070			
Specimen diameter, in.	1.380			
Specimen height, in.	2.790			
Height/diameter ratio	2.02			

**Description:** BROWN GRAY CLAY, MOIST - STIFF

LL =	PL =	PI =	Assumed GS= 2.70	Type: SS
------	------	------	------------------	----------

**Project No.:** N1095342  
**Date:** 2-8-10  
**Remarks:**  
 Lab No. 770

**Client:** NORTHERN KENTUCKY WATER DISTRICT  
**Project:** SUBDISTRICT H WATER MAIN EXT.  
**Source of Sample:** CR-1      **Depth:** 2.5-4'  
**Sample Number:** 2


**EXHIBIT B-2**

UNCONFINED COMPRESSION TEST  
**H. C. NUTTING COMPANY**

Figure \_\_\_\_\_

Tested By: SV      Checked By: GS

## UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	13542.8		
Undrained shear strength, psf	6771.4		
Failure strain,	5.4		
Strain rate, in./min.	0.027		
Water content, %	24.0		
Wet density, pcf	126.5		
Dry density, pcf	102.0		
Saturation, %	99.4		
Void ratio	0.6523		
Specimen diameter, in.	1.400		
Specimen height, in.	2.790		
Height/diameter ratio	1.99		

**Description:** BROWN GRAY CLAY, MOIST - VERY STIFF

LL =	PL =	PI =	Assumed GS= 2.70	Type: SS
------	------	------	------------------	----------

**Project No.:** N1095342

**Date:** 2-2-10

**Remarks:**  
Lab No. 683

**EXHIBIT B-3**

Figure \_\_\_\_\_

**Client:** NORTHERN KENTUCKY WATER DISTRICT

**Project:** SUBDISTRICT H WATER MAIN EXT.

**Source of Sample:** JL-3      **Depth:** 5-6.5'

**Sample Number:** 3


UNCONFINED COMPRESSION TEST

**H. C. NUTTING COMPANY**

**Tested By:** SV \_\_\_\_\_

**Checked By:** GS \_\_\_\_\_

## UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	4759.7			
Undrained shear strength, psf	2379.9			
Failure strain,	4.7			
Strain rate, in./min.	0.027			
Water content, %	29.2			
Wet density, pcf	121.5			
Dry density, pcf	94.0			
Saturation, %	99.5			
Void ratio	0.7927			
Specimen diameter, in.	1.440			
Specimen height, in.	2.790			
Height/diameter ratio	1.94			

**Description:** BROWN CLAY, MOIST - STIFF

LL =      PL =      PI =      Assumed GS= 2.70      Type: SS

**Project No.:** N1095342

**Date:** 2-8-10

**Remarks:**  
Lab No. 781

**Client:** NORTHERN KENTUCKY WATER DISTRICT

**Project:** SUBDISTRICT H WATER MAIN EXT. PHASE 4

**Source of Sample:** LL-1

**Depth:** 2.5-4'

**Sample Number:** 2

**EXHIBIT B-4**

UNCONFINED COMPRESSION TEST

**H. C. NUTTING COMPANY**

Figure \_\_\_\_\_

Tested By: SV      Checked By: GS



**APPENDIX C**  
**SUPPORTING DOCUMENTS**

## GENERAL NOTES

### DRILLING & SAMPLING SYMBOLS:

SS: Split Spoon – 1- <sup>3</sup> / <sub>8</sub> " I.D., 2" O.D., unless otherwise noted	HS: Hollow Stem Auger
ST: Thin-Walled Tube - 2" O.D., unless otherwise noted	PA: Power Auger
RS: Ring Sampler - 2.42" I.D., 3" O.D., unless otherwise noted	HA: Hand Auger
DB: Diamond Bit Coring - 4", N, B	RB: Rock Bit
BS: Bulk Sample or Auger Sample	WB: Wash Boring or Mud Rotary

The number of blows required to advance a standard 2-inch O.D. split-spoon sampler (SS) the last 12 inches of the total 18-inch penetration with a 140-pound hammer falling 30 inches is considered the "Standard Penetration" or "N-value".

### WATER LEVEL MEASUREMENT SYMBOLS:

WL: Water Level	WS: While Sampling	N/E: Not Encountered
WCI: Wet Cave in	WD: While Drilling	
DCI: Dry Cave in	BCR: Before Casing Removal	
AB: After Boring	ACR: After Casing Removal	

Water levels indicated on the boring logs are the levels measured in the borings at the times indicated. Groundwater levels at other times and other locations across the site could vary. In pervious soils, the indicated levels may reflect the location of groundwater. In low permeability soils, the accurate determination of groundwater levels may not be possible with only short-term observations.

**DESCRIPTIVE SOIL CLASSIFICATION:** Soil classification is based on the Unified Classification System. Coarse Grained Soils have more than 50% of their dry weight retained on a #200 sieve; their principal descriptors are: boulders, cobbles, gravel or sand. Fine Grained Soils have less than 50% of their dry weight retained on a #200 sieve; they are principally described as clays if they are plastic, and silts if they are slightly plastic or non-plastic. Major constituents may be added as modifiers and minor constituents may be added according to the relative proportions based on grain size. In addition to gradation, coarse-grained soils are defined on the basis of their in-place relative density and fine-grained soils on the basis of their consistency.

#### CONSISTENCY OF FINE-GRAINED SOILS

<u>Unconfined Compressive Strength, Qu, psf</u>	<u>Standard Penetration or N-value (SS) Blows/Ft.</u>	<u>Consistency</u>
< 500	<2	Very Soft
500 – 1,000	2-3	Soft
1,001 – 2,000	4-6	Medium Stiff
2,001 – 4,000	7-12	Stiff
4,001 – 8,000	13-26	Very Stiff
8,000+	26+	Hard

#### RELATIVE DENSITY OF COARSE-GRAINED SOILS

<u>Standard Penetration or N-value (SS) Blows/Ft.</u>	<u>Ring Sampler (RS) Blows/Ft.</u>	<u>Relative Density</u>
0 – 3	0-6	Very Loose
4 – 9	7-18	Loose
10 – 29	19-58	Medium Dense
30 – 49	59-98	Dense
50+	99+	Very Dense

#### RELATIVE PROPORTIONS OF SAND AND GRAVEL

<u>Descriptive Term(s) of other Constituents</u>	<u>Percent of Dry Weight</u>
Trace	< 15
With	15 – 29
Modifier	> 30

#### GRAIN SIZE TERMINOLOGY

<u>Major Component of Sample</u>	<u>Particle Size</u>
Boulders	Over 12 in. (300mm)
Cobbles	12 in. to 3 in. (300mm to 75 mm)
Gravel	3 in. to #4 sieve (75mm to 4.75 mm)
Sand	#4 to #200 sieve (4.75mm to 0.075mm)
Silt or Clay	Passing #200 Sieve (0.075mm)

#### RELATIVE PROPORTIONS OF FINES

<u>Descriptive Term(s) of other Constituents</u>	<u>Percent of Dry Weight</u>
Trace	< 5
With	5 – 12
Modifiers	> 12

#### PLASTICITY DESCRIPTION


<u>Term</u>	<u>Plasticity Index</u>
Non-plastic	0
Low	1-10
Medium	11-30
High	30+

# UNIFIED SOIL CLASSIFICATION SYSTEM

Criteria for Assigning Group Symbols and Group Names Using Laboratory Tests <sup>A</sup>				Soil Classification		
				Group Symbol	Group Name <sup>B</sup>	
<b>Coarse Grained Soils:</b> More than 50% retained on No. 200 sieve	<b>Gravels:</b> More than 50% of coarse fraction retained on No. 4 sieve	<b>Clean Gravels:</b> Less than 5% fines <sup>C</sup>	$Cu \geq 4$ and $1 \leq Cc \leq 3$ <sup>E</sup>	GW	Well-graded gravel <sup>F</sup>	
			$Cu < 4$ and/or $1 > Cc > 3$ <sup>E</sup>	GP	Poorly graded gravel <sup>F</sup>	
		<b>Gravels with Fines:</b> More than 12% fines <sup>C</sup>	Fines classify as ML or MH	GM	Silty gravel <sup>F,G,H</sup>	
			Fines classify as CL or CH	GC	Clayey gravel <sup>F,G,H</sup>	
	<b>Sands:</b> 50% or more of coarse fraction passes No. 4 sieve	<b>Clean Sands:</b> Less than 5% fines <sup>D</sup>	$Cu \geq 6$ and $1 \leq Cc \leq 3$ <sup>E</sup>	SW	Well-graded sand <sup>I</sup>	
			$Cu < 6$ and/or $1 > Cc > 3$ <sup>E</sup>	SP	Poorly graded sand <sup>I</sup>	
		<b>Sands with Fines:</b> More than 12% fines <sup>D</sup>	Fines classify as ML or MH	SM	Silty sand <sup>G,H,I</sup>	
			Fines Classify as CL or CH	SC	Clayey sand <sup>G,H,I</sup>	
<b>Fine-Grained Soils:</b> 50% or more passes the No. 200 sieve	<b>Silts and Clays:</b> Liquid limit less than 50	<b>Inorganic:</b>	$PI > 7$ and plots on or above "A" line <sup>J</sup>	CL	Lean clay <sup>K,L,M</sup>	
			$PI < 4$ or plots below "A" line <sup>J</sup>	ML	Silt <sup>K,L,M</sup>	
		<b>Organic:</b>	Liquid limit - oven dried	< 0.75	OL	Organic clay <sup>K,L,M,N</sup>
			Liquid limit - not dried		OH	Organic silt <sup>K,L,M,O</sup>
		<b>Silts and Clays:</b> Liquid limit 50 or more	<b>Inorganic:</b>	PI plots on or above "A" line	CH	Fat clay <sup>K,L,M</sup>
				PI plots below "A" line	MH	Elastic Silt <sup>K,L,M</sup>
	<b>Organic:</b>		Liquid limit - oven dried	< 0.75	OH	Organic clay <sup>K,L,M,P</sup>
			Liquid limit - not dried		OH	Organic silt <sup>K,L,M,Q</sup>
	<b>Highly organic soils:</b>	Primarily organic matter, dark in color, and organic odor			PT	Peat

- <sup>A</sup> Based on the material passing the 3-in. (75-mm) sieve
- <sup>B</sup> If field sample contained cobbles or boulders, or both, add "with cobbles or boulders, or both" to group name.
- <sup>C</sup> Gravels with 5 to 12% fines require dual symbols: GW-GM well-graded gravel with silt, GW-GC well-graded gravel with clay, GP-GM poorly graded gravel with silt, GP-GC poorly graded gravel with clay.
- <sup>D</sup> Sands with 5 to 12% fines require dual symbols: SW-SM well-graded sand with silt, SW-SC well-graded sand with clay, SP-SM poorly graded sand with silt, SP-SC poorly graded sand with clay
- <sup>E</sup>  $Cu = D_{60}/D_{10}$      $Cc = \frac{(D_{30})^2}{D_{10} \times D_{60}}$
- <sup>F</sup> If soil contains  $\geq 15\%$  sand, add "with sand" to group name.
- <sup>G</sup> If fines classify as CL-ML, use dual symbol GC-GM, or SC-SM.

- <sup>H</sup> If fines are organic, add "with organic fines" to group name.
- <sup>I</sup> If soil contains  $\geq 15\%$  gravel, add "with gravel" to group name.
- <sup>J</sup> If Atterberg limits plot in shaded area, soil is a CL-ML, silty clay.
- <sup>K</sup> If soil contains 15 to 29% plus No. 200, add "with sand" or "with gravel," whichever is predominant.
- <sup>L</sup> If soil contains  $\geq 30\%$  plus No. 200 predominantly sand, add "sandy" to group name.
- <sup>M</sup> If soil contains  $\geq 30\%$  plus No. 200, predominantly gravel, add "gravelly" to group name.
- <sup>N</sup>  $PI \geq 4$  and plots on or above "A" line.
- <sup>O</sup>  $PI < 4$  or plots below "A" line.
- <sup>P</sup> PI plots on or above "A" line.
- <sup>Q</sup> PI plots below "A" line.



# GENERAL NOTES

## Description of Rock Properties

### WEATHERING

Fresh Rock fresh, crystals bright, few joints may show slight staining. Rock rings under hammer if crystalline.

Very slight Rock generally fresh, joints stained, some joints may show thin clay coatings, crystals in broken face show bright. Rock rings under hammer if crystalline.

Slight Rock generally fresh, joints stained, and discoloration extends into rock up to 1 in. Joints may contain clay. In granitoid rocks some occasional feldspar crystals are dull and discolored. Crystalline rocks ring under hammer.

Moderate Significant portions of rock show discoloration and weathering effects. In granitoid rocks, most feldspars are dull and discolored; some show clayey. Rock has dull sound under hammer and shows significant loss of strength as compared with fresh rock.

Moderately severe All rock except quartz discolored or stained. In granitoid rocks, all feldspars dull and discolored and majority show kaolinization. Rock shows severe loss of strength and can be excavated with geologist's pick.

Severe All rock except quartz discolored or stained. Rock "fabric" clear and evident, but reduced in strength to strong soil. In granitoid rocks, all feldspars kaolinized to some extent. Some fragments of strong rock usually left.

Very severe All rock except quartz discolored or stained. Rock "fabric" discernible, but mass effectively reduced to "soil" with only fragments of strong rock remaining.

Complete Rock reduced to "soil". Rock "fabric" not discernible or discernible only in small, scattered locations. Quartz may be present as dikes or stringers.

### HARDNESS (for engineering description of rock – not to be confused with Moh's scale for minerals)

Very hard Cannot be scratched with knife or sharp pick. Breaking of hand specimens requires several hard blows of geologist's pick.

Hard Can be scratched with knife or pick only with difficulty. Hard blow of hammer required to detach hand specimen.

Moderately hard Can be scratched with knife or pick. Gouges or grooves to ¼ in. deep can be excavated by hard blow of point of a geologist's pick. Hand specimens can be detached by moderate blow.

Medium Can be grooved or gouged 1/16 in. deep by firm pressure on knife or pick point. Can be excavated in small chips to pieces about 1-in. maximum size by hard blows of the point of a geologist's pick.

Soft Can be gouged or grooved readily with knife or pick point. Can be excavated in chips to pieces several inches in size by moderate blows of a pick point. Small thin pieces can be broken by finger pressure.

Very soft Can be carved with knife. Can be excavated readily with point of pick. Pieces 1-in. or more in thickness can be broken with finger pressure. Can be scratched readily by fingernail.

**Joint, Bedding and Foliation Spacing in Rock <sup>a</sup>**

Spacing	Joints	Bedding/Foliation
Less than 2 in.	Very close	Very thin
2 in. – 1 ft.	Close	Thin
1 ft. – 3 ft.	Moderately close	Medium
3 ft. – 10 ft.	Wide	Thick
More than 10 ft.	Very wide	Very thick

**Rock Quality Designator (RQD) <sup>b</sup>**

**Joint Openness Descriptors**

RQD, as a percentage	Diagnostic description	Openness	Descriptor
Exceeding 90	Excellent	No Visible Separation	Tight
90 – 75	Good	Less than 1/32 in.	Slightly Open
75 – 50	Fair	1/32 to 1/8 in.	Moderately Open
50 – 25	Poor	1/8 to 3/8 in.	Open
Less than 25	Very poor	3/8 in. to 0.1 ft.	Moderately Wide
		Greater than 0.1 ft.	Wide

a. Spacing refers to the distance normal to the planes, of the described feature, which are parallel to each other or nearly so.

b. RQD (given as a percentage) = length of core in pieces 4 in. and longer/length of run.

References: American Society of Civil Engineers. Manuals and Reports on Engineering Practice - No. 56. Subsurface Investigation for Design and Construction of Foundations of Buildings. New York: American Society of Civil Engineers, 1976.

U.S. Department of the Interior, Bureau of Reclamation, Engineering Geology Field Manual.