

LG&E - KU- Ghent Unit 3 PJFF (Without SCR) Rev. B

B&V PROJECT #:	168908	LOCATION:	Carroll County, KY
PROJECT ESTIMATOR:	Ron Fields	PLANT TYPE:	PC Fired Boiler
PROJECT MANAGER:	Tim Hillman	CLIENT:	LG&E - KU
PURPOSE OF ESTIMATE:	Budgetary	PARTNER:	N/A
ESTIMATE DATE:	April-11	CURRENCY:	US Dollars

BLACK AND VEATCH CONFIDENTIAL AND PROPRIETARY INFORMATION

Contract Number	Description	PROJECT - TOTAL COSTS						% OF TOTAL C.V.	\$ PER KW 523
		Engr Equip	Commodities						
		Material \$	Material \$	Labor \$	Manhours	Other	TOTAL \$		

ESTIMATE SUMMARY

Purchase Contracts:

61.0000	Civil / Structural	\$2,431,204	\$298,100	\$1,096,286	15,840	\$100,000	\$3,925,590	2.73%	\$7.51
61.3801	Ductwork and breeching	\$3,102,400	\$0	\$0	0	\$0	\$3,102,400	2.16%	\$5.93
62.0000	Mechanical - Balance of Plant - (BOP)	\$0	\$0	\$0	0	\$50,000	\$50,000	0.03%	\$0.10
63.0000	Electrical - (BOP) Equipment and raceway	\$490,000	\$1,062,495	\$0	0	\$0	\$1,552,495	1.08%	\$2.97
63.3002	VFDs, Motors and Couplings	\$7,948,000	\$0	\$0	0	\$0	\$7,948,000	5.53%	\$15.20
63.1202	Cable Bus	\$0	\$327,912	\$0	0	\$16,200	\$344,112	0.24%	\$0.66
63.3603	Switchgear and MCCs	\$1,602,000	\$0	\$0	0	\$0	\$1,602,000	1.11%	\$3.06
63.3802	SUS Transformers	\$256,000	\$0	\$0	0	\$0	\$256,000	0.18%	\$0.49
63.3803	Aux Transformers	\$985,000	\$0	\$0	0	\$0	\$985,000	0.68%	\$1.88
64.0000	Control - DCS, Instrumentation	\$626,000	\$0	\$0	0	\$0	\$626,000	0.44%	\$1.20
64.0407	On-line Performance Monitoring - Neural Network	\$0	\$0	\$0	0	\$570,000	\$570,000	0.40%	\$1.09
65.3210	Remote Sorbent Injection Equipment	\$0	\$0	\$0	0	\$50,000	\$50,000	0.03%	\$0.10
65.3120	Fabric Filter	\$15,000,000	\$0	\$0	0	\$0	\$15,000,000	10.43%	\$28.68
65.3500	H-PAC Mercury Control	\$1,000,000	\$0	\$0	0	\$0	\$1,000,000	0.70%	\$1.91
66.1000	Piping & Tubing	\$315,018	\$0	\$0	0	\$0	\$315,018	0.22%	\$0.60
66.2070	Pipe Supports	\$0	\$79,250	\$0	0	\$0	\$79,250	0.06%	\$0.15
67.0414	Fly Ash Transfer System	\$0	\$0	\$0	0	\$2,300,000	\$2,300,000	1.60%	\$4.40
66.3000	Valves and Accessories	\$0	\$232,000	\$0	0	\$0	\$232,000	0.16%	\$0.44
67.9300	Air Compressors, Dryers, & Air Receivers	\$250,000	\$0	\$0	0	\$0	\$250,000	0.17%	\$0.48
67.9532	ID Fans	\$3,860,000	\$0	\$0	0	\$0	\$3,860,000	2.68%	\$7.38
Subtotal Purchase Contracts:		\$37,865,622	\$1,999,757	\$1,096,286	15,840	\$3,086,200	\$44,047,866	30.63%	\$84.22

Construction Contracts:

71.0100	Demolition works	\$0	\$0	\$0	\$0	\$400,000	\$400,000	0.28%	\$0.76
71.0401	Civil / Structural Construction - Cast In place Piling	\$0	\$0	\$0	\$0	\$2,415,000	\$2,415,000	1.68%	\$4.62
71.0403	Civil / Structural Construction - Super Structures	\$0	\$879,896	\$2,852,813	\$49,551	\$127,043	\$3,859,752	2.68%	\$7.38
71.0402	Civil / Structural Construction - Sub-Structures	\$0	\$15,000	\$4,255,354	\$61,485	\$4,280,000	\$8,550,354	5.94%	\$16.35
72.0000	Mechanical / Chemical Construction	\$0	\$0	\$14,283,571	232,519	\$3,420,250	\$17,703,821	12.31%	\$33.85
73.0000	Electrical / Control Construction	\$0	\$182,000	\$4,055,961	64,916	\$10,800	\$4,248,761	2.95%	\$8.12
77.5450	Field Erected Frac Tank	\$0	\$0	\$0	0	\$417,555	\$417,555	0.29%	\$0.80
78.0000	Service Contracts & Construction Indirects	\$0	\$3,274,064	\$3,771,554	80,924	\$11,765,076	\$18,810,693	13.08%	\$35.97
Subtotal Construction Contracts:		\$0	\$4,350,959	\$29,219,252	489,395	\$22,835,724	\$56,405,935	39.22%	\$107.85
Total Direct Costs		\$37,865,622	\$6,350,716	\$30,315,539	505,235	\$25,921,924	\$100,453,801	69.84%	\$192.07

Indirect Costs:

99.1100	Engineering Costs (Includes G&A)	\$0	\$0	\$2,460,000	60,000	\$3,655,560	\$6,115,560	4.25%	\$11.69
99.1200	EPC Construction Management (Includes G&A)	\$0	\$69,760	\$5,445,664	119,425	\$7,605,422	\$13,120,846	9.12%	\$25.09
99.1500	Project Insurance	\$0	\$0	\$0	0	\$1,714,505	\$1,714,505	1.19%	\$3.28
99.1600	Performance Bond	\$0	\$0	\$0	0	\$734,788	\$734,788	0.51%	\$1.40
99.1900	Sales Tax 6% of Indirect materials and services	\$0	\$59,997	\$0	0	\$0	\$59,997	0.04%	\$0.11
99.2500	Project Contingency 10 %	\$0	\$0	\$0	0	\$12,219,950	\$12,219,950	8.50%	\$23.37
99.2600	EPC Profit	\$0	\$0	\$0	0	\$9,409,000	\$9,409,000	6.54%	\$17.99
Total Indirect Costs		\$0	\$129,757	\$7,905,664	179,425	\$35,339,225	\$43,374,645	28.63%	\$82.93
Total Overnight (April 2011) EPC Capital Costs:		\$37,865,622	\$6,480,473	\$38,221,202	684,660	\$61,261,149	\$143,828,446	100.00%	\$275.01
		\$0	\$0	\$0	0	\$0	\$0	0.00%	\$0.00

LG&E - KU- Ghent Unit 3 PJFF (Without SCR) Rev. B

B&V PROJECT #:	168908	LOCATION:	Carroll County, KY
PROJECT ESTIMATOR:	Ron Fields	PLANT TYPE:	PC Fired Boiler
PROJECT MANAGER:	Tim Hillman	CLIENT:	LG&E - KU
PURPOSE OF ESTIMATE:	Budgetary	PARTNER:	N/A
ESTIMATE DATE:	April-11	CURRENCY:	US Dollars

BLACK AND VEATCH CONFIDENTIAL AND PROPRIETARY INFORMATION

Contract Number	Description	PROJECT - TOTAL COSTS						% OF TOTAL C.V.	\$ PER KW 523
		Engr Equip	Commodities						
		Material \$	Material \$	Labor \$	Manhours	Other	TOTAL \$		

ESTIMATE SUMMARY

Purchase Contracts:									
61.0000	Civil / Structural	\$5,533,604	\$298,100	\$1,096,286	15,840	\$100,000	\$7,027,990	4.89%	\$13.44
62.0000	Mechanical	\$4,425,018	\$311,250	\$0	0	\$2,350,000	\$7,086,268	4.93%	\$13.55
63.0000	Electrical	\$11,281,000	\$1,390,407	\$0	0	\$16,200	\$12,687,607	8.82%	\$24.26
64.0000	Control	\$626,000	\$0	\$0	0	\$570,000	\$1,196,000	0.83%	\$2.29
65.0000	Chemical	\$16,000,000	\$0	\$0	0	\$50,000	\$16,050,000	11.16%	\$30.69
Subtotal Purchase Contracts:		\$37,865,622	\$1,999,757	\$1,096,286	15,840	\$3,086,200	\$44,047,866	30.63%	\$84.22
Construction Contracts:									
71.0100	Demolition Works	\$0	\$0	\$0	0	\$400,000	\$400,000	0.28%	\$0.76
71.0203	Site Finishing	\$0	\$0	\$0	0	\$0	\$0	0.00%	\$0.00
71.0401	Cast In place Piling	\$0	\$0	\$0	0	\$2,415,000	\$2,415,000	1.68%	\$4.62
71.0402	Civil / Structural Construction -Substrucutres	\$0	\$879,896	\$2,852,813	49,551	\$127,043	\$3,859,752	2.68%	\$7.38
71.0403	Civil / Structural Construction- Superstructures	\$0	\$15,000	\$4,255,354	61,485	\$4,280,000	\$8,550,354	5.94%	\$16.35
72.0000	Mechanical / Chemical Construction	\$0	\$0	\$14,283,571	232,519	\$3,837,805	\$18,121,376	12.60%	\$34.65
73.0000	Electrical / Control Construction	\$0	\$182,000	\$4,055,961	64,916	\$10,800	\$4,248,761	2.95%	\$8.12
78.0000	Service Contracts & Construction Indirects	\$0	\$3,274,064	\$3,771,554	80,924	\$11,765,076	\$18,810,693	13.08%	\$35.97
Subtotal Construction Contracts:		\$0	\$4,350,959	\$29,219,252	489,395	\$22,835,724	\$56,405,935	39.22%	\$107.85
Total Direct Costs		\$37,865,622	\$6,350,716	\$30,315,539	505,235	\$25,921,924	\$100,453,801	69.84%	\$192.07
Indirect Costs:									
99.1100	Engineering Costs (With G&A)	\$0	\$0	\$2,460,000	60,000	\$3,655,560	\$6,115,560	4.25%	\$11.69
99.1200	Construction Management (With G&A)	\$0	\$69,760	\$5,445,664	119,425	\$7,605,422	\$13,120,846	9.12%	\$25.09
99.1500	Project Insurance	\$0	\$0	\$0	0	\$1,714,505	\$1,714,505	1.19%	\$3.28
99.1600	Performance Bond	\$0	\$0	\$0	0	\$734,788	\$734,788	0.51%	\$1.40
99.1900	Sale Tax 6% of Indirect materials and services	\$0	\$59,997	\$0	0	\$0	\$59,997	0.04%	\$0.11
99.2500	Project Contingency @ 10%	\$0	\$0	\$0	0	\$12,219,950	\$12,219,950	8.50%	\$23.37
99.2600	EPC profit	\$0	\$0	\$0	0	\$9,409,000	\$9,409,000	6.54%	\$17.99
Total Indirect Costs		\$0	\$129,757	\$7,905,664	179,425	\$35,339,225	\$43,374,645	30.16%	\$82.93
Total Overnight (April 2011) EPC Capital Costs:		\$37,865,622	\$6,480,473	\$38,221,202	684,660	\$61,261,149	\$143,828,446	100.00%	\$275.01

LG&E - KU- Ghent Unit 3 PJFF (Without SCR) Rev. B

B&V PROJECT #:	168908	LOCATION:	Carroll County, KY
PROJECT ESTIMATOR:	Ron Fields	PLANT TYPE:	PC Fired Boiler
PROJECT MANAGER:	Tim Hillman	CLIENT:	LG&E - KU
PURPOSE OF ESTIMATE:	Budgetary	PARTNER:	N/A
ESTIMATE DATE:	April-11	CURRENCY:	US Dollars

BLACK AND VEATCH CONFIDENTIAL AND PROPRIETARY INFORMATION

Contract Number	Description	PROJECT - TOTAL COSTS						% OF TOTAL C.V.	\$ PER KW 523	
		Engr Equip	Commodities							
		Material \$	Material \$	Labor \$	Manhours	Other	TOTAL \$			
Civil / Structural Purchase Contracts:										
61.0300	Grating	\$0	\$3,520	\$0	0	\$0	\$3,520	0.00%	\$0.01	
61.0810	Embeds and Anchor Bolts	\$0	\$54,390	\$0	0	\$0	\$54,390	0.04%	\$0.10	
61.3601	Chain Link Fence	\$0	\$25,000	\$0	0	\$100,000	\$125,000	0.09%	\$0.24	
61.3801	Ductwork and Breeching	\$3,102,400	\$0	\$0	0	\$0	\$3,102,400	2.16%	\$5.93	
61.4001	Structural Steel	\$2,431,204	\$0	\$0	0	\$0	\$2,431,204	1.69%	\$4.65	
61.4015	Handrail and stairs	\$0	\$36,990	\$0	0	\$0	\$36,990	0.03%	\$0.07	
Subtotal - Civil / Structural Purchase Contracts:		\$5,533,604	\$298,100	\$1,096,286	15,840	\$100,000	\$7,027,990	4.89%	\$13.44	
Mechanical Purchase Contracts:										
62.0205	Continuous Emissions Monitoring (CEM)	\$0	\$0	\$0	0	\$0		0.03%	\$0.10	
67.0414	Fly Ash Tranfer System	\$0	\$0	\$0	0	\$2,300,000	\$2,300,000	1.60%	\$4.40	
67.9300	Compressors and Air Dryers	\$250,000	\$0	\$0	0	\$0	\$250,000	0.17%	\$0.48	
67.9532	ID Booster Fans	\$3,860,000	\$0	\$0	0	\$0	\$3,860,000	2.68%	\$7.38	
66.1000	Piping and Tubing	\$315,018	\$0	\$0	0	\$0	\$315,018	0.22%	\$0.60	
66.3000	Valves	\$0	\$232,000	\$0	0	\$0	\$232,000	0.16%	\$0.44	
66.2070	Piping supports	\$0	\$79,250	\$0	0	\$0	\$79,250	0.06%	\$0.15	
Subtotal - Mechanical Purchase Contracts:		\$4,425,018	\$311,250	\$0	\$0	\$2,350,000	\$7,086,268	4.93%	\$13.55	
Electrical Purchase Contracts:										
63.0000	Electrical Equipment & Materials	\$0	\$0	\$0	0	\$0		0.00%	\$0.00	
63.0500	Lightning Protection Equipment and Materials	\$0	\$1,400	\$0	0	\$0	\$1,400	0.00%	\$0.00	
63.0601	Plant Communication System	\$0	\$2,220	\$0	0	\$0	\$2,220	0.00%	\$0.00	
63.0601	Plant Communication System	\$0	\$300,000	\$0	0	\$0	\$300,000	0.21%	\$0.57	
63.0802	Cable and Raceway	\$0	\$500,000	\$0	0	\$0	\$500,000	0.35%	\$0.96	
63.1001	Welding System	\$0	\$7,500	\$0	0	\$0	\$7,500	0.01%	\$0.01	
63.1201	Iso-Phase Bus Duct	\$430,000	\$0	\$0	0	\$0	\$430,000	0.30%	\$0.82	
63.1202	Cable Bus	\$0	\$327,912	\$0	0	\$16,200	\$344,112	0.24%	\$0.66	
63.2000	Metering & Relaying	\$60,000	\$0	\$0	0	\$0	\$60,000	0.04%	\$0.11	
63.2800	UPS System	\$0	\$221,375	\$0	0	\$0	\$221,375	0.15%	\$0.42	
63.2805	PanelBoards	\$0	\$30,000	\$0	0	\$0	\$30,000	0.02%	\$0.06	
63.3002	VFDs, Motors and couplings	\$7,948,000	\$0	\$0	0	\$0	\$7,948,000	5.53%	\$15.20	
63.3603	Low Voltage Switchgear	\$1,602,000	\$0	\$0	0	\$0	\$1,602,000	1.11%	\$3.06	
63.3802	SUS Transformers	\$256,000	\$0	\$0	0	\$0	\$256,000	0.18%	\$0.49	
63.3803	Aux. - Misc. Transformers	\$985,000	\$0	\$0	0	\$0	\$985,000	0.68%	\$1.88	
63.5010	Grounding Materials and Equipment	\$0	\$0	\$0	0	\$0	\$0	0.00%	\$0.00	
Subtotal - Electrical Purchase Contracts:		\$11,281,000	\$1,390,407	\$0	0	\$16,200	\$12,687,607	8.82%	\$24.26	
Control Purchase Contracts:										
64.0202	DCS / PLC mods	\$576,000	\$0	\$0	0	\$0	\$576,000	0.40%	\$1.10	
64.0407	On-line Performance Monitoring - Neural Network	\$0	\$0	\$0	0	\$570,000	\$570,000	0.40%	\$1.09	
64.1003	Instrumentation	\$50,000	\$0	\$0	0	\$0	\$50,000	0.03%	\$0.10	
Subtotal - Control Purchase Contracts:		\$626,000	\$0	\$0	0	\$570,000	\$1,196,000	0.83%	\$2.29	
Chemical Purchase Contracts:										
65.3210	Remote Sorbent Injection Equipment	\$0	\$0	\$0	0	\$0		0.03%	\$0.10	
65.3120	Fabric Filter	\$15,000,000	\$0	\$0	0	\$0	\$15,000,000	10.43%	\$28.68	
65.3500	H - PAC Injection system	\$1,000,000	\$0	\$0	0	\$0	\$1,000,000	0.70%	\$1.91	
Subtotal - Chemical Purchase Contracts:		\$16,000,000	\$0	\$0	0	\$50,000	\$16,050,000	11.16%	\$30.69	
Subtotal Purchase Contracts:		\$37,865,622	\$1,999,757	\$1,096,286	15,840	\$3,086,200	\$44,047,866	30.63%	\$84.22	

LG&E - KU- Ghent Unit 3 PJFF (Without SCR) Rev. B

B&V PROJECT #:	168908	LOCATION:	Carroll County, KY
PROJECT ESTIMATOR:	Ron Fields	PLANT TYPE:	PC Fired Boiler
PROJECT MANAGER:	Tim Hillman	CLIENT:	LG&E - KU
PURPOSE OF ESTIMATE:	Budgetary	PARTNER:	N/A
ESTIMATE DATE:	April-11	CURRENCY:	US Dollars

BLACK AND VEATCH CONFIDENTIAL AND PROPRIETARY INFORMATION

Contract Number	Description	PROJECT - TOTAL COSTS						% OF TOTAL C.V.	\$ PER KW 523
		Engr Equip	Commodities						
		Material \$	Material \$	Labor \$	Manhours	Other	TOTAL \$		
Civil / Structural Construction Contracts:		\$0	\$0	\$0	0	\$0			
71.0100	Demolition Works	\$0	\$0	\$0	0	\$400,000	\$400,000	0.28%	\$0.76
71.0401	Cast In place Piling	\$0	\$0	\$0	0	\$2,415,000	\$2,415,000	1.68%	\$4.62
71.0402	General Construction - Substructures	\$0	\$879,896	\$2,852,813	49,551	\$127,043	\$3,859,752	2.68%	\$7.38
71.0403	General Construction - Superstructures	\$0	\$15,000	\$4,255,354	61,485	\$4,280,000	\$8,550,354	5.94%	\$16.35
Subtotal - Civil / Structural Construction Contracts:		\$0	\$894,896	\$7,108,167	111,035	\$7,222,043	\$15,225,106	10.59%	\$29.11
Mechanical Construction Contracts:		\$0	\$0	\$0	0	\$0			
72.0401	Plant Piping Installation	\$0	\$0	\$2,179,588	34,580	\$0	\$2,179,588	1.52%	\$4.17
72.0403	Piping & Equipment Insulation	\$0	\$0	\$0	0	\$2,006,000	\$2,006,000	1.39%	\$3.84
72.0800	Fire Protection & Detection Systems	\$0	\$0	\$0	0	\$1,414,250	\$1,414,250	0.98%	\$2.70
77.0000	Mechanical Construction	\$0	\$0	\$12,103,982	197,939	\$0	\$12,103,982	8.42%	\$23.14
77.5450	Field Erected Tanks	\$0	\$0	\$0	0	\$417,555	\$417,555	0.29%	\$0.80
Subtotal - Mechanical Construction Contracts:		\$0	\$0	\$14,283,571	\$232,519	\$3,837,805	\$18,121,376	12.60%	\$34.65
Electrical / Control Construction Contracts:		\$0	\$0	\$0	0	\$0			
73.0201	Electrical Equipment Erection	\$0	\$182,000	\$3,813,038	61,028	\$10,800	\$4,005,838	2.79%	\$7.66
74.0201	Control & Instrumentation Installation	\$0	\$0	\$242,922	3,888	\$0	\$242,922	0.17%	\$0.46
Subtotal - Electrical / Control Construction Contracts:		\$0	\$182,000	\$4,055,961	64,916	\$10,800	\$4,248,761	2.95%	\$8.12
Construction Indirects & Service Contracts:		\$0	\$0	\$0	0	\$0			
78.0000	Service Contracts & Construction Indirects	\$0	\$3,274,064	\$3,771,554	80,924	\$11,519,776	\$18,565,393	12.91%	\$35.50
78.4000	Warranty	\$0	\$0	\$0	0	\$245,300	\$245,300	0.17%	\$0.47
Subtotal - Construction Indirects & Service Contracts:		\$0	\$3,274,064	\$3,771,554	80,924	\$11,765,076	\$18,810,693	13.08%	\$35.97
Subtotal - Construction Costs:		\$0	\$4,350,959	\$29,219,252	489,395	\$22,835,724	\$56,405,935	39.22%	\$107.85
Subtotal - Direct Costs:		\$37,865,622	\$6,350,716	\$30,315,539	505,235	\$25,921,924	\$100,453,801	69.84%	\$192.07
Indirect Costs:		\$0	\$0	\$0	0	\$0			
99.1100	Engineering Costs (Includes G&A)	\$0	\$0	\$2,460,000	60,000	\$3,655,560	\$6,115,560	4.25%	\$11.69
99.1200	EPC Construction Management (Includes G&A)	\$0	\$69,760	\$5,445,664	119,425	\$7,605,422	\$13,120,846	9.12%	\$25.09
99.1500	Project Insurance	\$0	\$0	\$0	0	\$1,714,505	\$1,714,505	1.19%	\$3.28
99.1600	Performance Bond	\$0	\$0	\$0	0	\$734,788	\$734,788	0.51%	\$1.40
99.1900	Sales Tax 6% of Indirect materials and services	\$0	\$59,997	\$0	0	\$0	\$59,997	0.04%	\$0.11
99.2500	Project Contingency	\$0	\$0	\$0	0	\$12,219,950	\$12,219,950	8.50%	\$23.37
99.2600	EPC profit	\$0	\$0	\$0	0	\$9,409,000	\$9,409,000	6.54%	\$17.99
Subtotal - Indirect Costs:		\$0	\$129,757	\$7,905,664	179,425	\$35,339,225	\$43,374,645	30.16%	\$82.93
Total Overnight (April 2011) EPC Capital Costs:		\$37,865,622	\$6,480,473	\$38,221,202	684,660	\$61,261,149	\$143,828,446	100.00%	\$275.01