COMMONWEALTH OF KENTUCKY

BEFORE THE PUBLIC SERVICE COMMISSION

In the Matter of:

ELECTRONIC APPLICATION OF LOUISVILLE)	
GAS AND ELECTRIC COMPANY FOR AN)	
ADJUSTMENT OF ITS ELECTRIC AND GAS)	
RATES, A CERTIFICATE OF PUBLIC)	0.40=.110
CONVENIENCE AND NECESSITY TO DEPLOY)	CASE NO.
ADVANCED METERING INFRASTRUCTURE,)	2020-00350
APPROVAL OF CERTAIN REGULATORY AND)	
ACCOUNTING TREATMENTS, AND)	
ESTABLISHMENT OF A ONE-YEAR)	
SURCREDIT)	

NOTICE OF FILING

Notice is given to all parties that the following materials have been filed into the record of this proceeding:

- The digital video recording of the evidentiary hearing conducted on August 18, 2021 in this proceeding;
- Certification of the accuracy and correctness of the digital video recording;
- All exhibits introduced at the evidentiary hearing conducted on August 18, 2021 in this proceeding;
- A written log listing, inter alia, the date and time of where each witness' testimony begins and ends on the digital video recording of the evidentiary hearing conducted on August 18, 2021.

A copy of this Notice, the certification of the digital video record, and hearing log have been served upon all persons listed at the end of this Notice. Parties desiring to view the digital video recording of the hearing may do so at https://youtu.be/bu3W8E8hhDs.

Parties wishing an annotated digital video recording may submit a written request by electronic mail to pscfilings@ky.gov. A minimal fee will be assessed for a copy of this recording.

Done at Frankfort, Kentucky, this 8th day of September 2021.

Linda C. Bridwell

Executive Director

Public Service Commission of Kentucky

ACOMMONWEALTH OF KENTUCKY

BEFORE THE PUBLIC SERVICE COMMISSION

In the Matter of:

ELECTRONIC APPLICATION OF KENTUCKY
UTILITIES COMPANY FOR AN ADJUSTMENT OF
ITS ELECTRIC RATES, A CERTIFICATE OF PUBLIC
CONVENIENCE AND NECESSITY TO DEPLOY
ADVANCED METERING INFRASTRUCTURE,
APPROVAL OF CERTAIN REGULATORY AND
ACCOUNTING TREATMENTS, AND
ESTABLISHMENT OF A ONE-YEAR SURCREDIT

CASE NOS. 2020-00349 & 2020-00350

ELECTRONIC APPLICATION OF LOUISVILLE GAS AND ELECTRIC COMPANY FOR AN ADJUSTMENT OF ITS ELECTRIC AND GAS RATES, A CERTIFICATE OF PUBLIC CONVENIENCE AND NECESSITY TO DEPLOY ADVANCED METERING INFRASTRUCTURE, APPROVAL OF CERTAIN REGULATORY AND ACCOUNTING TREATMENTS, AND ESTABLISHMENT OF A ONE-YEAR SURCREDIT

CERTIFICATION

- I, Candace H. Sacre, hereby certify that:
- The attached flash drive contains a digital recording of the Formal Hearing conducted in the above-styled proceeding on August 18, 2021. The Formal Hearing Log, Exhibit, and Exhibit List are included with the recording on August 18, 2021;
 - 2. I am responsible for the preparation of the digital recording;
- 3. The digital recording accurately and correctly depicts the Formal Hearing of August 18, 2021; and
- 4. The Formal Hearing Log attached to this Certificate accurately and correctly states the events that occurred at the Formal Hearing of August 18, 2021, and the time at which each occurred.

Signed this 1st day of September, 2021.

Candace H. Sacre

Administrative Specialist III

Stephanie Schweighardt Notary Public State at Large ID#: 614400 Commission Expires: January 14, 2023



Session Report - Detail

2020-00349 and 2020-00350 18Aug2021

Kentucky Utilities Company (KU) and Louisville Gas and Electric Company (LG&E)

Date:	Туре:	Location:	Department:
8/18/2021	Public Hearing\Public Comments	Hearing Room 1	Hearing Room 1 (HR 1)

Witness: Justin Barnes; Robert Conroy; Karl Rabago; Eileen Saunders; Stephen Seelye

Judge: Kent Chandler; Amy Cubbage

Clerk: Candace Sacre

Event Time	Log Event	
9:13:29 AM	Session Started	
9:13:34 AM	Chairman Chandler	
	Note: Sacre, Candace	Back on the record in Case Nos. 2020-00349 and 2020-00350 concerning KU/LG&E net metering and QF rates in addition to issues discussed in Commission's 8-12 Order on Companies' Petition for Rehearing.
9:13:39 AM	Camera Lock Deactivated	
9:13:54 AM	Chairman Chandler	
	Note: Sacre, Candace	Ended yesterday, having taken companies witnesses Arbough, Sinclair, Wolfe, and McFarland. (Click on link for further comments.)
9:14:23 AM	Chairman Chandler	
	Note: Sacre, Candace	Call next witness.
9:14:27 AM	Atty Riggs KU/LG&E	
	Note: Sacre, Candace	Before call next witness, motion issue of joint account liability, understands concerns, need changes, informal conference, scheduling. (Click on link for further comments.)
9:16:20 AM	Chairman Chandler	
	Note: Sacre, Candace	Commission will entertain motion when filed; single question have on issue is statutory deadline proposed tariffs Sept 24. (Click on link for further comments.)
9:16:54 AM	Atty Riggs KU/LG&E	,
	Note: Sacre, Candace	Will check follow up at break.
9:16:59 AM	Chairman Chandler	
	Note: Sacre, Candace	Waived or amended, taken consideration.
9:17:21 AM	Atty Riggs KU/LG&E	
	Note: Sacre, Candace	Will check at break and address that.
9:17:39 AM	Atty Fitzgerald Joint Intervenors	
	Note: Sacre, Candace	Speaking for most of folks remotely, heard suggested informal conference, what address is mystery, repeat what just said.
9:18:12 AM	Chairman Chandler	
	Note: Sacre, Candace	Proposing file motion, informal conference joint account liability as it relates to service and net metering credits discussed.
9:18:48 AM	Atty Riggs KU/LG&E	
	Note: Sacre, Candace	Will update as to inquiry on tariff at next break.
9:19:09 AM	Chairman Chandler	
0.40.40	Note: Sacre, Candace	Crosby introducing next witness?
9:19:13 AM	Atty Riggs KU/LG&E	V 111 (611 1116 6 11
0.10.26 444	Note: Sacre, Candace	Yes, next three. (Click on link for further comments.)
9:19:26 AM	Chairman Chandler Note: Sacre, Candace	Anything else?

0.40.05.411		
9:19:35 AM	Chairman Chandler	
	Note: Sacre, Candace	Next witness?
9:19:38 AM	Atty Crosby KU/LG&E	
	Note: Sacre, Candace	Steve Seelye.
9:19:42 AM	Chairman Chandler	
	Note: Sacre, Candace	Witness is sworn.
9:19:49 AM	Chairman Chandler - witness See	lye
	Note: Sacre, Candace	Examination. Name and address?
9:20:06 AM	Atty Crosby KU/LG&E - witness S	•
	Note: Sacre, Candace	Direct Examination. By whom employed, capacity?
9:20:16 AM	Atty Crosby KU/LG&E - witness S	eelye
	Note: Sacre, Candace	Cause be prepared and filed written direct and rebuttal as well as
		supplemental direct and rebuttal?
9:20:25 AM	Atty Crosby KU/LG&E - witness S	•
	Note: Sacre, Candace	Sponsor of data requests answered by companies?
9:20:30 AM	Atty Crosby KU/LG&E - witness S	eelye
	Note: Sacre, Candace	Corrections or updates?
9:20:37 AM	Atty Crosby KU/LG&E - witness S	eeyle
	Note: Sacre, Candace	Adopt prefiled testimony?
9:20:45 AM	Atty Crosby KU/LG&E - witness S	eelye
	Note: Sacre, Candace	Explain what it is have available to you?
9:20:58 AM	Atty Crosby KU/LG&E - witness S	eelye
	Note: Sacre, Candace	Lovekamp providing record by screen?
9:21:10 AM	Chairman Chandler	
	Note: Sacre, Candace	Questions?
9:21:29 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Cross Examination. Familiar with FERC, PURPA regulations?
9:21:50 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Rely on PURPA regs testimony?
9:22:02 AM	Atty Kurtz KIUC	
	Note: Sacre, Candace	Hand out documents, AG/KIUC Exhibits 1, 2, and 3 marked.
9:24:09 AM	Chairman Chandler	
	Note: Sacre, Candace	Portion of order, copy of entire order or link?
9:24:30 AM	Atty Kurtz KIUC	
	Note: Sacre, Candace	Send remotely.
9:24:48 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	QFs, two varieties?
9:24:58 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Small power production wind, solar, hydro, biomass, geothermal,
		waste?
9:25:15 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Waste can be bituminous coal refuse, anthracite refuse, petroleum
		coke, tires, plastic, refinery off-gas?
9:25:32 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Burn any of those, small power production facility>?
9:25:43 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Co-generation, topping cycle and bottoming cycle
9:25:58 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Also known combined heat and power?
9:26:51 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Two useful outputs from one input?
9:27:01 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Lot of different technologies and varieties of QFs?

9:27:24 AM	Atty Kurtz KIUC - witness Seelye	
0.20.05 AM	Note: Sacre, Candace	More to it than solar?
9:28:05 AM	Atty Kurtz KIUC - witness Seelye Note: Sacre, Candace	Fair amount of coal waste in Kentucky?
9:28:27 AM	Atty Kurtz KIUC - witness Seelye	Tall amount of coal waste in Kentucky:
3120127 741	Note: Sacre, Candace	Paper companies?
9:28:47 AM	Atty Kurtz KIUC - witness Seelye	•
	Note: Sacre, Candace	Exhibit 1, Rates for purchase 18 CFR 292.304, reading, (click on link
0.00 50 444		for further comments), general understanding?
9:28:50 AM	Atty Kurtz KIUC - witness Seelye	Exhibit 1. Dates for nurshass VDC 202 204, reading (click on link for
	Note: Sacre, Candace	Exhibit 1, Rates for purchase KRS 292.304, reading (click on link for further comments), general understanding?
9:30:13 AM	Atty Kurtz KIUC - witness Seelye	· a. a.i.s. commence,, goneral amadistanting.
	Note: Sacre, Candace	FERC order, page 12, paragraph 13, reading (click on link for further
		comments), avoided cost price cap?
9:31:18 AM	Atty Kurtz KIUC - witness Seelye	
0.25.40 AM	Note: Sacre, Candace	Just and reasonable to consumers, not QFs?
9:35:48 AM	Atty Kurtz KIUC - witness Seelye	Standard in federal law just and reasonable to consumers, not OEs
	Note: Sacre, Candace	Standard in federal law just and reasonable to consumers, not QFs developer?
9:36:02 AM	Atty Kurtz KIUC - witness Seelye	action of the second of the se
	Note: Sacre, Candace	No requirement ratepayers make sure investor earns reasonable
		rate of return?
9:36:20 AM	Atty Kurtz KIUC - witness Seelye	
0.04.54.44	Note: Sacre, Candace	Read paragraph 14 of FERC order?
9:36:56 AM	Atty Kurtz KIUC - witness Seelye	Understanding of structure communications are a series of the series of
	Note: Sacre, Candace	Understanding of structure companies proposing, your proposal consistent with that?
9:37:52 AM	Atty Kurtz KIUC - witness Seelye	consistent with that:
	Note: Sacre, Candace	Different standards for utilities in PJM and MISO versus companies
		here?
9:38:13 AM	Atty Kurtz KIUC - witness Seelye	
0.00.40.444	Note: Sacre, Candace	General distinction?
9:39:19 AM	Atty Kurtz KIUC - witness Seelye	What FFDC said if OF laceted averagined councils, maybet, as laws as
	Note: Sacre, Candace	What FERC said if QF located organized capacity market, as long as sell at fair market value, that's it?
9:39:51 AM	Atty Kurtz KIUC - witness Seelye	Sch de fair market value, that's let
	Note: Sacre, Candace	What about companies here not in PJM or MISO?
9:40:54 AM	Atty Kurtz KIUC - witness Seelye	·
	Note: Sacre, Candace	292.304(b)(2), middle first page, reading (click on link for further
		comments), paragraph (e), first part dealing with energy, regulatory
		authority, reading (click on link for further comments), in PJM or MISO LMP, if not competitive price?
9:42:38 AM	Atty Kurtz KIUC - witness Seelye	MISO LMF, II NOT COMpetitive price:
	Note: Sacre, Candace	Competitive price defined, page2, item 7, energy only, reading (click
	,	on link for further comments), understanding of market hub price
		applicable to companies?
9:44:02 AM	Atty Kurtz KIUC - witness Seelye	T3/A · · · · · · · · · · · · · · · · · · ·
0.44.07 AM	Note: Sacre, Candace	TVA interconnection price market price?
9:44:07 AM	Atty Kurtz KIUC - witness Seelye Note: Sacre, Candace	KU interface with MISO be market hub price?
9:44:11 AM	Atty Kurtz KIUC - witness Seelye	No interface with 19150 be market hab price:
	Note: Sacre, Candace	Combine cycle price below, similar use with CSR buy-through price,
	•	reading, (click on link for further comments), way to calculate
		energy rate?

9:44:46 AM	Atty Kurtz KIUC - witness Seelye	
9:44:57 AM	Note: Sacre, Candace Atty Kurtz KIUC - witness Seelye	Combined cycle not for capacity, in energy cycle?
3.11.37 AN	Note: Sacre, Candace	Page 46, bottom, rates for purchase, reading (click on link for further comments), see that?
9:45:27 AM	Atty Kurtz KIUC - witness Seelye	Turtier comments), see that:
	Note: Sacre, Candace	Competitive solicitation price, page 3 of 6, item 8, for energy and/or capacity, understanding if utility not in PJM/MISO, does competitive solication, as long as has right, way to avoid capacity price?
9:46:13 AM	Atty Kurtz KIUC - witness Seelye Note: Sacre, Candace	Companies tend do competitive solicitations for new capacity?
9:46:24 AM	Atty Kurtz KIUC - witness Seelye	companies tend do competitive solicitations for new capacity.
	Note: Sacre, Candace	Reason think QFs not allowed participate?
9:46:31 AM	Atty Kurtz KIUC - witness Seelye	
9:46:42 AM	Note: Sacre, Candace Atty Kurtz KIUC - witness Seelye	If most competitive price, are avoided costs and what get?
9.40.42 AM	Note: Sacre, Candace	Same as other utilities, fair market values determined by PJM/MISO?
9:46:52 AM	Atty Kurtz KIUC - witness Seelye	Same as other utilities, fall market values accommed by 1311/11150.
	Note: Sacre, Candace	Competitive solicitation price, middle toward bottom, page 3 of 6, reading (click on link for further comments), presumption doing competitive solicitations avoided capacity cost zero?
9:47:56 AM	Atty Kurtz KIUC - witness Seelye	
0-40-10 AM	Note: Sacre, Candace	If stopped, presumption no avoided capacity cost be over?
9:48:18 AM	Atty Kurtz KIUC - witness Seelye Note: Sacre, Candace	Why?
9:49:31 AM	Atty Kurtz KIUC - witness Seelye	willy:
	Note: Sacre, Candace	Back to (e), page 4 of 6, bottom, factors affecting purchases,
		reading (click on link for further comments), no competitive solicitation process, then go through factors determine avoided cost?
9:50:33 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Factors, go through them, reading (click on link for further comments, information required to file to let Commission determine avoided capacity, energy costs, IRP filing?
9:51:14 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	(ii), reading (click on link for further comments), availability of capacity, as to solar, does facility contribute peaks in winter?
9:51:47 AM	Atty Kurtz KIUC - witness Seelye	
9:51:58 AM	Note: Sacre, Candace	Seasonal winters peaks, contribute?
3.31.30 AM	Atty Kurtz KIUC - witness Seelye Note: Sacre, Candace	Solar facility contribute to seasonal winter peaks?
9:52:10 AM	Atty Kurtz KIUC - witness Seelye	,
	Note: Sacre, Candace	Solar on at 7 o'clock in morning in winter?
9:53:14 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	(a), ability of electric utility dispatch QF, companies dispatch intermittent resources?
9:53:26 AM	Atty Kurtz KIUC - witness Seelye	
O.F2.20 AM	Note: Sacre, Candace	Dispatch co-generation if contract provided for?
9:53:38 AM	Atty Kurtz KIUC - witness Seelye Note: Sacre, Candace	Intermittent resource less high grade compared to different resources dispatchable?
9:53:58 AM	Atty Kurtz KIUC - witness Seelye	•
	Note: Sacre, Candace	Solar reliable?
9:54:44 AM	Atty Kurtz KIUC - witness Seelye Note: Sacre, Candace	(c) terms of contract, reading (click on link for further comments,
		would be QF by QF determination?

9:55:12 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Contracts associated major QF purchase lengthy?
9:55:28 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Counter party strength, penalties non-performance, all different
9:55:44 AM	Atty Kurtz KIUC - witness Seelye	things, contract specific?
9.33.44 AM	Note: Sacre, Candace	In perspective, how much kW utility grade solar cost?
9:56:09 AM	Atty Kurtz KIUC - witness Seelye	in perspective, now much kw utility grade solal cost:
3.30.03 AN	Note: Sacre, Candace	Construction price, how much cost 80 mW solar?
9:56:39 AM	Atty Kurtz KIUC - witness Seelye	construction price, now much cost of miv solar.
	Note: Sacre, Candace	If be \$2000 kW, not be \$160 million, 80 million megawatts an hour?
9:56:50 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Payments from consumer \$240 million over 20 years?
9:57:00 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Can be major big deals?
9:57:10 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Distributed generation homeowner owns, who owns utility-scale
		multi-hundred-million-dollar solar QFs?
9:58:30 AM	Atty Kurtz KIUC - witness Seelye	
0.50.40.414	Note: Sacre, Candace	No requirement subsidize hedge funds, owns facilities?
9:58:49 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	(d), middle of page, coordinating scheduled outages, page 5 of 6,
9:59:20 AM	Atty Kurtz KIUC - witness Seelye	apply to solar?
9.39.20 AN	Note: Sacre, Candace	Co-generation do maintenance spring or fall?
9:59:31 AM	Atty Kurtz KIUC - witness Seelye	co generation do maintenance spring or rain:
3.33.31 /11	Note: Sacre, Candace	Lead to believe get to this section project specific avoided cost
		based upon power plant topping, bottoming, hydro, electric, waste,
		project specific avoided capacity price?
10:00:07 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	One size fits all capacity price inappropriate under section of
10.00.10.11		regulation?
10:00:46 AM	Atty Kurtz KIUC - witness Seelye	Davikian and an extra section of OF an extra section will
	Note: Sacre, Candace	Position consumers not pay for capacity of QF power plant until plant is needed?
10:01:09 AM	Atty Kurtz KIUC - witness Seelye	plant is needed?
10.01.03 AI1	Note: Sacre, Candace	If need is 2028, consumers not pay until 2028?
10:02:18 AM	Atty Kurtz KIUC - witness Seelye	ir ricca is 2020, consumers not pay until 2020:
101021107111	Note: Sacre, Candace	Choice of discount rates important?
10:02:26 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	What discount rate companies propose?
10:03:28 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Another proposed discount rate in record?
10:04:22 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	What is risk free rate?
10:04:31 AM	Atty Kurtz KIUC - witness Seelye	
	Note: Sacre, Candace	Under 1.4 percent discount rate, homeowner credit card balance,
10.05-03.454	Attack with KTUC and C. I	loaning money at 1.4 when paying 18 percent on credit card?
10:05:03 AM	Atty Kurtz KIUC - witness Seelye	Leaning manay to dayalanar at 1.4 parant?
10.05.22 44	Note: Sacre, Candace	Loaning money to developer at 1.4 percent?
10:05:22 AM	Atty Kurtz KIUC - witness Seelye Note: Sacre, Candace	Use as discount, consumer lending at that rate?
10:05:36 AM	Atty Kurtz KIUC - witness Seelye	ose as discount, consumer renaing at that rate:
10103130 API	Note: Sacre, Candace	Distributed generation, one percent cap, net metering?
	rioto: Sacrof Carladec	2.53.53coa gonoradori, one percent cap, net metering.

10:05:50 AM	Atty Kurtz KIUC - witness Seelye	Divide and water and managers at least atomical least 2
10:07:05 AM	Note: Sacre, Candace Atty Kurtz KIUC - witness Seelye	Buy-back rate one percent, at least staying local?
10:07:20 AM	Note: Sacre, Candace	Practical difference, no one percent cap on QF capacity?
10:07:20 AM	Atty Kurtz KIUC - witness Seelye Note: Sacre, Candace	No cap on QFs?
10:07:23 AM	Atty Kurtz KIUC - witness Seelye	•
10:07:46 AM	Note: Sacre, Candace Atty Kurtz KIUC - witness Seelye	Hedge fund owner QF facilities, money not staying local?
10.07.10711	Note: Sacre, Candace	Is QF terms of rate impact greater concern than net metering?
10:09:05 AM	Chairman Chandler	Ougstions?
10:09:25 AM	Note: Sacre, Candace Atty Spenard KYSEIA - witness So	Questions?
101031237111	Note: Sacre, Candace	Cross Examination. Applications November 25 2020, looked at WSS-1, summary of qualifications, have technical specialized knowledge regarding rates and assist Commission, expert on rates?
10:10:10 AM	Camera Lock Intervenor Activate	
10:10:26 AM	Atty Spenard KYSEIA - witness So	·
10 10 27 111	Note: Sacre, Candace	Supplemental testimony July 13 2021, included testimony?
10:10:37 AM	Atty Spenard KYSEIA - witness So	·
10:10:53 AM	Note: Sacre, Candace Atty Spenard KYSEIA - witness So	Rebuttal August 5 2021, included testimony?
10.10.55 AM	Note: Sacre, Candace	Supplemental, page 13, line 14, through page 22, line 9, discuss
	Note: Sacre, canadec	avoided ancillary service costs?
10:11:51 AM	Atty Spenard KYSEIA - witness So	•
	Note: Sacre, Candace	Rebuttal continued conversation ancillary service costs?
10:12:11 AM	Atty Spenard KYSEIA - witness Se	•
10 12 26 444	Note: Sacre, Candace	Supplemental, discuss companies open access transmission tariff?
10:12:36 AM	Atty Spenard KYSEIA - witness Son Note: Sacre, Candace	eerye OATT on file with FERC?
10:12:42 AM	Camera Lock Deactivated	OATT OITHE WILL FERC!
10:12:47 AM	Atty Spenard KYSEIA - witness Se	eelve
	Note: Sacre, Candace	Page 16, line 9, supplemental, discuss Schedule 3 of OATT?
10:12:49 AM	Camera Lock Intervenor Activate	•
10:13:04 AM	Atty Spenard KYSEIA - witness So	eelye
	Note: Sacre, Candace	Schedule 3 ancillary service charge applies power transmitted third party across companies transmission systems?
10:13:23 AM	Atty Spenard KYSEIA - witness So	
	Note: Sacre, Candace	Page17, line 4, part of answer, reading (click on link for further comments), compensation based on Schedule 3 charges set forth in OATT, determined be one percent avoided generation capacity cost, see that?
10:14:30 AM	Atty Spenard KYSEIA - witness Se	
	Note: Sacre, Candace	Line 6, Kentucky PSC?
10:15:00 AM	Atty Spenard KYSEIA - witness Se	eelye
	Note: Sacre, Candace	All of discussion in cross examination Kurtz, KIUC Exhibit 1, using state regulatory authority, commission FERC, regulator bodies like Kentucky PSC, generally?
10:15:40 AM	Camera Lock Deactivated	
10:18:11 AM	Atty Spenard KYSEIA - witness So	·
	Note: Sacre, Candace	Lines 4-7, page 17, supplemental, companies position this amount should be zero?
10:18:44 AM	Atty Spenard KYSEIA - witness Se	
	Note: Sacre, Candace	Further, second part, companies zero but two alternatives for setting cost?

10:20:11 AM	Atty Spenard KYSEIA - witness S	,
	Note: Sacre, Candace	KIUC Exhibit 1, record speak for self, recall number of hypotheticals
		related to hedge funds and all free-ranging discussions?
10:21:32 AM	Atty Spenard KYSEIA - witness S	eelye
	Note: Sacre, Candace	Testimony submitted with application supplemental testimony,
		rebuttal, where in any was subject, discussion of hedge funds?
10:23:10 AM	Chairman Chandler	
	Note: Sacre, Candace	Questions?
10:24:07 AM	Atty Miller Sierra Club - witness S	Seelye
	Note: Sacre, Candace	Cross Examination. Institutional investors in QFs, companies wholly-
	·	owned subsidiaries of PPL Corp?
10:24:26 AM	Atty Miller Sierra Club - witness S	Seelye
	Note: Sacre, Candace	Sound right two-thirds PPL shares institutional investors like funds
	•	and banks
10:24:42 AM	Atty Miller Sierra Club - witness S	Seelve
	Note: Sacre, Candace	Top 10 investors institutional like Vanguard and Blackrock?
10:25:03 AM	Atty Miller Sierra Club - witness S	·
10120100 7	Note: Sacre, Candace	QFs or PPL building things in Kentucky regardless of ownership, still
	Note: Sacre, canade	support local jobs and brings benefits to Commonwealth?
10:26:14 AM	Atty Miller Sierra Club - witness S	.,
10.20.11741	Note: Sacre, Candace	Not certain, agree possible could be area of growth?
10:26:35 AM	Chairman Chandler	Not certain, agree possible could be area or growth:
10.20.33 AN	Note: Sacre, Candace	Procedural discussion. (Click on link for further comments.)
10:27:20 AM	Chairman Chandler	riocedulal discussion. (Click of liffik for further confinence.)
10.27.20 AI*I		Pofero de la question Vivitz questions to Cookie whether
	Note: Sacre, Candace	Before go, one question, Kurtz questions to Seelye, whether companies proposal using Rhudes Creek Level 10 data necessarily in
		anticipation or in compliance with section competitive solicitation
		prices for QFs under PURPA? (Click on link for further comments.)
10:29:45 AM	Chairman Chandler	prices for Qr's under FORFA: (Click off link for further confinence.)
10.23.73 AN	Note: Sacre, Candace	Break until 10:40.
10:30:01 AM	Session Paused	bleak ullul 10.70.
10:41:23 AM	Session Resumed	
10:41:33 AM	Chairman Chandler	Mr. Diagra
10-41-4F AM	Note: Sacre, Candace	Mr. Riggs?
10:41:45 AM	Atty Riggs KU/LG&E	— 166 IIII III III III I
	Note: Sacre, Candace	Tariff condition would restrict ability to change way companies
		address closing accounts or joint ownership, there is not. (Click on
10-42-41 AM	Clarationna or Claration	link for further comments.)
10:42:41 AM	Chairman Chandler	
	Note: Sacre, Candace	Entering order on September 24 without addressing not preclude
		issue taken up same case in subsequent order? (Click on link for
10-45-50 AM	Chairman Chanadhan	further comments.)
10:45:58 AM	Chairman Chandler	W 0 1 2
	Note: Sacre, Candace	Mr. Crosby?
10:46:01 AM	Atty Crosby KU/LG&E	
	Note: Sacre, Candace	Methodology Sinclair proposed does not reflect anything with federal
		regulations, not requesting federal regulations be applied any
10.46.40.444	Charisman Cl. II	differently. (Click on link for further comments.)
10:46:49 AM	Chairman Chandler	
	Note: Sacre, Candace	Companies not proposing use solicitation process as way of setting
		avoided costs, proposing purchased portion of Kentucky regulation
10.47-56 444	A++ . 1/ + 1/TL 1/C	using Rhudes Creek or Level 10 what think otherwise purchase?
10:47:56 AM	Atty Kurtz KIUC	MOUNTED AND AND AND AND AND AND AND AND AND AN
	Note: Sacre, Candace	Will brief whether state has to follow federal regulations on this
		issue.

10:48:02 AM	Chairman Chandler Note: Sacre, Candace	Notes couple of things like brief on that. (Click on link for further
		comments.)
10:48:32 AM	Chairman Chandler	A4 E7 110
10.40.40 AM		Mr. Fitzgerald?
10:48:40 AM	Atty Fitzgerald Joint Intervenors - v	·
10.40.27 AM		Cross Examination. How many utility scale QFs in Kentucky?
10:49:27 AM	Atty Fitzgerald Joint Intervenors - Note: Sacre, Candace	Are in KU/LG&E service areas, how many?
10:49:52 AM	Atty Fitzgerald Joint Intervenors - v	·
101 13132 711 1	Note: Sacre, Candace	Conversation with Kurtz ownership of QFs, owners or investors are in Kentucky?
10:50:12 AM	Atty Fitzgerald Joint Intervenors - v	·
		Despite Kurtz implication owned by hedge funds, no knowledge?
10:51:00 AM	Atty Fitzgerald Joint Intervenors - v	
	Note: Sacre, Candace	Kurtz hypotheticals no basis in this proceeding, PURPA act?
10:51:21 AM	Atty Fitzgerald Joint Intervenors - v	witness Seelye
		Scope and purposes of regulation jurisdiction under Federal Power Act?
10:51:44 AM	Atty Fitzgerald Joint Intervenors - v	•
		This Commission limited in defining which costs avoided or reduced by introducing fed-in power using definition avoided cost under PERPA?
10:53:30 AM	Atty Fitzgerald Joint Intervenors - v	witness Seelye
	Note: Sacre, Candace	Commission ordered avoided cost used, ordered definition in 807 KAR 5:054 used?
10:54:37 AM	Atty Fitzgerald Joint Intervenors - v	witness Seelye
		Commission order Kentucky Power case set out principles and also number of specific cost components not in definition avoided cost created by FERC under PURPA?
10:55:43 AM	Atty Fitzgerald Joint Intervenors - v	witness Seelye
		And one, by law, not applicable relationship between retail customer and utility under net metering, is that not correct?
10:56:02 AM	Session Note Entry	
		Familiar with group New England Ratepayers Association?
10:56:20 AM	Atty Fitzgerald Joint Intervenors - v	·
10.FC.21 AM	•	Familiar with petition filed by New England Ratepayers Association?
10:56:21 AM	Atty Fitzgerald Joint Intervenors - Note: Sacre, Candace	Familiar with petition filed by New England Ratepayers Association
		with FERC seeking declaratory order FERC exclusive jurisdiction over
		wholesale energy rates and generation sources customer side meter
		and rates had be priced accordance with Federal Power Act in
		PURPA?
10:56:55 AM	Atty Fitzgerald Joint Intervenors - v	•
		Aware by FERC order July 16 2020 Docket EL20-42-100 denied
10 57 20 414		request and declined issue declaratory order?
10:57:30 AM	Atty Fitzgerald Joint Intervenors - Notes Spare Candage	
		Clear that nothing in federal law limits ability of Commission to define cost components or benefits considered, Commission not
		confined costs avoided or benefits accrued from fed-in energy from
		net metering customers or how compensatory rate set?
10:59:53 AM		witness Seelye
	Note: Sacre, Candace	Familiar with Commission regulation defining avoided costs net
		metering?

11:00:18 AM	Atty Fitzgerald Joint Intervenors - Note: Sacre, Candace	- witness Seelye Know whether adopted definition of avoided costs or costs relative to net metering?
11:01:03 AM	Atty Fitzgerald Joint Intervenors	_
11.01.03741	Note: Sacre, Candace	Agreed earlier cost components Ky Power order be considered what is COS and appropriate rate for fed-in solar, Commission adopted broader set components be evaluated in definition of avoided cost under PURPA?
11:02:19 AM	Atty Fitzgerald Joint Intervenors	
	Note: Sacre, Candace	FERC Order Docket No. EL20-42-000, ask reference included in record, published, 172 FERC Paragraph 61,042.
11:03:01 AM	Chairman Chandler	Objection?
11:03:20 AM	Note: Sacre, Candace JOINT INTERVENORS EXHIBIT 1	Objection?
11.03.20 AIM	Note: Sacre, Candace	ATTY FITZGERALD JOINT INTERVENORS - WITNESS SEELYE
	Note: Sacre, Candace	FERC ORDER DOCKET NO. EL20-42-000
11:03:33 AM	Chairman Chandler	TERC ORDER DOCKET NO. ELZO-42-000
11.05.55 AN	Note: Sacre, Candace	Marked three exhibits, 1, 2, and 3, move to introduce?
11:03:50 AM	Atty Kurtz KIUC	Trained and Sansia, 1, 2, and 3, more to indicade.
	Note: Sacre, Candace	Yes.
11:03:52 AM	Chairman Chandler	
	Note: Sacre, Candace	Objection?
11:04:02 AM	Chairman Chandler	
	Note: Sacre, Candace	Entered AG/KIUC Exhibits 1, 2, and 3, supplement 3 with entire version.
11:04:06 AM	AG/KIUC EXHIBIT 1	
	Note: Sacre, Candace	ATTY KURTZ KIUC - WITNESS SEELYE
	Note: Sacre, Candace	18 CFR 292.202 QUALIFING COGENERATION AND SMALL POWER PRODUCTION FACILITIES DEFINITIONS
11:04:07 AM	AG/KIUC EXHIBIT 2	
	Note: Sacre, Candace	ATTY KURTZ KIUC - WITNESS SEELYE
44 04 00 444	Note: Sacre, Candace	18 CFR 292.302 AVAILABILITY OF ELECTRIC UTILITY SYSTEM
11:04:09 AM	AG/KIUC EXHIBIT 3	ATTY MUDTZ MUC ANTENECC CEELVE
	Note: Sacre, Candace	ATTY KURTZ KIUC - WITNESS SEELYE
11:04:11 AM	Note: Sacre, Candace Chairman Chandler	18 CFR 292 AND 375 FACILITY RATES AND REQUIREMENTS
II.U4.II AM	Note: Sacre, Candace	Questions?
11:04:15 AM	General Counsel Vinsel PSC - witr	
11.04.13 AM	Note: Sacre, Candace	Cross Examination. Solar without inverter not support reactive
	Note: Sacre, Candace	power?
11:05:07 AM	General Counsel Vinsel PSC - witr	ness Seelye
	Note: Sacre, Candace	Look at KU or LG&E response to Seventh Request, Item 36?
11:05:31 AM	General Counsel Vinsel PSC - witr	ness Seelye
	Note: Sacre, Candace	Wolfe, not your response.
11:06:11 AM	General Counsel Vinsel PSC - witr	•
	Note: Sacre, Candace	Item A-36, reading (click on link for further comments), last sentence, reading (click on link for further comments), all inverters have smart functions?
11:07:39 AM	General Counsel Vinsel PSC	
	Note: Sacre, Candace	Follow up on previous cross regarding avoided cost definitions, introduce printed copies of KRS 278.465, definitions applicable to net metering statutes, and 278.466 part of net metering, marked Staff Exhibits 5 and 6.

11:09:55 AM	General Counsel Vinsel PSC - witness Seelye
	Note: Sacre, Candace Offering opinion definition avoided cost Commission regulation small cogeneration facilities, offering lay opinion or legal opinion?
11:10:41 AM	General Counsel Vinsel PSC - witness Seelye
11.10.11741	Note: Sacre, Candace Lay opinion?
11:10:55 AM	General Counsel Vinsel PSC - witness Seelye
11110100 7111	Note: Sacre, Candace Did you go to law school?
11:11:00 AM	General Counsel Vinsel PSC - witness Seelye
111111007111	Note: Sacre, Candace Did not pass bar?
11:11:04 AM	General Counsel Vinsel PSC - witness Seelye
111111017111	Note: Sacre, Candace Lay opinion, familiar either statutes?
11:11:19 AM	General Counsel Vinsel PSC - witness Seelye
	Note: Sacre, Candace Point where any statutes legislature said Commission apply avoided
	cost definition set forth in cogeneration regulation?
11:12:26 AM	General Counsel Vinsel PSC - witness Seelye
	Note: Sacre, Candace Make sure clear, not saying Commission limited considering avoided
	energy avoided capacity in calculating avoided cost net metering
	export rate?
11:13:32 AM	General Counsel Vinsel PSC - witness Seelye
	Note: Sacre, Candace Again, Commission established principles calculating net metering
44 44 00 444	export rate 2020-00174 Ky Power rate case?
11:14:00 AM	General Counsel Vinsel PSC - witness Seelye
11.14.20 AM	Note: Sacre, Candace Also, in order June 30, what components in avoided cost?
11:14:29 AM	General Counsel Vinsel PSC - witness Seelye
	Note: Sacre, Candace Based upon lay understanding, regulations have to list statutory authority why enacting particular regulation, reading 807 KAR 5:054,
	KRS 278.040(3), (click on link for further comments), agree?
11:16:08 AM	General Counsel Vinsel PSC - witness Seelye
111101007111	Note: Sacre, Candace Version of net metering and billing periods for dummies, in KYSEIA
	first data request, both you and Conroy response to question various
	scenarios, trying to understand what companies proposing netting
	period and billing period, fair to say netting frequency is different
	from billing cycle under requirements of Kentucky law?
11:18:08 AM	General Counsel Vinsel PSC - witness Seelye
44 40 22 414	Note: Sacre, Candace Talk about rate design?
11:18:22 AM	General Counsel Vinsel PSC - witness Seelye
	Note: Sacre, Candace Response KYSEIA First Request, Item 17-E, measurement interval
11:19:50 AM	instantaneous, describe what mean? General Counsel Vinsel PSC - witness Seelye
11.19.50 AIM	Note: Sacre, Candace Again, scenarios referenced, net metering customer produces and
	consumes own energy in totality, produces 100 kWh consumers
	same amount, what goes through meter?
11:21:35 AM	General Counsel Vinsel PSC - witness Seelye
	Note: Sacre, Candace Difference netting frequency and billing cycle?
11:22:09 AM	General Counsel Vinsel PSC - witness Seelye
	Note: Sacre, Candace Best of understanding KU/LG&E requesting approval of billing and
	not netting frequency in calculating bill credits?
11:22:49 AM	General Counsel Vinsel PSC - witness Seelye
	Note: Sacre, Candace Supplemental rebuttal, said regarding retirements Mill Creek 1 and 2
	and Brown Unit 3, 2021 business plan based on assumption Mill
44 22 22	Creek retire in 2024 and Mill Creek 2 and Brown in 2028?
11:23:39 AM	General Counsel Vinsel PSC - witness Seelye
	Note: Sacre, Candace Also said Mill Creek 1 and 2 and Brown 3 retirement uncertain,
	absent stricter environmental regulation units not retired until end of depreciable lives?
	acprediable lives:

11:25:04 AM	General Counsel Vinsel PSC - witr	pers Seelve
11.25.04 AM	Note: Sacre, Candace	Discussing degree of uncertainty regulations, any consideration of
	Note: Sacre, Canadee	more regulation and stricter regulation and impact on retirements
		and capacity for KU/LG&E?
11:26:11 AM	Chairman Chandler	, ,
	Note: Sacre, Candace	Move introduce exhibits?
11:26:14 AM	General Counsel Vinsel PSC	
	Note: Sacre, Candace	Yes.
11:26:16 AM	Chairman Chandler	
	Note: Sacre, Candace	Objections?
11:26:17 AM	PSC STAFF EXHIBIT 5	
	Note: Sacre, Candace	GENERAL COUNSEL VINSEL PSC - WITNESS SEELYE
	Note: Sacre, Candace	KRS 278.465 DEFINITIONS FOR KRS 278.465 TO 278.468
11:26:18 AM	PSC STAFF EXHIBIT 6	
	Note: Sacre, Candace	GENERAL COUNSEL VINSEL PSC - WITNESS SEELYE
	Note: Sacre, Candace	KRS 278.466 AVAILABILITY OF NET METERING
11:26:21 AM	Chairman Chandler	
	Note: Sacre, Candace	Objections?
11:26:24 AM	Chairman Chandler	
11.26.20 AM	Note: Sacre, Candace	Questions?
11:26:28 AM	Vice Chairman Cubbage - witness	·
11.21.00 AM	Note: Sacre, Candace	Examination. Avoided cost analogous to marginal cost?
11:31:08 AM	Vice Chairman Cubbage - witness	•
	Note: Sacre, Candace	Cost assigned on page 30, supplemental, NMS 2, table, avoided energy cost under recommended avoided cost essentially marginal
		cost generate next kWh?
11:32:18 AM	Vice Chairman Cubbage - witness	
	Note: Sacre, Candace	Avoided generation capacity cost under recommended is none,
	,	KU/LG&E do not forecast need for generation in short term?
11:36:07 AM	Vice Chairman Cubbage - witness	s Seelye
	Note: Sacre, Candace	KU/LG&E no forecast excess generation needs 2028, QF or net
		metering resources on market, cost of generation less, purchased
		cheaper price avoided generation cost if not need capacity?
11:37:39 AM	Vice Chairman Cubbage - witness	•
11 27 54 484	Note: Sacre, Candace	Energy cost line, not generation?
11:37:54 AM	Vice Chairman Cubbage - witness	•
11.40.02 AM	Note: Sacre, Candace	Where into discussion sunk costs?
11:40:03 AM	Vice Chairman Cubbage - witness	•
	Note: Sacre, Candace	Back to chart on page 30, your summary of Kentucky Power elements?
11:40:37 AM	Vice Chairman Cubbage - witness	
11. 10.57 AM	Note: Sacre, Candace	One getting ready to ask you about?
11:41:33 AM	Vice Chairman Cubbage - witness	
111111007111	Note: Sacre, Candace	Jobs benefit line, discussion Miller, assigned zero because consider
		externality, did not do specific analysis?
11:42:22 AM	Vice Chairman Cubbage - witness	s Seelye
	Note: Sacre, Candace	Did not do jobs benefit analysis?
11:42:40 AM	Chairman Chandler	
	Note: Sacre, Candace	Recess until 12:55.
11:43:19 AM	Session Paused	
1:01:50 PM	Session Resumed	
1:01:56 PM	Chairman Chandler	
	Note: Sacre, Candace	Back on record in Case Nos. 2020-00349 and 2020-00350, KU/LG&E
		net metering SQF and LQF and issues left over from petition for
		rehearing. (Click on link for further comments.)

1:02:15 PM	Chairman Chandler - witness Seelye Note: Sacre, Candace Examination. Been here for hearing?
1:02:54 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Anything find objectionable from Baron?
1:05:26 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Like to ask about that, heard questions to Wolfe, your experience have dealt with CPCNs, show a need for something and absence of duplication, show need replace cheaper than have, your experience?
1:06:15 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Brings me to what you said today, companies not paying avoided capacity cost when no need for capacity, need related to reliability?
1:07:02 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Taken further, although may get more reliability from incremental capacity, planning not determine necessary have reliability searching for?
1:07:48 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace When talk need for capacity or absence need, companies planning one in ten reliability scenario?
1:08:17 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Upper end reserve margin, loss of load expectation one event one day in ten years?
1:08:39 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace When said need, reliability need, can need be determined in sake of efficiency or cost savings, capital cost cheapest capacity resource, going forward or stay open, annual capacity, annual capital cost and fixed O&M, all in excess \$5 million, some resource stay open additional \$20 million, can find resource, can replace for cheaper than stay-open cost, something prudent to look at?
1:12:51 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Not asking specifically type resource, economic perspective, stayopen costs avoidable?
1:13:16 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Ignore single cycle CTs, vast majority remainder system coal units?
1:13:40 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace If any combined cycle CTs/coal units retire, companies avoid costs otherwise would have incurred if continue operate?
1:14:03 PM	Chairman Chandler - witness Seelye
1 14 27 014	Note: Sacre, Candace Just retire?
1:14:37 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Going way beyond question, asking solely looking at single unit when retires, costs not incur specific to unit that would have incurred had unit stayed open?
1:15:26 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Calculus company running every year comparing costs might or would disappear upon retirement is compared to other scenarios, cheaper to replace retired generator, other units could replace ultimately lead to lower rate, lower cost?
1:16:20 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Focusing first on first part of equation, what is number looking at with capacity, number looking at fixed cost absent retirement?
1:17:48 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Retiring generators, many retired cost of environmental compliance higher than replacement cost?

1:18:42 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Not retire because of age, end of useful life, certainly have over decades?
1:19:22 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Economics, wrong economics of situation, two parts, variable cost to produce electricity than rest of fleet, and lot of money overhaul the boilers, to continue to invest is unduly costly compared to replacement, fair characterization?
1:20:27 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace That's what companies base case, base case has built-in economics, then compared to alternatives?
1:21:16 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Create base, look at recurring basis, determine other scenarios maximize value or reduce costs over time?
1:21:53 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Brown Unit, companies could have spent ton of money updated, brand new place, expensive?
1:22:27 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Why, even when adequate capacity not avoided generation capacity value, continuing fixed O&M avoided generation capacity cost?
1:23:56 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace If retire unit, why continue every year incur costs keep doors open?
1:24:10 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Avoiding that cost, retire a unit, not pay people work at that unit, avoided cost?
1:26:15 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Companies proposing wants 1000 mW QF satisfy avoided generation capacity value QF rate should go to zero?
1:26:35 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace For reliability purposes?
1:26:37 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Assuming scenario1000 mW satisfied, companies proposing avoided generation capacity value back to zero, looking at base case scenario whether retire something not planned verse replacement generation scenario, comparing replacement generation against zero or against cost avoid if retire generator?
1:27:34 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Companies no significant retirements, Zorn CTs, small, no planning, no capacity additions or retirements, reserve margin within range, each year companies look at plan, base plan, if replacement generation, forget cost, compare to companies current generating fleet, no need for capacity reliability, replacement capacity cost, what cost compare that cost of replacement capacity determine more effective or efficient retire and go with replacement?
1:29:59 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Fixed O&M expenses, stay-open costs, annual capital costs, fixed O&M?
1:30:28 PM	Chairman Chandler - witness Seelye Note: Sacre, Candace If generator has \$7-10 million capital costs, reflected in variable fuel cost?
1:30:53 PM	Chairman Chandler - witness Seelye Note: Sacre, Candace Recurring annual fixed expenses avoided?
1:31:10 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Hypothetical to get to economics, what economic calculations companies running to see if situations actually occur?

1:31:54 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Baron discussed imbedded costs more accounting principle and avoided and marginal costs are more economic principles, agree?
1:32:28 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace State in testimony no relationship between avoided costs and imbedded costs?
1:32:43 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Basis for that one economics and one accounting?
1:33:40 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Imbedded costs include costs avoidable but incurred, makes imbedded?
1:34:07 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Talk about no correlation, difference, apples and oranges but apples imbedded, could have been oranges but became imbedded costs?
1:34:48 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Costs incurred makes them imbedded?
1:34:56 PM	Chairman Chandler - witness Seelye
1:35:03 PM	Note: Sacre, Candace In rearview mirror? Chairman Chandler - witness Seelye
1:33:03 PM	Note: Sacre, Candace Change in cost based on change in demand, very baseline simple
	definition of marginal cost?
1:35:55 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Linear, curvilinear chart, move along one axis change in demand, move along curvilinear, tangent?
1:36:35 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Moving along with one change in variable move along the line, how some marginal costs look, but talk about avoided capacity cost, no change in cost but may end up being a step-lodge change, economic possibility have marginal costs like that?
1:38:52 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Units in quantity, change in demand before change in cost, talking about how incurs, assign no benefit to smaller increments of replacement?
1:44:07 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Bringing forward retirement result in more savings?
1:44:40 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Economics, bring forward retirement, replacement in 2023 cheaper than continuing running for 3, 4, 5, 8 years, discount replacement capacity cost, generation cheaper, lend itself bring forward retirerment?
1:46:04 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Other than protecting customers calculus used against or for of discounting to present value those avoided generation capacity costs in base case?
1:46:57 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace No reliability need for seven years?
1:47:12 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Like Bluegrass units?
1:47:29 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Math companies doing cheaper, one part related to current generation, present value discounted of avoided generation capacity cost as reflected in companies base case?
1:48:22 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Planning horizon?

1.40.10 DM	Chairman Chandler witness Cooks
1:49:10 PM	Chairman Chandler - witness Seelye
1:49:28 PM	Note: Sacre, Candace Avoided cost is avoided cost? Chairman Chandler - witness Seelye
1.75.20 FM	Note: Sacre, Candace Cases in Commission around DSM?
1:49:43 PM	Chairman Chandler - witness Seelye
1. 15. 15 111	Note: Sacre, Candace Columbia last one?
1:49:46 PM	Chairman Chandler - witness Seelye
11.151.10.111	Note: Sacre, Candace DSM programs avoided energy/avoided generation capacity
	significant input determination effectiveness of programs?
1:50:13 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace If avoided cost same, SQF, LQF, 640 megawatt combined cycle,
	companies have avoided energy cost and avoided generation
	capacity cost, using for QF, use for demand response energy
4 50 00 014	efficiency, weatherization, cost effective?
1:52:20 PM	Chairman Chandler - witness Seelye
1.52.50 DM	Note: Sacre, Candace Baron said avoided utility cost system benefit?
1:52:50 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Companies position, discount avoided generation capacity cost outer years discounted present value determining capacity value today
	payment for avoided capacity cost?
1:53:21 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Not proposing to discount increments short of able actually avoid
	large chunks capacity?
1:54:11 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Specific to avoided generation capacity cost being discounted, dozen
	or so different types resources can provide capacity?
1:54:48 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Flip side, companies use avoided generation capacity costs, input in
1:55:04 PM	all demand response programs? Chairman Chandler - witness Seelye
1.55.04 FM	Note: Sacre, Candace In any proposals discounting avoided generation capacity values
	based off of inability of particular generator to offset full chunk of
	capacity?
1:55:33 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Across the board with avoided generation capacity value?
1:55:55 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Avoided generation capacity may look step-wise manner, probably
	case for most other avoided capacity values?
1:57:04 PM	Chairman Chandler - witness Seelye
4 57 00 014	Note: Sacre, Candace Agree chunky but very different?
1:57:20 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Fact that are presented charting out marginal cost, not discount contribution able to provide?
1:57:47 PM	Chairman Chandler - witness Seelye
1.57.47 114	Note: Sacre, Candace Avoiding upgrades, number of COS?
1:58:01 PM	Chairman Chandler - witness Seelye
1.50.01	Note: Sacre, Candace Minimum size study?
1:58:11 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Two ways do allocation certain distribution plan, customer portion,
	minimum or zero, minimum way simpler?
1:59:01 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Minimum system says smallest transformer this is cost, shortest pole
	we use, for sake of efficiency, stick with this conductor,
	understanding?

1:59:55 PM	Chairman Chandler - witness Seelye	
	Note: Sacre, Candace Not that smaller might not work, carry certain size for number of reasons?	
2:00:31 PM	Chairman Chandler - witness Seelye	
	Note: Sacre, Candace Different size transformer, have circuit certain size transformer, size needed?	
2:01:00 PM	Chairman Chandler - witness Seelye	
	Note: Sacre, Candace Two in stock big one smaller one, over time circuit, tornado, energy efficient, houses torn, down, loses load, end of life, retire, replace with smaller one next time?	
2:01:50 PM	Chairman Chandler - witness Seelye	
	Note: Sacre, Candace Replacement is cheaper, system benefit?	
2:02:04 PM	Chairman Chandler - witness Seelye	
	Note: Sacre, Candace Distribution system, how utility look at calculation and make determination cost effect, couple years, replace transformer, how utility calculate, planning purposes, most efficient reasonable cost plan in those scenarios?	
2:06:52 PM	Chairman Chandler - witness Seelye	
	Note: Sacre, Candace If found that, an alternative, internally as companies do calculations, asking about economics of situation, what cost saving, for avoided distribution capacity cost, may be circuit, this investment less than cost otherwise incur, cost otherwise incur if wouldn't incur, is avoided distribution capacity cost, how are companies calculating that value, base case to compare to, for internal planning today?	
2:10:52 PM	Chairman Chandler - witness Seelye	
	Note: Sacre, Candace What just said analogous what said earlier about avoided generation capacity? How two things not the same?	
2:12:14 PM	Chairman Chandler - witness Seelye	
	Note: Sacre, Candace QF maximum 80 mW, paid avoided energy and avoided capacity cost, under scenario, unless actually avoid next generator, not be paid avoided capacity value?	
2:15:01 PM	Chairman Chandler - witness Seelye	
	Note: Sacre, Candace Aggregate demand reduces over time, retire unit, not necessitate replacement, keeps in reserve margin?	
2:15:31 PM	Chairman Chandler - witness Seelye	
	Note: Sacre, Candace Chunkiness different but not mean not exist, all customers benefit, without any reduction of reliability, avoidance of cost?	
2:16:33 PM	Chairman Chandler - witness Seelye	
	Note: Sacre, Candace More interested or concerned, whatever use what build system, pay everyone \$1, save system \$2, always tried to do latter?	
2:17:09 PM	Chairman Chandler - witness Seelye	
	Note: Sacre, Candace Asking, from distribution perspective, \$2 value how being determined today?	
2:18:24 PM	Chairman Chandler - witness Seelye	
	Note: Sacre, Candace Moving on to net metering, trying to find out how to avoid distribution capacity value?	
2:20:12 PM	Chairman Chandler - witness Seelye Note: Sacre, Candace Standard formula assuming growth avoid additional capital cost?	
2:20:28 PM	Chairman Chandler - witness Seelye	
	Note: Sacre, Candace Companies situation, not saying companies approach assume demand is sunk, on flip side, how determine base cost verse alternatives trying to reduce capacity costs upon replacement of current assets?	
2:21:36 PM	Chairman Chandler - witness Seelye	
	Note: Sacre, Candace Wickliffe, far east, far west?	

2:22:50 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Forecast loads, replacement costs, base case compare alternatives?
2:23:31 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Engineering looking at demand, retire and replace, know cost today, escalate five years out, alternatives, study looked certain circuits, hit
	peak particular circuits, not determine anything actually avoided, net
	metering not only thing have impact?
2:24:37 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace When look at alternatives, better out there serve load and not have
	this size transformer, demand response or energy efficiency
	program, avoid this cost or that cost, companies position net metering not avoid any costs as anticipate or distribution capacity
	costs are across board with exception of growth unavoidable?
2:27:36 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Supplemental rebuttal, talk about LOLP, Barnes use LOLP to allocate
	avoided generation fixed costs?
2:28:46 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace How did he allocate avoided generation fixed costs?
2:30:00 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace COS LOLP used to allocate fixed production costs based on
	contribution certain classes to allocate costs to individual classes for COS purposes?
2:30:54 PM	Chairman Chandler - witness Seelye
2.50.5	Note: Sacre, Candace Talking upstream from allocation to classes, saying standing
	upstream but using contribution of solar during those hours to
	allocate avoided capacity costs?
2:31:43 PM	Chairman Chandler - witness Seelye
2.21.E7 DM	Note: Sacre, Candace Before allocation of expenses to individual classes?
2:31:57 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Supplemental rebuttal, page 8, new entry PJM, discussion about net cone, rebuttal to Barnes use PJM determination net CONE as proxy
	unit for avoided generation capacity cost?
2:34:36 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Talk about problem with approach, neither KU/LG&E member of
	PJM, no bearing on companies costs, page 8 net CONE rarely comes
	into play PJM, what your experience is or understanding of what role
2:35:45 PM	net CONE play at PJM? Chairman Chandler - witness Seelye
2.33.43 FIVI	Note: Sacre, Candace Saying minimal offer price new entry unit is net cost new entry net
	of energy and ancillary services revenues?
2:36:08 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Any other role net CONE plays?
2:36:15 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace BRR curve?
2:36:16 PM	Chairman Chandler - witness Seelye
2 26 24 24	Note: Sacre, Candace Understand BRR demand curve for PJM base residual option?
2:36:24 PM	Chairman Chandler - witness Seelye
2:36:36 PM	Note: Sacre, Candace Anchor point BRR curve setting demand base residual option? Chairman Chandler - witness Seelye
2.30.30 FM	Note: Sacre, Candace If PJM net CONE anchor point BRR curve, net CONE does come into
	play significant way for capacity?
2:37:30 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace No new capacity being built at PJM?
2:37:44 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace For reliability?

2:37:47 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Idea of market regardless reliability, if new entry push out more
	expensive current entrance, people can enter all the time?
2:38:40 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Surprised find out current generators not go below net ACR number
	of generators still bid at zero as price tankers in PJM?
2:38:59 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace As long as not MOPR?
2:39:03 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Combined cycle units being built PJM every year?
2:39:45 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace 160,000 mW any day?
2:39:52 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Net CONE not used other ways to determine capacity charge at
	PJM?
2:40:08 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Rarely comes into play at PJM?
2:40:18 PM	Chairman Chandler - witness Seelye
	Note: Sacre, Candace Anchor point for demand curve, taken into account clearing price?
2:40:41 PM	Chairman Chandler - witness Seelye
2110111111	Note: Sacre, Candace Page 10, line 17, little or no need additional capacity PJM, net CONE
	no significance, clarify?
2:41:44 PM	Chairman Chandler - witness Seelye
2	Note: Sacre, Candace Page 10, line 15, just as net CONE not apply capacity value PJM, not
	apply companies, net CONE does apply at PJM?
2:42:48 PM	Chairman Chandler
21.21.10	Note: Sacre, Candace Break until 3.
2:43:07 PM	Session Paused
3:02:39 PM	Session Resumed
3:02:48 PM	Chairman Chandler
3.02.10111	Note: Sacre, Candace Back on the record in Case Nos. 2020-0349 and 2020-00350.
3:02:56 PM	Chairman Chandler
3.02.30 FM	Note: Sacre, Candace Redirect?
3:03:00 PM	Atty Crosby KU/LG&E - witness Seelye
3.03.00 FM	·
	Note: Sacre, Candace Redirect Examination. Supplemental direct, lines 6 and 7, to which commission referring on line 6, reviewed?
3:04:01 PM	Atty Crosby KU/LG&E - witness Seelye
3.04.01 FM	Note: Sacre, Candace Kentucky PSC?
3:04:08 PM	Atty Crosby KU/LG&E - witness Seelye
3.04.00 FM	Note: Sacre, Candace Exchange with Chairman PJM net CONE, recall?
3:04:19 PM	Atty Crosby KU/LG&E - witness Seelye
3:04:19 PM	· · · · · · · · · · · · · · · · · · ·
	Note: Sacre, Candace Still testimony PJM net CONE no bearing on companies capacity costs?
3:04:35 PM	*****
3.04.33 PM	Atty Crosby KU/LG&E - witness Seelye
2.04.47 DM	Note: Sacre, Candace How procure capacity costs?
3:04:47 PM	Atty Crosby KU/LG&E - witness Seelye
2.05.04.014	Note: Sacre, Candace Would go to market, issuing request for proposals?
3:05:01 PM	Atty Crosby KU/LG&E - witness Seelye
0.05.44.55	Note: Sacre, Candace Lowest cost meet customer needs?
3:05:14 PM	Atty Crosby KU/LG&E - witness Seelye
0.05.55.55	Note: Sacre, Candace Supplemental direct?
3:05:20 PM	Atty Crosby KU/LG&E - witness Seelye
	Note: Sacre, Candace Page 30, table, different cost components?

3:16:41 PM	Chairman Chandler Note: Sacre, Candace	Questions?
2.16.41 DM	Chairman Charadlar	analysis?
2.10.10 [1]	Note: Sacre, Candace	Recall order sent to companies could include or omit jobs benefits
3:16:16 PM	Atty Fitzgerald Joint Intervenors -	if think good idea? - witness Seelve
	Note: Sacre, Candace	Recall either include analysis economic development or jobs but only
3:15:57 PM	Atty Fitzgerald Joint Intervenors -	· ·
J.13.30 1 11	Note: Sacre, Candace	Familiar with May 14 Ky Power Order and earlier order in this case?
3:15:38 PM	Atty Fitzgerald Joint Intervenors -	metering? - witness Seelve
	Note: Sacre, Candace	Do jobs benefits analysis type and number of jobs created net
3:15:12 PM	Atty Fitzgerald Joint Intervenors -	
311 113 1 1 11	Note: Sacre, Candace	Recross Examination. Jobs associated with net metering externality?
3:14:34 PM	Note: Sacre, Candace Atty Fitzgerald Joint Intervenors -	Questions? - witness Seelve
3:14:20 PM	Chairman Chandler	Questions?
2.14.20 054	·	capacity cost would be variable?
3113133 111	Note: Sacre, Candace	In terms of hybrid, one percent fixed and avoided generation
3:13:55 PM	Atty Spenard KYSEIA - witness Se	percent?
	Hotel Sacrey curiouse	different percentage amount, instead charge determined as .75
J.12.UT FIVI	Note: Sacre, Candace	Line 5, puts in contrast for me, alternatives, could have listed
3:12:04 PM	Atty Spenard KYSEIA - witness Se	those are alternatives arrived at uniquely by jurisdictional bodies?
		alternatives, compensation rate based upon FERC Schedule 3 charge OATT, or alternatively have charge determined by PSC, testimony is
J.0J.JJ FI'I	Note: Sacre, Candace	Recross Examination. Supplemental, page 17, in terms of two
3:09:35 PM	Note: Sacre, Candace Atty Spenard KYSEIA - witness Se	Questions?
3:09:20 PM	Chairman Chandler	Overtions?
	Note: Sacre, Candace	Were less, companies do it?
3:08:56 PM	Atty Kurtz KIUC - witness Seelye	costs and replace with something else?
	Note: Sacre, Candace	Evidence in record economic retire coal plant to eliminate employee
3:08:37 PM	Atty Kurtz KIUC - witness Seelye	,
	Note: Sacre, Candace	Retire coal plant, get rid of employee costs, net book value not go away?
3:08:21 PM	Atty Kurtz KIUC - witness Seelye	Define and others are side of
	Note: Sacre, Candace	All union employees?
3:08:12 PM	Atty Kurtz KIUC - witness Seelye	to combined cycle other ruendes:
	Note: Sacre, Candace	Recross Examination. Lots of people work big coal plants compared to combined cycle other facilities?
3:07:51 PM	Atty Kurtz KIUC - witness Seelye	
J.U/.TZ FIN	Note: Sacre, Candace	Questions?
3:07:42 PM	Note: Sacre, Candace Chairman Chandler	Recent ones little less than three cents?
3:07:30 PM	Atty Crosby KU/LG&E - witness S	eelye
	Note: Sacre, Candace	Understanding companies recent solar PPA experience indicate utility scale solar had for less than three cents kWh?
3:06:52 PM	Atty Crosby KU/LG&E - witness S	•
		would be?
	Note: Sacre, Candace	Your view of seven avoided cost components how many equally well avoided utility scale solar as by rooftop solar, which categories
3:05:39 PM	Atty Crosby KU/LG&E - witness S	eelye

3:16:46 PM	General Counsel Vinsel PSC - witr	nors Soolyo
3.10.70 FM	Note: Sacre, Candace	Recross Examination. Aware of RFP companies issued January?
3:16:58 PM	General Counsel Vinsel PSC - witr	·
3120130 111	Note: Sacre, Candace	Companies requesting 300 to 900 megawatts beginning 2025 to 2028 and earlier than 2025, at April 28 hearing, Bellar confirmed may seek additional capacity before 2025, reconcile KU/LG&E not need additional generation with RFP?
3:18:21 PM	General Counsel Vinsel PSC - witr	
	Note: Sacre, Candace	Can't reconcile fact RFP issued and fact companies not need additional generation?
3:19:08 PM	Chairman Chandler	
	Note: Sacre, Candace	Questions?
3:19:10 PM	Chairman Chandler - witness Seel	lye
	Note: Sacre, Candace	Examination. Conroy next best person to ask question Vinsel just asked?
3:19:34 PM	Chairman Chandler	
	Note: Sacre, Candace	Witness is excused.
3:19:37 PM	Chairman Chandler	
	Note: Sacre, Candace	Next witness?
3:20:17 PM	Atty Crosby KU/LG&E	
	Note: Sacre, Candace	Robert Conroy.
3:20:32 PM	Chairman Chandler	
2 20 40 DM	Note: Sacre, Candace	Witness is sworn.
3:20:40 PM	Chairman Chandler - witness Con	•
2,21,02 DM	Note: Sacre, Candace	Examination. Name and address?
3:21:02 PM	Atty Crosby KU/LG&E - witness Co Note: Sacre, Candace	Direct Examination. By whom employed and what capacity?
3:21:28 PM	Atty Crosby KU/LG&E - witness Co	
3.21.20 111	Note: Sacre, Candace	Cause prepared and filed written direct and rebuttal as well as supplemental direct and rebuttal?
3:21:29 PM	Atty Crosby KU/LG&E - witness Co	• •
• · · · · · · · · · · · · · · · · · · ·	Note: Sacre, Candace	Sponsor of data requests?
3:21:31 PM	Atty Crosby KU/LG&E - witness Co	•
	Note: Sacre, Candace	Adopt prefiled testimony and responses?
3:21:37 PM	Atty Crosby KU/LG&E - witness Co	onroy
	Note: Sacre, Candace	What have available to you or with you?
3:22:11 PM	Chairman Chandler	
	Note: Sacre, Candace	Questions?
3:22:18 PM	Atty Kurtz KIUC - witness Conroy	
	Note: Sacre, Candace	Cross Examination. QF contract 80 mW large impact?
3:22:45 PM	Atty Kurtz KIUC - witness Conroy	
	Note: Sacre, Candace	Within large 20-year QF contract, lots of terms and conditions, assignability, penalty for nonperformance, security deposits, covenants, could be lengthy?
3:23:24 PM	Atty Kurtz KIUC - witness Conroy	
	Note: Sacre, Candace	Bring to Commission for approval or just sign it?
3:23:38 PM	Atty Kurtz KIUC - witness Conroy	
	Note: Sacre, Candace	No objection if Commission required bring contracts?
3:23:50 PM	Chairman Chandler	
	Note: Sacre, Candace	Questions?
3:23:58 PM	Atty Spenard KYSEIA - witness Co	•
	Note: Sacre, Candace	Cross Examination. In terms of application, testimony submitted both applications?

3:24:28 PM	Atty Spenard KYSEIA - witness Conroy Note: Sacre, Candace Applications tendered Nov 25 2020 Volume 2 of 4, included your
	direct?
3:24:31 PM	Atty Spenard KYSEIA - witness Conroy Note: Sacre, Candace Appendix A qualifications, fair to say basically sets forth
	background?
3:24:55 PM	Atty Spenard KYSEIA - witness Conroy
	Note: Sacre, Candace Review of Appendix A, technical or other specialized knowledge rates?
3:25:23 PM	Atty Spenard KYSEIA - witness Conroy
	Note: Sacre, Candace In terms of experience, not attorney?
3:25:40 PM	Atty Spenard KYSEIA - witness Conroy Note: Sacre, Candace Not asking legal opinions, asked in context of understanding in
	terms of knowledge and background?
3:26:17 PM	Atty Spenard KYSEIA - witness Conroy
	Note: Sacre, Candace In terms of supplemental, page 4, line 12, jobs benefit?
3:26:39 PM	Atty Spenard KYSEIA - witness Conroy
2 27 24 514	Note: Sacre, Candace Rebuttal, page 4, line 16, discussion economic development study?
3:27:01 PM	Atty Spenard KYSEIA - witness Conroy
2-27-47 DM	Note: Sacre, Candace Global big picture question, Commission no authority consider job benefits or economic development ratemaking authority?
3:27:47 PM	Atty Spenard KYSEIA - witness Conroy
	Note: Sacre, Candace Companies required to be indifferent to jobs creation design of rates?
3:28:02 PM	Atty Spenard KYSEIA - witness Conroy
	Note: Sacre, Candace When designing rates, understanding companies required to be indifferent jobs creation, not part of rate design process?
3:28:33 PM	Atty Spenard KYSEIA - witness Conroy
	Note: Sacre, Candace Allowed to take into consideration job creation when designing rates?
3:29:08 PM	Atty Spenard KYSEIA - witness Conroy
	Note: Sacre, Candace Costs of service, COSSs, and also rate design, not necessarily synonymous concepts?
3:29:54 PM	Atty Spenard KYSEIA - witness Conroy
2 20 45 514	Note: Sacre, Candace Companies required to be indifferent to economic development?
3:30:15 PM	Atty Spenard KYSEIA - witness Conroy Note: Sacre, Candace Supplemental rebuttal, page 5, footnote 10, three orders 2020-
	00016 in support, May 8 2020 June 18 2020 and December 12 2020, aware of that?
3:31:06 PM	Atty Spenard KYSEIA - witness Conroy
	Note: Sacre, Candace Discussion in text lines 11-13, end reference footnote 10, aware of orders in 2020, rely upon those for testimony you cite?
3:31:58 PM	Atty Spenard KYSEIA - witness Conroy
	Note: Sacre, Candace Read each of those orders?
3:32:06 PM	Atty Spenard KYSEIA - witness Conroy
3:32:37 PM	Note: Sacre, Candace Application in 2020-00016, level of familiarity?
J.J2.J/ FI'I	Atty Spenard KYSEIA - witness Conroy Note: Sacre, Candace Remain testimony today Commission may not consider jobs benefit or economic when considering net metering rates?
3:33:14 PM	Atty Spenard KYSEIA - witness Conroy
3.33.11111	Note: Sacre, Candace Agree supplemental page 4 line 18 offers opinion as to limits of Commission jurisdiction?
3:33:42 PM	Atty Spenard KYSEIA - witness Conroy
	Note: Sacre, Candace Page 4, supplemental, looking at page 4, line 18, discussion begins line 16, Commission's jurisdiction?

3:34:08 PM	Atty Spenard KYSEIA - witness Co	,
	Note: Sacre, Candace	Question on line 16, Commission jurisdiction?
3:34:29 PM	Atty Spenard KYSEIA - witness Co	·
	Note: Sacre, Candace	Jobs benefit net metering line 18 stated, reading (click on link for
3:35:13 PM	Atty Spenard KYSEIA - witness Co	further comments), see that?
3.33.13 FM	Note: Sacre, Candace	Testimony, supplemental testimony, Commission's jurisdiction, page
	Note: Sacre, Canadee	4, line 16 next pages, twice in these cases offered opinion as to
		Commission jurisdiction with regard to jobs benefit and
		supplemental opinion jurisdiction economic development, fair
		characterization?
3:36:51 PM	Atty Spenard KYSEIA - witness Co	,
	Note: Sacre, Candace	Opinion Commission may not require companies study jobs benefits?
3:37:09 PM	Atty Spenard KYSEIA - witness Co	,
	Note: Sacre, Candace	Opinion may Commission require, mandate companies shall take action, Commission may require companies study economic
		development as to net metering rates?
3:37:46 PM	Atty Spenard KYSEIA - witness Co	•
	Note: Sacre, Candace	Asking opinion who has twice offered opinion in terms of
	,	Commission jurisdiction, asking whether Commission may require
		companies study economic development?
3:38:53 PM	Chairman Chandler	
	Note: Sacre, Candace	Questions?
3:39:05 PM	Atty Fitzgerald Joint Intervenors -	<i>,</i>
2.20.20 DM	Note: Sacre, Candace	Cross Examination. Duration of billing period KU/LG&E?
3:39:39 PM	Atty Fitzgerald Joint Intervenors - Note: Sacre, Candace	Different for commercial customers?
3:39:54 PM	Atty Fitzgerald Joint Intervenors -	
3.33.31111	Note: Sacre, Candace	Duration of billing period, same for customers residential or
	rioter basis, barrage	commercial under net metering tariff?
3:40:22 PM	Atty Fitzgerald Joint Intervenors -	-
	Note: Sacre, Candace	Period generally same for other PSC regulated utilities in Kentucky?
3:40:45 PM	Atty Fitzgerald Joint Intervenors -	<i>,</i>
	Note: Sacre, Candace	Changed in KU/LG&E system since 2018?
3:40:57 PM	Atty Fitzgerald Joint Intervenors -	•
2 44 40 014	Note: Sacre, Candace	Economic development, occasion to visit web site of parent PPL?
3:41:40 PM	Atty Fitzgerald Joint Intervenors -	•
3:41:55 PM	Note: Sacre, Candace Atty Fitzgerald Joint Intervenors -	Email list to get press releases from company?
J.71.JJ FM	Note: Sacre, Candace	October 6 2020 press release PPL international magazine KU/LG&E
	Note: Sacre, Canadee	top 20 utilities economic development success?
3:42:20 PM	Atty Fitzgerald Joint Intervenors	
	Note: Sacre, Candace	Publicly-available press release on web site, will send in hard copy
		as Joint Intervenors Exhibit 2. (Click on link for further comments.)
3:42:56 PM	Chairman Chandler	
	Note: Sacre, Candace	Note as Joint Intervenors Exhibit 2, share it, lay foundation and ask
2-42-00 DM	Att. Change of Jaint Telegraph	questions, and then will ask parties objection.
3:43:08 PM	Atty Fitzgerald Joint Intervenors -	<i>,</i>
3:43:25 PM	Note: Sacre, Candace Atty Fitzgerald Joint Intervenors -	Quote by Eileen Saunders, who is Eileen Saunders?
J.TJ.ZJ FIII	Note: Sacre, Candace	Quoted as saying, reading (click on link for further comments),
	. voter oder cy curiodec	familiar with the innovative programs and incentives companies
		have available for economic development?

3:44:27 PM	Atty Fitzgerald Joint Intervenors - witness Conroy Note: Sacre, Candace Include incentives rates more attractive otherwise available to
	customer in class?
3:45:01 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Supplemental rebuttal?
3:45:06 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Page 11, lines 18-22, read testimony?
3:45:59 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Page 12, lines 1-3, read please?
3:46:39 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace What evidence any joint intervenors direct financial ties to solar facilities?
3:47:08 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Consider direct financial ties?
3:47:25 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace What evidence joint intervenors, which are non-profit, tax-exempt
	organizations, have direct financial ties to small scale solar facilities?
3:48:30 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Implied joint intervenors organizations direct financial ties, what evidence have that these organizations profit from installation of small scale solar facilities?
3:49:25 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Suggesting Rabago or Barnes altered testimony or lied for personal gain?
3:49:48 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Implying skewed testimony to benefit?
3:50:25 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Does not companies have own solar offerings to customers?
3:50:46 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Do shareholders realize rate of return in your solar offerings?
3:51:09 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Do shareholders receive a rate of return on investments companies make in standing solar offerings?
3:51:46 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace And are you getting rate of return on that?
3:51:56 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Shareholders not either?
3:52:12 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Position that someone who hires expert or compensates witness casts doubt on veracity of testimony?
3:52:39 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Conversations with Rabago or Barnes about motivations?
3:52:55 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Of the mind value of rooftop solar exceeds cost?
3:53:12 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Read studies have looked at value of solar included in Rabago testimony SEIA.org benefit studies?
3:53:52 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Assume agree determination reasonable boundaries what reasonable established by May 14 2021 order Ky Power case?
3:55:08 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Understand Rabago and Barnes inclusion of solar rooftop improve value for all customers opposed to additional costs?
3:55:48 PM	Atty Fitzgerald Joint Intervenors - witness Conroy
	Note: Sacre, Candace Any of those folks testifying for free or being compensated?

3:56:07 PM Atty Fitzgerald 2 Note: Sacre, 3:56:54 PM Atty Fitzgerald 2 Note: Sacre, 3:57:46 PM Atty Fitzgerald 2 Note: Sacre, 3:59:22 PM Atty Fitzgerald 2 Note: Sacre, 4:00:03 PM Atty Fitzgerald 2 Note: Sacre, 4:00:40 PM Chairman Chair
3:56:54 PM Atty Fitzgerald 2 Note: Sacre, 3:57:46 PM Atty Fitzgerald 2 Note: Sacre, 3:59:22 PM Atty Fitzgerald 2 Note: Sacre, 4:00:03 PM Atty Fitzgerald 2 Note: Sacre, Atty Fitzgerald 2 Note: Sacre, Atty Fitzgerald 2 Note: Sacre,
Note: Sacre, 3:57:46 PM Atty Fitzgerald 2 Note: Sacre, 3:59:22 PM Atty Fitzgerald 2 Note: Sacre, 4:00:03 PM Atty Fitzgerald 2 Note: Sacre, Atty Fitzgerald 2 Note: Sacre, Note: Sacre,
Note: Sacre, 3:57:46 PM Atty Fitzgerald 2 Note: Sacre, 3:59:22 PM Atty Fitzgerald 2 Note: Sacre, 4:00:03 PM Atty Fitzgerald 2 Note: Sacre, Atty Fitzgerald 2 Note: Sacre, Note: Sacre,
Note: Sacre, 3:57:46 PM Atty Fitzgerald 2 Note: Sacre, 3:59:22 PM Atty Fitzgerald 2 Note: Sacre, 4:00:03 PM Atty Fitzgerald 2 Note: Sacre, Atty Fitzgerald 2 Note: Sacre, Note: Sacre,
3:57:46 PM Atty Fitzgerald 2 Note: Sacre, 3:59:22 PM Atty Fitzgerald 2 Note: Sacre, 3:59:58 PM Atty Fitzgerald 2 Note: Sacre, 4:00:03 PM Atty Fitzgerald 2 Note: Sacre, Note: Sacre,
Note: Sacre, 3:59:22 PM Atty Fitzgerald 2 Note: Sacre, 3:59:58 PM Atty Fitzgerald 2 Note: Sacre, 4:00:03 PM Atty Fitzgerald 2 Note: Sacre, Note: Sacre,
Note: Sacre, 3:59:22 PM Atty Fitzgerald 2 Note: Sacre, 3:59:58 PM Atty Fitzgerald 2 Note: Sacre, 4:00:03 PM Atty Fitzgerald 2 Note: Sacre, Note: Sacre,
Note: Sacre, 3:59:22 PM Atty Fitzgerald 2 Note: Sacre, 3:59:58 PM Atty Fitzgerald 2 Note: Sacre, 4:00:03 PM Atty Fitzgerald 2 Note: Sacre, Note: Sacre,
3:59:22 PM Atty Fitzgerald 3 Note: Sacre, 3:59:58 PM Atty Fitzgerald 3 Note: Sacre, 4:00:03 PM Atty Fitzgerald 3 Note: Sacre, Note: Sacre,
Note: Sacre, 3:59:58 PM Atty Fitzgerald 2 Note: Sacre, 4:00:03 PM Atty Fitzgerald 2 Note: Sacre,
Note: Sacre, 3:59:58 PM Atty Fitzgerald 2 Note: Sacre, 4:00:03 PM Atty Fitzgerald 2 Note: Sacre,
3:59:58 PM Atty Fitzgerald 3 Note: Sacre, 4:00:03 PM Atty Fitzgerald 3 Note: Sacre,
Note: Sacre, 4:00:03 PM Atty Fitzgerald Socre, Note: Sacre,
Note: Sacre, 4:00:03 PM Atty Fitzgerald Socre, Note: Sacre,
Note: Sacre, 4:00:03 PM Atty Fitzgerald Socre, Note: Sacre,
4:00:03 PM Atty Fitzgerald Note: Sacre,
Note: Sacre,
4.00.40 PM Chairman Chan
4.00.40 DM Chairman Chan
4:00:40 PM Chairman Chan
Note: Sacre,
4:00:58 PM Session Paused
4:10:07 PM Session Resume
4:10:17 PM Chairman Chan
Note: Sacre,
4:10:30 PM Chairman Chan
4:10:30 PM Chairman Chand Note: Sacre,
4:10:30 PM Chairman Chance Note: Sacre, 4:10:35 PM General Counse
4:10:30 PM Chairman Chang Note: Sacre, 4:10:35 PM General Counse Note: Sacre,
4:10:30 PM Chairman Chang Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L
4:10:30 PM Chairman Chand Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre,
4:10:30 PM Chairman Chane Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse
4:10:30 PM Chairman Chand Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre,
4:10:30 PM Chairman Chang Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre,
4:10:30 PM Chairman Chane Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre, 4:11:34 PM Atty Riggs KU/L
4:10:30 PM Chairman Chang Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre,
4:10:30 PM Chairman Chane Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre, 4:11:34 PM Atty Riggs KU/L
4:10:30 PM Chairman Change Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre, 4:11:34 PM Atty Riggs KU/L Note: Sacre, 4:11:34
4:10:30 PM Chairman Chane Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre, 4:11:34 PM Atty Riggs KU/L Note: Sacre, 4:12:16 PM Chairman Chane
4:10:30 PM Chairman Chane Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre, 4:11:34 PM Atty Riggs KU/L Note: Sacre, 4:12:16 PM Chairman Chane Note: Sacre,
4:10:30 PM Chairman Chand Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre, 4:11:34 PM Atty Riggs KU/L Note: Sacre, 4:12:16 PM Chairman Chand Note: Sacre, 4:12:54 PM Atty Riggs KU/L
4:10:30 PM Chairman Chane Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre, 4:11:34 PM Atty Riggs KU/L Note: Sacre, 4:12:16 PM Chairman Chane Note: Sacre,
4:10:30 PM Chairman Chand Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre, 4:11:34 PM Atty Riggs KU/L Note: Sacre, 4:12:16 PM Chairman Chand Note: Sacre, 4:12:54 PM Atty Riggs KU/L
4:10:30 PM Chairman Chane Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre, 4:11:34 PM Atty Riggs KU/L Note: Sacre, 4:12:16 PM Chairman Chane Note: Sacre, 4:12:54 PM Atty Riggs KU/L Note: Sacre, 4:12:54 PM Atty Riggs KU/L Note: Sacre,
4:10:30 PM Chairman Chane Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre, 4:11:34 PM Atty Riggs KU/L Note: Sacre, 4:12:16 PM Chairman Chane Note: Sacre, 4:12:54 PM Atty Riggs KU/L Note: Sacre, 4:13:41 PM General Counse
4:10:30 PM Chairman Chane Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre, 4:11:34 PM Atty Riggs KU/L Note: Sacre, 4:12:16 PM Chairman Chane Note: Sacre, 4:12:54 PM Atty Riggs KU/L Note: Sacre, 4:12:54 PM Atty Riggs KU/L Note: Sacre,
4:10:30 PM Chairman Chane Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre, 4:11:34 PM Atty Riggs KU/L Note: Sacre, 4:12:16 PM Chairman Chane Note: Sacre, 4:12:54 PM Atty Riggs KU/L Note: Sacre, 4:13:41 PM General Counse
4:10:30 PM Chairman Chane Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre, 4:11:34 PM Atty Riggs KU/L Note: Sacre, 4:12:16 PM Chairman Chane Note: Sacre, 4:12:54 PM Atty Riggs KU/L Note: Sacre, 4:13:41 PM General Counse
4:10:30 PM Chairman Chand Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre, 4:11:34 PM Atty Riggs KU/L Note: Sacre, 4:12:16 PM Chairman Chand Note: Sacre, 4:12:54 PM Atty Riggs KU/L Note: Sacre, 4:13:41 PM General Counse Note: Sacre,
4:10:30 PM Chairman Chane Note: Sacre, 4:10:35 PM General Counse Note: Sacre, 4:10:57 PM Atty Riggs KU/L Note: Sacre, 4:11:17 PM General Counse Note: Sacre, 4:11:34 PM Atty Riggs KU/L Note: Sacre, 4:12:16 PM Chairman Chane Note: Sacre, 4:12:54 PM Atty Riggs KU/L Note: Sacre, 4:13:41 PM General Counse Note: Sacre, 4:13:45 PM POST-HEARING

4:14:13 PM	Session Paused
4:14:23 PM 4:15:20 PM	Session Resumed General Counsel Vinsel PSC - witness Conroy
7.13.20 FM	Note: Sacre, Candace Follow up question to Seelye reconciling testimony KU/LG&E not
	need additional capacity, press release January 7 2021, copy all counsel. (Click on link for further comments.)
4:16:04 PM	General Counsel Vinsel PSC
	Note: Sacre, Candace Copy from KU/LG&E website, introduce as PSC Staff Exhibit 7.
4:17:20 PM	General Counsel Vinsel PSC - witness Conroy
	Note: Sacre, Candace Headline misleading in use of term energy, LG&E/KU request bids for energy to continue to reliably serve customers, use of term energy not reflecting energy versus capacity, reading (click on link for further comments), have accurately read?
4:18:23 PM	General Counsel Vinsel PSC - witness Conroy
	Note: Sacre, Candace Mill Creek 1 300 mW?
4:18:33 PM	General Counsel Vinsel PSC - witness Conroy
	Note: Sacre, Candace Mill Creek 2 little under at 297?
4:18:49 PM	General Counsel Vinsel PSC - witness Conroy
	Note: Sacre, Candace January 7 2021 RFP introduced into record, Joint Intervenors Exhibit 1, reading (click on link for further comments), companies intention replace shortfalls retirements of Mill Creek 1 in 2024 and additional retirements in 2028?
4:21:14 PM	General Counsel Vinsel PSC - witness Conroy
	Note: Sacre, Candace Saying Seelye correct companies not need additional capacity until after 2028?
4:23:01 PM	General Counsel Vinsel PSC - witness Conroy
	Note: Sacre, Candace Fair say KU/LG&E making plans need for capacity in 2024?
4:23:20 PM	General Counsel Vinsel PSC - witness Conroy
	Note: Sacre, Candace Press release not entirely correct, generation capacity expected shortfall created by retirements, including Mill Creek 1?
4:24:00 PM	General Counsel Vinsel PSC - witness Conroy
	Note: Sacre, Candace Discussion with Seelye, Staff reviewed billing period netting process, difference between measurement period, netting period, and billing cycle, how line up, correct me if wrong?
4:25:08 PM	General Counsel Vinsel PSC - witness Conroy
	Note: Sacre, Candace Energy is either consumed, goes through meter, energy back out into grid, instantaneous, talking about measurement?
4:27:41 PM	General Counsel Vinsel PSC - witness Conroy
	Note: Sacre, Candace Netting period is billing cycle?
4:27:54 PM	General Counsel Vinsel PSC - witness Conroy
	Note: Sacre, Candace Talking about dollar value energy produced and dollar value energy consumed, net goes to looking at billing period?
4:28:30 PM	General Counsel Vinsel PSC - witness Conroy
	Note: Sacre, Candace Issue TS-2 pipeline suppliers demand component, included wrong rate, lower than had been approved, what over or under collection and also ask for thoughts on how credited to or charged customers, June 30 order approved rate, lower than one approved on May 1?
4:29:43 PM	General Counsel Vinsel PSC - witness Conroy
	Note: Sacre, Candace Correct because subsequent case August 1 established another rate for TS-2?
4:30:14 PM	General Counsel Vinsel PSC - witness Conroy
	Note: Sacre, Candace July 1 - July 30 over and under collection or longer period?

4:31:49 PM	General Counsel Vinsel PSC - wit	ness Conrov
	Note: Sacre, Candace	Rehearing matter, companies asking Commission to nunc June 30
	·	Order to reflect rates approved for May, June, and July? Not want
		you to answer.
4:32:22 PM	Chairman Chandler - witness Cor	nroy
	Note: Sacre, Candace	Examination. Way Commission enter subsequent order fix problem
		indicated by companies, rate implemented that fixes problem
4 22 52 514		companies claim is there?
4:32:50 PM	Atty Crosby KU/LG&E - witness C	,
	Note: Sacre, Candace	Direct Examination. Currently billing correct rates because of GSC
4:33:04 PM	Atty Crosby KU/LG&E - witness C	proceeding?
T.33.0T FM	Note: Sacre, Candace	What has happened, difference between Order text had and what
	Note: Sacre, Caridace	companies billed, net \$90 detriment to companies, net
		undercollection?
4:33:34 PM	Chairman Chandler - witness Cor	
	Note: Sacre, Candace	Examination. Correct in mathematical sense, not necessarily rate in
	ŕ	Commission June 30 Order?
4:33:55 PM	General Counsel Vinsel PSC - wit	ness Conroy
	Note: Sacre, Candace	Cross Examination (cont'd). So there was no over- or under-
		collection?
4:34:29 PM	General Counsel Vinsel PSC - with	•
4.06.54.004	Note: Sacre, Candace	Asking application be amended reflect new tariffs?
4:36:51 PM	General Counsel Vinsel PSC - with	,
	Note: Sacre, Candace	Joint account issue, copy of KU/LG&E paper application on file in this case?
4:37:16 PM	General Counsel Vinsel PSC - wit	
1.57.110 111	Note: Sacre, Candace	Application for new residential customer service?
4:37:46 PM	General Counsel Vinsel PSC - with	• •
	Note: Sacre, Candace	Post-hearing data request, copies of KU/LG&E residential customers
	·	new service?
4:38:14 PM	POST-HEARING DATA REQUEST	
	Note: Sacre, Candace	GENERAL COUNSEL VINSEL PSC - WITNESS CONROY
	Note: Sacre, Candace	APPLICATION FOR NEW SERVICE - RESIDENTIAL CUSTOMERS
4:38:16 PM	General Counsel Vinsel PSC - wit	•
	Note: Sacre, Candace	Start service, what listed primary account holder, no option joint
4-20-20 PM	Consum Consum of Misson I DCC	account?
4:38:39 PM	General Counsel Vinsel PSC - wit	•
4:38:59 PM	Note: Sacre, Candace General Counsel Vinsel PSC - wit	Ms. Saunders better person?
4.30.33 FM	Note: Sacre, Candace	On line, way to set up authorized party, one person primary account
	Note: Sacre, Candace	holder, how know implication for service based on information from
		on-line application?
4:40:38 PM	General Counsel Vinsel PSC - wit	• •
	Note: Sacre, Candace	Supplemental referenced Commission regulation QF right to sell
		power cost greater than those KU/LG&E would occur, page 2, lines
		19-22, whether QF price above cost, what is benchmark? How
		benchmark align with KU/LG&E fuel adjustment clause economic
4.42.00 084	Conord Coursel Vizzel DCC	non-economic power highest cost unit calculation?
4:42:08 PM	General Counsel Vinsel PSC - wit	•
	Note: Sacre, Candace	Benchmark determine cost to purchase from QF higher than what companies would generate?
4:45:20 PM	Chairman Chandler	companies would generate:
	Note: Sacre, Candace	Questions?
		4

4:45:24 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Examination. Less than ten cents by definition economic?
4:46:45 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Determining factor, may not be ten cents, less than variable cost
	available to utility in that month, all purchases deemed economic under threshold?
4:47:15 PM	Chairman Chandler - witness Conroy
7.77.15111	Note: Sacre, Candace Rhude's Creek 2.7 cents kilowatt hour?
4:47:32 PM	Chairman Chandler - witness Conroy
11 17 132 111	Note: Sacre, Candace Seelye supplemental rebuttal, page 25, reading (click on link for
	further comments), see that?
4:49:49 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Answer, reading (click on link for further comments), that what
	says?
4:50:12 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Rhudes Creek 2.7 cents, equivalent to 1.8 cents?
4:50:39 PM	Chairman Chandler - witness Conroy
4 FO 44 BM	Note: Sacre, Candace May be \$7, may be \$5, may be \$17 someday?
4:50:44 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Market price for RECs, purchase price companies under get energy, RECs, pay 2.7 cents kWh?
4:51:07 PM	Chairman Chandler - witness Conroy
1.51.07 111	Note: Sacre, Candace Minimum, maximum, lot of terms, under highest unit cost
	calculation?
4:51:26 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Discuss 807 KAR 5:054 about lose obligation to pay or obligation
	ceases?
4:51:55 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Companies have position whether determination not economic
	purchase from QF that when ceases or when it hits marginal energy price?
4:53:20 PM	Chairman Chandler - witness Conroy
1.55.20 111	Note: Sacre, Candace Say Commission enters order setting cost QFs 2.7 cents, in excess
	marginal energy price per Seelye, run afoul of regulation provision
	discussing in testimony?
4:54:10 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace What just said for FAC purposes Rhude's Creek higher what filing
	each quarter?
4:54:45 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Proposing 2.7 cents Rhude's Creek price QF avoided energy rate not have RECs companies sell?
4:55:06 PM	Chairman Chandler - witness Conroy
T.33.00 FM	Note: Sacre, Candace Rhudes Creek price, also pointing to tariff obligation to purchase
	ends, companies looked at own proposal turn around for QF make it
	even though paying avoided cost at time implementation run afoul
	of regulation, never mind, no obligation pay that?
4:56:57 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace 2.3 as filed assume 2.3, QF produces electricity October shoulder
	month ready give available energy, testimony if cost companies
4:58:44 PM	generate equivalent amount energy lower, then curtail that entity? Chairman Chandler - witness Conroy
T.JU.TT FIVI	Note: Sacre, Candace Bringing to Commission regulation exists, if set at this rate, this
	regulation exists?

. = 0 = 0 = 0	
4:59:59 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Seelye supplemental rebuttal, page 24, bottom 23, sentence,
	Companies will make, reading (click on link for further comments),
	Seelye speak for companies on this issue or companies position FAC
	rules is/is not economic, companies understand rules and do
E-02-27 DM	whatever decide do?
5:02:27 PM	Chairman Chandler - witness Conroy
E 02 EE DM	Note: Sacre, Candace Not saying companies changed how look at off-system purchases?
5:02:55 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Companies position not economic purchases lower than companies
F.02.21 DM	marginal running costs?
5:03:21 PM	Chairman Chandler - witness Conroy
E-02-EC DM	Note: Sacre, Candace 5:054 Section 7, have that?
5:03:56 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Supplemental, line 8, reading (click on link for further comments),
F.04.17 DM	remember that?
5:04:17 PM	Chairman Chandler - witness Conroy Note: Sacre Candage - Regulation (7) and then Sub (5) reduction of fessil fuel use?
F.04.F2 DM	Note: Sacre, Candace Regulation, (7) and then Sub (5), reduction of fossil fuel use? Chairman Chandler - witness Conroy
5:04:52 PM	,
	Note: Sacre, Candace Does what read for 7(5)(b) take into account companies proposal
5:06:54 PM	avoided energy and avoid capacity cost? Chairman Chandler - witness Conroy
5.06.54 PM	,
	Note: Sacre, Candace Very next section (c) discusses line losses, Section 7(5)(c), only avoided energy avoided capacity, companies appropriately included
	line losses that would not have existed in initial proposal?
5:07:52 PM	Chairman Chandler - witness Conroy
3.07.32 114	Note: Sacre, Candace What in front of Commission in tariffs?
5:08:44 PM	Chairman Chandler - witness Conroy
5.00.44114	Note: Sacre, Candace Read final Ky Power order denying rehearing?
5:09:52 PM	Chairman Chandler - witness Conroy
J.03.JZ FM	Note: Sacre, Candace Part discusses what law requires netting under net metering, read?
5:10:23 PM	Chairman Chandler - witness Conroy
J.10.25 FM	Note: Sacre, Candace Aware differences what companies proposal for netting verse
	Commission clarified in June Order?
5:10:53 PM	Chairman Chandler - witness Conroy
3.10.33	Note: Sacre, Candace Ky Power proposed two netting periods?
5:11:09 PM	Chairman Chandler - witness Conrov
3.11.03 111	Note: Sacre, Candace Order, page 14, reading (click on link for further comments),
	companies proposal implementation all electricity consumed and all
	fed back consistent with this order?
5:16:26 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Billing line items?
5:16:40 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace School tax?
5:16:45 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Percentage of total bill?
5:16:46 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Start with percentage total bill, net metering customer, 500 kW
	charged retail rate in tariff?
5:17:03 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Bill credit worth \$300, company apply 500 kWh all riders based off
	kWh?
5:18:40 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Before sum two, calculating riders based off usage?

= 40 == = = = = = = = = = = = = = = = =		
5:18:53 PM	Chairman Chandler - witness Conroy	
		ll energy consume, all energy purchase from company?
5:19:22 PM	Chairman Chandler - witness Conroy	
		ther line items fixed based off usage percentage of riders, any
		asses net metering demand related other billing items or just those
		rree?
5:19:53 PM	Chairman Chandler - witness Conroy	
		xed amounts are fixed amounts, kWh based off kWh purchased
		om company, percentage of revenue based off what?
5:20:26 PM	Chairman Chandler - witness Conroy	
	·	ome up with bill what bought from us, take kWh times rate
		ommission set compensation and then sum what bill otherwise be
E 20 EZ D14		om first part of calculation?
5:20:57 PM	Chairman Chandler - witness Conroy	
		one once a billing cycle, 12 times a year, as a bill ordinarily done
E 24 44 DM		oday?
5:21:11 PM	Chairman Chandler - witness Conroy	
E 24 20 DM		ccumulation of credits frequency are determined?
5:21:38 PM	Chairman Chandler	
E 22 00 DM		uestions?
5:22:08 PM	Chairman Chandler	
E 22 42 DM	•	/itness is excused.
5:22:18 PM	Chairman Chandler	
E 22 22 D14	•	ext witness?
5:22:20 PM	Atty Crosby KU/LG&E	
E 22 42 D14	•	lleen Saunders.
5:22:43 PM	Chairman Chandler	
F-22-FC DM		ne more question for Conroy.
5:22:56 PM	Chairman Chandler - witness Conroy	
		xamination. Notification for rehearing, 278.190 emergency rate rocedures?
5:23:22 PM	רום Chairman Chandler - witness Conroy	
J.2J.22 FM	•	/hat know about emergency rate procedures?
5:23:51 PM	Chairman Chandler - witness Conroy	e , ,
J.2J.J1 FM	•	mergency reg relief under 278.190(2), familiar with statute?
5:26:57 PM	Note: Sacre, Candace Er Chairman Chandler - witness Conroy	- · ·
J.20.37 FM	,	ware of stipulation provision stay-out?
5:27:14 PM	Chairman Chandler - witness Conroy	
J.27.17 FM	•	ortion allows Commission suspend ordinary tariff for five months
	·	nd forecasted six months?
5:27:40 PM	Chairman Chandler - witness Conroy	
3.27. 10 114	•	ection stipulation cites for four-year stay-out?
5:27:56 PM	Chairman Chandler - witness Conroy	·
3.27.30 TM	•	/hat process around something happen now and four year stay-out
	The state of the s	ling for emergency rate relief?
5:28:33 PM	Chairman Chandler - witness Conroy	
3120133 111	•	x sentence from bottom, see that?
5:28:55 PM	Chairman Chandler - witness Conroy	
5120135 111	•	eading (click on link for further comments), see that?
5:29:21 PM	Chairman Chandler - witness Conroy	
	•	ompanies believe that emergency rate increase is necessary, that's
		hat stipulation say, saying ordinary rate case, determination
		mergency is made by Commission?
		- ,

5:30:22 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Sets up filing rate case, determination whether companies credit or
	operations materially damaged Commission determination?
5:30:50 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Companies file rate and Commission not think, companies filed rate case?
5:31:20 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Filed rate case before four years?
5:31:42 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Took petition asking either 30 days can file case or ordinary 30 days before filing case?
5:32:11 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Additional step request or file rate case?
5:32:26 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Just asking clarification before four years ordinary case or ask permission file prior to four years?
5:32:42 PM	Chairman Chandler
	Note: Sacre, Candace Witness is excused.
5:33:06 PM	Atty Crosby KU/LG&E
	Note: Sacre, Candace Eileen Saunders.
5:33:13 PM	Chairman Chandler
	Note: Sacre, Candace Witness is sworn.
5:33:23 PM	Chairman Chandler - witness Conroy
	Note: Sacre, Candace Examination. Name and address?
5:33:40 PM	Atty Crosby KU/LG&E - witness Saunders
	Note: Sacre, Candace Direct Examination. By whom employed, what capacity?
5:33:52 PM	Atty Crosby KU/LG&E - witness Saunders
	Note: Sacre, Candace Cause to be prepared and filed testimony and rebuttal?
5:34:09 PM	Atty Crosby KU/LG&E - witness Saunders
	Note: Sacre, Candace File data request responses?
5:34:14 PM	Atty Crosby KU/LG&E - witness Saunders
	Note: Sacre, Candace Any update to testimony or data requests?
5:34:29 PM	Atty Crosby KU/LG&E - witness Saunders
	Note: Sacre, Candace Description of corrections?
5:35:09 PM	Atty Crosby KU/LG&E - witness Saunders
	Note: Sacre, Candace Adopt prefiled testimony and responses?
5:35:19 PM	Atty Crosby KU/LG&E - witness Saunders
	Note: Sacre, Candace What have available at witness stand?
5:35:45 PM	Chairman Chandler
	Note: Sacre, Candace Questions?
5:36:06 PM	General Counsel Vinsel PSC - witness Saunders
	Note: Sacre, Candace Cross Examination. Response, Staff Seventh Request, Item 2,
	reading, (click on link for further comments), requirement in tariff
	application contain all adults?
5:37:09 PM	General Counsel Vinsel PSC - witness Saunders
	Note: Sacre, Candace Copies of tariffs application for service KU/LG&E current and
	proposed, primarily in first section with application, termination for
	service not in play, fair to say no requirement in tariff for applicant
F. 40.01 DN4	list all adults?
5:40:01 PM	General Counsel Vinsel PSC - witness Saunders
	Note: Sacre, Candace Pretty wide open piece, companies decide certain things not
5:40:27 DM	provided in tariff, does not put a new customer on notice? General Counsel Vinsel PSC - witness Saunders
5:40:37 PM	
	Note: Sacre, Candace Companies have on web site electronic form?

5:40:59 PM	General Counsel Vinsel PSC - witness Saunders
	Note: Sacre, Candace On form lists primary account holder?
5:41:15 PM	General Counsel Vinsel PSC - witness Saunders
	Note: Sacre, Candace Clarify it does not say joint, says authorized party?
5:42:44 PM	General Counsel Vinsel PSC - witness Saunders
	Note: Sacre, Candace In order to pull up pull-down entry, has to click authorized party?
5:43:02 PM	General Counsel Vinsel PSC - witness Saunders
	Note: Sacre, Candace Anything that says what authorized party is?
5:43:23 PM	General Counsel Vinsel PSC - witness Saunders
	Note: Sacre, Candace Again, if I want to open joint account, maybe not understand
	authorized party mean, customer not on notice can establish joint account?
5:44:29 PM	General Counsel Vinsel PSC - witness Saunders
3.44.29 PM	
5:44:52 PM	Note: Sacre, Candace Business office open during COVID? General Counsel Vinsel PSC - witness Saunders
3.44.32 PM	Note: Sacre, Candace When someone comes in, ask joint account or single name?
5:45:27 PM	General Counsel Vinsel PSC - witness Saunders
J. TJ. 27 T I'I	Note: Sacre, Candace What do you call it?
5:45:44 PM	POST-HEARING DATA REQUEST
5. 15. 11 111	Note: Sacre, Candace GENERAL COUNSEL VINSEL PSC - WITNESS SAUNDERS
	Note: Sacre, Candace CUSTOMER FACT SHEET
5:46:06 PM	General Counsel Vinsel PSC - witness Saunders
31 10100 111	Note: Sacre, Candace On-line account, authorized on bill and being joint account two or
	more people jointly accountable?
5:46:58 PM	General Counsel Vinsel PSC - witness Saunders
	Note: Sacre, Candace Again, one spouse service in that name only and wants to add
	spouse, can primary account holder call up and say add X person?
5:47:26 PM	General Counsel Vinsel PSC - witness Saunders
	Note: Sacre, Candace Not require second person be on phone call?
5:47:43 PM	General Counsel Vinsel PSC - witness Saunders
	Note: Sacre, Candace Check with CSRs, not always the case.
5:48:05 PM	General Counsel Vinsel PSC - witness Saunders
	Note: Sacre, Candace Change answer to typically, couple married 30 years, one spouse
	dies, surviving spouse service in my name, at what point KU/LG&E
F-40-10 DM	transfer account and not make new account?
5:49:19 PM	General Counsel Vinsel PSC - witness Saunders
E.EO.12 DM	Note: Sacre, Candace Any formal policy for that or informal? General Counsel Vinsel PSC - witness Saunders
5:50:12 PM	
5:50:40 PM	Note: Sacre, Candace Who making decision? General Counsel Vinsel PSC - witness Saunders
3.30.40 PM	Note: Sacre, Candace Does start with judgment call by CSR?
5:51:56 PM	General Counsel Vinsel PSC - witness Saunders
J.J1.J0 FM	Note: Sacre, Candace Sounds more informal process, while training, no default when
	spouse calls in what I need to do, any documentation of training
	covers scenario or script or fact sheet that CSR know this situation,
	steps I need to take?
5:53:07 PM	POST-HEARING DATA REQUEST
	Note: Sacre, Candace GENERAL COUNSEL VINSEL PSC - WITNESS SAUNDERS
	Note: Sacre, Candace CSR JOINT ACCOUNT SCRIPT/FACT SHEET STEPS TO TAKE WHEN
	CHANGE
5:53:33 PM	Chairman Chandler
	Note: Sacre, Candace Questions?
5:53:39 PM	Vice Chairman Cubbage - witness Saunders
	Note: Sacre, Candace Examination. On application form, language warning that both need
	to be on application in order to ensure continuity of service?

5:54:12 PM	Chairman Chandler	
	Note: Sacre, Candace	Questions?
5:54:17 PM	Atty Crosby KU/LG&E - witness	Saunders
	Note: Sacre, Candace	Redirect Examination. Tariff Sheet 97, second sentence first paragraph, information required?
5:54:41 PM	Atty Crosby KU/LG&E - witness	· · ·
ייוז דד.דכ.כ		Very end of sentence, and any other information company deems
	Note: Sacre, Candace	necessary?
5:54:52 PM	Atty Crosby KU/LG&E - witness	
	Note: Sacre, Candace	Could include other parties at premises?
5:55:10 PM	General Counsel Vinsel PSC	
	Note: Sacre, Candace	Move into evidence PSC Staff Exhibits 7, 8, 9, 10, and 11. (Click on link for further comments.)
5:55:23 PM	Chairman Chandler	,
	Note: Sacre, Candace	Exhibits 7 8 9 10 and 11.
5:55:24 PM	PSC STAFF EXHIBIT 7	
	Note: Sacre, Candace	GENERAL COUNSEL VINSEL PSC - WITNESS CONROY
	Note: Sacre, Candace	01/07/2021 LG&E/KY.COM PRESS RELEASE - LG&E AND KU
	noter sucrey surrages	REQUEST BIDS FOR ENERGY TO CONTINUE TO RELIABLY SERVE
		CUSTOMERS
5:55:25 PM	PSC STAFF EXHIBIT 8	
	Note: Sacre, Candace	GENERAL COUNSEL VINSEL PSC - WITNESS SAUNDERS
	Note: Sacre, Candace	KENTUCKY UTILITIES COMPANY PSC NO. 19, ORIGINAL SHEET NO.
		97
5:56:26 PM	PSC STAFF EXHIBIT 9	
	Note: Sacre, Candace	GENERAL COUNSEL VINSEL PSC - WITNESS SAUNDERS
	Note: Sacre, Candace	KENTUCKY UTILITIES COMPANY PSC NO. 20, ORIGINAL SHEET NO.
		97
5:56:27 PM	PSC STAFF EXHIBIT 10	
	Note: Sacre, Candace	GENERAL COUNSEL VINSEL PSC - WITNESS SAUNDERS
	Note: Sacre, Candace	LOUISVILLE GAS AND ELECTRIC PSC NO. 12 ORIGINAL SHEET NO.
	,	97
5:56:28 PM	PSC STAFF EXHIBIT 11	
	Note: Sacre, Candace	GENERAL COUNSEL VINSEL PSC - WITNESS SAUNDERS
	Note: Sacre, Candace	LOUISVILLE GAS AND ELECTRIC PSC NO. 13 ORIGINAL SHEET NO.
	,	97
5:56:29 PM	Chairman Chandler	
	Note: Sacre, Candace	Questions?
5:56:30 PM	Chairman Chandler	
	Note: Sacre, Candace	Witness is excused.
5:56:40 PM	Chairman Chandler	
	Note: Sacre, Candace	Recess until 6:10.
5:57:22 PM	Session Paused	
6:11:07 PM	Session Resumed	
6:11:20 PM	Chairman Chandler	
	Note: Sacre, Candace	Back on record in Case Nos. 2020-00349 and 2020-00350.
6:11:28 PM	Chairman Chandler	
	Note: Sacre, Candace	Next witness?
6:11:33 PM	Atty Spenard KYSEIA	
000 / / /	Note: Sacre, Candace	Justin R. Barnes.
6:11:44 PM	Chairman Chandler	
V	Note: Sacre, Candace	Witness is sworn.
6:11:58 PM	Chairman Chandler - witness Ba	
3.11.30 TT	Note: Sacre, Candace	Examination. Name and address?
	rioter sacre, carrade	Examination Hame and dualess:

6:12:28 PM	Atty Spenard KYSEIA - witness Ba	
	Note: Sacre, Candace	Direct Examination. Employer and job title?
6:12:38 PM	Atty Spenard KYSEIA - witness Ba	arnes
	Note: Sacre, Candace	On whose behalf appearing?
6:12:48 PM	Atty Spenard KYSEIA - witness Ba	arnes
	Note: Sacre, Candace	Prepare supplemental testimony filed into record?
6:13:00 PM	Atty Spenard KYSEIA - witness Ba	arnes
	Note: Sacre, Candace	Supplemental rebuttal filed into record?
6:13:15 PM	Atty Spenard KYSEIA - witness Ba	arnes
	Note: Sacre, Candace	Responses to requests for information
6:13:25 PM	Atty Spenard KYSEIA	
	Note: Sacre, Candace	Note KYSEIA made filing, errata sheet. (Click on link for further
		comments.)
6:14:07 PM	Atty Spenard KYSEIA - witness Ba	arnes
	Note: Sacre, Candace	Same questions, same answers?
6:14:22 PM	Atty Spenard KYSEIA - witness Ba	arnes
	Note: Sacre, Candace	Adopt and affirm?
6:14:26 PM	Atty Spenard KYSEIA - witness Ba	arnes
	Note: Sacre, Candace	Colleague entered testimony, Inskeep?
6:14:40 PM	Atty Spenard KYSEIA - witness Ba	arnes
	Note: Sacre, Candace	Adopting and affirming Inskeep?
6:14:52 PM	Atty Spenard KYSEIA - witness Ba	arnes
	Note: Sacre, Candace	Identify documents available in front of you?
6:15:43 PM	Chairman Chandler	
	Note: Sacre, Candace	Questions?
6:16:23 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Cross Examination. Page 6, August 5 testimony, reading (click on
		link for further comments), criticism companies approach?
6:17:13 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Your approach is, continue, reading (click on link for further
		comments), single technology neutral methodology, correct would
		apply same avoided capacity rate to every QF might ask?
6:18:42 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Methodology apply to wind, solar, biomass, hydroelectric, waste
		coal, burning tires, topping cycle cogeneration, and/or bottoming
C 10 00 DM	ALL IX I IXIIC 'I B	cycle cogeneration?
6:19:09 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Whether look at existing regulation on rates for purchase or new
		FERC regulation, did not take into account any factors when setting
6:19:47 PM	Atty Kurtz KILIC witness Parnes	rates for capacity purposes?
0.19.47 PM	Atty Kurtz KIUC - witness Barnes Note: Sacre, Candace	State regulation, reading (click on link for further comments), none
	Note. Sacre, Caridace	of factors in single technology avoided capacity rate?
6:21:03 PM	Atty Kurtz KIUC - witness Barnes	of factors in single technology avoided capacity fate:
0.21.05 FM	Note: Sacre, Candace	How ability to dispatch factored into proposal?
6:21:23 PM	Atty Kurtz KIUC - witness Barnes	riow ability to dispatch factored into proposal:
0.21.23 FM	Note: Sacre, Candace	How reliability, terms of contract, duration of obligation, termination
	Note: Sacre, Caridace	requirements factored into avoided capacity rate?
6:21:56 PM	Atty Kurtz KIUC - witness Barnes	requirements factored into avoided capacity face:
0.21.30 111	Note: Sacre, Candace	Terms of contract, duration of obligation, termination requirements,
	Note: Sacre, Caridace	ability to coordinate scheduled outages, none of those factored into
		approach?
6:23:03 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Where in testimony distinguish ten-year agreement, 15-year
		agreement, 20-year agreement as to how relate to price?
		- · · · · · · · · · · · · · · · · · · ·

6:23:58 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Companies proposed different rates for different technology, you proposed same rate for every type?
6:24:41 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Think all technologies have same capacity value?
6:24:47 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Page 19 of August 5 testimony, took capacity cost natural gas combined-cycle power plant and compressed annual capacity costs into June-September on-peak periods to develop rates in Table 3?
6:26:00 PM	Atty Kurtz KIUC - witness Barnes	
C-2C-4E DM	Note: Sacre, Candace	Why testimony page 6 say natural gas combined-cycle costs?
6:26:45 PM	Atty Kurtz KIUC - witness Barnes	Why words say prove natural gas combined sucle when Table 2
	Note: Sacre, Candace	Why words say proxy natural gas combined-cycle when Table 3 numbers use combustion turbine natural gas?
6:27:46 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Why say combined-cycle if use CT?
6:27:59 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Throughout testimony said used combined-cycle proxy, apparently Table 3 used CT as a cost, think costs same?
6:29:28 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Took capacity costs of combustion turbine gas power plant, compressed into 791 on-peak hours June-September, how developed rates on Table 3?
6:30:10 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	If QF produced in winter peak hours, zero capacity credit under proposal?
6:30:38 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Aware KU winter peaking utility?
6:31:03 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Any coincidence your recommendation provide capacity payments at precise time solar facilities expected operate maximum amount?
6:31:20 PM	Atty Spenard KYSEIA	
	Note: Sacre, Candace	Cut off witness entire answer.
6:31:38 PM	Chairman Chandler	Aller I e C 2
6.21.E1 DM	Note: Sacre, Candace	Additional portion of answer?
6:31:51 PM	Atty Kurtz KIUC - witness Barnes Note: Sacre, Candace	Coincidence your proposed capacity rate be maximum amount
	Note. Sacre, Caridace	possible to solar QF because exactly when generating electricity
		during summer during day?
6:33:48 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	791 hours represent nine percent hours per year?
6:34:03 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Generation during other 91 percent of hours get zero capacity credit?
6:34:25 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	KU winter peaking facility?
6:34:46 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Have copy of that?
6:34:54 PM	Atty Kurtz KIUC - witness Barnes	Colordata have much color OF course the comments using 2020 meta of
	Note: Sacre, Candace	Calculate how much solar QF capacity payments using 2026 rate of \$146.28 mWh, \$185 million capacity payment to 80 mW solar QF
		operated 791 hours summer peak period?
6:36:12 PM	Atty Kurtz KIUC - witness Barnes	- bearing hand have
	Note: Sacre, Candace	Capacity only, solar QF energy revenue?
	·	

6:36:23 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Year round no matter when generated?
6:37:02 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Pages 10 and 17, unusual language, reading (click on link for further
		comments), think under federal/state law Commission set just and
		reasonable rate for QF or just and reasonable rates for consumers?
6:39:00 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Aware under federal/state law rates for purchases from QFs shall be
		just and reasonable, entitled to nondiscriminatory rate, not a just
		and reasonable rate, think same thing?
6:39:52 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	CT available 24/7/365?
6:40:29 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Higher availability factor, ability dispatch more than solar which not
		dispatch at all?
6:41:24 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Fair for consumers pay for intermittent capacity same amount pay
		for dispatchable thermal capacity available year round?
6:42:21 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Revenues on page 19, Table 3, revenues consumers pay capacity
		only plus energy?
6:43:08 PM	Atty Kurtz KIUC - witness Barnes	
	Note: Sacre, Candace	Available year round and is dispatchable?
6:43:26 PM	Chairman Chandler	
	Note: Sacre, Candace	Questions?
6:43:58 PM	Atty Riggs KU/LG&E - witness Bar	nes
	Note: Sacre, Candace	Cross Examination. Qualifications, graduated University of
	,	Oklahoma?
6:44:36 PM	Atty Riggs KU/LG&E - witness Bar	nes
	Note: Sacre, Candace	Looked at degree on Michigan Tech University website, part of
		humanities and social sciences grad school program?
6:44:48 PM	Atty Riggs KU/LG&E - witness Bar	rnes
	Note: Sacre, Candace	Part of humanities and social sciences program?
6:45:04 PM	Atty Riggs KU/LG&E - witness Bar	rnes
	Note: Sacre, Candace	Eight years of experience?
6:45:42 PM	Atty Riggs KU/LG&E - witness Bar	rnes
	Note: Sacre, Candace	Fair to say 12 years work experience worked on renewable side?
6:45:54 PM	Atty Riggs KU/LG&E - witness Bar	nes
	Note: Sacre, Candace	Current employment EQ Research LLC and Keyes Fox and Wiedman
		LLP, a law firm, relationship between two entities?
6:46:49 PM	Atty Riggs KU/LG&E - witness Bar	rnes
	Note: Sacre, Candace	Currently employee of law firm?
6:47:05 PM	Atty Riggs KU/LG&E - witness Bar	nes
	Note: Sacre, Candace	Understand EQ Research owned by some lawyers from firm?
6:47:23 PM	Atty Riggs KU/LG&E - witness Bar	- · · · · · · · · · · · · · · · · · · ·
	Note: Sacre, Candace	Relationship with EQ employer/employee?
6:47:34 PM	Atty Riggs KU/LG&E - witness Bar	
	Note: Sacre, Candace	Not trained as engineer?
6:47:39 PM	Atty Riggs KU/LG&E - witness Bar	
	Note: Sacre, Candace	Given experience, never worked as generation system planner,
		transmission or distribution planning engineer?
6:48:04 PM	Atty Riggs KU/LG&E - witness Bar	,
	Note: Sacre, Candace	Not trained in economics?

C 40 20 DM	AU D' 1/11/1 COE '1 D
6:48:29 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Response to Data Request Three, supplemental, never performed
C 40 00 DM	imbedded COS?
6:49:08 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Understand never performed imbedded COS?
6:49:32 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Never performed marginal COS?
6:49:51 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Never performed avoided COS?
6:50:15 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Fair to say not have professional capacity to perform types of
	studies?
6:51:02 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Never demonstrated ability to perform any of these studies?
6:51:19 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace To perform a study?
6:51:28 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Performance of a study?
6:51:48 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Response questions Kurtz asked, interpretation of 2018 IRP,
	understood now accept companies at word next unit IRP not say
	install combined cycle turbine?
6:52:44 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Nowhere in testimony asserted single-cycle technology turbine
6 E4 0E DM	provide support any portion of IRP?
6:54:05 PM	Atty Riggs KU/LG&E - witness Barnes
C.E4.00 DM	Note: Sacre, Candace Now accept?
6:54:08 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Accept additions companies generation followed Solar Share program and Solar PPA?
6:54:36 PM	Atty Riggs KU/LG&E - witness Barnes
0.54.50 FM	Note: Sacre, Candace Without energy storage, rooftop solar installations not produce
	energy in dark?
6:54:56 PM	Atty Riggs KU/LG&E - witness Barnes
0.000	Note: Sacre, Candace Rooftop solar facilities provide energy to grid KU peak during
	January 6 pm?
6:55:15 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Combined cycle generator provide energy at 6 am?
6:55:29 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Provide at peak at 9 pm?
6:55:50 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Accept still dark at 9 pm in January?
6:56:00 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Combined cycle could provide at 6 pm in January?
6:56:12 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace KU winter peaking utility?
6:56:34 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Agree system peak occurs 6 pm or 9 pm in January?
6:56:51 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Assume not contending combined cycle combustion turbine not
	operate 6 pm January?
6:57:12 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Operationally, 6 pm or 9 pm solar technologically neutral?

C 57 20 DM	AU D: 1/11/1 COE :1 D	
6:57:30 PM	Atty Riggs KU/LG&E - witness Ba	
	Note: Sacre, Candace	Not contending operation at 6 am or 9 pm in January rooftop solar
6 F0 04 PM	A., B: 1/1// 00 5 ''	facility technologically neutral any particular hour?
6:58:01 PM	Atty Riggs KU/LG&E - witness Ba	
	Note: Sacre, Candace	Agree not technologically neutral operational standpoint that time of day that month?
6:58:38 PM	Atty Riggs KU/LG&E - witness Ba	irnes
	Note: Sacre, Candace	Technologically neutral, at those particular times are not?
6:59:10 PM	Atty Riggs KU/LG&E - witness Ba	rnes
	Note: Sacre, Candace	Not dispute KU needs capacity meet need at 6 pm or 9 pm in January?
7:00:04 PM	Atty Riggs KU/LG&E - witness Ba	•
	Note: Sacre, Candace	Distributed Barnes Cross Exhibit 1, have it?
7:02:02 PM	Atty Riggs KU/LG&E - witness Ba	·
	Note: Sacre, Candace	Three different scenarios, questions, fair enough?
7:02:23 PM	Atty Riggs KU/LG&E - witness Ba	
7102123 111	Note: Sacre, Candace	Scenario 1 assumes no changes environmental regulations
	Note: Sacre, Canadee	necessitate retirements Mill Creek 2 and Brown 3 in 2028, not need
		additional capacity until 2034, assumption, heard testimony?
7:03:05 PM	Atty Riggs KU/LG&E - witness Ba	
7.03.03 111	Note: Sacre, Candace	Scenario 1, capacity cost avoid in 2022?
7:04:19 PM	Atty Riggs KU/LG&E - witness Ba	
7.04.15114	Note: Sacre, Candace	Companies not need capacity, capacity to serve load, agree cannot
	Note: Sacre, Candace	avoid capacity by purchasing energy 2022 under scenario?
7:05:35 PM	Atty Riggs KU/LG&E - witness Ba	
7.05.55 114	Note: Sacre, Candace	Testimony O&M fixed cost and not variable?
7:05:51 PM	Atty Riggs KU/LG&E - witness Ba	•
7.03.31 FM	Note: Sacre, Candace	What fixed operational cost?
7:07:08 PM	Atty Riggs KU/LG&E - witness Ba	•
7.07.00 PM		Aware of practice in industry employees paid if unit potentially run?
7:07:44 PM	Note: Sacre, Candace	
7:07:44 PM	Atty Riggs KU/LG&E - witness Ba	
	Note: Sacre, Candace	Calculate avoided costs Scenario 1 20-year QF firm contract begins 2022, first necessary calculate present value avoided costs occur through 2034 and 2041?
7:09:36 PM	Atty Riggs KU/LG&E - witness Ba	
	Note: Sacre, Candace	Scenario 2, shows capacity not needed until 2028, see that?
7:09:58 PM	Atty Riggs KU/LG&E - witness Ba	·
, , , , , , , , , , , , , , , , , , , ,	Note: Sacre, Candace	Were to ask same questions, answers be the same, under scenario,
	Hotel basis, bandade	capacity incurred 2028 to 2041 again discount and levelize cost over
		life of contract?
7:10:39 PM	Atty Riggs KU/LG&E - witness Ba	rnes
	Note: Sacre, Candace	Position companies currently have insufficient capacity meet
		expected peak demand?
7:11:16 PM	Atty Riggs KU/LG&E - witness Ba	·
,,,	Note: Sacre, Candace	Today, currently companies sufficient capacity meet peak demand?
7:11:52 PM	Atty Riggs KU/LG&E - witness Ba	, , , , , , , , , , , , , , , , , , , ,
7111132 111	Note: Sacre, Candace	Base cost on current CONE from PJM?
7:12:40 PM	Atty Riggs KU/LG&E - witness Ba	
/ : 14: TU I'I'I	Note: Sacre, Candace	Determining net CONE, PJM discount cost generation capacity from
	Note. Jacie, Calluace	2034 to 2021?
7:13:02 PM	Atty Riggs KU/LG&E - witness Ba	
, . I J . U Z T I 'I	Note: Sacre, Candace	Same question net CONE, PJM discount cost generation capacity
	Note: Jacie, Calluace	2028 to 2021?

7.12.22 DM	Atta, Diago VII/I CO E with oca Powner
7:13:22 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Present value calculations, did not present present value calculations and not consider intervening years when need no additional
	capacity?
7:14:41 PM	Atty Riggs KU/LG&E - witness Barnes
7111111111	Note: Sacre, Candace Agree need to do present value calculation?
7:15:24 PM	Atty Riggs KU/LG&E - witness Barnes
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	Note: Sacre, Candace Sound practice not do present value calculation when calculating
	capacity payments long term?
7:15:41 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Avoided transmission and distribution, recommended Commission
	use imbedded unit cost approach in avoided
	transmission/distribution rates?
7:16:13 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Familiar with term imbedded cost?
7:16:22 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Includes revenue requirements?
7:16:40 PM	Atty Riggs KU/LG&E - witness Barnes
7.46.50.004	Note: Sacre, Candace Also familiar avoided cost?
7:16:50 PM	Atty Riggs KU/LG&E - witness Barnes
7.17.02 DM	Note: Sacre, Candace Familiar with Commission power production and co-generation?
7:17:02 PM	Atty Riggs KU/LG&E - witness Barnes
7.17.20 DM	Note: Sacre, Candace Familiar definition of avoided costs read during hearing?
7:17:29 PM	Atty Riggs KU/LG&E - witness Barnes Note: Sacre, Candace Definitions avoided costs same as imbedded costs?
7:18:48 PM	Atty Riggs KU/LG&E - witness Barnes
7.10. 1 0 FM	Note: Sacre, Candace Agree definitions imbedded costs and avoided costs not the same?
7:19:17 PM	Atty Riggs KU/LG&E - witness Barnes
7.13.17 11.1	Note: Sacre, Candace Agree definitions of avoided costs and imbedded costs not the
	same?
7:19:37 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Performed empirical costs comparing imbedded costs to avoided
	costs electric utilities?
7:21:00 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Performed those kinds of studies, if have, produce in post-hearing
	data response, willing do that?
7:21:10 PM	POST-HEARING DATA REQUEST
	Note: Sacre, Candace ATTY RIGGS KU/LG&E - WITNESS BARNES
	Note: Sacre, Candace STUDIES PERFORMED COMPARING IMBEDDED COSTS TO AVOIDED COSTS
7:21:30 PM	Atty Riggs KU/LG&E - witness Barnes
7.21.30 FM	Note: Sacre, Candace Aware any studies or surveys compared avoided transmission costs
	to imbedded transmission costs to a panel of utilities?
7:22:45 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Aware of any such studies?
7:22:59 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Aware of studies or surveys compare avoided capacity distribution
	costs to imbedded transmission costs?
7:23:31 PM	Atty Riggs KU/LG&E - witness Barnes
	Note: Sacre, Candace Agree difference marginal cost and imbedded cost imbedded fixed
	cost measures costs all plant installed and reflects cost of total
7,22,56 014	demand not incremental demand?
7:23:56 PM	Atty Riggs KU/LG&E - witness Barnes Note: Sacro Candaco Agroo marginal cost represents marginal or incremental cost?
	Note: Sacre, Candace Agree marginal cost represents marginal or incremental cost?

7:24:16 PM	Atty Riggs KU/LG&E - witness Ba	rnec
7.24.10 114	Note: Sacre, Candace	Under what situations marginal costs lower than imbedded costs?
7:25:13 PM	Atty Riggs KU/LG&E	onder what situations marginal costs lower than imbeduce costs:
7.23.13 111	Note: Sacre, Candace	Address Chair on scheduling issue. (Click on link for further comments.)
7:25:34 PM	Atty Riggs KU/LG&E - witness Ba	•
	Note: Sacre, Candace	Fitzgerald scheduling concerns, one quick question, agree possible for avoided costs lower than imbedded costs, yes or no?
7:26:37 PM	Atty Fitzgerald Joint Intervenors Note: Sacre, Candace	Owen excused? (Click on link for further comments.)
7:27:07 PM	Chairman Chandler	· · · · · · · · · · · · · · · · · · ·
	Note: Sacre, Candace	Questions for Owen, objections? (Click on link for further comments.)
7:27:57 PM	Chairman Chandler	
	Note: Sacre, Candace	No objection, witness Owen excused. (Click on link for further comments.)
7:28:22 PM	Chairman Chandler	
	Note: Sacre, Candace	Mr. Riggs, may proceed. (Click on link for further comments.)
7:28:52 PM	Chairman Chandler	
7 20 05 014	Note: Sacre, Candace	Questions?
7:29:05 PM	Atty Spenard KYSEIA - witness B	
	Note: Sacre, Candace	Redirect Examination. Asking opinion, understanding per KRS that PSC regulations include specific definition avoided costs with regard to QFs?
7:29:59 PM	Atty Spenard KYSEIA - witness B	arnes
	Note: Sacre, Candace	Testimony not suggest Commission substitute imbedded costs for avoided costs?
		avoided costs:
7:30:32 PM	Atty Spenard KYSEIA - witness B	
7:30:32 PM	Atty Spenard KYSEIA - witness Bandace	
7:30:32 PM 7:31:09 PM		Net metering statutes, definitions for avoided costs?
7:31:09 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace	arnes
	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler	Arnes Net metering statutes, definitions for avoided costs? Questions?
7:31:09 PM 7:31:17 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace	Net metering statutes, definitions for avoided costs?
7:31:09 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E	Arnes Net metering statutes, definitions for avoided costs? Questions? Witness is excused.
7:31:09 PM 7:31:17 PM 7:31:42 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace	Arnes Net metering statutes, definitions for avoided costs? Questions?
7:31:09 PM 7:31:17 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace Chairman Chandler	Arnes Net metering statutes, definitions for avoided costs? Questions? Witness is excused. Move admission KU/LG&E Barnes Cross Exhibit 1.
7:31:09 PM 7:31:17 PM 7:31:42 PM 7:31:49 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace	Arnes Net metering statutes, definitions for avoided costs? Questions? Witness is excused. Move admission KU/LG&E Barnes Cross Exhibit 1. Objection? Marked.
7:31:09 PM 7:31:17 PM 7:31:42 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace KU/LG&E BARNES CROSS EXHIB	Net metering statutes, definitions for avoided costs? Questions? Witness is excused. Move admission KU/LG&E Barnes Cross Exhibit 1. Objection? Marked.
7:31:09 PM 7:31:17 PM 7:31:42 PM 7:31:49 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace	Arnes Net metering statutes, definitions for avoided costs? Questions? Witness is excused. Move admission KU/LG&E Barnes Cross Exhibit 1. Objection? Marked.
7:31:09 PM 7:31:17 PM 7:31:42 PM 7:31:49 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace KU/LG&E BARNES CROSS EXHIBITATION	Arnes Net metering statutes, definitions for avoided costs? Questions? Witness is excused. Move admission KU/LG&E Barnes Cross Exhibit 1. Objection? Marked. IT 1 ATTY RIGGS KU/LG&E - WITNESS BARNES SCENARIOS 1, 2, AND 3 NEED FOR ADDITIONAL GENERATION
7:31:09 PM 7:31:17 PM 7:31:42 PM 7:31:49 PM 7:31:51 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace KU/LG&E BARNES CROSS EXHIB: Note: Sacre, Candace Note: Sacre, Candace	Arnes Net metering statutes, definitions for avoided costs? Questions? Witness is excused. Move admission KU/LG&E Barnes Cross Exhibit 1. Objection? Marked. IT 1 ATTY RIGGS KU/LG&E - WITNESS BARNES SCENARIOS 1, 2, AND 3 NEED FOR ADDITIONAL GENERATION
7:31:09 PM 7:31:17 PM 7:31:42 PM 7:31:49 PM 7:31:51 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace KU/LG&E BARNES CROSS EXHIBITATION NOTE: Sacre, Candace	Net metering statutes, definitions for avoided costs? Questions? Witness is excused. Move admission KU/LG&E Barnes Cross Exhibit 1. Objection? Marked. IT 1 ATTY RIGGS KU/LG&E - WITNESS BARNES SCENARIOS 1, 2, AND 3 NEED FOR ADDITIONAL GENERATION CAPACITY
7:31:09 PM 7:31:17 PM 7:31:42 PM 7:31:49 PM 7:31:51 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace KU/LG&E BARNES CROSS EXHIBITATION Note: Sacre, Candace Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Note: Sacre, Candace	Net metering statutes, definitions for avoided costs? Questions? Witness is excused. Move admission KU/LG&E Barnes Cross Exhibit 1. Objection? Marked. IT 1 ATTY RIGGS KU/LG&E - WITNESS BARNES SCENARIOS 1, 2, AND 3 NEED FOR ADDITIONAL GENERATION CAPACITY
7:31:09 PM 7:31:17 PM 7:31:42 PM 7:31:49 PM 7:31:51 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace KU/LG&E BARNES CROSS EXHIB: Note: Sacre, Candace Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Note: Sacre, Candace Atty Fitzgerald Joint Intervenors	Net metering statutes, definitions for avoided costs? Questions? Witness is excused. Move admission KU/LG&E Barnes Cross Exhibit 1. Objection? Marked. IT 1 ATTY RIGGS KU/LG&E - WITNESS BARNES SCENARIOS 1, 2, AND 3 NEED FOR ADDITIONAL GENERATION CAPACITY Witness?
7:31:09 PM 7:31:17 PM 7:31:42 PM 7:31:49 PM 7:31:51 PM 7:32:21 PM 7:32:28 PM 7:32:37 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace KU/LG&E BARNES CROSS EXHIBIT Note: Sacre, Candace Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace	Net metering statutes, definitions for avoided costs? Questions? Witness is excused. Move admission KU/LG&E Barnes Cross Exhibit 1. Objection? Marked. IT 1 ATTY RIGGS KU/LG&E - WITNESS BARNES SCENARIOS 1, 2, AND 3 NEED FOR ADDITIONAL GENERATION CAPACITY Witness?
7:31:09 PM 7:31:17 PM 7:31:42 PM 7:31:49 PM 7:31:51 PM 7:32:21 PM 7:32:28 PM 7:32:37 PM 7:33:13 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace KU/LG&E BARNES CROSS EXHIB: Note: Sacre, Candace Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Session Paused	Net metering statutes, definitions for avoided costs? Questions? Witness is excused. Move admission KU/LG&E Barnes Cross Exhibit 1. Objection? Marked. IT 1 ATTY RIGGS KU/LG&E - WITNESS BARNES SCENARIOS 1, 2, AND 3 NEED FOR ADDITIONAL GENERATION CAPACITY Witness? Karl Rabago.
7:31:09 PM 7:31:17 PM 7:31:42 PM 7:31:49 PM 7:31:51 PM 7:32:21 PM 7:32:28 PM 7:32:37 PM 7:33:13 PM 7:46:44 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace KU/LG&E BARNES CROSS EXHIB: Note: Sacre, Candace Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Session Paused Session Resumed	Net metering statutes, definitions for avoided costs? Questions? Witness is excused. Move admission KU/LG&E Barnes Cross Exhibit 1. Objection? Marked. IT 1 ATTY RIGGS KU/LG&E - WITNESS BARNES SCENARIOS 1, 2, AND 3 NEED FOR ADDITIONAL GENERATION CAPACITY Witness? Karl Rabago.
7:31:09 PM 7:31:17 PM 7:31:42 PM 7:31:49 PM 7:31:51 PM 7:32:21 PM 7:32:28 PM 7:32:37 PM 7:33:13 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace KU/LG&E BARNES CROSS EXHIBIT Note: Sacre, Candace Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Session Paused Session Resumed Chairman Chandler	Net metering statutes, definitions for avoided costs? Questions? Witness is excused. Move admission KU/LG&E Barnes Cross Exhibit 1. Objection? Marked. IT 1 ATTY RIGGS KU/LG&E - WITNESS BARNES SCENARIOS 1, 2, AND 3 NEED FOR ADDITIONAL GENERATION CAPACITY Witness? Karl Rabago. Break until 7:45.
7:31:09 PM 7:31:17 PM 7:31:42 PM 7:31:49 PM 7:31:51 PM 7:32:21 PM 7:32:28 PM 7:32:37 PM 7:33:13 PM 7:46:44 PM 7:47:00 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace KU/LG&E BARNES CROSS EXHIB: Note: Sacre, Candace Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Session Paused Session Resumed Chairman Chandler Note: Sacre, Candace	Net metering statutes, definitions for avoided costs? Questions? Witness is excused. Move admission KU/LG&E Barnes Cross Exhibit 1. Objection? Marked. IT 1 ATTY RIGGS KU/LG&E - WITNESS BARNES SCENARIOS 1, 2, AND 3 NEED FOR ADDITIONAL GENERATION CAPACITY Witness? Karl Rabago.
7:31:09 PM 7:31:17 PM 7:31:42 PM 7:31:49 PM 7:31:51 PM 7:32:21 PM 7:32:28 PM 7:32:37 PM 7:33:13 PM 7:46:44 PM	Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Riggs KU/LG&E Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace KU/LG&E BARNES CROSS EXHIBIT Note: Sacre, Candace Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Session Paused Session Resumed Chairman Chandler	Net metering statutes, definitions for avoided costs? Questions? Witness is excused. Move admission KU/LG&E Barnes Cross Exhibit 1. Objection? Marked. IT 1 ATTY RIGGS KU/LG&E - WITNESS BARNES SCENARIOS 1, 2, AND 3 NEED FOR ADDITIONAL GENERATION CAPACITY Witness? Karl Rabago. Break until 7:45.

7:47:16 PM	Atty Fitzgerald Joint Intervenors
	Note: Sacre, Candace Karl Rabago.
7:47:30 PM	Chairman Chandler
	Note: Sacre, Candace Witness is sworn.
7:47:43 PM	Chairman Chandler - witness Rabago
	Note: Sacre, Candace Examination. Name and address?
7:48:02 PM	Atty Fitzgerald Joint Intervenors - witness Rabago
	Note: Sacre, Candace Direct Examination. Cause to be entered testimony and rebuttal and
	responses?
7:48:15 PM	Atty Fitzgerald Joint Intervenors - witness Rabago
	Note: Sacre, Candace Affirm answers and adopt them?
7:48:27 PM	Atty Fitzgerald Joint Intervenors - witness Rabago
	Note: Sacre, Candace Same questions, same answers?
7:48:44 PM	Atty Fitzgerald Joint Intervenors - witness Rabago
	Note: Sacre, Candace Changes or corrections?
7:48:55 PM	Atty Fitzgerald Joint Intervenors - witness Rabago
	Note: Sacre, Candace What materials before you?
7:49:25 PM	Chairman Chandler
	Note: Sacre, Candace Questions?
7:49:37 PM	Asst Atty General Horne - witness Rabago
	Note: Sacre, Candace Cross Examination. Fair to say involved net metering issues across
	country?
7:50:15 PM	Asst Atty General Horne - witness Rabago
	Note: Sacre, Candace How long?
7:50:55 PM	Asst Atty General Horne - witness Rabago
	Note: Sacre, Candace Try to keep abreast of issues?
7:51:07 PM	Asst Atty General Horne - witness Rabago
	Note: Sacre, Candace Appear involved issues in CA?
7:51:17 PM	Asst Atty General Horne - witness Rabago
	Note: Sacre, Candace On resume, Chairman of Board Center for Resource Solution 1997 to
7.F1.20 DM	present?
7:51:28 PM	Asst Atty General Horne - witness Rabago
7.E1.46 DM	Note: Sacre, Candace Location based in Presidio, California?
7:51:46 PM	Asst Atty General Horne - witness Rabago Note: Sacre, Candace CA on forefront on solar and net metering issues?
7:52:14 PM	Note: Sacre, Candace CA on forefront on solar and net metering issues? Asst Atty General Horne - witness Rabago
7.32.1 4 PM	Note: Sacre, Candace Lot of sunshine?
7:52:24 PM	Asst Atty General Horne - witness Rabago
7.JZ.Z T FIN	Note: Sacre, Candace More than Kentucky?
7:52:31 PM	Asst Atty General Horne - witness Rabago
7.52.51 114	Note: Sacre, Candace Solar and net metering big issue in CA?
7:52:43 PM	Asst Atty General Horne - witness Rabago
7.52.75 114	Note: Sacre, Candace In opinion, CA still on forefront of solar and net metering?
7:52:59 PM	Asst Atty General Horne - witness Rabago
7.52.55 114	Note: Sacre, Candace Involved in legislation in CA?
7:53:29 PM	Asst Atty General Horne - witness Rabago
7.55.25 111	Note: Sacre, Candace Do you follow legislation in CA?
7:53:49 PM	Asst Atty General Horne - witness Rabago
7.55. 15 111	Note: Sacre, Candace Know Asssemblywoman Lorena Gonzalez?
7:54:06 PM	Asst Atty General Horne - witness Rabago
7.5 1.00 TPI	Note: Sacre, Candace Chair of Appropriations Committee, Assembly Bill 1139, Net Energy
	Metering, familiar?
7:54:29 PM	Asst Atty General Horne - witness Rabago
	Note: Sacre, Candace Addresses payment to utilities rooftop solar?

Note: Sacre, Candace Note: Sac	7:54:48 PM	Asst Atty General Horne - witness	s Rabago
Chairman Chandler Note: Sacre, Candace Note: Sacre, Candace Viscosians PSC - witness Rabago Note: Sacre, Candace N	7.6	•	_
7:55:33 PM General Counsel Vinsel PSC - witness Rabago Note: Sacre, Candace Note: Sacre, Cand	7:55:06 PM	· · · · · · · · · · · · · · · · · · ·	, ,
Note: Sacre, Candace Cross Examination. Supplemental, cited to and used information regarding Minnesota Value of Solar Methodology? 7:56:49 PM General Counsel Vinsel PSC - witness Rabago Note: Sacre, Candace State find Minnesota Solar Law and Methodology?		Note: Sacre, Candace	Questions?
regarding Minnesota Value of Solar Methodology? 7:56:03 PM General Counsel Vinsel PSC - witness Rabago Note: Sacre, Candace Note: Sacr	7:55:33 PM	General Counsel Vinsel PSC - witr	ness Rabago
7:56:03 PM		Note: Sacre, Candace	Cross Examination. Supplemental, cited to and used information
Note: Sacre, Candace and Methodology? 7:56:49 PM Secret Counsel Vinsel PSC - witness Rabago Note: Sacre, Candace approach reasonable, expand upon that? 7:59:38 PM General Counsel Vinsel PSC - witness Rabago Note: Sacre, Candace upon that? 8:00:22 PM Secret Counsel Vinsel PSC - witness Rabago Note: Sacre, Candace utilities working with various agencies update methodologies, correct utilities subject Minnesota jurisdiction required file spreadsheets and submit valued solar calculation annually? 8:00:22 PM Secret Counsel Vinsel PSC - witness Rabago Note: Sacre, Candace			regarding Minnesota Value of Solar Methodology?
and Methodology? 7:56:49 PM General Counsel Vinsel PSC - withness Rabago Note: Sacre, Candace Note: Sacre, Candac	7:56:03 PM		•
7:56:49 PM Note: Sacre, Candace Note: Sacre, Candac		Note: Sacre, Candace	· · · · · · · · · · · · · · · · · · ·
Note: Sacre, Candace Stated find Minnesota Solar Law and Methodology and overall approach reasonable, expand upon that? 7:59:38 PM	7 56 40 014	0 10 115 1800 11	
approach reasonable, expand upon that? Note: Sacre, Candace Note: Sacre	7:56:49 PM		•
7:59:38 PM Note: Sacre, Candace Note: Sacre, Candac		Note: Sacre, Candace	
Note: Sacre, Candace correct utilities subject Minnesota jurisdiction required file spreadsheets and submit valued solar calculation annually?	7.50.38 DM	General Councel Vincel PSC - witr	
Subject Minnesotra jurisdiction required file spreadsheets and submit valued solar calculation annually? 8:00:22 PM Secre, Candace Note: Sacre, Candace Response Staff Fourth Request to Joint Intervenors, asked familiarity Xcel Energy value of solar filings, correct? 8:00:41 PM Secre, Candace Note: Sacre, Candace Note: Sa	7.55.50 114		
Spreadsheets and submit valued solar calculation annually? 8:00:22 PM General Counsel Vinsel PSC - witherses Rabago Note: Sacre, Candace Response Staff Fourth Request to Joint Intervenors, asked familiarity Xcel Energy value of solar fillings, correct? 8:00:41 PM General Counsel Vinsel PSC - witherses Rabago Note: Sacre, Candace As post-hearing data request, provide copy Xcel Energy Sept 2020 value of solar calculation spreadsheets and compliance filling associated with spreadsheets. 8:01:04 PM POST-HEARING DATA REQUEST Note: Sacre, Candace Note:		Note: Sacre, Canadee	
Seneral Counsel Vinsel PSC - witness Rabago Note: Sacre, Candace Response Staff Fourth Request to Joint Intervenors, asked familiarity Xcel Energy value of solar filings, correct?			
Xcel Energy value of solar filings, correct? 8:00:41 PM Note: Sacre, Candace Note: Sacre, Candace 8:01:04 PM POST-HEARING DATA REQUEST Note: Sacre, Candace Note: Sacre, Candac	8:00:22 PM	General Counsel Vinsel PSC - witr	·
Seneral Counsel Vinsel PSC - witness Rabago Note: Sacre, Candace		Note: Sacre, Candace	Response Staff Fourth Request to Joint Intervenors, asked familiarity
Note: Sacre, Candace value of solar calculation spreadsheets and compliance filing associated with spreadsheets. 8:01:04 PM POST-HEARING DATA REQUEST Note: Sacre, Candace Note: Sacre, Candace Note: Sacre, Candace Sensor, Candace Note: Sacre, Candace Note: Sacr			
Substitution Subs	8:00:41 PM		•
Scotic process of the property of the property of the period of the pe		Note: Sacre, Candace	
B:01:04 PM			· · · · · · · · · · · · · · · · · · ·
Note: Sacre, Candace Note: Sac	Q:01:04 DM	POST-HEADING DATA PEOLIEST	associated with spreadsneets.
Note: Sacre, Candace SPEADSHEETS AND COMPLIANCE 8:01:30 PM Chairman Chandler Note: Sacre, Candace Questions? 8:01:40 PM Chairman Chandler - witness Rabago Note: Sacre, Candace Examination. Second case net metering successor rates, first Ky Power, expected rate case next couple of years, this case stay-out four years, four years before rates expected, PURPA, other states that had successor rates not use one-to-one kWh netting, time period in which expect/require/demand inputs into cost calculations updated or amended? 8:07:36 PM Chairman Chandler Note: Sacre, Candace Redirect? 8:08:28 PM Chairman Chandler Note: Sacre, Candace Questions? 8:09:04 PM Chairman Chandler Note: Sacre, Candace Witness is excused. 8:09:12 PM Chairman Chandler Note: Sacre, Candace Move to introduce exhibit? 8:10:08 PM Chairman Chandler Note: Sacre, Candace Objection? 8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace Note: Sacre,	0.01.04 FM	<u> </u>	GENERAL COLINSEL VINSEL PSC - WITNESS RARAGO
SPREADSHEETS AND COMPLIANCE 8:01:30 PM		•	
Note: Sacre, Candace Questions? Chairman Chandler - witness Rabago Note: Sacre, Candace Examination. Second case net metering successor rates, first Ky Power, expected rate case next couple of years, this case stay-out four years, four years before rates expected, PURPA, other states that had successor rates not use one-to-one kWh netting, time period in which expect/require/demand inputs into cost calculations updated or amended? 8:07:36 PM Chairman Chandler Note: Sacre, Candace Redirect? 8:08:28 PM Chairman Chandler Note: Sacre, Candace Questions? 8:09:04 PM Chairman Chandler Note: Sacre, Candace Witness is excused. 8:09:12 PM Chairman Chandler Note: Sacre, Candace Move to introduce exhibit? 8:09:35 PM Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Move Joint Intervenors 2, PPL press release. 8:10:08 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace ATTY FITZGERALD JOINT INTERVENORS - WITNESS CONROY Note: Sacre, Candace PPL NEWS RELEASE INTERNATIONAL MAGAZINE NAMES LG&E AND KU AMONG "TOP 20" U.S. UTILITIES 8:10:24 PM Chairman Chandler		Hotel Sacrey Carrage	
Second Chairman Chandler - witness Rabago Note: Sacre, Candace Examination. Second case net metering successor rates, first Ky Power, expected rate case next couple of years, this case stay-out four years, four years before rates expected, PURPA, other states that had successor rates not use one-to-one kWh netting, time period in which expect/require/demand inputs into cost calculations updated or amended? Note: Sacre, Candace Redirect?	8:01:30 PM	Chairman Chandler	
Note: Sacre, Candace Redirect? Second case net metering successor rates, first Ky Power, expected rate case next couple of years, this case stay-out four years, four years before rates expected, PURPA, other states that had successor rates not use one-to-one kWh netting, time period in which expect/require/demand inputs into cost calculations updated or amended? Second Case net metering successor rates, first Ky Power, expected rate case next couple of years, this case stay-out four years before rates expected, PURPA, other states that had successor rates not use one-to-one kWh netting, time period in which expect/require/demand inputs into cost calculations updated or amended? Second Case net metering successor rates, first Ky Power, expected rate case next couple of years, this case stay-out four years before rates expected, PURPA, other states that had successor rates not use one-to-one kWh netting that had successor rates not use one-to-one kWh netting that had successor rates not use one-to-one kWh netting that had successor rates not use one-to-one kWh netting that had successor rates not use one-to-one kWh netting that had successor rates not use one-to-one kWh netting that had successor rates not use one-to-one kWh netting that had successor rates not use one-to-one kWh netting that had successor rates not use one-to-one kWh netting that had successor rates not use one-to-one kWh netting that had successor rates not use one-to-one kWh netting that had successor rates not use one-to-one kWh netting that had successor rates not use one-to-one kWh netting that had successor rates not use one-to-one kWh netting time period in which expect/require/demand inputs into cost calculations updated or amended? Secondary demander Note: Sacre, Candace		Note: Sacre, Candace	Questions?
Power, expected rate case next couple of years, this case stay-out four years, four years before rates expected, PURPA, other states that had successor rates not use one-to-one kWh netting, time period in which expect/require/demand inputs into cost calculations updated or amended? 8:07:36 PM	8:01:40 PM	Chairman Chandler - witness Rab	ago
four years, four years before rates expected, PURPA, other states that had successor rates not use one-to-one kWh netting, time period in which expect/require/demand inputs into cost calculations updated or amended? 8:07:36 PM		Note: Sacre, Candace	
that had successor rates not use one-to-one kWh netting, time period in which expect/require/demand inputs into cost calculations updated or amended? 8:07:36 PM Chairman Chandler Note: Sacre, Candace Redirect? 8:08:28 PM Chairman Chandler Note: Sacre, Candace Questions? 8:09:04 PM Chairman Chandler Note: Sacre, Candace Witness is excused. 8:09:12 PM Chairman Chandler Note: Sacre, Candace Move to introduce exhibit? 8:10:08 PM Chairman Chandler Note: Sacre, Candace Move Joint Intervenors 2, PPL press release. 8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace Objection? 8:10:24 PM Chairman Chandler Note: Sacre, Candace Note: Sacre, Candac			
B:07:36 PM Chairman Chandler Note: Sacre, Candace Redirect? 8:08:28 PM Chairman Chandler Note: Sacre, Candace Questions? 8:09:04 PM Chairman Chandler Note: Sacre, Candace Witness is excused. 8:09:12 PM Chairman Chandler Note: Sacre, Candace Witness is excused. 8:09:35 PM Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Move to introduce exhibit? 8:10:08 PM Chairman Chandler Note: Sacre, Candace Move Joint Intervenors 2, PPL press release. 8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace Objection? 8:10:24 PM Chairman Chandler Note: Sacre, Candace ATTY FITZGERALD JOINT INTERVENORS - WITNESS CONROY PPL NEWS RELEASE INTERNATIONAL MAGAZINE NAMES LG&E AND KU AMONG "TOP 20" U.S. UTILITIES			
updated or amended? 8:07:36 PM Chairman Chandler Note: Sacre, Candace Redirect? 8:08:28 PM Chairman Chandler Note: Sacre, Candace Questions? 8:09:04 PM Chairman Chandler Note: Sacre, Candace Witness is excused. 8:09:12 PM Chairman Chandler Note: Sacre, Candace Move to introduce exhibit? 8:09:35 PM Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Move Joint Intervenors 2, PPL press release. 8:10:08 PM Chairman Chandler Note: Sacre, Candace Objection? 8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace ATTY FITZGERALD JOINT INTERVENORS - WITNESS CONROY Note: Sacre, Candace PPL NEWS RELEASE INTERNATIONAL MAGAZINE NAMES LG&E AND KU AMONG "TOP 20" U.S. UTILITIES 8:10:24 PM Chairman Chandler			
8:07:36 PM Chairman Chandler Note: Sacre, Candace Redirect? 8:08:28 PM Chairman Chandler Note: Sacre, Candace Questions? 8:09:04 PM Chairman Chandler Note: Sacre, Candace Witness is excused. 8:09:12 PM Chairman Chandler Note: Sacre, Candace Move to introduce exhibit? 8:09:35 PM Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Move Joint Intervenors 2, PPL press release. 8:10:08 PM Chairman Chandler Note: Sacre, Candace Objection? 8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace Note: S			
8:09:28 PM Chairman Chandler Note: Sacre, Candace Questions? 8:09:04 PM Chairman Chandler Note: Sacre, Candace Witness is excused. 8:09:12 PM Chairman Chandler Note: Sacre, Candace Move to introduce exhibit? 8:09:35 PM Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Move Joint Intervenors 2, PPL press release. 8:10:08 PM Chairman Chandler Note: Sacre, Candace Objection? 8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace ATTY FITZGERALD JOINT INTERVENORS - WITNESS CONROY PPL NEWS RELEASE INTERNATIONAL MAGAZINE NAMES LG&E AND KU AMONG "TOP 20" U.S. UTILITIES 8:10:24 PM Chairman Chandler	8:07:36 PM	Chairman Chandler	•
Note: Sacre, Candace Chairman Chandler Note: Sacre, Candace Witness is excused. 8:09:12 PM Chairman Chandler Note: Sacre, Candace Move to introduce exhibit? 8:09:35 PM Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Move Joint Intervenors 2, PPL press release. 8:10:08 PM Chairman Chandler Note: Sacre, Candace Objection? 8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace ATTY FITZGERALD JOINT INTERVENORS - WITNESS CONROY Note: Sacre, Candace PPL NEWS RELEASE INTERNATIONAL MAGAZINE NAMES LG&E AND KU AMONG "TOP 20" U.S. UTILITIES 8:10:24 PM Chairman Chandler		Note: Sacre, Candace	Redirect?
8:09:04 PM Chairman Chandler Note: Sacre, Candace Witness is excused. 8:09:12 PM Chairman Chandler Note: Sacre, Candace Move to introduce exhibit? 8:09:35 PM Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Move Joint Intervenors 2, PPL press release. 8:10:08 PM Chairman Chandler Note: Sacre, Candace Objection? 8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace ATTY FITZGERALD JOINT INTERVENORS - WITNESS CONROY Note: Sacre, Candace PPL NEWS RELEASE INTERNATIONAL MAGAZINE NAMES LG&E AND KU AMONG "TOP 20" U.S. UTILITIES 8:10:24 PM Chairman Chandler	8:08:28 PM	Chairman Chandler	
Note: Sacre, Candace Witness is excused. 8:09:12 PM Chairman Chandler Note: Sacre, Candace Move to introduce exhibit? 8:09:35 PM Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Move Joint Intervenors 2, PPL press release. 8:10:08 PM Chairman Chandler Note: Sacre, Candace Objection? 8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace ATTY FITZGERALD JOINT INTERVENORS - WITNESS CONROY Note: Sacre, Candace PPL NEWS RELEASE INTERNATIONAL MAGAZINE NAMES LG&E AND KU AMONG "TOP 20" U.S. UTILITIES 8:10:24 PM Chairman Chandler		· · · · · · · · · · · · · · · · · · ·	Questions?
8:09:12 PM Chairman Chandler Note: Sacre, Candace Move to introduce exhibit? 8:09:35 PM Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Move Joint Intervenors 2, PPL press release. 8:10:08 PM Chairman Chandler Note: Sacre, Candace Objection? 8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace ATTY FITZGERALD JOINT INTERVENORS - WITNESS CONROY Note: Sacre, Candace Not	8:09:04 PM		
Note: Sacre, Candace Move to introduce exhibit? 8:09:35 PM Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Move Joint Intervenors 2, PPL press release. 8:10:08 PM Chairman Chandler Note: Sacre, Candace Objection? 8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace	0.00.40.014	· · · · · · · · · · · · · · · · · · ·	Witness is excused.
8:09:35 PM Atty Fitzgerald Joint Intervenors Note: Sacre, Candace Move Joint Intervenors 2, PPL press release. 8:10:08 PM Chairman Chandler Note: Sacre, Candace Objection? 8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace ATTY FITZGERALD JOINT INTERVENORS - WITNESS CONROY Note: Sacre, Candace PPL NEWS RELEASE INTERNATIONAL MAGAZINE NAMES LG&E AND KU AMONG "TOP 20" U.S. UTILITIES 8:10:24 PM Chairman Chandler	8:09:12 PM		Maria ta intra disa antitita
Note: Sacre, Candace Move Joint Intervenors 2, PPL press release. 8:10:08 PM Chairman Chandler Note: Sacre, Candace Objection? 8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace ATTY FITZGERALD JOINT INTERVENORS - WITNESS CONROY Note: Sacre, Candace PPL NEWS RELEASE INTERNATIONAL MAGAZINE NAMES LG&E AND KU AMONG "TOP 20" U.S. UTILITIES 8:10:24 PM Chairman Chandler	0.00.2F DM		Move to introduce exhibit?
8:10:08 PM Chairman Chandler Note: Sacre, Candace Objection? 8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace ATTY FITZGERALD JOINT INTERVENORS - WITNESS CONROY Note: Sacre, Candace PPL NEWS RELEASE INTERNATIONAL MAGAZINE NAMES LG&E AND KU AMONG "TOP 20" U.S. UTILITIES 8:10:24 PM Chairman Chandler	8:09:35 PM	, -	Mayo Joint Intervenors 2 DDI proce release
Note: Sacre, Candace Objection? 8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace ATTY FITZGERALD JOINT INTERVENORS - WITNESS CONROY Note: Sacre, Candace PPL NEWS RELEASE INTERNATIONAL MAGAZINE NAMES LG&E AND KU AMONG "TOP 20" U.S. UTILITIES 8:10:24 PM Chairman Chandler	Q+10+0Q DM	· · · · · · · · · · · · · · · · · · ·	Prove Joint Thervenors 2, FFL press release.
8:10:09 PM JOINT INTERVENORS EXHIBIT 2 Note: Sacre, Candace Note: Sacre,	0.10.00 FM		Objection?
Note: Sacre, Candace Note: Sac	8:10:09 PM		objection.
Note: Sacre, Candace PPL NEWS RELEASE INTERNATIONAL MAGAZINE NAMES LG&E AND KU AMONG "TOP 20" U.S. UTILITIES 8:10:24 PM Chairman Chandler			ATTY FITZGERALD JOINT INTERVENORS - WITNESS CONROY
KU AMONG "TOP 20" U.S. UTILITIES 8:10:24 PM Chairman Chandler			
		,	
Note: Sacre, Candace Additional witness? (Click on link for further comments.)	8:10:24 PM		
		Note: Sacre, Candace	Additional witness? (Click on link for further comments.)

8:10:39 PM	Chairman Chandler	
	Note: Sacre, Candace	All exhibits in record? (Click on link for further comments.)
8:11:11 PM	Chairman Chandler	
	Note: Sacre, Candace	Outstanding motions, orders. (Click on link for further comments.)
8:13:12 PM	Chairman Chandler	
	Note: Sacre, Candace	Post-hearing data requests. (Click on link for further comments.)
8:13:58 PM	Chairman Chandler	
	Note: Sacre, Candace	Statutory date September 24.
8:14:14 PM	Chairman Chandler	
	Note: Sacre, Candace	Briefing schedule. (Click on link for further comments.)
8:16:15 PM	Chairman Chandler	
	Note: Sacre, Candace	Requests to counsel issues to address in briefs. (Click on link for further comments.)
8:18:57 PM	Chairman Chandler	
	Note: Sacre, Candace	Motion on informal conference. (Click on link for further comments.)
8:19:09 PM	Chairman Chandler	
	Note: Sacre, Candace	Scheduling order tomorrow. (Click on link for further comments.)
8:19:10 PM	Chairman Chandler	
	Note: Sacre, Candace	Anything else? (Click on link for further comments.)
8:19:16 PM	Chairman Chandler	
	Note: Sacre, Candace	Hearing adjourned.



2020-00349 and 2020-00350 18Aug2021

Kentucky Utilities Company (KU) and Louisville Gas and Electric Company (LG&E)

Name:	Description:
AG/KIUC EXHIBIT 1	18 CFR 292.202 QUALIFING COGENERATION AND SMALL POWER PRODUCTION FACILITIES DEFINITIONS
AG/KIUC EXHIBIT 2	18 CFR 292.302 AVAILABILITY OF ELECTRIC UTILITY SYSTEM
AG/KIUC EXHIBIT 3	18 CFR 292 AND 375 FACILITY RATES AND REQUIREMENTS
JOINT INTERVENORS EXHIBIT 1	FERC ORDER DOCKET NO. EL20-42-000
JOINT INTERVENORS EXHIBIT 2	PPL NEWS RELEASE INTERNATIONAL MAGAZINE NAMES LG&E AND KU AMONG "TOP 20" U.S. UTILITIES
KU/LG&E BARNES CROSS EXHIBIT 1	SCENARIOS 1, 2, AND 3 NEED FOR ADDITIONAL GENERATION CAPACITY
PSC STAFF EXHIBIT 05	KRS 278.465 DEFINITIONS FOR KRS 278.465 TO 278.468
PSC STAFF EXHIBIT 06	KRS 278.465 DEFINITIONS FOR KRS 278.465 TO 278.468
PSC STAFF EXHIBIT 07	01/07/2021 LGE-KU.COM PRESS RELEASE - LG&E AND KU REQUEST BIDS FOR ENERGY TO CONTINUE TO RELIABLY SERVE CUSTOMERS
PSC STAFF EXHIBIT 08	KENTUCKY UTILITIES COMPANY PSC NO. 19, ORIGINAL SHEET NO. 97
PSC STAFF EXHIBIT 09	KENTUCKY UTILITIES COMPANY PSC NO. 20, ORIGINAL SHEET NO. 97
PSC STAFF EXHIBIT 10	LOUISVILLE GAS AND ELECTRIC PSC NO. 12 ORIGINAL SHEET NO. 97
PSC STAFF EXHIBIT 11	LOUISVILLE GAS AND ELECTRIC PSC NO. 13 ORIGINAL SHEET NO. 97

e-CFR data is current as of August 12, 2021

Title 18 → Chapter I → Subchapter K → Part 292 → Subpart B → §292.202

Title 18: Conservation of Power and Water Resources

PART 292—REGULATIONS UNDER SECTIONS 201 AND 210 OF THE PUBLIC UTILITY REGULATORY POLICIES ACT OF 1978 WITH REGARD TO SMALL POWER PRODUCTION AND COGENERATION

Subpart B—Qualifying Cogeneration and Small Power Production Facilities

§292.202 Definitions.

For purposes of this subpart:

- (a) Biomass means any organic material not derived from fossil fuels;
- (b) Waste means an energy input that is listed below in this subsection, or any energy input that has little or no current commercial value and exists in the absence of the qualifying facility industry. Should a waste energy input acquire commercial value after a facility is qualified by way of Commission certification pursuant to §292.207(b), or self-certification pursuant to §292.207(a), the facility will not lose its qualifying status for that reason. Waste includes, but is not limited to, the following materials that the Commission previously has approved as waste:
 - (1) Anthracite culm produced prior to July 23, 1985;
- (2) Anthracite refuse that has an average heat content of 6,000 Btu or less per pound and has an average ash content of 45 percent or more;
- (3) Bituminous coal refuse that has an average heat content of 9,500 Btu per pound or less and has an average ash content of 25 percent or more;
- (4) Top or bottom subbituminous coal produced on Federal lands or on Indian lands that has been determined to be waste by the United States Department of the Interior's Bureau of Land Management (BLM) or that is located on non-Federal or non-Indian lands outside of BLM's jurisdiction, provided that the applicant shows that the latter coal is an extension of that determined by BLM to be waste.
- (5) Coal refuse produced on Federal lands or on Indian lands that has been determined to be waste by the BLM or that is located on non-Federal or non-Indian lands outside of BLM's jurisdiction, provided that applicant shows that the latter is an extension of that determined by BLM to be waste.

- (6) Lignite produced in association with the production of montan wax and lignite that becomes exposed as a result of such a mining operation;
 - (7) Gaseous fuels, except:
 - (i) Synthetic gas from coal; and
- (ii) Natural gas from gas and oil wells unless the natural gas meets the requirements of §2.400 of this chapter;
 - (8) Petroleum coke;
 - (9) Materials that a government agency has certified for disposal by combustion;
 - (10) Residual heat;
 - (11) Heat from exothermic reactions;
 - (12) Used rubber tires;
 - (13) Plastic materials; and
 - (14) Refinery off-gas.
- (c) Cogeneration facility means equipment used to produce electric energy and forms of useful thermal energy (such as heat or steam), used for industrial, commercial, heating, or cooling purposes, through the sequential use of energy;
- (d) Topping-cycle cogeneration facility means a cogeneration facility in which the energy input to the facility is first used to produce useful power output, and at least some of the reject heat from the power production process is then used to provide useful thermal energy;
- (e) Bottoming-cycle cogeneration facility means a cogeneration facility in which the energy input to the system is first applied to a useful thermal energy application or process, and at least some of the reject heat emerging from the application or process is then used for power production;
- (f) Supplementary firing means an energy input to the cogeneration facility used only in the thermal process of a topping-cycle cogeneration facility, or only in the electric generating process of a bottoming-cycle cogeneration facility;
- (g) Useful power output of a cogeneration facility means the electric or mechanical energy made available for use, exclusive of any such energy used in the power production process;
- (h) *Useful thermal energy output* of a topping-cycle cogeneration facility means the thermal energy:

- (1) That is made available to an industrial or commercial process (net of any heat contained in condensate return and/or makeup water);
- (2) That is used in a heating application (e.g., space heating, domestic hot water heating);
- (3) That is used in a space cooling application (*i.e.*, thermal energy used by an absorption chiller); or
- (4) That is used by a fuel cell system with an integrated steam hydrocarbon reformation process for production of fuel for electricity generation.
- (i) *Total energy output* of a topping-cycle cogeneration facility is the sum of the useful power output and useful thermal energy output;
- (j) *Total energy input* means the total energy of all forms supplied from external sources;
- (k) Natural gas means either natural gas unmixed, or any mixture of natural gas and artificial gas;
- (I) Oil means crude oil, residual fuel oil, natural gas liquids, or any refined petroleum products; and
- (m) Energy input in the case of energy in the form of natural gas or oil is to be measured by the lower heating value of the natural gas or oil.
- (n) Electric utility holding company means a holding company, as defined in section 2(a)(7) of the Public Utility Holding Company Act of 1935, 15 U.S.C. 79b(a)(7) which owns one or more electric utilities, as defined in section 2(a)(3) of that Act, 15 U.S.C. 79b(a)(3), but does not include any holding company which is exempt by rule or order adopted or issued pursuant to sections 3(a)(3) or 3(a)(5) of the Public Utility Holding Company Act of 1935, 15 U.S.C. 79c(a)(3) or 79c(a)(5).
- (o) *Utility geothermal small power production facility* means a small power production facility which uses geothermal energy as the primary energy resource and of which more than 50 percent is owned either:
- (1) By an electric utility or utilities, electric utility holding company or companies, or any combination thereof.
- (2) By any company 50 percent or more of the outstanding voting securities of which of which are directly or indirectly owned, controlled, or held with power to vote by an electric utility, electric utility holding company, or any combination thereof.
- (p) New dam or diversion means a dam or diversion which requires, for the purposes of installing any hydroelectric power project, any construction, or enlargement of any

impoundment or diversion structure (other than repairs or reconstruction or the addition of flashboards of similar adjustable devices);

- (q) Substantial adverse effect on the environment means a substantial alteration in the existing or potential use of, or a loss of, natural features, existing habitat, recreational uses, water quality, or other environmental resources. Substantial alteration of particular resource includes a change in the environment that substantially reduces the quality of the affected resources; and
- (r) Commitment of substantial monetary resources means the expenditure of, or commitment to expend, at least 50 percent of the total cost of preparing an application for license or exemption for a hydroelectric project that is accepted for filing by the Commission pursuant to §4.32(e) of this chapter. The total cost includes (but is not limited to) the cost of agency consultation, environmental studies, and engineering studies conducted pursuant to §4.38 of this chapter, and the Commission's requirements for filing an application for license exemption.
 - (s) Sequential use of energy means:
- (1) For a topping-cycle cogeneration facility, the use of reject heat from a power production process in sufficient amounts in a thermal application or process to conform to the requirements of the operating standard; or
- (2) For a bottoming-cycle cogeneration facility, the use of reject heat from a thermal application or process, at least some of which is then used for power production.
- (t) Electrical generating equipment means all boilers, heat recovery steam generators, prime movers (any mechanical equipment driving an electric generator), electrical generators, photovoltaic solar panels, inverters, fuel cell equipment and/or other primary power generation equipment used in the facility, excluding equipment for gathering energy to be used in the facility.

(Energy Security Act, Pub. L. 96-294, 94 Stat. 611 (1980) Public Utility Regulatory Policies Act of 1978, 16 U.S.C. 2601, et seq., Energy Supply and Environmental Coordination Act, 15 U.S.C. 791 et seq., Federal Power Act, as amended, 16 U.S.C. 792 et seq., Department of Energy Organization Act, 42 U.S.C. 7101 et seq., E.O. 12009, 42 FR 46267)

[45 FR 17972, Mar. 20, 1980, as amended at 45 FR 33958, May 21, 1980; 45 FR 66789, Oct. 8, 1980; Order 135, 46 FR 19231, Mar. 30, 1981; 46 FR 32239, June 22, 1981; Order 499, 53 FR 27002, July 18, 1988; Order 575, 60 FR 4857, Jan. 25, 1995; Order 872, 85 FR 54732, Sept. 2, 2020; Order 874, 86 FR 8140, Feb. 4, 2021]

e-CFR data is current as of August 12, 2021

Title 18 → Chapter I → Subchapter K → Part 292 → Subpart B → §292.203

Title 18: Conservation of Power and Water Resources

PART 292—REGULATIONS UNDER SECTIONS 201 AND 210 OF THE PUBLIC UTILITY REGULATORY POLICIES ACT OF 1978 WITH REGARD TO SMALL POWER PRODUCTION AND COGENERATION

Subpart B—Qualifying Cogeneration and Small Power Production Facilities

§292.203 General requirements for qualification.

- (a) Small power production facilities. Except as provided in paragraph (c) of this section, a small power production facility is a qualifying facility if it:
 - (1) Meets the maximum size criteria specified in §292.204(a);
 - (2) Meets the fuel use criteria specified in §292.204(b); and
- (3) Unless exempted by paragraph (d), has filed with the Commission a notice of self-certification, pursuant to §292.207(a); or has filed with the Commission an application for Commission certification, pursuant to §292.207(b)(1), that has been granted.
- (b) Cogeneration facilities. A cogeneration facility, including any diesel and dual-fuel cogeneration facility, is a qualifying facility if it:
- (1) Meets any applicable standards and criteria specified in §§292.205(a), (b) and (d); and
- (2) Unless exempted by paragraph (d), has filed with the Commission a notice of self-certification, pursuant to §292.207(a); or has filed with the Commission an application for Commission certification, pursuant to §292.207(b)(1), that has been granted.
- (c) Hydroelectric small power production facilities located at a new dam or diversion. (1) A hydroelectric small power production facility that impounds or diverts the water of a natural watercourse by means of a new dam or diversion (as that term is defined in §292.202(p)) is a qualifying facility if it meets the requirements of:
 - (i) Paragraph (a) of this section; and
 - (ii) Section 292.208.

(2) [Reserved]

- (d) Exemptions and waivers from filing requirement. (1) Any facility with a net power production capacity of 1 MW or less is exempt from the filing requirements of paragraphs (a)(3) and (b)(2) of this section.
- (2) The Commission may waive the requirement of paragraphs (a)(3) and (b)(2) of this section for good cause. Any applicant seeking waiver of paragraphs (a)(3) and (b)(2) of this section must file a petition for declaratory order describing in detail the reasons waiver is being sought.

[Order 732, 75 FR 15965, Mar. 30, 2010]

e-CFR data is current as of August 12, 2021

Title 18 → Chapter I → Subchapter K → Part 292 → Subpart B → §292.204

Title 18: Conservation of Power and Water Resources

PART 292—REGULATIONS UNDER SECTIONS 201 AND 210 OF THE PUBLIC UTILITY REGULATORY POLICIES ACT OF 1978 WITH REGARD TO SMALL POWER PRODUCTION AND COGENERATION

Subpart B—Qualifying Cogeneration and Small Power Production Facilities

§292.204 Criteria for qualifying small power production facilities.

- (a) Size of the facility—(1) Maximum size. Except as provided in paragraph (a)(4) of this section, the power production capacity of a facility for which qualification is sought, together with the power production capacity of any other small power production qualifying facilities that use the same energy resource, are owned by the same person(s) or its affiliates, and are located at the same site, may not exceed 80 megawatts.
- (2) Method of calculation. (i)(A) For purposes of this paragraph (a)(2), there is an irrebuttable presumption that affiliated small power production qualifying facilities that use the same energy resource and are located one mile or less from the facility for which qualification or recertification is sought are located at the same site as the facility for which qualification or recertification is sought.
- (B) For purposes of this paragraph (a)(2), for facilities for which qualification or recertification is filed on or after December 31, 2020 there is an irrebuttable presumption that affiliated small power production qualifying facilities that use the same energy resource and are located 10 miles or more from the facility for which qualification or recertification is sought are located at separate sites from the facility for which qualification or recertification is sought.
- (C) For purposes of this paragraph (a)(2), for facilities for which qualification or recertification is filed on or after December 31, 2020, there is a rebuttable presumption that affiliated small power production qualifying facilities that use the same energy resource and are located more than one mile and less than 10 miles from the facility for which qualification or recertification is sought are located at separate sites from the facility for which qualification or recertification is sought.
- (D) For hydroelectric facilities, facilities are considered to be located at the same site as the facility for which qualification or recertification is sought if they are located within one mile of the facility for which qualification or recertification is sought and use water from

the same impoundment for power generation.

- (ii) For purposes of making the determinations in paragraph (a)(2)(i), the distance between two facilities shall be measured from the edge of the closest electrical generating equipment for which qualification or recertification is sought to the edge of the nearest electrical generating equipment of the other affiliated small power production qualifying facility using the same energy resource.
- (3) Waiver. The Commission may modify the application of paragraph (a)(2) of this section, for good cause.
- (4) Exception. Facilities meeting the criteria in section 3(17)(E) of the Federal Power Act (16 U.S.C. 796(17)(E)) have no maximum size, and the power production capacity of such facilities shall be excluded from consideration when determining the size of other small power production facilities less than 10 miles from such facilities.
- (b) Fuel use. (1)(i) The primary energy source of the facility must be biomass, waste, renewable resources, geothermal resources, or any combination thereof, and 75 percent or more of the total energy input must be from these sources.
- (ii) Any primary energy source which, on the basis of its energy content, is 50 percent or more biomass shall be considered biomass.
- (2) Use of oil, natural gas and coal by a facility, under section 3(17)(B) of the Federal Power Act, is limited to the minimum amounts of fuel required for ignition, startup, testing, flame stabilization, and control uses, and the minimum amounts of fuel required to alleviate or prevent unanticipated equipment outages, and emergencies, directly affecting the public health, safety, or welfare, which would result from electric power outages. Such fuel use may not, in the aggregate, exceed 25 percent of the total energy input of the facility during the 12-month period beginning with the date the facility first produces electric energy and any calendar year subsequent to the year in which the facility first produces electric energy.

(Energy Security Act, Pub. L. 96-294, 94 Stat. 611 (1980) Public Utility Regulatory Policies Act of 1978, 16 U.S.C. 2601, et seq., Energy Supply and Environmental Coordination Act, 15, U.S.C. 791, et seq., Federal Power Act, as amended, 16 U.S.C. 792 et seq., Department of Energy Organization Act, 42 U.S.C. 7101, et seq.; E.O. 12009, 42 FR 46267)

[45 FR 17972, Mar. 20, 1980, as amended by Order 135, 46 FR 19231, Mar. 30, 1981; Order 575, 60 FR 4857, Jan. 25, 1995; Order 732, 75 FR 15966, Mar. 30, 2010; Order 872, 85 FR 54732, Sept. 2, 2020]

e-CFR data is current as of August 12, 2021

Title 18 → Chapter I → Subchapter K → Part 292 → Subpart B → §292.205

Title 18: Conservation of Power and Water Resources

PART 292—REGULATIONS UNDER SECTIONS 201 AND 210 OF THE PUBLIC UTILITY REGULATORY POLICIES ACT OF 1978 WITH REGARD TO SMALL POWER PRODUCTION AND COGENERATION

Subpart B—Qualifying Cogeneration and Small Power Production Facilities

§292.205 Criteria for qualifying cogeneration facilities.

- (a) Operating and efficiency standards for topping-cycle facilities—(1) Operating standard. For any topping-cycle cogeneration facility, the useful thermal energy output of the facility must be no less than 5 percent of the total energy output during the 12-month period beginning with the date the facility first produces electric energy, and any calendar year subsequent to the year in which the facility first produces electric energy.
- (2) Efficiency standard. (i) For any topping-cycle cogeneration facility for which any of the energy input is natural gas or oil, and the installation of which began on or after March 13, 1980, the useful power output of the facility plus one-half the useful thermal energy output, during the 12-month period beginning with the date the facility first produces electric energy, and any calendar year subsequent to the year in which the facility first produces electric energy, must:
- (A) Subject to paragraph (a)(2)(i)(B) of this section be no less than 42.5 percent of the total energy input of natural gas and oil to the facility; or
- (B) If the useful thermal energy output is less than 15 percent of the total energy output of the facility, be no less than 45 percent of the total energy input of natural gas and oil to the facility.
- (ii) For any topping-cycle cogeneration facility not subject to paragraph (a)(2)(i) of this section there is no efficiency standard.
- (b) Efficiency standards for bottoming-cycle facilities. (1) For any bottoming-cycle cogeneration facility for which any of the energy input as supplementary firing is natural gas or oil, and the installation of which began on or after March 13, 1980, the useful power output of the facility during the 12-month period beginning with the date the facility first produces electric energy, and any calendar year subsequent to the year in which the facility first produces electric energy must be no less than 45 percent of the energy input of natural gas and oil for supplementary firing.

- (2) For any bottoming-cycle cogeneration facility not covered by paragraph (b)(1) of this section, there is no efficiency standard.
- (c) Waiver. The Commission may waive any of the requirements of paragraphs (a) and (b) of this section upon a showing that the facility will produce significant energy savings.
- (d) Criteria for new cogeneration facilities. Notwithstanding paragraphs (a) and (b) of this section, any cogeneration facility that was either not a qualifying cogeneration facility on or before August 8, 2005, or that had not filed a notice of self-certification or an application for Commission certification as a qualifying cogeneration facility under §292.207 of this chapter prior to February 2, 2006, and which is seeking to sell electric energy pursuant to section 210 of the Public Utility Regulatory Policies Act of 1978, 16 U.S.C. 824a-1, must also show:
- (1) The thermal energy output of the cogeneration facility is used in a productive and beneficial manner; and
- (2) The electrical, thermal, chemical and mechanical output of the cogeneration facility is used fundamentally for industrial, commercial, residential or institutional purposes and is not intended fundamentality for sale to an electric utility, taking into account technological, efficiency, economic, and variable thermal energy requirements, as well as state laws applicable to sales of electric energy from a qualifying facility to its host facility.
- (3) Fundamental use test. For the purpose of satisfying paragraph (d)(2) of this section, the electrical, thermal, chemical and mechanical output of the cogeneration facility will be considered used fundamentally for industrial, commercial, or institutional purposes, and not intended fundamentally for sale to an electric utility if at least 50 percent of the aggregate of such output, on an annual basis, is used for industrial, commercial, residential or institutional purposes. In addition, applicants for facilities that do not meet this safe harbor standard may present evidence to the Commission that the facilities should nevertheless be certified given state laws applicable to sales of electric energy or unique technological, efficiency, economic, and variable thermal energy requirements.
- (4) For purposes of paragraphs (d)(1) and (2) of this section, a new cogeneration facility of 5 MW or smaller will be presumed to satisfy the requirements of those paragraphs.
- (5) For purposes of paragraph (d)(1) of this section, where a thermal host existed prior to the development of a new cogeneration facility whose thermal output will supplant the thermal source previously in use by the thermal host, the thermal output of such new cogeneration facility will be presumed to satisfy the requirements of paragraph (d)(1).

[45 FR 17972, Mar. 20, 1980, as amended by Order 478, 52 FR 28467, July 30, 1987; Order 575, 60 FR 4857, Jan. 25, 1995; Order 671, 71 FR 7868, Feb. 15, 2006; Order 732, 75 FR 15966, Mar. 30, 2010; 76 FR 50663, Aug. 16, 2011]

e-CFR data is current as of August 12, 2021

Title 18 → Chapter I → Subchapter K → Part 292 → Subpart C → §292.304

Title 18: Conservation of Power and Water Resources

PART 292—REGULATIONS UNDER SECTIONS 201 AND 210 OF THE PUBLIC UTILITY REGULATORY POLICIES ACT OF 1978 WITH REGARD TO SMALL POWER PRODUCTION AND COGENERATION

Subpart C—Arrangements Between Electric Utilities and Qualifying Cogeneration and Small Power Production Facilities Under Section 210 of the Public Utility Regulatory Policies Act of 1978

§292.304 Rates for purchases.

- (a) Rates for purchases. (1) Rates for purchases shall:
- (i) Be just and reasonable to the electric consumer of the electric utility and in the public interest; and
- (ii) Not discriminate against qualifying cogeneration and small power production facilities.
- (2) Nothing in this subpart requires any electric utility to pay more than the avoided costs for purchases.
- (b) Relationship to avoided costs. (1) For purposes of this paragraph, "new capacity" means any purchase from capacity of a qualifying facility, construction of which was commenced on or after November 9, 1978.
- (2) Subject to paragraph (b)(3) of this section, a rate for purchases satisfies the requirements of paragraph (a) of this section if the rate equals the avoided costs determined after consideration of the factors set forth in paragraph (e) of this section
- (3) A rate for purchases (other than from new capacity) may be less than the avoided cost if the State regulatory authority (with respect to any electric utility over which it has ratemaking authority) or the nonregulated electric utility determines that a lower rate is consistent with paragraph (a) of this section, and is sufficient to encourage cogeneration and small power production.
- (4) Rates for purchases from new capacity shall be in accordance with paragraph (b)(2) of this section, regardless of whether the electric utility making such purchases is simultaneously making sales to the qualifying facility.

- (5) In the case in which the rates for purchases are based upon estimates of avoided costs over the specific term of the contract or other legally enforceable obligation, the rates for such purchases do not violate this subpart if the rates for such purchases differ from avoided costs at the time of delivery.
- (6) Locational Marginal Price. There is a rebuttable presumption that a state regulatory authority or nonregulated electric utility may use a Locational Marginal Price as a rate for as-available qualifying facility energy sales to electric utilities located in a market defined in §292.309(e), (f), or (g).
- (7) Competitive Price. A state regulatory authority or nonregulated electric utility may use a Competitive Price as a rate for as-available qualifying facility energy sales to electric utilities located outside a market defined in §292.309(e), (f), or (g). A Competitive Price may be either a Market Hub Price or a Combined Cycle Price, determined as follows:
- (i) A *Market Hub Price* is a price established at a liquid market hub which a state regulatory authority or nonregulated electric utility determines represents an appropriate measure of the electric utility's avoided cost for as-available energy, and is a hub to which the electric utility has reasonable access, based on an evaluation by the state regulatory authority or nonregulated electric utility of the relevant factors, including but not limited to the following:
- (A) Whether the hub is sufficiently liquid that prices at the hub represent a competitive price;
 - (B) Whether prices developed at the hub are sufficiently transparent;
- (C) Whether the electric utility has the ability to deliver power from such hub to its load, even if its load is not directly connected to the hub; and
- (D) Whether the hub represents an appropriate market to derive an energy price for the electric utility's purchases from the relevant qualifying facility given the electric utility's physical proximity to the hub or other factors.
- (ii) A Combined Cycle Price is a price determined pursuant to a formula established by a state regulatory authority or nonregulated electric utility using published natural gas price indices, a proxy heat rate, and variable operations and maintenance costs for an efficient natural gas combined-cycle generating facility. Before establishing such a formula rate, a state regulatory authority or nonregulated electric utility must determine that the resulting Combined Cycle Price represents an appropriate measure of the purchasing electric utility's avoided cost for energy, based on its evaluation of the relevant factors, including but not limited to the following:
- (A) Whether the cost of energy from an efficient natural gas combined cycle generating facility represents a reasonable measure of a competitive price in the purchasing electric utility's region;

- (B) Whether natural gas priced pursuant to particular proposed natural gas price indices would be available in the relevant market;
- (C) Whether there should be an adjustment to the natural gas price to appropriately reflect the cost of transporting natural gas to the relevant market; and
- (D) Whether the proxy heat rate used in the formula should be updated regularly to reflect improvements in generation technology.
- (8) Competitive Solicitation Price. (i) A state regulatory authority or nonregulated electric utility may use a price determined pursuant to a competitive solicitation process to establish qualifying facility energy and/or capacity rates for sales to electric utilities, provided that such competitive solicitation process is conducted pursuant to procedures ensuring the solicitation is conducted in a transparent and non-discriminatory manner including, but not limited to, the following:
- (A) The solicitation process is an open and transparent process that includes, but is not limited to, providing equally to all potential bidders substantial and meaningful information regarding transmission constraints, levels of congestion, and interconnections, subject to appropriate confidentiality safeguards;
- (B) Solicitations are open to all sources, to satisfy that electric utility's capacity needs, taking into account the required operating characteristics of the needed capacity;
 - (C) Solicitations are conducted at regular intervals;
 - (D) Solicitations are subject to oversight by an independent administrator; and
- (E) Solicitations are certified as fulfilling the above criteria by the relevant state regulatory authority or nonregulated electric utility through a post-solicitation report.
- (ii) To the extent that the electric utility procures all of its capacity, including capacity resources constructed or otherwise acquired by the electric utility, through a competitive solicitation process conducted pursuant to paragraph (b)(8)(i) of this section, the electric utility shall be presumed to have no avoided capacity costs unless and until it determines to acquire capacity outside of such competitive solicitation process. However, the electric utility shall nevertheless be required to purchase energy from qualifying small power producers and qualifying cogeneration facilities.
- (iii) To the extent that the electric utility does not procure all of its capacity through a competitive solicitation process conducted pursuant to paragraph (b)(8)(i) of this section, then there shall be no presumption that the electric utility has no avoided capacity costs.
- (c) Standard rates for purchases. (1) There shall be put into effect (with respect to each electric utility) standard rates for purchases from qualifying facilities with a design capacity of 100 kilowatts or less.

- (2) There may be put into effect standard rates for purchases from qualifying facilities with a design capacity of more than 100 kilowatts.
 - (3) The standard rates for purchases under this paragraph:
 - (i) Shall be consistent with paragraphs (a) and (e) of this section; and
- (ii) May differentiate among qualifying facilities using various technologies on the basis of the supply characteristics of the different technologies.
- (d) Purchases "as available" or pursuant to a legally enforceable obligation. (1) Each qualifying facility shall have the option either:
- (i) To provide energy as the qualifying facility determines such energy to be available for such purchases, in which case the rates for such purchases shall be based on the electric utility's avoided cost for energy calculated at the time of delivery; or
- (ii) To provide energy or capacity pursuant to a legally enforceable obligation for the delivery of energy or capacity over a specified term, in which case the rates for such purchases shall, except as provided in paragraph (d)(2) of this section, be based on either:
 - (A) The avoided costs calculated at the time of delivery; or
 - (B) The avoided costs calculated at the time the obligation is incurred.
- (iii) The rate for delivery of energy calculated at the time the obligation is incurred may be based on estimates of the present value of the stream of revenue flows of future locational marginal prices, or Competitive Prices during the anticipated period of delivery.
- (2) Notwithstanding paragraph (d)(1)(ii)(B) of this section, a state regulatory authority or nonregulated electric utility may require that rates for purchases of energy from a qualifying facility pursuant to a legally enforceable obligation vary through the life of the obligation, and be set at the electric utility's avoided cost for energy calculated at the time of delivery.
- (3) Obtaining a legally enforceable obligation. A qualifying facility must demonstrate commercial viability and financial commitment to construct its facility pursuant to criteria determined by the state regulatory authority or nonregulated electric utility as a prerequisite to a qualifying facility obtaining a legally enforceable obligation. Such criteria must be objective and reasonable.
- (e) Factors affecting rates for purchases. (1) A state regulatory authority or nonregulated electric utility may establish rates for purchases of energy from a qualifying facility based on a purchasing electric utility's locational marginal price calculated by the applicable market defined in §292.309(e), (f), or (g), or the purchasing electric utility's applicable Competitive Price. Alternatively, a state regulatory authority or nonregulated electric utility may establish rates for purchases of energy and/or capacity from a qualifying

facility based on a Competitive Solicitation Price. To the extent that capacity rates are not set pursuant to this section, capacity rates shall be set pursuant to subsection (2).

- (2) To the extent that a state regulatory authority or nonregulated electric utility does not set energy and/or capacity rates pursuant to paragraph (e)(1) of this section, the following factors shall, to the extent practicable, be taken into account in determining rates for purchases from a qualifying facility:
- (i) The data provided pursuant to §292.302(b), (c), or (d), including State review of any such data;
- (ii) The availability of capacity or energy from a qualifying facility during the system daily and seasonal peak periods, including:
 - (A) The ability of the electric utility to dispatch the qualifying facility;
 - (B) The expected or demonstrated reliability of the qualifying facility;
- (C) The terms of any contract or other legally enforceable obligation, including the duration of the obligation, termination notice requirement and sanctions for non-compliance;
- (D) The extent to which scheduled outages of the qualifying facility can be usefully coordinated with scheduled outages of the electric utility's facilities;
- (E) The usefulness of energy and capacity supplied from a qualifying facility during system emergencies, including its ability to separate its load from its generation;
- (F) The individual and aggregate value of energy and capacity from qualifying facilities on the electric utility's system; and
- (G) The smaller capacity increments and the shorter lead times available with additions of capacity from qualifying facilities; and
- (iii) The relationship of the availability of energy or capacity from the qualifying facility as derived in paragraph (e)(2)(ii) of this section, to the ability of the electric utility to avoid costs, including the deferral of capacity additions and the reduction of fossil fuel use; and
- (iv) The costs or savings resulting from variations in line losses from those that would have existed in the absence of purchases from a qualifying facility, if the purchasing electric utility generated an equivalent amount of energy itself or purchased an equivalent amount of electric energy or capacity.
- (f) Periods during which purchases not required. (1) Any electric utility which gives notice pursuant to paragraph (f)(2) of this section will not be required to purchase electric energy or capacity during any period during which, due to operational circumstances, purchases from qualifying facilities will result in costs greater than those which the utility would incur if it did not make such purchases, but instead generated an equivalent amount

of energy itself.

- (2) Any electric utility seeking to invoke paragraph (f)(1) of this section must notify, in accordance with applicable State law or regulation, each affected qualifying facility in time for the qualifying facility to cease the delivery of energy or capacity to the electric utility.
- (3) Any electric utility which fails to comply with the provisions of paragraph (f)(2) of this section will be required to pay the same rate for such purchase of energy or capacity as would be required had the period described in paragraph (f)(1) of this section not occurred.
- (4) A claim by an electric utility that such a period has occurred or will occur is subject to such verification by its State regulatory authority as the State regulatory authority determines necessary or appropriate, either before or after the occurrence.

[Order 69, 45 FR 12234, Feb. 25, 1980, as amended by Order 872, 85 FR 54733, Sept. 2, 2020]

LII > Electronic Code of Federal Regulations (e-CFR)

- > Title 18 Conservation of Power and Water Resources
- > CHAPTER I FEDERAL ENERGY REGULATORY COMMISSION, DEPARTMENT OF ENERGY
- > SUBCHAPTER K REGULATIONS UNDER THE PUBLIC UTILITY REGULATORY POLICIES ACT OF 1978
- > PART 292 REGULATIONS UNDER SECTIONS 201 AND 210 OF THE PUBLIC UTILITY REGULATORY POLICIES ACT OF 1978 WITH REGARD TO SMALL POWER PRODUCTION AND COGENERATION
- > Subpart C Arrangements Between Electric Utilities and Qualifying Cogeneration and Small Power Production Facilities Under Section 210 of the Public Utility Regulatory Policies Act of 1978
- > § 292.302 Availability of electric utility system cost data.

18 CFR § 292.302 - Availability of electric utility system cost data.

CFR State Regulations

§ 292.302 Availability of electric utility system cost data.

(a) Applicability.

- (1) Except as provided in <u>paragraph (a)(2)</u> of this section, paragraph (b) applies to each electric utility, in any calendar year, if the total sales of electric energy by such utility for purposes other than resale exceeded 500 million kilowatt-hours during any calendar year beginning after December 31, 1975, and before the immediately preceding calendar year.
- (2) Each utility having total sales of electric energy for purposes other than resale of less than one billion kilowatt-hours during any calendar year beginning after December 31, 1975, and before the immediately preceding year, shall not be subject to the provisions of this section until June 30, 1982.

- (b) General rule. To make available data from which avoided costs may be derived, not later than November 1, 1980, June 30, 1982, and not less often than every two years thereafter, each regulated electric utility described in paragraph (a) of this section shall provide to its State regulatory authority, and shall maintain for public inspection, and each nonregulated electric utility described in paragraph (a) of this section shall maintain for public inspection, the following data:
 - (1) The estimated avoided cost on the electric utility's system, solely with respect to the energy component, for various levels of purchases from qualifying facilities. Such levels of purchases shall be stated in blocks of not more than 100 megawatts for systems with peak demand of 1000 megawatts or more, and in blocks equivalent to not more than 10 percent of the system peak demand for systems of less than 1000 megawatts. The avoided costs shall be stated on a cents per kilowatt-hour basis, during daily and seasonal peak and off-peak periods, by year, for the current calendar year and each of the next 5 years;
 - (2) The electric utility's plan for the addition of <u>capacity</u> by amount and type, for purchases of firm energy and <u>capacity</u>, and for <u>capacity</u> retirements for each year during the succeeding 10 years; and
 - (3) The estimated <u>capacity</u> costs at completion of the planned <u>capacity</u> additions and planned <u>capacity</u> firm purchases, on the basis of dollars per kilowatt, and the associated energy costs of each unit, expressed in cents per kilowatt hour. These costs shall be expressed in terms of individual generating units and of individual planned firm purchases.

(c) Special rule for small electric utilities.

- (1) Each electric utility (other than any electric utility to which <u>paragraph</u> (b) of this section applies) shall, upon request:
 - (i) Provide comparable data to that required under <u>paragraph</u> (b) of this section to enable qualifying facilities to estimate the electric utility's avoided costs for periods described in <u>paragraph</u> (b) of this section; or
 - (ii) With regard to an electric utility which is legally obligated to obtain all its requirements for electric energy and <u>capacity</u> from another electric utility, provide the data of its supplying utility and the rates at which it currently purchases such energy and <u>capacity</u>.
- (2) If any such electric utility fails to provide such information on request, the qualifying facility may apply to the State regulatory authority (which has ratemaking authority over the electric utility) or the Commission for an order

requiring that the information be provided.

(d) Substitution of alternative method.

- (1) After public notice in the area served by the electric utility, and after opportunity for public comment, any State regulatory authority may require (with respect to any electric utility over which it has ratemaking authority), or any non-regulated electric utility may provide, data different than those which are otherwise required by this section if it determines that avoided costs can be derived from such data.
- (2) Any State regulatory authority (with respect to any electric utility over which it has ratemaking authority) or nonregulated utility which requires such different data shall notify the <u>Commission</u> within 30 days of making such determination.

(e) State Review.

- (1) Any data submitted by an electric utility under this section shall be subject to review by the State regulatory authority which has ratemaking authority over such electric utility.
- (2) In any such review, the electric utility has the burden of coming forward with justification for its data.

[45 FR 12234, Feb. 25, 1980; 45 FR 24126, Apr. 9, 1980]



Law about... Articles from Wex
Table of Popular Names
Parallel Table of Authorities

ACCESSIBILITY

ABOUT LII

CONTACT US

ADVERTISE HERE

HELP

TERMS OF USE

PRIVACY



172 FERC ¶ 61,041 UNITED STATES OF AMERICA FEDERAL ENERGY REGULATORY COMMISSION

18 CFR Parts 292 and 375

[Docket Nos. RM19-15-000 and AD16-16-000; Order No. 872]

Qualifying Facility Rates and Requirements

Implementation Issues Under the Public Utility Regulatory Policies Act of 1978
(Issued July 16, 2020)

AGENCY: Federal Energy Regulatory Commission.

ACTION: Final rule.

<u>SUMMARY</u>: In this Order, the Federal Energy Regulatory Commission issues its final rule approving certain revisions to its regulations implementing sections 201 and 210 of the Public Utility Regulatory Policies Act of 1978 (PURPA). These changes will enable the Commission to continue to fulfill its statutory obligations under sections 201 and 210 of PURPA.

<u>DATES</u>: This rule will become effective [INSERT DATE 120 DAYS AFTER THE DATE OF PUBLICATION IN THE FEDERAL REGISTER].

FOR FURTHER INFORMATION CONTACT:

Lawrence R. Greenfield (Legal Information)
Office of the General Counsel
Federal Energy Regulatory Commission
888 First Street, NE
Washington, DC 20426
(202) 502-6415
lawrence.greenfield@ferc.gov

Helen Shepherd (Technical Information) Office of Energy Market Regulation Federal Energy Regulatory Commission 888 First Street, NE Washington, DC 20426 (202) 502-6176 helen.shepherd@ferc.gov

Thomas Dautel (Technical Information)
Office of Energy Policy and Innovation
Federal Energy Regulatory Commission
888 First Street, NE
Washington, DC 20426
(202) 502-6196
thomas.dautel@ferc.gov

SUPPLEMENTARY INFORMATION:

172 FERC ¶ 61,041 UNITED STATES OF AMERICA FEDERAL ENERGY REGULATORY COMMISSION

Before Commissioners: Neil Chatterjee, Chairman; Richard Glick, Bernard L. McNamee, and James P. Danly.

Qualifying Facility Rates and Requirements Docket Nos. RM19-15-000

Implementation Issues Under the Public Utility Regulatory Policies Act of 1978 AD16-16-000

Order No. 872

FINAL RULE

(Issued July 16, 2020)

TABLE OF CONTENTS

<u>Paragraph Num</u>	bers
I. Introduction	<u>1.</u>
II. Overview	<u>5.</u>
A. The Commission's PURPA Regulations, as revised by this Final Rule, Continue	e to
Encourage the Development of QFs within the Requirements of PURPA's Statutor	У
Limitations	•
1. Avoided Cost Cap on QF Rates	
2. Limitation on Small Power Production Facilities Located at the Same "Site"	. 17.
3. Termination of Purchase Obligation for QFs With Nondiscriminatory Access	to
Certain Competitive Markets	<u>18.</u>
4. Final Rule's Updating of the PURPA Regulations	<u>20.</u>
B. The Final Rule Ensures that the Commission's Implementation of PURPA	
Continues to Benefit QFs, Purchasing Electric Utilities, and Electric Consumers	28.
C. The Commission is Not Eliminating Fixed Rate Pricing for QFs, But Rather is	
Giving States the Flexibility to Require the Same Variable Energy Rate/Fixed Capa	acity
Rate Construct that Applies Throughout the Electric Industry	. 35.
D. The Rate Changes Implemented by this Final Rule Put QF Rates on the Same	
Footing as Electric Utility Rates and Are Not Discriminatory	39.
E. The PURPA Compliance Issues Raised by Some Commenters Are Outside the	
Scope of this Rulemaking Proceeding	. 42.

III. Background	<u>47.</u>
A. Passage of PURPA in 1978 and the Commission's Promulgation of its PURPA	
Regulations in 1980	
B. Circumstances Leading to the Commission's Re-evaluation of the PURPA	
Regulations and the Issuance of the NOPR	<u>51.</u>
C. Summary of Changes to the PURPA Regulations Implemented by this final rule	e. <u>56.</u>
IV. Discussion	<u>67.</u>
A. General Legal Standards Under PURPA	67.
1. Encouragement of QFs	
a. Comments	68.
b. Commission Determination	<u>70.</u>
2. Discrimination	79.
a. Comments	79.
b. Commission Determination	<u>82.</u>
3. Unlawful Delegation and the Role of Nonregulated Electric Utilities	<u>89.</u>
a. Comments	<u>89.</u>
b. Commission Determination	<u>93.</u>
B. QF Rates	<u>96.</u>
1. Overview	<u>96.</u>
2. Use of Competitive Market Prices to Set As-Available Avoided Cost Rates	103.
a. NOPR Proposal	<u>104.</u>
b. Comments	<u>107.</u>
c. Commission Determination	
3. LMP as a Permissible Rate for Certain As-Available Avoided Cost Rates	<u>124.</u>
a. NOPR Proposal	<u>124.</u>
b. Comments	<u>129.</u>
i. Comments in Opposition	
(a) Utilizing Western EIM to Establish Avoided Costs	
ii. Comments in Support	
(a) Utilizing Western EIM to Establish Avoided Costs	
iii. Comments in Support with Requested Modifications/Clarifications	
c. Commission Determination	
i. Arguments Against the NOPR Proposal	
ii. Requests for Modification or Clarification of the NOPR	
iii. Western EIM	
4. Use of Market Hub Prices as a Permissible Rate for Certain As-Available QF	
Energy Sales	
a. NOPR Proposal	
b. Comments	
i. Comments in Support	
ii. Comments in Opposition	
iii. Commission Determination	189.

c. Proposed Modifications	. <u>195.</u>
i. Comments	. 195.
ii. Commission Determination	.200.
5. Use of Formulas Based on Natural Gas Prices to Establish a Permissible Rat	e for
Certain As-Available QF Energy Sales	. 203.
a. NOPR Proposal	
b. Comments	
c. Commission Determination	
6. Permitting the Energy Rate Component of a Contract to be Fixed at the Time	
the LEO Using Forecasted Values of the Estimated Stream of Market Revenue	
a. Comments	
b. Commission Determination	$.\overline{227}.$
7. Providing for Variable Energy Rates in QF Contracts	
a. Background	
b. NOPR Proposal	
c. General Comments on the NOPR Proposal	
i. Comments in Support of NOPR Proposal	.245.
ii. Comments in Opposition to NOPR Proposal	
iii. Commission Determination	
d. Whether the Current Approach Has Resulted in Payments to QFs in Exception	
Avoided Costs	
i. Comments in Support of NOPR Proposal	. <u>265.</u>
ii. Comments in Opposition to NOPR Proposal	. <u>272.</u>
iii. Commission Determination	. <u>283.</u>
e. Whether the Proposed Change Would Violate the Statutory Requirement	that
the PURPA Regulations Encourage QFs	. 294.
i. Comments	
ii. Commission Determination	. 295.
f. Discrimination	. <u>297.</u>
i. Comments in Support of NOPR Proposal	. <u>297.</u>
ii. Comments in Opposition to NOPR Proposal	. <u>298.</u>
iii. Commission Determination	
g. Effect of Variable Energy Rates on Financing	. 304.
i. Comments in Support of the NOPR Proposal	. 304.
ii. Comments in Opposition to the NOPR Proposal	
iii. Commission Determination	. 335.
h. Other Claimed Benefits of Fixed Avoided Cost Energy Rates	. 350.
i. Comments	. 350.
ii. Commission Determination	. 351.
i. Potential Modifications to NOPR Proposal	. 354.
i. Comments	
ii. Commission Determination	
8. Consideration of Competitive Solicitations to Determine Avoided Costs	. 361.

a. NOPR Proposal	<u>361.</u>
b. Comments	<u>368.</u>
i. Comments in Opposition	<u>368.</u>
ii. Comments in Support	375.
iii. Comments Requesting Modifications/Clarifications	383.
(a) Requests for Clarification and/or Separate Proceedings	
(b) Requests Regarding Proposed Criteria	
(c) Other Requests	
c. Commission Determination	411.
i. Requests for Clarification and/or Separate Proceedings	415.
ii. Proposed Criteria	
iii. Other Requests	439.
C. Relief from Purchase Obligation in Competitive Retail Markets	442.
1. NOPR Proposal	442.
2. Comments	<u>444.</u>
3. Commission Determination	<u>456.</u>
D. Evaluation of Whether QFs are at Separate Sites	<u>458.</u>
1. Rebuttable Presumption of Separate Sites	<u>458.</u>
a. NOPR Proposal	<u>458.</u>
b. Commission Determination	<u>466.</u>
c. Need for Reform	<u>470.</u>
i. Comments	
ii. Commission Determination	<u>472.</u>
d. Site Definition	<u>473.</u>
i. Comments	
ii. Commission Determination	
e. Distance Between Facilities	<u>482.</u>
i. Comments	<u>482.</u>
ii. Commission Determination	<u>490.</u>
f. Factors	<u>497.</u>
i. Comments	
ii. Commission Determination	<u>508.</u>
g. Exemptions	<u>512.</u>
i. Comments	<u>512.</u>
ii. Commission Determination	<u>514.</u>
2. Electrical Generating Equipment	<u>515.</u>
a. NOPR Proposal	<u>515.</u>
b. Comments	
c. Commission Determination	<u>521.</u>
E. QF Certification Process.	<u>525.</u>
1. NOPR Proposal	<u>525.</u>
2. Comments	
3. Commission Determination	<u>547.</u>

F. Corresponding Changes to the FERC Form No. 556	. <u>570.</u>
1. NOPR Proposal	. <u>570.</u>
2. Comments	. 577.
3. Commission Determination	. 584.
G. PURPA Section 210(m) Rebuttable Presumption of Nondiscriminatory Access	to
Markets	. <u>597.</u>
1. PURPA Section 210(m) Implementation	
a. NOPR Proposal	
b. Comments in Opposition	
i. Insufficient Evidentiary Support	. 603.
ii. Administrative Burden and Complex Market Rules	. <u>611.</u>
c. Comments in Support	
d. Comments Requesting Modifications/Clarifications	. <u>617.</u>
e. Commission Determination	
2. Reliance on RFPs and Liquid Market Hubs to Terminate Purchase Obligation	n
Under PURPA Section 210(m)	. <u>648.</u>
a. NOPR Discussion	. <u>648.</u>
b. Comments	. <u>651.</u>
i. Comments in Opposition	. <u>651.</u>
ii. Comments in Support	. <u>655.</u>
c. Commission Determination	. <u>659.</u>
H. Legally Enforceable Obligation	. <u>663.</u>
1. NOPR Proposal	. <u>663.</u>
2. Comments	. <u>666.</u>
a. Comments in Opposition	. <u>666.</u>
b. Comments in Support	. <u>673.</u>
c. Comments Requesting Modification	. <u>676.</u>
i. Studies	
ii. Commercial Viability	. <u>679.</u>
iii. Financial Viability	. <u>681.</u>
iv. Rejecting QF Purchases and Expanded Curtailment Rights	
3. Commission Determination	. <u>684.</u>
V. Information Collection Statement	. <u>697.</u>
/I. Environmental Analysis	. 702.
A. Comments	
B. Commission Determination	
1. No EIS or EA is Required	
a. There is no Project that Defines the Scope and Limits of QF Development	
b. A Categorical Exclusion Applies	
i. Changes that are Clarifying in Nature	
ii. Changes that are Corrective in Nature	
iii. Changes that are Procedural in Nature	

2. The NEPA Analysis for Promulgation of the Original PURPA Regulations in	
1980 Cannot be Replicated Here	728 .
3. This Proceeding Does Not Trigger Any ESA Consultation Requirement	<u>737.</u>
VII. Regulatory Flexibility Act Certification	<u>743.</u>
VIII. Document Availability	<u>750.</u>
IX. Effective Dates and Congressional Notification	753 .

I. Introduction

- 1. In this Order, the Federal Energy Regulatory Commission (Commission) issues its final rule approving certain revisions to its regulations (PURPA Regulations)¹ implementing sections 201 and 210 of the Public Utility Regulatory Policies Act of 1978 (PURPA).²
- 2. On September 19, 2019, the Commission issued a notice of proposed rulemaking (NOPR) proposing to modify its PURPA Regulations.³ Those regulations were promulgated in 1980 and have been modified in only specific respects since then. Approximately 130 separate comments were submitted in response to the NOPR,⁴ several of which were submitted on behalf of multiple parties. In total, over 1,600 pages of comments were submitted, and in addition thousands of pages of exhibits were attached to the comments. The entities that filed comments are listed in Appendix A. This final rule addresses comments received in response to the NOPR.
- 3. We largely adopt the NOPR proposals. However, this final rule makes certain modifications to the NOPR proposals, as further discussed below.

¹ 18 CFR pt. 292 (2019). In connection with the revisions to the PURPA Regulations, the Commission also is revising its delegation of authority to Commission staff in 18 CFR pt. 375.

² 16 U.S.C. 796(17)-(18), 824a-3.

³ Qualifying Facility Rates and Requirements Implementation Issues Under the Public Utility Regulatory Policies Act of 1978, 168 FERC ¶ 61184 (2019) (NOPR).

⁴ See Appendix for list of commenters.

- 4. Given the Commission's expressed intent in the NOPR to propose revisions to the PURPA Regulations that more closely adhere to the goals and terms of PURPA,⁵ we considered comments regarding whether these proposals are consistent with the requirements of PURPA. Based on that review and further consideration, we adopt the following changes to the proposals in the NOPR, among certain others described below:
 - we establish a rebuttable presumption, rather than a per se rule, that locational marginal prices (LMPs) may reflect a purchasing electric utility's avoided energy costs;
 - we provide that any competitive solicitations used to establish avoided capacity costs must adhere to the Commission's *Allegheny*⁶ standard for evaluating competitive solicitations;
 - we do not adopt the proposed rule permitting states with retail competition to allow relief from the purchase obligation but instead clarify that the Commission's existing PURPA Regulations already require that states, to the extent practicable, must account for reduced loads in setting QF capacity rates;
 - we clarify terminology we used in the NOPR relating to the determination of whether small power production facilities are separate facilities to focus not on whether they are *separate facilities*, but rather to mirror the statutory language and thus focus on whether they are at "the same site";
 - we clarify in the regulations that protests may be made to initial selfcertifications and applications for Commission certification, but only to selfrecertifications and applications for Commission recertification making substantive changes to the existing certification;
 - we identify additional factors that can be considered for small power production qualifying facilities (QFs) located more than one but less than 10 miles apart, such as evidence of shared control systems, common permitting and land leasing, and shared step-up transformers;

⁵ NOPR, 168 FERC ¶ 61,184 at P 31.

 $^{^6}$ Allegheny Energy Supply Co., LLC, 108 FERC \P 61,082, at P 18 (2004) (Allegheny).

- we revise the regulations to lower the rebuttable presumption of small power production QFs' nondiscriminatory access to 5 MW, rather than 1 MW as proposed in the NOPR, and include factors that a small power production QF sized greater than 5 MW could rely on to rebut the presumption that it has nondiscriminatory access to markets defined in PURPA sections 210(m)(1); and
- we revise the proposed requirements to establish a legally enforceable obligation (LEO) to provide that with regard to the issue of obtaining permits, QFs need only have applied for all required permits, instead of being required to have already obtained those permits.

II. Overview

- 5. Before discussing each of the individual changes to the PURPA Regulations adopted herein, this final rule first addresses certain overall themes raised in the comments on the NOPR, both those supporting the NOPR and those opposing.
 - A. The Commission's PURPA Regulations, as revised by this Final Rule,
 Continue to Encourage the Development of QFs within the
 Requirements of PURPA's Statutory Limitations
- 6. PURPA section 210(a) requires that the Commission prescribe rules that it determines necessary to encourage the development of qualifying small power production facilities and cogeneration facilities.
- 7. The bulk of the criticism of the Commission's proposed rule changes is based on a widespread misunderstanding, as reflected in the comments on the NOPR, that PURPA and the PURPA Regulations were intended to encourage QF development without any limit, and that the rule changes proposed in the NOPR improperly reduce or even eliminate encouragement in contravention of the statute. Those commenters opposing the NOPR proposals argue that the Commission has determined, in contravention of the statute, that there no longer is a need to encourage QFs, or eliminated any provision that

provides such encouragement.⁷ Many of the commenters supporting the changes proposed in the NOPR applaud the Commission for eliminating what they argue amounts to an improper subsidy of QFs.⁸

- 8. Neither side is correct about either what PURPA and the current PURPA Regulations require, or the basis for the changes to the PURPA Regulations proposed in the NOPR.
- 9. As an initial matter, PURPA was not a directive to the Commission to encourage QF development without limitation. Indeed, as explained below, Congress included several limitations in PURPA. By reading the statute as a whole, and the PURPA Regulations as a whole as revised by this final rule, it is clear that the PURPA Regulations continue to encourage the development of QFs consistent with PURPA.
- 10. We also emphasize that we do not by this final rule change other elements to the Commission's existing PURPA Regulations that continue to encourage QF development. These elements include, but are not limited to, rules that: (1) require electric utilities to provide backup electric energy to QFs on a non-discriminatory basis and at just and

⁷ See, e.g., Biological Diversity Comments at 14; ConEd Development Comments at 2; Harvard Electricity Law Comments at 4; New England Small Hydro Comments at 4; NIPPC, CREIA, REC, and OSEIA Comments at 3, 21, 28; Public Interest Organizations Comments at 9, 39; Solar Energy Industries Comments at 4; Southeast Public Interest Organizations Comments at 17.

⁸ See Competitive Enterprise Institute Comments at 3; Progressive Policy Institute Comments at 1-2; SBE Council Comments at 2; Mr. Moore Comments at 1-2.

⁹ 16 U.S.C. 824a-3(a).

reasonable rates; (2) require electric utilities to interconnect with QFs; and (3) provide exemptions to QFs from many provisions of the Federal Power Act (FPA) and state laws governing utility rates and financial organization. ¹⁰ These provisions encourage the development of QFs by relieving them of certain regulatory burdens otherwise imposed on sellers of power and ensure they can operate their facilities. Moreover, we stress that, besides the changes to the PURPA Regulations regarding applications to terminate a purchasing electric utility's mandatory purchase obligation under PURPA section 210(m) (see *infra* section IV.G), nothing in this final rule eliminates QFs' rights to sell electric energy or capacity as provided under PURPA.

11. As discussed in greater detail below, while PURPA provided for the encouragement of cogeneration and small power production, PURPA also provided that the Commission could not prescribe a rule that provided for "a rate which exceeds the incremental cost to the electric utility of alternative electric energy." Furthermore, PURPA requires the Commission to "insure" that the resulting rates "shall be just and reasonable to the electric consumers of the electric utility and in the public interest[.]" Likewise, while PURPA provided for the encouragement of small power production,

¹⁰ See 18 CFR 292.303(c), 292.305, 292.601-02.

¹¹ Compare id. with 16 U.S.C. 824a-3(b).

¹² 16 U.S.C. 824a-3(b)(1).

PURPA also limited the facilities which could be encouraged to those facilities with no more than 80 MW power production capacity at the same site.¹³

12. Nothing in the text of PURPA requires the establishment of a subsidy for QFs.

This point was confirmed in the Conference Report accompanying PURPA's passage:

"The provisions of this section are not intended to require the rate payers of a utility to subsidize cogenerators or small power producers." Congress thus structured PURPA both specifically to give effect to its intent that QFs not be subsidized and also to impose other mandatory limits on the Commission's ability to encourage QFs that are relevant to this final rule, as briefly summarized below.

1. Avoided Cost Cap on QF Rates

13. PURPA section 210(b) sets out the standards governing the rates purchasing utilities must pay to QFs. ¹⁵ Sections 210(b)(1) and (b)(2) provide that QF rates "shall be just and reasonable to the electric consumers of the electric utility and in the public interest" and "shall not discriminate against qualifying cogenerators or qualifying small power producers." ¹⁶ After establishing these standards, Congress then placed, in the final sentence of section 210(b), a cap on the level of the rates utilities could be required to pay QFs: "No such rule prescribed under subsection (a) *shall provide for a rate which exceeds*

¹³ Compare 16 U.S.C. 824a-3(a) with 16 U.S.C. 796(17)(A)(ii).

¹⁴ H.R. Rep. No. 95-1750, at 98 (1978) (Conf. Rep.).

¹⁵ 16 U.S.C. 824a-3(b).

¹⁶ *Id*.

the incremental cost to the electric utility of alternative electric energy."¹⁷ As the Conference Report for PURPA explains:

[T]he utility would not be required to purchase electric energy from a qualifying cogeneration or small power production facility at a rate which exceeds the lower of the rate described above, namely a rate which is just and reasonable to consumers of the utility, in the public interest, and nondiscriminatory, or the incremental cost of alternate electric energy. This limitation on the rates which may be required in purchasing from a cogenerator or small power producer is meant to act as an upper limit on the price at which utilities can be required under this section to purchase electric energy. ¹⁸

- 14. This upper limit on QF rates established in section 210(b), equal to a purchasing utility's incremental costs, commonly called "avoided costs," implements Congress's intent that QFs not be subsidized. It ensures that the purchasing utility cannot be required to pay more for power purchased from a QF than it would otherwise pay to generate the power itself or to purchase power from a third party.
- 15. Consistent with the statutory standard, when the Commission issued its PURPA Regulations in 1980, it set the rates for QFs at, but not above, the statutorily defined incremental or avoided cost of alternative electric energy.¹⁹ The PURPA Regulations

¹⁷ *Id.* (emphasis added). The statute defines an electric utility's "incremental costs" as "the cost to the electric utility of the electric energy which, but for the purchase from such cogenerator or small power producer, such utility would generate or purchase from another source." 16 U.S.C. 824a-3(d); *see also* 18 CFR 292.101(b)(6) (implementing same and defining such "incremental costs" as "avoided costs").

¹⁸ Conf. Rep. at 98 (emphasis added).

 $^{^{19}}$ Compare 16 U.S.C. 824a-3(b) & (d) with 18 CFR 292.101(b)(6), 292.304(a)(2) & (b)(2).

applied this limitation generally to QF rates, without distinguishing between as-available energy ²⁰ and the fixed energy and capacity rate option applicable to long-term contracts or other legally enforceable obligations. ²¹ In either case, though, the PURPA Regulations essentially capped the rate paid to QFs at the purchasing electric utility's avoided costs. ²² 16. Order No. 69, in which the Commission promulgated the PURPA Regulations, ²³ makes clear that the Commission also recognized that allowing the option for a fixed energy and capacity rate option for long-term contracts or other legally enforceable obligations could result in a rate that, at times, exceeded incremental or avoided cost of alternative electric energy. The Commission acknowledged in this regard that some commenters had asserted that, "if the avoided cost of energy at the time it is supplied is less than the price provided in the contract or obligation, the purchasing utility would be

²⁰ 18 CFR 292.304(d)(1).

²¹ 18 CFR 292.304(d)(2) (providing QFs the right to elect avoided costs calculated at the time of delivery or avoided costs calculated at the time the obligation is incurred). In this final rule, we refer to the QF's option for avoided costs calculated at the time the obligation is incurred as the fixed energy and capacity rate option. 18 CFR 292.304(d)(2).

²² The regulations, however, also allowed both for negotiated rates that differed from the rates that would otherwise be applicable, *see* 18 CFR 292.301(b), and for rates to be set based on estimates of avoided costs even though such rates might differ from avoided costs at the time of delivery. *See* 18 CFR 292.304(b)(5).

Section 210 of the Public Utility Regulatory Policies Act of 1978, Order No. 69, FERC Stats. & Regs. ¶ 30,128, at 30,880 (cross-referenced 10 FERC ¶ 61,150), order on reh'g, Order No. 69-A, FERC Stats. & Regs. ¶ 30,160 (1980) (cross-referenced at 11 FERC ¶ 61,166), aff'd in part & vacated in part sub nom. Am. Elec. Power Serv. Corp. v. FERC, 675 F.2d 1226 (D.C. Cir. 1982), rev'd in part sub nom. Am. Paper Inst., Inc. v. Am. Elec. Power Serv. Corp., 461 U.S. 402 (1983) (API).

required to pay a rate for purchases that would subsidize the qualifying facility at the expense of the utility's other ratepayers."²⁴ In response, the Commission stated that it "recognize[d] this possibility, but is cognizant that in other cases, the required rate will turn out to be lower than the avoided cost at the time of purchase."²⁵ The Commission concluded that any over- and under-recoveries compared to avoided cost "will balance out" and, based on this conclusion, found that the fixed energy and capacity rate option applicable to long-term contracts or other legally enforceable obligations did not violate the statutory cap.²⁶ But, to be clear, the option the Commission implemented in 1980 was not based on any determination by the Commission that the rates in QF contracts may routinely exceed avoided costs in the ordinary course of events in order to encourage QFs.

2. <u>Limitation on Small Power Production Facilities Located at the Same "Site"</u>

17. Another way in which Congress set boundaries on the Commission's ability to encourage development of QFs was to define small power production facilities, one of the categories of generators that under the statute is to be encouraged. The definition of small power production facilities applies to almost all renewable resources that wish to be QFs, requiring that those facilities have "a power production capacity which, together with any other facilities located at the same site (as determined by the Commission), is not greater

²⁴ Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,880.

²⁵ *Id*.

²⁶ *Id*.

than 80 megawatts."²⁷ In order to comply with this statutory requirement that the capacity of all small power production facilities "located at the same site" cannot exceed 80 MW, the Commission is required to define what constitutes a "site." The Commission determined in 1980 that, essentially, those facilities that are owned by the same or affiliated entities and using the same energy resource should be deemed to be at the same site "if they are located within one mile of the facility for which qualification is sought."²⁸ This definition, known as the "one-mile rule," interpreted Congress's limitation of 80 MW located at the same site to apply to just those affiliated small power production qualifying facilities located within one mile of each other.

3. <u>Termination of Purchase Obligation for QFs With</u> Nondiscriminatory Access to Certain Competitive Markets

- 18. Finally, Congress amended PURPA in 2005 to further limit the statute. Congress amended PURPA section 210 to add section 210(m), which provides for termination of the requirement that an electric utility enter into a new obligation or contract to purchase from a QF if the QF has nondiscriminatory access to certain defined types of markets.²⁹ This amendment reflected Congress's judgment that non-discriminatory access to these markets provided adequate encouragement for those QFs.
- 19. Congress directed the Commission to implement this requirement, which it did in Order No. 688. In that order, the Commission identified certain markets in which utilities

²⁷ 16 U.S.C. 796(17)(A)(ii).

²⁸ 18 CFR 292.204(a)(ii).

²⁹ See 16 U.S.C. 824a-3(m).

would no longer be subject to the PURPA mandatory purchase obligation under PURPA section 210(m) because certain QFs have nondiscriminatory access to such markets.³⁰
Although not required in the new PURPA section 210(m), the Commission established a rebuttable presumption that a QF with a net power production capacity at or below 20 MW does *not* have nondiscriminatory access to such markets.³¹ In creating this rebuttable presumption, the Commission found persuasive arguments that some QFs may not have nondiscriminatory access to markets in light of their small size.

4. Final Rule's Updating of the PURPA Regulations

20. In this final rule, we are amending the PURPA Regulations, principally with regard to the three statutory provisions described above, i.e.: (1) the avoided cost cap on QF rates; (2) the 80 MW limitation applicable to the combined capacity of affiliated small power production QFs located at the same site; and (3) the termination of the mandatory purchase obligation for QFs with nondiscriminatory access to certain markets. Contrary to commenters' assertions that the Commission has determined that it no longer is necessary to encourage QFs and therefore that the Commission is making these changes in an impermissible attempt to undo PURPA,³² we are modifying the PURPA Regulations

³⁰ New PURPA Section 210(m) Regulations Applicable to Small Power Production and Cogeneration Facilities, Order No. 688, 117 FERC ¶ 61,078, at PP 9-12 (2006), order on reh'g, Order No. 688-A, 119 FERC ¶ 61,305 (2007), aff'd sub nom. Am. Forest & Paper Ass'n v. FERC, 550 F.3d 1179 (D.C. Cir. 2008).

³¹ 18 CFR 292.309(d)(1).

³² Biomass Power Comments at 2; Biological Diversity at 12; EPSA Comments at 6 ("[T]he NOPR changes 'would effectively gut' PURPA."); NIPPC, CREA, REC, and OSEIA Comments at 28-29; Public Interest Groups Comments at 25 ("[T]he changes

based on demonstrated changes in circumstances since the current PURPA Regulations were first adopted to ensure that the regulations continue to comply with PURPA's statutory requirements established by Congress.

- 21. For example, as explained in more detail below, the Commission's expectation expressed in 1980 that over- and under-recovery in rates compared to avoided cost "will balance out" was critical to the Commission's determination in 1980 that the fixed energy and capacity rate option applicable to long-term contracts or other legally enforceable obligations did not violate the statutory avoided cost cap on QF rates.

 However, record evidence now demonstrates that this expectation no longer is necessarily accurate. The Commission's change to the PURPA Regulations adopted in this final rule, giving states the ability to require variable energy rates in long-term contracts or other legally enforceable obligations, allows the states to better ensure that QF rates are at, but do not exceed, the statutory maximum rate established by Congress.
- 22. This change is important for purposes of compliance with PURPA's statutory mandates. As explained below, setting QF rates at avoided costs allows the Commission to comply with the statutory goals of encouraging QFs and providing for nondiscriminatory rates while at the same time ensuring that such rates are just and reasonable to consumers and do not subsidize QFs. The record shows that on some

proposed in the NOPR will gut PURPA-mandated measures to encourage QF development."); Solar Energy Industries Comments at 8-14.

³³ Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,880.

occasions long-term fixed QF rates were well above actual avoided costs, thereby causing consumers to subsidize those QFs in contravention of PURPA and the Commission's expectations.

- 23. Similarly, the changes implemented by the Commission in this final rule to the one-mile rule are intended to better ensure compliance with the statutory requirement that small power production facilities located at the same site cannot exceed 80 MW. And, 15 years after Congress added PURPA section 210(m), because the Commission can now make the determination, described below, that smaller QFs have non-discriminatory access to RTO/ISO markets, an update to the rebuttable presumption regarding non-discriminatory access to those markets is appropriate to better ensure compliance with the statute.
- 24. Some commenters incorrectly assert that the final rule impermissibly revises the PURPA Regulations in a way that no longer encourages QFs. PURPA section 210(a) provides not simply that the Commission is to prescribe rules that encourage QFs, but rather that the Commission is to "prescribe, and from time to time thereafter revise, such rules as it determines necessary to encourage" QFs. Carrying out Congress's directive to "from time to time thereafter revise" the rules is at the heart of what the Commission is doing in this final rule. Consistent with this directive, the Commission is considering revisions to "such rules as it determines necessary to" encourage QFs in light of current industry circumstances.³⁴

³⁴ We view the revisions to our rules implementing PURPA that we adopt in this final rule as consistent with Congress's explicit directive that the Commission "from time

- 25. The changes adopted in this final rule result from the need for the PURPA Regulations to continue to comply with the directives Congress established when it enacted PURPA in 1978, and then again when Congress amended PURPA in 2005. These changes are not based on any determination by the Commission that the encouragement directed by PURPA is no longer needed. The question of whether QFs should continue to be encouraged or not remains a question for Congress.
- 26. Moreover, PURPA also requires the Commission to insure that the rates for QF purchases be "just and reasonable to the electric consumers of the electric utility and in the public interest[.]"³⁵ The obligation to encourage is also limited by the requirement that, "No such rule prescribed under subsection (a) [the encouragement provision] shall provide for a rate which exceeds the incremental cost to the electric utility of alternative electric energy."³⁶
- 27. We recognize that some of the comments opposing the NOPR may have been influenced by the Commission's recitation in the Background section of the NOPR of the broad changes in circumstances since the PURPA Regulations were first promulgated 40 years ago, including the discovery of significant new natural gas reserves, the evolution of the electric industry to include a significant independent power presence, the

to time thereafter [to] revise" the rules. We do not view Congress as intending that the Commission only ever consider the circumstances that existed in the late 1970s and not current circumstances, 40 years later.

³⁵ 16 U.S.C. 824a-3(b).

³⁶ 16 U.S.C. 824a-3(b).

establishment of organized competitive markets, and the advances in renewable energy technologies.³⁷ We clarify that the Commission referenced this general background information in the NOPR primarily to explain why it decided to re-evaluate its PURPA Regulations at all and as Congress said we should, and not necessarily to support the individual proposals included in the NOPR. The facts we rely on to propose specific changes, which include some, but not all, of those background facts, were cited in the specific sections of the NOPR describing those proposed changes. And the facts on which we rely to promulgate the specific changes in this final rule again are cited in the specific sections describing those changes.

- B. The Final Rule Ensures that the Commission's Implementation of PURPA Continues to Benefit QFs, Purchasing Electric Utilities, and Electric Consumers
- 28. The final rule implements additional changes consistent with PURPA that also are designed to benefit QFs, purchasing utilities, and electric consumers. The changes to the PURPA Regulations adopted in this final rule will enable the Commission to continue satisfying the statutory requirement that the Commission promulgate rules to encourage QF development consistent with PURPA's requirements. Claims to the contrary by commenters to the effect that the "proposals are uniformly biased against QF development" have no merit.

³⁷ NOPR, 168 FERC ¶ 61,184, at PP 15-27.

³⁸ Harvard Electricity Law Comments at 1.

- 29. As an initial matter, we are not changing the determination in the PURPA Regulations that QF rates must equal a purchasing electric utility's full avoided costs.³⁹
 As the Supreme Court noted in *API*, the full avoided cost rate requirement represents the maximum rate permitted under PURPA, and thereby provides important encouragement to QFs.⁴⁰ The Court explained that the full avoided cost rate requirement encourages QF development because QFs "retain an incentive to produce energy under the full-avoided-cost rule so long as their marginal costs did not exceed the full avoided cost of the purchasing utility."⁴¹
- 30. In addition, several of the changes to the current PURPA Regulations implemented by this final rule are based expressly on a finding that they are beneficial to QFs as well as to purchasing utilities and ratepayers. For example, the provisions of the final rule allowing for energy rates to be based on transparent, competitive market prices—in appropriate circumstances—are supported by comments submitted at the Technical Conference, where representatives of QFs and utilities both expressed a preference for

³⁹ See 18 CFR 292.304(b)(2); NOPR, 168 FERC ¶ 61,184 at P 34.

⁴⁰ API, 461 U.S. at 413. PURPA does not use the terms "avoided cost" or "full avoided cost"; rather, PURPA uses the term "incremental cost of alternative electric energy." The Commission's regulations and subsequent decisions have used the term "avoided cost" to explain the Commission's application of the "incremental cost" standard. The API decision and early Commission precedents referred to "full" avoided costs to distinguish between the Commission's decision to set QF rates at avoided costs and proposals from certain parties that rates be set at something less than avoided costs. We continue to use the terms avoided costs and full avoided costs as being consistent with the statutory term incremental cost.

⁴¹ *Id.* at 416.

transparent prices for QFs.⁴² This conclusion is supported by the Fitch Report, cited by NIPPC, CREA, REC, and OSEIA, explaining how Fitch evaluates the financial strength of renewable energy projects. In this report, Fitch states that it gives a "stronger" evaluation to projects with power sales contract prices that are "indexed using simple, broad-based publicly available indexation formulas."⁴³

31. Setting prices that are indexed using simple, broad-based publicly available formulas is precisely what the Commission's changes permitting reference to competitive market prices will achieve. Such prices reflect avoided costs in a simpler, more transparent, and predictable manner than through an administrative process, which should encourage the development of QFs while at the same time providing benefits to utilities and consumers. Using transparent market prices to establish as-available avoided cost rates also allows QFs, utilities, and the states to avoid the expenditure of the time and resources involved in litigating administratively-set avoided cost rates, and allows those rates to automatically adjust—up and down—as avoided costs change.

⁴² See American Forest & Paper Association, Comments, Docket No. AD16-16-000, at 8 (filed June 8, 2016) ("To the extent possible, these determinations [of avoided costs] should not be made in a 'black box', but rather, as part of an open and transparent method and process."); Edison Electric Institute (EEI) Comments, Docket No. AD16-16-000, at 3 (filed June 30, 2016) ("Where transparent competitive markets with day ahead prices exist, there is no reason to adhere to second-best avoided cost pricing mechanisms.").

⁴³ NIPPC, CREA, REC, and OSEIA Comments at 37-38 (citing FitchRatings, Global Infrastructure & Project Finance, *Renewable Energy Project Rating Criteria*," at 3 (Feb. 26, 2019), https://www.fitchratings.com/site/re/10061770).

- 32. Similarly, the provisions regarding competitive solicitations adopted herein were added at the suggestion of both NARUC and certain developers of renewable resource QFs, such as Solar Energy Industries. These competitive solicitations can provide a fair and transparent method for QFs to establish full avoided cost rates. As Solar Energy Industries stated in its comments, "[c]ompetitive solicitations, with adequate safeguards, can deliver substantial value." Competitive solicitations may be an especially appropriate tool in those regions outside of Regional Transmission Organizations (RTOs) and Independent System Operators (ISOs) where there are no organized competitive markets where QFs can make sales.
- 33. Likewise, the LEO provisions adopted herein provide important benefits to QFs.

 Under the current PURPA Regulations, a LEO gives QFs the enforceable right to require utilities to purchase the QFs' power at avoided cost rates. This is an important right that contributes to a QF owner's ability to obtain financing, especially the development financing needed to engage in the activities necessary to subsequently obtain construction

⁴⁴ Solar Energy Industries Comments at 38. Solar Energy Industries agreed that the competitive solicitation provisions proposed in the NOPR "set forth many important safeguards," but recommended that additional safeguards be implemented. Those comments are discussed below, and we have specifically adopted Solar Energy Industries request made earlier in this proceeding that all competitive solicitations must be conducted pursuant to the Commission's *Allegheny* standard. *See* Solar Energy Industries Supplemental Comments, Docket No. AD16-16-000, at 32-34 (filed Aug. 28, 2019).

⁴⁵ See 18 CFR 292.304(d)(2). Although the final rule gives states the flexibility to require that energy rates vary over the term of the LEO and be calculated at the time of delivery, the final rule retains the QF's option to choose a fixed capacity rate calculated at the time the LEO is established.

and permanent financing. However, the PURPA Regulations are silent as to when and how a LEO is established, which can leave QFs uncertain as to when this key right has been established. By providing more specific guidance as to when a LEO is established, the new rule creates greater certainty for QFs (and utilities) on this important element of OF development.

34. Some commenters assert that the guidance provided by the Commission may make it more difficult to obtain a LEO.⁴⁶ Their specific concerns are discussed in detail below. But what those commenters ignore is that, by establishing objective and reasonable state-determined criteria limited to demonstrating commercial viability and financial commitment, we also are protecting QFs against onerous requirements for a LEO that hinder financing, such as a requirement for a utility's execution of an interconnection

⁴⁶ See NIPPC, CREA, REC, and OSEIA Comments at 81 ("[A]ny requirement to demonstrate financing to create a LEO violates the fundamental rule that the utility's actions should not be allowed to deny the QF a LEO because the utility could prevent creation of a LEO simply by refusing to sign the PPA needed to secure such financing."); Public Interest Organizations Comments at 98 ("[T]he Commission's proposal to require QFs to demonstrate commercial viability in order to obtain a LEO will prevent many QFs from ever attaining commercial viability at all. Creating a new administrative obstacle to QF financing in this way flies in the face of PURPA's mandate to reduce barriers to QF development."); Solar Energy Industries Comments at 41 ("Establishing higher barriers to a determination of 'commercial viability' will only lead QF developers to invest additional development capital and will simply weed out those smaller companies that choose not to, or are unable to, invest heavily in early-stage development activity before an avoided cost rate is known. It is unjust and unreasonable to cause QFs to invest tens of millions of dollars in site control, permit acquisition, interconnection, and other development costs simply to secure the opportunity to negotiate with the purchasing utility for a contractual commitment."); Southeast Public Interest Organizations Comments at 41 (describing proposal as "discourag[ing] QF development since achieving some of the indicia suggested by the Commission often circularly requires that QF developers have already obtained financing").

agreement⁴⁷ or power purchase agreement,⁴⁸ or requiring that QFs file a formal complaint with the state commission,⁴⁹ or limiting LEOs to only those QFs capable of supplying firm power,⁵⁰ or requiring the QF to be able to deliver power in 90 days.⁵¹ By making clear in the PURPA Regulations that such conditions are not permitted, but describing which prerequisites a state may impose to establish a LEO to determine which QFs are commercially viable and financially committed, we are providing objective criteria to clarify when a LEO commences, which we find will encourage the development of QFs.

- C. The Commission is Not Eliminating Fixed Rate Pricing for QFs, But Rather is Giving States the Flexibility to Require the Same Variable Energy Rate/Fixed Capacity Rate Construct that Applies Throughout the Electric Industry
- 35. Another misconception reflected in several comments is that the Commission proposed in the NOPR to eliminate fixed rate pricing for QFs. Commenters argue that QFs cannot obtain financing without fixed rates, and from this they claim that the proposal

⁴⁷ See, e.g., FLS Energy, Inc., 157 FERC ¶ 61,211, at P 26 (2016) (FLS) (stating that requiring signed interconnection agreement as prerequisite to LEO is inconsistent with PURPA Regulations).

⁴⁸ See, e.g., Murphy Flat Power, LLC, 141 FERC ¶ 61,145, at P 24 (2012) (finding that requiring a signed and executed contract with an electric utility as a prerequisite to a LEO is inconsistent with PURPA Regulations.

⁴⁹ See, e.g., Grouse Creek Wind Park, LLC, 142 FERC ¶ 61,187, at P 40 (2013).

⁵⁰ Exelon Wind 1, L.L.C. v. Nelson, 766 F.3d 380, 400 (5th Cir. 2014).

⁵¹ Power Resource Group, Inc. v. Public Utility Comm'n of Texas, 422 F.3d 231, (5th Cir. 2005).

to give states the flexibility to require variable energy rates would have a devastating effect on future QF development.⁵²

- 36. This assertion that the Commission has eliminated fixed rates for QFs is not correct. The NOPR proposal (which we adopt in this final rule) gave states the flexibility, should they choose to take advantage of this flexibility, to require that the avoided cost *energy* rates in QF contracts must vary depending on avoided costs at the time of delivery (rather than being fixed at the time a LEO is incurred). The NOPR thus made clear: "under the proposed revisions to § 292.304(d), a QF would continue to be entitled to a contract with avoided *capacity* costs calculated and fixed at the time the LEO is incurred." We are retaining in this final rule the option granted to QFs to fix their capacity rates for the term of their contracts at the time the LEO is incurred.
- 37. The fact that we are giving states the flexibility to either require QF contracts to have fixed capacity and variable energy rates or to continue as before to provide QFs the option of fixed capacity and fixed energy rates has important consequences for the ability of QF owners to finance their projects. The energy rates of purchasing electric utilities, upon which avoided cost energy rates would be based, typically reflect mainly the variable costs of producing energy, such as the cost of fuel and variable operations and

⁵² See, e.g., Public Interest Organizations Comments at 35-38 (allowing variable rates will further discourage wind and solar QF development); Alloo Comments at 9-11 (without the ability to obtain a fixed long-term forecasted rate, QF solar energy development will not exist).

⁵³ See NOPR, 168 FERC ¶ 61,184 at P 66.

maintenance (O&M), especially for a fossil fuel generator. Meanwhile, a purchasing electric utility's capacity rates, upon which avoided cost capacity rates would be based, tend to reflect fixed costs, including the financing costs of facilities (i.e., debt repayment and a return on the equity invested in the facility). Consequently, a fixed capacity rate in a QF contract based on a purchasing electric utility's capacity rates should typically be sufficient to recover the QF's financing costs and should therefore continue to facilitate QF financing. We recognize that a QF's financing costs may be different from the purchasing electric utility's avoided costs and, therefore, the full avoided cost rate that the QF receives may not support the financing of a QF. But this is a consequence of how Congress structured PURPA, which sets rates based on the avoided costs of the purchasing utility rather than on the actual costs the QF incurs producing the power being sold. 55

38. Another important aspect of the variable energy rate/fixed capacity rate construct is that this is the standard rate structure used throughout the electric industry for power sales agreements that include the sale of capacity.⁵⁶ That states will be allowed to require QF

⁵⁴ See Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,865.

⁵⁵ See API, 461 U.S. at 414, 415 (stating that "Congress did not intend to impose traditional ratemaking concepts on sales by qualifying facilities to utilities" and that QFs "would retain an incentive to produce energy under the full-avoided-cost rule so long as their marginal costs did not exceed the full avoided cost of the purchasing utility").

⁵⁶ Cf. Town of Norwood v. FERC, 962 F.2d 20, 21, 24 (D.C. Cir. 1992) ("The rate design before us, like most wholesale electric rates, consists of separate monthly demand and energy charges. The demand component is calculated to recover NEPCO's fixed (or capacity-related) costs, such as construction and debt service, which it incurs regardless of how much electricity it produces. The energy charge is designed to recover the

contracts to be structured similarly to the contract structure used in the rest of the electric industry has important implications. In particular, this provides flexibility to states to ensure that the avoided cost rate will be closer to the actual rate the purchasing electric utility and its customers would have paid if the purchasing electric utility had generated this electric energy itself or purchased such electric energy from another source.

Furthermore, the record evidence demonstrating significant amounts of non-QF generation facilities in operation today shows that the owners of such facilities are able to obtain financing based on this same variable energy rate/fixed capacity rate construct. This represents important evidence that QFs likewise should be able to obtain financing under the same rate construct, especially considering that QFs benefit from the statutory right to sell pursuant to a mandatory purchase obligation while non-QFs do not have that right.

company's variable costs, which it incurs only in the course of actually producing electricity; fuel is a prime example. . . . With the cost outlook constantly in flux due to changing economic conditions, some degree of volatility is necessary if prices are to signal the market accurately—as accurately, that is, as current prices can anticipate future costs. Price volatility alone, therefore, cannot provide a ground for overturning a marginal cost rate structure.").

⁵⁷ EIA, Form EIA-860 detailed data with previous form data Early Release (EIA-860A/860B) (June 2, 2020), https://www.eia.gov/electricity/data/eia860/ shows 77.6 GW of operational QF nameplate capacity and 450.453.5 GW of operational non-QF independent power producer nameplate capacity as of end 2019.

⁵⁸ Some commenters raise concerns with the Commission's reliance on the financing of non-QF generation facilities to support the conclusion that QFs could obtain financing with variable energy rate contracts, pointing out that the Commission has not identified any QFs that have obtained financing under this structure. The reason for this, however, is that QFs typically do not employ this structure because currently they are entitled to a fixed energy rate/fixed capacity rate construct. Accordingly, evidence regarding the financing of similar types of independently owned generation projects by non-QFs using such a construct constitutes the best and most relevant evidence of how it

D. The Rate Changes Implemented by this Final Rule Put QF Rates on the Same Footing as Electric Utility Rates and Are Not Discriminatory

- 39. The fact that variable energy rate/fixed capacity rate contracts are standard in the electric industry also explains why, contrary to assertions made by a number of commenters, allowing states to require such contracts for QFs is not discriminatory.⁵⁹ QFs selling at wholesale pursuant to such contracts will be selling under the same rate structure employed in the power sales contracts typically used elsewhere in the electric industry, including by public utilities when they make sales at wholesale to each other, and QFs will be doing so at full avoided cost rates—the highest rates permitted under PURPA.
- 40. It is true that electric utilities with franchised service territories that make sales at retail are often effectively guaranteed the recovery of their energy costs in their retail rates by their state regulatory authorities—provided that such costs are prudently incurred. But the electric utilities' retail rates are cost-based, such that their rates are set based on costs they actually incur to produce electricity for their customers. Importantly, moreover, the incremental energy costs that an electric utility will recover from its retail customers at an

would affect QF financing.

⁵⁹ See, e.g., EPSA Comments at 9 ("The NOPR avoided rate proposal must therefore be rejected because it puts QFs at a disadvantage to utility-owned generation, in violation of the non-discrimination mandate under PURPA."); Public Interest Organizations Comments at 51 ("[L]imiting QFs to contracts providing no price certainty for energy values, while non-QF generation regularly obtains fixed price contracts and utility-owned generation receives guaranteed cost recovery from captive ratepayers, constitutes discrimination.").

incremental level would be the same energy costs that are used in determining the electric utilities' avoided costs that will, in turn, set the as-available avoided cost rates to be charged by QFs.

41. Thus, QF variable energy rate/fixed capacity rate contracts not only would be structured similarly to the standard wholesale power sales agreements used in the electric industry, but application of traditional cost-based ratemaking principles to sales by QFs is exactly what would be required in order to provide QFs with the same guaranteed cost recovery that applies to electric utilities. Guaranteeing QFs cost recovery is fundamentally inconsistent with PURPA, which sets the rate the QF is paid at the purchasing electric utility's avoided cost, not at the QF's cost. Such a rate structure is not discriminatory.

E. The PURPA Compliance Issues Raised by Some Commenters Are Outside the Scope of this Rulemaking Proceeding

42. Finally, several commenters assert that certain states located outside of RTO/ISO markets are dominated by large integrated public utilities whose state commissions do not implement PURPA correctly.⁶⁰ They argue that, as a consequence, there is little development of independent generation—QFs or otherwise—in those states. They assert that the proposals in the NOPR might be appropriate in states with RTO/ISO markets that

⁶⁰ American Dams Comments at 5-6; Biological Diversity Comments at 13; CA Cogeneration Comments at 6-7; Con Edison Comments at 2; ELCON Comments at 7-8; EPSA Comments at 1-2; IdaHydro Comments at 5; NIPPC, CREA, REC, and OSEIA Comments at 14-15; Solar Energy Industries Comments at 15-20, 24; SC Solar Alliance Comments at 3-4; Two Dot Wind Comments at 14-19.

are subject to significant competition, but would only make matters worse outside of the RTO/ISO markets.

- 43. As explained above, several changes implemented by this final rule ensure that the PURPA Regulations will continue to encourage QF development. Other changes, such as allowing variable energy rates in QF contracts, not only ensure the PURPA Regulations are consistent with PURPA but also address some states' primary concern with the current PURPA Regulations, i.e., the Commission's now allowing states the flexibility to set variable energy rates could mitigate the states' reluctance to implement PURPA in a way that better encourages development of QFs. For example, the Idaho Commission has indicated that its current policy of limiting QF contracts to two years is based on its concern about fixed QF rates, and that the ability to require variable energy rates could lead to longer contract terms. We expect that these changes could facilitate QF development in states where little QF capacity has been added to date.
- 44. Further, commenters' claims about lack of QF development outside of the RTO/ISO markets appear to be overstated. For example, the most recent data from the U.S. Energy Information Administration (EIA) on the total amount of wind and solar QF capacity in each state shows that 9 of the 20 states with the greatest combined wind and

⁶¹ See Idaho Commission Comments at 4 (stating that an energy rate established at the time of contract formation that provides for "revisions to the energy rate at regular intervals, consistent with, for example, a purchasing electric utility's [integrated resource plan] to reflect updated avoided cost calculations" would allow states to consider longer term contracts without putting ratepayers at risk).

solar QF capacity are located outside of the RTO/ISO markets.⁶² Of these 9 states, three are located in the Southeast—the region asserted by commenters to be the most hostile to PURPA—including North Carolina, which has the highest total amount of wind and solar QF capacity in the country.⁶³ Other states in the top 20 include Idaho—with the fourth most wind and solar QF capacity—and Oregon,⁶⁴ two states that have been criticized as being hostile to PURPA. EIA data also shows that five of the top 10 states in terms of renewable QF capacity additions from 2008-17 are located outside of the RTO/ISO markets, including North Carolina (with the most renewable QF capacity additions), Idaho, Georgia, and Oregon,⁶⁵ each of which commenters have identified as being hostile to PURPA.

45. But whether any individual state has or has not failed to implement the PURPA Regulations properly is not an issue for this final rule, which implements changes to the

⁶² EIA, Form EIA-860 detailed data with previous form data (EIA-860A/860B) Release date (June 2, 2020), https://www.eia.gov/electricity/data/eia860/. The top 20 states with combined QF solar and wind nameplate capacity in 2018 were: (1) California, Texas, Minnesota, Oklahoma, Massachusetts, New Mexico, Nebraska, New Jersey, Michigan, New York, Illinois (all fully or partially inside RTOs/ISOs); and (2) North Carolina, Idaho, Utah, South Carolina, Georgia, Oregon, Colorado, Arizona, Wyoming(outside of RTOs/ISOs). We note that some of these states are located in both RTO/ISO and non-RTO/ISO regions.

⁶³ *Id.* We note that five of the 20 states with the most solar capacity—perhaps a better measure of the Southeast Region's PURPA compliance given the lack of wind resources in this region—are located in the Southeast.

⁶⁴ *Id*.

⁶⁵ See EIA, PURPA-qualifying capacity increases, but it's still a small portion of added renewables (Aug. 16, 2018), https://www.eia.gov/todayinenergy/detail.php?id=36912.

PURPA Regulations but does not modify Commission's rules for addressing claims that states are not complying with the Commission's existing PURPA Regulations. We promulgate this final rule based on the expectation that the states will fulfill their legal obligation to implement the Commission's PURPA Regulations as revised.⁶⁶

46. Further, although Congress required the Commission to establish the general parameters for establishing QF rates, Congress delegated to the states—not the Commission—the role to set QF rates.⁶⁷ To the extent that any entity believes a state is failing to implement the Commission's PURPA Regulations, PURPA section 210(h) provides that entity an avenue to seek relief.⁶⁸

⁶⁶ 16 U.S.C. 824a-3(f)(1). The same obligation to implement the Commission's PURPA Regulations as revised, we note, is imposed on nonregulated electric utilities. 16 U.S.C. 824a-3(f)(2).

⁶⁷ See 16 U.S.C. 824a-3(f)(1) ("[E]ach State regulatory authority shall, after notice and opportunity for public hearing, implement such rule (or revised rule) for each electric utility for which it has ratemaking authority.").

section 210(h) against a state regulatory authority, chooses not to initiate an enforcement action within 60 days of the filing of the petition, the statute authorizes the petitioning electric utility or QF to itself initiate a suit directly against the state in U.S. District Court. 16 U.S.C. 824a-3(h)(2)(B). The same statutory provision similarly governs petitions for enforcement against nonregulated electric utilities. *Id.* PURPA section 210(g) also provides for review of state regulatory authorities and nonregulated electric utilities in state fora. 16 U.S.C. 824a-3(g). The Commission's policies with respect to PURPA enforcement are more fully set out in its *Policy Statement Regarding the Commission's Enforcement Role Under Section 210 of the Public Utility Regulatory Policies Act of 1978*, 23 FERC ¶ 61,304 (1983).

III. Background

A. Passage of PURPA in 1978 and the Commission's Promulgation of its PURPA Regulations in 1980

- 47. PURPA was enacted in 1978 as part of a package of legislative proposals intended to reduce the country's dependence on oil and natural gas, which at the time were in short supply and subject to dramatic price increases. PURPA sets forth a framework to encourage the development of alternative generation resources that do not rely on traditional fossil fuels (i.e., oil, natural gas and coal) and cogeneration facilities that make more efficient use of the heat produced from the fossil fuels that were then commonly used in the production of electricity.
- 48. To accomplish this goal, PURPA section 210(a) directs that the Commission "prescribe, and from time to time thereafter revise, such rules as [the Commission] determines necessary to encourage cogeneration and small power production," including rules requiring electric utilities to offer to sell electricity to, and purchase electricity from, QFs. PURPA section 210(f) required each state regulatory authority and nonregulated electric utility (together, states) to implement the Commission's rules.
- 49. In 1980, the Commission issued Order Nos. 69 and 70, which promulgated the required rules that, with limited exceptions, remain in effect today.⁷⁰ The Commission

⁶⁹ 16 U.S.C. 824a-3(a).

⁷⁰ Order No. 69, FERC Stats. & Regs. ¶ 30,128; Small Power Production and Cogeneration Facilities – Qualifying Status, Order No. 70, FERC Stats. & Regs. ¶ 30,134 (cross-referenced at 10 FERC ¶ 61,230), orders on reh'g, Order No. 70-A, FERC Stats. & Regs. ¶ 30,159 (cross-referenced at 11 FERC ¶ 61,119) and FERC Stats. & Regs. ¶ 30,160 (cross-referenced at 11 FERC ¶ 61,166), order on reh'g, Order No. 70-B, FERC Stats. &

explained that, at the time of the passage of PURPA, cogenerators and small power producers faced three major obstacles: (1) electric utilities were not required to purchase these generators' electric output or to make purchases at an appropriate rate; (2) electric utilities sometimes charged discriminatorily high rates for backup services; and (3) cogenerators and small power producers ran the risk of being considered public utilities themselves and thus being subject to state and federal regulation as utilities.⁷¹ Further, at that time, there was no open access transmission and little competition in electric wholesale markets. Electric utilities were vertically-integrated and held dominant market positions. As a result of their control over transmission access, it was virtually impossible for third parties – whether independent power producers or other electric utilities – to compete with them to make sales of electricity.

50. Given the Congressional mandate described above, the Commission determined in Order No. 69 to set rates for sales by QFs equal to the purchasing electric utilities' avoided costs.⁷² The Commission also directed that electric utilities provide backup

Regs. \P 30,176 (cross-referenced at 12 FERC \P 61,128), order on reh'g, FERC Stats. & Regs. \P 30,192 (1980) (cross-referenced at 12 FERC \P 61,306), amending regulations, Order No. 70-D, FERC Stats. & Regs. \P 30,234 (cross-referenced at 14 FERC \P 61,076), amending regulations, Order No. 70-E, FERC Stats. & Regs. \P 30,274 (1981) (cross-referenced at 15 FERC \P 61,281).

⁷¹ Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,863. *See infra* P 78 & note 112 (addressing how the PURPA Regulations as revised continue to address these obstacles).

⁷² 18 CFR 292.304(a)(2); see API, 461 U.S. at 412-18.

electric energy to QFs on a non-discriminatory basis and at just and reasonable rates,⁷³ and that electric utilities interconnect with QFs.⁷⁴ Pursuant to section 210(e) of PURPA,⁷⁵ the Commission further provided exemptions from many provisions of the FPA and state laws governing utility rates and financial organization.⁷⁶

B. <u>Circumstances Leading to the Commission's Re-evaluation of the PURPA Regulations and the Issuance of the NOPR</u>

51. In the NOPR, the Commission described three important changes in the circumstances that had originally prompted Congress to pass PURPA in 1978. First, as the Commission explained, the United States has seen an unprecedented change in the dynamics of the natural gas market and the relevant supply and demand.⁷⁷ Led by advancements in production technologies, primarily in accessing shale reserves, natural gas supplies increased dramatically.⁷⁸ Further, the EIA forecasted continued supply

 $^{^{73}}$ Order No. 69, FERC Stats. & Regs. \P 30,128 at 30,887-90; see also 18 CFR 292.305.

⁷⁴ Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,874; see also 18 CFR 292.303(c).

⁷⁵ 16 U.S.C. 824a-3(e).

 $^{^{76}}$ Order No. 69, FERC Stats. & Regs. \P 30,128 at 30,864; $accord\ id.$ at 30,863, 30,894-96; $see\ also$ 18 CFR 292.601-.602.

⁷⁷ NOPR, 168 FERC ¶ 61,184 at P 19.

⁷⁸ Domestic natural gas production, which appeared to peak in the early 1970s at 21.7 Tcf per year, increased from 18.1 Tcf in 2005 to 30.4 Tcf in 2018. EIA, Monthly Energy Review (Aug. 27, 2019) (in table 4.1 see column labeled "Natural Gas Production (Dry)" on the Annual tab of the xls version), https://www.eia.gov/totalenergy/data/monthly/.

growth over the next 25 years.⁷⁹ In short, as the Commission found in issuing the NOPR, there no longer are shortages of natural gas supply.

52. Second, the Commission found that, since 1978, the outlook for the development of alternatives to natural gas and oil-fired generation resources, such as renewable resources, has changed equally dramatically. ⁸⁰ The once-nascent renewables industry has grown and matured over the past 40 years and has only accelerated subsequent to the Energy Policy Act of 2005's amendment of PURPA. The Commission noted that the cost of building renewable facilities has decreased substantially to the point that the cost of renewable resources is now or is shortly expected to approach the cost of traditional electric generation. ⁸¹ The Commission also recognized that renewable resources (including

Because load must be continuously balanced, generating units with the capability to vary output to follow demand (dispatchable technologies) generally have more value to a system than less flexible units (nondispatchable technologies) such as those using intermittent resources to operate. The

⁷⁹ EIA's forecast showed supplies increasing to nearly 40 Tcf by 2035 and 43 Tcf by 2050. EIA, Annual Energy Outlook 2018, at tbl.13 (Jan. 24, 2019) (in table see row labeled "Dry Gas Production" under the reference case) (Annual Energy Outlook 2019), https://www.eia.gov/outlooks/aeo/data/browser/#/?id=13-AEO2019&cases=ref2018&sourcekey=0.

 $^{^{80}}$ NOPR, 168 FERC \P 61,184 at P 20.

⁸¹ Id. (citing EIA, Updated Capital Cost Estimates for Utility Scale Electricity Generating Plants, https://www.eia.gov/analysis/studies/powerplants/capitalcost/; EIA, Levelized Cost and Levelized Avoided Cost of New Generation Resources in the Annual Energy Outlook 2019 (Feb. 2019), https://www.eia.gov/outlooks/aeo/pdf/electricity_generation.pdf; Lawrence Berkeley National Lab, Wind Technologies Market Report, https://emp.lbl.gov/wind-technologies-market-report/). However, EIA has cautioned against directly comparing the costs of dispatchable and nondispatchable generation:

hydro) provide a significant share of the electricity currently generated in the United States,⁸² that most renewable resources today are not QFs,⁸³ and that 65 percent of capacity additions in 2019 were expected to come from renewable resources.⁸⁴

53. Third, the introduction of QFs as competing sources of electricity to the incumbent electric utilities has led to the development of significant non-QF independent power

LCOE values for dispatchable and non-dispatchable technologies are listed separately in the tables because comparing them must be done carefully.

EIA, Levelized Cost and Levelized Avoided Cost of New Generation Resources in the Annual Energy Outlook 2019, at 2 (Feb. 2019), https://www.eia.gov/outlooks/archive/aeo19/pdf/electricity_generation.pdf.

⁸² NOPR, 168 FERC ¶ 61,184 at P 21 (citing EIA, *August 2019 Monthly Energy Review* at Figure 7.2a, https://www.eia.gov/totalenergy/data/monthly; Office of Energy Projects, *Energy Infrastructure Update For July 2019* at 4 (July 2019), https://www.ferc.gov/legal/staff-reports/2019/july-energy-infrastructure.pdf).

⁸³ NOPR, 168 FERC ¶ 61,184 at P 22.

⁸⁴ *Id.* (citing EIA, Today in Energy, *New electric generating capacity in 2019 will come from renewables and natural gas* (Jan. 10, 2019), https://www.eia.gov/todayinenergy/detail.php?id=37952 (Form EIA-860M, Preliminary Monthly Electric Generator Inventory).

production.⁸⁵ In addition, RTOs and ISOs have developed competitive wholesale electric markets that serve roughly two-thirds of electricity consumers in the United States.⁸⁶

- 54. In PURPA section 210(a), Congress directed not only that the Commission prescribe regulations, but that the Commission revise those regulations "from time to time thereafter." The Commission determined in the NOPR that, in light of these dramatic changes in circumstances since the passage of PURPA, it was appropriate to review the PURPA Regulations to determine whether changes to those regulations were warranted consistent with our statutory mandate. 88
- 55. After identifying these three important changes in the industry that have taken place since 1980, we further identified evidence demonstrating that overestimations of

NOPR, 168 FERC ¶ 61,184 at P 25. The Commission cited to data showing that that net generation of energy by non-utility owned renewable resources in the United States escalated from 51.7 TWh in 2005 when EPAct 2005 was passed, to 340 TWh in 2018. This also included significant growth in non-utility renewable resources in states outside of RTOs. For example, net generation by non-utility renewable resources in the region defined by EIA as the Mountain State region increased from 3.6 TWh in 2005 to 19.5 TWh in 2012, and to 42.5 TWh in 2018. Pacific Northwest (Oregon and Washington) net non-utility generation from renewable resources increased from 1.5 TWh in 2005, to 8.7 TWh in 2012, and to 10.6 TWh in 2018. In the Southeast region of the country, non-utility renewable resources saw a lesser increase from 2.6 TWh in 2005 to 2.7 TWh in 2012, but expanded to 6.5 TWh in 2018. NOPR, 168 FERC ¶ 61,184 at P 27 (citing data taken from EIA's Electricity Data Browser, www.eia.gov/electricity/data/browser (select net generation, other renewables, independent power producers)).

⁸⁶ ISO/RTO Council, *The Role of ISOs and RTOs*, https://isorto.org.

^{87 16} U.S.C. 824a-3(a).

^{88 16} U.S.C. 824a-3(b).

avoided cost have not been balanced by underestimations, and that this trend may persist with the general decline in the cost of electricity.⁸⁹

C. <u>Summary of Changes to the PURPA Regulations Implemented by this</u> final rule

56. We now are revising our PURPA Regulations based on the record of this proceeding, including comments submitted in the technical conference in Docket No. AD16-16-000 (Technical Conference), ⁹⁰ the record evidence cited in the NOPR, and the comments submitted in response to the NOPR. These changes, including modifications to the proposals made in the NOPR, are summarized below. ⁹¹

⁸⁹ See NOPR, 168 FERC ¶ 61,184 at P 30. Evidence submitted in response to the NOPR shows that, as a result, customers may be paying more than avoided costs. See infra PP 265 ("Duke Energy claims that, among the factors contributing to this overpayment of \$2.26 billion for the remainder of these QF contracts, the primary factor has been the requirement to offer fixed avoided cost energy rates during a period of rapidly declining energy prices"), 268 ("Massachusetts DPU argues that a 10-year, fixed energy rate based on current New England wholesale energy market prices is highly likely to diverge from actual energy market prices over the ten-year contract term and could significantly harm ratepayers").

⁹⁰ Supplemental Notice of Technical Conference, *Implementation Issues Under the Public Utility Regulatory Policies Act of 1978*, Docket No. AD16-16-000 (May 9, 2016). The Technical Conference covered such issues as: (1) various methods for calculating avoided cost; (2) the obligation to purchase pursuant to a LEO; (3) application of the onemile rule; and (4) the rebuttable presumption the Commission has adopted under PURPA section 210(m) that QFs 20 MW and below do not have nondiscriminatory access to competitive organized wholesale markets.

⁹¹ In its post-NOPR comments, Bloom Energy requested that the Commission "[u]pdate the definition of 'useful thermal energy output' of a topping-cycle cogeneration facility to reflect the commercialization of solid oxide fuel cells that produce heat for the industrial purpose of producing hydrogen, a fuel that the fuel cells use to generate electricity." Bloom Energy Comments at 2. We do not take action on this request in this proceeding because we do not view this proposal as a logical outgrowth of the NOPR.

- 57. *First*, we grant states the flexibility to require that energy rates (but not capacity rates) in QF power sales contracts and other LEOs⁹² vary in accordance with changes in the purchasing electric utility's as-available avoided costs at the time the energy is delivered. Under this change, if a state exercises this flexibility, a QF no longer would have the ability to elect to have its energy rate be fixed, but would continue to be entitled to a fixed capacity rate for the term of the contract or LEO.⁹³
- 58. Second, we grant states additional flexibility to allow QFs to have a fixed energy rate, but to provide that such state-authorized fixed energy rate can be based on projected energy prices during the term of a QF's contract based on the anticipated dates of delivery.
- 59. *Third*, we grant states flexibility to set "as-available" QF energy rates as follows: We are establishing a rebuttal presumption, rather than a per se rule as proposed in the NOPR, that the LMP established in the organized electric markets defined in 18 CFR 292.309(e), (f), or (g) represents the as-available avoided costs of electric utilities located

⁹² The Commission has held that a LEO can take effect before a contract is executed and may not necessarily be incorporated into a contract. *JD Wind 1, LLC*, 129 FERC ¶ 61,148, at P 25 (2009), *reh'g denied*, 130 FERC ¶ 61,127 (2010) ("[A] QF, by committing itself to sell to an electric utility, also commits the electric utility to buy from the QF; these commitments result either in contracts or in non-contractual, but binding, legally enforceable obligations."). For ease of reference, however, references herein to a contract also are intended to refer to a LEO that is not incorporated into a contract.

⁹³ Moreover, any state—whether located in regions where energy prices are competitively based or whether located in regions where they are not—would be permitted to require that the fixed energy rate established at the time of the contract include provisions, established at the time the contract is established, providing for revisions to the energy rate at regular intervals, consistent with, for example, a purchasing electric utility's integrated resource plan, to reflect updated avoided cost calculations.

in these markets. ⁹⁴ So long as this presumption is not rebutted, a state can at its option establish as-available energy avoided cost rates for QFs selling to such electric utilities at the LMP. With respect to QFs selling to electric utilities located outside of the organized electric markets defined in 18 CFR 292.309(e), (f), or (g), states have the option to set as-available energy avoided cost rates at competitive prices from liquid market hubs or calculated from a formula based on natural gas price indices and specified heat rates, provided that the states first determine that such prices represent the purchasing electric utilities' avoided costs. The states would have the flexibility to choose to adopt one or more of these options or to continue setting QF rates under the standards long established in the PURPA Regulations.

- 60. Fourth, states would have the flexibility to set energy and capacity rates pursuant to a competitive solicitation process conducted pursuant to transparent and non-discriminatory procedures consistent with the Commission's *Allegheny* standard, described in this final rule.
- 61. *Fifth*, we do not adopt the proposed rule permitting states with retail competition to allow relief from the purchase obligation. We instead clarify in this final rule that the Commission's existing PURPA Regulations already require that states, to the extent practicable, must account for reduced loads in setting QF capacity rates.

⁹⁴ These are the markets operated by Midcontinent Independent System Operator, Inc. (MISO); PJM Interconnection, L.L.C. (PJM); ISO New England Inc. (ISO-NE); New York Independent System Operator, Inc. (NYISO); Electric Reliability Council of Texas (ERCOT); California Independent System Operator, Inc. (CAISO); and Southwest Power Pool, Inc. (SPP).

- 62. Sixth, we modify the Commission's "one-mile rule" for determining whether generation facilities are considered to be at the same site for purposes of determining qualification as a qualifying small power production facility. Specifically, we allow electric utilities, state regulatory authorities, and other interested parties to show that affiliated small power production facilities that use the same energy resource and are more than one mile apart and less than 10 miles apart actually are at the same site (with distances one mile or less apart still irrebuttably at the same site, and distances 10 miles or more apart irrebuttably at separate sites). We also allow a small power production facility seeking QF status to provide further information in its certification (whether a selfcertification or an application for Commission certification) or recertification (whether a self-recertification or an application for Commission recertification) to defend preemptively against subsequent challenges, by identifying factors affirmatively demonstrating that its facility is indeed at a separate site from other affiliated small power production qualifying facilities. We further add a definition of the term "electrical generating equipment" to the PURPA Regulations to clarify how the distance between facilities is to be calculated.
- 63. Seventh, we allow an entity to challenge an initial self-certification or self-recertification without being required to file a separate petition for declaratory order and to pay the associated filing fee. However, we clarify in this final rule that such protests may be made to new certifications (both self-certifications and applications for Commission certification) but to only self-recertifications and applications for Commission recertifications making substantive changes to the existing certification.

- 64. Eighth, we revise the Commission's regulations implementing PURPA section 210(m), which provide for the termination of an electric utility's obligation to purchase from a QF with nondiscriminatory access to certain markets. Currently, there is a rebuttable presumption that QFs with a net capacity at or below 20 MW do not have nondiscriminatory access to such markets. We update the rebuttable presumption for small power production facilities (but not cogeneration facilities) from 20 MW to 5 MW and, in this final rule, revise the regulations to include examples of factors, among others, that QFs may argue show that they lack nondiscriminatory access to such markets.
- 65. Finally, we clarify that a QF must demonstrate commercial viability and a financial commitment to construct its facility pursuant to objective and reasonable state-determined criteria before the QF is entitled to a contract or LEO. States may not impose any requirements for a LEO other than a showing of commercial viability and a financial commitment to construct the facility. We also clarify in this final rule that, to the extent that the permitting factor is relied upon, a QF need only show that it has applied for all required permits and paid all applicable fees, and not that it has obtained such permits.
- 66. As explained in detail in the relevant sections below, these changes will enable the Commission to continue to fulfill its statutory obligations under sections 201 and 210 of PURPA. We emphasize that these changes are effective prospectively for new contracts or LEOs and for new facility certifications and recertifications filed on or after the effective date of this final rule; we do not by this final rule permit disturbance of existing contracts or LEOs or existing facility certifications.

IV. Discussion

A. General Legal Standards Under PURPA

67. Several comments were submitted regarding: (1) the requirement in PURPA section 210(a) that "the Commission shall prescribe, and from time to time thereafter revise, such rules as it determines necessary to encourage cogeneration and small power production"; and (2) the requirement in PURPA section 210(b) that rates paid by purchasing utilities to QFs "shall not discriminate against qualifying cogenerators or qualifying small power producers." In addition, a claim was made that the Commission has unlawfully delegated its authority to the states. These comments apply to several of the revisions implemented by this final rule and therefore are discussed prior to the discussion of specific revisions implemented herein.

1. Encouragement of QFs

a. Comments

68. Commenters make two general arguments regarding the statutory requirement that the Commission's PURPA Regulations should encourage QFs. First, they note that the statutory requirement that the PURPA Regulations encourage QFs is mandatory and that the Commission has no discretion to determine that such encouragement no longer is necessary. Harvard Electricity Law states that "Congress'[s] mandate to encourage QFs is not contingent on industry conditions and does not expire." Further, they assert, "[t]he

⁹⁵ 16 U.S.C. 824a-3(a), (b).

⁹⁶ Harvard Electricity Law Comments at 1.

Commission may not overwrite Congress's instruction to issue rules that it 'determines necessary to encourage cogeneration and small power production.'" Public Interest Organizations similarly object to the NOPR as violating the encouragement requirement because, they assert, the NOPR "reflect[s] a belief that the current rules support too much QF development and a desire to reduce the incentives in current rules for QF development." NIPPC, CREA, REC, and OSEIA assert that "[t]he Commission cannot take it upon itself to change the underlying policy directives to encourage QFs." 99

69. Public Interest Organizations advance a second general argument based on the encouragement requirement, arguing that "[t]o amend the rules, the Commission must first determine that the actual changes it proposes increase development and utilization of QFs." ¹⁰⁰ Similarly, Allco attacks the NOPR on the grounds that "the proposed changes do not encourage QF generation." ¹⁰¹

b. Commission Determination

70. We agree with commenters that PURPA does not provide discretion to the Commission to determine whether QFs should be encouraged. That is a determination left to Congress, and we have not premised this final rule on a belief that QFs should not be

⁹⁷ Id. at 4 (quoting PURPA section 210(a)).

⁹⁸ Public Interest Organizations Comments at 10.

⁹⁹ NIPPC, CREA, REC, and OSEIA Comments at 29.

¹⁰⁰ Public Interest Organizations Comments at 11.

¹⁰¹ Allco Comments at 8.

encouraged. However, the requirement that the Commission promulgate regulations necessary to encourage QFs is not unbounded. Instead, as noted briefly earlier, there are statutory limitations on the extent that the PURPA Regulations can encourage QFs.

71. First, PURPA section 210(b) sets out standards with which the Commission must comply in setting QF rates. The last sentence of PURPA section 210(b) sets out an upper limit on such rates. "No such rule prescribed under subsection (a) shall provide for a rate which exceeds the incremental cost to the electric utility of alternative electric energy." 102
72. If there were any doubt from the statutory language that incremental costs (avoided costs) are intended to be a hard cap on QF rates, such doubt is dispelled by the Conference Report to PURPA, which provided: "This limitation on the rates which may be required in purchasing from a cogenerator or small power producer *is meant to act as an upper limit on the price* at which utilities can be required under this section to purchase electric

energy."103 The Conference Report also described the reason for the avoided cost cap on

¹⁰² Furthermore, PURPA section 210(b)(1) requires that QF rates be "just and reasonable to the electric consumers of the electric utility and in the public interest." 16 U.S.C. 824a-3(b)(1). Although the exact scope of the "just and reasonable to the electric consumers" criterion has never been addressed explicitly, the Supreme Court held in *API* that the requirement in the PURPA Regulations that QF rates be set at full avoided costs does not violate this criterion. *API*, 461 U.S. at 415-16. This "just and reasonable to the electric consumers" criterion likely would be violated if the Commission were to allow a rate above the purchasing electric utility's avoided costs.

¹⁰³ Conf. Rep. at 98 (emphasis added).

QF rates. "The provisions of this section are not intended to require the rate payers of a utility to subsidize cogenerators or small power produc[er]s." 104

- 73. Therefore, PURPA section 210(b) imposes an important limit on the Commission's ability to encourage QFs by imposing an upper boundary on the rates at which QFs may require electric utilities to purchase their electric energy. The Commission cannot require QF rates that exceed the avoided costs of the purchasing electric utility.¹⁰⁵
- 74. Second, another way in which Congress limited the Commission's ability to encourage QFs was to define small power production facilities, the PURPA category applicable to almost all renewable resources that wish to be QFs, as having "a power production capacity which, together with any other facilities *located at the same site* (as determined by the Commission), is not greater than 80 megawatts." The statutory 80 MW limitation, as well as any definition of "the same site" that may be established by the Commission, will of necessity have an effect on the encouragement of QFs, because it will limit the capacity of QFs both *ab initio* and also for those located at the same site to 80 MW.
- 75. Third, Congress amended PURPA section 210 to add section 210(m), which provides for termination of the requirement that an electric utility enter into a new obligation or contract to purchase from a QF if the QF has nondiscriminatory access to

¹⁰⁴ *Id.* (emphasis added).

¹⁰⁵ 16 U.S.C. 824a-3(b)(1).

¹⁰⁶ 16 U.S.C. 796(17)(A)(ii).

certain defined types of markets.¹⁰⁷ We interpret this amendment as reflecting Congress's judgment that these markets provide adequate encouragement for those QFs having nondiscriminatory access to such markets. To the extent that a party asserts that the termination of the purchase obligation for QFs with nondiscriminatory access to these markets discourages QFs, that party's argument is not with the Commission, but rather with Congress. PURPA section 210(m) obligates the Commission to grant any request to terminate a utility's obligation to purchase from a QF with nondiscriminatory access to the specified markets.¹⁰⁸

76. Finally, we disagree with any suggestion that a rule originally adopted in 1980 cannot be changed once adopted, or that our revised regulations cannot be different in how they encourage QFs than the regulations the Commission issued in 1980. For one thing, as explained above, PURPA itself includes certain limitations on the Commission's ability to encourage QFs, and a provision in the final rule intended to comply with these statutory limitations cannot be found to violate PURPA even if such a provision individually does not affirmatively encourage QFs to the same degree now as in 1980. As explained herein, we do not seek, through this final rule, to cease encouraging the development of QFs. Instead, this final rule is intended to ensure that the Commission is

¹⁰⁷ See 16 U.S.C. 824a-3(m).

¹⁰⁸ *Id*. ("[N]o electric utility shall be required to enter into a new contract or obligation to purchase electric energy from a [QF] if the Commission finds that the [QF] has nondiscriminatory access to [specified markets].").

¹⁰⁹ See 18 U.S.C. 824a-3(a).

compliant with the statute in how it does encourage the development of QFs. In doing so, the Commission may end up encouraging QF development differently from the current PURPA Regulations, but the Commission's regulations continue to encourage QF development, as contemplated by PURPA.

- 77. Many of the commenters' assertions seem to be based on a reading of the statute that requires that every individual change made to the PURPA Regulations in isolation must individually encourage QFs notwithstanding the statute's provisions. But, as discussed above, Congress established boundaries in PURPA that must be considered, such as the "cap" on incremental costs; just and reasonable rates for electric customers; the 80 MW limit; and whether QFs have nondiscriminatory access to markets.

 Furthermore, the statutory requirement to encourage QF development applies to the PURPA Regulations "such *rules* as [the Commission] determines necessary" as a whole. 110
- 78. In that regard, we find that the Commission's PURPA Regulations as a whole when modified by this final rule continue to encourage the development of QFs, consistent with PURPA. The PURPA Regulations in particular, continue to require that QF rates be set at full avoided costs, a provision the Supreme Court described as "provid[ing] the maximum incentive for the development of cogeneration and small power production." In addition, this final rule retains provisions of the PURPA Regulations adopted in 1980 that

¹¹⁰ See 16 U.S.C. 824a-3(a) (emphasis added).

¹¹¹ API, 461 U.S. at 418.

provide encouragement through other means recognized by the Supreme Court in *FERC v*. *Miss*. ¹¹² (e.g., certain regulatory relief, ¹¹³ interconnection provisions, ¹¹⁴ and requirements that utilities sell power to QFs that will enable QFs to continue operations). ¹¹⁵ Moreover, several of the changes implemented by this final rule also provide additional encouragement for QFs as described in more detail below.

2. <u>Discrimination</u>

a. Comments

79. Commenters opposing the proposals in the NOPR also cite to the statutory requirement in PURPA section 210(b)(1) that QF rates "shall not discriminate against" QFs. EPSA asserts that "[n]otably, this standard is more restrictive than the [FPA's] prohibition against 'unduly discriminatory' rates." Public Interest Organizations state that "[i]n other statutes, prohibiting price discrimination without the modifiers 'unreasonable' or 'undue,' means any difference in price for the same commodity." 117

¹¹² 456 U.S. 742, 750-51 (1982) (holding that Congress "felt that two problems impeded the development of nontraditional generating facilities: (1) traditional electricity utilities were reluctant to purchase power from, and to sell power to, the nontraditional facilities, and (2) the regulation of these alternative energy sources by state and federal utility authorities imposed financial burdens upon the nontraditional facilities and thus discouraged their development" (internal citations omitted)).

¹¹³ 18 CFR 292.601-02.

¹¹⁴ 18 CFR 292.303(c).

¹¹⁵ 18 CFR 292.305.

¹¹⁶ EPSA Comments at 8.

¹¹⁷ Public Interest Organizations Comments at 47 (citing FTC v. Anheuser - Busch,

- 80. In discussing the requirement that QF rates not be discriminatory, some commenters compare the treatment afforded to QFs under the NOPR with the rate treatment applicable to public utilities. For example, NIPPC, CREA, REC, and OSEIA point out that "[u]tilities can rate-base long-term investments, thereby ensuring that they can recover their capital investments plus an authorized return, and then also recover their actual operating costs under traditional cost-of-service ratemaking." By contrast, Harvard Electricity Law asserts, "QFs do not have the same ability that the electric utilities have to 'rate base' their facilities and, thereby, guarantee capital recovery." 119
- 81. Based on this difference between utilities and QFs, commenters allege that certain aspects of the NOPR are discriminatory, including those provisions of the NOPR regarding the use of LMPs and other competitive rates to set as-available energy rates, ¹²⁰

Inc., 363 U.S. 536, 549 (1960)).

¹¹⁸ NIPPC, CREA, REC, and OSEIA Comments at 36; *see also* IdaHydro Comments at 11; Industrial Energy Consumers Comments at 12-13; SC Solar Alliance Comments at 5-10; Solar Energy Industries Comments at 33, 36-38.

¹¹⁹ Harvard Electricity Law Comments at 28.

¹²⁰ See, e.g., Public Interest Organizations Comments at 64 (stating that the use of competitive prices to set as-available energy avoided cost rates is discriminatory because non-QF generators are not limited to competitive prices and utilities can, and regularly do, pay effective prices for energy that exceed the price determined by competitive prices).

to allow for variable energy rates in QF contracts, ¹²¹ and to allow avoided costs to be set through competitive solicitations (i.e., requests for proposals (RFPs)). ¹²²

b. <u>Commission Determination</u>

82. As an initial matter, we agree with EPSA that the statutory requirement in PURPA section 210(b)(1) that QF rates "shall not discriminate against" QFs is more restrictive than the FPA's prohibition against 'unduly discriminatory' rates. 123 However, the avoided cost cap on QF rates that limits the Commission's ability to encourage QFs, discussed above, also applies to the Commission's ability to address these claims of discrimination under PURPA. PURPA section 210(b) makes clear that "[n]o such rule prescribed under subsection (a) shall provide for a rate which exceeds the incremental cost to the electric utility of alternative electric energy." 124

¹²¹ See, e.g., EPSA Comments at 9 ("The NOPR avoided rate proposal must therefore be rejected because it puts QFs at a disadvantage to utility-owned generation, in violation of the non-discrimination mandate under PURPA."); Public Interest Organizations Comments at 51 ("[L]imiting QFs to contracts providing no price certainty for energy values, while non-QF generation regularly obtains fixed price contracts and utility-owned generation receives guaranteed cost recovery from captive ratepayers, constitutes discrimination.").

¹²² See, e.g., Allco Comments at 12 (stating that allowing a state commission to use a competitive solicitation price is simply giving another tool to a state commission to kill QF projects).

¹²³ EPSA Comments at 8.

¹²⁴ Furthermore, as noted above, PURPA section 210(b)(1) requires that QF rates also be "just and reasonable to the electric consumers of the electric utility and in the public interest." *See supra* note 102.

- 83. We are retaining in this final rule the requirement that QF rates be set at a purchasing utility's full avoided costs. The Supreme Court held in *API* that "the full-avoided-cost rule plainly satisfies the nondiscrimination requirement." Although the Court did not provide a detailed explanation for this holding, the reasoning is apparent. If the purchasing utility is paying the same rate to a QF for power that it otherwise would have paid for incremental power, by definition such a rate could not be discriminatory. But even if it were possible to posit a situation where the payment of a full avoided cost rate to a QF somehow were discriminatory, the Commission nevertheless would be prohibited by PURPA section 210(b) from requiring a rate to be paid to the QF that is *above* the full avoided costs of the purchasing electric utility.
- 84. For the same reasons, Public Interest Organizations are mistaken when they assert that, without the modifiers "unreasonable" or "undue," any difference in price for the same commodity violates PURPA. So long as a QF's rate is set at the purchasing utility's full avoided cost, the QF's rate should be the same as the rate the purchasing utility otherwise would be paying or the cost it would be incurring, and such a rate would not be discriminatory. And, in any event, as noted above, the Commission cannot require a rate that is any higher.

¹²⁵ API, 461 U.S. at 413.

¹²⁶ Public Interest Organizations Comments at 47 (citing *FTC v. Anheuser - Busch, Inc.*, 363 U.S. at 549).

85. With respect to comparisons between QFs, with no guarantee of cost recovery, and electric utilities, which if they have a franchised service territory and sell at retail in that territory are effectively guaranteed the opportunity to seek to recover prudently-incurred costs in their retail rates, we observe that Congress acknowledged this difference when enacting PURPA. As emphasized in the PURPA Conference Report:

The conferees recognize that cogenerators and small power producers are different from electric utilities, *not being guaranteed a rate of return on their activities* generally or on the activities vis a vis the sale of power to the utility and whose risk in proceeding forward in the cogeneration or small power production enterprise *is not guaranteed to be recoverable*.¹²⁷

86. In recognizing this difference and yet not seeking to eliminate it, Congress also made clear its intent not to treat QFs like electric utilities in this regard:

It is not the intention of the conferees that [QFs] become subject. . . to the type of examination that is traditionally given to electric utility rate applications to determine what is the just and reasonable rate that they should receive for their electric power. 128

87. Based on this legislative history, the Supreme Court concluded in *API* that, "Congress did not intend to impose traditional ratemaking concepts on sales by qualifying facilities to utilities." But application of traditional cost-based ratemaking principles to sales by QFs is exactly what would be required in order to provide QFs with the same

¹²⁷ Conf. Rep. at 97-98 (emphasis added).

¹²⁸ *Id.* at 97.

¹²⁹ API, 461 U.S. at 414.

guaranteed cost recovery that applies to electric utilities. Also, guaranteeing QFs cost recovery is fundamentally inconsistent with PURPA, which sets the rate the QF is paid at the utility's avoided cost, not at the QF's cost.

88. It therefore is clear that Congress did not intend for the PURPA nondiscrimination criterion to require that QF rates be set in a way that guarantees recovery of a QF's own costs, even as Congress recognized that franchised electric utilities selling at retail typically do have such guarantees for their own costs. Congress thus withheld from the Commission the authority to provide to QFs the same opportunity to recover costs at retail that franchised electric utilities have to recover their costs at retail; it was done by Congress intentionally and cannot be impermissibly discriminatory. ¹³⁰

3. <u>Unlawful Delegation and the Role of Nonregulated Electric Utilities</u>

a. Comments

89. Allco argues that PURPA section 210(f) requires states to "implement" the Commission's rules, and that those rules cannot redelegate the Commission's authority. Allco claims that the statutory requirement to implement the Commission's rules cannot simply be a façade for delegating broad authority to states to undercut PURPA's directive that QF small power production must be encouraged. Allco concludes that Congress intended for the Commission to adopt actual rules rather than "a menu of factors" that

¹³⁰ See 16 U.S.C. 824a-3(a) (rules Commission is directed to prescribe "may not authorize a [QF] to make any sale for purposes other than resale").

essentially leaves states with all the discretion as to what to implement in order to encourage QF generation. ¹³¹

- 90. Allco also asserts that the NOPR's proposed delegation of authority to nonregulated electric utilities is an unconstitutional delegation. According to Allco, such a delegation would mean that nonregulated electric utilities (some of which are among the largest utilities in the United States) were regulating themselves. Allco argues that a private entity such as a nonregulated electric utility cannot constitutionally be delegated regulatory power.¹³²
- 91. Nebraska Board states that there is no state agency in Nebraska that has ratemaking authority over retail electric suppliers and that all retail electric suppliers are consumerowned. Nebraska Board states its understanding that each retail electric supplier in Nebraska would have jurisdiction to exercise flexibilities provided to states in the NOPR.
- 92. Public Interest Organizations argue that the Commission failed to comply with PURPA section 210's requirement to consult with federal and state regulatory agencies with ratemaking authority. 133

b. Commission Determination

93. Allco's unlawful delegation claims are misplaced. By enacting PURPA section 210(f)(1), Congress delegated to the states the obligation to implement the Commission's

¹³¹ Allco Comments at 39-40.

¹³² *Id.* at 40 (citing *Ass'n of Am. R.R. v. DOT*, 721 F.3d 666, 677 (D.C. Cir. 2013), vacated on other grounds, 135 S. Ct. 1225 (2015)).

¹³³ Public Interest Organizations Comments at 19 (citing 16 U.S.C. 824a-3(a)).

PURPA rules, and the Commission is acting consistent with that delegation. Congress's delegation to the states was upheld in *FERC v. Miss.* ¹³⁴ and we are ensuring that the rules we have imposed abide by all the terms of the statute. Further, the Commission's current PURPA Regulations, promulgated in 1980, set forth a list of factors that the states are to consider, "to the extent practicable," in setting QF rates. ¹³⁵ In so doing, the Commission emphasized that states have "great latitude in determining the manner of implementation of the Commission's rules, provided that the manner chosen is reasonably designed to implement the requirements of Subpart C [which includes the pricing rules of 18 CFR 292.304]." ¹³⁶ This final rule adds factors that must be taken into account to the extent practicable in setting rates, while retaining the "great latitude" the states always have had to implement the PURPA Regulations and which have been an important feature of the Commission's PURPA Regulations since their inception.

94. With respect to Allco's claim that the NOPR proposed an unconstitutional delegation to nonregulated electric utilities, we note that PURPA section 210(f)(2)

¹³⁴ 456 U.S. at 760 ("FERC has declared that state commissions may implement this by, among other things, 'an undertaking to resolve disputes between qualifying facilities and electric utilities arising under [PURPA]."").

¹³⁵ 18 CFR 292.304(e).

¹³⁶ Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,891-92. The Commission explained that "[s]uch latitude is necessary in order for implementation to accommodate local conditions and concerns, so long as the final plan is consistent with statutory requirements." *Policy Statement Regarding the Commission's Enforcement Role Under Section 210 of the Public Utility Regulatory Policies Act of 1978*, 23 FERC ¶ 61,304,at 61,646.

specifically provides that "each nonregulated electric utility shall, after notice and opportunity for public hearing, implement" the Commission's rules regarding the rates to be paid to QFs. Consistent with this statutory provision, the PURPA Regulations regarding the setting of QF rates have applied to nonregulated electric utilities since those regulations were promulgated in 1980.¹³⁷ The final rule does nothing more than continue to implement this statutory requirement in the same way it always has been implemented. Given PURPA's unique statutory scheme involving state regulatory authorities, nonregulated electric utilities, QFs, and the Commission, we therefore reject Allco's assertion that the rules proposed in the NOPR—and adopted in this final rule—establish an unconstitutional delegation of authority to a private entity. ¹³⁸ And it is beyond the Commission's purview to consider whether this statutory grant is constitutional. ¹³⁹

¹³⁷ See Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,864 ("The implementation of these rules is reserved to the State regulatory authorities and nonregulated electric utilities.").

¹³⁸ See Allco Comments at 40.

administrative agencies "have neither the power nor the competence to pass on the constitutionality of administrative or legislative action") (quoting *Murray v. Vaughn*, 300 F. Supp. 688, 695 (D. R.I. 1969)); see also Gibas v. Saginaw Mining Co., 748 F.2d 1112, 1117 (6th Cir. 1984) ("[A]dministrative bodies like the Board do not have the authority to adjudicate the validity of legislation which they are charged with administering."); Spiegel, Inc. v. FTC, 540 F.2d 287, 294 (7th Cir. 1976) (finding that the federal agency erred by making a constitutional determination); Downen v. Warner, 481 F.2d 642, 643 (9th Cir. 1973) ("Resolving a claim founded solely upon a constitutional right is singularly suited to a judicial forum and clearly inappropriate to an administrative board."); cf. Woodrow v. FERC, 2020 WL 2198050, at *9 (D.D.C. May 6, 2020) ("When Congress creates an intricate statutory-review process that incorporates agency

Accordingly, when we refer to states in this final rule, we usually are referring to both state regulatory authorities and nonregulated electric utilities.

95. Regarding Public Interest Organizations assertion that the Commission failed to comply with PURPA section 210's requirement to consult with federal and state regulatory agencies with ratemaking authority, we find that the 2016 Technical Conference's invitation to the public (including state regulatory authorities) to speak, as well as the notice and comment process on the NOPR itself, encompasses the required consultation. The notices soliciting comments were open to all state authorities. Indeed, since the Commission first announced that technical conference and up to our receipt of comments on the NOPR, representatives from several states have filed comments expressing their views on how the Commission should implement PURPA.

B. QF Rates

1. <u>Overview</u>

96. PURPA requires that the Commission promulgate rules, to be implemented by the states, ¹⁴¹ that "shall insure" that the rates electric utilities pay for purchases of electric

consideration and ultimately an avenue to petition an Article III court, we assume it wants that scheme to control.").

¹⁴⁰ See Notice Inviting Post-Technical Conference Comments, *Implementation Issues Under the Public Utility Regulatory Policies Act of 1978*, Docket No. AD16-16-000 (Sept. 6, 2016); Supplemental Notice of Technical Conference, *Implementation Issues Under the Public Utility Regulatory Policies Act of 1978*, Docket No. AD16-16-000 (Mar. 4, 2016) (announcing preliminary agenda and inviting interested speakers).

¹⁴¹ Nonregulated electric utilities implement the requirements of PURPA with respect to themselves. An electric utility that is "nonregulated" is any electric utility other than a "state regulated electric utility." 16 U.S.C. 2602(9). The term "state regulated"

energy from QFs meet the statutory criteria described above, including that "[n]o such rule... shall provide for a rate which exceeds" the purchasing utility's "incremental cost... of alternative electric energy." Under PURPA, such rates must: (1) be just and reasonable to the electric consumers of the electric utility and in the public interest; (2) not discriminate against qualifying cogenerators or qualifying small power producers; ¹⁴³ and, as noted above, (3) not exceed "the incremental cost to the electric utility of alternative electric energy," which is "the cost to the electric utility of the electric energy which, but for the purchase from such cogenerator or small power producer, such utility would generate or purchase from another source." The "incremental cost to the electric utility of alternative electric energy" referred to in prong (3) above, which sets out a statutory upper bound on a QF rate, has been consistently referred to by the Commission and industry by the short-hand phrase "avoided cost," ¹⁴⁶ although the term "avoided cost" itself does not appear in PURPA.

electric utility," in contrast, means any electric utility with respect to which a state regulatory authority has ratemaking authority. 16 U.S.C. 2602(18). The term "state regulatory authority," as relevant here, means a state agency which has ratemaking authority with respect to the sale of electric energy by an electric utility. 16 U.S.C. 2602(17).

¹⁴² 16 U.S.C. 824a-3(b).

¹⁴³ 16 U.S.C. 824a-3(b)(1)-(2).

¹⁴⁴ 16 U.S.C. 824a-3(b).

¹⁴⁵ 16 U.S.C. 824a-3(d) (emphasis added).

¹⁴⁶ See 18 CFR 292.101(b)(6) (defining avoided costs in relation to the statutory terms); see also Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,865 ("This definition is derived from the concept of 'the incremental cost to the electric utility of alternative"

- 97. In addition, the PURPA Regulations currently provide a QF two options for how to sell its power to an electric utility. The QF may choose to sell as much of its energy as it chooses when the energy becomes available, with the rate for the sale calculated at the time of delivery (frequently referred to as a so-called "as-available" sale and rate). Alternatively, the QF may choose to sell pursuant to a legally enforceable obligation or LEO (such as a contract) over a specified term. 148
- 98. If the QF chooses to sell under the second option, the PURPA Regulations then provide the QF the further option of receiving, in terms of pricing, either: (1) the purchasing electric utility's avoided cost calculated at the time of delivery; ¹⁴⁹ or (2) the purchasing electric utility's avoided cost calculated and fixed at the time the LEO is incurred. ¹⁵⁰
- 99. In implementing the PURPA Regulations, the Commission recognized that a contract with avoided costs calculated at the time a LEO is incurred could exceed the

electric energy' set forth in section 210(d) of PURPA. It includes both the fixed and the running costs on an electric utility system which can be avoided by obtaining energy or capacity from qualifying facilities.").

¹⁴⁷ 18 CFR 292.304(d)(1).

 $^{^{148}}$ 18 CFR 292.304(d)(2)(i)-(ii); see also FLS, 157 FERC ¶ 61,211 at P 21 (citing 18 CFR 292.304(d)). The LEO or contract is frequently referred to as a long-term transaction, when contrasted with an "as available" sale and rate.

¹⁴⁹ 18 CFR 292.304(d)(2)(i).

^{150 18} CFR 292.304(d)(2)(ii). Rates calculated at the time of a LEO (for example, a contract) do not violate the requirement that the rates not exceed avoided costs if they differ from avoided costs at the time of delivery. 18 CFR 292.304(b)(5).

electric utility's avoided costs at the time of delivery in the future, thereby seemingly violating PURPA's requirement that QFs not be paid more than an electric utility's avoided costs. But the Commission believed that the fixed avoided cost rate might also turn out to be lower than the electric utility's avoided costs over the course of the contract and that, "in the long run, 'overestimations' and 'underestimations' of avoided costs will balance out." The Commission's justification for allowing QFs to fix their rate at the time of the LEO for the entire life of the contract was that fixing the rate provides "certainty with regard to return on investment in new technologies." 152

100. In the NOPR, the Commission proposed to revise its PURPA Regulations to permit states to incorporate competitive market forces in setting QF rates. Specifically, the Commission proposed to revise its PURPA Regulations with regard to QF rates to provide states with the flexibility to:

• require that "as-available" QF energy rates paid by electric utilities located in RTO/ISO markets be based on the market's LMP, or similar energy price derived by the market, in effect at the time the energy is delivered.

¹⁵¹ Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,880. See also 18 CFR 292.304(b)(5) ("In the case in which the rates for purchases are based upon estimates of avoided costs over the specific term of the contract or other legally enforceable obligation, the rates for such purchases do not violate this subpart if the rates for such purchases differ from avoided costs at the time of delivery."); Entergy Servs., Inc., 137 FERC ¶ 61,199, at P 56 (2011) ("Many avoided cost rates are calculated on an average or composite basis, and already reflect the variations in the value of the purchase in the lower overall rate. In such circumstances, the utility is already compensated, through the lower rate it generally pays for unscheduled QF energy, for any periods during which it purchases unscheduled QF energy even though that energy's value is lower than the true avoided cost.").

¹⁵² Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,880.

- require that "as-available" QF energy rates paid by electric utilities located outside of RTO/ISO markets be based on competitive prices determined by: (1) liquid market hub energy prices; or (2) formula rates based on observed natural gas prices and a specified heat rate.
- require that energy rates under QF contracts and LEOs be based on as-available energy rates determined at the time of delivery rather than being fixed for the term of the contract or LEO.
- implement an alternative approach of requiring that the fixed energy rate be calculated based on estimates of the present value of the stream of revenue flows of future LMPs or other acceptable as-available energy rates at the time of delivery.
- require that energy and/or capacity rates be determined through a competitive solicitation process, such as an RFP, with processes designed to ensure that the competitive solicitation is performed in a transparent, non-discriminatory fashion. 153
- 101. Although the Commission proposed to modify how the states are permitted to calculate avoided costs, it did not propose to terminate the requirement that the states continue to calculate, and to set QF rates at, such avoided costs.
- 102. We adopt these proposals in this final rule, with certain modifications. Each such proposal, and our final determination, is discussed further below.

2. <u>Use of Competitive Market Prices to Set As-Available Avoided</u> <u>Cost Rates</u>

103. In addition to commenting on the specific methods for determining as-available avoided cost rates, several commenters addressed more generally the Commission's proposal in the NOPR that states be given the flexibility to use competitive market prices to set such rates. Before discussing the specific methods proposed in the NOPR, we first

¹⁵³ NOPR, 168 FERC ¶ 61,184 at PP 32-33.

discuss the determination that the use of competitive market prices, however determined, can be an appropriate approach to determining as-available avoided cost rates.

a. NOPR Proposal

104. In the NOPR, the Commission proposed to give the states the flexibility to use competitive market prices to set as-available avoided cost rates. The Commission stated its belief that consideration of transparent, competitive market prices in appropriate circumstances would help to identify an electric utility's avoided costs in a simpler, more transparent, and more predictable manner that would, in conjunction with the Commission's other existing and proposed PURPA Regulations, act to encourage QFs. 154 105. For those utilities located in RTO/ISO markets, the NOPR identified LMP as a competitive market price that states could choose to adopt as representing an as-available avoided energy cost. The Commission explained that LMP could provide an accurate measure of the varying actual avoided costs for each receipt point on an electric utility's system where the utility receives power from QFs. 155 In addition to these benefits, the Commission observed that LMPs, in contrast to the administrative pricing methodologies used to set as-available QF rates by many states, could promote the more efficient use of the transmission grid, promote the use of the lowest-cost generation, and provide for transparent price signals. 156

¹⁵⁴ *Id.* P 13.

¹⁵⁵ *Id.* P 45.

¹⁵⁶ Id. P 48 (citing Cal. Indep. Sys. Operator Corp., 105 FERC ¶ 61,140, at PP 48-50 (2003); Cf. Price Formation in Energy and Ancillary Servs. Mkts Operated by Reg'l

106. For utilities located outside of RTO/ISO markets, the NOPR proposed to allow states to use two other potential competitively priced measures of a utility's as-available avoided cost rates: (1) energy rates established at liquid market hubs; or (2) energy rates determined pursuant to formulas based on natural gas price indices and a proxy heat rate for an efficient natural gas combined-cycle generating facility. In each such case, though, the state would need to find that that price reasonably represents a competitive market price that represents the avoided costs of the purchasing electric utility. ¹⁵⁷

b. Comments

107. Allco argues that the only reason for including the use of competitive market prices to set as-available energy rates is to create a menu of prices from which a state regulatory authority or unregulated electric utility can choose the lowest price. Allco claims this proposal would not encourage QF generation, would be inconsistent with the rules of economic dispatch, and would be inconsistent with the language of PURPA. BluEarth makes similar arguments. In contrast, El Paso Electric argues that state regulatory authorities should be able to set avoided cost rates based on the lesser of a market hub price or a combined cycle price. Similarly, the California Commission argues that

Transmission Orgs. and Indep. Sys. Operators, 153 FERC ¶ 61,221, at P 2 (2015)).

¹⁵⁷ NOPR, 168 FERC ¶ 61,184 at P 51.

¹⁵⁸ Allco Comments at 8.

¹⁵⁹ BluEarth Comments at 2.

¹⁶⁰ El Paso Electric Comments at 3-4.

utilities located in organized markets (not just non-organized markets) should also be expressly permitted to use any competitive price (whether derived from a market hub, competitive solicitation, or a combined cycle price) to set avoided cost rates. The California Commission also argues that states should have the ability to use competitive prices for not just as-available energy pricing, but also for capacity pricing, and proposes minor modifications to the relevant regulation text proposed in the NOPR in order to clarify these points.¹⁶¹

108. The California Commission argues that the proposed regulations should be modified to: (1) define the newly permissible avoided cost methodologies within the definitions section of Part 292; (2) eliminate any perception that the new methodologies can only be used to set avoided costs for as-available energy; (3) allow any appropriate market-based methodology to set avoided-cost rates for energy, capacity or both; and (4) define "Organized Electric Market." The California Commission believes that the new regulations should indicate: (1) that they do not provide states any more flexibility than they already have; (2) that utilities located in organized markets may use any Market Hub Price, Competitive Solicitation Price, or Combined Cycle Price to establish avoided-cost rates; and (3) that a price based on LMP or a Competitive Price is just and reasonable and nondiscriminatory. ¹⁶³

¹⁶¹ California Commission Comments at 23-27.

¹⁶² *Id.* at 11-14.

¹⁶³ *Id.* at 23-25.

109. Some commenters object to the use of competitive markets prices on the grounds that these competitive prices represent only short-term, or spot prices that do not reflect the long-term marginal costs and other costs avoided by purchasing utilities. 164 Similarly, some commenters assert that competitive prices cannot support the financing of QFs. 165 110. Public Interest Organizations argue that using competitive prices to set as-available energy avoided cost rates is discriminatory because non-QF generators are not limited to competitive prices and utilities can, and regularly do, pay effective prices for energy that exceed the price determined by competitive prices. 166 Several other commenters express concern about setting QF prices by referencing short-term liquid hub prices while allowing utilities to rate base and recover their long-term investments. 167 Industrial Energy Consumers argue that, if the Commission implements the liquid market hub proposal, there must be assurances that utilities' self-builds face the same market risk exposure as QFs. For example, they argue, if states expose QFs to variable rates for their energy output, utility-owned generation should also be exposed to variable rates for their energy output. 168

¹⁶⁴ IdaHydro Comments at 11; Southeast Public Interest Organizations Comments at 19; NIPPC, CREA, REC, and OSEIA Comments at 52, 55 (citing *Exelon Wind I, LLC*, 140 FERC ¶ 61,152, at P 52 (2012)); Union of Concerned Scientists Comments at 6.

¹⁶⁵ BluEarth Renewables Comments at 2; Biological Diversity at 8; Covanta Comments at 9; Public Interest Organization Comments at 43-44.

¹⁶⁶ Public Interest Organizations Comments at 64.

¹⁶⁷ IdaHydro Comments at 11; Industrial Energy Consumers Comments at 12-13.

¹⁶⁸ Industrial Energy Consumers Comments at 12-13.

- 111. Several commenters assert that QF rates should reflect benefits other than the avoided cost of energy. ¹⁶⁹ For example, Biogas and Biomass Power state that non-energy benefits, like waste reduction and economic development must be incorporated into avoided cost determinations. ¹⁷⁰ Biogas and Resources for the Future state that locational values should be incorporated into avoided cost calculations. ¹⁷¹ American Dams states that utilities' avoided transmission charges should be included in avoided cost determinations. ¹⁷² Xcel states that hidden integration and utility planning costs should also be incorporated into avoided cost calculations. ¹⁷³ American Dams argues that for high capital projects like hydro, the Commission should consider longer-term public benefits and not just short-term market pricing. ¹⁷⁴
- 112. Solar Energy Industries asserts that payments based on the LMP should not relieve the purchasing utility of the requirement to compensate the QF for any values in addition to electricity (e.g., renewable energy credits, frequency response capabilities, pro-rated capacity value, etc.). ¹⁷⁵

¹⁶⁹ Biogas Comments at 1-2; Biomass Power Comments at 1; EPSA Comments at 14-16; Resources for the Future Comments at 4; Xcel Comments at 3-5.

¹⁷⁰ Biogas Comments at 2; Biomass Power Comments at 1.

¹⁷¹ Biogas Comments at 1; Resources for the Future Comments at 4.

¹⁷² American Dams Comments at 4.

¹⁷³ Xcel Comments at 3-5.

¹⁷⁴ American Dams Comments at 2.

¹⁷⁵ Solar Energy Industry Comments at 27-28.

113. California Utilities request that the Commission clarify that states may but are not required to consider state policies when establishing avoided costs. Harvard Electricity Law requests that the Commission clarify its rule allowing states to set tiered rates. 177

c. <u>Commission Determination</u>

about the use of competitive market prices to set as-available energy rates for QFs are based on the incorrect assumption that the NOPR proposal would permit states to use competitive market prices to set as-available energy rates for QFs even when competitive market prices are below the purchasing utility's avoided costs. In fact, however, the use of competitive market prices to set QF rates is explicitly subject to the requirement that such prices are equal to the purchasing utility's avoided energy costs. As the Supreme Court noted in *API*, the full avoided cost rate requirement represents the maximum rate permitted under PURPA, and thereby provides important encouragement to QFs. And as the Supreme Court also noted in the same decision, "the full-avoided-cost rule plainly satisfies the nondiscrimination requirement." Further, in requiring full avoided cost

¹⁷⁶ California Utilities Comments at 18-19.

¹⁷⁷ Harvard Electricity Law Comments at 32-33.

¹⁷⁸ Arguments that the various competitive market prices identified in this final rule do not represent avoided energy costs are addressed below with respect to each such specific market price.

¹⁷⁹ API, 461 U.S. at 413.

¹⁸⁰ *Id*.

rates, "[t]he Commission did not ignore the interest of electric utility consumers 'in receiving electric energy at equitable rates." 181

- 115. For this reason, Allco is incorrect when it claims that the competitive price proposal represents a menu of prices that a state can select to choose the lowest rate. In the event that more than one competitive price option potentially could apply, the state would be required to select the option that reasonably reflects the purchasing utility's avoided costs, which is what PURPA requires. ¹⁸²
- 116. Further, the record supports the conclusion that the use of transparent, competitive market prices provides encouragement to QFs, represents the avoided cost, and can ensure that the rate does not exceed the incremental cost to the purchasing electric utility. In addition to the testimony to this effect presented at the technical conference and cited in the NOPR, ¹⁸³ the conclusion is further supported by comments submitted in response to

¹⁸¹ *Id.* at 415 (quoting Conf. Rep. at 97).

¹⁸² In a competitive market, the transportation costs between any such two hubs and a QF would be such that they would make the QF rate the same, no matter which hub was selected. *See* FERC, *Energy Primer*, *A Handbook of Market Basics*, at 64 (June 2020), https://www.ferc.gov/market-assessments/guide/energy-primer-2020.pdf (Energy Primer) ("If there are no transmission constraints, or congestion, LMPs will not vary significantly across the RTO footprint. However, when transmission congestion occurs, LMPs will vary across the footprint because operators are not able to dispatch the least-cost generators across the entire region and some more expensive generation must be dispatched to meet demand in the constrained area.").

¹⁸³ See American Forest & Paper Association Comments, Docket No. AD16-16-000, at 8 (filed June 8, 2016) ("To the extent possible, these determinations [of avoided costs] should not be made in a 'black box', but rather, as part of an open and transparent method and process."); EEI Comments, Docket No. AD16-16-000, at 3 (filed June 30, 2016) ("Where transparent competitive markets with day ahead prices exist, there is no

the NOPR. For example, NIPPC, CREA, REC, and OSEIA cite to a report by Fitch, which explains how Fitch evaluates the financial strength of renewable energy projects. In this report, Fitch states that it gives a "stronger" evaluation to projects with power sales contract prices that are "indexed using simple, broad-based publicly available indexation formulas." In addition, Solar Energy Industries notes the difficulties QFs face in expending large sums to develop their projects "[f]or states that do not publish the avoided costs, or for utilities that treat their avoided cost methodologies as confidential trade secrets." ¹⁸⁵

117. We agree with commenters who assert that competitive market prices represent only short-run spot prices that do not reflect electric utilities' long-run costs that QFs can displace. However, we are authorizing states to use competitive market prices only to establish as-available energy rates for QFs. The comments misunderstand the fundamental difference between the value to a purchasing utility of such as-available energy and the value to a purchasing utility of capacity.

118. A QF has no obligation under the as-available avoided cost rate provisions to deliver any set amount of electric energy at any point in the future, but merely is paid for the amount of electric energy actually delivered. Therefore, the delivery of as-available

reason to adhere to second-best avoided cost pricing mechanisms.").

¹⁸⁴ NIPPC, CREA, REC, and OSEIA Comments at 37-38 (citing *FitchRatings*, *Global Infrastructure & Project Finance, Renewable Energy Project Rating Criteria*, at 3 (Feb. 26, 2019), https://www.fitchratings.com/site/re/10061770).

¹⁸⁵ Solar Energy Industries Comments at 41.

energy does not displace any long-term energy the purchasing electric utility would generate itself or purchase from another source but rather allows the purchasing utility to reduce the amount of energy it otherwise would generate itself or purchase from another entity at the time the QF delivers the energy. Because the QF has no obligation to deliver any energy in the future, the utility is unable to avoid constructing or contracting for capacity to meet its future needs as a consequence of the delivery of energy by the QF. As-available energy rates therefore appropriately reflect only the short-run value of energy delivered at the particular moment in time when and if the QF has energy available to be delivered to the utility.

119. A QF can displace an electric utility's own generation or purchases from alternative sources over the long-run when a QF sells capacity to a utility in addition to as-available energy. In contrast to as-available energy, a sale of capacity would typically compensate the QF for maintaining the capability to deliver a set amount of energy in the future (i.e., capital costs), ¹⁸⁶ and thus allows the purchasing utility to avoid the cost of making alternative arrangements, either through a self-build or an alternative purchase, to obtain that amount of energy. Consequently, the price of capacity purchased from a QF would reflect this long-run avoided cost. And this final rule does not alter a purchasing utility's

¹⁸⁶ See Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,885 ("Energy costs are the variable costs associated with the production of electric energy (kilowatt-hours). They represent the cost of fuel, and some operating and maintenance expenses. Capacity costs are the costs associated with providing the capability to deliver energy; they consist primarily of the capital costs of facilities.").

existing obligation to pay QFs for any avoided capacity benefit that allows the utility to avoid acquiring capacity. 187

For these reasons, we decline to grant the California Commission's request to allow using competitive prices for not just as-available energy pricing, but also for capacity pricing. 188 We also reject the California Commission's request to permit all electric utilities, both those located in organized markets and those located in non-organized market areas, to use any competitive price (whether a Market Hub Price or Combined Cycle Price, or alternatively a Competitive Solicitation Price) to set avoided cost rates. The Market Hub Price and Combined Cycle Price, as well as the Competitive Solicitation Price are options that should generally reflect a purchasing electric utility's avoided asavailable energy costs in non-RTO/ISO areas, while the LMP should generally reflect a purchasing electric utility's avoided as-available energy costs in RTO/ISO market areas. With respect to the discrimination claims, our decision to give states the flexibility to use competitive prices is driven by the fact that the competitive market price represents the purchasing utility's avoided costs. And, as explained in Section IV.A.2 above, a rate set at full avoided costs by definition cannot be discriminatory and, in any event, the Commission is without authority under PURPA section 210(b) to require a rate above avoided costs.

¹⁸⁷ See Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,881-86 (describing how states must calculate avoided capacity costs).

¹⁸⁸ See infra sections IV.B.3-5. We note that states may use competitive solicitations to set both energy and capacity avoided cost rates. See infra section IV.B.8.

- 122. Further, Industrial Energy Consumers are incorrect when they suggest that public utility energy rates do not vary with costs in the same way that the competitive market prices potentially applicable to QFs under the final rule vary. To the contrary, the Commission and most states provide for fuel adjustment clauses applicable to rates, which allow utility rates to adjust automatically with changes in utility fuel and purchased power costs. ¹⁸⁹ And even utilities whose rates do not include fuel and purchased power adjustment clauses nevertheless typically must charge their retail customers cost-based rates, which means that their energy charges will vary from one rate case to the next as their fuel and purchased power costs vary from year to year. These mechanisms for ensuring that utility rates vary with the cost of energy result in variances in utility energy rates that are similar to the variance in QF energy rates for those states that elect a Competitive Price option (either a Market Hub Price or a Combined Cycle Price) for as-available avoided cost rates.
- 123. Finally, although we are sympathetic to the claims of certain QFs that they provide non-energy benefits (such as environmental benefits, waste reduction benefits, and economic development benefits) that are not reflected in avoided cost rates, PURPA section 210(b) prohibits the Commission from requiring QF rates to be set above full

¹⁸⁹ See 18 CFR 35.14 (Fuel Cost and Purchased Economic Power Adjustment Clauses); ELCON, Fuel Adjustment Clauses & Other Cost Trackers, https://elcon.org/fuel-adjustment-clauses-cost-trackers ("Fuel adjustment clauses are in effect in almost all states."); NARUC, Staff Subcommittee on Accounting and Finance, Fuel and Purchased Power Survey Results (Sept. 23, 2015), https://pubs.naruc.org/pub/4AA28D50-2354-D714-5149-B773EFC3EFEF (stating that only one state surveyed said that it did not employ a fuel adjustment clause).

avoided costs. Because the Commission already requires states to set QF rates at full avoided costs, it is barred from requiring QF rates set higher than that based on the non-energy benefits that QFs may also provide. However, nothing in PURPA, the PURPA Regulations as they currently exist, or this final rule would prevent states from rewarding QFs for such non-energy benefits so long as that is done outside of PURPA, such as is now done for renewable energy credits (RECs) to compensate QFs for providing unique environmental or other non-PURPA benefits. We address in the sections below each type of competitive price that could be used as an acceptable energy avoided cost.

3. <u>LMP as a Permissible Rate for Certain As-Available Avoided Cost Rates</u>

a. NOPR Proposal

- 124. The Commission proposed to revise 18 CFR 292.304 to add subsections (b)(6) and (e)(1). In combination, these subsections would permit a state the flexibility to set the asavailable energy rate paid to a QF by an electric utility located in an RTO/ISO at LMPs calculated at the time of delivery.
- 125. The Commission explained that RTO/ISO markets calculate a LMP at each location on the RTO/ISO-controlled grid, and that all sellers receive the LMP for their location and all buyers pay the market clearing price for their location. The Commission further recognized that LMPs reflect the true marginal cost of production, taking into

¹⁹⁰ See, e.g., American Ref-Fuel Co., 105 FERC ¶ 61,004, at PP 22-24 (2003), denying reh'g, 107 FERC ¶ 61,016 at PP 12, 15-16 (2004), dismissing pet. for review sub nom. Xcel Energy Servs. Inc. v. FERC, 407 F.3d 1242 (D.C. Cir. 2005).

account all physical system constraints, and these prices would fully compensate all resources for the variable cost of providing service, ¹⁹¹ and explained that prices in such an LMP-based rate structure are designed to reflect the least-cost of meeting an incremental megawatt-hour of demand at each location on the grid in each period, and thus such prices can vary based on location and time. ¹⁹²

126. The Commission therefore preliminarily found that LMP is an accurate measure of avoided costs. Unlike, for example, average system-wide cost measures of avoided cost used by many states, LMP could provide an accurate measure of the varying actual avoided costs for each receipt point on an electric utility's system where the utility receives power from QFs; LMP is the per MWh cost of obtaining incremental supplies at each point. Further, the Commission explained that these prices are not rigid, long-lasting prices as tends to be the case currently for administratively-determined avoided costs, but prices that are calculated daily (for the day-ahead markets) and/or every five minutes (for real-time markets) and they vary to reflect changing system conditions (e.g., they tend to rise as demand increases and the system operator dispatches increasingly expensive supplies to meet that higher demand). In addition, the Commission observed that LMPs, in contrast to the administrative pricing methodologies used to set as-available QF rates by

¹⁹¹ Offer Caps in Mkts Operated by Reg'l Transmission Orgs. and Independent Sys. Operators, Order No. 831, 157 FERC ¶ 61,115, at P 7 (2016), order on reh'g and clarification, Order No. 831-A, 161 FERC ¶ 61,156 (2017).

¹⁹² Sacramento Mun. Util. Dist. v. FERC, 616 F.3d 520, 524 (D.C. Cir. 2010) (SMUD); see also FERC v. Elec. Power Supply Ass'n, 136 S. Ct. 760, 768-69 (2016) (describing how LMP is typically calculated).

many states, could promote the more efficient use of the transmission grid, promote the use of the lowest-cost generation, and provide for transparent price signals. Finally, the Commission also noted that Congress, through enactment of PURPA section 210(m), appears to have recognized that RTO/ISO LMP pricing provides sufficient encouragement for QFs.

127. The Commission requested comment on whether the real-time prices established in the CAISO-administered Energy Imbalance Market (EIM)¹⁹⁴ are similar for these purposes to the LMP in RTOs/ISOs. In this regard, the Commission requested comment on whether "prices developed in the EIM similarly 'reflect the least-cost of meeting an incremental megawatt-hour of demand at each location on the grid,' as the Commission has found to be the case with LMP rates."¹⁹⁵

¹⁹³ See, e.g., Cal. Indep. Sys. Operator Corp., 105 FERC ¶ 61,140, at PP 48-50 (2003); cf. Price Formation in Energy and Ancillary Servs. Mkts Operated by Reg'l Transmission Orgs. and Indep. Sys. Operators, 153 FERC ¶ 61,221, at P 2.

¹⁹⁴ The Commission noted that, by seeking comment regarding the Western EIM prices, the Commission did not mean to imply that real-time energy prices established by CAISO within its balancing authority area do not already satisfy the requirement for setting as-available QF rates.

¹⁹⁵ NOPR, 168 FERC 61,184 at P 47 (quoting *SMUD*, 616 F.3d at 524). Use of real time prices in the Western EIM was addressed at the Technical Conference, but only in the context of whether that market could satisfy the requirements for termination of the mandatory purchase obligation under PURPA section 210(m)(1)(C). *See* Supplemental Notice of Technical Conference, *Implementation Issues Under the Public Utility Regulatory Policies Act of 1978*, Docket No. AD16-16-000 (May 9, 2016). The Commission here requested comments on whether it would be appropriate to use the Western EIM price to develop an as-available energy rate.

128. The Commission understood that some states already use LMP to establish avoided cost energy rates under the existing PURPA Regulations. The Commission thus proposed also to clarify that, while a state in the past may have been able to conclude that LMP was an appropriate measure of the energy component of avoided costs, a state would, under the proposal in the NOPR, be able to adopt LMP as a per se appropriate measure of the as-available energy component of avoided costs.

¹⁹⁶ See Exelon Wind 1, LLC, 140 FERC ¶ 61,152, at P 11, reconsideration denied, 155 FERC ¶ 61,066 (2016) (recognizing that the Texas Public Utility Commission has permitted Southwestern Public Service Company to set avoided costs at LMP); Xcel Energy Services Inc., Request for Reconsideration, Docket No. EL12-80-001, at 13 & n.23 (filed Sept. 27, 2012) (stating that Maryland, New Jersey, North Carolina, Virginia, Connecticut, New Hampshire, Kentucky, and Michigan have set avoided costs at LMP).

¹⁹⁷ See 18 CFR 292.304(e).

¹⁹⁸ The Commission recognized in the NOPR that this proposal could be seen as a departure from the Commission's statement in Exelon Wind 1, LLC, 140 FERC ¶ 61,152 at P 52, reconsideration denied, 155 FERC ¶ 61,066 ("The problem with the methodology proposed by [Southwestern Public Service Company] and adopted by the Texas Commission is that it is based on the price that a QF would have been paid had it sold its energy directly in the [Energy Imbalance Service] Market, instead of using a methodology of calculating what the costs to the utility would have been for self-supplied, or purchased, energy 'but for' the presence of the QF or QFs in the markets, as required by the Commission's regulations."). The Commission has since found that this statement was overtaken by events, namely SPP's evolution from an energy imbalance service market into an Integrated Marketplace, with day-ahead and real-time energy and operating reserve markets and the Texas Commission's approving a separate request from Southwestern Public Service Company to substitute LMP for Locational Imbalance Prices in calculating avoided costs. Exelon Wind 1, LLC, 155 FERC ¶ 61,066 at P 11. The Commission also has acknowledged that, if adopted in a final rule, the reasoning in the NOPR supported a departure from precedent. See Cal. Pub. Utils. Comm'n v. FERC, 879 F.3d 966, 977 (9th Cir. 2018) ("When an agency changes policy, the requirement that it provide a reasoned explanation for its action demands, at a minimum, that the agency 'display awareness that it is changing position.") (citing FCC v. Fox Television Stations, Inc., 556 U.S. 502, 515 (2009)).

b. Comments

i. <u>Comments in Opposition</u>

129. Several commenters oppose the NOPR's LMP proposal. 199 American Biogas asserts that, by definition, LMP rates assume that generating facilities are receiving other compensation to fund their operations and that the marginal rate reflects only the value of the energy. American Biogas asserts that LMP ignores biogas facilities' unique municipal infrastructure role and multiple benefits to the community. 200 Covanta argues that avoided costs paid to small baseload QFs should incorporate all long-run avoided costs for capacity and energy and include other externalities such as the value of renewable baseload energy, greenhouse gas mitigation, landfill diversion, reliable and resilient power and other benefits of small baseload QFs. 201 Biological Diversity argues that LMP pricing ignores variability across the country and is inappropriate in regions like the Southeast which lack RTOs and ISOs and are instead still dominated by vertically-integrated monopolies. 202

¹⁹⁹ Biogas Comments at 2; Covanta Comments at 8-9; Biological Diversity Comments at 8-9; CA Cogeneration Comments at 8-9; ELCON Comments at 23-25; ENGIE Comments at 4; New England Small Hydro Comments at 8-11; NIPPC, CREA, REC, and OSEIA Comments at 53-60; Public Interest Organizations Comments at 52-64; Union of Concerned Scientists Comments at 4-9; Southeast Public Interest Organizations Comments at 21-25.

²⁰⁰ Biogas Comments at 2.

²⁰¹ Covanta Comments at 8.

²⁰² Biological Diversity Comments at 8-9.

130. CA Cogeneration argues that LMP may not represent a truly competitive price for electricity because, in California, the majority of supply is through bilateral contracts, not through competitive bidding in the market. CA Cogeneration states that rooftop solar distorts LMP by reducing load and not bidding in its full long-term marginal cost. CA Cogeneration states that LMPs can be well below the operating cost of conventional generation and combined heat and power, and even negative, especially when there is an abundance of procured resources such as hydro, solar, and wind. CA Cogeneration asserts that combined heat and power can survive only if: (1) fixed capacity prices are sufficiently high to cover the energy price risk; (2) the market price reflects the full cost of contracted power and includes all sources of supply; or (3) 18 CFR 292.304(f)(1) is modified to provide QF operations first priority, except in special circumstances related to reliability. On the contracted power and includes all sources of supply; or (3) the market price reflects the full cost of contracted power and includes all sources of supply; or (3) the market price reflects the full cost of contracted power and includes all sources of supply; or (3) the market price reflects the full cost of contracted power and includes all sources of supply; or (3) the market price reflects the full cost of contracted power and includes all sources of supply; or (3) the market price reflects the full cost of contracted power and includes all sources of supply; or (3) the market price reflects the full cost of contracted power and includes all sources of supply; or (3) the market price reflects the full cost of contracted power and includes all sources of supply; or (3) the market price reflects the full cost of contracted power and includes all sources of supply; or (3) the market price reflects the full cost of contracted power and includes all sources of supply; or (3) the market price reflects the full cost of contracted power and includes all

131. ELCON argues that allowing utilities to use LMP and other competitive market prices would allow states to ignore long-standing factors established by Commission regulation in determining the avoided cost rates, including: (1) availability of capacity or energy from a QF during the system daily and seasonal peak periods; (2) dispatchability and reliability; (3) the relationship of the availability of energy or capacity from the QF to the ability of the utility to avoid costs; (4) costs or savings from variations in line losses;

²⁰³ CA Cogeneration Comments at 8-9.

²⁰⁴ *Id*.

²⁰⁵ *Id*.

and (5) application of technology-specific avoided cost rates.²⁰⁶ ENGIE argues that allowing states to set energy rates at LMP, while also allowing them to set capacity rates at zero if it is determined that a utility has no need for capacity, could allow traditional utilities to corner the market on capacity, leaving smaller independent QFs to fill energy-only contracts at LMP.²⁰⁷

132. New England Small Hydro states that the Commission has not supported the NOPR's assertion that LMP is an accurate measure of avoided costs because the NOPR: (1) inappropriately relies on the Energy Policy Act of 2005's changes in PURPA section 210(m) to support its proposed changes to calculation of the avoided cost rate; (2) ignores the costs that the utility pays to procure power (i.e., RFPs, other power contracts, planned retirements); and (3) ignores the fact that LMP and the default service rates that exist in ISO-NE-based states are quite different. ²⁰⁸ In addition, New England Hydro states that, for the avoided cost calculation, the appropriate LMP is the day-ahead LMP, not the real-time LMP, because utilities primarily purchase energy in the day-ahead market pursuant to bilateral contracts or RFPs, not in the real-time market. ²⁰⁹ New England Hydro also believes that utilities or state regulatory bodies should be required to establish and

²⁰⁶ ELCON Comments at 23-24.

²⁰⁷ ENGIE Comments at 4.

²⁰⁸ New England Small Hydro Comments at 8-10.

²⁰⁹ *Id.* at 10.

maintain long-term avoided energy forecasts upon which QF PURPA power purchase rates would be based.²¹⁰

NIPPC, CREA, REC, and OSEIA claim that LMPs only promote more efficient use of the transmission grid in the short-term because factors such as temporary outages, equipment failures, weather extremes, and the like can cause LMPs to spike, but these have no impact on long-term transmission availability.²¹¹ NIPPC, CREA, REC, and OSEIA believe that, while LMPs are a useful tool for developers to identify points on the grid where transmission is relatively more or less congested, developers have strong incentives to avoid congestion, and they will generally be guided to areas of low congestion during the transmission interconnection process, whether or not they face LMP-based contract prices. NIPPC, CREA, REC, and OSEIA claim that if transmission constraints prevent a generator from delivering power to a specific node, the LMP at that node cannot be an appropriate measure of costs avoided by purchase of power from that generator. NIPPC, CREA, REC, and OSEIA argue that LMP or Western EIM prices at the time of delivery are not a true measure of the long-term avoided costs of incumbent utilities unless those utilities are relying on those markets as a means to obtain long-term resources.²¹²

²¹⁰ *Id.* at 11.

²¹¹ NIPPC, CREA, REC, and OSEIA Comments at 57-59.

²¹² *Id.* at 55 (citing *Exelon Wind I*, 140 FERC ¶ 61,152 at P 52).

- 134. NIPPC, CREA, REC, and OSEIA assert that the NOPR proposal fails to recognize: (1) the Commission's struggle to develop effective capacity markets in the RTO/ISO regions; (2) the fact that the merchant generation model is now in serious question; and (3) that the Commission's claim that Congress endorsed the use of LMP to set avoided cost rates by adoption of section 210(m) cannot be squared with the plain language of the statute. NIPPC, CREA, REC, and OSEIA argue that there is substantial evidence that LMP prices are distorted by certain practices, such as zero-cost bids, so that plants operate uneconomically. NIPPC, CREA, REC, and OSEIA further maintain that the 2000-01 California market demonstrated that these volatile short-term markets can reach extreme and unpredictable highs under stress conditions.
- 135. Similarly, Public Interest Organizations cite to studies by the Sierra Club²¹⁶ and Bloomberg New Energy Finance,²¹⁷ for the proposition that the use of LMP as the QF price discriminates against QFs where utility-owned generation and non-QF generators are not limited to the LMP for recovery of their costs, and where utilities depress LMP

²¹³ *Id.* at 57-59.

²¹⁴ *Id.* at 55.

²¹⁵ *Id.* at 57.

²¹⁶ Public Interest Organizations Comments at 53-56 (citing Jeremy Fisher, Sierra Club, *Playing with Other People's Money, How Non-Economic Coal Operations Distort Energy Markets*, Sierra Club, Oct. 2019, at 4).

²¹⁷ *Id.* at 57 (citing William Nelson & Sophia Liu, *Half of U.S. Coal Fleet on Shaky Economic Footing; Coal Plant Operating Margins Nationwide*, Bloomberg New Energy Finance, March 26, 2018).

through uneconomic dispatch of their own generation facilities.²¹⁸ Union of Concerned Scientists states that LMPs are not an accurate measure of avoided costs and should not be used to set QF rates because the practice of providing utility-owned generation with out-of-market cost-recovery in areas like MISO, PJM, SPP, the SERC Reliability Corporation, and the Western Electricity Coordinating Council suppresses the clearing prices in the markets where this is allowed.²¹⁹

136. Southeast Public Interest Organizations argue that the NOPR's proposed avoided cost methodology does not take into account: (1) long-term or seasonal purchases made from third parties or affiliates; (2) adjustments for transmission and distribution losses; (3) capacity deferrals; (4) avoided environmental compliance costs; or (5) a QF's dispatchability. Southeast Public Interest Organizations state that LMP-based rates for QFs in Virginia have enticed little-to-no QF development in Virginia. Southeast Public Interest Organizations urge the Commission either to rescind the NOPR's LMP provisions or at least to implement this provision on a case-by-case basis.

²¹⁸ *Id.* at 52-64.

²¹⁹ Union of Concerned Scientists Comments at 3-8.

²²⁰ Southeast Public Interest Organizations Comments at 22.

²²¹ *Id.* at 23.

²²² *Id.* at 24.

(a) <u>Utilizing Western EIM to Establish Avoided</u> Costs

137. Solar Energy Industries argues that, because as-available QF resources are not eligible to participate in the Western EIM (also known as the CAISO EIM), either directly or through the purchasing utility, it would be inappropriate to use the Western EIM price as a proxy because that market does not factor in the participation of the QF resource. ELCON asserts that the Western EIM is not a complete measure of avoided energy costs because the Western EIM merely covers imbalance conditions, and therefore does not capture the vast majority of unit commitment and dispatch scheduling cost parameters. Union of Concerned Scientists asserts that allowing a state to adopt real-time prices established in the Western EIM as an accurate measure of avoided costs will be discriminatory.

ii. Comments in Support

138. Several commenters support the Commission's proposal to permit a state the flexibility to use LMPs to set the as-available energy rate paid to a QF by an electric utility located in an RTO/ISO.²²⁶

²²³ Solar Energy Industries Comments at 27.

²²⁴ ELCON Comments at 24.

²²⁵ Union of Concerned Scientists Comments at 9.

²²⁶ APPA Comments at 11; Arizona Public Service Comments at 5; CA Utilities Comments at 17; Conn. Authority Comments at 13; DTE Electric Comments at 4; EEI Comments at 22-24; Comments at 4-5; Idaho Commission Comments at 3-4; Indiana Municipal Comments at 5; Kentucky Commission Comments at 4-5; NorthWestern Comments at 4-7; NRECA Comments at 6-7; Ohio Commission Energy Advocate Comments at 4-5; Pennsylvania Commission Comments at 7-9; South Dakota

- 139. CA Utilities state that the NOPR's LMP proposal is a return to the Commission's policy as expressed in *Winding Creek*, ²²⁷ and will facilitate payments to QFs that more accurately represent a utility's actual avoided costs. CA Utilities assert that the NOPR's LMP proposal affirms that a formula energy price contract complies with PURPA if coupled with a fixed capacity price. CA Utilities state that a formula energy price contract will have the additional benefit of avoiding the need to develop and administer a new PURPA contract. ²²⁸
- 140. NRECA supports the Commission's proposal because many utilities that participate in the RTO/ISO markets offer the entirety of their generation into the market, and purchase all of their requirements to serve load from that market, at LMP prices. ²²⁹
 141. The Pennsylvania Commission supports the NOPR proposal because LMP prices vary through the day based on changing system conditions, such as changes in electricity demand, supply, congestion, and line losses. The Pennsylvania Commission asserts that, because some utilities in Pennsylvania (and other states) have already incorporated LMP elements in their as-available energy rates, a corresponding revision to the Commission's

Commission Comments at 2; US Chamber of Commerce Comments at 4; We Stand Comments at 1; Xcel Comments at 5.

 $^{^{227}}$ CA Utilities Comments at 15-17 (citing *Winding Creek Solar LLC*, 151 FERC ¶ 61,103, at P 6 (2015)).

²²⁸ *Id.* at 17.

²²⁹ NRECA Comments at 6.

regulations that incorporates such practices and harmonizes state and federal regulations would bring greater predictability to suppliers, electric utilities and customers.²³⁰

- 142. The Ohio Commission Energy Advocate believes that, in the parts of the country with organized nodal wholesale electricity markets, LMP is an appropriate and fair means by which to calculate avoided costs because electricity supply and demand must be balanced in real time. The Ohio Commission Energy Advocate notes that Ohio has nodal LMPs that reflect the true value of energy at the place and the time it is produced or delivered, and this value can change dramatically, even within a day or an hour. The Ohio Commission Energy Advocate concludes that reflecting the dynamic nature of electricity pricing in avoided cost calculations will send the most accurate price signals to QFs and will appropriately and fairly value the energy they produce.²³¹
- 143. The South Dakota Commission supports using LMP for certain as-available QF energy sales because using LMP will increase states' flexibility. The South Dakota Commission regulates six vertically integrated electric utilities, five of which are RTO members, and five of which are multi-jurisdictional.²³²
- 144. Xcel submits that compensating QFs based on LMPs at the time of delivery will not impair QFs' ability to obtain financing because other factors can drive the ability to obtain financing, including other project options, location, size, interconnection costs,

²³⁰ Pennsylvania Commission Comments at 7-8.

²³¹ Ohio Commission Energy Advocate Comments at 4-5.

²³² South Dakota Commission Comments at 2.

experience of the developer, current economic conditions, creditworthiness of the developer, economies of scale, and other factors. Xcel states that some resource specific information generally suggests that the right project in the right location can obtain financing if the project receives hourly payment based on LMPs.²³³

(a) <u>Utilizing Western EIM to Establish Avoided</u> <u>Costs</u>

145. NorthWestern and EIM Entities agree that the Western EIM real-time prices are similar to LMPs and reflect the least cost of meeting an incremental megawatt-hour of demand at each location on the grid. 234 Xcel asserts that prices in the Western EIM are calculated using the same methodology as LMPs because, in both cases, units are dispatched on a least-cost basis that respects applicable transmission constraints. Xcel requests that the Commission allow avoided costs to be based on Western EIM prices at the time of delivery absent a showing that prices would be suppressed in comparison to an LMP-style-market. 235 Arizona Public Service states that it is a participant in the Western EIM, and requests that states be given flexibility to set the as-available energy rate to be paid to a QF by an electric utility that participates in the Western EIM at the LMP. 236

²³³ Xcel Comments at 5-7.

²³⁴ EIM Entities Comments at 2-3, 7-13; NorthWestern Comments at 4-5.

²³⁵ Xcel Comments at 7-8.

²³⁶ Arizona Public Service Comments at 5-6.

iii. Comments in Support with Requested Modifications/Clarifications

- 146. APPA urges the Commission to clarify that nothing in the proposed rule is intended to call into question state regulatory authorities' existing implementation of PURPA's avoided cost requirements, such as their existing use of LMP.²³⁷
- 147. Industrial Energy Consumers do not object to the use of LMP as the avoided cost rate for electric utilities' purchases of QF energy in RTO/ISO regions, ²³⁸ but they maintain that in non-RTO/ISO regions, there must be assurance that utilities' self-builds face the same market risk exposure as QFs. ²³⁹
- 148. The Kentucky Commission supports the NOPR's LMP proposal but prefers that the Commission in the final rule allow states to determine whether the LMP calculation should use the generator LMP or the load LMP on a case-by-case basis.²⁴⁰
- 149. Solar Energy Industries assert that, where the purchasing utility has demonstrated that it procures its marginal energy from an LMP market, the utility may use the LMP price as a proxy for avoided energy costs calculated at the time the obligation is incurred, so long as there are published prices at the location.²⁴¹ Solar Energy Industries request that the Commission make clear that: (1) the flexibility to set QF payment rates for as-

²³⁷ APPA Comments at 9.

²³⁸ Industrial Energy Consumers Comments at 11.

²³⁹ *Id.* at 12.

²⁴⁰ Kentucky Commission Comments at 4-5.

²⁴¹ Solar Energy Industries Comments at 25-26.

available energy at the applicable LMP requires an on-the record determination that the purchasing utility procures incremental energy from the identified LMP market at those prices; (2) payments based on an LMP do not relieve the purchasing utility of the requirement to compensate the QF for any values in addition to electricity (e.g., renewable energy credits, frequency response capabilities, pro-rated capacity value, etc.); and (3) the state's flexibility to allow utilities to set QF payment rates for as-available energy at the applicable LMP does not in any way limit QFs' rights to establish a LEO or contract for a longer-term sale at fixed, full avoided costs. ²⁴²

150. NorthWestern believes that as-available rates based on LMPs should accurately capture current events impacting prices, including times when there is a high saturation of energy available causing prices to be negative. However, NorthWestern believes that it is appropriate to deduct from the avoided cost rate the cost for ancillary services to balance and integrate energy resources.²⁴³

c. <u>Commission Determination</u>

151. We affirm with one modification the NOPR proposal to allow LMP to be used as a measure of as-available energy avoided costs for electric utilities located in RTO/ISO markets for the reasons set forth in the NOPR²⁴⁴ and those provided by various commenters.

²⁴² *Id.* at 27-28.

²⁴³ NorthWestern Comments at 4-5.

²⁴⁴ NOPR, 168 FERC ¶ 61,184 at PP 44-45.

- 152. We recognize that an LMP selected by a state to set a purchasing utility's avoided energy cost component might not always reflect a purchasing utility's actual avoided energy costs. Accordingly, we find that it is appropriate to modify the option for a state to set avoided energy costs using LMP from a per se appropriate measure of avoided cost to a rebuttable presumption that LMP is an appropriate means to determine avoided cost. While a state could rely on the presumption, an aggrieved entity (such as a OF) may attempt to rebut the presumption that LMP reflects the purchasing electric utility's avoided costs. The aggrieved entity would be able to challenge the state's decision to rely on LMP in the appropriate forum, which could include any one or more of the following: (1) initiating or participating in proceedings before the relevant state commission or governing body; (2) filing for judicial review of any state regulatory proceeding in state court (under PURPA section 210(g)); or, alternatively (3)) filing a petition for enforcement against the state at the Commission and, if the Commission declines to act, later filing a petition against the state in U.S. district court (under PURPA section 210(h)(2)(B)).²⁴⁵
- 153. Commenters have not persuaded us that LMP may not presumptively reflect a purchasing electric utility's avoided energy costs. LMP sets day-ahead and real-time energy prices through competitive auctions in RTOs/ISOs that optimally dispatch resources to balance supply and demand, while taking into account actual system

Section 210 of the Public Utility Regulatory Policies Act of 1978, 23 FERC \P 61,304.

conditions including congestion on the transmission system. We continue to find that: (1) LMPs reflect the true marginal cost of production of energy, taking into account all physical system constraints; (2) these prices would fully compensate all resources for their variable cost of providing service; (3) LMP prices are designed to reflect the least-cost of meeting an incremental megawatt-hour of demand at each location on the grid, and thus prices vary based on location and time; and (4) unlike average system-wide cost measures of the avoided energy cost used by many states, LMP should provide a more accurate measure of the varying actual avoided energy costs, hour by hour, for each receipt point on an electric utility's system where the utility receives power from QFs.²⁴⁶ Various commenters have provided additional reasons for supporting the NOPR proposal concerning LMP. NRECA explains that LMP rates for energy are appropriate because many utilities that participate in the RTO/ISO markets offer the entirety of their generation into the market at LMP prices and buy all of their load requirements from the market at LMP prices.²⁴⁷ This scenario described by NRECA is a common one, and it demonstrates that the market itself, with its LMP pricing, can be the electric utility resource that would be displaced by a QF purchase. Furthermore, as argued by Pennsylvania Commission, because some utilities in Pennsylvania and other states have

²⁴⁶ See NOPR, 168 FERC ¶ 61,184 at PP 44-45 (citing SMUD, 616 F.3d at 524; FERC v. Elec. Power Supply Ass'n, 136 S. Ct. at 768-69 (describing how LMP is typically calculated); Order No. 831, 157 FERC ¶ 61,115, at P 7, order on reh'g and clarification, Order No. 831-A, 161 FERC ¶ 61,156).

²⁴⁷ NRECA Comments at 6.

already incorporated LMP in their as-available energy rates, a corresponding revision to the Commission's regulations that incorporates such practices and harmonizes state and federal regulations would bring greater predictability to suppliers, electric utilities and customers.²⁴⁸

i. Arguments Against the NOPR Proposal

155. Commenters have not offered persuasive arguments for rejecting the use of LMP for avoided cost energy rate determination. We disagree with the argument made by Union of Concerned Scientists, ²⁴⁹ NIPPC, CREA, REC, and OSEIA, ²⁵⁰ and Public Interest Organizations ²⁵¹ that LMP should not be used as a measure of avoided energy costs because LMP prices are depressed in many markets where self-scheduling rights and state cost-recovery mechanisms for fuel and operating costs create the opportunity for market participation at a loss. We recognize that, all other things being equal, self-scheduling of resources may impact market clearing prices. This potential price effect, however, does not mean that the LMP is not an accurate measure of avoided energy costs. The Commission's regulations, using language from PURPA section 210(d), define avoided costs as "the incremental costs to an electric utility of electric energy or capacity

²⁴⁸ Pennsylvania Commission Comments at 7-8.

²⁴⁹ Union of Concerned Scientists Comments at 3-8.

²⁵⁰ NIPPC, CREA, REC, and OSEIA Comments at 52.

²⁵¹ Public Interest Organizations Comments 52-64.

or both which, *but for* the purchase from the qualifying facility or qualifying facilities, such electric utility would generate for itself *or purchase from another source*."²⁵²
156. In organized wholesale electric market areas, the electric utility purchases that would be displaced by QF purchases would, as NRECA explains, in all likelihood be priced at the relevant LMP. These LMPs are impacted by many factors, such as self-scheduling, generator outages, and transmission outages, that may result in LMPs that are lower or higher than they might otherwise have been. Thus, while self-scheduling or other factors may impact LMPs, in any case, an electric utility's purchases during periods when these price impacts are occurring would be made at the resulting LMPs, whatever those LMPs may be. Therefore, LMPs meet the Commission's long-standing definition of avoided costs for a purchasing electric utility, even if they happen to reflect price impacts from self-scheduling or other factors.

157. Furthermore, while commenters discuss the possibility that utility-owned coal-fired resources are self-scheduling only because retail ratepayers are subsidizing such activities, even if such claims were true they would not alter the above analysis. The LMPs that result from a market that includes self-scheduled resources still represent the price of purchases in the market that would be displaced by the QF purchase.

158. In addition, we reject the related request for clarification made by Solar Energy Industries, 253 i.e., that the flexibility to set QF payments for as-available energy at the

²⁵² 18 CFR 292.101(b)(6) (emphasis added).

²⁵³ Solar Energy Industry Comments at 27-28.

applicable LMP should require an on-the-record determination that the purchasing utility procures incremental energy from the identified LMP market at those prices. Unless an aggrieved entity seeks to rebut this presumption in a state avoided cost adjudication, rulemaking, legislative determination, or other proceeding, that state would not need to make such an on-the-record determination before it decides to use LMP.

159. Entities may seek to rebut the presumption in particular cases, as described earlier, and whether the utility actually procures energy from the identified LMP market or from resources with prices tied to the identified LMP may be a relevant factor in such rebuttal arguments. Consistent with the reasons described above for why there should be such a rebuttable presumption in favor of LMP, this delineation of rights appropriately places the initial burden on entities seeking to rebut the presumption, rather than on the states who wish to rely on LMP for setting avoided cost rates for as-available energy. The Commission could consider such issues if and when they may arise in individual cases appropriately brought to the Commission, including whether the state has adequately justified its use of that rebuttable presumption.

160. We reject the arguments made by NIPPC, CREA, REC, and OSEIA that, more generally, prices for long-term QF contracts should be set by reference to long-term price indices or other indicators that genuinely reflect the long-term costs of generation avoided by the purchasing utility.²⁵⁴ This final rule only addresses as-available energy, and as-

²⁵⁴ NIPPC, CREA, REC, and OSEIA Comments at 53.

available energy prices by definition are short term, as explained below in Section IV.B.7.c.

- We also reject the arguments made by NIPPC, CREA, REC, and OSEIA that, while the NOPR is correct that LMPs are intended to promote more efficient use of the transmission grid, that is true only in the short term since factors such as temporary outages, equipment failures, weather extremes, and the like can cause LMPs to spike, but these have no impact on long-term transmission availability. LMPs promote efficient use of the transmission grid in the long term as well as the short term. Persistence of significant price separation between different LMP nodes provides an indication of the value of various possible transmission system upgrades and can show transparently how system efficiencies may be improved by such transmission system upgrades. Developers may have some incentive to avoid congestion without LMPs, but LMPs provide an important price signal as to how economic or uneconomic a particular production site may be. In any event, the potential for more efficient use of the transmission grid is merely an additional benefit of using LMP for avoided energy cost determinations. Our adoption of LMP as a measure of avoided energy costs in the RTO/ISO markets is based principally on the fact that, in RTO/ISO markets, LMP accurately represents the purchasing electric utility's avoided energy cost at the time the energy is delivered, for the reasons described earlier.
- 162. We also are not persuaded by arguments that, if transmission constraints prevent a generator from delivering power to a specific node, the LMP at that node cannot be an appropriate measure of costs avoided by purchase of power from that generator. As

discussed above, an avoided cost rate should reflect not only the cost of energy that was avoided by the purchasing electric utility, but also the cost to deliver the QF energy to the purchasing electric utility's load, such that the total cost avoided is reflected in the rate. In an RTO/ISO market, a state appropriately is entitled to consider whether the cost of delivery from the QF node to the load node (including any redispatch costs necessary to facilitate such delivery over a system that is otherwise constrained between those nodes) should be reflected in the LMP at the QF supply node. In instances commenters refer to where transmission constraints prevent a generator from delivering power to a specific node, we disagree that such delivery is actually "prevented." Rather, redispatch of system resources would be necessary to facilitate the delivery, and the respective LMPs reflect those redispatch costs.

163. We also reject the argument made by NIPPC, CREA, REC, and OSEIA that the 2000-01 California market demonstrated that volatile short-term markets can reach extreme and unpredictable highs under stress conditions. First we note that, in the wake of the 2000-2001 California energy crisis, all RTO/ISO markets developed more comprehensive *ex ante* market power mitigation measures than existed in CAISO at that time, including offer caps and reference level replacement offers, meant in part to moderate such extremes. In any event, any price volatility that may currently exist in

²⁵⁵ NIPPC, CREA, REC, and OSEIA Comments at 57. Curiously, these commenters here essentially take the position that higher LMPs and resulting higher avoided cost energy rates, which would normally seem to be beneficial to QFs, are instead now anathema.

²⁵⁶ See generally Wholesale Competition in Regions with Organized Elec. Mkts.,

LMP markets, regardless of the reason for the price volatility, and regardless of whether the volatility causes LMPs to be lower or higher, nevertheless accurately represents the avoided cost of the purchasing electric utilities in those markets in those hours, as explained elsewhere in this final rule.

164. Finally, we remain convinced that Congress recognized that RTO/ISO LMP pricing provides sufficient encouragement for QFs through the enactment of PURPA section 210(m) with its directive that, essentially, the mandatory purchase obligation can be lifted upon QFs having non-discriminatory access to RTO/ISO markets. As noted earlier, however, our decision to grant states the flexibility to rely on a rebuttable presumption that RTO/ISO LMP pricing is an appropriate measure of avoided energy costs (and thus set as-available energy rates in reliance on LMPs) reflects our view that, in RTO/ISO markets, as a general matter LMP indeed accurately represents the purchasing electric utility's avoided energy costs.

165. We also disagree with ELCON's²⁵⁷ argument that LMP should not be used to measure avoided costs because that would allow states to ignore long-standing factors established by the Commission that should be used to determine avoided costs. The factors referenced by ELCON are relevant to the traditional administrative determination of avoided cost, and our revisions to the regulations preserve these factors for that purpose

Order No. 719, 125 FERC ¶ 61,071 (2008), *order on reh'g*, Order No. 719-A, 128 FERC ¶ 61,059, *order on reh'g*, Order No. 719-B, 129 FERC ¶ 61,252 (2009).

²⁵⁷ ELCON Comments at 23-24.

and for avoided capacity costs. If a state chooses instead to rely on LMP to set avoided energy cost rates, then it will necessarily not be using those administrative means of determining avoided costs, and these factors thus will not be relevant.

166. We are not persuaded by the arguments of various commenters that LMP cannot be used for avoided cost rates because it ignores the unique municipal infrastructure role and the multiple benefits of the community of biogas facilities, ²⁵⁸ including the value of renewable baseload energy, greenhouse gas mitigation, landfill diversion, reliable and resilient power and other benefits of small baseload QFs. ²⁵⁹ PURPA frames the determination of QF rates in terms of avoided cost and does not authorize the Commission in determining QF rates, particularly as-available energy rates, to consider non-energy-related factors such as a generator's unique municipal infrastructure role, greenhouse gas mitigation, and landfill diversion.

167. We also are not persuaded by the argument of CA Cogeneration that LMP may not represent a truly competitive price for electricity in California since the majority of California supply is through bilateral contracts, not through competitive bidding in the market, and that other factors also distort LMP such as roof top solar. CA Cogeneration, in essence, objects to the state of California's decision to award preferred resource status to some resources, such as solar and wind, and not others, such as cogeneration. These are procurement decisions made at the state level in connection with resource planning and

²⁵⁸ Biogas Comments at 2.

²⁵⁹ Covanta Comments at 8.

retail ratemaking. Even if those decisions impact the resulting LMPs, as CA Cogeneration claims, that impact would not invalidate the arguments made above for why LMP is presumptively an appropriate measure of as-available energy avoided costs in RTO/ISO markets. The aggrieved entity would be able to challenge the state's decision to rely on LMP in the appropriate forum, which could include any one or more of the following: (1) initiating or participating in proceedings before the relevant state commission or governing body; (2) filing for judicial review of any state regulatory proceeding in state court (under PURPA section 210(g)); or, alternatively (3) filing a petition for enforcement against the state at the Commission and, if the Commission declines to act, later filing a petition against the state in U.S. district court (under PURPA section 210(h)(2)(B)). ²⁶⁰ We reject the argument made by New England Small Hydro that the Commission has not supported its view that LMP is an accurate measure of avoided costs since LMP ignores the costs that the utility pays to procure power, including through competitive solicitations, other power contracts, planned retirements and other factors that are considered in a utility's long-term plans; and ignores the fact that LMP and the default service rates that exist in ISO-NE-based states are quite different. ²⁶¹ The costs that a purchasing utility pays to procure power, including through competitive solicitations, other power contracts, planned retirements and other factors that are considered in a

See Policy Statement Regarding the Commission's Enforcement Role Under Section 210 of the Public Utility Regulatory Policies Act of 1978, 23 FERC \P 61,304.

²⁶¹ New England Small Hydro Comments at 8-10.

utility's long-term plans may be relevant to the utility's purchase of capacity using long-term contracts, but not to the determination of the proper as-available energy avoided cost rate to be paid to QFs, which rates will necessarily vary as system conditions vary over time, as reflected by variances in LMP over time. The fact that LMP and the default service rates that exist in ISO-NE-based states may diverge is to be expected because the latter, unlike the as-available energy rates charged by QFs in RTO/ISO markets that LMP is being used to price, normally include transmission and distribution costs (and possibly firm supplier capacity costs) necessary to ensure that firm supply is continually available to residential customers. While utilities or state regulatory authorities continue to have the authority to establish and maintain long-term avoided energy forecasts upon which QF PURPA power purchase rates may be based, and to recognize the actual future energy costs incorporated in new power contracts that are being signed by New England utilities,

²⁶² Compare ISO-NE, Transmission, Markets, and Services Tariff, LMPs and Real-Time Reserve Clearing Prices Calculation, § III.2.5 (describing how nodal real-time prices are calculated in ISO-NE at each node using energy offers and bids, transmission constraints, and other factors) with National Grid, Investigation as to the Propriety of Proposed Tariff Changes, Docket No. DPU 18-150, Exh. NG-HSG-1, Gorman Test. 3:18-4:6 (Nov. 15, 2018),

https://fileservice.eea.comacloud.net/FileService.Api/file/FileRoom/10043215 ("The Company's filing is based on its investments and costs incurred to provide distribution service to its customers. An [Allocated Cost of Service Study] directly assigns or allocates each element of the revenue requirement, including plant and other investments, operating expenses, depreciation and taxes, among the rate classes, in order to determine the costs of providing service to each rate class. Each element of the total revenue requirement is analyzed and assigned to or allocated among the rate classes, so the utility can establish rates that, subject to assumptions such as kilowatt-hour ('kWh') delivery volumes and the number of customers, provide it with a fair opportunity to recover its costs and to earn an appropriate return.").

elsewhere in this final rule the Commission explains why the use of variable prices can be appropriate for long-term energy contracts.

169. We are not persuaded by the argument of Southeast Public Interest Organizations that the NOPR does not establish a framework for just and reasonable and nondiscriminatory rates because the proposed avoided cost methodology does not take into account any long-term or seasonal purchases made from third parties or affiliates, adjustments for transmission and distribution losses, capacity deferrals, avoided environmental compliance costs, or dispatchability of the QF.²⁶³ LMP pricing, in fact, does reflect transmission and distribution losses. The other factors that the Southeast Public Interest Organizations mention here, such as environmental compliance costs, dispatchability, long-term or seasonal purchases and capacity deferrals, are factors that are more applicable to the pricing of capacity and long-term contracts, not the pricing of asavailable energy, which is what the Commission's NOPR proposal as adopted in this final rule addresses.

170. The Commission rejects the argument made by Biological Diversity²⁶⁴ that LMP pricing ignores the variability of conditions across the country. LMP prices by definition vary as supply, demand, and system conditions change across the country. In any event, the Commission agrees that LMP pricing would not currently be applicable in regions like the Southeast that lack RTOs and ISOs and thus that do not use LMP.

²⁶³ Southeast Public Interest Organizations Comments at 22.

²⁶⁴ Biological Diversity Comments at 8-9.

171. We further reject the argument made by ENGIE that allowing states to set energy rates using LMPs combined with the ability to set capacity rates at zero if it is determined that a utility has no need for capacity has the potential to allow traditional utilities to corner the market on capacity, leaving smaller independent QFs to provide only energyonly service.²⁶⁵ PURPA does not direct the Commission to guarantee that OF sales make up some specified share of utilities' capacity needs nor does it require that each QF receive compensation for providing capacity. PURPA instead focuses on the purchasing electric utility's avoided costs and provides that the Commission cannot require that prices charged by a QF exceed the purchasing electric utility's avoided cost, if a purchasing electric utility has no need for additional capacity (and thus the purchasing utility's avoided cost for capacity would be zero), ²⁶⁶ the only service that QFs (and other suppliers) would need to provide that utility is energy. However, a utility's ability to "corner the market" on capacity depends not uniquely on the pricing of QF sales to the utility, but on a host of factors including the utility's analysis of its need for capacity and, without a specific inquiry into the circumstances of each utility, it cannot be concluded that any utility's decision will always be deficient or that it has been adversely and inappropriately affected by the Commission's action here.

²⁶⁵ ENGIE Comments at 4.

²⁶⁶ See, e.g., NOPR, 168 FERC ¶ 61,184 at P 33 n.58; see also City of Ketchikan, Alaska, 94 FERC ¶ 61,293 at 62,061 (2001) ("[A]voided cost rates need not include the cost for capacity in the event that the utility's demand (or need) for capacity is zero. That is, when the demand for capacity is zero, the cost for capacity may also be zero.").

172. Several commenters maintain that reliance on LMP will make it difficult for QFs to obtain financing.²⁶⁷ This argument is addressed below in section IV.B.7 of this final rule.

ii. Requests for Modification or Clarification of the NOPR

- 173. We will not provide the clarifications requested by New England Small Hydro that the Commission require the use of the day-ahead LMP for QF rates set at LMP, or Southeast Public Interest Organizations' request to require the use of real-time LMP rather than average LMP. States that choose to use LMP will determine the LMP most representative of the avoided cost of the relevant purchasing utility.
- 174. While the Kentucky Commission requests that the Commission allow the use of the LMP at a delivery (load) node rather than a receipt (generator or QF) node, we find that this decision should be made by the state as it determines which particular LMP best reflects the avoided cost of the purchasing electric utility.
- 175. We grant APPA's request for clarification that, while the NOPR provides greater clarity as to states' entitlement to rely on competitively-set prices as a measure of avoided cost rates, nothing in the final rule is intended to call into question any particular state's existing implementation of PURPA's avoided cost requirements, such as their existing use of LMP.²⁶⁸ While in the past a state may have been able to conclude that LMP was an

²⁶⁷ Biogas Comments at 2; BluEarth Renewables Comments at 2; Biological Diversity at 8; Covanta Comments at 9; Distributed Sun Comments at 1-2; New England Small Hydro Comments at 10; NIPPC, CREA, REC, and OSEIA Comments at 53.

²⁶⁸ APPA Comments at 9.

appropriate measure of the avoided cost for energy, a state can now also rely on a rebuttable presumption that LMP is an appropriate measure of the as-available avoided cost for energy to be used in determining a QF's as-available avoided cost energy rate. We provide the following clarification in response to the Solar Energy Industries' request that the Commission make clear that payments based on LMP do not relieve the purchasing utility of the requirement to compensate the OF for any values in addition to electricity (e.g., RECs, etc.), and that the state's flexibility to allow utilities to set OF payment rates for as-available energy at the applicable LMP does not in any way limit QFs' rights to establish a LEO or contract for a longer-term sale at fixed, full avoided costs.²⁶⁹ In Windham Solar LLC,²⁷⁰ the Commission summarized its precedent concerning RECs. The Commission stated that the states have the authority to determine who owns RECs in the initial instance and how they are transferred, and that the automatic transfer of RECs within a sale of power at wholesale must find its authority in state law, not PURPA. But the Commission also held that a state may not assign ownership of RECs to utilities based on a logic that the avoided cost rates in PURPA contracts already compensate QFs for RECs in addition to compensating QFs for energy and capacity, because under PURPA the avoided cost rates are, in fact, compensation just for energy and capacity.²⁷¹ We see no reason to disturb that precedent in this final rule. With regard

²⁶⁹ Solar Energy Industry Comments at 27-28.

²⁷⁰ 156 FERC ¶ 61,042 (2016).

²⁷¹ *Id.* P 4.

to the right of QFs to establish a LEO, that right is neither limited nor expanded by a state's choice of LMP as the measure of avoided costs for energy.

iii. Western EIM

177. We hereby find that the Western EIM prices, like other LMP prices, may presumptively be used as a measure of as-available energy avoided costs for utilities able to participate in the Western EIM market. As Xcel points out, "prices in the EIM are calculated using the same methodology as LMPs" since, "in both cases, units are dispatched on a least-cost basis that respects applicable transmission constraints (i.e., congestion)," and "[t]he formula for price calculation involves determination of the system marginal energy cost, which is the cost of providing the next increment of energy to the system, minus congestion costs, minus losses, and, in some cases, minus the cost of carbon." As with LMP, these Western EIM price components presumptively reflect the avoided cost of as-available energy incurred by purchasing electric utilities that are able to participate in the Western EIM region.

178. We reject arguments that Western EIM prices should not be used to establish asavailable avoided cost energy rates for sales by QFs. With respect to the unit commitment
and dispatch scheduling cost parameters ELCON refers to, it is true that the Western EIM
is a real-time imbalance market built on a decentralized unit commitment that may not
result in exactly the same real-time dispatch and LMP as would result from an RTO
market with centralized day-ahead unit commitment and co-optimized energy and

²⁷² Xcel Comments at 7-8.

reserves. Nonetheless, Western EIM prices represent quite precisely the avoided cost of as-available energy for utilities operating in that market structure since those prices show the cost of obtaining an additional unit of energy at any particular place and time. With regard to the argument of Union of Concerned Scientists concerning the cost recovery mechanisms available to utility-owned and -affiliated generation, ²⁷³ as discussed above with respect to the rebuttable presumption that LMP may be used for avoided cost rate determination, we do not find these unproven allegations of use of retail cost recovery mechanisms to subsidize wholesale RTO/ISO market participation at a loss sufficient to make a blanket finding prohibiting the use of Western EIM prices to set as-available avoided cost energy rates for sales by QFs.

179. With regard to the argument concerning the ability to participate in the Western EIM raised by Solar Energy Industries, ²⁷⁴ for PURPA rate purposes, it is not relevant whether QFs are able to participate in the Western EIM. The rates at issue here are intended, per the statute, to reflect the costs of alternative electric energy that the purchasing utility is avoiding. In this context, all that matters is whether the Western EIM's prices accurately reflect a purchasing electric utility's avoided costs for energy. Thus, as long as the purchasing electric utility is able to participate in the Western EIM, a rebuttable presumption should apply that Western EIM prices reflect the purchasing electric utility's avoided costs for energy.

²⁷³ Union of Concerned Scientists Comments at 9.

²⁷⁴ Solar Energy Industry Comments at 27.

4. <u>Use of Market Hub Prices as a Permissible Rate for Certain As-</u> Available QF Energy Sales

a. NOPR Proposal

180. In the NOPR, the Commission recognized that competitive bilateral energy markets have arisen outside of the RTO/ISO energy markets. Particularly in the Western United States, price hubs such as the Mid-Columbia (Mid-C) and Palo Verde hubs are liquid markets with prices the Commission has recognized as representing competitive market prices at those hubs.²⁷⁵ For the same reasons that LMPs could represent an appropriate avoided cost energy rate for QFs selling to electric utilities located in RTO/ISO markets, the Commission proposed to find that liquid market hubs can represent appropriate rates for QFs selling to electric utilities located outside of RTO/ISO markets. Like LMP, liquid market hubs would rely on competition to derive an avoided cost. From a price determination perspective, liquid market hub prices differ from LMP mainly in that they measure price at only one or a few points, whereas RTOs/ISOs derive unique LMPs for all receipt and delivery points on a specific area of the system.²⁷⁶

²⁷⁵ NOPR, 168 FERC ¶ 61,184 at P 52 (citing *Price Discovery in Nat. Gas and Elec. Mkts.*, 109 FERC ¶ 61,184, at P 66 (2004) (approving the use of published prices at market hubs with sufficient liquidity to set prices charged in tariffs); *El Paso Elec. Co.*, 148 FERC ¶ 61,051, at P 7 (2014) (approving the use of the Palo Verde price to set imbalance charges); *Idaho Power Co.*, 121 FERC ¶ 61,181 at P 27 (2007) (approving use of Mid-Columbia prices to set energy imbalance charge); *PacifiCorp*, 95 FERC ¶ 61,467, at 62,676 (2001) (approving setting energy imbalance rate at average of four market hub prices); *Pinnacle West Energy Corp.*, 92 FERC ¶ 61,248, at 61,791 (2000) (accepting the use of the Palo Verde price to set prices for affiliate transactions because the Palo Verde Index is a recognized market hub with competitive prices)).

²⁷⁶ NOPR, 168 FERC ¶ 61,184 at P 53.

181. Consequently, the Commission proposed in the NOPR to revise the PURPA Regulations in 18 CFR 292.304 to add a subsection (b)(7) which, in combination with new subsection (e)(1), would permit a state to set the as-available energy rate paid to a QF by electric utilities located outside of RTO/ISO markets at energy rates established at liquid market hubs. The Commission proposed to define Market Hub Prices as prices determined at a liquid market hub to which the purchasing electric utility has reasonable access. States electing to set QF energy rates using a Market Hub Price also would identify the particular market hub used to set the price. Such determination would require the state to find that the prices at such hub are competitive prices that reflect the costs an electric utility would avoid but for the purchase from the QF.²⁷⁷

b. <u>Comments</u>

i. Comments in Support

182. Arizona Public Service and El Paso Electric state that the Palo Verde/Hassayampa hub represents a regional liquid market hub that could be used to set as-available energy avoided costs.²⁷⁸ Portland General likewise asserts that the Mid-C price hub should be approved as appropriate for use in establishing as-available energy avoided costs.²⁷⁹
183. Xcel provides two additional factors to support the liquid market hub proposal.
First, Xcel cites to the 2018 State of the Market report issued by the Commission's Office

²⁷⁷ *Id.* P 56.

²⁷⁸ Arizona Public Service Comments at 6-8; El Paso Electric Comments at 2-3.

²⁷⁹ Portland General Comments at 6-7.

of Enforcement's Division of Energy Market Oversight, which states that trading hub prices generally align with energy prices associated with competitive, market-based sales. Second, Xcel cites to wholesale power sales contracts providing for the purchase of excess energy based on a combination of day-ahead prices at Palo Verde and at Four Corners, which Xcel asserts demonstrates that prices at Palo Verde and Four Corners are reasonably representative of the value of energy.²⁸⁰

ii. Comments in Opposition

184. Several commenters argue that liquid market hubs are short-term spot markets and do not represent long-term energy rates or the other costs associated with that energy including, but not limited to, congestion, transmission, and capacity costs. Other commenters express concern with setting QF prices at short-term liquid hub prices while allowing utilities to rate base and recover their long-term investments. 282

185. Public Interest Organizations assert that the liquid market hub proposal is discriminatory because non-QF generators are not limited to the liquid market hub price and utilities can, and regularly do, pay effective prices for energy that exceed the price determined by regional trading.²⁸³ Union of Concerned Scientists similarly asserts that

²⁸⁰ Xcel Comments at 8.

²⁸¹ IdaHydro Comments at 11; Southeast Public Interest Organizations Comments at 19.

²⁸² IdaHydro Comments at 11; Industrial Energy Consumers Comments at 12-13.

²⁸³ Public Interest Organizations Comments at 64.

liquid market hub prices are distorted by the participation of integrated utilities that submit bids below their total costs.²⁸⁴

because such markets are not sufficiently competitive, nondiscriminatory, and transparent to be used as the basis for calculating a utility's avoided cost payment. Industrial Energy Consumers urge the Commission not to assume that non-competitive markets are, in fact, competitive. Southeast Public Interest Organizations state that no southeast state could credibly identify a particular market hub that is reasonably accessible and has competitive prices that actually relate to the costs an electric utility would avoid but for the purchase from the QF. Southeast Public Interest Organizations also assert that the liquid market hub proposal does not require states to determine whether liquid market hub prices represent a utility's avoided costs, and therefore the proposal would allow liquid market hubs to set avoided energy prices even when they do not represent avoided energy costs. Set

²⁸⁴ Union of Concerned Scientists Comments at 8.

²⁸⁵ Industrial Energy Consumers Comments at 12.

²⁸⁶ *Id*.

²⁸⁷ Southeast Public Interest Organizations Comments at 18.

²⁸⁸ *Id.* at 19.

187. ELCON asserts that a liquid regional hub does not necessarily imply liquidity at a more granular level.²⁸⁹ According to ELCON, the basis spread resulting from transmission congestion outside of RTO/ISOs is often opaque in real time and poorly documented in hindsight, and this is a clear indication that discriminatory treatment and barriers to the bulk transmission system persist under current conditions outside of RTO/ISOs.²⁹⁰ ELCON states that for these and other reasons, bilateral markets alone are insufficient to serve as complete avoided cost measures.²⁹¹

188. Allco states that prices at liquid market hubs would suffer from shortcomings with respect to small QFs connected to the distribution system, because purchases from such QFs also allow the purchasing utility to avoid transmission costs, including line losses.²⁹²

iii. Commission Determination

189. We adopt the proposal in the NOPR to give the states flexibility to set as-available avoided cost energy rates using prices from a liquid market hub to which the purchasing electric utility has reasonable access. For the reasons explained in the NOPR, we find that liquid market hubs can represent appropriate as-available avoided cost energy rates for QFs selling to electric utilities located outside of RTO/ISO markets. However, as the Commission also found in the NOPR, before relying on prices from liquid market hubs, a

²⁸⁹ ELCON Comments at 25.

²⁹⁰ Id

²⁹¹ *Id*.

²⁹² Allco Comments at 7-8.

state must find that the liquid market hub price in question represents the purchasing utility's avoided cost for as-available energy.²⁹³

190. Examples of factors a state reasonably could consider in making this determination (in addition to the core finding that the liquid market hub represents the purchasing utility's avoided cost for as-available energy) are: (1) whether the hub is sufficiently liquid that prices at the hub represent a competitive price; ²⁹⁴ (2) whether the prices developed at the hub are sufficiently transparent; (3) whether the electric utility has the ability to deliver power from such hub to its load, even if its load is not directly connected to the hub; and (4) whether the hub represents an appropriate market to derive an energy price for the electric utility's purchases from the relevant QFs given the electric utility's physical proximity to the hub. These factors are not intended to be exhaustive, and states reasonably could consider other factors in identifying a relevant liquid market hub for setting as-available QF energy rates.

191. In order for prices at market hubs to represent a purchasing electric utility's avoided costs, the market hub price may need to be subject to adjustments to account for transmission costs the electric utility would incur before such prices could serve as a factor in determining appropriate QF rates.²⁹⁵ In addition, market prices in a region may

²⁹³ See NOPR, 168 FERC ¶ 61,184 at PP 53, 56.

²⁹⁴ In considering whether a hub is sufficiently liquid, states could, for example, consider such factors as those identified by the Commission in *Price Discovery in Nat. Gas and Elec. Mkts.*, 109 FERC ¶ 61,184, at P 66.

²⁹⁵ Other adjustments also may be necessary in other situations in order for the

be determined based on a formula that includes adjustments to the market hub price or that incorporates prices at more than one market hub located in the region, when such prices represent standard pricing practice in the region where the purchasing electric utility is located.²⁹⁶ Such adjustments may be necessary to ensure that the competitive market price reflects a purchasing utility's actual avoided costs for as-available energy.

- 192. Arguments regarding the short-term nature of liquid market hubs and claims that use of such prices is discriminatory are addressed in Section IV.B.2 above.
- 193. We will not address in this final rule arguments about whether particular market hubs should be found to represent avoided costs or, to the contrary, that particular market hubs may be too illiquid or insufficiently granular, or that prices at particular market hubs may not reflect avoided costs. We are not making any determination in this final rule that the prices at any specific market hub do or do not represent the avoided costs of any specific utility. Rather, we are allowing the states the flexibility to rely on prices at liquid market hubs to set as-available avoided cost energy rates for QF sales in regions outside RTO/ISO markets upon a state finding that it is appropriate to do so given the specific circumstances governing a particular market hub and the purchasing utility involved. The aggrieved entity would be able to challenge the state's decision to use a liquid market hub price in the appropriate forum, which could include any one or more of the following: (1) initiating or participating in proceedings before the relevant state commission or

adjusted hub price to reasonably reflect the purchasing electric utility's avoided cost.

²⁹⁶ NOPR, 168 FERC ¶ 61,184 at P 58.

governing body; (2) filing for judicial review of any state regulatory proceeding in state court (under PURPA section 210(g)); or, alternatively (3) filing a petition for enforcement against the state at the Commission and, if the Commission declines to act, later filing a petition against the state in U.S. district court (under PURPA section 210(h)(2)(B))...²⁹⁷ 194. With respect to Southeast Public Interest Organizations' assertion that the liquid market hub proposal in the NOPR does not require states to determine whether liquid market hub prices represent a utility's avoided costs, the Commission intended to impose such a requirement as a prerequisite before a liquid market hub may be relied on as a measure of a purchasing utility's avoided cost of as-available energy. However, we acknowledge that the regulatory text in the NOPR was ambiguous in that regard.

Therefore, the regulatory text of 18 CFR 292.304(b)(7)(i) in the final rule has been revised to make this more clear.

c. **Proposed Modifications**

i. Comments

195. APPA requests that the Commission clarify that, in addition to liquid market hubs, as-available energy avoided costs could be determined based on prices of comparable competitive quality.²⁹⁸ APPA states that amending the proposed regulation in this fashion

²⁹⁷ See Policy Statement Regarding the Commission's Enforcement Role Under Section 210 of the Public Utility Regulatory Policies Act of 1978, 23 FERC ¶ 61,304.

²⁹⁸ APPA Comments at 13.

would also enable utilities proximate to (or embedded within) RTO/ISO markets to reference prices in those markets as viable alternatives in establishing avoided costs.²⁹⁹
196. The California Commission requests that the Commission clarify that states previously were permitted to use liquid market hub prices under the current PURPA Regulations and that the proposed revisions simply codify and confirm the validity of this past practice.³⁰⁰ The California Commission and Massachusetts DPU further request that the proposed rules be modified to permit states to use competitive prices to set both energy and capacity costs, and to not be limited to using such mechanisms only for asavailable energy prices.³⁰¹

197. EEI notes that some states may be located in regions with access to more than one market hub and those states should have the flexibility to use an average of market hub prices or develop a formula correlated to the appropriate market hubs to develop the electric utility's avoided cost.³⁰² EEI notes that this proposal is not new, but its inclusion in the Commission's regulations will provide certainty to states.³⁰³

²⁹⁹ *Id.* at 13.

³⁰⁰ California Commission Comments at 24.

³⁰¹ California Comments at 25; Massachusetts DPU Comments at 8-10.

³⁰² EEI Comments at 26.

³⁰³ *Id.* at 27.

198. NIPPC, CREA, REC, and OSEIA assert that the liquid market hub proposal should not be adopted without making significant changes.³⁰⁴ For example, they argue, only long-term contract prices reported at market hubs should be used.³⁰⁵ Even with respect to market-hub prices for long-term contracts, they assert that the Commission should include safeguards to ensure that prices are set based on liquid trading with a sufficient number of competitors to assure effective price discovery, that prices are not subject to manipulation, and that reported price indices are accurate and not subject to mis-reporting or other forms of manipulation.³⁰⁶ Finally, they argue that the Commission should require avoided costs to include the costs of transmission to and from such hubs except in cases where the utility's system directly interconnects with that hub.³⁰⁷ Resources for the Future makes similar arguments.³⁰⁸

199. In contrast, NorthWestern asserts that liquid market hub prices should be adjusted downward by a transmission differential to reflect the cost of getting energy from the market to load.³⁰⁹ NorthWestern states that reliance on the market hub to establish

³⁰⁴ NIPPC, CREA, REC, and OSEIA Comments at 60.

³⁰⁵ *Id*.

³⁰⁶ *Id*.

³⁰⁷ *Id*.

³⁰⁸ Resources for the Future Comments at 8.

³⁰⁹ NorthWestern Comments at 5.

avoided costs only remains a valid option if the prices are less than what it would cost a utility to build a resource to supply its customers' needs.³¹⁰

ii. Commission Determination

200. We clarify that, in adopting a rule allowing states to use liquid market hubs to determine as-available avoided energy costs, we are not finding that the use of liquid market hubs for this purpose prior to the issuance of this final rule was not permitted. Depending on the specific circumstances, a state may appropriately have determined, prior to the final rule, that a liquid market hub price represented a purchasing utility's as-available avoided energy cost. After the effective date of this final rule, an aggrieved entity may seek review of a state's determination to use liquid market hubs in the appropriate forum.³¹¹

201. We confirm that: (1) states located in regions with access to more than one market hub have the flexibility to use an appropriate average of market hub prices or to develop an appropriate formula that relies on data from relevant market hubs to develop an electric utility's as-available avoided energy cost, so long as doing so yields a price that accurately reflects the purchasing electric utility's as-available avoided energy cost;³¹² (2) states must determine that a liquid market hub is sufficiently liquid that its prices represent a

³¹⁰ *Id*.

³¹¹ See Policy Statement Regarding the Commission's Enforcement Role Under Section 210 of the Public Utility Regulatory Policies Act of 1978, 23 FERC ¶ 61,304.

³¹² NOPR, 168 FERC ¶ 61,184 at P 58.

competitive price;³¹³ and (3) the market hub price may need to be subject to adjustments to account for transmission costs the electric utility would incur.³¹⁴

202. Finally, we find that the general ruling requested by APPA regarding the use of "prices of comparable competitive quality" to set as-available avoided cost rates is beyond the scope of this rulemaking in that here we were proposing only particular discrete changes to our regulations for setting as-available avoided cost energy rates charged by QFs.

5. <u>Use of Formulas Based on Natural Gas Prices to Establish a</u> Permissible Rate for Certain As-Available QF Energy Sales

a. NOPR Proposal

203. The Commission observed in the NOPR that, in regions where there are no RTOs/ISO or liquid market hubs, the price of electricity generated by efficient combined-cycle natural gas generation facilities would appear to represent a reasonable measure of a competitive energy price.³¹⁵

204. The Commission therefore proposed to revise the PURPA Regulations in 18 CFR 292.304 to add a subsection (b)(7) which, in combination with new subsection (e)(1), would permit a state to set the as-available energy rate paid to a QF by electric utilities located outside of RTO/ISO markets at Combined Cycle Prices, defined as a formula rate established by the state using published natural gas price indices and a proxy heat rate for

³¹³ *Id.* P 57.

³¹⁴ *Id.* P 58.

³¹⁵ *Id.* P 59.

an efficient natural gas combined-cycle generating facility. The state would need to determine that the resulting Combined Cycle Price represents an appropriate approximation of the purchasing electric utility's avoided costs. This determination would involve consideration of such factors as, for example: (1) whether the cost of energy from an efficient natural gas combined-cycle generating facility represents a reasonable approximation of a competitive price in the purchasing electric utility's region; (2) whether natural gas priced in accordance with a particular proposed natural gas price index would be available in the relevant market; (3) whether there should be an adjustment to the natural gas price to appropriately reflect the cost of transporting natural gas to the relevant market; and (4) whether the proxy heat rate used in the formula should be updated regularly to reflect improvements in generation technology. The Commission described the above factors as not exhaustive and proposed providing states the flexibility to apply other factors that also might be appropriate for consideration.³¹⁶ The Commission stated that natural gas price indices coupled with the heat rate of 205. an efficient natural gas combined-cycle generating facility may be a reasonably accurate measure of avoided cost, at least in those markets where natural gas-fired resources are commonly the marginal units. In such markets, the Commission stated that it would expect that new supplies of energy would need to be offered at a price equal to or less than the incremental cost of using these efficient gas units in order to displace them economically. Thus, the Commission found preliminarily that using natural gas price

³¹⁶ *Id*.

indices and the heat rate of an efficient combined-cycle natural gas generating facility to establish an avoided cost energy rate relies on competitive market forces, in this case competitive forces in natural gas markets for the fuel used by natural gas combined-cycle generating facilities that the purchasing electric utility, but for the purchase from the QF, would generate itself or purchase from another source.³¹⁷

b. Comments

206. Several entities oppose the NOPR's Combined Cycle Prices proposal. Allco asserts that this is exactly the type of administrative avoided cost determination about which NARUC and utilities have complained. Allco also argues that the only reason for including the Combined Cycle Prices proposal in the Commission's regulations is to create a menu of prices from which a state commission or unregulated utility can choose the lowest price, which Allco claims would not encourage QF generation, and would be inconsistent with the rules of economic dispatch and the language of PURPA. Public Interest Organizations argue that the Combined Cycle Price proposal is discriminatory to QFs for all the same reasons that restricting QF rates to LMP is discriminatory (i.e., because utilities can, and allegedly do, pay effective prices for energy that exceed the

³¹⁷ *Id.* P 54.

³¹⁸ Allco Comments at 8; BluEarth Comments at 1-2; ELCON Comments at 25-26; Industrial Energy Consumers Comments at 10-11; Public Interest Organizations Comments at 64; R Street Comments at 5; Southeast Public Interest Organizations Comments at 19-20.

³¹⁹ Allco Comments at 8.

 $^{^{320}}$ *Id*

calculation from natural gas prices and assumed combined cycle heat rates).³²¹ Southeast Public Interest Organizations argue that the Combined Cycle Prices proposal does not require states to include variable O&M costs in the proxy combined cycle plant or an adjustment for natural gas transportation, even though a utility-owned combined cycle gas plant would be allowed to recover both types of costs.³²²

207. In contrast, R Street opposes the proposal because using natural gas combined cycle plants as the basis for QF rates in non-RTO/ISO regions could lead to the overpayment of a QF. R Street argues that regions without organized wholesale markets should instead price QF rates at the lowest cost resource based on an administratively determined avoidable cost.³²³

208. Similarly, ELCON argues that the proposal is complicated by the fact that natural gas units are not always marginal, especially in export-constrained subregions when renewables output is high. ELCON believes this proposal would be subject to extensive forecasting error, and therefore argues that careful assessment should precede its adoption.³²⁴

209. Other entities support the NOPR's Combined Cycle Price proposal.³²⁵ The California Commission and EEI argue that states already had this flexibility under the

³²¹ Public Interest Organizations Comments at 64.

³²² Southeast Public Interest Organizations Comments at 19-20.

³²³ R Street Comments at 5.

³²⁴ ELCON Comments at 26.

³²⁵ APPA Comments at 12-13; Arizona Public Service Comments at 6; California

current regulations, and request that the Commission acknowledge this fact in a final rule.³²⁶ Similarly, other supporters of the Combined Cycle Price proposal argue that states should have the ability to develop as-available energy price formulas based on technologies other than combine cycle gas plants, if doing so would more accurately reflect the relevant purchasing utility's avoided cost.³²⁷

210. El Paso Electric argues that: (1) the gas index price should be adjusted to account for the basis differential between the price at the natural gas hub and the price of natural gas in or near the utility's service area; and (2) states should be allowed to update the formula periodically to reflect improved efficiencies in combined cycle generating facilities.³²⁸

c. <u>Commission Determination</u>

211. We adopt the NOPR proposal to revise 18 CFR 292.304 to add a subsection (b)(7) which, in combination with new subsection (e)(1), would permit a state to set the asavailable energy rate paid to a QF by electric utilities located outside of RTO/ISO markets at Combined Cycle Prices, defined as a formula rate established by the state using published natural gas price indices and a proxy heat rate for an efficient natural gas

Commission Comments at 23; Chamber of Commerce Comments at 4; Duke Energy Comments at 9-10; EEI Comments at 27; El Paso Electric Comments at 3; Idaho Commission Comments at 3; Southern Comments at 9.

³²⁶ California Commission Comments at 23; EEI Comments at 27-28.

³²⁷ APPA Comments at 13; Duke Energy Comments at 10; EEI Comments at 27; Idaho Commission Comments at 3; Southern Comments at 9-11.

³²⁸ El Paso Electric Comments at 3-4.

combined-cycle generating facility. We also clarify that the formulas used to set asavailable energy rates based on natural gas prices should include recovery of variable O&M costs.

While some commenters oppose allowing states to use Combined Cycle Prices (or 212. other competitive prices) to set avoided energy cost rates, states already had the flexibility to determine avoided costs in this manner under the current regulations, as the California Commission and EEI observe. 329 If Combined Cycle Prices accurately represent a particular purchasing utility's avoided energy costs, their use would be consistent with the Commission's existing definition of avoided costs as "the incremental costs to an electric utility of electric energy or capacity or both which, but for the purchase from the qualifying facility or qualifying facilities, such utility would generate itself or purchase from another source."330 Furthermore, as noted above in section IV.B.2, the use of competitive market prices, including Combined Cycle Prices, to set QF rates is explicitly subject to the requirement that such prices are equal to the purchasing utility's avoided energy costs. Therefore, this proposal merely codifies more explicitly an option for determining avoided cost rates that already existed, i.e., where a state determines that a Combined Cycle Price is a measure of the purchasing electric utility's avoided cost for asavailable energy.

³²⁹ States could have used any of the competitive prices adopted in this final rule to set avoided cost energy rates as long as such prices met, to the extent practicable, the factors described 18 CFR 292.304(e).

³³⁰ See 18 CFR 292.101(b)(6).

- 213. The concerns of R Street, ELCON, and others that Combined Cycle Prices may not reflect a particular purchasing electric utility's avoided cost are addressed by the requirement that the state would need to determine that the Combined Cycle Price indeed represents the purchasing electric utility's avoided cost for as-available energy.
- 214. While some commenters requested that we expand the proposed regulation explicitly to include technologies other than combined cycle natural gas generating facilities, we decline to do so for two reasons. First, as already mentioned, the current regulations are already flexible enough to accommodate states calculating avoided costs based on the cost of the generating units or technology that accurately reflects the relevant purchasing utility's avoided cost. Second, this proposal focused specifically on combined cycle technology, as opposed to other generating technologies, because combined cycle generation makes up such a large portion of the nation's generation fleet. This relative ubiquity, coupled with the fact that combined cycle natural gas generation facilities are often the marginal units in many regions, justifies an elevated profile in the PURPA Regulations for combined cycle technology compared to other technologies. This final rule does not foreclose other technologies from being used for

³³¹ See 18 CFR 292.101(b)(6).

³³² According to EIA data, the nameplate capacity of natural gas-fired combined cycle generation technology, exceeds the nameplate capacity of generation from any other fuel source. See EIA, Electric Power Annual Table 4.7.A Net Summer Capacity of Utility Scale Units by Technology and by State, 2018 and 2017 (Megawatts), https://www.eia.gov/electricity/annual/html/epa_04_07_a.html, and 4.7.C Net Summer Capacity of Utility Scale Units Using Primarily Fossil Fuels and by State, 2018 and 2017 (Megawatts), https://www.eia.gov/electricity/annual/html/epa_04_07_c.html.

avoided cost determination, upon an appropriate finding by the state that they accurately measure a purchasing electric utility's avoided cost for as-available energy.

- 215. Southeast Public Interest Organizations support their opposition to Combined Cycle Prices in part by claiming that the Commission did not specifically require states to include variable O&M in the formula. We agree that variable O&M expenses are an appropriate cost component of formula rates and should be included in any Combined Cycle Price formulae in order to accurately reflect the relevant purchasing electric utility's avoided costs.
- 216. With respect to the arguments of Southeast Public Interest Organizations regarding natural gas transportation costs, the regulation we adopt in this final rule, 18 CFR 292.304(b)(7)(ii)(C), specifically requires that states consider whether there should be an adjustment to the natural gas price to appropriately reflect the cost of transporting natural gas to the relevant market. As to El Paso Electric's arguments regarding index price adjustments using basis differentials, and periodic formula updates to reflect efficiency improvements, we note that the revisions to the PURPA Regulations, which we adopt in this final rule, provide that states which choose to rely on Combined Cycle Prices must consider, when designing their formulae, whether and to what extent to include these costs, based on their assessment of how best to identify a relevant purchasing electric utility's avoided cost for as-available energy.³³³

³³³ See new 18 CFR 292.304(b)(7)(ii).

- 6. Permitting the Energy Rate Component of a Contract to be Fixed at the Time of the LEO Using Forecasted Values of the Estimated Stream of Market Revenues
- 217. The NOPR noted that, frequently, price forecasts are available for LMPs in RTOs/ISOs, for liquid market hubs located outside of RTOs/ISOs, and for natural gas pricing hubs. Accordingly, the NOPR suggested that such forecasts could be used to allow QFs to request a fixed energy rate component calculated at the time a LEO is incurred. The Commission therefore proposed to add a new option in 18 CFR 292.304(d)(1)(iii) permitting fixed energy rates to be based on forecasted estimates of the stream of revenue flows during the term of the contract.³³⁴ In other words, states could rely on estimates of forecasted energy prices at the time of delivery over the anticipated life of the contract such estimates are commonly referred to as forward price curves to develop a fixed energy rate component for that contract when such estimates reflect the purchasing electric utility's avoided costs.
- 218. The NOPR stated that the fixed energy rate component of the contract could be a single energy rate, based on the amortized present value of the forecast energy prices, or it could be a series of specified energy rates that are different in future years (or other periods).³³⁵ Under this proposal, the QF would be able to establish, at the time the LEO is

³³⁴ NOPR, 168 FERC ¶ 61,184 at P 61.

³³⁵ *Id.* P 62 (noting that the PURPA Regulations already require that the fixed energy rate would need to account for the operating characteristics of the QF, including the QF's ability to deliver energy during peak periods and the utility's ability to dispatch energy from the QF (citing 18 CFR 292.304(e)(2)).

incurred, the applicable energy rate(s) for the entire term of a contract; however, the energy rate in the contract could be different from year-to-year (or some other period) and nevertheless comply with the current requirement in 18 CFR 292.304(d)(2)(ii) that the energy rate be fixed for the term of the contract.³³⁶

a. Comments

219. Two commenters oppose the NOPR proposal to add a new option in 18 CFR 292.304(d)(1)(iii) permitting fixed energy rates to be based on forecasted estimates of the stream of revenue flows during the life of the contract.³³⁷ Southeast Public Interest Organizations and Mr. Mattson state that the NOPR proposal is a departure from past precedent.³³⁸ Southeast Public Interest Organizations state that this proposal suffers the same deficiencies as the LMP and liquid market hub price proposals. Furthermore, according to Southeast Public Interest Organizations, the NOPR provides no analysis as to

Regulations (citing *Windham Solar LLC*, 157 FERC ¶ 61,134, at PP 5-6 (2016) (*Windham Solar*) ("[A]lthough state regulatory authorities cannot preclude a QF . . . from obtaining a legally enforceable obligation with a forecasted avoided cost rate, we remind the parties that the Commission's regulations allow state regulatory authorities to consider a number of factors in establishing an avoided cost rate. These factors which include, among others, the availability of capacity, the QF's dispatchability, the QF's reliability, and the value of the QF's energy and capacity, allow state regulatory authorities to establish lower avoided cost rates for purchases from intermittent QFs than for purchases from firm QFs." (citing 18 CFR 292.304(e)-(f)) (footnote omitted))).

³³⁷ Southeast Public Interest Organizations Comments at 25; Mr. Mattson Comments at 26.

³³⁸ Southeast Public Interest Organizations Comments at 25; Mr. Mattson Comments at 26.

how or whether the forward price curves result in just and reasonable and nondiscriminatory rates as required by PURPA.³³⁹

220. Other commenters support the NOPR proposal to add a new option in 18

CFR 292.304(d)(1)(iii) permitting fixed energy rates to be based on forecasted estimates of the stream of revenue flows during the term of the contract. The South Dakota Commission and Pennsylvania Commission state that they support the NOPR proposal on forecasted values of the estimated stream of revenues because it forecasts a steady stream of revenue and provides built-in flexibility. According to these commenters, the proposal also balances the QF's need for a steady stream of revenue with the purchasing electric utility's responsibility to have a prudent mix of supply contracts for its provider of last resort obligations. The Chamber of Commerce states that, while future rates are not guaranteed to materialize, the projected rates will more accurately reflect those realized than a single avoided cost rate set at the inception of a QF contract. As

³³⁹ Southeast Public Interest Organizations Comments at 25.

³⁴⁰ Allco Comments at 8; APPA Comments at 14; Arizona Public Service Comments at 2-3; Chamber of Commerce Comments at 4-5; Connecticut Authority at 13; Distributed Sun Comments at 2; EEI Comments at 28-30; Idaho Commission Comments at 4; NorthWestern Comments at 6; NRECA Comments at 8; Pennsylvania Commission Comments at 8; Resources for the Future Comments at 8; South Dakota Commission Comments at 3.

³⁴¹ Pennsylvania Commission Comments at 8-9; South Dakota Commission Comments at 3.

³⁴² Pennsylvania Commission Comments at 8-9.

³⁴³ Chamber of Commerce Comments at 4-5.

- 221. Arizona Public Service states that it supports the proposal because it grants states additional flexibility, which helps protect utilities' customers from over-paying for generation due to QFs need for sales guarantees and financing.³⁴⁴ NRECA agrees that states must have flexibility in determining forecasted market prices including appropriate discounting to ensure that utilities and consumers are not locked into contracts with fixed prices that are higher than prevailing market prices.³⁴⁵
- 222. NRECA requests that the Commission clarify proposed revisions to 18 CFR 292.304(d)(1)(i), (ii), and (iii) to state that an electric utility is exempt from offering a stream of market revenue as payment, even if there is a market hub price that could be relevant. The Connecticut Authority also suggests that the Commission modify 18 CFR 292.304(d)(1)(ii) to specify that a state may set a series of energy rates. For this option, Connecticut Authority argues, the regulatory text should provide greater regulatory and commercial certainty to QF developers, avoiding disputes with distribution utilities and states. 347
- 223. Connecticut Authority supports revisions to 18 CFR 292.304(d)(2) because the rule would permit a state to limit a QF's option to select a preferred energy rate

³⁴⁴ Arizona Public Service Comments at 2-3.

³⁴⁵ NRECA Comments at 8.

³⁴⁶ *Id.* at 9.

³⁴⁷ Connecticut Authority Comments at 14.

methodology.³⁴⁸ Connecticut Authority also supports the proposed 18 CFR 202.304(d)(iii) that permits states to set a stated or fixed rate for energy that is calculated using the present value of the expected stream of revenue from as-available energy rates during the life of the contract or LEO.

- 224. EEI states that this proposal is not novel, and as an example notes that the Commission and a federal district court have already found that the Connecticut Authority could set avoided cost rates based on a forecast of future avoided costs. According to EEI, the Commission has not ruled either that any form of forecasting is mandated or that any is unacceptable. 350
- 225. Allco states that the proposed new option in 18 CFR 292.304(d)(1)(iii) permitting fixed energy rates to be based on forecasted estimates of the stream of revenue flows during the life of the contract is consistent with PURPA section 210 and is already permitted. Allco also states that forecasts need to be non-discriminatory. According to Allco, utilities and states frequently use one forecast when dealing with QFs and another when obtaining approval for their favored projects; Allco asserts that this practice is discriminatory.³⁵¹

³⁴⁸ *Id.* at 13.

 $^{^{349}}$ EEI Comments at 28 (citing *Allco Renewable Energy Ltd. v. Mass. Elec. Co.*, 208 F. Supp. 3d. 390, 395 (D. Mass. 2016); *Windham Solar*, 157 FERC \P 61,134 at P 5.

³⁵⁰ EEI Comments at 28-30.

³⁵¹ Allco Comments at 8.

226. APPA states that the proposed change is a logical extension of the conclusion that market options are a legitimate alternative means of specifying avoided costs.³⁵²

Distributed Sun states that it supports permitting states to set fixed energy rates with forward curves or through competitive solicitations.³⁵³ NorthWestern supports the proposal to permit fixed energy rates to be on a forward price curve developed from prices in either the organized markets or liquid market hubs.³⁵⁴

b. <u>Commission Determination</u>

227. We adopt the proposal to add a new option in 18 CFR 292.304(d)(1)(iii) permitting fixed energy rates to be based on forecasted estimates of the stream of revenue flows during the term of the contract. The Commission has previously permitted the use of this method to establish energy and capacity rates over the term of a contract or LEO.³⁵⁵

Nevertheless, given the flexibilities we adopt in this final rule with respect to competitive market prices and variable energy rates, we clarify here that a state may use competitive market prices and/or variable energy rates in the context of a more fixed estimated avoided cost energy rate (together with a fixed avoided capacity rate) that is determined at the time an LEO or contract is incurred. The fixed energy rate component of the contract could be a single rate, based on the amortized present value of forecast energy prices, or it

³⁵² APPA Comments at 14.

³⁵³ Distributed Sun Comments at 2.

³⁵⁴ NorthWestern Comments at 6.

³⁵⁵ Windham Solar, 157 FERC ¶ 61,134 at P 4 (citing 18 CFR 292.304(d)(2)).

could be a series of specified rates that change from year-to-year (or other periods) in future years. We also will allow the state to establish the applicable energy rate(s) for the QF for the entire term or the rate may change from year-to-year (or some other period) of the contract at the time the LEO is incurred.

- 228. Southeast Public Interest Organizations and Mr. Mattson state that the NOPR proposal is a departure from past precedent. The very purpose of a proceeding like this is to consider changes to our regulations and our doing so is not impermissible.
- 229. Southeast Public Interest Organizations also state that the proposal suffers the same deficiencies as the LMP and liquid market hub pricing proposals and that the NOPR provides no evidence as to how or if the forward price curves present just and reasonable and non-discriminatory rates as required by PURPA. Given that we find above that LMPs and liquid market hub prices may reflect avoided as-available energy costs and that estimates of such prices over the term of a contract can therefore reflect a purchasing electric utility's avoided as-available costs over time, we do not believe Southeast Public Interest Organizations and Mr. Mattson's concerns are justified.
- 230. Although, as described below, we allow states to require variable avoided cost energy rates, allowing forward price curves determined at the time an LEO is incurred provides an additional option for states to calculate avoided energy costs in advance while also using transparent metrics for those calculations. Use of the forward price curve does not deter the adoption of just and reasonable and non-discriminatory rates required by PURPA, moreover, and insofar as we require that states determine that the estimated stream of revenues reflects the purchasing electric utility's avoided energy, such pricing is

fully consistent with the statute's requirements. With regard to forecasts, we acknowledge that the forecast used to set the avoided cost rate must meaningfully and reasonably reflect the utility's avoided costs over time.³⁵⁶

231. We decline to modify this proposal expressly either to permit or prohibit a state from setting a series of estimated avoided energy costs over time. Each state will be required to determine whether a particular estimated stream of revenues represents a purchasing electric utility's avoided costs over a specified term. Similarly, in order to provide states flexibility to use LMPs and other competitive market prices to establish asavailable avoided energy costs, we will not require a state to use this option to guarantee a stream of revenues.

7. Providing for Variable Energy Rates in QF Contracts

a. Background

232. As explained above, if a QF chooses to sell energy and/or capacity pursuant to a contract, the PURPA Regulations currently provide the QF the option of receiving the purchasing electric utility's avoided cost calculated and fixed at the time the LEO is incurred.³⁵⁷ The Commission's justification in Order No. 69 for allowing QFs to fix their rate at the time of the LEO for the entire term of a contract was that fixing the rate

³⁵⁶ See 18 CFR 292.304(b)(5). Rates calculated at the time of a LEO (for example, a contract) do not violate the requirement that the rates not exceed avoided costs if they differ from avoided costs at the time of delivery.

³⁵⁷ 18 CFR 292.304(d)(2)(ii).

provides certainty necessary for the QF to obtain financing.³⁵⁸ The Commission stated that its regulations pertaining to LEOs "are intended to reconcile the requirement that the rates for purchases equal the utilities' avoided costs with the need for qualifying facilities to be able to enter contractual commitments based, by necessity, on estimates of future avoided costs."³⁵⁹ Further, the Commission agreed with the "need for certainty with regard to return on investment in new technologies."³⁶⁰ The Commission stated its belief that any overestimations or underestimations "will balance out."³⁶¹

233. The provision that QFs be permitted to fix their rates for the entire term of a contract or other LEO has proved to be one of the most controversial aspects of the Commission's PURPA Regulations. Some commenters at the Technical Conference submitted data indicating that energy prices have declined in recent years, leaving the fixed energy portion of the QF rate, even when levelized, well above market prices that likely would represent the purchasing electric utility's actual avoided energy costs at the time of delivery. Based on this concern, some commenters recommended that the

³⁵⁸ Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,880 (justifying the rule on the basis of "the need for certainty with regard to return on investment in new technologies").

³⁵⁹ *Id*.

³⁶⁰ *Id*.

³⁶¹ *Id*.

³⁶² See Alliant Energy Comments, Docket No. AD16-16-000, at 5 (Nov. 7, 2016) ("Current market-based wind prices in the Iowa region of MISO are approximately 25 [percent] lower than the PURPA contract obligation prices [Interstate Power and Light Company] is forced to pay for the same wind power for long-term contracts entered into as of June 2016. As a result, PURPA-mandated wind power purchases associated with

Commission allow states to "price generation [energy] from QFs at market prices, and to update those prices regularly so that the prices for [QFs] are not burdensome on customer rates" and that the Commission should limit avoided cost energy rates in a LEO to no higher than avoided cost rates at the time of delivery. ³⁶³ QFs, in turn, argued that elimination of the option to fix QF rates for the term of a contract would threaten a QF's ability to obtain financing. ³⁶⁴

just one project could cost Alliant Energy's Iowa customers an incremental \$17.54 million above market wind prices over the next 10 years.") (emphasis in original); EEI Supplemental Comments, Docket No. AD16-16-000, attach. A at 3-4 (June 25, 2018) (EEI Supplemental Comments) ("On August 1, 2014, a 10-year fixed price contract at the Mid-Columbia wholesale power market trading hub was priced at \$45.87/MWh. On June 30, 2016, the same contract was priced as \$30.22/MWh, a decline of 34 [percent] in less than two years. However, over the next 10 years, PacifiCorp has a legal obligation to purchase 51.9 million MWhs under its PURPA contract obligations at an average price of \$59.87/MWh. The average forward price curve for the Mid-Columbia trading hub during the same period is \$30.22/MWh, or 50 [percent] below the average PURPA contract price that PacifiCorp will pay. The additional price required under long-term fixed contracts will cost PacifiCorp's customers \$1.5 billion above current forward market prices over the next 10 years."); Comm'r Kristine Raper, Idaho Commission Comments, Docket No. AD16-16-000, at 3-4 (filed June 30, 2016) ("Idaho Power demonstrated that the average cost for PURPA power since 2001 has exceed the Mid-Columbia (Mid-C) Index Price and is projected to continue to exceed the Mid-C price through 2032. Likewise, PacifiCorp's levelized avoided cost rates for 15-year contract terms in Wyoming shows a decrease of approximately 50 [percent] from 2011 through 2015 (from approximately \$60 per megawatt-hour to less than \$30 per megawatt-hour).").

³⁶³ EEI Supplemental Comments, attach. A at 4; *see also* Southern Company Comments, Docket No. AD16-16-000, at 7 (filed June 30, 2016) ("[T]he avoided energy cost payment to the QF should be based on actual avoided energy cost at the time the QF delivers energy.").

³⁶⁴ See Technical Conference, Docket No. AD16-16-000, Tr. 26:22-25, 27:1-3 (June 29, 2016) (filed July 8, 2016) (Technical Conference Tr.) (Solar Energy Industries) ("The Power Purchase Agreement is the single most important contract of the development and financing of an energy project that's not owned by a utility. Without the long-term commitment to buy the output of that agreement at a fixed price, there is no predictable

b. NOPR Proposal

234. In the NOPR, the Commission proposed to revise 18 CFR 292.304(d) to permit a state to limit a QF's option to elect to fix at the outset of a LEO the energy rate for the entire length of its contract or LEO, and instead allow the state the flexibility to require QF energy rates to vary during the term of the contract. However, under the proposed revisions to 18 CFR 292.304(d), a QF would continue to be entitled to a contract with avoided *capacity* costs calculated and fixed at the time the contract or LEO is incurred. Only the *energy* rate in the contract or LEO could be required by a state to vary. Further, the NOPR did not propose to obligate states to require variable avoided cost energy rates—they would retain the ability to allow the QF's energy rate be fixed at the time the LEO is incurred.³⁶⁵

235. The Commission preliminarily found compelling the record evidence that overestimations have not been adequately balanced by underestimations in past years. Further, it appeared to the Commission that this trend may persist into the future with the continuing general decline in the cost of both wind and solar generation.³⁶⁶ Consequently,

stream of revenue. Without a predictable stream of revenues, there is no financing. Without any financing, there is no project.").

³⁶⁵ NOPR, 168 FERC ¶ 61,184 at P 67.

³⁶⁶ *Id.* P 68 (citing EIA, Today in Energy, *Average U.S. construction costs for solar and wind continued to fall in 2016* (Aug. 8, 2018), https://www.eia.gov/todayinenergy/detail.php?id=36813 ("Based on 2016 EIA data for newly constructed utility-scale electric generators (those with a capacity greater than one megawatt) in the United States, annual capacity-weighted average construction costs for solar photovoltaic systems and onshore wind turbines declined")).

the Commission found that it may be necessary to allow states to provide for a variable energy rate in order to reflect more accurately the purchasing electric utility's avoided costs and therefore to satisfy the statutory requirement that QF rates not exceed the utility's avoided cost and "be just and reasonable to the electric consumers of the electric utility and in the public interest." 367

236. The Commission acknowledged that the current PURPA Regulations allowing a QF to fix its rates for the life of a contract or LEO were based on the recognition that fixed rates are beneficial for obtaining financing for QF projects. The Commission also recognized that QF developers have continued to assert that they require fixed rates to finance new projects. However, the Commission stated that it did not view the proposed modification to the PURPA Regulations as materially affecting the ability of QFs to obtain financing for several reasons.³⁶⁸

237. First, the Commission expressed its understanding that fixed energy rates are not generally required in the electric industry in order for electric generation facilities to be financed. For example, RTO/ISO capacity markets provide only for fixed capacity payments, leaving capacity owners to sell their energy into the organized electric markets at LMPs that vary based on market conditions at the time the energy is delivered. The Commission stated that these fixed capacity and variable energy payments have been sufficient to permit the financing of significant amounts of new capacity in the RTOs and

³⁶⁷ *Id.* P 68 (internal quotations omitted) (citing 16 U.S.C. 824a-3(b)(1)).

³⁶⁸ *Id.* P 69.

ISOs.³⁶⁹ Testimony presented at the Technical Conference similarly showed that non-QF independent power projects located outside of RTOs enter into contracts with fixed capacity and variable energy prices.³⁷⁰ Other comments at the Technical Conference suggested that a fixed capacity charge likewise would be adequate for financing a QF project.³⁷¹

238. The Commission further noted that there are financial products available, such as contracts for differences, which allow generation owners to hedge their exposure to fluctuating energy prices.³⁷² The Commission stated that financial products can provide additional comfort to lenders regarding the level of energy rate revenues that a QF can

³⁶⁹ *Id.* P 70 (citing Monitoring Analytics, LLC., *Third Quarter, 2018 State of the Market Report for PJM, January through September*, at 249, Table 5-6 (Nov. 8, 2018), http://www.monitoringanalytics.com/reports/PJM_State_of_the_Market/2018/2018q3-som-pjm.pdf (over 23,000 MW of new capacity constructed in PJM Interconnection, L.L.C. since 2007-2008; including over 16,000 MW of new capacity added in the last four years)).

³⁷⁰ *Id.* (citing Technical Conference Tr. at 167-69 (Southern Company) ("So if we enter into a bilateral contract with an independent power producer for combustion turbine or combined cycle capacity, we don't fix the energy price. The capacity payment is a fixed payment. That's their fixed [stream]. The energy price is typically indexed to the price of natural gas."); *id.* at 178 (American Forest & Paper Association) ("Now, you sign a long-term IPP contract. That contract [has] got a variable energy cost in it.")).

³⁷¹ *Id.* P 70 (citing Solar Energy Industries Comments, Docket No. AD16-16-000, at 3 (filed June 30, 2016) ("Developers need rates for such sales of *energy and/or capacity* to be fixed.") (emphasis added)).

 $^{^{372}}$ Id. P 72 (citing Elec. Storage Participation in Mrkts. Operated by Reg'l Transmission Org. and Independent Sys. Operators, Order No. 841, 162 FERC ¶ 61,127, at P 299 (2018) (noting that "market participants that purchase energy from the RTO/ISO markets . . . may enter into bilateral financial transactions to hedge the purchase of that energy")).

expect from the energy it delivers, in addition to the fixed capacity payments the QF is entitled to receive under its contract.³⁷³

239. The Commission also explained that, although it may have been true at the time the Commission promulgated its PURPA Regulations in 1980 that QFs needed to fix their energy rate for the term of their contract in order to obtain financing of their facilities, there is evidence that this no longer is true. This evidence comes in the form of data, described below, showing that independent generators that have not qualified as QFs under PURPA (including renewable resources that could qualify as QFs but have not sought QF status) have been able to obtain financing for new facilities. The Commission stated that the fact that owners of such facilities, which do not have recourse to the avoided cost rate provisions of PURPA, have been able to obtain financing for new projects is relevant to the question of whether the existing PURPA avoided cost provisions – including the requirement to enter into contracts with fixed energy rates – are necessary for QFs to obtain financing. ³⁷⁴

240. For example, EIA data showed that, since 2005, QFs have made up only 10% to 20% of all renewable resource capacity in service in the United States, demonstrating that most renewable resources no longer need to rely on PURPA avoided cost rates to sell their output economically.³⁷⁵ EIA data also showed that net generation of energy by non-utility

³⁷³ *Id.* P 72.

³⁷⁴ *Id.* P 73.

³⁷⁵ Id. P 74 (citing EIA, Today in Energy, North Carolina has More PURPA-Qualifying Solar Facilities than any other State, figure titled PURPA qualifying facilities

owned renewable resources in the United States escalated from 51.7 terawatt hours (TWh) in 2005 when EPAct 2005 was passed, to 340 TWh in 2018. The Commission further observed that, while much of this growth was in states located in RTOs/ISOs, there also was significant growth of non-utility renewable generation in other states. For example, net generation by non-utility renewable resources in the region defined by EIA as the Mountain State region³⁷⁶ increased from 3.6 TWh in 2005 to 19.5 TWh in 2012, and to 42.5 TWh in 2018. Pacific Northwest (Oregon and Washington) net non-utility generation from renewable resources increased from 1.5 TWh in 2005, to 8.7 TWh in 2012, and to 10.6 TWh in 2018.³⁷⁷

241. The Commission found that EIA data on independently-owned natural gas-fired generation capacity told a similar story. Natural gas-fired capacity without the requisite cogeneration technology cannot qualify as qualifying small power production or cogeneration, and thus most of this capacity would not be within the scope of the PURPA avoided cost rate provisions. The Commission cited to EIA data showing that, in 2018, approximately 44% of all energy produced by natural gas-fired generation in the United States was generated by independently-owned capacity.³⁷⁸ The total amount of energy

⁽¹⁹⁸⁰⁻²⁰¹⁵⁾ percent of total renewable capacity (Aug. 23, 2016), https://eia.gov/todayinenergy/detail.php?id=27632).

³⁷⁶ Arizona, Colorado, Idaho, Montana, Nevada, New Mexico, Utah, and Wyoming.

³⁷⁷ NOPR, 168 FERC ¶ 61,184 at P 74.

 $^{^{378}}$ NOPR, 168 FERC \P 61,184 at P 75 (citing EIA, *Electric Power Monthly with Data for December 2018*, at tbl. 1.7.B,

produced in 2018 by independently-owned natural gas-fired generation was 651 TWh, an increase of 13.7% from 2017.³⁷⁹ Again, the percentage of independently-owned natural gas generation outside of RTOs/ISOs was lower than in RTOs/ISOs, but still was significant. In the Mountain State region, 21.4% of the energy produced by natural gasfired generation in 2018 was produced by independently-owned capacity, and in Oregon and Washington 45.4% of natural gas-fired energy was produced by independently-owned capacity.³⁸⁰ From this, the Commission concluded that independent owners of non-OF generation have been, and continue to be, able to obtain financing for their facilities.³⁸¹ 242. The Commission did not suggest that this evidence supports the conclusion that substantial non-QF capacity is being financed and constructed without any form of fixed revenue to support financing. Rather, the Commission concluded that the evidence demonstrated that the existing PURPA avoided cost rate provisions are not necessary for some independent power generators to put in place contractual arrangements, including fixed revenue streams, that are sufficient to obtain financing. The Commission reasoned that OFs, which have the ability to take advantage of PURPA's mandatory purchase requirements, should be better positioned than non-QFs to negotiate the necessary contractual arrangements for financing. Moreover, the Commission noted that QFs are

https://www.eia.gov/electricity/monthly/current_month/epm.pdf.).

³⁷⁹ *Id*.

³⁸⁰ *Id*.

³⁸¹ *Id*.

equally as well positioned as non-QF independent generators to take advantage of federal and state incentives designed to encourage the construction of renewable resources. ³⁸² 243. Further, the Commission pointed to evidence that the desire to limit the effect of fixed QF contract rates had directly led to PURPA implementation issues that affected QF financing in other respects, particularly with respect to the length of QF contracts. ³⁸³ For example, a commissioner of the Idaho Commission testified at the Technical Conference that the Idaho Commission's decision to limit QF contracts to a two-year term was based on the Idaho Commission's concern that longer contract terms at fixed rates would lead to payments above avoided costs. ³⁸⁴ Similarly, Southern Company testified that the fixed rate requirement is "resulting in . . . typically shorter contract term lengths." ³⁸⁵ Golden Spread Electric Cooperative recommended that, if the fixed rate requirement is not eliminated, the Commission permit shorter contract terms, "as short as one-year or three years at most." ³⁸⁶

³⁸² *Id.* P 76.

³⁸³ *Id.* P 65 (citing Natural Resources Defense Council Comments, Docket No. AD16-16-000, at 4 (filed June 30, 2016)).

³⁸⁴ *Id.* P 65 (citing Technical Conference Tr. at 142-43 (Idaho Commission) ("No matter the starting point, allowing QFs to fix their avoided cost rates for long terms results in rates which will eventually exceed and overestimate avoided cost rates into the future. The longer the term, the greater the disparity. . . . [The Idaho Commission] recently reduced PURPA contract lengths to two years in order to correct the disparity. We didn't reduce contract lengths to kill PURPA. We did it to allow periodic adjustment of avoided cost rates.")).

³⁸⁵ *Id.* P 65 (citing Technical Conference Tr. at 202 (Southern Company)).

³⁸⁶ Id. P 65 (citing Golden Spread Electric Cooperative Comments, Docket

244. Finally, the Commission addressed one particular standard form of QF contract rate currently employed by a number of utilities, which is a one-part rate, applicable to each MWh of energy delivered by the QF. This one-part rate is calculated to reflect both avoided capacity costs and avoided energy costs. Contracts employing such rates also typically impose a must purchase obligation on the purchasing utility. The Commission stated that its proposed rule was not intended to prevent states from implementing such an approach to setting QF contract rates in the future. The Commission proposed that, to the extent a state determines to establish a one-part QF contract rate that recovers both avoided capacity and avoided energy costs, the rate must continue to be subject to the QF's option to select a fixed rate for the term of the contract, as provided in 18 CFR 304(d)(2)(ii). Any requirement to impose a variable energy QF contract rate would need to be accomplished through a multi-part rate that includes separate avoided capacity cost rates and avoided energy cost rates.³⁸⁷

c. General Comments on the NOPR Proposal

i. Comments in Support of NOPR Proposal

245. Several commenters support the NOPR proposal to allow energy rates to vary in QF contracts and other LEOs, arguing it will reduce overpayments and protect customers.³⁸⁸ In that regard, Duke Energy asserts that the primary factor behind

No. AD16-16-000, at 10 (filed June 30, 2016)).

³⁸⁷ *Id.* P 81.

³⁸⁸ Conservative Action Comments at 1; Consumer Energy Alliance Comments at 2; EEI Comments at 30-31; Idaho Power Comments at 7-8; Idaho Commission Comments

overpayment has been the requirement to offer fixed avoided cost energy rates during a period of rapidly declining energy prices.³⁸⁹ Several other commenters similarly cite to the general decline of energy prices coupled with the fact that QFs have been able to lock in rates over the life of a contract or other LEO as reasons for their support of the NOPR proposal.³⁹⁰

246. Several commenters also support the NOPR's variable rate proposal because it will allow states greater flexibility to determine avoided cost rates accurately and to meet PURPA's consumer protection goals.³⁹¹ LG&E/KU states that such flexibility is appropriate and necessary to meet the statutory requirement that ratepayers not pay a rate that exceeds the electric utility's incremental cost of alternative energy.³⁹² NorthWestern argues that providing such flexibility will assist in guaranteeing that customers are held harmless by purchases of OF power.³⁹³

at 4; LG&E/KU Comments at 3; NextEra Comments at 5; see also Alaska Power Comments at 1; Arizona Public Service Comments at 3-4; Basin Comments at 6-8; Chamber of Commerce Comments at 4; Freedom Center Comments at 1-2; R Street Comments at 5; Tax Reform Comments at 1-2.

³⁸⁹ Duke Energy Comments at 5-7.

³⁹⁰ Consumer Energy Alliance Comments at 2; Idaho Power Comments at 7-8; Idaho Commission Comments at 4; LG&E/KU Comments at 3; Ohio Commission Energy Advocate Comments at 4.

³⁹¹ Alliant Energy Comments at 9; Duke Energy Comments at 8-9; LG&E/KU Comments at 4; MA DPU Comments at 1, 7; NorthWestern Comments at 6-7.

³⁹² LG&E/KU Comments at 4.

³⁹³ NorthWestern Comments at 6-7.

247. Supporters of the NOPR variable rate proposal also commented on specific aspects of the proposal. These comments are discussed in more detail in the following sections.

ii. Comments in Opposition to NOPR Proposal

248. Several commenters oppose the NOPR variable energy rate proposal.³⁹⁴ In addition to objections as to specific aspects of that proposal, which are discussed in the following sections, some commenters raise threshold issues regarding this proposal.

249. NIPPC, CREA, REC, and OSEIA cite to the PURPA Conference Report as expressing Congress's intent that QFs be entitled to long-term fixed energy rates.

Specifically, they cite to the statement in the Conference Report that "the Commission and States should look to the reliability of that power to the utility and the cost savings to the utility which may result at some later date by reason of supply to the utility at that time of power from the cogenerator or small power producer." According to NIPPC, CREA, REC, and OSEIA, this statement shows that "Congress also recognized that attempts to set

³⁹⁴ Allco Comments at 9-11; AllEarth Comments at 2; Biogas Comments at 2; BluEarth Comments at 2; CARE Comments at 3-5; Biological Diversity Comments at 8; ELCON Comments at 18, 21-23; EPSA Comments at 6-13; Massachusetts AG Comments at 8-9; North Carolina DOJ Comments at 2-6; North Carolina Commission Staff Comments at 2-4; New England Hydro Comments at 8; NIPPC, CREA, REC, and OSEIA Comments at 29-48; North American-Central Comments at 4-6; Public Interest Organizations Comments at 6-7, 27-51; Resources for the Future Comments at 4-7; Solar Energy Industries Comments at 28-38; SC Solar Alliance Comments at 4-10; Southeast Public Interest Organizations Comments at 9-18; sPower Comments at 10-13; State Entities Comments at 2-3; Mr. Mattson Comments at 26-27; Two Dot Wind Comments at 11-13; Western Resource Councils Comments at 2.

³⁹⁵ NIPPC, CREA, REC, and OSEIA Comments at 27 (quoting Conf. Rep. at 98-99).

the rates based on the avoided costs at the time of delivery would likely be insufficient to encourage such facilities."³⁹⁶

- 250. Harvard Electricity Law asserts that the Commission may not authorize state regulators to change rates in existing contracts.³⁹⁷ Harvard Electricity Law then asserts that the Commission: (1) attempts to portray its agenda as consistent with Congressional intent by providing a skewed summary of the legislative history; (2) presents an unsupported statement that its rules will "continue to encourage" QF development, which ignores the administrative record and fails to account for regulatory changes since PURPA's enactment; (3) misreads its own rules in claiming that repeal is necessary to protect consumers; and (4) relies on a finding that fixed price energy contracts are not necessary to encourage QFs that is based on irrelevant data and questionable assumptions that are not grounded in reasoned decision making.
- 251. Harvard Electricity Law also asserts that allowing long-term contracts to include variable rates is contrary to PURPA.³⁹⁸ In support of this assertion, Harvard Electricity Law cites to two decisions which it claims stand for the proposition that the Commission's proposed rule would impose forbidden utility-type regulation on QFs.³⁹⁹

³⁹⁶ Id

³⁹⁷ Harvard Electricity Law Comments at 23 (citing *API*, 461 U.S. at 414).

³⁹⁸ *Id.* at 28.

³⁹⁹ Id. at 29 (citing Freehold Cogeneration Assoc. v. Bd. of Regulatory Comm'rs. of N.J., 44 F.3d 1178, 1193 (3d Cir. 1995) (Freehold Cogeneration); Smith Cogeneration Mgt. v. Corp. Comm'n., 863 P.2d 1227 (Okla. 1993) (Smith Cogeneration)).

252. NIPPC, CREA, REC, and OSEIA and Public Interest Organizations assert that it is unclear whether independent power producers that have obtained financing did so with short-term variable rate conditions. North American-Central argues that, if a variable rate will preclude a QF from receiving financing in the first place, it is irrelevant that a state might be more willing to offer a longer-term contract. 401

iii. <u>Commission Determination</u>

- 253. In this final rule, we adopt without modification the NOPR variable rate proposal. We find that setting QF energy avoided cost contract and other LEO rates at the level of the purchasing utility's avoided energy costs at the time the energy is delivered is consistent with PURPA, which limits QF rates to the purchasing utility's avoided costs. Indeed, a variable energy avoided cost approach is a more accurate way to ensure that payments to QFs equal, but do not exceed, avoided costs. It is inevitable that, in contrast, over the life of a QF contract or other LEO a fixed energy avoided cost rate, such as that used in past years, will deviate from actual avoided costs.
- 254. As described in more detail in the following sections, the record overwhelmingly supports our conclusions that long-term forecasts of avoided energy costs are inherently less accurate, and that states should be given the flexibility to rely on a more accurate variable avoided cost energy rate approach. Further, there are numerous instances where

⁴⁰⁰ NIPPC, CREA, REC, and OSEIA Comments at 46.

⁴⁰¹ North American-Central Comments at 5-6.

⁴⁰² 16 U.S.C. 824a-3(b)(1).

overestimates and underestimates have not balanced out.⁴⁰³ When that has occurred, consumers have borne the brunt of the overpayments, which subsidized QFs, in contravention of Congressional intent and the Commission's expectations.

⁴⁰³ See Duke Comments at 6 (Duke's QF contracts cost \$4.66 billion but its "actual current avoided costs" are \$2.4 billion); Idaho Power Comments at 10-11 ("The cost of PURPA generation contained in Idaho Power's base rates, on a dollars per MWh basis, is not just greater than Mid-C market prices, it is greater than all the net power supply cost components currently recovered in base rates. Idaho Power's average cost of PURPA generation included in base rates is \$62.49/MWh. At \$62.49/MWh, the average cost of PURPA purchases is greater than the average cost of FERC Account 501, Coal at \$22.79/MWh; greater than FERC Account 547, Natural Gas at \$33.57/MWh; greater than FERC Account 555, Non-PURPA Purchases at \$50.64/MWh; and significantly greater than what is being sold back to the market as FERC Account 447, Surplus Sales at \$22.41/MWh."); Portland General Comments at 5 ("for a typical 3 MW Solar QF project that incurred a LEO in 2016 and reaches commercial operations three years later, [Portland General's customers would pay 67% more for the project's energy than if the 2019 avoided cost rate had been used. As a result of this lag, [Portland General's] customers would pay an additional \$1.6 million more for the energy from the QF facility over the 15year contract term."); see also NOPR, 168 FERC 61,184 at P 64 n.101 (citing Alliant Energy, Comments, Docket No. AD16-16-000, at 5 (filed Nov. 7, 2016) ("Current marketbased wind prices in the Iowa region of MISO are approximately 25% lower than the PURPA contract obligation prices [Interstate Power and Light Company] is forced to pay for the same wind power for long-term contracts entered into as of June 2016. As a result, PURPA-mandated wind power purchases associated with just one project could cost Alliant Energy's Iowa customers an incremental \$17.54 million above market wind prices over the next 10 years.") (emphasis in original); EEI Supplemental, Comments, attach. A at 3-4 ("On August 1, 2014, a 10-year fixed price contract at the Mid-Columbia wholesale power market trading hub was priced at \$45.87/MWh. On June 30, 2016, the same contract was priced as \$30.22/MWh, a decline of 34% in less than two years. However, over the next 10 years, PacifiCorp has a legal obligation to purchase 51.9 million MWhs under its PURPA contract obligations at an average price of \$59.87/MWh. The average forward price curve for the Mid-Columbia trading hub during the same period is \$30.22/MWh, or 50% below the average PURPA contract price that PacifiCorp will pay. The additional price required under long-term fixed contracts will cost PacifiCorp's customers \$1.5 billion above current forward market prices over the next 10 years."); Comm'r Kristine Raper, Idaho Commission Comments, Docket No. AD16-16-000, at 3-4 (filed June 30, 2016) ("Idaho Power demonstrated that the average cost for PURPA power since 2001 has exceed the Mid-Columbia (Mid-C) Index Price and is projected to continue to exceed the Mid-C price through 2032. Likewise, PacifiCorp's levelized avoided cost rates for 15-year

- 255. Given that PURPA section 210(b) prohibits the Commission from requiring QF rates in excess of avoided costs, 404 this record evidence supports our decision to give the states the flexibility to require variable avoided cost energy rates in QF contracts and other LEOs to prevent QF rates from exceeding avoided costs. We discuss specific aspects of the variable energy rate provisions below, but at the outset address certain threshold issues raised in the comments.
- 256. We reiterate the points made in detail above in Section II. The variable energy avoided cost rate provision is not based on any determination that the Commission's rules no longer should encourage QF development. The question of whether QFs should continue to be encouraged is a question for Congress. Rather, we are revising the PURPA Regulations by giving states the flexibility to require variable avoided cost energy rates in QF contracts and other LEOs in order to better comply with Congress's clear instruction in PURPA that the Commission may not require QF rates in excess of a purchasing utility's avoided costs.
- 257. By its very nature, the question of fixed versus variable energy rates is a question of how risk from increases in avoided energy costs over the life of a QF contract or other LEO should be allocated. Answering this question requires the Commission to allocate this risk either to (i) customers of electric utilities, or (ii) QFs and their investors and

contract terms in Wyoming shows a decrease of approximately 50% from 2011 through 2015 (from approximately \$60 per megawatt-hour to less than \$30 per megawatt-hour).").

⁴⁰⁴ This prohibition is described in Section IV.A.

lenders. But the Commission does not have unlimited discretion in how it resolves the question. Congress in PURPA section 210(b) provided guidance to the Commission in how it should perform that allocation – by mandating that the Commission cannot adopt a rule that provides for a rate that exceeds the incremental cost of alternative electric energy. 405

258. Opponents of variable avoided cost energy rates urge the Commission to continue placing this risk on the customers of electric utilities, as it did in the past, by retaining the option for QFs to fix their avoided cost energy rates in their contracts or LEOs notwithstanding record evidence, discussed elsewhere in this final rule, that fixed energy rates compared to actual avoided costs have not balanced out over time. But, after consideration of the record, the Commission has decided instead to allow states to reduce the risk to customers by giving states the flexibility to require variable avoided cost energy rates in QF contracts and LEOs. The Commission's determination ensures that the PURPA Regulations continue to be consistent with the statutory avoided cost rate cap in PURPA section 210(b), coupled with the directive in the Conference Report that customers of utilities not be required to subsidize QFs. 406

⁴⁰⁵ 16 U.S.C. 824a-3(b); see also 16 U.S.C. 824a-3(d); 18 CFR 292.101(b)(6), 292.304(b)(2).

⁴⁰⁶ Conf. Rep. at 98 ("The provisions of this section are not intended to require the rate payers of a utility to subsidize cogenerators or small power produc[er]s.") (emphasis added).

259. Third, there is no merit to the contention that the PURPA Conference Report expresses Congressional intent that QFs are entitled to long-term fixed energy rates. The statement in the Conference Report cited by NIPPC, CREA, REC, and OSEIA does not support this contention. The example provided in the PURPA Conference Report was of a utility owning a hydroelectric generating facility. Congress hypothesized that this utility might be able to avoid drawing down its reservoir as a result of a purchase from a QF, and thereby be able to generate electricity from the hydroelectric facility at a later date rather than running a more expensive fossil fuel unit at that later date. Congress stated that the avoided cost in its example should be based on the cost of the more expensive fossil unit whose operation was avoided at a later date rather than the avoided cost at the time the QF delivered its energy. 408

⁴⁰⁷ See NIPPC, CREA, REC, and OSEIA Comments at 27 (quoting Conf. Rep. at 98-99).

⁴⁰⁸ *Id.* at 98-99 ("In interpreting the term 'incremental cost of alternative energy,' the conferees expect that the Commission and the states may look beyond the cost of alternative sources which are instantaneously available to the utility. Rather, the Commission and states should look to the reliability of that power to the utility and the cost savings to the utility which may result at some later date by reason of supply to the utility at that time of power from the cogenerator or small power producer; for example an electric utility which owns a source of hydroelectric power and which is offered the sale of electric energy from a cogenerator or small power producer might, if measured over the short term, have a low incremental cost of alternative power because of its access to hydropower; however, it may be the case that by purchasing from the cogenerator or small power producer and saving hydropower for later use, the utility can avoided the use of expensive electric energy generated by fossil fired units during later months of its seasonal generation cycle. Thus, viewed over the longer period of time, the incremental cost of alternative electric energy might be substantially higher than that measured by the instantaneously available hydropower.").

260. While Congress recognized that the better measure of avoided cost in that scenario might be the cost of the alternative fossil fuel unit that would not be run at that later date, 409 nothing in the quoted section of the PURPA Conference Report suggests that Congress intended the Commission to require that all avoided cost energy rates be fixed at the outset for the life of a QF contract or other LEO. And nothing in the revision being implemented in this final rule would prohibit a state from calculating a QF's avoided cost energy rate for a QF contract or LEO in the manner suggested in the PURPA Conference Report or, indeed, in the manner the Commission has long allowed, if a state determined that such an approach best reflects the purchasing electric utility's avoided costs.

261. Fourth, the variable avoided cost energy rate provision adopted herein does not run afoul of the *Freehold Cogeneration* and *Smith Cogeneration* cases cited by Harvard Electricity Law. Those decisions, which overturned state avoided cost determinations allowing for changes in QF rates, were based on the provision in the original PURPA Regulations giving QFs the option to select contracts with long-term fixed avoided cost rates. Indeed, the *Smith Cogeneration* decision quotes at length from the explanation in

⁴⁰⁹ Under the approach adopted in this final rule, with the flexibility granted to states to adopt – but not a mandate directing states to adopt – variable avoided cost energy rates for QF contracts and other LEOs, states can adopt a pricing approach that best fits their circumstances, including adopting the pricing approach described by the Conference Report to address the circumstances described by the Conference Report.

⁴¹⁰ Harvard Electricity Law Comments at 29 (citing *Freehold Cogeneration*, 44 F.3d at 1193; *Smith Cogeneration*, 863 P.2d at 1227).

⁴¹¹ See Smith Cogeneration, 863 P.2d at 1241 (holding that allowing reconsideration of established avoided costs "makes it impossible to comply with PURPA and FERC regulations requiring established rate certainty for the duration of long term

Order No. 69 of the Commission's justification for its requiring in its regulations fixed avoided cost rates in QF contracts and LEOs. 412 Neither decision suggests that PURPA would prevent the Commission from revising its regulations to allow states the flexibility to require variable avoided cost energy rates, as the Commission is doing here. 262. Harvard Electricity Law also relies on Freehold Cogeneration and Smith Cogeneration to assert that the Commission is imposing "utility-type" regulation in violation of Congressional intent as expressed in the PURPA Conference Report. 413 However, those holdings do not address the changes the Commission is implementing here. By adopting a provision that allows states the option to require variable avoided cost energy rates, we are not mandating "utility-type" regulation. The PURPA Conference Report states that: "It is not the intention of the conferees that [QFs] become subject . . . to the type of examination that is traditionally given to electric utility rate applications to determine what is the just and reasonable rate that they should receive for their electric power."414 Our action today is consistent with that statement; we are not subjecting OFs to the same type of examination that is traditionally given to electric utility rate applications (e.g., cost-of-service rate regulation).

contracts for qualifying facilities that have incurred an obligation to deliver power") (emphasis added); Freehold Cogeneration, 44 F.3d at 1193 (relying on Smith Cogeneration analysis that "that PURPA and FERC regulations preempted the State Commission rule") (emphasis added).

⁴¹² Smith Cogeneration, 863 P.2d at 1240.

⁴¹³ Harvard Electricity Law Comments at 30.

⁴¹⁴ Conf. Rep. at 97.

- 263. Indeed, the regulation adopted today does not subject QF rates to any examination whatsoever of the costs incurred by QFs in producing and selling power. Rather, the variable avoided cost energy rate provision applicable to QF contracts and other LEOs that is adopted in this final rule sets QF rates based on the avoided costs of the purchasing utility. In no sense can this variable avoided cost energy rate provision be characterized as imposing utility-style regulation on the QFs themselves.
- 264. Finally, we agree with Harvard Electricity Law that state regulators may not change rates in existing QF contracts or other existing LEOs. He will be stated as a sanctioning the modification of existing fixed-rate QF contracts and LEOs.

d. Whether the Current Approach Has Resulted in Payments to QFs in Excess of Avoided Costs

i. Comments in Support of NOPR Proposal

265. Duke Energy states that its experience shows the Commission's original assumption that overestimations and underestimations will balance out over time was incorrect. From 2012 to 2017, Duke Energy states that it experienced explosive growth in solar QF contracts, and entered into at a time of rapidly declining natural gas prices—which drove down Duke Energy's avoided costs. Duke Energy states that, as of July 1,

⁴¹⁵ Harvard Electricity Law Comments at 23 (citing API, 461 U.S. at 414).

2019, it has almost 4,000 MW of QF power under contract and in commercial operation. Duke Energy claims the total estimated financial obligation on Duke Energy's retail and wholesale customers to pay for this QF power is approximately \$4.66 billion over the next approximately 15 years. If the contracts had been permitted to contain rates that mirrored the utilities' declining incremental costs either to generate that electric energy itself or to purchase alternative electric energy, i.e., Duke Energy's "actual current avoided costs," Duke Energy asserts that the contracts would be valued at \$2.4 billion. Duke Energy claims that, among the factors contributing to this overpayment of \$2.26 billion for the remainder of these QF contracts, the primary factor has been the requirement to offer fixed avoided cost energy rates during a period of rapidly declining energy prices. 416 266. EEI argues that relying on certain avoided cost methods, such as the costs of a proxy unit at a fixed point in time, may result, and has resulted, in the over estimation of future energy prices, leaving customers saddled with uneconomic PURPA contracts. According to EEI, the Commission's variable rate proposal will help ensure that the variable energy rate more accurately reflects the electric utility's actual avoided cost of energy so that rates for customers are just and reasonable. EEI describes this change as important for states, especially those in RTO/ISO markets, that elect to have the avoided cost rate set at LMP.

267. EEI also submitted with its comments a study performed by Concentric Energy Advisors showing that the avoided cost rates in the sample of solar and wind QF contracts

⁴¹⁶ Duke Energy Comments at 6.

they reviewed generally exceeded rates that are realized in competitive markets for solar and wind energy. According to that report, the total overpayment ranged between \$2.7 billion and \$3.9 billion. Several other commenters also cited the Concentric Energy Advisors report for the proposition that consumers nationwide have overpaid for QF contracts between 2009-2018. Berkshire Hathaway represents that PURPA contracts held by PacifiCorp will cost customers more than \$1.2 billion above projected market costs over the next 10 years. 418

268. Massachusetts DPU argues that a 10-year, fixed energy rate based on current New England wholesale energy market prices is highly likely to diverge from actual energy market prices over the ten-year contract term and could significantly harm ratepayers. Mr. Transeth represents that Consumers Energy's QF contracts are priced between 30 to 50% higher than their current market value. 420

269. APPA supports the variable energy rate proposal because the discrepancy between administratively set, locked-in, long-run avoided costs and actual market prices for the purchase of equivalent energy can be enormous, as demonstrated by the evidence submitted in the Technical Conference. According to APPA, were continued development of the IPP and renewable industries in jeopardy, the Commission might have

⁴¹⁷ Alliant Energy Comments at 7-8; Conservative Action Comments at 1; Duke Energy Comments at 5-7; Mr. Moore Comments at 2; Mr. Transeth Comments at 2.

⁴¹⁸ Berkshire Hathaway Comments at 5.

⁴¹⁹ Massachusetts DPU Comments at 7 (citing NOPR, 168 FERC ¶ 61,184 at 40).

⁴²⁰ Mr. Transeth Comments at 2.

grounds to conclude that enabling QFs to lock in energy payments over the course of their agreement is needed in order to bolster these resources, but the growth in the IPP and renewables industries in RTOs/ISOs indicate otherwise.⁴²¹

- 270. Commissioner O'Donnell asserts that the Montana Public Service Commission has addressed concerns about overpayments by shortening QF contract length from 25 years to 15, which has resulted in litigation currently pending before the Montana Supreme Court. Commissioner O'Donnell asserts that, because the energy component of an avoided cost rate reflects the price at which the purchasing electric utility could purchase power on the open market, there is no need to fix that fluid energy component for as long as 25 years.⁴²²
- 271. Competitive Enterprise asserts that long-term fixed price rates "serve only to reward certain financial investors at the expense of consumers, who are forced to pay inflated rates for electricity" and insists that utilities should only be required to purchase from resources that are needed and competitively priced.⁴²³

ii. Comments in Opposition to NOPR Proposal

272. Harvard Electricity Law observes that the Commission's examples of contract rates that exceed avoided costs calculated years prior illustrate the general proposition that "energy forecasts have a manifest record of failure." Harvard Electricity Law notes,

⁴²¹ APPA Comments at 16.

⁴²² Commissioner O'Donnell Comments at 2.

⁴²³ Competitive Enterprise Comments at 2.

⁴²⁴ Harvard Electricity Law Comments at 24 (citing Vaclav Smil, *Energy at the*

however, that in issuing Order No. 69, the Commission recognized that industry changes are difficult to forecast, but the Commission nonetheless concluded in Order No. 69 that the possibility that consumers would be harmed by high rates was outweighed by the Commission's duty to encourage QFs. Harvard Electricity Law further claims that the repeal of the fixed-price rule is not necessary to protect consumers from rates in future contracts. Harvard Electricity Law argues that the Commission's rules do not require an annual matching between avoided costs and rates, nor prevent states from setting declining avoided costs (which Order No. 69 explicitly condones). 427

273. Several commenters argue that the NOPR's assertion of artificially high avoided cost rates is unsupported or relies on flawed data and analysis. For example, NIPPC, CREA, REC, and OSEIA argue that the Commission relied on flawed data and analysis by using actual market prices that resulted after substantial QF penetration (which they assert has reduced power prices). 429

Crossroads: Global Perspectives and Uncertainties, Mass. Inst. Tech., 2003, at 121, 145-149).

⁴²⁵ Harvard Electricity Law Comments at 24.

⁴²⁶ *Id.* at 23.

⁴²⁷ *Id.* at 23-24 (citing Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,881).

⁴²⁸ NIPPC, CREA, REC, and OSEIA Comments at 30; Public Interest Organizations Comments at 39-40; Public Interest Organizations Comments at 43; Solar Energy Industries Comments at 34-36.

⁴²⁹ NIPPC, CREA, REC, and OSEIA Comments at 30-31.

- 274. Public Interest Organizations claim that the NOPR's evidence of overestimations is based on a selective choice of years reflecting general wholesale price declines, in which QF contracts were executed just before unforeseen natural gas price declines. Public Interest Organizations argue that these recent electricity price overestimations are not unique to QFs and can be explained by general declines in natural gas prices since the adoption of hydraulic fracturing and the 2007-2009 recession. 431
- 275. Public Interest Organizations dispute Alliant's asserted overestimation by claiming that Alliant likely would have procured non-QF energy at the same price and further point out that Alliant does not disclose the data upon which it relies. Public Interest Organizations assert that the Commission similarly erred in relying on EEI's description of overestimations of avoided costs in PacifiCorp's QF contracts because PacifiCorp only compares those prices to the Mid-C hub and does "not contain an analysis of the long-term balancing of its forecasted avoided energy rates with actual avoided energy costs." Public Interest Organizations contend that this comparison implies that PacifiCorp would have relied entirely on the Mid-C hub for all of its needs but for the QF contracts.

⁴³⁰ Public Interest Organizations Comments at 39-40.

⁴³¹ *Id.* at 47-50.

⁴³² *Id.* at 40-41.

 $^{^{433}}$ *Id.* at 41 (citing NOPR, 168 FERC ¶ 61,184 at P 64 n.101 (citing EEI Supplemental Comments, Docket No. AD16-16-000, attach. A at 3-4 (June 25, 2018))).

⁴³⁴ *Id*.

276. SC Solar Alliance contests Duke Energy's estimate of \$2.26 billion in overpayments for QF power. According to SC Solar Alliance, "an expert witness for South Carolina's Office of Regulatory Staff, which represents the interests of the using and consuming public in proceedings before the South Carolina Commission, recently testified that Duke's estimation of 'overpayments' to QFs was not reliable and that he 'wouldn't put a whole lot of weight in [Duke's estimate]." "435

277. GridLab attacks the conclusions of the Concentric Report, raising two principal arguments. First, according to GridLab, QF contracts are executed in non-competitive markets where utilities do not perform competitive solicitations. If QF avoided cost pricing is higher than prices set through competitive bidding, GridLab asserts that is because the utility's production costs are higher than competitive prices. Second, GridLab asserts that Concentric has compared two datasets that are different in several ways, most notably project size—with larger projects enjoying economies of scale that result in lower costs. According to GridLab, the difference in project size and its impact on cost is a significant factor that could account for the whole of the reported increase on price. 437

⁴³⁵ SC Solar Alliance Comments at 7 (quoting Public Service Commission of South Carolina, Docket No. 2019-185 & 186-E, Hearing Transcript Vol. 2 at 596, lines 6 – 21 (Horii Test.)) (attached as Appendix 1 to SC Solar Alliance Comments).

⁴³⁶ GridLab Comments at 1-2.

⁴³⁷ *Id.* at 4.

278. NIPPC, CREA, REC, and OSEIA argue that it was unreasonable for the Commission in the NOPR to assume that electricity price declines are permanent, given recent integrated resource plans (IRP) in the Northwest predicting significantly increased electricity demand and market prices at the Mid-C and Palo Verde hubs. NIPPC, CREA, REC, and OSEIA represent that electricity prices will climb significantly in the Northwest. NIPPC, CREA, REC, and OSEIA also assert that 100% renewable or non-emitting generation mandates and increased electrification of transportation could substantially increase electricity demand. NIPPC, CREA, REC, and OSEIA contend that fixed-price QF contracts protect consumers from the potential for future rising prices, market volatility, market risk, and project risk.

279. Resources for the Future reasons that "while fixed prices determined [five to ten] years ago would likely exceed current average market prices, that may not be true for fixed prices determined either more recently or in the future." Resources for the Future states that, contrary to the NOPR, there is no consensus that wind and solar generation costs will continue to decline because any capital cost declines will be relatively modest and will be offset by declining federal tax credits. Furthermore, Resources for the Future attributes these cost declines to the recent U.S. natural gas boom and points out that

⁴³⁸ NIPPC, CREA, REC, and OSEIA Comments at 33-34.

⁴³⁹ *Id.* at 34-36.

⁴⁴⁰ Resources for the Future Comments at 4.

⁴⁴¹ *Id.* at 5.

this decline is therefore not likely to continue.⁴⁴² sPower similarly argues that recent energy price declines will not necessarily continue, especially given expiring tax credits and additional tariffs.⁴⁴³

280. Several commenters assert that the risk of overpayments to QFs should be compared to the alternative generation sources used by the utility. 444 For example, ELCON claims that critics who assert that QFs are "locking-in" consumers to artificially high rates must acknowledge that utility procurement does exactly the same via the preapproval process, sometimes for even longer durations. ELCON argues that QFs can only benefit consumers by competing on a level playing field with comparable terms and conditions. 445 North Carolina Commission Staff similarly asserts that the risk of overpayment to QFs should be considered in the context of a utility's long-term commitment to build plants where "generation decisions are based upon uncertain forecasts that could result in ratepayers bearing the same type of forecast risk from utility plants as they do from QFs."446

⁴⁴² *Id.* at 4.

⁴⁴³ sPower Comments at 10-11.

⁴⁴⁴ ELCON Comments at 22; North Carolina Commission Staff Comments at 2-3; NIPPC, CREA, REC, and OSEIA Comments at 31; Public Interest Organizations Comments at 40,43; Solar Energy Industries Comments at 36-38.

⁴⁴⁵ ELCON Comments at 22.

⁴⁴⁶ North Carolina Commission Staff Comments at 2-3.

281. According to Solar Energy Industries, the risk from utility generation construction is allocated to ratepayers for the life of these assets regardless of ongoing changes in energy prices, while PURPA was designed to shift this risk away from ratepayers. Solar Energy Industries state that there is no evidence that ratepayers are harmed by long-term QF contracts any more than other long-term contracts or utility recovery of generation assets in their rate base. Solar Energy Industries state that, even though solar prices have declined over time, solar QFs should not be penalized for utility failures to update their avoided cost calculations to keep pace with such declines.⁴⁴⁷

282. The DC Commission states that, with respect to the fact that long-term contracts (e.g., 20 years) using fixed avoided energy costs could create stranded costs potentially due to inaccurate projections, the chance of creating stranded costs is substantially reduced when the most up-to-date data regarding avoided energy costs is used. The DC Commission states that, if the contract length is permitted to be flexible, the possibility of stranded costs would be significantly reduced for shorter term contracts. The DC Commission states that, without the worry of stranded costs, there is no need to eliminate the fixed price contract option for QFs. 449

⁴⁴⁷ Solar Energy Industries Comments at 36-38.

⁴⁴⁸ DC Commission Comments at 8.

⁴⁴⁹ *Id*.

iii. Commission Determination

As explained above, the NOPR proposal to give states the flexibility to require variable energy pricing in OF contracts and other LEOs, instead of providing OFs the right to elect fixed energy prices, was based on the Commission's concern that, at least in some circumstances, long-term fixed avoided cost energy rates have been well above the purchasing utility's avoided costs for energy—a result prohibited by PURPA section 210(b). And the record evidence demonstrates just that, i.e., that QF contract and LEO prices for energy can exceed and have exceeded avoided costs for energy without any subsequent balancing out. In addition to the examples presented in the record of the Technical Conference that were cited in the NOPR, commenters have provided additional examples of such overpayments, as described above. 450 Such evidence has persuaded us that it is necessary to give states the flexibility to address QF contract and LEO rates for energy that exceed avoided costs for energy, while at the same time still allowing states the flexibility to continue requiring long-term fixed avoided cost energy rates in QF contracts and other LEOs when such treatment is appropriate.

284. As Harvard Electricity Law concedes, the examples of QF contract rates that exceed avoided costs that are in the record illustrate the general proposition that "energy forecasts have a manifest record of failure."

⁴⁵⁰ See Duke Comments at 6; Idaho Power Comments at 10-11; Portland General Comments at 5; NOPR, 168 FERC ¶ 61,184 at P 64 n.101.

⁴⁵¹ Harvard Electricity Law Comments at 24 (citing Vaclav Smil, *Energy at the Crossroads: Global Perspectives and Uncertainties*, Mass. Inst. Tech., 2003, at 121, 145-

including evidence in the record that the failure has been at the expense of consumers, that drives us to make the change adopted in the final rule. 452

285. While some commenters challenge the idea that avoided cost energy rates in QF contracts and other LEOs have exceeded actual avoided costs, their arguments largely either concede that overestimations have occurred while arguing that such overestimations impacted purchasing electric utilities just as much as QFs, or attempt to argue that such overestimations were temporary or unusual. For these reasons, they assert that the Commission should not conclude that historical overestimations of avoided cost require a change to the current PURPA Regulations requiring states to allow QFs to fix their avoided costs energy rates for the term of their contracts. These arguments do not cause us to reconsider our determination, for the reasons explained below.

286. First, Harvard Electricity Law's citation to the Commission's original determination in Order No. 69 that it was not necessary to provide for variable avoided cost energy rates carries little weight. The purpose of the NOPR was to reconsider the Commission's determinations made in Order No. 69 in light of changes in circumstances and additional evidence that was not available to the Commission when it issued Order No. 69 in 1980. The record evidence cited above demonstrates that, contrary to the Commission's finding in 1980, overestimations and underestimations of future avoided

^{149)..}

⁴⁵² See, e.g., supra P 254 & note 403.

⁴⁵³ *Id.* at 23-24 (citing Order No. 69, FERC Stats. & Regs. ¶ 30,128, at 30,881).

costs may not even out. 454 Consequently, the Commission's determination in 1980 does not preclude the Commission from changing the rule adopted at that time.

287. We agree with Public Interest Organizations that the recent electricity price overestimations were not unique to QFs and can be explained by general declines in natural gas prices since the adoption of hydraulic fracturing and the 2007-2009 recession. But that is precisely why the estimates of avoided costs reflected in the QF contracts and LEOs were incorrect and why the resulting fixed avoided cost energy rates reflected in such QF contracts and other LEOs resulted in QF rates well above utility avoided costs in violation of PURPA section 210(b); the precipitous decline in natural gas prices caused a corresponding reduction in utilities' energy costs, and thus in their energy avoided costs but this decline was not reflected in the QFs' fixed contract rates that remained at their previous levels.

288. Similarly, arguments from commenters that electric utilities also based resource acquisitions on incorrect forecasts of natural gas prices⁴⁵⁶ ignore a key distinction between utility rates and fixed QF rates. Electric utilities may have relied on incorrect natural gas price forecasts to justify the timing and type of their resource acquisitions, as commenters

⁴⁵⁴ See Duke Comments at 6; Idaho Power Comments at 10-11; Portland General Comments at 5; NOPR, 168 FERC ¶ 61,184 at 64 n.101.

⁴⁵⁵ Public Interest Organizations Comments at 47-50.

⁴⁵⁶ ELCON Comments at 22; North Carolina Commission Staff Comments at 2-3; NIPPC, CREA, REC, and OSEIA Comments at 31; Public Interest Organizations Comments at 40,43; Solar Energy Industries Comments at 36-38.

assert. But once an electric utility resource decision was made, their cost-based rate regimes typically obligated the electric utility eventually to pass through to customers any energy cost savings realized as a result of declining natural gas and other fuel prices, as well as any energy cost savings due to lower purchased power rates resulting from the decline in natural gas prices. By contrast, once QF avoided cost energy rates were fixed based on now-incorrect (and now-high) natural gas price forecasts, those energy rates remained fixed for the term of the QFs' contracts and LEOs. Therefore, unlike fixed avoided cost energy rates in QF contracts and LEOs, cost-based electric utility energy rates declined as the cost of natural gas and other fuels and purchased power declined. We also disagree with Public Interest Organizations' assertions that it was improper to have used competitive market hub prices to determine whether fixed QF contract and LEO prices resulted in overpayments as compared to electric utilities' actual avoided costs. 457 We recognize that the competitive market hub prices used in the comparisons may not have precisely reflected the avoided energy costs of all electric utilities located in the same region as the competitive market hub. However, as explained above in the discussion of the use of Market Hub Prices to determine avoided energy costs, competitive market prices in general should reflect the marginal avoided energy costs of utilities with access to such markets. Certainly, those markets generally reflect the marginal cost of energy in the region.⁴⁵⁸ The magnitude of the differences between the market hub prices

⁴⁵⁷ Public Interest Organizations Comments at 40-41.

⁴⁵⁸ A review of recent Mid-C Hub daily spot prices (from Intercontinental Exchange (ICE) https://www.eia.gov/electricity/wholesale/, indicates that they reflect the

and the QF contract and LEO prices provides solid evidence that the QF contract and LEO prices used in the comparison were well above actual avoided energy costs at the time the energy was delivered by the QFs, even if the exact magnitude is unclear.

290. We acknowledge that energy prices may increase in the future, as several commenters point out. 459 However, as noted by Harvard Electricity Law, "energy forecasts have a manifest record of failure." 460 Moreover, the fact that energy prices may increase in the future does not eliminate the risk that fixed avoided cost energy rates could still be above actual avoided costs. That is, if the actual increase in energy prices is still lower than the forecasted increase that would form the basis of the fixed avoided cost energy rate, then the fixed avoided cost energy rate will be above actual avoided energy costs. Giving states the flexibility to require variable avoided cost energy rates in QF contracts and in other LEOs will allow states to better ensure that avoided cost energy payments made to QFs will more accurately reflect the purchasing utility's avoided costs

marginal cost of energy in that area since they are usually the result of a significant number of trades (averaging 54 per day), counterparties (averaging 16 per day), and trading volume (averaging 26,714 MWh/day), which usually exceed those of the NP-15 trading hub, an active Western trading hub in Northern California in the CAISO footprint (averaging 6 trades per day, 4 counterparties per day, and 2,756/MWh per day). The prices for Mid-C ranged between an average of approximately \$16/MWh high price and \$13/MWh low price during the recent spring (Mar 19-Jun 20, 2020). During this period the index was reported for 65 trading days for Mid-C and 9 trading days for NP-15.

⁴⁵⁹ NIPPC, CREA, REC, and OSEIA Comments at 33-36; Resources for the Future Comments at 4; sPower comments at 10-11.

⁴⁶⁰ Harvard Electricity Law Comments at 24 (citing Vaclav Smil, *Energy at the Crossroads: Global Perspectives and Uncertainties*, Mass. Inst. Tech., 2003, at 121, 145-149).

energy prices do in fact increase, variable avoided cost energy pricing would protect and even benefit the QF itself, as it would not be locked into a fixed energy rate contract or LEO that would be below the purchasing electric utility's avoided energy cost. 291. Although many commenters agreed that fixed QF energy rates were higher than actual avoided energy costs in at least some instances, challenges were raised against both Duke Energy's estimate that its fixed OF contract rates were \$2.6 billion above market costs, and the Concentric Report's comparison of QF fixed rates for wind and solar facilities with the cost of wind and solar projects with competitive, non-PURPA contracts. 292. However, the expert testimony cited by the SC Solar Alliance, that the witness "wouldn't put a whole lot of weight in [Duke's estimate],"461 does not address Duke's calculation of past overpayments. Rather, the witness was answering a question regarding the potential for overpayments "[f]or going forward solar," i.e., future overpayments as a result of the new fixed avoided cost rates being considered by the South Carolina Commission that were the subject of the expert witness' testimony. 462 The same witness

regardless of whether energy prices are increasing or declining. We also note that, if

acknowledged the past overpayments made by Duke Energy, which he attributed to

⁴⁶¹ SC Solar Alliance Comments at 7 (quoting, Public Service Commission of South Carolina, Docket No. 2019-185 & 186-E, Hearing Transcript Vol. 2, Tr. at 596: 6–21 (Horii Test)) (attached as Appendix 1 to SC Solar Alliance Comments).

⁴⁶² Public Service Commission of South Carolina, Docket No. 2019-185 & 186-E, Hearing Transcript Vol. 2, Tr. 596: 3-4 (Horii Test)) (attached as Appendix 1 to SC Solar Alliance Comments).

"drops in natural gas prices that no one could've foreseen." It is these overpayments due to unforeseen declines in natural gas prices that form an important basis for the Commission's determination in this final rule to now give states the flexibility to require variable avoided cost energy rates in QF contracts and LEOs.

293. With respect to the criticisms of the Concentric Report, we emphasize that we have not relied on that report to support the variable energy avoided cost provision adopted in the final rule. It is not clear that the lower cost of the competitively priced renewable resources identified in the report represents the avoided costs of the purchasing utilities that entered into the QF contracts at fixed rates for renewable resources under PURPA. Therefore, it is not clear that the difference in costs identified by Concentric can be ascribed to the fixed rates in the QF contracts or rather to the fact that the avoided cost rates in the QF contracts were based on more expensive non-renewable capacity that was avoided by the purchasing utilities.

e. Whether the Proposed Change Would Violate the Statutory Requirement that the PURPA Regulations Encourage QFs

i. Comments

294. Several commenters argue that the NOPR's variable rate proposal is inconsistent with PURPA's mandate that the PURPA Regulations "encourage" the development of QFs. 464 Southeast Public Interest Organizations state that removing QFs' right to a fixed

⁴⁶³ *Id.* at 593:21-22.

⁴⁶⁴ Allco Comments at 9; Con Edison at 3, 4; Harvard Electricity Law Comments at 1; North American-Central Comments at 4-6; Southeast Public Interest Organizations at

energy rate would flout Congressional intent that PURPA encourage QF development because fixed rates are necessary to attract QF financing. Harvard Electricity Law states that Congress's mandate to encourage QFs is not contingent on industry conditions and does not expire. Harvard Electricity Law states that Congress's mandate to encourage QFs is not contingent on industry conditions.

ii. Commission Determination

295. As explained above in Section IV.A.1, the statutory requirement that the Commission's PURPA Regulations encourage QFs remains, but it is bounded by the statutory provision in PURPA section 210(b) that QF rates may not exceed a purchasing utility's avoided costs. Further, as explained above, we have determined, based on the record evidence, that it is not necessarily the case that overestimations and underestimations of avoided energy costs will balance out. Consequently, a fixed energy rate in a QF contract or LEO potentially could violate the statutory avoided cost cap on QF rates.

296. The Commission's PURPA Regulations continue to encourage the development of QFs by, among other things, allowing a state to vary the rate paid to the QF over time but in a way that satisfies the rate cap established in PURPA section 210(b). In this way, the QF can obtain a higher rate when the utility's avoided costs increase, and ratepayers are not paying more than the utility's avoided costs when prices decrease. Furthermore, as

^{9-11.}

⁴⁶⁵ Southeast Public Interest Organizations Comments at 9-10.

⁴⁶⁶ Harvard Electricity Law Comments at 1.

discussed above, allowing the use of variable energy rates may promote longer contract terms, which would help encourage and support QFs. 467 It therefore is consistent with PURPA section 210(b), as well as the obligation imposed by PURPA section 210(a) to revise the Commission's PURPA Regulations "from time to time," to provide the states the flexibility to require that QF contracts and other LEOs implement variable avoided cost energy rates in order to prevent payments to QFs in excess of the purchasing electric utility's avoided energy costs. PURPA section 210(b) prohibits the Commission from requiring QF rates above avoided costs even if, according to some commenters, a fixed avoided cost energy rate would provide greater encouragement to QFs than a variable avoided cost energy rate.

f. <u>Discrimination</u>

i. Comments in Support of NOPR Proposal

297. Alliant Energy observes that utility-owned generation and traditional power purchase agreements (PPAs) are subject to a demonstration of need and that traditional PPAs are subject to re-evaluation during their term to determine whether they continue to be cost-competitive and in the best interests of customers. Alliant Energy asserts that, by contrast, QFs are not required to demonstrate that their projects are needed and that, once a contract is executed, it is not subject to re-evaluation.⁴⁶⁸

⁴⁶⁷ See infra P 349.

⁴⁶⁸ Alliant Energy Comments at 6-7.

ii. Comments in Opposition to NOPR Proposal

298. Several commenters assert that the NOPR's variable avoided cost energy rate proposal is discriminatory. For example, EPSA argues that PURPA requires the Commission to implement regulations that, for rates for electric utility purchases from QFs, "shall not discriminate against qualifying cogenerators or qualifying small power producers." EPSA describes this standard as more restrictive than the FPA's prohibition against "unduly discriminatory" rates. According to EPSA, the fact that long-term QF contracts are substantially above prevailing market prices due to declining wholesale prices over the long-term does not justify the variable rate proposal because electric utility-owned generation is similarly based on imperfect long-term forecasts of energy prices that oftentimes prove to be too high. EPSA therefore argues that the NOPR variable rate proposal should not be adopted unless utility-owned assets are also subject to a similar cost recovery regime. The NOPR variable cost recovery regime.

299. sPower describes the NOPR proposal to allow variable rates as providing a significant advantage to electric utilities over QFs, given that electric utilities themselves, according to sPower, have not had to lower rates to consumers as energy prices have declined.⁴⁷¹ ELCON asserts that pushing more market risk to OFs while utility assets

⁴⁶⁹ ELCON Comments at 21-22; SC Solar Alliance Comments at 5-10; sPower Comments at 13; *see also* ELCON Comments at 22; North Carolina Commission Staff Comments at 2-3; NIPPC, CREA, REC, and OSEIA Comments at 31; Public Interest Organizations Comments at 40, 43; Solar Energy Industries Comments at 36-38.

⁴⁷⁰ EPSA Comments at 8-9.

⁴⁷¹ sPower Comments at 13.

remain insulated from markets creates an investment risk asymmetry. ELCON claims this puts QFs at a competitive disadvantage and shifts the consumer burden to more utility builds, which have generally been higher cost than merchant builds.⁴⁷²

- 300. SC Solar Alliance states that utilities often rely on fuel price forecasts over time to justify rate base approval for generation assets that might run beyond price forecasts. SC Solar Alliance argues that allowing utilities this right, but not QFs, holds QFs to a much higher standard than utilities and therefore is discriminatory.⁴⁷³
- 301. Commissioner Slaughter argues that, by removing the fixed, long-term contract option for independent power producers, the NOPR threatens to hamper the competitiveness of renewable-based energy firms challenging vertically integrated utilities in many localities across the country.⁴⁷⁴

iii. Commission Determination

302. The discrimination claims are based on the incorrect assumption that electric utilities have not been required to lower their energy rates as prices have declined. To the contrary, as explained above, utilities typically charge their customers cost-based rates, and as their fuel and purchased power costs have declined, they typically have been required to provide corresponding reductions in the energy portion of their rates to their

⁴⁷² ELCON Comments at 21-22.

⁴⁷³ SC Solar Alliance Comments at 5-10.

⁴⁷⁴ Commissioner Slaughter Comments at 4.

customers.⁴⁷⁵ Requiring QF avoided cost energy rates to likewise change as purchasing electric utilities' avoided energy costs change does not create a discriminatory difference, but rather puts QF rates on par with utility rates.

303. Further, we are not changing the requirement that QF avoided cost energy rates be set at the purchasing utility's full avoided energy costs. As the Supreme Court held in *API*, "the full-avoided-cost rule plainly satisfies the nondiscrimination requirement." Rather, we are allowing the states the option to now choose to require QF avoided cost energy rates that vary with the purchasing utility's avoided costs of energy, rather than QF avoided cost rates that are fixed for the life of the QF's contract or LEO, to ensure the rates comply with PURPA.

g. <u>Effect of Variable Energy Rates on Financing</u>

i. Comments in Support of the NOPR Proposal

304. Several commenters state that fixed energy payments are not necessary for QFs to obtain financing.⁴⁷⁷ Alliant states that it is on track to be the third largest utility owner-operator of wind facilities in the United States, with 1.9 GW on its system and in addition is increasing the pace of solar resource development in its Wisconsin territory. Alliant

⁴⁷⁵ See supra PP 40, 122, 288.

⁴⁷⁶ API, 461 U.S. at 413.

⁴⁷⁷ APPA Comments at 16-17; Indiana Commission Comments at 6.

states it therefore does not believe that the proposed change will slow renewable deployment and adoption. 478

305. Several commenters assert that PURPA's must-purchase requirement itself should necessarily afford QF developers a degree of certainty and enables developers to attract capital at advantageous terms. The Idaho Commission states that, even if modified as proposed, QF contract terms would remain superior to competitively bid renewable projects where the energy is not "must take" and curtailment and other reliability parameters are imposed. Also

306. Finadvice and APPA argue that maintaining a fixed capacity rate, as proposed by the Commission, will help attract capital and ameliorate any negative effect that the variable energy rate proposal may impose. Ohio Commission Energy Advocate argues, as evidence that QFs can still flourish under a variable energy rate, that the PJM market has successfully attracted new supplies and ensured resource adequacy through fixed capacity and variable energy rates.

307. The Idaho Commission states that variable energy prices protect the ratepayer while allowing the QF to ensure a stream of revenue through a longer-term contract. The

⁴⁷⁸ Alliant Energy Comments at 6.

⁴⁷⁹ APPA Comments at 16-17; Finadvice Comments at 2; Idaho Commission Comments at 4; Commissioner O'Donnell Comments at 3.

⁴⁸⁰ Idaho Commission Comments at 4.

⁴⁸¹ APPA Comments at 16-17; Finadvice Comments at 2.

⁴⁸² Ohio Commission Energy Advocate Comments at 3-4.

Idaho Commission affirms that the rapid growth of non-QF renewable projects and their ability to obtain financing should quell any concerns about a QF's ability to obtain financing as long as PURPA's "must take" provision remains. Commissioner O'Donnell asserts that QFs should bear some market risk as energy prices rise and fall in a way that balances risks to all parties.

308. EEI argues that PURPA does not require the Commission or the states to implement regulations that guarantee a QF's financeability. EEI represents that Congress intended QFs to be treated similarly to merchant generation and simply required QFs to have non-discriminatory access. According to EEI, because QFs are not subjected to the oversight or regulatory responsibilities applicable to electric utilities, it was not expected or intended that QFs be treated the same as electric utilities. Similarly, Duke argues that the central design criteria for PURPA rates and terms should be customer indifference, just and reasonableness, and non-discrimination. Duke Energy states that a design that requires QF financeability as a criterion will inevitably lead to a QF boom and customer harm. Buke Energy further asserts that several factors affect financeability

⁴⁸³ Idaho Commission Comments at 4.

⁴⁸⁴ Commissioner O'Donnell Comments at 3.

⁴⁸⁵ EEI Comments at 35.

⁴⁸⁶ Duke Energy Comments at 17-18.

and that, therefore, claims by QFs that they require fixed energy payments for financing purposes should be rejected. 487

309. EEI claims QFs that require third-party financing will still be able to obtain financing if the Commission adopts the proposals in the NOPR, because they are additional options, in addition to those currently being used by states, that will be available to determine avoided costs. EEI maintains that a QF developer will be able to obtain financing under any of the options, provided it can build a cost-efficient plant that can profit at an avoided cost rate. EEI claims that independent power producers lacking the certainty of the mandatory purchase obligation are building most renewable generation today because merchant power plants may be developed and financed using a variety of hedging and risk management tools, such as commodity hedges, that lock in cash flows and facilitate construction at the outset. 489

- 310. APPA states that much of the renewable development that has occurred over the past 20 years has taken place within RTO/ISO footprints and therefore is largely unaided by PURPA obligations.⁴⁹⁰
- 311. Duke Energy states that concern about the potential for fixed avoided cost contract rates exceeding actual avoided costs at the time of delivery have led both North Carolina

⁴⁸⁷ *Id.* at 13.

⁴⁸⁸ EEI Comments at 35-36.

⁴⁸⁹ *Id.* at 36.

⁴⁹⁰ APPA Comments at 16-17.

and South Carolina to enact laws placing limits on the length of QF contracts. 491 The Idaho Commission states that there is no evidence that variable energy prices would be fatal to QF development. 492 The Idaho Commission states that it reduced contract length on large projects to two years because it did not interpret the Commission's current rules to allow for a variable energy rate inside a long-term contract. The Idaho Commission states that, because its experience dictated that the longer the contract term, the more inflated the avoided cost rate, the Idaho Commission set parameters to balance OF interests against utility ratepayer interests. The Idaho Commission states that an energy rate established at the time of contract formation that provides for "revisions to the energy" rate at regular intervals, consistent with, for example, a purchasing electric utility's [integrated resource planning (IRP)] to reflect updated avoided cost calculations" would allow states to consider longer term contracts without putting ratepayers at risk. 493 NorthWestern represents that the Montana Commission has lowered the length of QF contracts from 25 to 15 years in response to the current requirement that OFs are entitled to fixed avoided cost rates for energy in their contracts and a concern that rates calculated at the time a contract is signed are likely to change over the life of that contract. 494

⁴⁹¹ Duke Energy Comments at 9; LG&E/KU Comments at 4.

⁴⁹² Idaho Commission Comments at 4.

⁴⁹³ *Id.* (citing NOPR, 168 FERC ¶ 61,184 at P 5 n.5).

⁴⁹⁴ NorthWestern Comments at 6-7.

ii. Comments in Opposition to the NOPR Proposal

312. Many commenters assert that the NOPR's variable energy rate proposal will result in QFs being unable to obtain financing. Several commenters also assert that it is discriminatory that utilities and non-QF generators can rate-base long-term investments and recover actual operating costs, while the NOPR's proposed rules would deprive QFs of a reasonable ability to forecast their cost recovery with no guarantees. Several commenters assert that the NOPR lacks evidence on the record to conclude that the variable rate proposal would not affect the ability of QFs to obtain financing. NIPPC, CREA, REC, and OSEIA argue that the NOPR contained no record evidence

demonstrating how this proposal would continue to encourage OFs in a non-

discriminatory manner, ⁴⁹⁸ and lacks evidence on how QF generation can be financed

Allco Comments at 9; AllEarth Comments at 2; Biogas Comments at 2; BluEarth Comments at 2; Biological Diversity Comments at 8; Commissioner Slaughter Comments at 4; Con Edison Comments at 3, 4; Covanta Comments at 7-8; DC Commission Comments at 6-8; Distributed Sun Comments at 1; EPSA Comments at 2; Energy Recovery at 4; Harvard Electricity Law Comments at 5; Massachusetts AG Comments at 8-9; New England Hydro Comments at 8; NIPPC, CREA, REC, and OSEIA Comments at 37-38; North Carolina DOJ Comments at 3, 6; North American-Central Comments at 4-6; Public Interest Organizations Comments at 6-7; Resources for the Future Comments at 6-7. SC Solar Alliance Comments at 5-7; Southeast Public Interest Organizations Comments at 9-11; State Entities Comments at 2-3; Two Dot Wind Comments at 11-13.

⁴⁹⁶ Allco Comments at 9; Commissioner Slaughter at 4; Harvard Electricity Law Comments at 5; NIPPC, CREA, REC, and OSEIA Comments at 36-37; Public Interest Organizations Comments at 6-7; Solar Energy Industries at 29-30.

⁴⁹⁷ NIPPC, CREA, REC, and OSEIA Comments at 29, 46; Harvard Electricity Law Comments at 22, 25-27; Public Interest Organizations Comments at 6-7, 33-35.

⁴⁹⁸ NIPPC, CREA, REC, and OSEIA Comments at 29.

without a fixed energy rate. 499 Similarly, Harvard Electricity Law asserts that repealing the fixed-price PPA requirement is premised on irrelevant data and ignores the record, and disagrees with the Commission's demonstration of information on non-QF capacity to show that QF development no longer relies on contracts with fixed energy rates. 500 314. Public Interest Organizations assert that testimony from Southern Company, American Forest and Paper Association, and Solar Energy Industries, upon which the NOPR relies, states that non-QF renewable PPAs generally entail fixed energy rates rather than variable energy rates. 501 In particular, Public Interest Organizations state that testimony from Solar Energy Industries, refers to reliance on fixed rates for energy and/or capacity without describing them as alternatives but rather "an acknowledgement that a [power purchase agreement] may provide fixed capacity in addition to fixed energy revenue, not a suggestion that a QF can be developed without a predictable energy revenue stream." 502

315. Allco describes programs in California, Massachusetts, Connecticut, and Vermont that offer standard QF contract programs with variable energy rates, none of which,

⁴⁹⁹ *Id.* at 46-48.

 $^{^{500}}$ Harvard Electricity Law Comments at 22, 25 (citing NOPR, 168 FERC \P 61,184 at PP 69-70, 76).

⁵⁰¹ Public Interest Organizations Comments at 33-35 (citing NOPR, 168 FERC ¶ 61,184, at P 70 n.114 (citing Tech. Conference, Docket No. AD16-16-000, Tr. at 153, 200 (filed June 30, 2016))).

 $^{^{502}}$ *Id.* at 35 (citing NOPR, 168 FERC ¶ 61,184, at P 70 n.115 (citing Solar Energy Industries Comments, Docket No. AD16-16-000, at 3 (filed June 30, 2016))).

according to Allco, have led to the construction of solar projects. ⁵⁰³ Allco claims that these programs prove that, without the ability to obtain a fixed long-term forecasted rate, QF solar energy development will not exist. ⁵⁰⁴ Southeast Public Interest Organizations assert that Southeastern states with fixed QF energy rates have seen vigorous QF development, while Southeastern states with variable energy rates have seen virtually no QF development, undermining the Commission's assertion that QFs can be financed without fixed energy rates. ⁵⁰⁵

316. Covanta and Energy Recovery state that the NOPR's variable rate proposal would have an especially negative effect on Waste to Energy facilities. ⁵⁰⁶ Covanta states that, because Waste to Energy depends on finite local tax resources, a loss in energy revenue due to price variability cannot be easily replaced. ⁵⁰⁷ Covanta states that, without adequate QF pricing and multi-year contracts (and consistent, predictable pricing throughout the life of the contract), local governments may be forced to close their Waste to Energy facilities prematurely, to minimize loss and stranding that investment. ⁵⁰⁸ Energy Recovery states

⁵⁰³ Allco Comments at 10.

⁵⁰⁴ *Id.* at 9-11.

⁵⁰⁵ Southeast Public Interest Organizations Comments at 9-11, 15-16.

⁵⁰⁶ Covanta Comments at 7-8; Energy Recovery Comments at 1, 4.

⁵⁰⁷ Covanta Comments at 7-8.

⁵⁰⁸ *Id.* at 8.

that the inability to secure suitable rates through a long-term contract has closed seventeen Waste to Energy facilities in the last fifteen years. ⁵⁰⁹

NIPPC, CREA, REC, and OSEIA state that the NOPR's anecdotal reliance on tax incentives to encourage QF development is irrelevant because these incentives are declining or disappearing, thereby requiring OFs to rely even more on energy rates.⁵¹⁰ NIPPC, CREA, REC, and OSEIA predict that the NOPR's proposed rules would make QF development riskier and would thereby slow the development of new technologies such as energy storage, hydrogen fuels, and other advanced renewable energy technologies.⁵¹¹ Solar Energy Industries states that financing for QFs differs from financing for fossil fuel generators because "much of the cost of installation is incurred up-front, but once installed, the generation has little, if any, variable cost."512 Likewise, Harvard Electricity Law observes that wind and solar OFs, for example, have higher capital costs, lower operating costs, and provide energy intermittently, and therefore have characteristics that may present different financing challenges as compared to non-OF natural gas fired capacity. 513 Similarly, Public Interest Organizations argue that, unlike independent power producer natural gas generators with fixed capacity payments and

⁵⁰⁹ Energy Recovery Comments at 3.

⁵¹⁰ NIPPC, CREA, REC, and OSEIA Comments at 40-41.

⁵¹¹ *Id.* at 41-42.

⁵¹² Solar Energy Industries Comments at 30.

⁵¹³ Harvard Electricity Law Comments at 26.

variable energy costs, renewable QFs rely on fixed energy payments to cover their capital costs given their own nominal variable energy costs.⁵¹⁴

319. NIPPC, CREA, REC, and OSEIA state that the financeability of generation with fixed capacity prices and variable energy prices inside RTOs/ISOs is irrelevant to regions that lie outside of RTOs/ISOs. ⁵¹⁵ NIPPC, CREA, REC, and OSEIA criticize the NOPR's reliance on an independent power producer natural gas turbine's financeability outside the RTO/ISO context as irrelevant to QFs because these natural gas turbines receive fixed capacity payments and variable energy payments to account for the fluctuating price of fuel; whereas a QF would need a sufficient fixed capacity payment to support financing and an energy rate that removes market risk. ⁵¹⁶

320. NIPPC, CREA, REC, and OSEIA state that the NOPR's reference to hedging instruments to reduce risks from fluctuating prices is irrelevant. NIPPC, CREA, REC, and OSEIA state that hedging makes projects less financeable because it increases transaction and compliance costs for small power producer QFs that cannot afford large legal divisions and trading floors to employ such hedges. S18

⁵¹⁴ Public Interest Organizations Comments at 33-34.

⁵¹⁵ NIPPC, CREA, REC, and OSEIA Comments at 42-43.

⁵¹⁶ *Id*

⁵¹⁷ *Id.* at 44-45 (citing NOPR, 168 FERC ¶ 61,184 at P 72 & n.117).

⁵¹⁸ *Id.* at 45-46.

- 321. Resources for the Future states that wind projects have used bank hedges, synthetic PPAs, and proxy revenue swaps.⁵¹⁹ Resources for the Future claims, however, that these products would be inaccessible to most wind QFs if fixed energy payments are eliminated. Resources for the Future argues that solar QFs would have even less access to such hedging given their smaller size and high transaction costs. Resources for the Future states that QFs under 5 MW in RTO/ISOs and QFs outside of RTO/ISOs thus would be unable to obtain financing.⁵²⁰
- 322. Solar Energy Industries states that QFs in RTO/ISO markets without a fixed energy rate would require a hedging instrument to finance their projects. Solar Energy Industries further states that QFs outside RTO/ISO markets without a fixed energy rate would be unable to finance their projects because they would have no access to such hedging mechanisms. Solar Energy Industries states that the NOPR failed to consider which markets offer financial products, whether these financial products are available to QFs outside RTOs/ISOs, and whether these products will be sufficient to provide financing to OFs. Solar Energy Industries states that the NOPR failed to consider which markets offer financial products, whether these products will be sufficient to provide financing to OFs. Solar Energy Industries states that the NOPR failed to consider which markets offer financial products, whether these products will be sufficient to provide financing to OFs. Solar Energy Industries states that the NOPR failed to consider which markets offer financial products, whether these products will be sufficient to provide financing to OFs. Solar Energy Industries states that the NOPR failed to consider which markets offer financial products, whether these products will be sufficient to provide financing to OFs.
- 323. Solar Energy Industries states that financing for QFs differs from financing for fossil fuel generators because much of the cost of installation is incurred up-front, with

⁵¹⁹ Resources for the Future Comments at 6.

⁵²⁰ *Id.* at 6-7.

⁵²¹ Solar Energy Industries Comments at 30.

⁵²² *Id.* at 31.

virtually no variable costs. Solar Energy Industries states that, because of this difference, financiers "examine the QF's projected revenue stream to ensure that the revenue stream is sufficient to recover the installed costs plus a competitive return." Solar Energy Industries reasons that QFs must therefore know in advance their facility's energy and capacity values and obtain a legally enforceable contract that fits into common underwriting models. 524

- 324. North Carolina DOJ asserts that allowing avoided cost energy prices to fluctuate could eliminate fixed-price power sales contracts, thereby making compensation to QFs more volatile and discouraging renewable energy financing.⁵²⁵
- 325. Distributed Sun agrees with Commissioner Glick's dissent on the NOPR that revoking the fixed energy price requirement would halt the construction of most distributed energy resources. Solar Energy Industries states that it is not aware of a meaningful number of QFs that have been constructed using capacity rates alone or capacity rates with variable energy rates. Solar Energy Industries states that it is not aware of a meaningful number of QFs that have been constructed using capacity rates alone or
- 326. Mr. Mattson argues that a variable rate or a rate based on a projected stream of revenues during the contract are not long-term contracts. Mr. Mattson argues that this

⁵²³ *Id*.

⁵²⁴ *Id*.

⁵²⁵ North Carolina DOJ Comments at 3.

⁵²⁶ Distributed Sun Comments at 3.

⁵²⁷ Solar Energy Industries Comments at 28.

violates legislative intent and precedent and is not viable, suggesting that PURPA requires avoided cost data to be kept by a utility for public inspection.⁵²⁸

327. Western Resource Councils represents that PURPA, in the rural Northern Plains and Rocky Mountain West, is the only vehicle for small businesses to obtain project financing and that variable rates undermine the certainty of QFs obtaining financing. 529 328. Public Interest Organizations assert that the NOPR has no basis to speculate that the Idaho Commission shortened contract lengths to two years because of the fixed rate requirement or that it would provide longer contracts if it could require variable energy rates. 530 According to Public Interest Organizations, the fact that no solar and wind QFs have been developed since the Idaho Commission set a two year contract length, even while they are currently entitled to fixed rates, shows that allowing variable rates will further discourage wind and solar QF development. 531

329. sPower argues that, even with long-term contracts, QFs will not be viable without fixed energy rates and explains that, if the Commission seeks to encourage states to offer longer contract terms, it should just require longer terms.⁵³²

⁵²⁸ Mr. Mattson Comments at 26.

⁵²⁹ Western Resource Councils Comments at 2.

⁵³⁰ Public Interest Organizations Comments at 36.

⁵³¹ *Id.* at 35-38.

⁵³² sPower Comments at 11.

- 330. The DC Commission states that, in the jurisdictions where the contract length has been adjusted to "short-term," such as Idaho's two-year contract,⁵³³ further elimination of the QF fixed price contract option would discourage or eliminate new small renewable energy facilities entering the markets, which is not consistent with PURPA's objective of encouraging the construction of renewable generation.⁵³⁴
- 331. NIPPC, CREA, REC, OSEIA, and Public Interest Organizations argue that the fact that states have shortened the length of QF contracts in response to fixed energy prices means that the Commission should require a minimum contract length. Green Power supports the creation of longer-term standard contract lengths for both cogeneration and small power production facilities. Green Power recommends that cogeneration developers are offered 5, 8, or 10-year contracts and that small power producers developers are offered 10, 15, or 20-year contracts. Mr. Mattson proposes that long-term contracts, defined as 20 years or longer, be available to QFs at their discretion. CARE notes that a purchasing utility's fixed capacity value may be zero if the state determines that the electric utility has no need for additional capacity resources. In that

⁵³³ DC Commission Comments at 8 (citing NOPR, 168 FERC ¶ 61,184 at P 77).

⁵³⁴ *Id*.

⁵³⁵ NIPPC, CREA, REC, and OSEIA Comments at 47-48; Public Interest Organizations Comments at 6-7.

⁵³⁶ Green Power Comments at 2, 10.

⁵³⁷ *Id.* at 10.

⁵³⁸ Mr. Mattson Comments at 7-9.

circumstance, there would be no fixed element in an avoided cost contract, which CARE believes would be inconsistent with the Commission's rationale justifying variable energy rate contracts. ⁵³⁹ EPSA similarly argues that, as noted in the NOPR, an electric utility is not required to pay for QF capacity that the state has determined is not needed. EPSA claims that the variable rate proposal therefore would create substantial uncertainty for QF developers and investors in non-ISO/RTO regions. ⁵⁴⁰

- 333. American Biogas argues that LMP prices are not sufficient to sustain existing biogas projects or to increase their number.⁵⁴¹ Several commenters state that LMP cannot sustain QFs in general.⁵⁴²
- 334. NIPPC, CREA, REC, and OSEIA argue that the NOPR proposal to base QF pricing on LMP or Western EIM will limit competition, because QFs will be stuck with no long-term assurance of investment recovery, and thus with no means to finance their projects, while regulated incumbent utilities will be able to rate-base their generation assets, thus guaranteeing long-term recovery of their investments.⁵⁴³ NIPPC, CREA, REC, and OSEIA maintain that prices for long-term QF contracts should be set by reference to long-term price indices or other indicators that, unlike highly-variable LMP and Western EIM

⁵³⁹ CARE Comments at 4 n.7.

⁵⁴⁰ EPSA Comments at 12.

⁵⁴¹ Biogas Comments at 2.

⁵⁴² BluEarth Renewables Comments at 2; Biological Diversity at 8; Covanta Comments at 9; Public Interest Organization Comments at 43-44.

⁵⁴³ NIPPC, CREA, REC, and OSEIA Comments at 55-56.

prices, genuinely reflect the long-term costs of generation avoided by the purchasing utility.⁵⁴⁴

iii. Commission Determination

- 335. As an initial matter, the Commission agrees with commenters that PURPA does not guarantee QFs a rate that guarantees financing. PURPA only requires the Commission to adopt rules that encourage the development of QFs; it does not provide a guarantee that any particular QF will be developed or profitable. This is evident from the structure of PURPA, which caps QF rates at the purchasing utility's avoided costs rather than providing for rates that guarantee the recovery of a QF's costs. The legislative history confirms that Congress did not intend to guarantee QF financing. As stated in the PURPA Conference Report, "the Conferees recognize that [QFs] are different from electric utilities, not being guaranteed a rate of return on their activities generally or on the activities vis-a-vis the sale of power to the utility and whose risk in proceeding forward in the [QF] enterprise is not guaranteed to be recoverable." 545
- 336. Notwithstanding that PURPA does not guarantee QF financeability, the Commission believes that the variable avoided cost energy rate option implemented by this final rule will still allow QFs to obtain financing.
- 337. Before addressing specific comments on this issue, however, we reiterate that we are not eliminating fixed rate pricing for QFs. Under this final rule, QFs will continue to

⁵⁴⁴ *Id.* at 53.

⁵⁴⁵ Conf. Rep. at 97-98 (emphasis added).

be able to require fixed avoided cost capacity rates in their contracts and LEOs. Capacity costs, as relevant here, include the cost of constructing the capacity being avoided by purchasing utilities as a consequence of their purchases from QFs. As will be discussed below, a combination of fixed avoided cost capacity rates and variable energy rates can provide important revenue streams that can support the financing of QFs.

338. Furthermore, merely because QFs have had access to fixed avoided cost energy rates does not mean that QFs must have access to such rates to obtain future financing. Up to now, QFs have had the right under the PURPA Regulations to both fixed capacity and fixed energy rates, and we understand that most QFs executing long-term contracts have exercised this right. Commenters insisting that the Commission cannot allow states the option to impose variable avoided cost energy rates without evidence that QFs have obtained financing under such contract structures⁵⁴⁶ are attempting to impose a standard that could never be satisfied.

339. In any event, there is ample evidence outside of the PURPA context demonstrating that generation projects with fixed capacity rate-variable energy contracts are financeable. As the Commission explained in detail in the NOPR, since the time of the passage of PURPA a large new independent power production industry has developed in the United States. Like QFs, independent power producers sell power at wholesale, and have no ability to rate-base their facilities or to otherwise recover their costs through regulated

⁵⁴⁶ See Solar Energy Industries Comments at 28; NIPPC, CREA, REC, and OSEIA Comments at 29, 46; Harvard Electricity Law Comments at 22, 25-27; Public Interest Organizations Comments at 6-7, 33-35.

rates to retail customers, unlike traditional utilities with franchised service territories and retail customers. Unlike QFs, however, independent power producers have had no right to require utilities to purchase their power or to impose fixed energy cost pricing in their power sales contracts. 547

340. The record shows that, even without the right to require long-term fixed energy rates, non-QF independent power producers nevertheless have been able to obtain financing for large amounts of generation capacity, including from renewables. EIA data shows that, in 2019, approximately 44% of all energy produced by natural gas-fired generation in the United States was generated by independently owned capacity. 548

Furthermore, EIA data demonstrates that net generation of energy by non-utility owned renewable resources in the United States grew by almost 700% between 2005 and 2018, which speaks to the reality that renewable resources are able to acquire financing even without the right to require long-term fixed energy rates. 549 Based on this data, we find that the right to require counterparties to pay fixed energy rates is not essential for the financing of independent power generation capacity.

⁵⁴⁷ See NOPR, 168 FERC ¶ 61,184 at P 76.

⁵⁴⁸ EIA, *Electric Power Monthly with Data for December 2018*, at tbl. 1.7.B (February 2020), https://www.eia.gov/electricity/monthly/archive/february2020.pdf).

⁵⁴⁹ *Id.* P 74 (explaining that net generation of energy by non-utility owned renewable resources in the United States escalated from 51.7 TWh in 2005 when EPAct 2005 was passed, to 340 TWh in 2018) (citing EIA, Electricity Data Browser, www.eia.gov/electricity/data/browser).

- 341. We acknowledge that a number of different financing mechanisms were used for this independent power generation capacity, not all of which will be available to QFs. Nevertheless, we understand that a standard rate structure employed in the electric industry is a fixed capacity rate-variable energy rate structure, and that many independent power production facilities have been financed based on this structure. Accordingly, record evidence and historical data regarding the financing and construction of significant amounts of independent power production facilities supports the Commission's conclusion that a fixed capacity rate-variable energy rate structure—which will apply in those states choosing the variable avoided cost energy rate option—also will support financing of QFs.
- 342. For the reasons described below, we do not find compelling the concerns expressed by some commenters that a fixed capacity rate-variable energy rate construct may not work for solar and wind resources, which have high fixed capacity costs and minimal variable energy costs.⁵⁵¹ Similarly, we are not persuaded by comments that point out that

⁵⁵⁰ American Public Power Association, *How New Generation is Funded* (Aug. 29, 2018), https://www.publicpower.org/blog/how-new-generation-funded ("Beginning in 2015, merchant generation [in RTOs/ISOs markets] began to increase dramatically from prior years, amounting to 19.3 percent of new capacity in 2015, 7.2 percent in 2016, and 29.1 percent in 2017."). In RTOs and ISOs with capacity markets, merchant generators are compensated through variable energy rates and fixed capacity rates, along with whatever ancillary service revenues they can earn.

⁵⁵¹ See Harvard Electricity Law Comments at 26; Public Interest Organizations Comments at 33-34; Solar Energy Industries Comments at 30.

energy rates in typical independent power production contracts are designed to recover the cost of a facility's fuel, whereas variable energy rates would provide no such guarantee.⁵⁵² 343. As an initial matter, as we have noted, the record demonstrates that the amount of renewable resources being developed outside of PURPA greatly exceeds the amount of renewable resources developed as QFs.⁵⁵³ Renewable resources developed outside of PURPA may not have a legal right to long-term contracts with fixed energy rates, yet nevertheless have been able to obtain financing.

344. The Commission also disagrees with those commenters who assert that, as a consequence of the above factors, the Commission should "require[] the variable energy component to be structured in a way that removes market risk from the QF." This argument runs directly counter to one of the fundamental premises of PURPA, which is that QFs must accept the market risk associated with their projects by being paid no more than the purchasing utility's avoided cost, thereby preventing utility retail customers from subsidizing QFs. PURPA does not allow the Commission to require QFs to be paid rates above avoided costs in order to make certain types of QF technologies financeable. If a state determines that it is necessary to require variable avoided cost energy rates in

⁵⁵² NIPPC, CREA, REC, and OSEIA Comments at 42-43.

⁵⁵³ See supra P 240.

⁵⁵⁴ NIPPC, CREA, REC, and OSEIA Comments at 43.

⁵⁵⁵ See Conf. Rep. at 97-98 (stating that the "risk in proceeding forward in the [QF] enterprise is not guaranteed to be recoverable"); accord API, 461 U.S. at 416 (holding that QFs "would retain an incentive to produce energy under the full-avoided-cost rule so long as their marginal costs did not exceed the full avoided cost of the purchasing utility").

order to avoid paying QFs an above-avoided cost rate, which is a bedrock requirement of PURPA, then the impact this may have on facilities not financeable with a fixed capacity rate-variable energy rate contract structure is a direct result of the requirements of PURPA itself. Concerns regarding the alleged mismatch between avoided costs and the costs of renewable technologies therefore are collateral attacks on the requirements of PURPA itself, not our proposed implementation of it.

345. In the NOPR, the Commission noted the availability of various hedging devices that would allow QFs to fix or limit the variability of a variable avoided cost energy rate. ⁵⁵⁷ We acknowledge those comments explaining that hedging tools increase project expense and may not be available to all QFs. ⁵⁵⁸ However, the Commission never intended to suggest that hedging is cost-free or that it would be appropriate for all QFs. The commenters all agree that hedging is available for at least some QFs. ⁵⁵⁹ For such QFs, hedging can help provide energy rate certainty if such certainty is required for financing.

⁵⁵⁶ See Connecticut Authority Comments at 14 ("[C]ontracted QF rates that take into account New England market conditions would not deter lenders and investors. Many QFs have no fuel costs and low variable costs of production; therefore, it is reasonable to find that these QFs would earn substantial inframarginal rents on energy sales. Further, QFs may be able to sell RECs and/or participate in other Connecticut programs.").

⁵⁵⁷ NOPR, 168 FERC ¶ 61,184 at P 72.

⁵⁵⁸ NIPPC, CREA, REC, and OSEIA Comments at 45-46; Resources for the Future Comments at 6-7; Solar Energy Industries Comments at 30.

⁵⁵⁹ *Id*.

To the extent that certainty is required, then the cost of hedging is a part of the cost of financing the project that PURPA requires QFs to bear.

346. Public Interest Organizations cite testimony from the Technical Conference stating that Southern Company has negotiated non-QF renewable contracts with fixed energy rates rather than variable energy rates. However, that testimony does not support the contention that the Commission must provide for fixed avoided cost energy rates for QF contracts and other LEOs. As the cited testimony notes, Southern agreed to contracts with longer terms and with fixed energy rates only because the renewable energy developers agreed to a rate that was 50 to 60 percent of the projected long-term avoided cost. Certain commenters expressed concern that, when a purchasing electric utility is not avoiding the construction or purchase of capacity as a consequence of entering into a contract with a QF, under the NOPR's proposed rules a state could limit the QF's contract rate to variable energy payments. However, in that event, the only costs being avoided by the purchasing electric utility would be the incremental costs of purchasing or

⁵⁶⁰ Public Interest Organizations Comments at 33-34 (citing NOPR, 168 FERC ¶ 61,184 at P 70 n.114 (citing Tech. Conference, Docket No. AD16-16-000, Tr. 200 (filed June 30))).

⁵⁶¹ Tech. Conference, Docket No. AD16-16-000, Tr. at 200 (filed June 30). The Commission notes that the PURPA Regulations specifically permit QFs and utilities to agree to rates that differ from what the PURPA Regulations require. 18 CFR 292.301(b). As the testimony cited by the Public Interest Organizations suggests, QFs that believe fixed energy avoided cost rates are required to obtain financing are free to offer rate and/or other contractual concessions in exchange for a fixed rate.

⁵⁶² CARE Comments at 4 n.7; EPSA Comments at 12.

producing energy at the time the energy is delivered.⁵⁶³ Nothing in PURPA or the legislative history of PURPA suggests that the Commission should set QF rates so as to facilitate the financing of new QF capacity in locations where no new capacity is needed.

348. In the NOPR, the Commission also observed that the variable avoided cost energy rate proposal might cause states to make other changes to their administration of PURPA in ways that would improve the financeability of QF projects. Most notably, states that had limited the length of contract terms because of concerns about overpayments for energy might be willing to allow longer term contracts if the contracts have variable avoided cost energy rates. Longer term contracts with fixed avoided cost capacity rates, in turn, would provide greater revenue assurance to QFs.⁵⁶⁴ The comments submitted in response to the NOPR support our analysis.

⁵⁶³ See, e.g., City of Ketchikan, 94 FERC ¶ 61,293, at 62,061 (2001) ("[A]voided cost rates need not include the cost for capacity in the event that the utility's demand (or need) for capacity is zero. That is, when the demand for capacity is zero, the cost for capacity may also be zero.").

NOPR, 168 FERC ¶ 61,184 at P 65. Contrary to assertions by some commenters, the Commission's conclusion in the NOPR about the possible positive effects of the variable avoided cost energy rate proposal was not based on speculation. See Public Interest Organizations Comments at 36. Rather, the Commission relied on testimony presented at the Technical Conference. See Technical Conference Tr. at 142-43 (Idaho Commission) ("No matter the starting point, allowing QFs to fix their avoided cost rates for long terms results in rates which will eventually exceed and overestimate avoided cost rates into the future. The longer the term, the greater the disparity. . . . [The Idaho Commission] recently reduced PURPA contract lengths to two years in order to correct the disparity. We didn't reduce contract lengths to kill PURPA. We did it to allow periodic adjustment of avoided cost rates.").

349. Further, there is some evidence that variable avoided cost energy rates in contracts and LEOs could result in longer-term contracts.⁵⁶⁵ To be clear, we are not finding that the variable avoided cost energy rate provision in this final rule will necessarily lead to longer term contracts and LEOs in every state, nor does our decision to adopt this provision rely on such a finding.⁵⁶⁶ However, the record supports the conclusion that the variable avoided cost energy rate provision could lead to longer term contracts in at least some states, and that likelihood provides support for the conclusion that QFs will be able to obtain financing for their projects under this provision if their costs are indeed below the purchasing utility's avoided costs.

h. Other Claimed Benefits of Fixed Avoided Cost Energy Rates

i. Comments

350. Public Interest Organizations assert that maintaining the requirement to pay QFs fixed rates serves as a hedge for consumers because QFs, unlike utilities, bear their own risks and have provided "billions of dollars" in benefits to consumers. Public Interest Organizations assert that eliminating QFs' rights to fixed rate contracts ignores these

⁵⁶⁵ Idaho Commission Comments at 4 (allowing states to set variable QF energy avoided costs "would allow states to consider longer term contracts without putting ratepayers at risk") (citing NOPR, 168 FERC ¶ 61,184 at 5 n.5).

⁵⁶⁶ We are not finding that variable avoided cost energy rates would be appropriate only if they cause states to require longer term contracts, and we are not adopting the suggestion made by certain commenters that the Commission order states to require longer contract terms. *See* NIPPC, CREA, REC, and OSEIA Comments at 47-48; Public Interest Organizations Comments at 6-7; sPower Comments at 11.

benefits to consumers and puts them at risk.⁵⁶⁷ Likewise, Solar Energy Industries portrays a fixed energy rate as providing a hedge to a utility that the purchasing electric utility may use as a revenue stream in connected markets. Solar Energy Industries nevertheless argues that, in order to encourage QF development, the Commission must ensure that QFs know the energy price at the time of contracting and that utilities publish rates stating the energy, capacity, and environmental attributes of the QF rate.⁵⁶⁸

ii. Commission Determination

351. Fixed and variable energy rates each can provide benefits to electric utility customers. These benefits are the converse of each other: variable avoided cost energy rates provide protection to customers when energy costs decline, and fixed avoided cost energy rates provide protection to customers when energy costs increase. By giving the states the flexibility to choose either variable or fixed avoided cost energy rates in QF contracts and LEOs, the Commission is giving each state the ability to choose the protection that is best suited for electric customers in their state, based on each state's

⁵⁶⁷ Public Interest Organizations Comments at 45-46 (citing S. Rep. No. 95-442, at 9, 22-23, 33 (1977), *as reprinted in* 1978 U.S.C.C.A.N. 7903, 7906, 7919-21, 7930; Public Interest Organizations, Comments, Docket No. AD16-16-000, at 5, 19-21 (Oct. 17, 2018)). In earlier comments in Docket No. AD16-16-000, cited by Public Interest Organizations in response to the NOPR, Public Interest Organizations asserted that long-term fixed QF contracts often act as a hedge that lowers QF financing expenses, which benefits ratepayers, and insulates ratepayers from fuel price fluctuations. Public Interest Organizations, Comments, Docket No. AD16-16-000, at 20-21 (Oct. 17, 2018).

⁵⁶⁸ Solar Energy Industries Comments at 31-32.

view of what the future may hold and the likelihood that variable energy avoided costs will exceed fixed energy avoided costs during the life of a QF contract or LEO.

- 352. We acknowledge that fixed avoided energy cost rates can serve as a hedge against future fuel price increases in a way that protects ratepayers, assuming such price increases actually occur. Given that PURPA both places an avoided cost cap on QF rates, and requires that such rates must be just and reasonable to the electric consumers of the electric utility, we find it is appropriate to provide flexibility to states to decide how to apportion such risks to their ratepayers in a way that ensures QF avoided energy cost rates are consistent with PURPA's requirements (i.e., by using either fixed or variable avoided cost energy rates to best meet those requirements).
- 353. We caution, though, that having made that choice, a state is not free to toggle a QF's contractual rate structure back and forth unilaterally from one to the other as circumstances change; QFs are entitled to the certainty that once a state has made its choice with respect to a particular QF's contract or LEO, that QF's contract or LEO is not subject to change during the term of that contract or LEO except by mutual consent.

i. Potential Modifications to NOPR Proposal

i. Comments

354. The California Commission, Connecticut Authority, and Massachusetts DPU support the variable energy rate proposal and suggest that, in addition, states be given the discretion to require the avoided capacity rate to vary.⁵⁶⁹

⁵⁶⁹ California Commission Comments at 27-28; Connecticut Authority Comments

- 355. In contrast, NIPPC, CREA, REC, and OSEIA urge the Commission, if it allows variable energy rates, to adopt strict parameters for setting capacity rates in order to provide some predictability to QFs to allow them to obtain financing. NIPPC, CREA, REC, and OSEIA recommend that the Commission require forecasted capacity rates be "offered in a long-term contract of at least 20 years after commencement of sales under the agreement" for "[a]ll years during the term of the QF's long-term contract after which the utility forecasted to be capacity deficit in its load and resource balance, as forecasted in its resource plan in effect at the time of the legally enforceable obligation" and "[a]ny time the utility is planning or undertaking actions to acquire a major generation resource or a major capital investment at an aging facility at the time of creation of the legally enforceable obligation." ⁵⁷⁰
- 356. Commissioner O'Donnell urges the Commission to provide additional guidance to states on the minimum required contract duration that would enable a QF to obtain financing from investors while providing sufficient ratepayer protections.⁵⁷¹

ii. Commission Determination

357. We decline to adopt the California Commission's, Connecticut Authority's, and Massachusetts DPU's requests to permit a state to require variable avoided cost capacity rates in addition to variable avoided cost energy rates. There is a fundamental difference

at 14-15; Massachusetts DPU Comments at 8-10.

⁵⁷⁰ NIPPC, CREA, REC, and OSEIA Comments at 51.

⁵⁷¹ Commissioner O'Donnell Comments at 3.

between avoided energy costs and avoided capacity costs. Unlike avoided energy costs, which fluctuate with changes in the variable cost of the purchasing utility's marginal energy resource, a purchasing utility's avoided capacity cost is determined at the time the utility incurs the obligation to purchase capacity from a QF rather than self-build a capacity resource or enter into a power purchase agreement with a third party. Although a purchasing utility's avoided capacity cost may later change as additional capacity acquisitions are avoided, the cost of the capacity avoided by the purchasing utility as a consequence of purchasing capacity from a particular QF at a particular moment in time does not change.

358. As a simple illustrative example, if a utility is able to avoid constructing a new generation facility with a capacity cost of \$10/MW-month as a result of purchasing power from a QF, its avoided capacity cost is the \$10/MW-month capacity cost that it would have been incurred to construct the new facility. Once the utility commences its purchases from the QF, it may not need additional capacity, and its avoided capacity cost for the next QF would drop to \$0/MW-month. It would not be appropriate to then reduce the original QF's avoided capacity charge to \$0/MW-month, however, because the only reason that the utility does not need additional capacity is because it already purchased capacity from the original QF in order to avoid the \$10/MW-month capacity cost. That is, without the purchase from the original QF, the utility would have incurred a capacity cost of \$10/MW-month, and that is the utility's avoided capacity cost for the term of its contract with the original QF. It would be inappropriate, in other words, for avoided cost

capacity rates to change after they are first set at the time a LEO (such as a contract) is established.

- 359. We also decline to adopt the suggestion of NIPPC, CREA, REC, and OSEIA to adopt additional criteria for establishing avoided capacity costs, including minimum contract lengths. We believe that the existing rate-setting provisions adequately set out the criteria that should be considered by a state in determining avoided capacity costs. ⁵⁷² To the extent that any party believes a state has not appropriately applied these criteria, that party has recourse to the enforcement provisions of PURPA sections 210(g) and (h). ⁵⁷³
- 360. We decline to specify a minimum required contract length given that it is up to states to decide appropriate contract lengths in a way that accurately calculates avoided costs so as to meet all statutory requirements.

8. <u>Consideration of Competitive Solicitations to Determine Avoided Costs</u>

a. NOPR Proposal

361. The Commission in the NOPR proposed to revise the PURPA Regulations in 18 CFR 292.304 to add subsection (b)(8). In combination with new subsection (e)(1), this subsection would permit a state the flexibility to set avoided cost energy and/or capacity

⁵⁷² See 18 CFR 292.304(e).

⁵⁷³ See also Policy Statement Regarding the Commission's Enforcement Role Under Section 210 of the Public Utility Regulatory Policies Act of 1978, 23 FERC ¶ 61,304.

rates using competitive solicitations (i.e., requests for proposals or RFPs), conducted pursuant to appropriate procedures.

362. The Commission recognized that one way to enable the industry to move toward more competitive QF pricing is to allow states to establish QF avoided cost rates through a competitive solicitation process. The Commission previously has explored this issue. In 1988, the Commission issued a notice of proposed rulemaking proposing to adopt regulations that would allow bidding procedures to be used in establishing rates for purchases from QFs.⁵⁷⁴ That rulemaking proceeding, along with several related proceedings, ultimately was withdrawn as overtaken by events in the industry.⁵⁷⁵ 363. Since then, the Commission held in a 2014 order addressing the specific facts of the particular competitive solicitation at issue that an electric utility's obligation to purchase power from a QF under a LEO could not be curtailed based on a failure of the QF to win an only occasionally-held competitive solicitation.⁵⁷⁶ In a separate proceeding involving a

Competitive solicitation processes have been used more recently in a number of states, including Georgia, North Carolina, and Colorado. Georgia's competitive

⁵⁷⁴ Regulations Governing Bidding Programs, FERC Stats. & Regs. ¶ 32,455 (1988) (cross-referenced at 42 FERC ¶ 61,323) (Bidding NOPR); see also Administrative Determination of Full Avoided Costs, Sales of Power to Qualifying Facilities, and Interconnection Facilities, FERC Stats. & Regs. ¶ 32,457 (1988) (cross-referenced at 42 FERC ¶ 61,324) (ADFAC NOPR).

⁵⁷⁵ See Regulations Governing Bidding Programs, 64 FERC ¶ 61,364 at 63,491-92 (1993) (terminating Bidding NOPR proceeding); see also Administrative Determination of Full Avoided Costs, Sales of Power to Qualifying Facilities, and Interconnection Facilities, 84 FERC ¶ 61,265 (1998) (terminating ADFAC NOPR proceeding).

⁵⁷⁶ See, e.g., Hydrodynamics, Inc., 146 FERC \P 61,193, at PP 31-35 (2014) (Hydrodynamics).

different competitive solicitation, the Commission declined to initiate an enforcement action where the state competitive solicitation was an alternative to a PURPA program. 577 364. Given this precedent, the Commission proposed to amend its regulations to clarify that a state could establish QF avoided cost rates through an appropriate competitive solicitation process. Consistent with its general approach of giving states flexibility in the manner in which they determine avoided costs, the Commission did not propose in the NOPR to prescribe detailed criteria governing the use of competitive solicitations as tools to determine rates to be paid to QFs, as well as to determine other contract terms. The Commission stated that states arguably may be in the best position to consider their particular local circumstances, including questions of need, resulting economic impacts, amounts to be purchased through auctions, and related issues.

365. Nevertheless, in considering what constitutes proper design and administration of a competitive solicitation, the Commission found it was appropriate to establish certain minimum criteria governing the process by which competitive solicitations are to be conducted in order for a competitive solicitation to be used to set QF rates. In that regard, the Commission noted that it has addressed competitive solicitations in prior orders in a

solicitation process is described at Ga. Comp. R. & Regs. 515-3-4.04(3) (2018). North Carolina's competitive solicitation process is described at 4 N.C. Admin. Code 11.R8-71 (2018). Colorado's competitive solicitation process is described at *sPower Development Co., LLC v. Colorado Pub. Utils. Comm'n*, 2018 WL 1014142 (D. Colo. Feb. 22, 2018).

⁵⁷⁷ Winding Creek Solar LLC, 151 FERC \P 61,103, reconsideration denied, 153 FERC \P 61,027 (2015). But see Winding Creek Solar LLC v. Peterman, 932 F.3d 861 (9th Cir. 2019).

number of contexts that provide potential guidance to states and others. For example, the Commission's policy for the establishment of negotiated rates for merchant transmission projects, ⁵⁷⁸ the Bidding NOPR, and the *Hydrodynamics* case ⁵⁷⁹ all suggest factors that could be considered in establishing an appropriate competitive solicitation that is conducted in a transparent and non-discriminatory manner.

366. These factors, as proposed in the NOPR, include, among others: (a) an open and transparent process; (b) solicitations should be open to all sources to satisfy the purchasing electric utility's capacity needs, taking into account the required operating characteristics of the needed capacity; ⁵⁸⁰ (c) solicitations conducted at regular intervals; (d) oversight by an independent administrator; and (e) certification as fulfilling the above criteria by the state regulatory authority or nonregulated electric utility. The Commission proposed that a state may use a competitive solicitation to set avoided cost energy and capacity rates,

⁵⁷⁸ Allocation of Capacity on New Merchant Transmission Projects and New Cost-Based, Participant-Funded Transmission Projects, 142 FERC ¶ 61,038 (2013).

⁵⁷⁹ See Hydrodynamics, 146 FERC ¶ 61,193 at P 32 n.70 (citing Bidding NOPR, FERC Stats. & Regs. ¶ 32,455 at 32,030-42). The Commission notes that, while QFs not awarded a contract pursuant to an competitive solicitation would retain their existing PURPA right to sell energy as available to the electric utility, if the state has concluded that such QF capacity puts tendered after an competitive solicitation was held are "not needed," the capacity rate may be zero because an electric utility is not required to pay a capacity rate for such puts if they are not needed. See Hydrodynamics, 146 FERC ¶ 61,193 at P 35 (referencing City of Ketchikan, 94 FERC ¶ 61,293 at 62,061 ("[A]voided cost rates need not include the cost for capacity in the event that the utility's demand (or need) for capacity is zero. That is, when the demand for capacity is zero, the cost for capacity may also be zero.")).

⁵⁸⁰ See 18 CFR 292.304(e); Windham Solar, 157 FERC ¶ 61,134 at PP 5-6.

provided that such competitive solicitation process is conducted pursuant to procedures ensuring the solicitation is transparent and non-discriminatory. The Commission proposed that such a competitive solicitation must be conducted in a process that includes, but is not limited to, the factors identified above which would be set forth in proposed subsection (b)(8).

367. In addition, the Commission sought comment on whether it should provide further guidance on whether, and under what circumstances, a competitive solicitation can be used as a utility's exclusive vehicle for acquiring QF capacity.⁵⁸¹

b. <u>Comments</u>

i. Comments in Opposition

368. Several commenters oppose the NOPR proposal to allow states the ability to set avoided cost energy and capacity rates through a competitive solicitation such as an RFP.⁵⁸²

369. Allco states that allowing a state commission to use a competitive solicitation price is simply giving another tool to a state commission to eliminate QF projects. Allco also contends that this proposal creates an apples and oranges scenario where a competitive

⁵⁸¹ The Commission proposed that, even if a competitive solicitation were used as an exclusive vehicle for an electric utility to obtain QF capacity, QFs that do not receive an award in the competitive solicitation would be entitled to sell energy to the electric utility at an as-available avoided cost energy rate.

⁵⁸² Allco Comments at 12; Blue Earth Comments at 1-2; Boulder Comments at 6; CA Cogeneration Comments at 10-11; Green Power Comments at 1-3; Industrial Energy Consumers Comments at 13.

⁵⁸³ Allco Comments at 12.

solicitation could be won by solar projects of 80 MWs at a low, steeply discounted price that may never get built, resulting in a state commission publishing that as an avoided cost for a 1 MW solar project connected to the distribution system.⁵⁸⁴ Allco points to California's Renewable Marketing Adjustment Tariff program as an example of a competitive solicitation price failure.⁵⁸⁵

- 370. CA Cogeneration states that relying on a competitive solicitation violates PURPA's mandatory purchase obligation, and the regulations must always preserve the right of a QF to negotiate a contract for the purchase of its output at an avoided cost rate. CA Cogeneration states that reliance on a competitive solicitation also fails to provide the necessary financial and operational encouragement for combined heat and power. Covanta asserts that the Commission's proposed competitive solicitation process would disadvantage technologies like Waste to Energy that are not growing, or are closing facilities.
- 372. Southeast Public Interest Organizations argue that, in the states that currently require some form of competitive solicitation, many utilities do not regularly hold competitive solicitations, do not make competitive solicitations open to all QFs, or do not

⁵⁸⁴ *Id*.

⁵⁸⁵ *Id*.

⁵⁸⁶ CA Cogeneration Comments at 10.

⁵⁸⁷ *Id.* at 11.

⁵⁸⁸ Covanta Comments at 9.

provide QFs the ability to sell to the utility outside of a competitive solicitation process.⁵⁸⁹ Southeast Public Interest Organizations maintain that the competitive solicitation process can be overly burdensome and costly for smaller facilities. Southeast Public Interest Organizations assert that no state requires, and no utility conducts, a competitive solicitation to determine how best to meet the ongoing energy needs that it currently meets through the operation of its existing generation fleet and market purchases. ⁵⁹⁰ In particular, Southeast Public Interest Organizations represent that: (1) Florida does not require an independent evaluator as part of its competitive solicitation process; (2) Colorado and Oklahoma allow utilities to apply for waivers of the competitive solicitation requirement; and (3) North Carolina allows the incumbent utility to participate in the competitive bidding process and to receive preferential treatment in the form of waiving post bid security required for any independently owned projects.⁵⁹¹ Southeast Public Interest Organizations conclude that, while a well-designed and well-implemented competitive solicitation process could be an appropriate procurement and rate-setting tool in some cases, competitive solicitations should never be the only way to set rates or for QFs to sell their output, and close consideration should be given to determinations of

⁵⁸⁹ Southeast Public Interest Organizations Comments at 26.

⁵⁹⁰ *Id.* at 26-27.

⁵⁹¹ *Id.* at 27.

utility capacity needs that could be manipulated to limit renewable energy procurements.⁵⁹²

373. Mr. Mattson states that precedent and legislative intent remove competitive solicitations from being a PPA option.⁵⁹³ Both Mr. Mattson and Two Dot Wind point to the Commission's ruling in *Hydrodynamics* that "requiring a QF to win a competitive solicitation as a condition to obtaining a long-term contract imposes an unreasonable obstacle to obtaining a legally enforceable obligation."⁵⁹⁴ Two Dot Wind also states that competitive solicitations have not worked in Montana, and that the NOPR's suggestion that competitive bidding can replace PURPA is not supported by the factual record in Montana.⁵⁹⁵

374. Industrial Energy Consumers expresses concern that the parameters for competitive solicitations are not sufficiently developed to ensure a well-structured, fairly administered, transparent, and non-discriminatory process for procurement, and therefore opposes allowing a competitive solicitation process to determine avoided costs at this time. ⁵⁹⁶

⁵⁹² *Id.* at 25-26.

⁵⁹³ Mr. Mattson Comments at 23.

 $^{^{594}}$ *Id.*; Two Dot Wind Comments at 10 (citing *Hydrodynamics*, 146 FERC \P 61,193).

⁵⁹⁵ Two Dot Wind Comments at 9-10.

⁵⁹⁶ Industrial Energy Consumers Comments at 13.

ii. Comments in Support

are several commenters support the NOPR proposal to allow states the ability to set energy and capacity rates through a competitive solicitation such as an RFP. ⁵⁹⁷

376. Multiple commenters, including EEI, NRECA, and the Oregon Commission, support the notion that the states are in the best position to tailor the competitive solicitation process to their needs, and that the Commission should not provide detailed criteria governing the use of competitive solicitations. ⁵⁹⁸ EEI states that the fact that competitive solicitations may be used to set avoided costs is an idea nearly as old as PURPA. ⁵⁹⁹ EEI also supports the Commission's proposal for a state to allow a competitive solicitation to be used as the exclusive vehicle for acquiring QF capacity. ⁶⁰⁰ NRECA notes that numerous NRECA members have already had success using competitive solicitations to establish both energy and capacity rates in states where competitive solicitations are permitted. ⁶⁰¹

377. Growth and Opportunity Center states that competitive solicitation processes, in place of avoided cost calculations, provide better signals to investors of where their

⁵⁹⁷ Alaska Power Comments at 1; Distributed Sun Comments at 2; EEI Comments at 32-33; El Paso Electric Comments at 4; NARUC Comments at 3; NRECA Comments at 11; South Dakota Commission Comments at 2-3.

⁵⁹⁸ EEI Comments at 32-33; NRECA Comments at 11; Oregon Commission Comments at 3-4.

⁵⁹⁹ EEI Comments at 32.

⁶⁰⁰ *Id.* at 33.

⁶⁰¹ NRECA Comments at 11.

electricity is most valuable because competitive solicitations reflect more informed estimates of the real-time needs of electricity consumers. Growth and Opportunity Center contends that the proposed rule changes, by giving states more latitude to use competitive solicitations in complying with PURPA, should result in prices for consumers that more accurately reflect market costs for electricity. Growth and Opportunity Center also asserts that in states using competitive solicitation processes, nondiscrimination rules should be enforced to ensure that solicitations are competitive and that no providers receive preferential treatment.

378. The Michigan Commission states that it recently approved using competitive solicitations to determine avoided capacity costs for a large electric utility in Michigan.⁶⁰⁴ The Michigan Commission states that it believes that that recently approved structure aligns with the Commission's proposal in the NOPR.⁶⁰⁵

379. Portland General asserts that, because the output of an competitive solicitation represents a resource's true market costs, a competitive solicitation is the correct method to determine avoided cost. Portland General states that, given the competitive nature of competitive solicitations, bidders are highly motivated, which results in the procurement

⁶⁰² Growth and Opportunity Center Comments at 9.

 $^{^{603}}$ *Id.* at 10.

⁶⁰⁴ Michigan Commission Comments at 4.

⁶⁰⁵ *Id.* at 5.

⁶⁰⁶ Portland General Comments at 11.

of resources with high benefit-to-cost ratios. Portland General cites as an example its recent competitive solicitation, which resulted in a \$40.70-levelized price and reflects a combination of technologies (wind, solar, and battery), whereas QFs, which Portland General asserts provide lower capacity, are currently offered at a \$45.19 levelized price for solar energy. 607

380. Xcel urges the Commission's to give the states the option of procuring all needed capacity through competitive bidding processes. Xcel strongly believes that states must have the ability to control capacity additions to ensure that customer needs and state policy goals are met. Xcel explains that in many states, including some in which the Xcel operating companies operate, resource procurement is accomplished largely through state-administered IRP processes, which are utilized to ensure a resource mix that meets the overall public interest in affordable and clean energy. Xcel states that these carefully calibrated processes can be upset when QFs bring capacity on to a utility's system that does not align with the state's vision of its optimal resource mix and when those QFs also attempt to collect above-market payments from utilities and therefore customers. Xcel states that Colorado's procurement efforts have been so successful that in 2016 more than 400 bids for 238 distinct projects were submitted for Public Service Company of Colorado alone, and that this process resulted in some of the lowest prices for renewables seen as of

⁶⁰⁷ *Id*

⁶⁰⁸ Xcel Comments at 10.

⁶⁰⁹ *Id.* at 8.

that date, with a median wind price of \$19.30/MWh and a median solar price of \$30.96/MWh. Xcel argues that unsolicited puts by QFs, in contrast, can impede the ability of states to meet their resource planning goals and can undermine the competitive markets that states like Colorado have already created or are striving to create. 381. North Carolina Commission Staff states that North Carolina has implemented a competitive solicitation process for solar energy that complements the PURPA reforms adopted by the state, with the first solicitation concluding in April 2019. North Carolina Commission Staff states that an independent administrator estimated the initial nominal savings for the competitive solicitation with a 20-year contract versus traditional avoided cost pricing to exceed \$370 million for the utilities involved. 282. Duke Energy shares its state-specific experience with North Carolina's competitive solicitation for renewable energy as a positive example. Duke Energy states that Duke Energy Carolinas, LLC and Duke Energy Progress, LLC recently completed their Tranche

1 Competitive Procurement of Renewable Energy RFP and procured approximately 550

MW of new solar capacity for 20-year fixed price contract terms at a projected savings of

⁶¹⁰ *Id.* at 9.

⁶¹¹ North Carolina Commission Staff Comments at 3-4.

⁶¹² *Id.* at 4.

⁶¹³ Duke Energy Comments at 10-12.

approximately \$261 million relative to administratively determined forecasts of avoided costs over this same period.⁶¹⁴

iii. Comments Requesting Modifications/Clarifications

(a) Requests for Clarification and/or Separate Proceedings

383. NIPPC, CREA, REC, and OSEIA argue that the NOPR fails to explain (1) whether the Commission is proposing to merely clarify that a state could use the lowest offer prices submitted in a competitive solicitation to set the avoided costs of energy and capacity on a prospective basis for any QF seeking a contract until the next competitive solicitation, or (2) whether the Commission is proposing a radical change in its precedent by revising its rules to provide that a QF may only sell under a long-term contract if that QF wins a competitive solicitation, which NIPPC, CREA, REC, and OSEIA assert would be contrary to the *Hydrodynamics*⁶¹⁵ and *Winding Creek*⁶¹⁶ cases.⁶¹⁷

384. NIPPC, CREA, REC, and OSEIA request that any requirement to win a competitive solicitation to obtain a long-term PURPA contract should exempt small facilities. NIPPC, CREA, REC, and OSEIA further state that the Commission should:

(1) require that the competitive solicitation include no utility-ownership options; or (2) if

⁶¹⁴ *Id.* at 12.

⁶¹⁵ *Hydrodynamics*, 146 FERC ¶ 61,193.

⁶¹⁶ Winding Creek Solar LLC v. Peterman, 932 F.3d 861.

⁶¹⁷ NIPPC, CREA, REC, and OSEIA Comments at 62-63.

⁶¹⁸ *Id.* at 67.

utility-owned generation may result, the competitive solicitation must be: (i) administered and scored (not just overseen) by a qualified independent party, not the utility; (ii) any utility or utility-affiliate ownership bid must be capped at its bid price and not allowed traditional cost-plus ratemaking treatment; and (iii) the product sought, minimum bidding criteria, and detailed scoring criteria must be made known to all parties at the same time. Additionally, NIPPC, CREA, REC, and OSEIA contend that an option for long-term contracts should remain available for both small QFs and existing QFs outside of a competitive solicitation.

385. The Michigan Commission states that it would welcome guidance on whether, and under what circumstances, a competitive solicitation can be used as a utility's exclusive vehicle for acquiring QF capacity. Similarly, the Montana Commission recommends that the Commission provide as much guidance to states as possible regarding the requirements for transparency and non-discrimination. 622

386. The California Commission states that the NOPR does not provide states any more flexibility than they already have, and the Commission's final order adopting revised regulations should clearly state this.⁶²³

⁶¹⁹ *Id*.

⁶²⁰ *Id.* at 67-68.

⁶²¹ Michigan Commission Comments at 5.

⁶²² Montana Commission Comments at 3.

⁶²³ California Commission Comments at 23.

387. Several commenters suggest that the Commission should conduct focused additional processes on this topic.⁶²⁴ Advanced Energy Economy suggests that the Commission conduct one or more workshops or technical conferences, to explore in detail the specific factors that would make a utility competitive solicitation process a truly competitive process of a "comparative quality" to competitive wholesale energy and capacity markets. 625 Advanced Energy Economy contends that such workshops or technical conferences could ultimately be the basis for developing proposed regulations better guiding the states and electric utilities in implementing open and competitive solicitation processes to obtain relief from the mandatory purchase obligation under PURPA section 210(m)(1)(C). 626 Industrial Energy Consumers argues that, if the Commission seeks to allow states to rely on competitive solicitation processes, the Commission should undertake a separate inquiry, with necessary technical conferences, to develop specific parameters to govern such processes.⁶²⁷ If the Commission relies directly on competitive solicitation processes in the final rule, Industrial Energy Consumers states that if, after undertaking the competitive solicitation, the utility rejects all offers and decides to self-build, then the all-inclusive price of the self-build option should at least

⁶²⁴ Advanced Energy Economy Comments at 13; EPSA Comments at 15-16; Industrial Energy Consumers Comments at 13-14.

⁶²⁵ Advanced Energy Economy Comments at 13.

⁶²⁶ Id.

⁶²⁷ Industrial Energy Consumers Comments at 13-14.

establish the avoided cost rate for QFs seeking to develop in that area. EPSA argues that the Commission should require further proceedings, including another technical conference, to discuss the protections that would be necessary in order to have a genuinely level playing field for competitive solicitations. 629

388. Commissioner Slaughter states that PURPA sits at the intersection of competition and regulatory policy in an area of vital and urgent interest, and that the Commission should establish fair, non-discriminatory guidelines for competitive solicitations that would help states and other stakeholders maximize the benefits of competition from low-cost energy sources, particularly utility-scale renewable energy facilities. ⁶³⁰

Commissioner Slaughter states that such guidelines could form the basis for transitioning many local markets from administratively determined prices to environments of dynamic price discovery in which the rapidly decreasing cost of utility-scale renewable energy can put maximum pressure on both new and pre-existing fossil fuel-based sources of electricity. ⁶³¹

389. EPSA states that the Commission should ensure that competitive solicitations are properly designed to ensure that QFs have meaningful opportunities to compete against

⁶²⁸ *Id.* at 14.

⁶²⁹ EPSA Comments at 16.

⁶³⁰ Commissioner Slaughter Comments at 1-2.

⁶³¹ *Id.* at 3.

resources owned by incumbent utilities on a level playing field. EPSA states that the Commission should use this opportunity to do a full assessment of how competitive solicitations are working and could be enhanced, while providing continued protections to prevent discrimination against QFs. EPSA also emphasizes that, regardless of whatever competitive solicitation rules the Commission ultimately adopts, the Commission must continue to exercise its "backstop" oversight and enforcement authority to ensure that any requirements are implemented in a consistent and appropriate manner by individual states. 634

(b) Requests Regarding Proposed Criteria

390. Several commenters requested that the Commission clarify the criteria that solicitations be conducted at regular intervals. Several commenters request that the Commission reconsider or remove that criteria. Shower argues that the Commission should require that such competitive solicitations be conducted at a minimum every two years. Colorado Independent Energy asserts that competitive solicitations should be held at regular intervals to test the market, and that the Commission should consider the

⁶³² EPSA Comments at 3.

⁶³³ *Id.* at 14.

⁶³⁴ *Id.* at 16-17.

⁶³⁵ APPA Comments at 17-18; Basin Comments at 9; Montana Commission Comments at 3; sPower Comments at 9-10.

⁶³⁶ NorthWestern Comments at 7-8.

⁶³⁷ sPower Comments at 9-10.

entire market, not just projects 80 MW and under, in evaluating whether there are full and competitive opportunities.⁶³⁸

391. Several commenters oppose the requirement for an independent administrator. ⁶³⁹ APPA argues that the entire PURPA administrative construct is designed to entrust to state regulatory authorities the responsibility to carry out the duties they are assigned under the Commission's regulations. ⁶⁴⁰ NRECA believes that states are in the best position to determine the need for "oversight by an independent administrator" and recommends this criterion be deleted. ⁶⁴¹ NRECA requests that, if the Commission retains the requirement that competitive solicitation processes include some type of oversight, instead of requiring oversight by an independent administrator, the Commission should allow states the flexibility to allow electric utilities to retain a third-party consultant for this purpose. ⁶⁴² NRECA contends that many cooperatives have long-standing relationships with third-party consultants that assist the cooperatives in evaluating power supply options, and requiring those cooperatives to now use some other entity (i.e., the

⁶³⁸ Colorado Independent Energy Comments at 9-12.

⁶³⁹ APPA Comments at 18; NRECA Comments at 11.

⁶⁴⁰ APPA Comments at 18 (citing 16 U.S.C. 824a-3(f) (expressly calling for state regulatory authorities and nonregulated electric utilities to implement Commission-issued PURPA regulations)).

⁶⁴¹ NRECA Comments at 11.

⁶⁴² *Id.* at 12.

independent administrator) would be disruptive and costly.⁶⁴³ Colorado Independent Energy notes that, while independent evaluators are helpful, they are often employed by utilities and thus sometimes reluctant to offer third party criticism of the bid evaluation process.⁶⁴⁴

- 392. The Montana Commission requests clarification of the term "independent administrator" and "certified" as those terms are used in the proposed revisions to § 292.304(b).⁶⁴⁵
- 393. sPower disagrees that a competitive solicitation should "take into account the required operating characteristics of the needed capacity" in order to produce accurate avoided cost rates and recommends that a final rule remove that language from condition (ii) in the Commission's list of conditions that a competitive solicitation must meet. 646 394. Colorado Independent Energy states that, in addition to the guidelines provided in the NOPR, the Commission should include additional guidelines, including that fairness of an "all-source" competitive solicitation must also be determined based on bid evaluation and not just on a competitive solicitation. Colorado Independent Energy asserts that competitive solicitation *submissions* can be technology-specific, but not the evaluation or the analysis of the need to be met by a competitive solicitation. Colorado

⁶⁴³ *Id*.

⁶⁴⁴ Colorado Independent Energy Comments at 8.

⁶⁴⁵ Montana Commission Comments at 3.

⁶⁴⁶ sPower Comments at 8.

Independent Energy asserts that a true all-source selection process must allow resource planning models to optimize among all bids received without bias toward QF-eligible technologies such as renewable generation or cogeneration.⁶⁴⁷

395. Several commenters stated that competitive solicitations must be assessed using the criteria set forth in *Allegheny*. ⁶⁴⁸ EPSA further states that, while the *Allegheny* principles provide a good starting point, additional protections will be required to level the playing field between independent generators and utilities. ⁶⁴⁹ R Street asserts that, if an auction can meet the *Allegheny* standard, then generators in that state would not be eligible for QF designations. R Street suggests that QFs should not be able to force their power on utilities if they lose such fairly administered auctions. ⁶⁵⁰

396. Solar Energy Industries asserts that the Commission should require a purchasing electric utility to provide the state commission, and make available for public inspection, a post-solicitation report that: (1) identifies the winning bidders; (2) includes a copy of any reports issued by the independent evaluator; and (3) demonstrates that the solicitation program was implemented without undue preference for the interests of the purchasing utility or its affiliates. Solar Energy Industries further assert that the solicitation program

⁶⁴⁷ Colorado Independent Energy at 2.

⁶⁴⁸ EPSA Comments at 14-15 (citing *Allegheny*, 108 FERC ¶ 61,082); R Street Comments at 3-4; Solar Energy Industries Supplemental Comments, Docket No. AD16-16-000, at 32-37 (filed Aug. 28, 2019).

⁶⁴⁹ EPSA Comments at 15.

⁶⁵⁰ R Street Comments at 3-4.

should include clear details regarding the manner in which the bids will be scored and clearly specify price and non-price criteria under which bids are evaluated including: (1) acceptable delivery points and any scoring deductions for delivery to other points; (2) credit evaluation criteria and development securing requirements; and (3) performance requirements.⁶⁵¹

397. Public Interest Organizations argue that the Commission's proposal does not require that state competitive solicitation procedures meet the statutory floor established through PURPA that rates both (1) encourage small power producers and (2) not discriminate relative to the utility's own generation and other non-QF generators. To ensure competitive solicitations actually meet the statutory criteria, the Commission must ensure that competitive solicitations meet four minimum standards. First, Public Interest Organizations state that solicitations must account for utility-owned and non-QF generation and cannot be a limited competition between QFs without the ability to displace non-QF generation. As an example of an incorrectly-conducted, and unlawfully-discriminatory, bidding process, Public Interest Organizations cite the Nevada competitive solicitation process that is limited to QFs to meet a small, segregated portion

⁶⁵¹ Solar Energy Industries Supplemental Comments, Docket No. AD16-16-000, at 21 (filed August 28, 2019).

⁶⁵² Public Interest Organizations Comments at 69-70.

⁶⁵³ *Id.* at 70.

⁶⁵⁴ *Id*.

of the utility's energy and unmet capacity requirements. Second, to ensure that QFs receive the same price that other generation receives, Public Interest Organizations state that all sources of supply must compete in the competitive solicitation—including the utility's own generation. Third, Public Interest Organizations state that the solicitation process cannot be used in any way to curtail or delay a utility's obligation to purchase from QFs. Fourth, the "required operating characteristics of the needed capacity" factor suggested in the NOPR cannot be used as a surrogate to define characteristics of only non-QF generation or to allow a utility to pick among favored generators.

398. Biogas states that, if QFs are to enter into competitive solicitations as a vehicle for PURPA, then there must be some correcting for the inequitable tax and regulatory provisions afforded to incumbent utilities and select renewable technologies, in order to ensure a fair market opportunity.⁶⁵⁹

399. American Dams requests that QFs competing against a utility that can rate base the cost of new generation should be entitled to similar valuation provided that QF costs are at or less than those of the utility.⁶⁶⁰

⁶⁵⁵ *Id.* at 71-72.

⁶⁵⁶ *Id.* at 72.

⁶⁵⁷ *Id.* at 72-73.

⁶⁵⁸ *Id.* at 73.

⁶⁵⁹ Biogas Comments at 2.

⁶⁶⁰ American Dams Comments at 3.

(c) Other Requests

400. In their comments to the NOPR, Solar Energy Industries reference their August 28, 2019 comments in Docket No. AD16-16-000,⁶⁶¹ in which they describe the "SEIA Counterproposal." That document proposes that, where a utility seeks to meet identified capacity needs through an open, fairly designed, and independently administered competitive solicitation: (i) the purchasing electric utility would only have to pay QFs for capacity to the extent that the purchasing electric utility failed to meet identified need through the competitive solicitation; and (ii) the QF would be paid for its output (energy and capacity) at the market rate established through the competitive solicitation process. ⁶⁶² 401. Solar Energy Industries request that the Commission supplement proposed 18 CFR 292.304(b)(5) to require that: (1) participants are provided with complete and transparent information regarding transmission constraints, levels of congestion, and interconnections; and (2) the solicitation is linked with the purchasing utility's IRP and is conducted for the entirety of a utility's anticipated capacity needs. ⁶⁶³

402. Solar Energy Industries request that the Commission expressly implement safeguards to prevent utility self-dealing and affiliate abuse, with regard to both price and non-price terms. 664 Solar Energy Industries reference their previous comments in this

⁶⁶¹ Solar Energy Industries Supplemental Comments, Docket No. AD16-16-000, at 17-40 (filed Aug. 28, 2019).

⁶⁶² Solar Energy Industries Comments at 38.

⁶⁶³ *Id.* at 39.

⁶⁶⁴ *Id*.

proceeding, which they state describe practices of PacifiCorp,⁶⁶⁵ NorthWestern,⁶⁶⁶

Duke,⁶⁶⁷ and Xcel⁶⁶⁸ purportedly showing that these utilities have attempted to reduce

QFs' ability to sell while simultaneously seeking to build and rate base their own substantial renewable resources.⁶⁶⁹

403. ELCON states that it continues to see shortcomings in competitive procurement practices across regions.⁶⁷⁰ A current example ELCON provides is Dominion Energy Virginia's 2019 RFP which, ELCON argues, limited competition in a manner that all but guarantees that a Dominion self-build option will prevail because it restricts participation to new resources only and does not permit an independent third party to evaluate bids.⁶⁷¹ Another example ELCON provides is a recent Entergy Louisiana solicitation through which a natural gas generating facility was approved despite opposition from Louisiana industrial consumers who argued that the competitive solicitation was improperly designed to limit resource options to new construction comparable to a self-build.⁶⁷²

⁶⁶⁵ Solar Energy Industries Supplemental Comments, Docket No. AD16-16-000, at 25-28 (filed August 28, 2019).

⁶⁶⁶ *Id.* at 28-29.

⁶⁶⁷ *Id.* at 29-31.

⁶⁶⁸ *Id.* at 21.

⁶⁶⁹ Solar Energy Industries Comments at 40.

⁶⁷⁰ ELCON Comments at 27.

⁶⁷¹ *Id*.

⁶⁷² *Id.* at 28.

404. ELCON asserts that, to be competitive, a competitive solicitation must be transparent, face independent oversight, have safeguards against affiliate abuse involving transactions between franchised utilities and their market-based affiliates, and have well-defined technical parameters. ELCON states that experiences with competitive solicitations thus far expose the challenges of achieving a workably competitive process. ELCON urges the Commission to set a high bar, with enforcement to verify that a process is sufficiently competitive. 674

405. NorthWestern states that it supports the Commission's proposal to use competitive solicitations or RFPs to establish avoided *capacity* costs, but not avoided *energy* costs, because NorthWestern believes that an energy-only competitive solicitation has no relation to the market whereas a capacity competitive solicitation does. NorthWestern believes that use of a competitive solicitation should be the preferred vehicle for setting avoided capacity rates for QFs because this will ensure that the capacity is acquired at the least cost thereby benefiting customers. 676

406. Institute for Energy Research states that it would go even further than the NOPR proposal and require that competitive solicitations be the default whenever possible, with states having to justify case-by-case why a non-competitive solicitation is needed, because

⁶⁷³ *Id.* at 28-29.

⁶⁷⁴ *Id*.

⁶⁷⁵ NorthWestern Comments at 7.

⁶⁷⁶ *Id*.

solicitation is the best expression of the Congressional mandate to encourage competition.⁶⁷⁷

407. Harvard Electricity Law states that the NOPR's proposed 18 CFR 292.304(b)(8)(ii), requiring solicitations must be open to "all sources"—could be read as inconsistent with the Commission's *CPUC* orders⁶⁷⁸ and the 2019 *CARE v. CPUC* decision.⁶⁷⁹ Harvard Electricity Law argues that, if the Commission amends its avoided cost rules to allow states to set avoided cost rates based on competitive solicitations, it should clarify that states may set tiered rates, as the Commission and the U.S. Court of Appeals for the Ninth Circuit has allowed in the above cases.⁶⁸⁰

408. The Oregon Commission recommends that the Commission emphasize the need for states to have adequate safeguards to protect bidders' confidential and commercially sensitive proprietary information when using competitive solicitations to determine or inform avoided cost rates.⁶⁸¹

⁶⁷⁷ Institute for Energy Research Comments at 1.

⁶⁷⁸ Cal. Pub. Utils. Comm'n, 133 FERC ¶ 61,059, clarification and reh'g denied, 133 FERC ¶ 61,059 (2010), reh'g denied, 134 FERC ¶ 61,044 (2011) (CPUC).

⁶⁷⁹ Californians for Renewable Energy v. Cal. Pub. Utils. Comm'n, 922 F.3d 929, 937 (9th Cir. 2019) (CARE v. CPUC) (holding that "where a state has [a renewable portfolio standard (RPS)] and the utility is using a QF's energy to meet the RPS, the utility cannot calculate avoided costs based on energy sources that would not also meet the RPS[,]" which "comports with PURPA's goal to put QFs on an equal footing with other energy providers").

⁶⁸⁰ Harvard Electricity Law Comments at 31.

⁶⁸¹ Oregon Commission Comments at 4.

- 409. sPower states that the issue of using a competitive solicitation process to establish avoided cost rates has sometimes been conflated with using a competitive solicitation process to establish a LEO, and sPower encourages the Commission to continue to analyze these distinct issues separately.⁶⁸²
- 410. Resources for the Future stresses that competitive solicitations alone would minimize QF costs but would not establish avoided cost rates, which depend on much more than the cost of QF generation. However, used in concert with forward curves, Resources for the Future states that competitive solicitations could provide an effective complementary method. 684

c. <u>Commission Determination</u>

411. In this final rule, we affirm the NOPR proposal to revise the PURPA Regulations to explicitly permit a state the flexibility to set avoided energy and/or capacity rates using competitive solicitations (i.e., RFPs), conducted pursuant to appropriate procedures in a transparent and non-discriminatory manner. A primary feature of a transparent and non-discriminatory competitive solicitation is that a utility's capacity needs are open for bidding to all capacity providers, including QF and non-QF resources, on a level playing field. This level playing field ensures that any QF's capacity rates that result from the competitive solicitation are just and reasonable and non-discriminatory avoided cost rates.

⁶⁸² sPower Comments at 3.

⁶⁸³ Resources for the Future Comments at 8-9.

⁶⁸⁴ *Id.* at 9.

- 412. Consistent with our general approach of giving states flexibility in the manner in which they determine avoided costs, we do not prescribe detailed criteria governing the use of competitive solicitations as tools to determine rates to be paid to QFs, as well as to determine other contract terms. States arguably are in the best position to consider their particular local circumstances, including questions of need, resulting economic impacts, amounts to be purchased through auctions, and related issues.
- 413. In considering what constitutes proper design and administration of a competitive solicitation, however, we find it appropriate to establish certain minimum criteria governing the process by which competitive solicitations are to be conducted in order for an competitive solicitation to be used to set QF rates. These factors, which we proposed in the NOPR and adopt here, include, among others: (a) an open and transparent process; (b) solicitations should be open to all sources to satisfy that purchasing electric utility's capacity needs, taking into account the required operating characteristics of the needed capacity; (c) solicitations conducted at regular intervals; (d) oversight by an independent administrator; and (e) certification as fulfilling the above criteria by the state regulatory authority or nonregulated electric utility.
- 414. We affirm that such competitive solicitations must be conducted in a process that includes, but is not limited to, the factors identified above that will be set forth in 18 CFR 292.304(b)(8). This rule does not undo any competitive solicitations conducted prior to the effective date of this final rule that may not have met these criteria. This rule applies only to competitive solicitations conducted after the effective date of the final rule.

We also provide modifications and clarifications to the NOPR proposal, as described below.

i. Requests for Clarification and/or Separate Proceedings

- 415. As an initial matter, in the NOPR, the Commission addressed competitive solicitations in two related but distinct contexts. The first, to be discussed in this section, relates to the proposal to explicitly permit a state the flexibility to set avoided cost energy and/or capacity rates using competitive solicitations (i.e., RFPs), conducted pursuant to appropriate procedures. The second, to be discussed below, in section IV.G.2 of this final rule, concerns the NARUC proposal that urged the Commission to give meaning to PURPA section 210m(1)(C) by establishing a "yardstick" by which a vertically integrated utility outside of an RTO or ISO could apply to terminate the mandatory purchase obligation if it conducts sufficiently competitive RFPs for energy or capacity.
- competition in the procurement of generation and to encourage the development of QFs in a way that most accurately reflects a purchasing utility's avoided costs. We believe that allowing QFs to compete to provide capacity and energy needs, through a properly administered competitive solicitation, may help ensure an accurate determination of the purchasing electric utility's avoided cost, and therefore result in prices meeting the PURPA's statutory requirements. We also believe that it is reasonable for states to choose to require QFs to be responsive to price signals as to where and when capacity is needed.

We believe that a properly administered competitive solicitation can help provide such price signals.

Furthermore, we believe that competitive solicitations may be an especially appropriate tool for developing competition in the markets outside of RTOs and ISOs, where there are no organized competitive markets in place where QFs can make sales. We emphasize, however, that neither the Commission's current regulations, nor 418. those adopted in this final rule, require a state or a purchasing electric utility to use a competitive solicitation to determine avoided cost rates for QFs. Consistent with other changes in our regulations discussed above, we give states the flexibility to use a properly structured competitive solicitation for this purpose, but we do not mandate that they do so. 419. Furthermore, in light of the substantial experience the industry has with competitive solicitations within and outside of the PURPA context, and the voluminous comments the Commission has received regarding competitive solicitations, we find that there is not currently a need for a separate proceeding or additional procedures to address competitive solicitation issues, such as holding workshops or technical conferences. Should further procedures appear beneficial in light of actual competitive solicitation experience under PURPA and the regulations adopted today, such a proceeding may be appropriate in the future.

ii. Proposed Criteria

420. We continue to find that competitive solicitations as discussed in this final rule may accurately reflect a purchasing electric utility's avoided costs and ensure that the resulting rates for winners of such competitive solicitations are consistent with PURPA. A

competitive solicitation may more accurately value QF capacity over time by subjecting it to competition with other sources. Such competitive solicitations may provide more certainty both to QFs regarding when and how often they will be eligible to compete and to purchasing utilities regarding how they may expect to fulfill their capacity needs.

- 421. The Commission clarifies that, if a utility acquires all of its capacity through properly conducted competitive solicitations (using the factors described above), and does not add capacity through self-building and purchasing power from other sources outside of such solicitations, the competitive solicitations could be the exclusive vehicle for the purchasing electric utility to pay avoided capacity costs from a QF. In this situation, using properly conducted competitive solicitations as the exclusive vehicle to determine the purchasing electric utility's avoided cost capacity rates would allow QFs a chance to compete to provide the utility's capacity needs on a level playing field with the utility. We clarify that it is up to the states to determine whether to require that a utility's total planned self-build and power purchase options must compete in the competitive solicitations, and we will not direct such a requirement here.
- 422. If a state decides to require utility self-build and power purchase options to participate in competitive solicitations, then a QF that does not obtain an award in a competitive solicitation would have no right to an avoided cost capacity rate more than zero because the utility's full capacity needs would have been met by the competitive solicitation. However, QFs would continue to have the right to put energy to the utility

⁶⁸⁵ This would be consistent with *City of Ketchikan*, 94 FERC at 62,061 ("[A]voided cost rates need not include the cost for capacity in the event that the utility's

to avoid incurring the cost of generating energy even when it does not need new capacity.

423. If the state does not require utility self-build and purchase options to participate in competitive solicitations, then QFs that lose in a competitive solicitation still may have the right to avoided cost capacity rates more than zero if the state determines that the utility still has capacity needs after the competitive solicitation that otherwise could be met through the utility's self-build or purchase options.

at the as-available avoided cost energy rate because the purchasing utility will still be able

424. The Commission has held and we reaffirm here that, when capacity is not needed, the avoided capacity cost rate can be zero. Competitive solicitations conducted pursuant to the rules adopted in this final rule that are held whenever capacity is needed provide QFs a level playing field on which to compete to sell capacity. This approach further shields purchasing electric utilities from situations like those explained by Xcel, where QFs could simply sit out the competitive solicitation process (or participate but not have their bids accepted), but then seek to sell capacity to the purchasing electric utility and to receive a separate higher administratively-determined avoided cost rate including an avoided cost capacity rate, and even potentially displace non-QF competitive

demand (or need) for capacity is zero. That is, when the demand for capacity is zero, the cost for capacity may also be zero.").

⁶⁸⁶ *Id.* at 62,061 ("[A]voided cost rates need not include the cost for capacity in the event that the utility's demand (or need) for capacity is zero. That is, when the demand for capacity is zero, the cost for capacity may also be zero.").

solicitation winners.⁶⁸⁷ This approach benefits ratepayers because allowing QFs to compete in properly conducted, competitive solicitations that are held whenever capacity is needed allows the purchasing utility to obtain needed capacity efficiently. To be clear, the competitive solicitation is not to be a means to determine a QF's right to put as-available energy to the utility. But the competitive solicitation can be the means to determine what, if any, rate the QF will be paid for capacity.

- 425. Multiple commenters point out that using competitive solicitations could be a beneficial way to carry out the Congressional intent behind PURPA. However, many of these same commenters claim that the competitive solicitations carried out to date do not live up to this standard. In other words, commenters assert that the competitive solicitations conducted to date have often not been properly conducted and instead have been unfair. As described above, assertions about specific states' competitive solicitation processes include that:
 - the competitive solicitations conducted in Florida are unfair because they do not require an Independent Evaluator as part of the competitive solicitation process; 688
 - the competitive solicitations conducted in Colorado and Oklahoma are unfair because purchasing electric utilities are allowed to apply for waivers of the competitive solicitation requirement; 689

⁶⁸⁷ See Xcel Comments at 2-3, 9-10.

⁶⁸⁸ Southeast Public Interest Organizations Comments at 27.

⁶⁸⁹ *Id*.

- the competitive solicitations conducted in North Carolina are unfair because the
 incumbent purchasing electric utility can receive preferential treatment in the form
 of waivers of the post bid security otherwise required for any independently owned
 projects;⁶⁹⁰ and
- the competitive solicitations conducted in Nevada are unfair because the process is limited to QFs to meet a small, segregated portion of the utility's energy and unmet capacity requirements.⁶⁹¹
- 426. Commenters also make assertions about unfair practices of purchasing electric utilities, including that the purchasing electric utilities have attempted to reduce QFs' ability to sell while the purchasing electric utilities are simultaneously seeking to build and rate base their own substantial renewable resources.
- 427. The criteria proposed in the NOPR were aimed at ensuring that competitive solicitations are conducted fairly. In this final rule, the Commission finds that, in order to use the results of a competitive solicitation to set avoided cost rates, the competitive solicitation must be conducted in a transparent and non-discriminatory manner. Such a competitive solicitation must be conducted in a process that includes, but is not limited to, the following factors: (i) the solicitation process is an open and transparent process that includes, but is not limited to, providing equally to all potential bidders substantial and meaningful information regarding transmission constraints, levels of congestion, and

⁶⁹⁰ *Id*.

⁶⁹¹ Public Interest Organizations Comments at 71-72.

interconnections, subject to appropriate confidentiality safeguards; (ii) solicitations must be open to all sources, to satisfy that purchasing electric utility's capacity needs, taking into account the required operating characteristics of the needed capacity; (iii) solicitations are conducted at regular intervals; (iv) solicitations are subject to oversight by an independent administrator; and (v) solicitations are certified as fulfilling the above criteria by the relevant state regulatory authority or nonregulated electric utility through a post-solicitation report.

- 428. Without judging the competitive solicitations conducted to date, we find that henceforth any competitive solicitation that does not comply with these factors will be viewed as not transparent and discriminatory, and not a basis for either setting the avoided cost capacity rate that a QF may charge the purchasing electric utility or limiting which generators can receive a capacity rate. Phrased differently, we will presume that any future competitive solicitation that does not comply with the factors adopted in this final rule does not comply with the Commission's regulations implementing PURPA.
- 429. In addition, to further promote fairness, the Commission makes several clarifications, as described below.
- 430. We clarify that competitive solicitations must also be conducted in accordance with the *Allegheny* principles under which the Commission evaluates a competitive solicitation: (1) transparency, a requirement that the solicitation process be open and fair;
- (2) definition, a requirement that the product, or products, sought through the competitive solicitation be precisely defined; (3) evaluation, a requirement that the evaluation criteria be standardized and applied equally to all bids and bidders; and (4) oversight, a

requirement that an independent third party design the solicitation, administer bidding, and evaluate bids prior to selection. While the NOPR's proposed guidelines for competitive solicitations were generally inclusive of the *Allegheny* principles, in order to more precisely define what is and what is not a properly conducted competitive solicitation that can be used to determine what generators will be entitled to an avoided cost capacity rate, and what that rate will be, we specifically clarify here that the *Allegheny* principles apply as well.

431. We also revise the proposed language in 18 CFR 292.304(d)(8)(i) to clarify that participants must be provided with substantial and meaningful information regarding transmission constraints, levels of congestion, and interconnections, subject to appropriate confidentiality safeguards. We believe that it is important that all participants in the competitive solicitation have access to these data as a necessary predicate for a nondiscriminatory competitive solicitation process, and we find that requiring that this information be provided will help ensure that a competitive solicitation is open and transparent. We acknowledge the risk that competitive solicitation participants could use this information to gain a competitive advantage that could be used outside of the competitive solicitation, but find that this risk can be minimized through the use of non-disclosure agreements and placing reasonable limits on those persons permitted to review the information, just as is done in other Commission proceedings where this issue arises.

⁶⁹² *Allegheny*, 108 FERC ¶ 61,082 at P 18.

- 432. We also clarify that the requirement that the competitive solicitation process be open and transparent includes that the electric utility provide the state commission, and make available for public inspection, a post-solicitation report that: (1) identifies the winning bidders; (2) includes a copy of any reports issued by the independent evaluator; and (3) demonstrates that the solicitation program was implemented without undue preference for the interests of the purchasing utility or its affiliates. We find this consistent with the requirement that competitive solicitations be open and transparent, to not only ensure that utilities are not discriminating against QFs, but also to help all stakeholders and the public at large better understand the utility's competitive solicitation processes and thus to be confident in the fairness of the process and of the results.
- 433. Regarding the requirement that solicitations must be open to all sources to satisfy the purchasing electric utility's capacity needs, taking into account the required operating characteristics of the needed capacity, we decline to remove the phrase "taking into account the operating characteristics of the needed capacity." There may be times when a utility needs capacity with specific attributes, such as specific ramping capability, that cannot be filled by certain types of generators. However, we agree with Public Interest Organizations that this phrase may not be used to define characteristics of only non-QF generation or to allow a utility to select favored generators. ⁶⁹³
- 434. We decline to be overly prescriptive as to what constitutes "regular intervals." In general, utilities should be reviewing their capacity needs frequently, and the state or

⁶⁹³ Public Interest Organizations Comments at 73.

nonregulated electric utility is in the best position to determine the frequency of that review. However, there may be times when a utility's review of capacity needs reveals that no capacity is needed, and it would not make sense for a competitive solicitation to be mandated at such a time.

435. We similarly decline to be overly prescriptive as to what constitutes an "independent administrator." Commenters argue on both sides whether the NOPR proposal goes too far or not far enough. On the one hand, NRECA argues that states are in the best position to determine the need for oversight by an independent administrator and recommends this criterion be deleted. On the other hand, Colorado Independent Energy notes that independent administrators are often employed by utilities and thus sometimes reluctant to offer third party criticism of the bid evaluation process. We clarify that the independent administrator, who is responsible for administering the competitive solicitation, must be an entity independent from the purchasing electric utility in order to help ensure fairness. Whether the entity is called an independent administrator or a third-party consultant, the substantive requirement of this factor is that the competitive solicitation not be administered by the purchasing electric utility itself or its

⁶⁹⁴ NRECA Comments at 11. In this final rule, we note, for ease of readability we have used the word "state" to refer to both state regulatory authorities and to nonregulated electric utilities. Thus, in the context of nonregulated electric utilities in particular, to say that the "state" can fairly administer the competitive solicitation is to say that the nonregulated electric utility can, essentially, be both the purchasing electric utility and potentially the independent administrator of its own competitive solicitation. That is a result we cannot countenance.

⁶⁹⁵ Colorado Independent Energy Comments at 8.

affiliates, but rather by a separate, unbiased, and unaffiliated entity not subject to being influenced by the purchasing utility. We recognize, however, that such an independent administrator will need to be selected and paid. Though we are not directing a process, we note that the selection and payment could be done under the auspices of a state regulatory authority or by mutual agreement between the utility and the competitive solicitation participants.

- In response to the Montana Commission's request for clarification as to what "certified" means within the guideline that requires certification of the competitive solicitation by the state regulatory authority or nonregulated electric utility as fulfilling the above criteria, we clarify that, after a thorough review of the competitive solicitation procedures used and the competitive solicitation results, certification of the competitive solicitation requires a written, formally-issued finding by the state that the competitive solicitation and its results comply with PURPA and this Commission's PURPA regulations – and must include the independent administrator's report to the same effect. We decline at this time to add any additional requirements for competitive 437. solicitations. We continue to believe that states may be in the best position to consider their particular local circumstances. We think that the guidelines adopted here, in conjunction with the *Allegheny* principles and other clarifications made here, provide an adequate framework for competitive solicitations to be conducted efficiently, transparently and in a nondiscriminatory manner.
- 438. We also clarify that, if a competitive solicitation is not conducted fairly and in accordance with the guidelines here, then an aggrieved entity may challenge the state's

competitive solicitation in the appropriate forum, which could include any one or more of the following: (1) initiating or participating in proceedings before the relevant state commission or governing body; (2) filing for judicial review of any state regulatory proceeding in state court (under PURPA section 210(g)); or, alternatively (3) filing a petition for enforcement against the state at the Commission and, if the Commission declines to act, later filing a petition against the state in U.S. district court (under PURPA section 210(h)(2)(B)).

iii. Other Requests

439. We decline to grant Solar Energy Industries request to require that solicitations be linked with the purchasing electric utility's IRP. Where a state has an IRP,⁶⁹⁶ it may make sense to link the competitive solicitation processes with the IRP so that the competitive solicitation is conducted for the entirety of a utility's anticipated capacity needs. On the other hand, IRPs may come in a variety of forms. For example, an IRP may merely be a general projection of short- and long-term load growth and potential resources to meet such growth, and each generation project may be subject to specific approval based on actual specific need. In order to provide states flexibility in conducting these processes, we will not require such links between competitive solicitations and IRPs, although such links certainly are permitted if a state deems it to be appropriate.

⁶⁹⁶ 16 U.S.C. 2621(a), (d)(7) (requiring states to consider whether to employ integrated resource planning).

440. Regarding facilities not designed primarily to sell electricity to the purchasing electric utility, such as waste to power small power production facilities and cogeneration facilities, we find that an exemption from competitive solicitation processes is unnecessary. We do not exempt small power production facilities from the competitive solicitation process; we are not persuaded that such an exemption is appropriate given that exempting large classes of small power producers could frustrate the price discovery function of the competitive solicitation. A large number of exempted small facilities could disrupt the competitive solicitation process. We clarify, however, that QFs whose capacity is 100 kW or less already are entitled to standard rates regardless of whether they compete in a competitive solicitation and we do not change that regulation in this final rule. 697 Given that we view competitive solicitations as an important price discovery tool and that states already are required to establish standard rates for such entities, there is no need to determine prices for QFs at 100 kW or less through a competitive solicitation. 441. The Commission clarifies that any competitive solicitation conducted may not force alteration of existing OF contracts. A OF receiving a capacity payment is entitled to that payment for the duration of the term of its contract, and a competitive solicitation is necessarily forward looking based on the results of that auction.

⁶⁹⁷ See 18 CFR 292.304(c).

C. Relief from Purchase Obligation in Competitive Retail Markets

1. NOPR Proposal

- 442. The Commission in the NOPR proposed to add regulatory text at the end of § 292.303(a) of the PURPA Regulations to provide that a utility's purchase obligation may be reduced to the extent the purchasing electric utility's supply obligation has been reduced by a state retail choice program. The Commission stated that it was reasonable for electric utilities' PURPA capacity purchase obligations to be reduced to the extent retail choice reduces their supply obligations. To the extent Provider of Last Resort (POLR) supplies are obtained through solicitations having a particular contract term such as one year, the Commission proposed that the length of the utility's PURPA purchase contract should match the term of the POLR supply solicitation contracts in order to more accurately reflect the utility's avoided costs.
- 443. The Commission proposed, through this change, to provide that state regulatory authorities and nonregulated electric utilities have flexibility to respond to the possibility that, over time, a utility's POLR supply obligation may decrease (or increase). The Commission intended that this proposal would apply prospectively from the effective date of a final rule and would not disturb contracts in effect at the time the utility's supply obligation is reduced.

2. Comments

444. APPA, DTE Electric, EEI, Institute for Energy Research, NorthWestern, NRECA, Pennsylvania Commission, Portland General, and We Stand for Energy filed comments in support of the Commission's proposal to provide that the purchase obligation may be

reduced to the extent the purchasing electric utility's supply obligation has been reduced by a state retail choice program.⁶⁹⁸

Organizations filed opposing comments arguing that the Commission lacks the statutory authority to implement this proposal because the Commission lacks discretion to reduce an electric utility's mandatory purchase obligation except through PURPA section 210(m). New England Small Hydro claims that PURPA section 210(a) clearly states that electric utilities must purchase the electric energy from QFs, and that the Commission does not have the authority to deviate from the statute. NIPPC, CREA, REC, and OSEIA argues that the Commission's existing regulations adequately address the concern at issue because any reduction in the long-term capacity needs of the utility due to retail access should be reflected in avoided capacity rates offered to QFs. Public Interest Organizations claim that the Commission proposes to remove state authority by requiring QF contracts with a POLR to match the term of the POLR's other supply contracts.

⁶⁹⁸ APPA Comments at 20; DTE Electric Comments at 4-5; EEI Comments at 41-42; Institute for Energy Research Comments at 1-2; NorthWestern Comments at 8; NRECA Comments at 13-14; Pennsylvania Commission Comments at 6-7; Portland General Comments at 12-13; and We Stand Comments at 1.

⁶⁹⁹ New England Small Hydro Comments at 15-16; NIPPC, CREA, REC, and OSEIA Comments at 68-69; and Public Interest Organizations Comments at 74-75.

⁷⁰⁰ New England Small Hydro at 16 (citing *Chevron U.S.A., Inc. v. Nat. Res. Def. Council*, 467 U.S. 837 (1984)).

⁷⁰¹ NIPPC, CREA, REC, and OSEIA Comments at 69.

⁷⁰² Public Interest Organizations Comments at 74.

Public Interest Organizations also state that even if the Commission had such authority, there is no evidence in the record to support matching QF contract lengths with a POLR's other supply contracts. Public Interest Organizations also assert that the Commission's proposal unlawfully discriminates against QFs to the extent that it fails to treat QF contracts in parity with any of a POLR's other supply contracts. ⁷⁰³

446. Biogas and Covanta argue that the rationale for this proposal is unclear and that the NOPR fails to justify the reduction of a utility's obligation to purchase QF power based on the amount of any non-utility generator's supply into the utility's service territory. 704

Covanta states that the NOPR incorrectly concludes that all public power is renewable power. 705 Biogas and Covanta assert that the existence of a competitive retail market does not mean there is a competitive retail market for biogas or waste-to-energy QFs. 706

Biogas and Covanta also argue that the NOPR would reduce that already limited market by providing greater leverage to the purchasing electric utility, and urge the Commission to remove barriers to local government options for energy purchase rates.

447. Ohio Commission Energy Advocate states that under Ohio law, an electric distribution utility is required to provide consumers within its certified territory a standard service offer of all competitive retail electric services necessary to maintain essential

⁷⁰³ *Id.* at 75.

⁷⁰⁴ Biogas Comments at 2; Covanta Comments at 9.

⁷⁰⁵ Covanta Comments at 9.

⁷⁰⁶ Biogas Comments at 2; Covanta Comments at 9-10.

electric services to customers, including a firm supply of electric generation services. ⁷⁰⁷ Ohio Commission Energy Advocate claims that all PUCO-regulated electric distribution utilities satisfy this obligation through competitive solicitation for default service within the context of an electric security plan. ⁷⁰⁸ Ohio Commission Energy Advocate believes that the electric distribution utility should retain the full purchase obligation because the regulated utility maintains the obligation to serve as the POLR for all "wires-connected" customers. ⁷⁰⁹ Ohio Commission Energy Advocate also states that it is concerned by the lack of alternatives to the mandatory purchase obligation and would question any interpretation of PURPA that contemplates a scenario where no entity has a purchase obligation for a OF. ⁷¹⁰

448. ELCON, California Utilities, Chamber of Commerce, Connecticut Authority, and Michigan Commission request further clarification on how the Commission's proposal will be implemented. ELCON states that industrial customers conditionally support the reduction in obligation to purchase based on a state retail choice program, subject to the development of clear and enforceable criteria that exclude mandatory purchase obligation relief for default supply obligations that utilities meet with their own generation.⁷¹¹

⁷⁰⁷ Ohio Commission Energy Advocate Comments at 5.

⁷⁰⁸ *Id.* at 6.

⁷⁰⁹ *Id.* at 6-7.

⁷¹⁰ *Id*.

⁷¹¹ ELCON Comments at 19.

Similarly, California Utilities state that because of the various ways states have developed restructured retail markets, the Commission should provide additional guidance as to the various ways that state commissions can address load reductions due to retail choice while protecting legacy utilities. 712 California Utilities explain that they need Commission guidance to ensure that cost recovery for past and future mandated QF purchases is equitable to the remaining retail customers in the legacy utilities' distribution service areas and that future PURPA mandates or costs are fairly allocated consistent with costcausation principles.⁷¹³ Chamber of Commerce states that the Commission should clarify that the reduction in a utility's QF purchase obligation is measured against the amount of a utility's load that has elected an alternative supplier, as opposed to eligible load.⁷¹⁴ Chamber of Commerce claims that in certain states, only a portion of an electric utility's load is eligible to select an alternative electricity supplier and that such percentage would serve as the limit for any corresponding reduction in a utility's QF purchase obligation. Michigan Commission states that its retail choice program caps retail choice at 10 percent of an electric utility's retail customer demand, and seeks clarification on (1) whether the reduction in a utility's purchase obligation would equal the reduction in its supply obligation, be based on the percentage of its customer demand participating in the state's

⁷¹² California Utilities Comments at 5.

⁷¹³ *Id.* at 7.

⁷¹⁴ Chamber of Commerce Comments at 5.

retail choice program, or some other metric; and (2) how fluctuations in the state's retail choice program and resulting purchase obligation should be addressed.⁷¹⁵

- 449. Connecticut Authority supports the proposal to modify distribution utilities' must-purchase obligations. The Connecticut Authority states that since Connecticut's electric industry restructuring, distribution utilities' purchases of QF output have not been used to serve retail customers, rather the distribution utility acts as an intermediary selling output into the New England markets. Connecticut Authority asserts that the Commission should clarify that the state regulatory authority is responsible for determining the appropriate adjustment to the distribution utility's must-purchase obligation and providing notice of such determination to the Commission.
- 450. Connecticut Authority claims that QF output is different from, and cannot be substituted in for, distribution utility-provided default standard or last resort services. Connecticut Authority explains that standard service is procured in six-month tranches, last resort service is procured in three-month tranches, and that distribution utilities do not self-manage their default service supply portfolios.⁷¹⁸
- 451. Connecticut Authority states that while it agrees that matching the contract terms for default service supply and QF supply could potentially reduce the burden of over-

⁷¹⁵ Michigan Commission Comments at 5-6.

⁷¹⁶ Connecticut Authority Comments at 16.

⁷¹⁷ *Id.* at 17.

⁷¹⁸ *Id*.

estimated avoided costs and give states flexibility to respond quickly to changes to a distribution utility's default supply obligation, the Commission should not mandate any term length for the mandatory purchase obligation.⁷¹⁹ Instead, Connecticut Authority asserts that the Commission should allow the state to establish the term based on state-specific circumstances.

- 452. California Utilities request that the Commission reaffirm that all alternative retail suppliers, including Electric Service Providers (ESP) and Community Choice Aggregators (CCA), are electric utilities subject to the PURPA purchase obligation. California Utilities explain that ESPs and CCAs are the two types of entities that California allows to sell power to retail customers in the distribution service territories of CPUC-regulated utilities, and argues that such entities meet the definition of electric utility used in PURPA.
- 453. California Utilities state that the Commission should clarify that a state has no authority to exempt any traditional or alternative retail supplier from the PURPA mandatory purchase obligation in order to ensure QFs that there is a robust market to sell their energy and capacity to entities that actually serve load in the event a legacy utility is relieved of all or part of its PURPA obligations.⁷²² California Utilities also state that the

⁷¹⁹ *Id.* at 18.

⁷²⁰ California Utilities at 9.

⁷²¹ *Id.* at 9-10.

⁷²² *Id*. at 11.

Commission should clarify that alternative retail suppliers must make avoided cost information publicly available to allow QFs to locate and identify potential buyers that may have higher avoided costs than legacy utilities that have lost load and may no longer have capacity needs.

454. California Utilities argue that for states such as California that allow alternative retail suppliers to opt out of procuring capacity and require legacy utilities to provide capacity on their behalf, it would be unfair for legacy utilities to pay a QF any amount for energy greater than the LMP unless the price differential for which the legacy utility can sell the energy in the market is paid for by the alternative retail supplier that was short on capacity. California Utilities explain that this would prevent cost shifts to customers who remain with the legacy utility such that all costs associated with the mandatory PURPA purchases made by the legacy utility on behalf of the alternative retail supplier would be borne by customers of the alternative retail supplier. California Utilities also argue that the Commission should clarify that if legacy utilities are required to procure capacity from QFs on behalf of alternative retail suppliers, states must require alternative retail suppliers to pay for such QF purchases at the avoided cost rate set by the state for the legacy utility for capacity.

455. California Utilities urge the Commission to adopt a stranded cost regulation addressing PURPA obligations incurred by legacy utilities that lose load to retail

⁷²³ *Id.* at 12.

⁷²⁴ *Id*. at 13.

competition consistent with the cost recovery guarantee in PURPA section 210(m)(7)(A).⁷²⁵ California Utilities argue that such regulation should be clear that prudently incurred costs include any costs associated with a purchase under a statemandated contract. California Utilities propose new language to § 292.304(g) regarding implementation of the cost recovery mandate in section 210(m)(7)(A) of PURPA stating, in part, that "[a] state commission may not find any costs associated with any legally enforceable obligation that it has imposed on an electric utility imprudent."⁷²⁶

3. <u>Commission Determination</u>

456. In this final rule, we decline to adopt the proposed regulation permitting states with retail competition to allow relief from the purchase obligation. We instead clarify that the Commission's existing PURPA Regulations already require that states, to the extent practicable, must account for reduced loads in setting QF rates.

457. Specifically, 18 CFR 292.304(e)(3) already does and will continue to allow states, when setting avoided cost rates, to take into account "the ability of the electric utility to avoid costs, including the deferral of capacity additions." We regard this existing regulation as allowing a state to consider reductions in a purchasing electric utility's supply obligations given retail competition and the purchasing electric utility's POLR obligations under state law. We further clarify that this clarification is not intended to be reflected as a MW-for-MW reduction (or increase) based on yearly changes in load and

⁷²⁵ *Id.* at 14.

⁷²⁶ *Id*. at 15.

therefore does not and may not serve to terminate a purchasing utility's mandatory purchase obligation under PURPA section 210(a).⁷²⁷

D. Evaluation of Whether QFs are at Separate Sites

1. Rebuttable Presumption of Separate Sites

a. NOPR Proposal

458. The Commission proposed to allow entities challenging a QF certification to rebut the presumption that affiliated facilities located more than one mile apart are considered to be separate QFs. The Commission proposed that this change would be effective as of the date of the final rule, which means that such challenges could only be made to QF certifications and recertifications that are submitted after the effective date of the final rule in this proceeding.

459. The Commission proposed that an entity can seek to rebut the presumption only for those facilities that are located more than one mile apart and less than 10 miles apart. The Commission believed that, just as there are some facilities that may be so close that it is reasonable to irrebuttably treat them as a single facility (those a mile or less apart), so there are some facilities that are sufficiently far apart that it is reasonable to treat them as irrebuttably separate facilities. That latter distance, the Commission believed, is 10 miles or more apart. Thus, if two affiliated facilities are one mile or less apart, they would

⁷²⁷ 18 CFR 292.304(e)(3).

 $^{^{728}}$ NOPR, 168 FERC ¶ 61,184 at P 101. As discussed in detail in section IV.D.1.d below, this final rule will change the references to "separate facilities" or "the same facility" to "at separate sites" or "at the same site."

continue to be irrebuttably presumed to be a single facility at a single site. If affiliated facilities are 10 miles or more apart, they would be irrebuttably presumed to be separate facilities at separate sites.

The Commission proposed that if affiliated facilities are more than one mile apart 460. and less than 10 miles apart, there would still be a presumption, but it would be a rebuttable presumption, that they are separate facilities at separate sites. Purchasing electric utilities and others thus would be able to file a protest attempting to rebut the presumption for facilities more than one mile apart and less than 10 miles apart and argue that they should be treated as a single facility. The Commission could also act *sua sponte*. The Commission proposed that self-certifications will remain effective after a protest has been filed, until such time as the Commission issues an order revoking the certification. The Commission proposed allowing an entity seeking QF status to provide further 461. information in its certification (both self-certification and application for Commission certification), to preemptively defend against rebuttal by asserting factors that affirmatively show that the affiliated facilities are indeed separate facilities at separate sites. 729 Anyone challenging the QF certification would be allowed to assert factors to show that the facilities are actually part of the same, single facility.

⁷²⁹ While a QF with a net power production capacity of 1 MW or less is not required to formally certify its QF status (either through a self-certification or application for Commission certification), if the QF's status is later challenged (i.e., by a petition for declaratory order), the QF would be able to respond by affirmatively demonstrating that its facilities are not located at the same site as other affiliated facilities and thus that the QF does not exceed the 80 MW size limitation.

- 462. The Commission proposed limiting protests challenging QF status by requiring any entity filing a protest to specify facts that make a prima facie demonstration that the facility described in the self-certification, self-recertification, or Commission certification does not satisfy the requirements for QF status. General allegations or unsupported assertions would not be a basis for denial of certification. The Commission further proposed limiting protests to QF status by requiring that once the Commission has affirmatively certified an applicant's QF status through either a Commission certification proceeding or in response to protests challenging QF status, any later protest to a QF's existing certification asserting that facilities further than one mile apart are part of a single QF must demonstrate changed circumstances that call into question the continued validity of the earlier certification.
- 463. The Commission proposed that physical and ownership factors may be asserted to rebut or defend against rebuttal. Noting that no single factor would be dispositive, the Commission proposed the following factors: (1) physical characteristics including such common characteristics as: infrastructure, property ownership, interconnection agreements, control facilities, access and easements, interconnection facilities up to the point of interconnection to the distribution or transmission system, collector systems or facilities, points of interconnection, motive force or fuel source, off-take arrangements, property leases, and connections to the electrical grid; and (2) ownership/other characteristics, including such characteristics as whether the facilities in question are: owned or controlled by the same person(s) or affiliated persons(s), operated and maintained by the same or affiliated entity(ies), selling to the same electric utility, using

common debt or equity financing, constructed by the same entity within 12 months, managing a power sales agreement executed within 12 months of a similar and affiliated facility in the same location, placed into service within 12 months of an affiliated project's commercial operation date as specified in the power sales agreement, or sharing engineering or procurement contracts. The Commission solicited comments on whether the Commission should rely on some or any of these factors, or other factors, or whether the various factors should be considered together and weighed.

464. The Commission stated that it will continue to rely on its definition of "affiliate" provided in 18 CFR 35.36(a)(9), and noted that subsection (iii) provides that the Commission may determine, after appropriate notice and opportunity for hearing, that a person stands in such relation to a specified company that there is likely to be an absence of arm's-length bargaining in transactions between them as to make it necessary or appropriate in the public interest or for the protection of investors or consumers that the person be treated as an affiliate. The Commission intended, when applying its rules on separate facilities, to consider this provision of its regulations, when entities otherwise would not be deemed affiliates under the other provisions of the definition, to determine whether a person nevertheless should be treated as an affiliate. In doing so, the Commission stated that it could take into consideration many of the same factors that would reasonably be considered in evaluating whether facilities located over one and less than 10 miles apart are a single facility or separate facilities.

⁷³⁰ 18 CFR 35.36(a)(9)(iii).

465. The Commission believed that this change, together with the proposed definition of "electrical generating equipment" and revision to the FERC Form No. 556, would more closely align with Congress's requirement that QFs seeking to certify as small power production facilities are in fact below the 80 MW statutory limit for such facilities.⁷³¹

b. Commission Determination

466. As further discussed and revised in the following sections, we adopt the NOPR proposal. Henceforth, if a small power production facility seeking QF status is located one mile or less from any affiliated small power production QFs that use the same energy resource, it will be irrebuttably presumed to be at the same site as those affiliated small power production QFs. If a small power production facility seeking QF status is located ten miles or more from any affiliated small power production QFs that use the same energy resource, it will be irrebuttably presumed to be at a separate site from those affiliated small power production QFs. If a small power production facility seeking QF status is located more than one mile but less than ten miles from any affiliated small power production QFs that use the same energy resource, it will be rebuttably presumed to be at a separate site from those affiliated small power production QFs.

467. We adopt the proposal to allow a small power production facility seeking QF status to provide further information in its certification (both self-certification and application

⁷³¹ See 16 USC 796(17)(A)(ii) (defining small power production facility as, *inter alia*, "a facility which is an eligible solar, wind, waste, or geothermal facility, or a facility which—. . . has a power production capacity which, together with any other facilities located at the same site (as determined by the Commission), is not greater than 80 megawatts").

for Commission certification) or recertification (both self-certification and application for Commission recertification), to preemptively defend against anticipated challenges by identifying factors that affirmatively show that its facility is indeed at a separate site from affiliated small power production QFs that use the same energy resource and that are more than one but less than 10 miles from its facility. We will correspondingly allow any interested person or entity to challenge a QF certification (both self-certification and application for Commission certification) or recertification (both self-recertification or application for Commission recertification) that makes substantive changes to the existing certification as further described below).⁷³²

- 468. As explained in section IV.D.1.f below, we adopt the NOPR's proposed factors, with certain additions.
- 469. We adopt the proposal to clarify that challenges to QF status require that the interested person or entity filing a protest must specify facts that make a prima facie demonstration that the facility described in the certification (both self-certification and application for Commission certification) or recertification (both self-recertification and application for Commission recertification) does not satisfy the requirements for QF status. Additionally, any protest must be adequately supported, with supporting documents, contracts, or affidavits, as appropriate. General allegations or unsupported assertions will not provide a basis for denial of certification or recertification. We

⁷³² We note that a protester must separately file for intervention seeking to be made a party to the proceeding; the filing of a protest does not make that person or entity a party. 18 CFR 385.102(c), 385.211(a)(2).

additionally limit protests, as described more fully in section IV.E below, by clarifying that protests may be made to an initial certification (both self-certification and application for Commission certification) filed on or after the effective date of this final rule, but only to a recertification (both self-recertification and application for Commission recertification) filed on or after the effective date of this final rule that makes substantive changes to the existing certification. We adopt the proposal to limit protests by requiring that once the Commission has affirmatively certified an applicant's QF status in response to a protest opposing a self-certification or self-recertification, or in response to an application for Commission certification or recertification, any later protest to a recertification (self-recertification or application for Commission recertification) making substantive changes to a QF's existing certification must demonstrate changed circumstances from the facts on which the Commission acted on the certification filing that call into question the continued validity of the earlier certification. ⁷³³ Finally, the Commission retains the discretion to summarily reject protests where a protest reiterates arguments already made against the same QF that the Commission previously denied or otherwise rejected.

⁷³³ An interested person or entity can choose to file a petition for declaratory order, with fee, at any time (that is, not only within 30 days from the date of the filing of the Form No. 556). However, if the Commission has affirmatively certified an applicant's QF status in response to a protest opposing a self-certification or self-recertification, or in response to an application for Commission certification or recertification, any later petition for declaratory order protesting the QFs existing certification must demonstrate changed circumstances from the time the Commission acted on the certification that call into question the continued validity of the earlier certification.

c. Need for Reform

i. <u>Comments</u>

470. Multiple parties have expressed concern that some QF developers of small power production facilities are circumventing the one-mile rule, and thereby circumventing PURPA, by strategically siting small power production facilities that use the same energy resource slightly more than one mile apart in order to qualify as separate small power production facilities.⁷³⁴ Several commenters state that the NOPR-proposed changes will reduce the opportunity for gaming.⁷³⁵

471. Several commenters argue, to the contrary, that there is no evidence of gaming of the current one-mile rule.⁷³⁶ Con Edison argues that utilities are not overwhelmed with QFs using the one-mile rule and there is little to no evidence to the contrary.⁷³⁷ sPower

⁷³⁴ See APPA Comments at 21; Center for Growth and Opportunity Comments at 5-6; Consumers Energy Comments at 4; East River Comments at 1-2; EEI Comments at 43; ELCON Comments at 35; Governor of Idaho Comments at 1; Idaho Commission Comments at 5-7; Idaho Power Comments at 13; Missouri River Energy Comments at 5; Mr. Moore Comments at 2; Northern Laramie Range Alliance Comments at 2; NorthWestern Comments at 9; NRECA Comments at 14-15; Portland General Comments at 14.

⁷³⁵ APPA Comments at 21; Center for Growth and Opportunity Comments at 5-6; Consumers Energy Comments at 4; East River Comments at 1-2; EEI Comments at 43; ELCON Comments at 35; Governor of Idaho Comments at 1; Idaho Commission Comments at 5-7; Idaho Power Comments at 13; Missouri River Energy Comments at 5; Mr. Moore Comments at 2; Northern Laramie Range Alliance Comments at 2; NorthWestern Comments at 12; NRECA Comments at 14-15; Portland General Comments at 14.

⁷³⁶ Solar Energy Industries Comments at 51; Southeast Public Interest Organizations Comments at 31; SC Solar Alliance Comments at 19.

⁷³⁷ Con Edison Comments at 5.

states that it is difficult to see how developers that comply with this clear bright-line rule could be said to be circumventing.⁷³⁸ New England Small Hydro argues that the Commission is attempting to address perceived abuses of the 80 MW limitation by burdening projects that do not abuse the system.⁷³⁹

ii. Commission Determination

A72. The record shows that, since the establishment of the one-mile rule in the PURPA Regulations in 1980, the development of large numbers of affiliated renewable resource facilities, requires a revision of the one mile-rule. We find that the final rule will reduce the opportunity for developers of small power production facilities to circumvent the current one-mile rule by strategically siting small power production facilities that use the same energy resource slightly more than one mile apart. While such circumvention may not be an everyday occurrence, we agree with commenters that the record demonstrates it is still a sufficient possibility under the current regulations that the Commission is justified in addressing it in order to comply with the statute. The final

⁷³⁸ sPower Comments at 5.

⁷³⁹ New England Small Hydro Comments at 17.

⁷⁴⁰ The regulation, in practice, is only of consequence if the facilities located "at the same site" would exceed a power production capacity of 80 MW, as that is the size limit for a small power production facility to qualify as a QF. 16 U.S.C. 796(17)(A)(ii).

⁷⁴¹ See APPA Comments at 21; Center for Growth and Opportunity Comments at 5-6; Consumers Energy Comments at 4; East River Comments at 1-2; EEI Comments at 43; ELCON Comments at 35; Governor of Idaho Comments at 1; Idaho Commission Comments at 5-7; Idaho Power Comments at 13; Missouri River Energy Comments at 5; Mr. Moore Comments at 2; Northern Laramie Range Alliance Comments at 2; NorthWestern Comments at 9; NRECA Comments at 14-15; Portland General Comments

rule, as adopted, still retains the presumption that small power production QFs more than one mile apart are located at separate sites, but simply makes the presumption rebuttable for small power production QFs located more than one mile but less than 10 miles apart, allowing the Commission the ability to address those circumstances.

d. Site Definition

i. <u>Comments</u>

Commission found that "the critical test under PURPA relates to whether the facilities are located at one site rather than whether they are integrated as a project." Solar Energy Industries argue that the proposed rule, as drafted, abandons the focus on whether the facilities are located at one site and transforms it into an analysis as to whether affiliated QFs are part of the same project. Solar Energy Industries similarly contend that it is arbitrary to change from a "same site" to an "integrated project" standard. NIPPC, CREA, REC, and OSEIA state that the existing rule is a reasonable means of implementing the statutory phrase "same site," particularly given the statutory directive to encourage QF development, and state that they prefer the current bright line rule. Allco argues that the proposed rule is divorced from the statutory use of "site." Allco

at 14.

⁷⁴² Solar Energy Industries Comments at 60 (quoting *El Dorado Cty. Water Agency*, 24 FERC \P 61,280, at 61,578 (1983)).

⁷⁴³ *Id.* at 61-62.

⁷⁴⁴ NIPPC, CREA, REC, and OSEIA Comments at 70.

asserts that the Commission lacks authority to define the term "site" in a manner other than one reasonably related to its ordinary meaning and argues that the Commission's definition of site arbitrarily limits QF development for no apparent reason.⁷⁴⁵ The DC Commission would like the Commission to leave the resolution of certain disputes over whether QFs are separate to state commissions.⁷⁴⁶ Idaho also requests that states be given as much discretion as possible.⁷⁴⁷

475. EEI states that the interpretation of "same site" is determined by the Commission, and that there is nothing in the statute that prevents the Commission from modifying its interpretation of the term "same site."⁷⁴⁸

ii. <u>Commission Determination</u>

476. We modify the NOPR proposal to change terminology relating to the determination of whether small power production facilities are separate facilities to focus not on whether they are *separate facilities*, but rather to mirror the statutory language and thus focus on whether they are at "the same site." In that regard, we change references to "separate facilities" or "the same facility" to "at separate sites" or "at the same site."

477. The NOPR refers to determining whether affiliated facilities are "separate facilities" or "a single facility." However, both the statute and the existing regulations

⁷⁴⁵ Allco Comments at 16.

⁷⁴⁶ DC Commission Comments at 9.

⁷⁴⁷ Idaho Comments at 1.

⁷⁴⁸ EEI Comments at 42.

contemplate that the Commission will determine what is "the same site," 749 and do not require the Commission to determine whether two facilities are a single facility. The statute defines a small power production facility as an eligible facility, which, together with other facilities located at the same site (as determined by the Commission), has a power production capacity no greater than 80 MW, 750 and the Commission's regulations have long approached the matter as defining how to determine "the same site." We find that the Commission's determination of whether or not a small power production facility is a QF (i.e., exceeds a power production capacity of 80 MW) should continue to be focused on whether the small power production facility seeking QF status and other nearby affiliated small power production QFs are at the same site or at separate sites. 478. We also modify the NOPR proposal to change the irrebuttable and rebuttable presumptions regarding affiliated facilities to instead apply to affiliated *small power* production qualifying facilities. As noted, the NOPR refers to determining whether affiliated facilities are "separate facilities" or "a single facility." We find that only affiliated small power production OFs are relevant to the determination of whether the small power production facility seeking QF status and other nearby facilities are at the same site or separate sites. 752 Correspondingly, as further detailed below, we will allow

⁷⁴⁹ 16 U.S.C. 796(17)(A)(i); 18 CFR 292.204(a).

⁷⁵⁰ 16 U.S.C. 796(17)(A)(i).

⁷⁵¹ 18 CFR 292.204(a).

⁷⁵² We note, however, that, in the context of a PURPA section 210(m) proceeding, *all* affiliates are relevant in evaluating whether a QF has nondiscriminatory access to a

entities challenging a QF certification (both self-certification and application for Commission certification) or recertification (both self-recertification and application for Commission recertification) to rebut the presumption that a small power production facility seeking QF status is at a separate site from any affiliated small power production QFs that use the same energy resource and that are located more than one but less than 10 miles from it.⁷⁵³

479. We therefore modify the language proposed in the NOPR. In sum, we find that if a small power production facility seeking QF status is located one mile or less from any affiliated small power production QFs that use the same energy resource, it will be irrebuttably presumed to be "at the same site" as those affiliated small power production QFs (rather than a single facility at a single site, as proposed in the NOPR). The Commission finds that if a small power production facility seeking QF status is located ten miles or more from any affiliated small power production QFs that use the same energy resource, it will be irrebuttably presumed to be at a separate site from those affiliated small power production QFs (rather than separate facilities at separate sites, as proposed by the NOPR). We find that if a small power production facility seeking QF status is located more than one but less than ten miles from any affiliated small power production OFs that use the same energy resource, it will be rebuttably presumed to be at a separate

competitive market.

⁷⁵³ Though not at issue here, we also note that the facilities need to use the same energy resource. 18 CFR 292.204(a)(1).

site from those affiliated small power production QFs (rather than separate facilities at separate sites, as proposed in the NOPR).

- Purchasing electric utilities and others will be able to file a protest and identify factors attempting to rebut the presumption for a small power production facility seeking OF status that has an affiliated small power production OF that uses the same energy resource more than one but less than 10 miles from it, and argue that the small power production facility seeking OFs status should be treated as "at the same site" as the affiliated small power production QF located more than one but less than 10 miles from it (rather than as a single facility, as proposed in the NOPR). We will allow a small power production facility seeking QF status to provide further information in its certification (both self-certification and application for Commission certification) or recertification (both self-recertification and application for Commission recertification) to preemptively defend against rebuttal by identifying factors that affirmatively show that its facility is indeed at a separate site from an affiliated small power production OF located more than one but less than 10 miles from it (rather than separate facilities at separate sites, as proposed in the NOPR).
- 481. Regarding the requests to allow states to decide whether affiliated small power production QFs are located at separate sites, we note that, in PURPA section 201, now codified in section 3 (17) of the FPA, Congress authorized the Commission to determine whether the applicant and other facilities are located at the same site. This Commission will therefore continue to make these determinations.

e. Distance Between Facilities

i. <u>Comments</u>

- 482. Several commenters contend that the proposal to institute a rebuttable presumption for facilities that are more than one mile but less than 10 miles apart is arbitrary and lacks sufficient supporting evidence.⁷⁵⁴ ELCON notes that the choice of 10 miles as the threshold is not supported by any evidence.⁷⁵⁵
- 483. Regarding the proposed rebuttable presumption for QFs more than one but less than 10 miles apart, Terna Energy argues that the NOPR effectively increases the "exclusion zone" around a QF's electrical generating equipment from approximately three square miles (3.1415 square miles, the circle with one-mile radius around the QF's electrical generating equipment, assuming a point generating source) to over 300 square miles (i.e. a 10-mile radius circle), a 100-times increase to the "exclusion area" for a single QF.⁷⁵⁶
- 484. New England Small Hydro notes that hydroelectric generators are located where river conditions are ideal for generating and that, while they are not generally located

⁷⁵⁴ Allco Comments at 16; Ares Comments at 7; Borrego Solar Comments at 4; ELCON Comments at 19; Public Interest Organizations Comments at 93; SC Solar Alliance Comments at 17; Solar Energy Industries Comments at 60, 62.

⁷⁵⁵ ELCON Comments at 35-36.

⁷⁵⁶ Terna Energy Comments at 4.

within one mile, there may be some projects owned by affiliates that are within 10 miles of each other.⁷⁵⁷

Borrego Solar opposes applying the proposed changes to the one-mile rule to distributed generation and finds that it would restrict the ability of developers to follow market signals when locating projects and significantly increase the regulatory burden. Borrego Solar notes that there are several reasons that otherwise different projects from the same company would be within 10 miles of each other, including land zoning restrictions, available substation capacity, and optimal topology or insolation. ⁷⁵⁸ Borrego Solar notes that it is common for projects on the distribution system to be within two miles of a substation or three-phase lines to reduce interconnection costs. Borrego Solar states that it is also common for multiple unaffiliated developers to site their projects in a single area within just a few miles of each other, and later sell those projects to a single entity much later in the process, inadvertently violating the Commission's rules. 759 Borrego Solar would like the Commission to exclude projects directly interconnected to the distribution system or initially developed by different entities from any presumption of common development. Borrego Solar urges the Commission to, at a minimum, establish a streamlined, low-cost option for challenging any presumption of common development, to

⁷⁵⁷ New England Small Hydro Comments at 17.

⁷⁵⁸ Borrego Solar Comments at 3-4.

⁷⁵⁹ *Id.* at 4.

avoid casting a chill over project development and driving developers and long-term owners out of the market due to the risks of having the projects disqualified. 760 North Carolina DOJ argues that the proposed rule, by discouraging facilities from being placed close to one another, also runs counter to a North Carolina policy based on efficient use of electric resources. 761 North Carolina DOJ and North Carolina Commission Staff state that the rules in North Carolina incentivize the installation of production facilities close to substations so projects naturally appear in clusters surrounding transmission and distribution infrastructure. 762 North Carolina DOJ says that the proposed rule fails to take into account the complex and regionally specific factors driving the siting, financing, operation, and maintenance of production facilities. ⁷⁶³ 487. Industrial Energy Consumers state that the NOPR does not distinguish between merchant small power production OFs built to sell electricity to third parties and selfsupply QFs built primarily to support manufacturing or industrial processes. Industrial Energy Consumers state that there are many manufacturing company sites that are of a 10mile length. Industrial Energy Consumers state that the Commission's proposed changes to the one-mile rule should be clarified to exclude "self-supply" QFs. 764

⁷⁶⁰ *Id.* at 5.

⁷⁶¹ North Carolina DOJ Comments at 8.

⁷⁶² *Id.*; North Carolina Commission Staff Comments at 6.

⁷⁶³ North Carolina DOJ Comments at 6.

⁷⁶⁴ Industrial Energy Consumers Comments at 16.

- 488. Solar Energy Industries believes that for facilities less than one mile apart the Commission should continue to waive the rule where appropriate.⁷⁶⁵
- 489. Regarding the proposed irrebuttable presumption that facilities located more than 10 miles apart are separate facilities, NorthWestern urges the Commission to consider increasing the distance. NorthWestern explains that its operations in Montana are geographically very expansive and 10 miles in Montana is not a substantial distance, especially when compared to other states that are geographically much smaller.

 NorthWestern states that Montana's electric system has more than 24,450 miles of electric transmission and distribution lines to serve approximately 374,000 customers, and that its electric operations are very rural and cover more than 97,500 square miles. The NorthWestern therefore recommends that the Commission consider expanding this distance to accommodate utilities in the West that have very large service territories.

ii. <u>Commission Determination</u>

490. We adopt the NOPR proposal that an entity can seek to rebut the presumption of separate sites only for an entity seeking small power production QF status with an affiliated small power production QF or QFs that are located more than one and less than 10 miles from it.

⁷⁶⁵ Solar Energy Industries Comments at 60-61 (citing *Windfarms*, *Ltd.*, 13 FERC ¶ 61,017, at 61,032 (1980) (*Windfarms*)).

⁷⁶⁶ NorthWestern Comments at 10.

⁷⁶⁷ *Id*

491. We recognize, as we have previously for the one-mile rule, ⁷⁶⁸ that it is debatable as to where exactly these thresholds are most appropriately set. PURPA requires that no small power production facility, together with other facilities located "at the same site." exceed 80 MWs, and Congress has tasked the Commission with defining what constitutes facilities being at the same site for purposes of PURPA. We find that providing set geographic distances will limit unnecessary disputes over whether facilities are at the same site, and therefore must choose reasonable distances at which small power production facilities will be considered irrebuttably at the same site or irrebuttably at separate sites. There are some affiliated small power production facilities using the same energy resource that are so close together that it is reasonable to treat them as irrebuttably at the same site. The Commission finds that one mile or less is a reasonable distance to treat such facilities as irrebuttably at the same site. Likewise, there are some small power production facilities that are affiliated and may use the same energy resource but that are sufficiently far apart that it is reasonable to treat them as irrebuttably at separate sites. The Commission finds that 10 miles or more is a reasonable distance to treat such facilities as irrebuttably at separate sites. For affiliated small power production facilities using the same resource that are more than one mile but less than 10 miles apart, the Commission finds that the distinction between same site or separate site is not as clear, and therefore finds that it is reasonable to treat them as rebuttably at separate sites, and to allow interested parties to provide evidence to attempt to rebut that presumption. The

⁷⁶⁸ See Windfarms, 13 FERC at 61,032.

Commission finds that establishing these reasonable distances, and particularly establishing the ability to rebut the presumption of separate sites for affiliated small power production facilities more than one mile but less than 10 miles apart, better allows the Commission to address the evolving shape and configuration of resources, such as modular solar or wind power plants, that are being developed as QFs, and provides for improved administration of PURPA. The Commission therefore finds that the one-mile and 10-mile limits are reasonable inflection points for differentiating between the same site and separate sites.

492. The Commission understands that there may be many reasons that guide developers' decisions on where to site facilities, and for siting them near to (or far from) each other. The Commission reiterates that for affiliated small power production QFs that are more than one and less than 10 miles apart, there is still a presumption that they are at separate sites, though the Commission today makes that presumption a rebuttable presumption. We also adopt today the proposal to allow an entity seeking QF status to provide further information in its certification (both self-certification and application for Commission certification) or recertification (both self-recertification and application for Commission recertification) to preemptively defend against rebuttal by identifying factors

⁷⁶⁹ For hydroelectric generating facilities, the regulations currently provide that the same energy resources essentially means "the same impoundment for power generation," *see* 18 CFR 292.204(a)(2)(i), and it is unlikely that hydroelectric generating facilities located more than a mile apart would rely on the same impoundment. Should that circumstance arise, though, the applicant facility could seek waiver, arguing that the facilities should not be considered to be at the same site. *See* 18 CFR 292.204(a)(3).

that affirmatively show that its facility is indeed at a separate site from affiliated small power production QFs more than one but less than 10 miles from it. Additionally, we note that we are retaining waiver provision in 18 CFR 292.204(a)(3), allowing the Commission to waive the method of calculation of the size of the facility for good cause.⁷⁷⁰ 493. Borrego Solar raises the concern that unaffiliated developers may site their projects within a few miles of each other, and later sell those projects to a single entity much later in the process, inadvertently violating the Commission's rules. The Commission finds that it is reasonable to expect the single purchasing entity in the example to be on notice about the size and locations of its QF acquisitions and the requirements of both PURPA and the Commission's regulations, just as it would need to consider other regulatory requirements associated with its acquisition. Moreover, ownership by a single entity of multiple small power production OFs in close proximity to each other that together exceed a power production capacity of 80 MW, and whether this improperly circumvents the Commission's regulations, is precisely what the new rebuttable presumption is seeking to address.

494. Regarding Industrial Energy Consumers' request that the Commission's changes be clarified to exclude "self-supply" QFs, the Commission declines to do so. PURPA limits the power production capacity of a small power production QF, together with any other facilities located at the same site (as determined by the Commission), to 80 MW.⁷⁷¹ The

⁷⁷⁰ See 18 CFR 292.204(a)(3).

⁷⁷¹ 16 U.S.C. 796 (17)(A)(ii).

Commission finds that Industrial Energy Consumer's argument that "self-supply" QFs are built primarily to support manufacturing and industrial processes does not negate the fact that the "self-supply" OFs in question are small power production facilities limited to 80 MW. Similarly, its argument also does not justify different application of the same site determination. The Commission will therefore apply the same site determinations to all small power production QFs. The Commission notes that, as with other small power production QFs, an individual "self-supply" QF may assert relevant factors to show why it should not be considered to be at the same site as an affiliated small power production QF that is more than one but less than 10 miles away from it. For example, if a self-supply facility seeking QF status was within 10 miles of an affiliated small power production QF, but the energy from each facility was used primarily to supply different end users, the selfsupply facility seeking QF status could argue that this fact supports that it is at a separate site from the affiliated small power production QF, and the Commission would consider this fact in its evaluation.

- 495. Regarding Terna Energy's contention that the new rule causes a 100-times increase to the "exclusion zone" around a QF's electrical generating equipment, we believe that the rule providing for a rebuttable presumption for affiliated small power production QFs located more than one but less than 10 miles apart, as promulgated today, is necessary to address allegations of improper circumvention of the one-mile rule that both previously and in comments have been presented to the Commission.
- 496. We reject NorthWestern's request to increase the distance of the irrebuttable presumption of separate sites to more than 10 miles. Northwestern argues that 10 miles is

not a significant distance compared to the geographic expansiveness of its system. We believe this is an irrelevant comparison; what matters is not how large or small the purchasing electric utility's service territory is or how rural it may be or how many miles of transmission lines it may have, but the question presented by the statute, i.e., whether or not the affiliated small power production QFs are located at the same site. As described above, we have decided that 10 miles is a reasonable and appropriate distance at which to apply the irrebuttable presumption of separate sites, irrespective of how expansive, or diminutive, the purchasing electric utility's system may be.

f. Factors

i. Comments

497. Several commenters state that they support the factors for evaluating whether or not facilities are at the same site, which are described in the NOPR.⁷⁷² SC Solar Alliance and the Southeast Public Interest Organizations support considering a common point of interconnection or a single real estate parcel or owner as factors weighing towards a determination that multiple projects are a single facility.⁷⁷³

498. Several commenters offer additional factors for consideration.⁷⁷⁴ North Carolina Commission Staff states that the Commission should also consider whether the QF is

⁷⁷² APPA Comments at 21-22; Connecticut Authority Comments at 19-20; Idaho Commission Comments at 6-7; NARUC Comments at 5; Portland General Comments at 15.

⁷⁷³ SC Solar Alliance Comments at 17; Southeast Public Interest Organization Comments at 34.

⁷⁷⁴ Allco Comments at 16; Idaho Commission Comments at 6-7; North Carolina

attempting to game the system by getting rates for which they would otherwise be ineligible, as well as where the facilities were constructed and when common ownership commenced. The Northern Laramie Range Alliance suggests that relevant factors could include, for example, direct or indirect ownership by the same party or parties, interconnection at a single substation, simultaneous site acquisition and/or state and local permitting. The Allco proposes that the criteria to determine if sites are separate should be whether they share infrastructure, private roads or interconnection agreements in common. NRECA proposes that the types of evidence could include evidence of contemporaneous construction, shared interconnection, common communication and control, use of the same step-up transformer, and common permitting and land leasing. The Idaho Commission proposes that relevant factors include whether they share an interconnection agreement, obtained local, state or federal permits under the same application or as the same entity, and if they have a revenue sharing agreement.

Commission Staff Comments at 6; Northern Laramie Range Alliance Comments at 3; NRECA Comments at 15-16.

⁷⁷⁵ North Carolina Commission Staff Comments at 6.

⁷⁷⁶ Northern Laramie Range Alliance Comments at 3.

⁷⁷⁷ Allco Comments at 16.

⁷⁷⁸ NRECA Comments at 15-16.

⁷⁷⁹ Idaho Commission Comments at 6-7.

Portland General suggests that the Commission include past ownership of projects as a factor.⁷⁸⁰

Regarding the relative weight of the factors, the Southeast Public Interest Organizations would like the Commission to identify which factors would be definitive in a OF being able to proactively demonstrate that their site is separate.⁷⁸¹ Both Basin and EEI would like the Commission to clarify that the list of factors to be considered is not exhaustive or weighted. 782 NorthWestern contends that the Commission should specify that a showing of any one factor is sufficient to rebut the presumption. NorthWestern argues that the Commission should have the flexibility to deal with this issue on a caseby-case basis and expand or modify the list of factors where appropriate.⁷⁸³ 500. NorthWestern states that it has concerns about the Commission's reliance on 18 CFR 35.36(a)(9), because, according to NorthWestern, developers carefully structure the ownership of their companies to ensure that they are not, technically, legal affiliates when, in fact, considering the totality of the circumstances, they are affiliates. For these reasons, NorthWestern strongly urges the Commission to consider the physical characteristic factors identified for determining the distance between facilities in order to also determine

⁷⁸⁰ Portland General Comments at 15.

⁷⁸¹ Southeast Public Interest Organization Comments at 34.

⁷⁸² Basin Comments at 12; EEI Comments at 45.

⁷⁸³ NorthWestern Comments at 11.

if facilities are owned by affiliates.⁷⁸⁴ NorthWestern states that, for example, if one facility only owns five percent voting interest in another facility, but the two facilities have one interconnection request and use the same collector system, the Commission should be able to find that there are sufficient facts so that they are treated as affiliates for purposes of the one-mile rule.⁷⁸⁵

501. Several commenters opposed the Commission's proposed factors.⁷⁸⁶ SC Solar Alliance states that the range of factors included under the categories of "ownership/other characteristics" and "physical characteristics" is overly broad and could be subject to inconsistent or problematic interpretation. For example, SC Solar Alliance states that the term "infrastructure" is undefined and ambiguous, and "control facilities," "access and easements," "collector systems or facilities," and "property leases" are all vague and imprecise.⁷⁸⁷ SC Solar Alliance agrees with Solar Energy Industries' emphasis that under no scenario should common financing be relevant, as unquestionably distinct facilities are frequently financed as part of a bundled portfolio.⁷⁸⁸

⁷⁸⁴ *Id.* at 12.

⁷⁸⁵ *Id*.

⁷⁸⁶ Ares Comments at 5-7; Borrego Solar Comments at 3-4; NIPPC, CREA, REC, and OSEIA Comments at 73; Solar Energy Industries Comments at 62; SC Solar Alliance Comments at 16-18; Southeast Public Interest Organizations Comments at 34.

⁷⁸⁷ SC Solar Alliance Comments at 17.

⁷⁸⁸ *Id.* at 16 (citing Solar Energy Industries Supplemental Comments, Docket No. AD16-16, at 55-56 (August 28, 2019)).

502. NIPPC, CREA, REC, and OSEIA strongly oppose use of common interconnection facilities as a factor because separately owned facilities are likely to share interconnection facilities to reduce costs and build off of existing infrastructure. NIPPC, CREA, REC, and OSEIA state that, given that there are only a limited number of qualified maintenance providers and other service contractors, the fact that two facilities use the same contractors should not be relevant to common ownership and control of two facilities. NIPPC, CREA, REC, and OSEIA state that the fact that two facilities are constructed within 12 months of each other could merely be evidence that the market conditions at the time favored construction of the facilities, not that the facilities are intended to be one facility. 789

503. SC Solar Alliance states that the extensive list of "ownership/other characteristics" as written is highly problematic. Control and maintenance, particularly in North and South Carolina where there are a substantial number of distributed solar facilities, is often contracted for by a limited number of solar maintenance companies. Allowing the existence of a common maintenance company to in any way dictate QF status is entirely unreasonable and bears no relationship to the question at hand. Similarly, other factors included in the NOPR, including the sale of electricity to a common utility, a common financing lender, the use of a mutual contractor for project construction, the timing of contract execution, and the timing of facilities being placed into service do not provide

⁷⁸⁹ NIPPC, CREA, REC, and OSEIA Comments at 73-74.

⁷⁹⁰ SC Solar Alliance Comments at 17-18.

qF. Applying these factors would create an unnecessary and undue burden on QFs, particularly smaller distribution-connected QFs that have been constructed relatively nearby and which often rely on a limited number of local contractors and partners to complete this necessary work.⁷⁹¹

504. The Southeast Public Interest Organizations are concerned that the use of common contractors, financing entity, maintenance companies, or sales to the same entity and such could be used against QFs that are built in the same area but are otherwise separate sites.⁷⁹²

505. SC Solar Alliance states that the Commission's statement that "no single factor would be dispositive" is troubling, and that it is inconceivable that QF ownership would not be dispositive in any such rebuttable presumption. SC Solar Alliance states that it would be wholly unjust and unreasonable to consider a solar facility owned by one solar developer to be considered part of a solar facility owned by a distinct and unaffiliated solar developer. SC Solar Alliance states that any rebuttable presumption should include "separate ownership" as a dispositive indication of separate facilities.⁷⁹³

506. North Carolina DOJ states that the element of common control is a challenging question because of the limited number of companies available to operate renewable

⁷⁹¹ *Id*.

⁷⁹² Southeast Public Interest Organizations Comments at 34.

⁷⁹³ SC Solar Alliance Comments at 17.

energy facilities. North Carolina DOJ asserts that a handful of firms are responsible for the operation and maintenance work for close to half of the country's solar energy production facilities.⁷⁹⁴

507. NIPPC, CREA, REC, and OSEIA state that the Commission should include substantially more specific parameters about what evidence a project would need to submit to demonstrate single-project status and should make clear that this test has no applicability unless generators within one to 10 miles are owned by the same company or affiliates of the same company. NIPPC, CREA, REC, and OSEIA assert that "the decisive factors are the 'stream of benefits' from the project and control of the venture," which the Commission defined "to include entitlement to profits, losses, and surplus after return of initial capital contribution." These criteria could be used to objectively evaluate whether two QFs within 10 miles are commonly owned or controlled, as opposed to also putting two separately owned and controlled facilities at risk of violating the rule based solely on physical characteristics. 796

ii. Commission Determination

508. We adopt the physical and ownership factors proposed in the NOPR, including as noted above the ability of a QF to preemptively identify the factors in its filing in

⁷⁹⁴ North Carolina DOJ Comments at 8.

 $^{^{795}}$ NIPPC, CREA, REC, and OSEIA Comments at 73 (citing *CMS Midland, Inc.*, 50 FERC ¶ 61,098, at 61,278-279 (1990), *aff'd Mich. Municipal Coop. Group v. FERC*, 990 F.2d 1377 (D.C. Cir. 1993)).

⁷⁹⁶ *Id*.

anticipation of protests to its filing. As explained above in section IV.D.1.d we are modifying the NOPR proposal to change terminology relating to the determination of whether facilities are separate facilities to focus not on whether they are *separate facilities*, but rather to mirror the statutory language and thus focus on whether they are at "the same site." Accordingly, we adopt these factors as relevant indicia of whether affiliated small power production facilities are "at the same site." In addition, we modify the NOPR proposal to identify the following additional physical factors as indicia that small power production facilities should be considered to be located at the same site: (1) evidence of shared control systems; (2) common permitting and land leasing; and (3) shared step-up transformers.

509. Specifically, we adopt the factors listed below as examples of the factors the Commission may consider in deciding whether small power production facilities that are owned by the same person(s) or its affiliates are located "at the same site": (1) physical characteristics, including such common characteristics as: infrastructure, property ownership, property leases, control facilities, access and easements, interconnection agreements, interconnection facilities up to the point of interconnection to the distribution or transmission system, collector systems or facilities, points of interconnection, motive force or fuel source, off-take arrangements, connections to the electrical grid, evidence of shared control systems, common permitting and land leasing, and shared step-up transformers; and (2) ownership/other characteristics, including such characteristics as whether the facilities in question are: owned or controlled by the same person(s) or

affiliated persons(s),⁷⁹⁷ operated and maintained by the same or affiliated entity(ies), selling to the same electric utility, using common debt or equity financing, constructed by the same entity within 12 months, managing a power sales agreement executed within 12 months of a similar and affiliated small power production qualifying facility in the same location, placed into service within 12 months of an affiliated small power production QF project's commercial operation date as specified in the power sales agreement, or sharing engineering or procurement contracts.

OF status to provide further information in its certification (both self-certification and application for Commission certification) or recertification (both self-recertification and application for Commission recertification) to preemptively defend against rebuttal, by identifying factors that affirmatively show that its facility is indeed at a separate site from affiliated small power production QFs more than one but less than 10 miles away from it. Any party challenging the QF certification (both self-certification and application for Commission certification) or recertification (both self-recertification and application for Commission recertification) that makes substantive changes to the existing certification would, in its protest, be allowed to correspondingly identify factors to show that the small

⁷⁹⁷ Definitionally, if the facilities are not owned by the same person(s) or its affiliates, then the issue of compliance with the one-mile rule, even as revised in this final rule, becomes irrelevant. *See* 18 CFR 292.204(a)(1). That is, two facilities owned by two different persons are definitionally not located at the same site.

power production facility seeking QF status and affiliated small power production QFs more than one but less than 10 from that facility are actually at the same site.

511. We reiterate that, as a general matter, no one factor is dispositive.⁷⁹⁸ Rather, we will conduct a case-by-case analysis, weighing the evidence for and against, and the more compelling the showing that affiliated small power production QFs should be considered to be at the same site as the small power production facility seeking QF status in a specific case, the more likely the Commission will be to find that the facilities involved in that case are indeed located "at the same site."

g. <u>Exemptions</u>

i. Comments

512. Ares notes that small power producers have certain exemptions from utility regulation, including exemptions from FPA sections 203 and 204 if under 30 MW and exemptions from FPA sections 205 and 206 if under 20 MW (or 30 MW in special cases), as well as exemptions from some state utility laws and PUHCA if under 30 MW.⁷⁹⁹ Ares is concerned that the rebuttable presumption and the factors will make many small power QFs ineligible for these exemptions.⁸⁰⁰ Ares argues that the aggregation of small power QFs may result in many required applications for market-based rate authority for sales that are minor. Ares argues that the Commission has no basis for, did not consider, and has

⁷⁹⁸ But see supra note 797.

⁷⁹⁹ Ares Comments at 4-5.

⁸⁰⁰ *Id.* at 5-6.

sought no comments on the removal of regulatory obligations when small power QFs are aggregated under the new ten-mile proposal.⁸⁰¹

513. Solar Energy Industries note that many facilities could lose their FPA and PUHCA exemptions if there are multiple facilities within 10 miles, which is particularly harmful to QFs that are not selling to their host utility. Solar Energy Industries state that PURPA section 210(e)(1) instructs that the Commission shall exempt QFs from regulation if such exemption "is necessary to encourage cogeneration and small power production."⁸⁰²

ii. Commission Determination

514. The Commission's current one-mile rule is a rule used to measure, ultimately, whether or not small power production facilities are within PURPA's limit on small power production QFs of 80 MW, and thus whether such facilities are QFs, and the Commission has consistently applied the one-mile rule generally to the regulations issued pursuant to PURPA. There is no persuasive reason it should not be equally applied in the context of the regulations implementing section 210(e) of PURPA. That being said, we are not removing or amending the exemptions provided by the regulations implementing PURPA section 210(e). If a QF qualifies for exemptions pursuant to PURPA section 210(e) and

⁸⁰¹ *Id.* at 11-12.

⁸⁰² Solar Energy Industries Comments at 55.

 $^{^{803}}$ SunE B9 Holdings LLC, 157 FERC ¶ 61,044, at P 16 & n.24 (2016) (citing Windfarms, 13 FERC ¶ 61,017 at 61,031).

the Commission's implementing regulations, 804 then that QF is entitled to those exemptions. But, if a small power production facility does not meet the 80 MW limit for whatever reason, including because an affiliated small power production OF is located at the same site, then it does not qualify for such exemption because it would not be a QF. 805 There is nothing inappropriate about this consequence; a facility that is not a OF is not entitled to the exemptions available to OFs. We further note that there will now be a rebuttable presumption that affiliated small power production OFs located more than one but less than 10 miles apart are indeed located at separate sites. That is no different than the one-mile rule as it has long existed. What is different is that, with this final rule, the presumption will be rebuttable while before it was irrebuttable; the presumption that the facilities are at separate sites, though, remains unchanged. Only if a party rebuts that presumption and shows that the small power production facility seeking OF status and affiliated small power production QFs should be viewed as located at the same site will the capacity of such facilities be counted together. In that event, if the small power production facility seeking OF status and affiliated small power production OFs located at the same site have a combined power production capacity that exceeds 80 MW, the entity seeking QF status would not qualify as a QF and would properly not be entitled to the exemptions that are available to QFs.

^{804 18} CFR 292.601, 292.602.

⁸⁰⁵ See 16 U.S.C. 796(17)(A)(ii).

2. Electrical Generating Equipment

a. NOPR Proposal

- 515. The Commission proposed defining "electrical generating equipment" to refer to all boilers, heat recovery steam generators, prime movers (any mechanical equipment driving an electric generator), electrical generators, photovoltaic solar panels and/or inverters, fuel cell equipment and/or other primary power generation equipment used in the facility, excluding equipment for gathering energy to be used in the facility. The Commission expected that each wind turbine on a wind farm and each solar panel in a solar facility would be considered "electrical generating equipment" because each wind turbine and each solar panel is independently capable of producing electric energy. The Commission sought comments on this approach, and on what equipment if not individual wind turbines and solar panels should be considered "electrical generating equipment" for wind and solar plants.
- 516. The Commission also proposed specifying how to measure the distance between facilities that have multiple, separate sets of "electrical generating equipment" such as wind farms and solar facilities. The Commission proposed measuring the distance between the nearest "electrical generating equipment" of any two facilities such that, for the facilities to be presumed irrebuttably separate, all such equipment of one QF must be at least 10 miles away from all such equipment of another QF. The Commission believed this is the appropriate way to measure the distance between affiliated sets of "electrical generating equipment" because this reflects the distance between the components directly tied to producing electric energy.

517. The Commission sought comment on this approach, and whether alternative approaches would be more appropriate. For example, some parties had suggested in QF certification proceedings that the Commission could use the geographic center of the plant footprint or a weighted average of the locations of the individual pieces of "electrical generating equipment." The Commission was concerned these approaches could be easily gamed, but sought comment on whether they may be constructed in a way that would prevent gaming, and whether such formulations would be preferable to the proposed approach.

b. <u>Comments</u>

- 518. Many commenters support the definition of "electrical generating equipment" proposed in the NOPR.⁸⁰⁷ However, ELCON objects to both the proposed definition of "electric generating equipment" and the approach to measuring distance.⁸⁰⁸
- 519. Many commenters support the method for measuring distance between sites proposed in the NOPR, which would require measuring the distance between the nearest "electrical generating equipment" of any two affiliated facilities. 809 Several commenters

⁸⁰⁶ See Beaver Creek Wind II, LLC, 160 FERC ¶ 61,052, at P 9 (2017).

⁸⁰⁷ Alliant Energy Comments at 19; APPA Comments at 23; Basin Comments at 11; Connecticut Authority Comments at 19-20; EEI Comments at 49; Idaho Commission Comments at 6; Kentucky Commission Comments at 7; NRECA Comments at 17; Portland General Comments at 16-17; Southeast Public Interest Organizations Comments at 37-38.

⁸⁰⁸ ELCON Comments at 36.

⁸⁰⁹ Alliant Energy Comments at 19; APPA Comments at 23; Basin Comments at 11; Connecticut Authority Comments at 19-20; EEI Comments at 49; Kentucky Commission Comments at 7; NARUC Comments at 4-5; Portland General Comments at

note their opposition to measuring the distance between sites using the geographic center of the plant or a weighted average of the locations of individual pieces of "electrical generating equipment," both methods the Commission sought comment on in the NOPR. The Southeast Public Interest Organizations request clarification of whether to measure from the edge of a solar panel or the center of a solar array. 811

520. Several commenters request that the Commission discuss how energy storage (sometimes referred to as battery storage) would be considered in relation to the proposed definition of electrical generating equipment. The California Commission requests that a battery storage facility be excluded from consideration as electrical generating equipment provided the storage is charged solely by the small power production facility, and that energy stored by the storage facility be considered to be of the same energy source of that energy before it was stored. The California Commission also requests that the Commission affirm that storage does not permit a facility to exceed the maximum size criteria of a small power production facility.

^{16-17;} Southeast Public Interest Organizations Comments at 37-38.

⁸¹⁰ Connecticut Authority Comments at 21; Kentucky Commission Comments at 7; NorthWestern Comments at 12-13; NRECA Comments at 18; Portland General Comments at 18.

⁸¹¹ Southeast Public Interest Organizations Comments at 38.

⁸¹² Alliant Energy Comments at 19; EEI Comments at 46-47; Energy Storage Comments at 3; NorthWestern Comments at 13.

⁸¹³ California Commission at 16-17.

⁸¹⁴ *Id.* at 15.

collect data on storage resources as well as electrical generating equipment for purposes of measuring distance to an affiliated small power production QF.⁸¹⁵

c. Commission Determination

- 521. We adopt the NOPR proposal that "electrical generating equipment" refers to all boilers, heat recovery steam generators, prime movers (any mechanical equipment driving an electric generator), electrical generators, photovoltaic solar panels, inverters, fuel cell equipment and/or other primary power generation equipment used in the facility, excluding equipment for gathering energy to be used in the facility. Each wind turbine at a wind facility and each solar panel in a solar facility would be considered "electrical generating equipment" because each wind turbine and each solar panel is independently capable of producing electric energy.
- 522. We require the distance between the facility seeking small power production QF status and any affiliated small power production QFs using the same energy resource to be measured by the distance between the nearest "electrical generating equipment" of each such facility, such that, for the entity seeking QF status to be presumed irrebuttably at a separate site from any affiliated small power production QF, all such equipment of the affiliated small power production QF must be at least 10 miles away from all such equipment of the entity seeking small power production QF status. The Commission finds that this is the most appropriate way to measure the distance between affiliated sets of

⁸¹⁵ EEI at 51-52.

"electrical generating equipment" at small power production facilities because this reflects the distance between the components directly tied to producing electric energy.

- 523. The point used in the distance calculation will always be from the edge of the electrical generating equipment closest to the affiliated small power production QF's nearest electrical generating equipment. Thus, we clarify that for a solar facility, the measurement should be from the edge of the small power production facility seeking QF status' solar panel or inverter that is closest to the edge of the nearest "electrical generating equipment" of that affiliated small power production QF. For a wind facility, the measurement should similarly be from the edge of the small power production facility seeking QF status' wind turbine or inverter closest to the edge of the nearest "electrical generating equipment" of the affiliated small power production QF. For a wind facility, we clarify that the relevant point for measuring distance of an individual wind turbine is the tower (not the projection of the blade's wingspans onto the ground). We also clarify that only horizontal distances are taken into consideration for purposes of this rule (such that elevation changes have no effect on facility distance).
- 524. We find that the role of battery storage in QFs, including with regard to the distance between QFs, is beyond the scope in this proceeding.

E. **QF Certification Process**

1. NOPR Proposal

525. In the NOPR, the Commission proposed to revise 18 CFR 292.207(a) to allow interested persons to intervene in, and to file a protest of a self-certification or self-recertification of a facility without the necessity of filing a separate petition for

declaratory order and without having to pay the filing fee required for a declaratory order. Because an applicant for self-certification or self-recertification is required to serve a copy of its submission on interested electric utilities (principally those with which it is interconnected and those to which it will be selling) as well as the relevant state regulatory authorities, the Commission proposed to allow interested persons 30 days from the date of filing at the Commission to intervene and/or to file a protest (without paying a filing fee).⁸¹⁶

Any party submitting a protest would have the burden of specifying facts that make a prima facie demonstration that the facility described in the self-certification or self-recertification does not satisfy the requirements for QF status. General allegations that the facility is not a QF without reference to the specific regulatory provision that has not been satisfied (and without an explanation why the provision has not been satisfied), or unsupported assertions that the self-certification does not satisfy an aspect of the PURPA Regulations, would not satisfy this burden and would not be a basis for denial of certification. However, if this prima facie burden is met, then the burden would shift to the applicant submitting the self-certification or self-recertification to demonstrate that the claims raised in the protest are incorrect and that certification is, in fact, warranted.

527. QF self-certification is effective upon filing and would remain effective if a protest is filed, until such time as the Commission rules that certification is revoked. The

^{816 18} CFR 292.207(c)(1).

filed. The Commission also reserved the right to request more information from the protester, the entity seeking QF status, or both.⁸¹⁷ If the Commission requests more information, the time period for the Commission order would be extended to 60 days from the filing of a complete answer to the information request.

- 528. There may be instances, however, when the Commission may need additional time to review the record in light of the nature of the protests. In those cases, the Commission proposed that, in addition to any extension resulting from a request for information, the Commission also may toll the 90-day period during which the Commission commits to act within one additional 60-day period. The Commission proposed to delegate to the Commission's Secretary, or the Secretary's designee, the authority to toll the 90-day period for this purpose.
- 529. The Commission believed these procedures would allow for timely but thorough review of protested self-certifications and self-recertifications. The Commission sought comment on whether these procedures impose an undue burden on the QF even though the QF remains certified pending the review.

⁸¹⁷ Such information requests could be issued by the Commission or by staff under any applicable delegated authority. For example, under 18 CFR 375.307(b)(3)(ii), the Director of the Office of Energy Market Regulation is authorized to "[i]ssue and sign requests for additional information regarding applications, filings, reports and data processed by the Office of Energy Market Regulation."

2. Comments

530. Many commenters raise the issue of granting legacy treatment, colloquially known as "grandfathering," to existing QF certifications and their future recertifications. Most of these comments support granting legacy treatment to current QFs and their future recertifications. Several commenters note that the application of the rule to existing or recertifying QFs will create uncertainty and cause disruptions of the sale of these QFs. Several Commenters note that applying the proposed rule to existing QFs could trigger financing defaults if those QFs lose their status. The Southeast Public Interest Organizations state that the proposed rebuttable presumption has implications for existing solar QFs in the Southeast, noting that QFs would be required to seek recertification as their existing PPAs expire, adding a significant burden. The Southeast Public Interest Organizations provide maps showing the ten-mile radius of utility-scale

⁸¹⁸ Ares Comments at 12; Basin Comments at 11; BluEarth Comments at 2; DC Commission at 9; New England Small Hydro Comments at 17; Industrial Energy Consumers Comments at 17; NIPPC, CREA, REC, and OSEIA Comments at 74; Solar Energy Industries Comments at 61-63; SC Solar Alliance Comments at 18; Southeast Public Interest Organizations Comments at 29-31; Terna Energy Comments at 16-18.

⁸¹⁹ Ares Comments at 12; BluEarth Comments at 2; New England Small Hydro Comments at 17; Industrial Energy Consumers Comments at 17; NIPPC, CREA, REC, and OSEIA Comments at 74; Solar Energy Industries Comments at 61-63; SC Solar Alliance Comments at 18; Southeast Public Interest Organizations Comments at 29-31; Terna Energy Comments at 16-18.

⁸²⁰ New England Small Hydro Comments at 17; NIPPC, CREA, REC, and OSEIA Comments at 74; Terna Energy Comments at 16-18.

⁸²¹ New England Small Hydro Comments at 17.

⁸²² Southeast Public Interest Organizations Comments at 29.

projects could lead to many overlapping affiliated territories under the new rules. SC Solar Alliance also notes the large number of small solar QFs overlapping within a tenmile radius across North Carolina and South Carolina and finds that the application of the more-than-one-but-less-than-10-miles rebuttable presumption to recertifications will be burdensome and unwieldy. NIPPC, CREA, REC, and OSEIA warn that the application of the new rule to existing QFs will effectively bar the transfer or sale (or potentially any number of less significant changes) of existing assets that were lawfully qualified under the one-mile rule but would pass the 80 MW aggregate threshold under the new rule.

NIPPC, CREA, REC, and OSEIA find this to be a violation of the existing QFs contractual and constitutional rights.

532. Terna Energy states that granting legacy treatment to existing QFs and their recertifications is necessary to protect investment decisions and contracts made under the long-standing one-mile rule.⁸²⁶ Terna Energy contends that, without clarification on the legacy treatment of recertifications, QFs could lose their status even for non-substantive revisions to their FERC Form No. 556s such as contact information, street address, ownership or operation.⁸²⁷ Terna Energy warns that absent the clarification of legacy

⁸²³ *Id.* at 30-31.

⁸²⁴ SC Solar Alliance Comments at 18.

⁸²⁵ NIPPC, CREA, REC, and OSEIA Comments at 75.

⁸²⁶ Terna Energy Comments at 1-2.

⁸²⁷ *Id.* at 2.

treatment for existing QF recertifications, QFs might go to extremes to avoid updating their FERC Form No. 556s with information changes.⁸²⁸

533. Solar Energy Industries state that retroactively applying a more-than-one-but-lessthan-10-miles rebuttable presumption to physical facilities that were developed based on the original one-mile rule will inject instability, will erode trust from the investment community, and will discourage the development of QFs as well as investment in the industry in general.⁸²⁹ Ares notes that not granting legacy treatment to existing OFs is inconsistent with past Commission actions on PURPA, such as the granting of legacy treatment to existing QF contracts in Order No. 671 or other QF related proceedings. 830 New England Small Hydro supports granting legacy treatment to existing QFs to avoid upsetting the settled expectations of existing generation.⁸³¹ New England Small Hydro gives the example of three hypothetical projects, each located nine miles apart that, when capacities are totaled, exceed 80 MW. If there is an ownership change that triggers the need for a recertification but the entities remain affiliates, under the Commission's proposed rule, all three projects would lose OF status. According to New England Small Hydro, this could trigger defaults under financing documents and the utility might be able to terminate the power contract, because many PPAs for QFs require the project to remain

⁸²⁸ *Id.* at 7.

⁸²⁹ Solar Energy Industries Comments at 62.

⁸³⁰ Ares Comments at 12.

⁸³¹ New England Small Hydro Comments at 17.

a QF for the term of the PPA. New England Small Hydro states that, as a result, a minor ownership change could have cascading negative effects to QFs.⁸³²

535. Terna Energy requests that existing QFs be granted legacy treatment as long as they do not make changes to electrical generating equipment of the facility, because that is the equipment that determines compliance with the one-mile rule. Terna Energy argues that otherwise an existing QF could be subject to challenge anytime it makes a non-substantive revision to its FERC Form No. 556, including a change to contact information, street address, ownership, or operator, effectively eliminating legacy treatment. Terna Energy states that granting legacy treatment is necessary to protect the sanctity of investments and contracts made in reliance upon the Commission's current PURPA regulations and the one-mile rule. Terna Energy submits revised language for 18 CFR 292.204(a)(2) and (3) to clarify that existing QF recertifications, unless they change the electrical generating equipment, should not be subject to the new rules.

536. Basin, on the other hand, asks the Commission to be clear that recertifications filed by QFs will trigger application of the proposed rule. Basin also recommends the Commission allow petitions seeking de-certification of QFs that have previously filed

⁸³² *Id*.

⁸³³ Terna Energy Comments at 2.

⁸³⁴ *Id.* at 1-2.

⁸³⁵ *Id.* at 8-9.

⁸³⁶ Basin Comments at 11.

self-certifications because some QFs self-certify at an early stage of project development and ultimately never proceed to development.⁸³⁷

- 537. The DC Commission would like the Commission to clarify whether the changes to the one-mile rule will apply to QFs under construction when the rule goes into effect. The DC Commission would like the Commission to leave the issue of legacy treatment of existing OFs up to the states. Sa9
- 538. Several commenters oppose the NOPR proposal to allow a party to protest a self-certification or self-recertification of a facility without being required to file a separate petition for declaratory order and pay the associated filing fee. Several commenters argue that this proposal will lead to a flood of challenges that will discourage the growth of QFs. Several commenters state that there will be substantial costs associated with this proposal that will fall on ratepayers and QFs. Several commenters state that the

⁸³⁷ *Id*.

⁸³⁸ DC Commission Comments at 9.

⁸³⁹ *Id*.

⁸⁴⁰ Allco Comments at 21; BluEarth Comments at 3; CARE Comments at 7; Con Edison Comments at 5; Distributed Sun Comments at 3; ENGIE Comments at 4; Public Interest Organizations Comments at 9, 97-98; Western Resource Councils Comments at 144; Solar Energy Industries Comments at 57-59.

⁸⁴¹ Allco Comments at 21; BluEarth Comments at 3; Distributed Sun Comments at 3; Public Interest Organizations Comments at 97; Western Resource Councils Comments at 144.

⁸⁴² Con Edison Comments at 5; ENGIE Comments at 4; Public Interest Organizations Comments at 97; Solar Energy Industries Comments at 58.

proposed changes will lead to increased administrative burden and expense⁸⁴³ or litigation risk.⁸⁴⁴ Several commenters state that the proposed changes will lead to uncertainty⁸⁴⁵ and deter development.⁸⁴⁶

539. Solar Energy Industries state that the proposed changes to the one-mile rule will substantially increase the regulatory burden on QFs and the self-certification process will no longer be quick.⁸⁴⁷ Solar Energy Industries is concerned that QFs may need to defend numerous self-certifications over a facility's lifetime, and assert that QFs could be forced to recertify any time the information represented in the Form No. 556 changes, including

⁸⁴³ Ares Comments at 6; Borrego Solar Comments at 4; Con Edison Comments at 5; Public Interest Organizations Comments at 97-98; Solar Energy Industries Comments at 51-52, 54, 57-58; SC Solar Alliance Comments at 15-18; Southeast Public Interest Organizations Comments at 29, 35; sPower Comments at 14.

⁸⁴⁴ Con Edison Comments at 5; Distributed Sun Comments at 3; ELCON Comments at 19-20; NIPPC, CREA, REC, and OSEIA Comments at 71-72; Public Interest Organizations Comments at 97-98; Solar Energy Industries Comments at 58-60; SC Solar Alliance Comments at 16, 18; Southeast Public Interest Organizations Comments at 29,35; sPower Comments at 14.

⁸⁴⁵ Ares Comments at 9; Distributed Sun Comments at 3; ELCON Comments at 19-20, 38; NIPPC, CREA, REC, and OSEIA Comments at 69-72; Public Interest Organizations Comments at 97-98; Solar Energy Industries Comments at 58-60, 62-63; SC Solar Alliance Comments at 16, 18; Southeast Public Interest Organizations Comments at 29, 35, 38, 93, 97-98; sPower Comments at 14.

⁸⁴⁶ Allco Comments at 16; Borrego Solar Comments at 4-5; Biological Diversity Comments at 9; Con Edison Comments at 4-5; Distributed Sun Comments at 3; NIPPC, CREA, REC, and OSEIA Comments at 72-73; North Carolina DOJ Comments at 8; Public Interest Organizations Comments at 93, 99; Solar Energy Industries Comments at 51-52, 59-63; SC Solar Alliance Comments at 2, 18; Southeast Public Interest Organizations Comments at 31-36, 38, 93.

⁸⁴⁷ Solar Energy Industries Comments at 52.

ownership changes to affiliated facilities located within 10 miles.⁸⁴⁸ Solar Energy Industries state that the burden will be increased exponentially if the one-mile rule is expanded in a ten-mile rule.⁸⁴⁹ Solar Energy Industries state that the NOPR's estimate of an additional eight hours and \$632 per docket for each QF self-certification or recertification is a substantial underestimation. 850 Solar Energy Industries estimate that it would require an additional approximately 90 to 120 hours per year to comply with the new requirements. Solar Energy Industries state that a OF could be forced to recertify any time the information represented changes, including ownership changes to affiliated facilities located within 10 miles. Solar Energy Industries note that a QF may have to engage in multiple defenses of its status, each time needing to engage legal counsel and devote internal company resources to preserve the status of its already-installed plant. 851 Solar Energy Industries assert that the flood of self-certification filings and updates would be a substantial burden on Commission staff and provide little value to the Commission or the public. 852 Solar Energy Industries also state that, unless and until the Commission makes a determination on the burden associated with collecting, reporting, and updating the Connected Entity⁸⁵³ information, it would be unjust and unreasonable for the

⁸⁴⁸ Solar Energy Industries at 57.

⁸⁴⁹ *Id.* at 53.

⁸⁵⁰ *Id.* at 52.

⁸⁵¹ *Id.* at 58.

⁸⁵² *Id.* at 53-54.

⁸⁵³ Id. at 54 (citing Data Collection for Analytics and Surveillance and Market-

Commission to impose similar burdens on QF entities through the FERC Form No. 556.⁸⁵⁴ Solar Energy Industries state that the increased regulatory burden that will arise for these entities is similar in scope and the Commission has not provided a rationale for the increased information collection requirements.⁸⁵⁵

540. Allco describes the Commission's Regulatory Flexibility Act (RFA) analysis of the proposed rules' effect on small businesses as improperly limited to proposed paperwork changes, ignoring the impact on small QFs' abilities to construct facilities. Allco states that the Commission did not attempt to minimize the impacts on small renewable energy producers, consider alternative structures, or describe these steps or considerations in a mandatory final RFA analysis. Allco asserts that the Commission failed to support its finding that the NOPR's proposed revisions will not significantly impact a substantial number of small entities (specifically, solar energy QFs); Allco therefore claims that the Commission violated the Small Business Regulatory Enforcement Fairness Act. Solar Energy Industries state that the NOPR lacks important details such as whether the Commission's determination is subject to rehearing, and whether a final

Based Rate Purposes, Order No. 860, 168 FERC ¶ 61,039, at P 183 (2019)).

⁸⁵⁴ *Id.* at 54, 57.

⁸⁵⁵ *Id.* at 54.

⁸⁵⁶ Allco Comments at 33.

⁸⁵⁷ *Id*.

⁸⁵⁸ *Id*.

decision can be appealed under the FPA to an appellate court. Solar Energy Industries state that an adverse determination by the Commission could impose upwards of \$100 million in harm on a QF, and it is unclear whether the QF would have a path to relief if the Commission erred in its determination. Solar Energy Industries state that the current practice, where the challenger bears the responsibility of seeking declaratory relief, strikes an appropriate balance.

542. Several commenters, on the other hand, support the NOPR proposal to allow a party to protest a self-certification or self-recertification of a facility without being required to file a separate petition for declaratory order and to pay the associated filing fee. Several commenters argue that the proposed amendment would strike the right balance and distribute the burdens of proof appropriately. Several commenters also state that this proposal would increase the efficiency of the process, reduce administrative costs, and could solve potential certification problems before they even begin. Second

⁸⁵⁹ *Id.* at 58.

⁸⁶⁰ *Id.* at 59.

⁸⁶¹ Alaska Power Comments at 2; Alliant Energy Comments at 22-23; APPA Comments at 31-35; Duke Energy Comments at 23-24; Indiana Municipal Comments at 10; NRECA Comments at 21-22; Portland General Comments at 21-22; Ohio Commission Energy Advocate Comments at 10; Chamber of Commerce Comments at 8; We Stand Comments at 3.

⁸⁶² APPA Comments at 31-35; NRECA Comments at 21-22; Ohio Commission Energy Advocate Comments at 10.

⁸⁶³ Indiana Municipal Comments at 10; NRECA Comments at 21-22; Portland General Comments at 21-22.

- 543. Other commenters support the NOPR proposal, but with caveats or extra requests. ⁸⁶⁴ Golden Valley recommends that the 30-day clock to challenge QF self-certification or self-recertification begins when the QF serves notice to the interested electric utility, not when the QF makes its filing with the Commission. ⁸⁶⁵ NIPPC, CREA, REC, and OSEIA state that the Commission should provide a 60-day deadline after the filings are complete by which time a failure of the Commission to rule results in the objection being denied by operation of law. ⁸⁶⁶
- 544. NorthWestern requests the QFs be subject to various discovery requests when they self-certify or self-recertify.⁸⁶⁷ Two commenters argue that any challenging party should be required to include an affidavit from a company official.⁸⁶⁸
- 545. NorthWestern and Northern Laramie Range Alliance request that QF developers seeking certification with the Commission should be required to publish notice in local newspapers in the states in which the development would be located, in order to alert affected parties so they could intervene in the certification process.⁸⁶⁹ El Paso Electric is

3.

⁸⁶⁴ DTE Electric Comments at 9-10; Golden Valley Electric Comments at 1-2, 3-7; Industrial Energy Consumers Comments at 14; Northern Laramie Range Alliance Comments at 3; NorthWestern Comments at 17-18; ELCON Comments at 19-20, 37-38.

⁸⁶⁵ Golden Valley Electric Comments at 2.

⁸⁶⁶ NIPPC, CREA, REC, and OSEIA Comments at 74.

⁸⁶⁷ NorthWestern Comments at 17-18.

⁸⁶⁸ Industrial Energy Consumers Comments at 14; ELCON Comments at 20, 38.

NorthWestern Comments at 3; Northern Laramie Range Alliance Comments at

concerned by the proposal to limit the ability to challenge QF status once it has been certified in a Commission certification proceeding or in response to a challenge unless the new challenger can demonstrate a change in the facility circumstances that threaten the validity of the previous finding. El Paso Electric states that sometimes QFs fail to provide utilities with their QF application and so the utility does not know to protest. ⁸⁷⁰

546. Ares notes that small power production QFs could be aggregated under the more-than-one-but-less-than-10-miles rebuttable presumption and not even be aware of the other small power production QFs because of a lack of information. ⁸⁷¹

3. <u>Commission Determination</u>

547. We adopt the NOPR proposal to revise 18 CFR 292.207(a) to allow an interested person or entity to seek to intervene and to file a protest of a self-certification or self-recertification of a QF, and not have to file a petition for declaratory order and pay the filing fee for petitions. We also adopt the other changes to the QF certification process proposed in the NOPR, with the additions detailed below. We find that any increased administrative burden or litigation risk imposed by the new rule is justified by the need to ensure that QFs meet the statutory criteria for QF status.

548. The ability to intervene and to file a protest of a self-certification or self-recertification of a QF without having to file a petition for declaratory order and pay the

⁸⁷⁰ El Paso Electric Comments at 5.

⁸⁷¹ Ares Comments at 6.

⁸⁷² We amend the proposed regulation in the NOPR to move the sections referring to protests and interventions from 18 CFR 292.204 to 18 CFR 292.207.

filing fee for petitions is effective as of the effective date of the final rule. However, we will grant legacy treatment to existing QFs under certain circumstances, as we explain below. With the exceptions noted below, protests pursuant to this final rule will not be allowed to QF certifications and recertifications (including self-certifications and self-recertifications) that are submitted before the effective date of the final rule, although entities may still challenge by filing a petition for declaratory order and submitting the required fee. Conversely, protests *can* be made to QF certifications (both self-certification and application for Commission certification) or recertifications (both self-recertification and application for Commission recertification) that are submitted on or after the effective date of this final rule. We note here that it is the date of filing for certification or recertification, and not the date of construction, that determines whether our new protest rule applies to the certification or recertification.

549. Many commenters have argued for expansive legacy treatment for recertification of existing projects. They have noted that QFs need to recertify when property is transferred, PPAs expire, or even for non-substantive changes, such as changes in contact information or street address.⁸⁷³ Commenters argue that, if the new protest rules apply to recertifications, existing QFs could lose their QF status, even if their configuration or other relevant factors do not materially change, when they file their recertifications, upsetting the settled expectations under which the QFs built their facilities.

 $^{^{873}}$ NIPPC, CREA, REC, and OSEIA Comments at 75; Terna Energy Comments at 1-2, 7.

550. We agree that QF recertifications to implement or address non-substantive changes should not be subject to our new protest rule; the settled expectations of the QFs should be respected in such instances. Accordingly, we find that protests may be filed to an initial certification (both self-certification and application for Commission certification) filed on or after the effective date of this final rule, but only to a recertification (both selfrecertification and application for Commission recertification) that makes substantive changes to the existing certification and that are filed on or after the effective date of this final rule. Substantive changes that may be subject to a protest may include, for example, a change in electrical generating equipment that increases power production capacity by the greater of 1 MW or 5 percent of the previously certified capacity of the QF, or a change in ownership in which an owner increases its equity interest by at least 10% from the equity interest previously reported. We find that recertifications (both selfrecertifications and applications for Commission recertifications) making "administrative only" changes should not be subject to a protest pursuant to this final rule. 874 We believe that excepting from protests QF recertifications making non-substantive changes will allow QFs to make such changes and recertify without potentially losing their QF status. Solar Energy Industries asserts that the certification process will no longer be 551. quick, and estimates that it would require an additional approximately 90 to 120 hours per year to comply with these new requirements. Solar Energy Industries is concerned that

⁸⁷⁴ As noted elsewhere in this final rule, our allowing protests does not eliminate the ability to file a petition for declaratory order seeking revocation of qualifying status.

QFs may need to defend numerous self-certifications over a facility's lifetime, and asserts that QFs could be forced to recertify any time the information represented in the Form No. 556 changes.⁸⁷⁵

- 552. We do not agree with Solar Energy Industries' estimates. First, we note that 18 CFR 292.207(d) (which we are not altering in this rule except to renumber as 18 CFR 292.207(f)) already states that if a QF fails to conform with any material facts or representations presented in the certification, the QF status of the facility may no longer be relied upon,⁸⁷⁶ and hence it is long-standing practice that a QF must recertify when material facts or representations in the Form No. 556 change.
- 553. Second, certifications and recertifications are already subject to protests, albeit in the form of petitions for declaratory order, and therefore dealing with objections to a certification or recertification is not new. Although the new procedures may result in more protests being filed than the number of petitions that have been filed, we believe that the conditions we impose in this final rule will limit the number of protests filed. The Commission anticipates that most, though not all, of the protests filed pursuant to the new 18 CFR 292.207(a) will relate to the new more-than-one-but-less-than-10-miles rebuttable presumption. Such protests will necessarily be limited because not all certifications and

⁸⁷⁵ Solar Energy Industries at 57.

^{876 18} CFR 292.207(d), which this final rule will renumber to 18 CFR 292.207(f).

⁸⁷⁷ While we anticipate that most protests will involve interested persons or entities attempting to rebut the presumption of separate sites for affiliated small power production qualifying facilities that are more than one and less than 10 miles apart, we note that protesters may also protest any fact or representation in the Form No. 556, or other aspect

recertifications will be subject to the new more-than-one-but-less-than-10-miles rebuttable presumption. Only small power production facilities seeking QF status that have an affiliated small power production QF more than one but less than 10 miles away and that uses the same energy resource are subject to the rebuttable presumption. Small power production facilities that do not have multiple small power production facilities or affiliates will not be affected by the new rebuttable presumption. Nor will cogeneration QFs be affected by the new rebuttable presumption. 878 Additionally, in general as described above, protests may only be made to an initial certification (both self-certification and application for Commission certification) filed on or after the effective date of this final rule, and only to a recertification (self-recertification or application for Commission recertification) that makes substantive changes to the existing certification that are filed after the effective date of this final rule.

554. Third, we are also instituting time limits on protests that may be filed under this final rule. We adopt the NOPR proposal that interested parties will have 30 days from the date of the filing of the Form No. 556 at the Commission to file a protest (without paying a fee). Additionally, a protestor must concurrently serve its protest on the Form No. 556 applicant pursuant to 18 CFR 385.2010.

of a QF's filing they believe is inconsistent with PURPA or our PURPA Regulations.

⁸⁷⁸ The 80 MW limit and same site determination only apply to small power production facilities, not cogeneration facilities. *See* 16 USC 796(17)(A).

⁸⁷⁹ We note that section 292.207(c) of the PURPA Regulations requires the applicant to concurrently with its filing serve a copy of the filing on each applicable electric utility as well as the applicable State regulatory authority. We expect an applicant

555. Fourth, regarding Solar Energy Industries' concern that a QF may have to engage in multiple defenses of its status, in addition to the above limits on protests, once the Commission has affirmatively certified an applicant's QF status in response to a protest opposing a self-certification or self-recertification, or in response to an application for Commission certification or Commission recertification, any later protest to a recertification (self-recertification or application for Commission recertification) making substantive changes to a QF's existing certification, e.g., asserting that the entity seeking QF status is at the same site as affiliated small power production QFs more than one but less than 10 miles from it, must demonstrate changed circumstances from the facts on which the Commission acted on the certification filing that call into question the continued validity of the earlier certification.

556. Finally, even if it indeed takes *some* small power production facilities an additional 90 to 120 hours (and we think that unlikely), that is not an unreasonable burden to impose to ensure that a generating facility that seeks to be a QF is, in fact, entitled to QF status and complying with PURPA. ⁸⁸⁰

seeking QF status (or recertifying its status) to timely comply with that regulation. Therefore, a utility should also receive the filing at the same time that the filing is made at the Commission.

⁸⁸⁰ The regulations adopted in this final rule explicitly make self-certifications and self-recertifications effective upon filing and allow them to remain effective even if challenged until such time as the Commission finds that a facility does not qualify to be a QF. Additionally, entities seeking QF status can file self-certifications years in advance of facility operation, such that the few months contemplated by the new process should not cause delay. Finally, with regard to the time it may take to fill in the Form No. 556, we note that while an entity seeking QF status *may choose* to preemptively defend against claims that it should be considered to be at the same site as affiliated small power

- 557. Turning to the requirements for a protest, as proposed in the NOPR, we will require any person or entity filing a protest to specify facts that make a prima facie demonstration that the facility described in the certification (both self-certification and application for Commission certification) or recertification (both self-recertification or application for Commission recertification) does not satisfy the requirements for QF status. We will also require any protest to be adequately supported with any supporting documents, contracts, or affidavits, as appropriate. Just as public utilities are typically not subject to discovery with regard to their rate filings under section 205 of the FPA prior to the Commission's instituting trial-type evidentiary hearings, ⁸⁸¹ we similarly decline to make QFs subject to discovery requests when they self-certify or self-recertify.
- 558. The Commission also orders here that an applicant's response to a protest will be allowed under 18 CFR 385.213(a)(2). By this final rule, we are consistent with that regulation, "otherwise order[ing]" that such answers may be filed. They will be due no later than 30 days after the filing of the protest.
- 559. Rooftop solar developers frequently finance the initial development of rooftop solar photovoltaic (PV) systems of individual homeowners, and then retain ownership of such PV systems for extended periods of time until the ownership is eventually transferred to the relevant homeowners. While these rooftop solar PV systems are owned by the

production qualifying facilities located more than one but less than 10 miles from it, this is optional, not required.

^{881 18} CFR 385.401(a).

developer, each individual rooftop solar PV system would be considered affiliated electrical generating equipment of every other rooftop solar PV system owned by that developer. When there are multiple co-owned rooftop solar PV systems within a mile, and thus at the same site, they may exceed 1 MW and therefore be required to file for certification or recertification unless they receive a waiver. Moreover, whenever they add an additional rooftop solar PV system to their portfolio, or alternatively transfer the ownership of such a rooftop solar PV system to the relevant homeowner, their facility could be viewed as no longer conforming with the material facts in their prior certification or recertification; thus they would need to recertify.

560. Due to the unique nature of rooftop solar PV developers, the Commission finds the recertification requirement for PV developers could be unduly burdensome. Therefore, to lessen the burden on such developers when recertifying, we will permit rooftop solar PV developers an alternative option to file their recertification applications. That is, rather than be required to file for recertification each time the rooftop solar developer adds or removes a rooftop facility, a rooftop solar PV developer may recertify on a quarterly basis. The filing would be due within 45 days after the end of the calendar quarter. However, if in any quarter a rooftop solar PV developer either has no changes or only has changes of power production capacity of 1 MW or less, then it would not be required to recertify until it has accumulated changes greater than 1 MW total over the quarters since its last

⁸⁸² See Sunrun, Inc., 167 FERC ¶ 61,059 (2019).

filing. 883 Additionally, we note that rooftop solar PV developers, like all small power production facilities, will not be subject to protests when they file recertifications that are "administrative only" in nature, but would be subject to such protests when they make substantive changes to the existing certification as detailed above in this section.

561. We take this opportunity to clarify that, when the Commission issues an order revoking QF certification, such order is subject to rehearing and appeal pursuant to the FPA. 884 The Commission's authority to determine whether or not a facility is a qualifying small power production facility stems from PURPA section 201, which amended FPA section 3 to add paragraph (17). 885 Similarly, FPA section 3(18) grants the Commission authority to determine whether a cogeneration facility meets the Commission's requirements. 886 Because the Commission's authority is grounded in the FPA, the

⁸⁸³ For example, if a rooftop solar QF increases its power production capacity by 0.9 MW in a quarter, it would not need to file to recertify for that quarter. However, if in the next quarter the rooftop solar QF increased its power production capacity by 0.9 MW, it would need to recertify for that quarter because cumulatively over the quarters since its last filing it has changed its power production capacity by more than 1 MW (i.e., under this example the rooftop solar QF changed its power production capacity since its last recertification filing by 1.8 MW).

⁸⁸⁴ Similarly, when the Commission issues an order affirmatively certifying an applicant's QF status (in response to a protest opposing a self-certification or self-recertification, or in response to an application for Commission certification or recertification), any party to that proceeding aggrieved by the order, including the protestant, may seek rehearing and appeal pursuant to the FPA.

⁸⁸⁵ 16 U.S.C. 796(17). Section 3(17) of the FPA mandates a size requirement for a small power production facility: it must have "a power production capacity which, together with any other facilities located at the same site (as determined by the Commission), is not greater than 80 megawatts."

^{886 16} U.S.C. 796(18).

Commission's order revoking QF certification is subject to rehearing and appeal pursuant to FPA section 313.887

562. El Paso Electric states that sometimes the utility does not know to protest, because sometimes QFs fail to provide utilities with their QF application, and El Paso Electric is therefore concerned by the Commission's proposal to limit protests by requiring that once the Commission has affirmatively certified an applicant's QF status, any later protest must demonstrate changed circumstances. We note that a QF that is filing a FERC Form No. 556 is currently required by 18 CFR 292.207(c) (which we are not altering in this rule except to renumber as 18 CFR 292.207(e)) to serve a copy on each electric utility with which it expects to interconnect, transmit or sell electric energy to, or purchase supplementary, standby, back-up or maintenance power from, and the state regulatory authority of each state where the facility and each affected utility is located. This final rule does not change that requirement and we expect applicants to timely comply with that regulation. Should an issue arise, though, the Commission can address it on a case-by-case basis as the circumstances warrant. Additionally, we note that, if a self-certification

order revoking QF status, *Golden Valley Elec. Ass'n, Inc.*, 167 FERC ¶ 61,208 (2019), *reh'g denied*, 170 FERC ¶ 61,025 (2020), and of an order denying petitions to revoke QF status, *N. Laramie Range All.*, 138 FERC ¶ 61,171, *reh'g denied*, 139 FERC ¶ 61,190 (2012), *appeal dismissed*, 733 F.3d 1030. There have also been appeals of orders denying petitions to revoke QF status. *N. Laramie Range All. v. FERC*, 733 F.3d 1030 (10th Cir. 2013) (dismissing appeal on other grounds); *Brazos Elec. Power Coop. Inc.*, *v. FERC*, 205 F.3d 235 (5th Cir. 2000) (denying petition for review). Unlike PURPA section 210, PURPA section 201 amends the FPA and is therefore subject to FPA section 313. *See Portland Gen. Elec. Co. v. FERC*, 854 F.3d 692, 700 (2017); *Midland Power Coop. v. FERC*, 774 F.3d 1, 3 (2014).

or self-recertification is not protested within the 30 day-period permitted for protests, then, just as it could prior to this final rule, a challenger still has the ability to file a petition for declaratory order, with the filing fee, without being required to show changed circumstances to do so.

- 563. Regarding Basin's request to allow petitions seeking de-certification of QFs that have previously filed self-certifications and ultimately never proceed to development, 888 as we note above we limit the ability to file a protest (rather than a petition for declaratory order, with the accompanying filing fee) to within 30 days of the date of the filing of the self-certification or self-recertification. If an interested party would like to contest a self-certification or self-recertification later than 30 days after the date of its filing, then the interested party may file a petition for declaratory order with the accompanying filing fee, just as they could prior to the effective date of this final rule.
- 564. We decline to adopt the requests that QF developers seeking certification with the Commission be required to publish notice in local newspapers in the states in which the development would be located. We find that the service requirement already in our regulations cited above should serve to provide adequate notice to affected entities.
- 565. We decline to impose a 60-day deadline after which a failure of the Commission to rule on the protest results in the protest being denied by operation of law. Self-certification will be effective upon filing and we adopt the NOPR proposal that the self-certifications will remain effective after a protest has been filed, until such time as the

⁸⁸⁸ Basin Comments at 11.

Commission issues an order revoking certification. We also clarify that selfrecertifications will likewise remain effective after a protest has been filed, until such time as the Commission issues an order revoking certification.

566. We also will adopt the NOPR's proposed timeline for issuance of an order following protests to a QF self-certification and self-recertification. The Commission will issue an order within 90 days of the filing of a protest. However, if the Commission requests more information, the time period for the Commission order would be extended to 60 days from the filing of a complete answer to the information request. In addition to any extension resulting from a request for information, the Commission also may toll the 90-day period during which the Commission commits to act for one additional 60-day period. We clarify, however, that, absent Commission action by the date of the expiration of the tolling period, a protest will be deemed denied, and the self-certification or self-recertification will remain effective. We find that this timeline provides both QFs and other interested persons with certainty about the QFs' status within a reasonable amount of time.

567. Regarding Ares' concern that small power production QFs could be aggregated under the new rule without being aware of the other small power production QFs with which they are aggregated, the Commission notes that this concern would only apply to small power production facilities owned by the same person or its affiliates; it is unlikely that the owner(s) of one facility would not be aware of other, affiliated QFs. Furthermore, the presumption continues to be that a small power production facility seeking QF status that is located more than one but less than 10 miles from any affiliated small power

production QFs is at a separate site from those affiliated small power production QFs, and the Commission here is simply making this presumption rebuttable. If an entity challenges that presumption, the applicant seeking QF status would necessarily be served with the protest⁸⁸⁹ and thus informed of the challenge, and given the opportunity to defend against the challenge.

Connected Entity proceeding, that is a separate proceeding and beyond the scope of this proceeding. Moreover, the data collection at issue in that proceeding does not eliminate the need for the Commission to collect the data required by the FERC Form No. 556 so that the Commission has the information it needs to determine whether a facility qualifies to be a QF consistent with the standards laid out in the statute. In any event, we note that the Connected Entity rulemaking was about market-based rate sellers, not QFs, and it is likely that the Connected Entity rulemaking would not apply to many QFs in the first place since they often nether seek nor have the authority to sell at market-based rates.

569. Regarding Allco's concerns about the RFA, we discuss the RFA issue in section VII.

F. Corresponding Changes to the FERC Form No. 556

1. NOPR Proposal

570. The Commission proposed changes to the FERC Form No. 556, corresponding to the new rules discussed above regarding whether QFs are at separate sites. Currently,

^{889 18} CFR 385.211(b).

item 8a of FERC Form No. 556 requires that the applicant identify any facilities with electrical generating equipment within one mile of the instant facility's electrical generating equipment, as shown below:

8a Identify any facilities with electrical generating equipment located within 1 mile of the electrical generating equipment of the instant facility, and for which any of the entities identified in lines 5a or 5b, or their affiliates, holds at least a 5 percent equity interest.

Check here if no such facilities exist.

	Facility location (city or county, state)	Root docket # (If any)	Common owner(s)	Maximum net power production capacity
1)		QF		kW
2)		QF		kw
3)		QF		kw

- Check here and continue in the Miscellaneous section starting on page 19 if additional space is needed
- 571. The Commission proposed adding a new item 8b, 890 which would be similar to the current item 8a, except that it would cover affiliated facilities whose nearest electrical generating equipment is *greater than 1 mile and less than 10 miles* from the electrical generating equipment of the instant facility.
- 572. The Commission proposed that the instructions for the new item 8b would also allow applicants with facilities identified under item 8b (i.e., facilities more than one mile apart and less than 10 miles apart) to, if they choose, explain (in the Miscellaneous section starting on page 19 of the form) why the facilities identified under item 8b should be considered separate facilities, ⁸⁹¹ considering the relevant physical and ownership factors.

⁸⁹⁰ Subsequent items in that section of the FERC Form No. 556 would be retained but re-numbered and moved down accordingly.

⁸⁹¹ As discussed in detail in section IV.D.1.d, this final rule will change the references to "separate facilities" or "the same facility" to "at separate sites" or "at the same site."

The Commission further proposed to provide reference, in the instructions to the new item 8b, to the paragraphs of this final rule which discuss the relevant physical and ownership factors that may be asserted to defend against rebuttal.

- 573. The Commission sought comment on whether item 8a (existing) should be revised and item 8b (as proposed) written to require that the applicant specify the distance from the instant facility to each affiliated facility listed. We also sought comment on whether items 8a and (new) 8b should require the applicant to document (in the Miscellaneous section on page 19 of the FERC Form No. 556) how the distances reported were calculated. Specifically, we sought comment on whether the applicant should be required to identify the particular electrical generating equipment and associated geographic coordinates used in calculating the distance(s) between the facilities.
- 574. The Commission noted that item 8a currently requires applicants to list all affiliated "facilities." Under this requirement, an applicant would have to list all affiliated QFs as well as affiliated *non*-QFs. We requested comment on whether such a requirement is more burdensome than necessary. It was not clear that requiring the listing of affiliated *non*-QFs is necessary in monitoring for compliance with the relevant QF regulations, which are concerned only with the distance between affiliated *QFs*.
- 575. The Commission also sought comment on whether item 3c (geographic coordinates) and the Geographic Coordinates instructions on page 4 of the current FERC Form No. 556 should be modified such that reporting of geographic coordinates should be required for *all* applications, rather than only for applications where there is no facility street address (as has been the case). We believed such information may provide more

transparency in measuring distances between facilities, and that such transparency may be useful for both the public and Commission staff in monitoring compliance with the Commission's QF regulations.

576. The Commission noted, as it did in Order No. 732, 892 and as in the general form instructions on page 4 of the FERC Form No. 556, that such coordinates can be obtained through certain free online map services (with links and instructions available through the Commission's QF website); GPS devices (including smartphones, which are now nearly ubiquitous); Google Earth; property surveys; various engineering or construction drawings; property deeds; or municipal or county maps showing property lines. The Commission also noted that the Commission has a link on its QF webpage (https://www.ferc.gov/industries-data/electric/power-sales-and-markets/purpa-qualifying-facilities) which provides assistance with determining geographic coordinates of facilities. As such, the Commission believed that the burden that would be created by requiring every QF to provide geographic coordinates would be limited. Even so, the Commission sought comment on whether the value of the information to the public and the Commission would outweigh the limited burden.

⁸⁹² Revisions to Form, Procedures, and Criteria for Certification of Qualifying Facility Status for a Small Power Production or Cogeneration Facility, Order No. 732, 130 FERC ¶ 61,214, at P 100 (2010).

2. Comments

577. A few commenters oppose the changes to FERC Form No. 556 as proposed in the NOPR.⁸⁹³ Solar Energy Industries and the Southeast Public Interest Organizations contend that the proposed new item 8b that requests a list of all affiliated facilities within one to 10 miles from the certifying QF would be a significant increase in information collection, time, effort, and cost of QF certification.⁸⁹⁴

578. The Southeast Public Interest Organizations further object that the obligation to show how distances are calculated and to identify electrical generating equipment and their associated geographic coordinates are overly burdensome for facilities that are presumed to be separate and contradicts the rebuttable presumption of separate facilities, which usually places the burden on the challenger.⁸⁹⁵

579. The Southeast Public Interest Organizations also assert it would be reasonable to ask for only affiliated QFs and to exclude non-QF affiliates from the questions in item 8. 896
580. Several commenters support changes to FERC Form No. 556 as proposed in the NOPR. 897 A few commenters support the proposed changes to item 8a and proposed new

⁸⁹³ Solar Energy Industries Comments at 8; Southeast Public Interest Organizations Comments at 36-37.

⁸⁹⁴ Solar Energy Industries Comments at 56; Southeast Public Interest Organizations Comments at 36-37.

⁸⁹⁵ Southeast Public Interest Organizations Comments at 37-38.

⁸⁹⁶ *Id*.

⁸⁹⁷ APPA Comments at 23; EEI Comments at 50; Portland General Comments at 17-18; Subsurface Engineering Association Comments at 1.

item 8b and argue that the additional information might be otherwise difficult to find and will be useful to clarify if the assumption of separate facilities is appropriate. Some commenters support requiring all applicants to supply geographic coordinates in item 3c, regardless of whether they have a street address.

- 581. Two commenters support the collection of information for all affiliated facilities, not just QF affiliates, within the one or ten-mile radius requested in item 8a and proposed item 8b, respectively, because they believe it will be needed to identify QFs not complying with the proposed rule. 900
- 582. Solar Energy Industries assert that the proposed item 8b to the Form No. 556, requiring a listing of all affiliated facilities whose nearest electrical generating equipment is greater than one mile and less than 10 miles from the electrical generating equipment of the certifying QF, is a substantial expansion of the information collection requirements and goes against the Commission's previously-granted blanket exemptions for QFs to relieve the burden of public utility regulation. Solar Energy Industries argue that this is not a mere information collection requirement, but a request for information that is not otherwise publicly available and is inconsistent with the Commission's finding on the burden of collecting Connected Entity information. Solar Energy Industries argue that

⁸⁹⁸ APPA Comments at 23-24; EEI Comments at 50.

⁸⁹⁹ EEI Comments at 50; Idaho Commission Comments at 7; Subsurface Engineering Association Comments at 1.

⁹⁰⁰ EEI Comments at 50-51; Portland General Comments at 18.

collecting such information from QFs is unwarranted discriminatory treatment and is arbitrary and capricious. 901

583. A few commenters requested additional changes to FERC Form No. 556. 902 North American-Central would like the Commission to create separate Form No. 556 forms for small power producers and cogeneration QFs for a more distinct and simplified application process. 903 EEI would like Form No. 556 to explicitly include battery storage. 904 EEI requests that the Form No. 556 collect information on the rated capacity and notes that net capacity may not be the appropriate measure of power production. Solar Energy Industries also noted that the Commission stated in Order No. 732 that future changes to Form No. 556 would not go through a rulemaking and would instead be reviewed by the Office of Management and Budget with a period for public comments. 905

3. Commission Determination

584. We adopt the NOPR proposals regarding changes to the FERC Form No. 556, with the further clarifications and additions described below. The revised Form No. 556 will be attached to this rule in eLibrary, but will not be published in the *Federal Register* or Code of Federal Regulations. The Commission finds that the added information collected

⁹⁰¹ Solar Energy Industries Comments at 56-57.

⁹⁰² EEI Comments at 51; El Paso Electric Comments at 5-6; North American-Central Comments at 7.

⁹⁰³ North American-Central Comments at 7.

⁹⁰⁴ EEI Comments at 51-52.

⁹⁰⁵ Solar Energy Industries Comments at 56.

by these changes is necessary to implement the changes made to the regulations in this final rule, and thus justifies the increase in reporting burden.

585. The currently effective Form No. 556 contains a "Who Must File" section which specifies when an applicant seeking QF status or recertification of QF status must file a self-certification, and when such applicant is exempt from the filing requirement. We will revise the "Who Must File" section to clarify that the exemption from the requirement to complete or file a Form No. 556 applies to an applicant seeking QF status for a small power production facility that, together with any affiliated small power production QFs within one mile of the entity seeking small power production QF status, has a net power production capacity of 1 MW or less. While we did not seek comment on this corrective change in the NOPR, this change is consistent with the Commission's determination in *SunE B9 Holdings LLC*, 906 and serves to make the Form No. 556 more transparent in its application.

586. We also revise the "Who Must File" section to include a "Recertification" section which provides the text of revised 18 CFR 292.207(f), (previously 18 CFR 292.207(d)) which states that a QF must file for recertification whenever the QF "fails to conform with any material facts or representation presented . . . in its submittals to the Commission." 907

 $^{^{906}}$ 157 FERC ¶ 61,044 at P 16 ("the one-mile rule of section 292.204(a)(2) is a size determination which the Commission has consistently applied generally to the regulations pursuant to PURPA, and which applies here to determining the applicability of the less-than-1-MW exemption of section 292.203(d)") (internal citations omitted).

⁹⁰⁷ 18 CFR 292.207(d).

This addition does not alter our recertification requirements, and we include it here simply to make the Form No. 556 clearer in its application.

The total burden estimates in the "Paperwork Reduction Act Notice" section of 587. FERC Form No. 556 will be updated based on the changes in this final rule, to provide the following estimates: 1.5 hours for self-certifications of facilities of 1 MW or less; 1.5 hours for self-certifications of a cogeneration facility over 1 MW; 50 hours for applications for Commission certification of a cogeneration facility; 3.5 hours for selfcertifications of small power producers over 1 MW and less than a mile or more than 10 miles from affiliated small power production QFs that use the same energy resource; 56 hours for an application for Commission certification of a small power production facility over 1 MW and less than a mile or more than 10 miles from affiliated small power production QFs that use the same energy resource; 9.5 hours for self-certifications of small power producers over 1 MW with affiliated small power production QFs more than one but less than 10 miles that use the same energy resource; 62 hours for an application for Commission certification of a small power production facility over 1 MW with affiliated small power production QFs more than one but less than 10 miles that use the same energy resource.

588. We find that an explanatory "Protest to the Filing" section should be added to the FERC Form No. 556 to note that, pursuant to 18 CFR 292.207, an interested person or entity has 30 days from the date of the filing of the FERC Form No. 556 to intervene or file a protest. The "Protest to the Filing" section will state that the protestor must concurrently serve a copy of such filing, pursuant to 18 CFR 385.211(b), on the Form No.

556 applicant. The "Protest to the Filing" section will also state that the Form No. 556 applicant will have 30 days to file any answer to a protest. The "Protest to the Filing" section will also state that protests may be made to any initial certification, and any recertifications on or after the effective date of this final rule making substantive changes to the existing certification, which may include, for example, a change in electrical generating equipment that increases power production capacity by the greater of 1 MW or 10 percent of the previously certified capacity of the QF, or a change in ownership in which an owner increases their equity interest by at least 10% from the equity interest previously reported. The "Protest to the Filing" section will note that "administrative only" changes will not be subject to protests.

- 589. The Commission finds that item 3c (geographic coordinates) and the Geographic Coordinates instructions on page 4 of the current FERC Form No. 556 will be revised to require all applicants to report the applicant facility's geographic coordinates, rather than only for applications where there is no street address (as was the case previously). We find that such information will provide more transparency regarding the location of each site, and that such transparency may be useful for both the public and Commission staff in monitoring compliance with the Commission's QF regulations.
- 590. The Commission will change item 8a, which currently requires applicants to list all affiliated facilities within one mile, to instead require that the applicant only list affiliated small power production OFs using the same energy resource within one mile.
- 591. We modify the NOPR's proposal to add the collection of information for affiliated facilities whose nearest electrical generating equipment is more than one but less than 10

miles from the electrical generating equipment of the applicant's facility to instead add the collection of information for affiliated small power production QFs using the same energy resource located more than one mile but less than 10 miles from the electrical generating equipment of the applicant's facility. However, rather than adding a separate item 8b to the Form No. 556 specifically for such QFs, as proposed in the NOPR, we are expanding the existing item 8a to require the applicant to list all affiliated small power production QFs using the same energy resource whose nearest electrical generating equipment is *less than 10 miles* from the electrical generating equipment of the entity seeking small power production QF status.

592. We determine that the revised item 8a will require the applicant to list the geographic coordinates of the nearest "electrical generating equipment" of both its own facility and the affiliated small power production QF in question based on the definitions adopted in this final rule. The distance between the entity seeking small power production QF status and each affiliated small power production QF will be automatically calculated based on these coordinates. For any affiliated small power production QFs that cannot be described in item 8a due to space limitations, the instructions will direct applicants to provide the required information for such small power production QFs in the Miscellaneous section of the form. To facilitate the uniform calculation of distances for facility data that are entered into the Miscellaneous section of the form, a distance calculator will be added to the form, and the form instructions will direct applicants to use the calculator to convert their facilities' geographic coordinates into distance.

- 593. The Commission also adopts the NOPR proposal to allow applicants with affiliated small power production QFs *greater than one mile and less than 10 miles* from the electrical generating equipment of the entity seeking small power production QF status identified under item 8a to, if they choose, explain why the affiliated small power production QFs *greater than one mile and less than 10 miles* from the nearest electrical generating equipment of the entity seeking QF status identified under item 8a should be considered to be at separate sites from the entity seeking QF status, considering the relevant physical and ownership factors. The instructions will provide references to the relevant physical and ownership factors, as defined in this final rule, that may be asserted to defend against rebuttal.
- 594. Regarding Solar Energy Industries' concern regarding the expansion of the information collection requirements, we find that the added information collected by item 8a of the Form No. 556 is necessary to implement the changes made to the regulations in this final rule, and thus justifies the increase in reporting burden. As noted in section IV.E, the currently pending Connected Entity proceeding is a separate proceeding and beyond the scope of this proceeding. Moreover, the data collection at issue in that proceeding does not eliminate the need for the Commission to collect the data required by the FERC Form No. 556 so that the Commission has the information it needs to determine whether a facility qualifies to be a QF consistent with the standards laid out in the statute.

- 595. We note that these changes and any future changes to Form No. 556 will continue to be reviewed by the Office of Management and Budget following solicitation of comments from the public, as described in Order No. 732. 908
- 596. We find the requests for additional changes to FERC Form No. 556 beyond the scope of this proceeding.

G. PURPA Section 210(m) Rebuttable Presumption of Nondiscriminatory Access to Markets

1. PURPA Section 210(m) Implementation

a. NOPR Proposal

597. In 2006, when Order No. 688 was issued, the organized electric markets had been in existence for only a few years and were not well understood by all market participants. Now, fourteen years later, the markets are more mature, and the mechanics of participation in such markets are improved and better understood. Consequently, in the NOPR, the Commission determined that small power production facilities below 20 MW should now be able to participate in such markets under most circumstances. The Commission therefore proposed to revise 18 CFR 292.309(d) to reduce the net power production capacity level at which the presumption of nondiscriminatory access to a market attaches for small power production facilities, but not cogeneration facilities, from 20 MW to 1 MW.

⁹⁰⁸ Order No. 732, 130 FERC ¶ 61,214.

598. The Commission determined that, in light of the maturation of organized electric markets, such a reduction was consistent with Congress's intent to relieve electric utilities of their obligation to purchase when a QF has nondiscriminatory access to competitive markets.

599. The Commission noted that, in establishing the original presumption that QFs whose net power production capacity was 20 MW or below lacked nondiscriminatory access to markets defined in sections 210(m)(1)(A)-(C) of PURPA, it had acknowledged that "there is no unique and distinct megawatt size that uniquely determines if a generator is small." The Commission noted that, in using 20 MW to separate the presumption that large QFs had nondiscriminatory access and small QFs lacked such access, the Commission had recognized: (1) Order No. 671's exemption for QFs that are 20 MW or smaller from sections 205 and 206 of the FPA; and (2) Order Nos. 2006 and 2006-A's setting 20 MW as the demarcation for different interconnection standards between small and large generators. The NOPR stated that, while the Commission had not (and

⁹⁰⁹ Order No. 688-A, 119 FERC ¶ 61,305 at P 97.

⁹¹⁰ See Order No. 688, 117 FERC ¶ 61,078 at P 76, order on reh'g, Order No. 688-A, 119 FERC ¶ 61,305 at P 97; see also 18 CFR 292.601(c)(1) ("[S]ales of energy or capacity made by qualifying facilities 20 MW or smaller, or made pursuant to a contract executed on or before March 17, 2006 or made pursuant to a state regulatory authority's implementation of section 210 the Public Utility Regulatory Policies Act of 1978, 16 U.S.C. 824a-1, shall be exempt from scrutiny under sections 205 and 206."); Revised Regulations Governing Small Power Production and Cogeneration Facilities, Order No. 671, 114 FERC ¶ 61,102, at P 98, order on reh'g, Order No. 671-A, 115 FERC ¶ 61,225 (2006) (establishing exemption for QFs 20 MW or below from 205 and 206 of FPA); Standardization of Small Generator Interconnection Agreements and Procedures, Order No. 2006, 111 FERC ¶ 61,220, at P 75, order on reh'g, Order No. 2006-A, 113 FERC ¶ 61,195 (2005), order granting clarification,

likewise did not in the NOPR) propose to revise the exemptions for QFs from sections 205 and 206 of the FPA, the Commission had elsewhere taken steps to ease both interconnection and market access for generation resources with small capacities since it first implemented section 210(m) of PURPA.

Fast-Track interconnection process for some interconnection customers whose capacity is up to and including 5 MW (up from the previous 2 MW threshold), ⁹¹¹ and had required each RTO/ISO to revise its tariff to include a participation model for electric storage resources that establishes a minimum size requirement for participation in the RTO/ISO markets that does not exceed 100 kW. ⁹¹² While both of these changes do not apply only to generation types that could become QFs or only to RTOs/ISOs, the Commission stated that it believed they generally show that small power production facilities below 20 MW, specifically those whose capacity exceeds 1 MW, now have greater access to the markets defined in section 210(m)(1) of PURPA than they did when the Commission first established the presumptions of market access. The Commission also stated that, under the NOPR proposal and like QFs over 20 MW today, small power production facilities

Order No. 2006-B, 116 FERC ¶ 61,046 (2006).

 $^{^{911}}$ Small Generator Interconnection Agreements and Procedures, Order No. 792, 145 FERC ¶ 61,159, at P 103 (2013), clarifying, Order No. 792-A, 146 FERC ¶ 61,214 (2014).

⁹¹² Order No. 841, 162 FERC ¶ 61,127 at P 265.

over 1 MW would still be able to rebut the presumption of access due to operational characteristics or transmission constraints.⁹¹³

The Commission did not propose to make the same reduction applicable to cogeneration facilities. The Commission stated that, unlike small power production facilities, which are constructed solely to produce and sell electricity, cogeneration facilities seeking QF certification after February 2, 2006 are statutorily required to show that they are intended primarily to provide heat for an industrial, commercial, residential or institutional process rather than fundamentally for sale to an electric utility. 914

Consequently, the production and sale of electricity is a byproduct of these thermal processes, and owners of cogeneration facilities might not be as familiar with energy markets and the technical requirements for such sales. The Commission stated that retention of the existing 20 MW level for the presumption of access to markets therefore would be appropriate for cogeneration facilities.

b. <u>Comments in Opposition</u>

602. Numerous commenters oppose the NOPR proposal to revise 18 CFR 292.309(d) to reduce the net power production capacity level at which the presumption of

⁹¹³ See 18 CFR 292.309(c), (e), (f).

⁹¹⁴ See 16 U.S.C. 824a-3(n); 18 CFR 292.205(d)(3). We recognize that cogeneration facilities seeking certification 5 MW or smaller after February 2, 2006 are presumed to satisfy this requirement. 18 CFR 292.205(d)(4).

nondiscriminatory access to a market attaches for small power production facilities, but not cogeneration facilities, from 20 MW to 1 MW.⁹¹⁵

i. <u>Insufficient Evidentiary Support</u>

- 603. Several commenters argue that the record does not support the proposal. 916
- 604. Advanced Energy Economy asserts that, when an agency reverses course on a policy issue, and the "new policy rests upon factual findings that contradict those which underlay" the previous policy, then the agency must "provide a more detailed justification than what would suffice for new policy created on a blank slate." Advanced Energy Economy argues that the NOPR falls short of that standard. 918

⁹¹⁵ Allco Comments at 2, 17-19; Advanced Energy Economy Comments at 1-12; AllEarth Comments at 2; Biogas Comments at 2-3; Biological Diversity Comments at 8-9; California Commission Comments at 31-33; CARE Comments at 5-6; Con Edison Comments at 5; Covanta Comments at 10-12; DC Commission Comments at 4-5; Distributed Sun Comments at 2-3; ELCON Comments at 18, 31-35; Energy Recovery Comments at 4-5; ENGIE Comments at 3-4; Commissioner Slaughter Comments at 2, 4; Green Power Comments at 3; Industrial Energy Consumers Comments at 6-10; Massachusetts AG Comments at 6-8; Michigan Commission Comments at 6-7; North American-Central at 2-4; One Energy Comments at 2; South Dakota Commission Comments at 5; Solar Energy Industries Comments at 44-51; State Entities Comments at 5-6; Western Resource Councils Comments at 1-144.

⁹¹⁶ AllEarth Comments at 2; Advanced Energy Economy Comments at 5-9; Biological Diversity Comments at 9; ELCON Comments at 31-32; Industrial Energy Consumers Comments at 8; New England Hydropower Comments at 11-12; NIPPC, CREA, REC, and OSEIA Comments at 77; Public Interest Organizations Comments at 76-78; SC Solar Alliance Comments at 12; Solar Energy Industries Comments at 45-48; Southeast Public Interest Organization Comments at 39-40.

⁹¹⁷ Advanced Energy Economy Comments at 6 (citing *FCC v. Fox Television Stations, Inc.*, 556 U.S. at 515).

⁹¹⁸ *Id.* at 7.

605. Public Interest Organizations and NIPPC, CREA, REC and OSEI argue that the Commission fails to cite any evidence supporting the premise that the markets are more mature, and that the mechanics of participation in such markets are improved and better understood. Public Interest Organizations and NIPPC, CREA, REC, and OSEIA state that the Commission asserts that QFs smaller than 20 MW can now participate in markets on a nondiscriminatory basis "under most circumstances," but that the Commission does not explain what those "circumstances" are, or whether they apply as a general matter to most small QFs. ⁹¹⁹

606. Several commenters state that, in Order No. 688-A, the Commission, rejected utility proposals to set the threshold at 1 MW, and confirmed that 20 MW was an appropriate threshold. 920 Advanced Energy Economy states that the Commission's explanation in Order No. 688-A, which stated that the rebuttable presumptions were based on the Commission's experience of implementing non-discriminatory open access transmission over the past 11 years, dealing with QF issues over the past 29 years and its experience with RTO/ISO markets for almost 10 years, contradicts the Commission's justification in the NOPR of limited experience with organized electric markets. 921 Advanced Energy Economy and Southeast Public Interest Organizations assert that, since

⁹¹⁹ Public Interest Organizations Comments at 78; NIPPC, CREA, REC, and OSEIA Comments at 77 (citing NOPR, 168 FERC ¶ 61,184 at P 126).

⁹²⁰ Advanced Energy Economy Comments at 5-6; ELCON Comments at 31-32.

⁹²¹ Advanced Energy Economy Comments at 8-9.

Order No. 688, the Commission has repeatedly found that utilities in organized markets have failed to rebut the presumption of nondiscriminatory access to QFs, instead finding that OFs 20 MW and under do not have sufficient access.⁹²²

607. Public Interest Organizations and NIPPC, CREA, REC, and OSEIA argue that the Commission fails to explain the relevance of its Fast-Track interconnection process or energy storage order or which barriers these developments alleviate for small QFs' access to markets. Advanced Energy Economy asserts that the expansion of the Fast-Track procedures only applied to a narrow slice of inverter-based resources under 20 MW and is insufficient to support a rebuttable presumption that all QFs under 20 MW have nondiscriminatory access. 924

608. Solar Energy Industries and New England Hydro argue that, just because some small QFs participate in energy markets, that is not sufficient justification to find that all small QFs meet the statutory standard required for granting waiver for all QFs 20 MW or

⁹²² *Id.* (citing, e.g., *PPL Elec. Utils Corp.*, 145 FERC ¶ 61,053, at P 24 (2013); *City of Burlington*, 145 FERC ¶ 61,121, at P 36 (2013); *Fitchburg Gas and Elec. Light Co.*, 146 FERC ¶ 61,186, at PP 32-33 (2014); *Va. Elec. & Power Co.*, 151 FERC ¶ 61,038, at P 21 (2015); *N. States Power Co.*, 151 FERC ¶ 61,110 (2015)); Southeast Public Interest Organizations Comments at 39-40.

⁹²³ NIPPC, CREA, REC, and OSEIA at 77; Public Interest Organizations Comments at 78 (citing *Motor Vehicle Mfrs. Ass'n of U.S., Inc. v. State Farm Mut. Auto. Ins. Co.*, 463 U.S. 29, 43 (1983) (explaining that an agency's failure to consider the relevant factors and supply a "rational connection between the facts found and the choice made" renders its decision arbitrary and capricious)).

⁹²⁴ Advanced Energy Comments at 7-8.

less. Public Interest Organizations assert that proper implementation of section 210(m) requires that exemption from the mandatory purchase obligation only applies where QF development will be stimulated by market forces; otherwise Congress intended QF development to continue to be encouraged by the mandatory purchase obligation. Protesters assert that the record does not provide evidence that could reasonably allow the Commission to conclude that small QF development will be stimulated by market forces. On the contrary, the Public Interest Organizations assert that the Commission's proposal placing the burden on small QFs to rebut the presumption of access is itself a barrier to QF development.

609. Solar Energy Industries argue that, along with the energy markets, the capacity markets in the RTO/ISO regions have not evolved to provide a meaningful opportunity for any QF to sell long-term capacity. Solar Energy Industries argue that PURPA section 210(m) requires the Commission to find that a QF has nondiscriminatory access to a market for long-term sales of capacity prior to relieving the purchase obligation. Solar Energy Industries provide several examples such as MISO's Planning Resources Auction

⁹²⁵ Solar Energy Industries Comments at 46; New England Hydro Comments at 11-12.

⁹²⁶ Public Interest Organizations Comments at 76 (citing New PURPA Section 210(m) Regulations Applicable to Small Power Production and Cogeneration Facilities, Order No. 688, 117 FERC ¶ 61,078, at P 6 (2006), order on reh'g, Order No. 688-A, 119 FERC ¶ 61,305 (2007), aff'd sub nom. Am. Forest and Paper Ass'n v. FERC, 550 F.3d 1179).

⁹²⁷ *Id*.

⁹²⁸ Solar Energy Industries Comments at 45.

that only provides a one-year purchase agreement, PJM not purchasing capacity since the Commission's July 2019 Order, and that SPP does not have a centralized capacity market. Solar Energy Industries argue that without a specific finding that RTO/ISO markets provide QFs with an opportunity to sell long-term capacity, the Commission is statutorily required to maintain utilities' obligation to purchase output from QFs 20 MWs or less. 929 610. Mr. Mattson asserts, without elaboration, that FPA sections 205 and 206 disallow the Commission from lowering the nondiscriminatory access threshold from 20 MW to 1 MW, and, therefore, claims it would amount to a violation of state-jurisdictional rights and a taking of property. 930

ii. Administrative Burden and Complex Market Rules

611. The DC Commission state that QFs 20 MW or less lack the capability to participate in a complicated wholesale market such as PJM where there is a need to understand membership obligations and rules in order to appropriately execute transactions. ⁹³¹ 612. Allco argues that, in retail choice states, PURPA is the only way small QFs can sell to utilities. Allco asserts that in retail choice states there is a shifting retail customer base, therefore utilities want obligations reduced and contracts limited to a year. Allco asserts that utilities and state commissions cannot limit contracts due to a potentially disappearing customer base and then argue that a sufficient wholesale market exists for long-term sales

⁹²⁹ *Id.* at 49.

⁹³⁰ Mr. Mattson Comments at 10.

⁹³¹ DC Commission Comments at 4-5.

of electric energy and capacity to support nondiscriminatory access for small QFs under 20 MW. 932

613. Public Interest Organizations argue that giving special exemptions to cogeneration facilities is discriminatory against small power producer QFs.⁹³³ Two commenters also assert that small QFs are at an inherent disadvantage compared to larger QFs because smaller QFs are often engaged in other business enterprises, such as governmental units distributing irrigation water or local companies unfamiliar with energy markets.⁹³⁴

c. Comments in Support

614. Numerous commenters support the proposal to revise 18 CFR 292.309(d) for small power production facilities but not cogeneration facilities, to reduce the net power production capacity level at which the presumption of nondiscriminatory access to a market applies from 20 MW to 1 MW. 935 DTE Electric argues that RTO/ISOs can now

⁹³² Allco Comments at 18.

⁹³³ Public Interest Organizations Comments at 74.

⁹³⁴ NIPPC, CREA, REC, and OSEIA Comments at 18-19, 24-25; Mr. Mattson Comments at 15.

⁹³⁵ Alliant Energy Comments at 13-16; Tax Reform Comments at 2; APPA Comments at 24-26; Arizona Public Service Comments at 8-10; Basin Comments at 12-13; Freedom Center Comments at 2; Colorado Independent Energy Comments at 14; Connecticut Commission Comments at 21-22; Conservative Action Comments at 2; Consumers Alliance Comments at 1-2; Consumers Energy Comments at 4-5; DTE Electric Comments at 4-5; East Kentucky Comments at 3; East River Comments at 2; EEI Comments 54-59; FirstEnergy Comments at 2-3; Idaho Power comments at 14; Indiana Municipal Comments at 6-9; Institute for Energy Research Comments at 2; Kentucky Commission Comments at 8; Missouri River Energy Comments at 3-4; NorthWestern at 14; TAPS Comments at 4; Ohio Commission Energy Advocate Comments at 8; Taxpayers Protection Alliance Comments at 2; Chamber of Commerce Comments at 7; We Stand

provide smaller resources non-discriminatory access, and therefore electric utilities should no longer be required to purchase electric energy from them. EEI supports the proposal because resource diversity has improved and markets have evolved as smaller resources, including QFs, are increasingly participating in the RTO/ISO markets. RTOs/ISOs have also increasingly adjusted their bidding rules, forecasts, and operations to better accommodate variable resources. Alliant and the Ohio Commission Energy Advocate state that small resources have increased access to wholesale markets and that RTO/ISO rule flexibility allows for the non-discriminatory participation of very small resources and the aggregation of even smaller resources in the markets, therefore the 20 MW threshold is no longer appropriate. 38

615. Consumer Alliance and EEI argue that reducing the threshold will reduce costs to customers because currently some QFs with access to markets are foregoing the opportunity to participate in those markets and electing to contract with electric utilities under state-implemented PURPA programs, which EEI argues compensate QFs at an above-market rate. 939

Comments at 1-144; Taxpayer Protection Alliance Comments at 2; TAPS Comments at 4.

⁹³⁶ DTE Electric Comments at 5-6.

⁹³⁷ EEI Comments at 56-58.

⁹³⁸ Alliant Energy Comments at 13-14; Ohio Commission Energy Advocate Comments at 7-8.

⁹³⁹ EEI Comments at 58-59; Consumers Alliance Comments at 1-2.

616. The Ohio Commission Energy Advocate argues that the rebuttable presumption process for QFs provides an appropriate safety valve for the lower threshold. 940

d. Comments Requesting Modifications/Clarifications

- 617. Institute for Energy Research requests that the Commission expand the rebuttable presumption of non-discriminatory access to QFs 1 MW and below if the market structure in a given state is appropriate. Institute for Energy Research gives the example of Texas's open market model, where generation is open to all comers of all sizes. Institute for Energy Research also suggests that the Commission should include some threshold now such that when other states achieve similar open access market designs QFs 1 MW and below could be rebuttably presumed to have non-discriminatory access to those markets, without the need to undertake, at that time, a separate rulemaking on QFs 1 MW and below. 941
- 618. The Connecticut Commission suggests reducing the threshold at which the presumption of nondiscriminatory access attaches to 0 MW because the markets are more mature, the mechanics of participating in the markets are improved and the law requires nondiscriminatory access to the markets for all resources. Missouri River Energy recommends lowering the threshold to 500 kW. FirstEnergy recommends the

⁹⁴⁰ Ohio Commission Energy Advocate Comments at 8.

⁹⁴¹ Institute of Energy Research Comments at 2.

⁹⁴² Connecticut Commission Comments at 21-23.

⁹⁴³ Missouri River Energy Comments at 3.

Commission treat both small power production resources and cogeneration resources consistently by lowering the rebuttable presumption threshold from 20 MW to 1 MW for all QFs. 944 Indiana Municipal requests that the Commission automatically apply the 1 MW threshold to utilities that have already been granted waiver for QFs over 20 MW to promote the efficient use of the Commission's resources and savings to utilities. 945 The Michigan Commission requests clarification on the NOPR proposal specifically regarding: (1) how existing contracts with OFs greater than 1 MW but below 20 MWs are to be treated under the NOPR, and if they would be subject to early termination or would be granted legacy treatment indefinitely or until the end of the existing contract term; (2) whether utilities that have already received relief from the mandatory purchase obligation from the Commission for operating within the footprint of an organized wholesale electricity market automatically qualify for relief under the 1 MW threshold; and (3) how interconnection requirements would be considered for QFs between 1 MW and 20 MWs – specifically whether these projects would need to interconnect at transmission level voltages to be considered as having access to the wholesale electricity market. 946 The Michigan Commission notes that there is some tension between the proposal and the market rules for MISO and PJM. 947

⁹⁴⁴ FirstEnergy Comments at 2-3.

⁹⁴⁵ Indiana Municipal Comments at 8-9.

⁹⁴⁶ Michigan Commission Comments at 6-7

⁹⁴⁷ *Id.* at 7 (commenting that MISO, for example, utilizes a 5 MW threshold as the cut off point for Network Modeling purposes and that resources less than 5 MW are

- 620. Several commenters request that the Commission expand the exemption for cogeneration to small power QFs whose primary purpose is to self-supply but still rely on PURPA when making occasional sales to the interconnected utility when QF output exceeds on-site consumption. However producers seeking a 20 MW self-supply exemption meet the "fundamental use test" which currently applies to cogeneration facilities. Other commenters assert that behind-themeter distributed energy resources, Sources, Waste to Energy resources, and baseload renewables are similar to cogeneration facilities and should be included in the exemption.
- 621. Public Interest Organizations request that the Commission clarify that utilities are required to petition to eliminate the must-purchase obligation for small QFs, even for those utilities that have previously made such a showing for QFs larger than 20 MW. 953 NRECA, concerned over a potential change in aggregation for distributed energy resources in RTOs/ISOs, requests that the Commission clarify that the presumption will

modeled on a case-by-case basis only).

⁹⁴⁸ ELCON Comments at 32-33; Industrial Energy Consumers Comments at 6-8; Chamber of Commerce Comments at 7.

⁹⁴⁹ Industrial Energy Consumers Comments at 9-10.

⁹⁵⁰ One Energy Comments at 2.

⁹⁵¹ Industrial Energy Consumers Comments at 9-10.

⁹⁵² Renewable Baseload Coalition Comments at 2.

⁹⁵³ Public Interest Organizations Comments at 76.

only apply to those facilities having sufficient transmission access to the RTO/ISO markets. 954

Hydropower Association asserts that, despite their potential, hydropower resources do not receive the same tax treatment and eligibility for state RPSs and therefore have not enjoyed the same growth rate as other renewable energy small power producers. Hydropower Association urges the Commission to retain the 20 MW rebuttable presumption for hydropower resources, as would be the case for cogenerators, because hydropower resources are required by the FPA section 10(a) to be best adapted for comprehensive uses, including non-power generation purposes such as irrigation, flood control, navigation, recreation, environmental restoration, and wildlife preservation. Hydropower Association states that non-powered dams by definition were not constructed to generate power. Because power generation is therefore a secondary use of these facilities, Hydropower Association asserts that subjecting these facilities to new avoided cost calculations will necessarily burden hydropower resources more than other small power production facilities. Hydropower Association also asserts that there is almost 5 GW of potential non-power dams that could be developed and that the 20 MW exemption should be retained for these resources. 955

623. Ohio Consumers Counsel states that lowering the rebuttable presumption could permit electric utilities and state policies to deny QFs and distributed energy resources

⁹⁵⁴ NRECA Comments at 18-19.

⁹⁵⁵ Hydropower Association Comments at 2-7 (citing 16 U.S.C. 803).

under 20 MW from having unrestricted and nondiscriminatory access to wholesale markets. For example, Ohio Consumers Counsel states that the NOPR would permit electric distribution utilities to limit the availability of after-the-meter generation and storage from PJM's markets, such as through restrictive net metering requirements, unreasonably low compensation for distributed energy resources, or other state regulatory and policy restrictions. Ohio Consumers Counsel urges the Commission to require that investor-owned electric distribution utilities demonstrate that they have not restricted market access to QFs and distributed energy resources rated between 1 MW and 20 MW. 956

e. <u>Commission Determination</u>

624. We agree with commenters that, in Order Nos. 688 and 688-A, given conditions at the time, the Commission established the rebuttable presumption at QFs 20 MW or less. Furthermore, as commenters noted in reviewing several individual cases in 2013-2015, the Commission continued to find that those individual small power production facilities 20 MW or less still needed the additional protections and encouragement. However, since Order Nos. 688 and 688-A the Commission has recognized multiple examples of small power production facilities under 20 MW participating in RTO/ISO energy markets. The

⁹⁵⁶ Ohio Consumers Counsel Comments at 2-5.

 $^{^{957}}$ PPL Elec. Utilities Corp., 145 FERC \P 61,053 at P 24; Va. Elec. & Power Co., 151 FERC \P 61,038, at P 21; N. States Power Co., 151 FERC \P 61,110.

Commission found that the electric utilities in those proceedings rebutted the presumption of no market access and therefore terminated the mandatory purchase obligation. 958 625. We adopt the proposal to revise 18 CFR 292.309(d) to reduce the net power production capacity level at which the presumption of nondiscriminatory access to a market attaches for small power production facilities, but not for cogeneration facilities. However, recognizing some of the challenges that QFs near 1 MW have in participating in such markets that have been identified by commenters, in this final rule we lower the rebuttable presumption from 20 MW to 5 MW, rather than from 20 MW to 1 MW as proposed in the NOPR. Under the final rule, small power production facilities with a net power production capacity at or below 5 MW will be presumed *not* to have nondiscriminatory access to markets, and, conversely, small power production facilities with a net power production capacity over 5 MW will be presumed to have nondiscriminatory access to markets.

626. A number of commenters oppose the reduction below 20 MW, arguing the lack of a record to support the proposal. We disagree. In Order Nos. 688 and 688-A, the Commission determined that small QFs may not have nondiscriminatory access to wholesale markets and, therefore, it was reasonable to establish a presumption for small QFs. At that time, the Commission found that it was "reasonable and administratively workable" to define "small" for purposes of this regulation to be QFs below 20 MW. 959

⁹⁵⁸ See, e.g., Fitchburg Gas and Elec. Light Co., 146 FERC ¶ 61,186, at P 33 (2014); City of Burlington, Vt., 145 FERC ¶ 61,121, at P 33 (2013).

⁹⁵⁹ See Order No. 688, 117 FERC ¶ 61,078 at PP 74-78 (establishing rebuttable

We also note that a number of commenters, including state entities which are charged with applying PURPA in their jurisdictions, ⁹⁶⁰ supported a reduction in the 20 MW threshold. 627. The Commission acknowledged that there is no unique number to draw a line for determining what is a small entity. ⁹⁶¹ In establishing 20 MW presumption as the line between large and small QFs for purposes of section 210(m), the Commission looked at other non-QF rulemaking orders in which it considered what was a small entity and those orders showed 20 MW was a reasonable number at which to draw the line. ⁹⁶² But, as explained below, the Commission has since determined, based on changed circumstances since the issuance of Order Nos. 688 and 688-A, that entities with capacity lower than 20 MW have nondiscriminatory access to the markets and, therefore, capacity level of 20 MW may no longer be a reasonable place to establish the presumption on what constitutes a smaller entity under our regulations.

presumption); Order No. 688-A, 119 FERC ¶ 61,305 at P 95 ("There is no perfect bright line that can be drawn and we have reasonably exercised our discretion in adopting a 20 MW or below demarcation for purposes of determining which QFs are unlikely to have nondiscriminatory access to markets.").

⁹⁶⁰ See Connecticut Commission Comments at 20-21; Kentucky Commission Comments at 8.

⁹⁶¹ Order No. 688-A, 119 FERC ¶ 61,305 at P 97 ("Although there is no unique and distinct megawatt size that uniquely determines if a generator is small, in other contexts the Commission has used 20 MW, based on similar considerations to those presented here, to determine the applicability of its rules and policies.").

 $^{^{962}}$ See Order No. 688, 117 FERC \P 61,078 at P 76; Order No. 688-A, 119 FERC \P 61,305 at PP 96-97.

- 628. Similar to our analysis in Order No. 688, we have determined that entities below 20 MW now can participate in RTO/ISO markets. 963 Here, we are updating the rebuttable presumption based on industry changes since Order No. 688. Moreover, it is reasonable to update the rebuttable presumption as markets defined in PURPA section 210(m)(1)(A), (B), and (C) evolve because that statute itself does not establish a presumption and we are updating the rules, as PURPA provides we will do from time to time, to ensure we comply with PURPA. However, because the revised presumption established in this final rule is a rebuttable presumption, QFs can seek to overcome it.
- 629. Over the last 15 years, the RTO/ISO markets have matured, market participants have gained a better understanding of the mechanics of such markets, and, as a result, we find that it is reasonable to presume that access to the RTO/ISO markets has improved and that it is appropriate to update the presumption for smaller production facilities. As we did in Order No. 688, we have looked to indicia in other orders to determine where the presumption should be set.
- 630. We find that at this time, market rules are inclusive of power producers below 20 MW participating in markets. For example, since the issuance of Order No. 688, the Commission has required public utilities to increase the availability of a Fast-Track interconnection process for projects up to 5 MW. 964 That the Commission chose a 5 MW

⁹⁶³ In fact, when the Commission established the rebuttable presumption of 20 MW, commenters in that proceeding cited instances where QFs at 1 MW or above had already had nondiscriminatory access to RTOs/ISOs. *See* Order No. 688, 117 FERC ¶ 61,078 at PP 64-66.

⁹⁶⁴ Order No. 792, 145 FERC ¶ 61,159, at P 103, clarified, Order No. 792-A,

cut-off for eligibility for the fast-track procedures represents an implicit judgment by the Commission that facilities larger than 5 MW do not need such procedures to be able to interconnect to the grid.

- 631. While the existence of Fast-Track interconnection processes does not on its own demonstrate nondiscriminatory access for resources under 20 MW, it does indicate that entities smaller than 20 MW have access to the market. Presuming that QFs above 5 MW have such access is therefore a reasonable approach to identifying a capacity level at which to update the rebuttable presumption of nondiscriminatory market access.
- 632. Additionally, since the issuance of Order No. 688 the Commission has required each RTO/ISO to update its tariff to include a participation model for electric storage resources that established a minimum size requirement for participation in the RTO/ISO markets that does not exceed 100 kW. 965 These proposals require RTO/ISOs to revise their tariffs to provide easier access for smaller resources. Requiring markets to accommodate storage resources to as low as 100 kW also supports that resources smaller than 20 MW have nondiscriminatory access to those RTO/ISO markets. The Commission believes that these developments support updating the 20 MW presumption to a lower number.
- 633. Commenters argue that individually each of these changes in circumstances, standing alone, may not support the reduction of the threshold below 20 MW. But when

¹⁴⁶ FERC ¶ 61,214.

⁹⁶⁵ Order No. 841, 162 FERC ¶ 61,127 at P 265.

the changes are viewed together, we find that their cumulative effect demonstrates that it is reasonable for the Commission to maintain a small entity rule but update its determination of what is a small entity under this presumption under the PURPA regulations. Additionally, the prospect of increased participation of distributed energy resources in energy markets further supports the proposition that wholesale markets are accommodating resources with smaller capacities. 966

- 634. The Commission recognizes that certain of these precedents would support reducing the presumption below 5 MW, and perhaps even lower than 1 MW. However, the Commission has carefully considered the comments detailing the problems that QFs have had in participating in RTO/ISO markets, problems that necessarily are more acute for smaller QFs at or near the 1 MW threshold proposed in the NOPR. The Commission therefore has determined that a 5 MW is a more reasonable threshold of non-discriminatory access to RTO/ISO markets.
- 635. Based on the foregoing, we find it reasonable to update the presumption under these regulations as to what constitutes a small entity that has non-discriminatory access to

⁹⁶⁶ See, e.g., Elec. Participation in Mkts Operated by Reg'l Transmission Orgs and Independent Sys. Operators, 157 FERC ¶ 61,121, P 129 (2016) ("The costs of distributed energy resources have decreased significantly, which when paired with alternative revenue streams and innovative financing solutions, is increasing these resources' potential to compete in and deliver value to the organized wholesale electric markets." (footnote omitted)).]

⁹⁶⁷ See, e.g., Allco Comments at 17-19; Advanced Energy Economy Comments at 10-11; DC Commission Comments at 5; Public Interest Organizations Comments at 89-90; SEIA Comments at 45-49.

RTO/ISO markets and markets of comparable competitive quality below 20 MW, and that 5 MW represents a reasonable new threshold that accounts for the change of circumstances indicating that 20 MW no longer is appropriate but also accommodates commenters' concerns that a 1 MW threshold would be too low. We acknowledge that "there is no unique and distinct megawatt size that uniquely determines if a generator is small." We find that a 5 MW threshold accords with PURPA's mandate to encourage small power production facilities, recognizes the progress made in wholesale markets as discussed above, and balances the competing claims of those seeking a lower threshold and those seeking a higher threshold.

- 636. Individual small power production QFs that are over 5 MW and less than 20 MW can seek to make the case, however, that they do not truly have nondiscriminatory access to a market and should still be entitled to a mandatory purchase obligation.
- 637. Regarding Advanced Energy Economy's argument that the Commission failed to sufficiently justify its change in policy, we disagree. In FCC v. Fox Television, the court stated that, when an agency makes a change in policy, the agency must show that there are good reasons for the change, "[b]ut it need not demonstrate to a court's satisfaction that the reasons for the new policy are better than the reasons for the old one; it suffices that the new policy is permissible under the statute, that there are good reasons

 $^{^{968}}$ Order No. 688-A, 119 FERC ¶ 61,305 at P 97.

⁹⁶⁹ Advanced Energy Economy Comments at 6 (citing *FCC v. Fox Television*, 556 U.S. at 515).

for it, and that the agency *believes* it to be better, which the conscious change of course adequately indicates."⁹⁷⁰

- entities potentially may not have non-discriminatory access for purposes of PURPA section 210(m). However, as explained above, the Commission has determined that using 20 MW as an indicator of what constitutes a small entity is no longer valid. Entities below 20 MW increasingly have access to the markets, become familiar with practices and procedures, and that markets have since implemented several changes to provide easier access to smaller facilities, including small power production QFs, storage facilities, and distributed energy resources. These changes demonstrate a change in facts since the time we issued Order No. 688 which supports our updating of what constitutes a small entity for purposes of PURPA section 210(m).
- 639. Accordingly, we decline to adopt Ohio Consumers Counsel's suggestion that electric utilities continue to have the burden to demonstrate that certain small power production QFs under 20 MW have nondiscriminatory access to markets like PJM before being relieved of the mandatory purchase obligation for such QFs.
- 640. While we find that it is reasonable to update the rebuttable presumption from 20 MW to 5 MW, we recognize commenters' concerns regarding specific barriers to participation in RTO markets that may affect the nondiscriminatory access to those markets of some individual small power production facilities between 5 MW and 20 MW.

⁹⁷⁰ FCC v. Fox Television, 556 U.S. at 515.

To address these concerns, we additionally are revising 18 CFR 292.309(c)(2)(i)-(vi) to include factors that small power production facilities between 5 MW and 20 MW can point to in seeking to rebut the presumption that they have nondiscriminatory access. These factors are in addition to the existing ability, pursuant to 18 CFR 292.309(c), to rebut the presumption of access to the market by demonstrating, *inter alia*, operational characteristics or transmission constraints.

641. Specifically, the Commission adds to 18 CFR 292.309(c) the following five factors: (1) specific barriers to connecting to the interstate transmission grid, such as excessively high costs and pancaked delivery rates; (2) the unique circumstances impacting the time/length of interconnection studies/queue to process small power QF interconnection requests; (3) a lack of affiliation with entities that participate in RTO/ISO markets; (4) a predominant purpose other than selling electricity which would warrant the small power QF being treated similarly to cogenerators (e.g., municipal solid waste facilities, biogas facilities, run-of-river hydro facilities, and non-powered dams); (5) the QF has certain operational characteristics that effectively prevent the qualifying facility's participation in a market; and (6) the QF lacks access to markets due to transmission constraints, including that it is located in an area where persistent transmission constraints in effect cause the QF not to have access to markets outside a persistently congested area to sell the QF output or capacity. This is not intended to be an exhaustive list of the factors that a QF could rely upon in seeking to rebut the presumption. These factors, among other indicia of lack of nondiscriminatory access, will be assessed by the Commission on a case-by-case basis in considering a claim that the presumption of

nondiscriminatory access to the defined markets should be considered rebutted for a specific QF.

- The addition of these factors addresses commenters' concern that not all small power production facilities between 5 and 20 MW may have nondiscriminatory access to competitive markets, and facilitates the ability of small power production facilities facing barriers to participation in RTO markets to demonstrate their lack of access. For example, while a small power production facility between 5 MW and 20 MW does not need to be physically interconnected to transmission facilities to be considered as having access to the statutorily-defined wholesale electricity markets, we recognize there are some small power production facilities between 5 MW and 20 MW that may face additional barriers, such as excessively high costs and pancaked delivery rates, to access wholesale markets. For example, several commenters express concern over the resources or 643. administrative burden for some small power QFs that lack the necessary experience or expertise to participate in energy markets. Recognizing these concerns, we have added consideration of both the fact that some small power production facilities will face additional difficulties due to costs, administrative burdens, length of the interconnection study process and the size of the queues, and the fact that some small power production QFs do not have access to the expertise of affiliated entities.
- 644. We agree with commenters that some small power production facilities are similar to cogeneration facilities because their predominant purpose is not power production.

 Like cogeneration facilities, the sale of electricity from these small power production facilities is a byproduct of another purpose and these facilities might not be as familiar

with energy markets and the technical requirements for such sales. Therefore, we will allow the small subset of small power production facilities that are between 20 MW and 5 MW to rebut the presumption of access to markets where the predominant purpose of the facility is other than selling electricity, and the sale of electricity is simply a byproduct of that purpose. Finally, like all QFs over 20 MW, we recognize that there may be particular small power production facilities with certain operational characteristics or that are located in an area where persistent transmission constraints in effect cause the QF not to have access to markets outside a persistently congested area to sell the QF output or capacity.

645. While we appreciate Indiana Municipals' concern over preserving Commission resources, we will deny its request to automatically apply the lower threshold to utilities that have already been granted termination for QFs over the 20 MW threshold. We find that it is appropriate to require utilities that were previously granted termination of the mandatory purchase obligation for new contracts and obligations for QFs above 20 MW, but are now seeking to terminate the mandatory purchase obligation for new contracts and obligations for small power production facilities between 5 and 20 MW to follow the procedures in 18 CFR 292.310, including procedures for providing notice to those potentially affected QFs within their footprint. That is, those utilities for which the Commission has already granted relief from the mandatory purchase obligation for small power production facilities over 20 MW must reapply with the Commission requesting relief from the mandatory purchase obligation for small power production facilities between 5 MW and 20 MW.

646. Among other factors, the regulation's notice provision mentioned above will allow small power production facilities between 5 MW and 20 MW an opportunity, if applicable, to present evidence that their facility does not have nondiscriminatory access to defined markets based on the factors discussed above. 971 In the proceeding in which the utility seeks to terminate the mandatory purchase obligation between 5 MW and 20 MW, we will not entertain arguments that the utility should lose its previously granted termination of purchase obligation at 20 MW and above; our regulations provide how a mandatory purchase obligation can be reinstated. We do not, in this final rule, change a QF's right to seek reinstatement of the mandatory purchase obligation where the conditions set forth in 18 CFR 292.309(a), (b), or (c) are no longer met. 972 647. Regarding the Michigan Commission's questions, this final rule preserves the rights or remedies of any party under existing contracts or obligations, in effect or pending approval before the appropriate state regulatory authority or non-regulated electric utility on or before [INSERT DATE 120 DAYS AFTER THE DATE OF PUBLICATION IN THE FEDERAL REGISTER] with QFs between 5 MW and 20 MW. Consistent with Commission precedent, this final rule defines the term "obligations" broadly to encompass any existing legally enforceable obligation. 973

⁹⁷¹ 18 CFR 292.310.

⁹⁷² See 18 CFR 292.311.

⁹⁷³ See Cedar Creek Wind LLC, 137 FERC ¶ 61,006, at PP 35-36 n.62 (2011) (stating that courts have recognized negotiations regarding terms that parties to the negotiations intend to become finalized or written contract, may in some circumstances result in legally enforceable obligations on those parties notwithstanding the absence of a

2. Reliance on RFPs and Liquid Market Hubs to Terminate Purchase Obligation Under PURPA Section 210(m)

a. NOPR Discussion

648. In the NOPR, the Commission noted that NARUC had proposed that the Commission allow utilities to rely on RFPs (in combination with liquid market hubs) to establish eligibility to terminate a utility's purchase obligation pursuant to PURPA section 210(m)(1)(C). 974 After describing generally how such a proposal might be structured, NARUC suggested that "[t]he Commission should create a yardstick of characteristics that describe in detail how a utility could qualify for an exemption under subparagraph (C)."975 649. The Commission stated that, under the PURPA Regulations, electric utilities already may seek to terminate their mandatory purchase obligation pursuant to PURPA section 210(m)(1)(C) by demonstrating that a particular market is of comparable competitive quality to markets described in PURPA section 210(m)(1)(A) and (B). 976 The

writing). See generally Burbach Broadcasting Co. of Delaware v. Elkins Radio Corp., 278 F.3d 401, 407-09 (4th Cir. 2002); Adjustrite Systems, Inc. v. GAB Business Serv., Inc., 145 F.3d 543, 550 (2d Cir. 1998); Miller Constr. Co. v. Stresstek, 697 P.2d 1201, 1202-04 (Idaho 1985).); see also JD Wind 1, LLC, 129 FERC ¶ 61,148 at P 25; Grouse Creek Wind Park, LLC, 142 FERC ¶ 61,187 at PP 40-41.

⁹⁷⁴ NOPR, 168 FERC ¶ 61,184 at P 131 (citing NARUC Supplemental Comments, Docket No. AD16-16-000 (filed Oct. 17, 2018)).

⁹⁷⁵ *Id.*, attach. A at 9.

⁹⁷⁶ *Id.* P 132 (citing Order No. 688-A, 119 FERC ¶ 61,305 at P 43 ("Congress believed the two types of markets identified in subparagraphs (A) and (B), while distinct between themselves, contain certain competitive qualities that justify termination of the purchase requirement for any QF with nondiscriminatory access to those markets. Subparagraph (C) directs the Commission to consider these competitive qualities when analyzing whether there are other markets that, while not meeting the specific requirements of subparagraphs (A) and (B), are sufficiently competitive to justify

Commission further noted that the current PURPA Regulations are not prescriptive about how an electric utility must make such a demonstration and nothing in the PURPA Regulations or precedent would bar an electric utility from arguing that RFPs in combination with liquid market hubs are sufficient to satisfy PURPA section 210(m)(1)(C).

along the lines proposed by NARUC potentially could satisfy the statutory requirements under PURPA section 210(m)(1)(C) and that it would consider such proposals on a case-by-case basis. Although the Commission did not propose additional criteria a utility or utilities may rely on to satisfy PURPA section 210(m)(1)(C), the Commission sought comments on any specific factors that would be useful to consider in determining how a utility or utilities may satisfy PURPA section 210(m)(1)(C).⁹⁷⁷

b. Comments

i. Comments in Opposition

651. A few commenters do not support allowing competition to be an alternative to the mandatory purchase obligation. 978 ELCON is concerned that no state competitive

termination of the purchase requirement.")); cf. Pub. Serv. Co. of N.M., 140 FERC ¶ 61,191, at PP 29-38 (2012) (denying application to terminate mandatory purchase obligation on the grounds that the Four Corners Hub is not of comparable competitive quality to markets in sections 210(m)(1)(A) and (B) of PURPA)).

⁹⁷⁷ *Id.* P 133.

⁹⁷⁸ Allco Comments at 17-19; Public Interest Organizations Comments at 90.

procurement is robust enough to replace avoided capacity costs.⁹⁷⁹ Solar Energy Industries supports using RFPs to set avoided cost rates, but does not support using RFPs to vitiate utilities' mandatory purchase obligations.⁹⁸⁰

- 652. Public Interest Organizations contend that RFPs are not comparable in quality to PURPA section 210(m)(1)(A) or (B) markets because there is only a single buyer and there are no safeguards against the anti-competitive behavior of that buyer, such as favoring its own or an affiliate's generation. NIPPC, CREA, REC, and OSEIA state that, while they agree in principle that competition should be the motivating force in energy markets, their experience shows that utility-sponsored RFP programs often fall far short of genuine competition. P82
- 653. Public Interest Organizations state that Order No. 688-A specifies that demonstrating that a market offers "a meaningful opportunity to sell" usually requires evidence of QF transactions, which is not possible with a market hub. 983 Public Interest Organizations argue that market hubs are not equivalent to PURPA section 210(m)(1)(A)

⁹⁷⁹ ELCON Comments at 19.

⁹⁸⁰ Solar Energy Industries Comments at 24 (citing Solar Energy Industries, Supplemental Comments, Docket No. AD16-16-000, at 10-37, 40-58 (filed Aug. 28, 2019)).

⁹⁸¹ Public Interest Organizations Comments at 93.

⁹⁸² NIPPC, CREA, REC, and OSEIA Comments at 66.

 $^{^{983}}$ Public Interest Organizations Comments at 92 (citing Order No. 688-A, 119 FERC \P 61,305 at P 38).

or (B) markets because, unlike an independently administered auction, there is no guarantee that a QF will be able to sell their energy even if it is the lowest cost resource. 984 654. Public Interest Organizations further contend that the Commission does not have the authority to approve RFPs or liquid market hubs as PURPA section 210(m)(1)(C) wholesale markets because they are not of comparable qualify to Day 1 or Day 2 markets, i.e., to PURPA section 210(a)(1)(A) or (B) markets. 985

ii. Comments in Support

- 655. Several commenters support allowing competition to be an alternative to the mandatory purchase obligation. 986 ELCON supports competitive procurements that exempt industrial self-supply. 987
- 656. APPA supports the Commission reviewing factors that would determine if a market is competitive and comparable to PURPA sections 210(m)(1)(A) and (B). Section 210(m)(1)(C) test should evaluate whether market players have a reasonable opportunity to participate in the market, rather than whether the type of market is similar to PURPA section 210(m)(1)(A) and (B) markets. Section 210(m)(1)(A) and (B) markets.

⁹⁸⁴ Id

⁹⁸⁵ *Id.* at 90-91.

⁹⁸⁶ Advanced Energy Economy Comments at 12; APPA Comments at 29; Colorado Independent Energy Comments at 7; Xcel Comments at 11.

⁹⁸⁷ ELCON Comments at 19.

⁹⁸⁸ APPA Comments at 26-29.

⁹⁸⁹ Xcel Comments at 11.

commenters requested a technical conference to identify the criteria for determining what processes are competitive. ⁹⁹⁰ Colorado Independent Energy would like the RFP standard for PURPA section 210(m)(1)(C) status to be higher than for QF pricing and include evaluation of bid data and the modeling process to show the absence of bias against renewable and cogeneration projects and likewise the absence of bias for utility self-build projects. ⁹⁹¹

obligation pursuant to PURPA section 210(m)(1)(C). Arizona Public Service believes this proposal is one way a utility could demonstrate that a market is of comparable competitive quality to the markets described in PURPA sections 210(m)(1)(A) and (B). 992
658. APPA argues that market hubs should be considered as possibly comparable, particularly to PURPA section 210(m)(1)(B), which requires that QFs have access to Commission-approved transmission service and competitive wholesale markets for long and short-term capacity and energy sales. 993 APPA highlights the Commission finding

⁹⁹⁰ Advanced Energy Economy Comments at 13; ELCON Comments at 19.

⁹⁹¹ Colorado Independent Energy Comments at 6, 11-12.

⁹⁹² Arizona Public Service Comments at 8-10.

⁹⁹³ APPA Comments at 27.

that the Mid-Columbia and Palo Verde hubs have sufficient liquidity to find just and reasonable rates and adds that an empirical test of market liquidity could be created. 994

c. Commission Determination

- 659. In this final rule, we affirm that we will consider utility proposals to terminate the purchase obligation pursuant to PURPA section 210(m)(1)(C) on a case-by-case basis, including utility proposals based on competitive solicitations or liquid market hubs.

 660. In response to Public Interest Organizations, as explained above in Section IV.A.1, PURPA section 210(m) obligates the Commission to grant any request to terminate a utility's obligation to purchase from a QF with nondiscriminatory access to the specified markets that satisfy that provision. Whether any particular market is of comparable quality to a Day 1 or Day 2 market necessarily must be determined in the context of an individual case.
- 661. We refrain from outlining here an exhaustive list of factors that will be used in any such case-by-case evaluation, but at a minimum we will be guided by the important criteria discussed previously in this rule in section IV.B.8 on the use of competitive solicitations to determine avoided costs.
- 662. Consistent with our findings and discussion in section IV.B.4 on the use of market hubs to determine avoided cost, the Commission finds that competitive market prices in general should reflect the avoided cost energy rates of utilities with access to such markets in a given region. We will therefore consider, on a case-by-case basis, whether a properly

⁹⁹⁴ *Id.* at 28.

run RFP or competitive acquisition process may also justify termination of the PURPA purchase obligation pursuant to PURPA section 210(m)(1)(C).

H. <u>Legally Enforceable Obligation</u>

1. NOPR Proposal

- 663. The Commission proposed to add regulatory text in 18 CFR 292.304(d)(3) to require QFs to demonstrate that a proposed project is commercially viable and that the QF has a financial commitment to construct the proposed project pursuant to objective, reasonable, state-determined criteria in order to be eligible for a LEO. The Commission further proposed to provide that states have flexibility as to what constitutes an acceptable showing of commercial viability and financial commitment.
- of 64. The Commission stated that its objective in requiring a showing of commercial viability and the QF's financial commitment to construct the project was to ensure that no electric utility obligation is triggered for those QF projects that are not sufficiently advanced in their development and, therefore, for which it would be unreasonable for a utility to include in its resource planning, while at the same time ensuring that the purchasing utility does not unilaterally and unreasonably decide when its obligation arises. The NOPR proposed that states may require a showing, for example, that a QF has satisfied, or is in the process of undertaking, at least some of the following prerequisites:

 (1) obtaining site control adequate to commence construction of the project at the proposed location; (2) filing an interconnection application with the appropriate entity; (3) securing local permitting and zoning; or (4) other similar, objective, reasonable criteria that allow a QF to demonstrate its commercial viability and financial commitment to

construct the facilities. The NOPR stated that these proposed indicia were not intended to be exhaustive and the Commission sought comment on these indicia and others that also might be appropriate for consideration.

665. The Commission stated that it believed requiring QFs to demonstrate their commercial viability and financial commitment to construct the facilities based on such indicia before obtaining a LEO would allow electric utilities to reliably plan their systems while ensuring resource adequacy. Additionally, the development and definition of objective and reasonable factors to determine commercial viability and financial commitment to construct a facility would encourage the development of QFs by providing QFs with more certainty as to when they will obtain a LEO. 995

2. Comments

a. Comments in Opposition

demonstrate that a proposed project is commercially viable and the QF has a financial commitment to construct the proposed project pursuant to objective, reasonable, state-determined criteria in order to be eligible for a LEO and that states have flexibility as to what constitutes an acceptable showing of commercial viability and financial commitment, arguing it undermines PURPA's intent to promote QF development. 996

⁹⁹⁵ Because QFs already in operation have necessarily demonstrated a commitment to construct the project, the Commission stated that it does not intend commercial viability and financial commitment requirements to serve as prerequisites to QFs already in operation with existing LEOs to obtaining new LEOs.

⁹⁹⁶ NIPPC, CREA, REC, and OSEIA Comments at 81; Public Interest

- of MIPPC, CREA, REC, and OSEIA argue that developers cannot obtain financing without the financial commitment of a PPA or LEO from the utility and therefore requiring financial viability as a condition precedent to obtain a LEO is problematic. Western Resource Councils argues that the NOPR proposal represents an onerous financial and bureaucratic barrier that will lead to a substantial reduction in the number of OFs. 998
- 668. Southeast Public Interest Organizations argue that the proposal does not sufficiently narrow the range of divergent LEO tests that have already been adopted by the states and opposes allowing states additional flexibility in establishing criteria up to a fully executed agreement. Power requests that the Commission establish specific criteria and prohibit states from imposing any additional criteria. Solar Energy Industries requests that the Commission develop a concrete baseline in determining when a QF is entitled to a purchase contract.
- 669. Solar Energy Industries and Public Interest Organizations argue that requiring developers to invest additional capital prior to obtaining a LEO will prevent smaller companies who are unable to invest heavily in early state development activity from

Organizations Comments at 98; Western Resource Councils Comments at 144.

⁹⁹⁷ NIPPC, CREA, REC, and OSEIA Comments at 81.

⁹⁹⁸ Western Resource Councils Comments at 144.

⁹⁹⁹ Southeast Public Interest Organizations Comments at 43

¹⁰⁰⁰ sPower Comments at 14.

participating.¹⁰⁰¹ Solar Energy Industries argue that it is unjust and unreasonable to require QFs to invest millions of dollars in site control, permit acquisition and interconnection costs in order to secure the opportunity to negotiate with the purchasing utility. For those states that do not willingly disclose their avoided cost rates or methodology, the NOPR's LEO proposal requires QFs to incur substantial expense to establish their commercial viability without a reasonable understanding of what their rate may be.¹⁰⁰²

In striking a balance between interconnection and development risk, Solar Energy Industries proposes that the first prerequisite to a LEO formation be either: (a) the completion of the System Impact Study (or the equivalent in the state interconnection process); or (b) where the utility cannot complete the System Impact Study within a reasonable period of time, one year after tendering an interconnection request to the host utility. Where a QF has obtained site control, initiated state permitting processes, submitted an interconnection request and associated study deposit, and has been certified through the submission of a Form No. 556, the Commission should find that the QF is eligible to establish a LEO to sell to the purchasing utility, provided that: (1) the QF has received a System Impact Study report (or equivalent) or one year has elapsed since the

¹⁰⁰¹ Solar Energy Industries Comments at 41; Public Interest Organization Comments at 80-82.

¹⁰⁰² Solar Energy Industries Comments at 41.

¹⁰⁰³ *Id.* at 43.

QF's interconnection request was tendered to the host utility; and (2) the QF commits to achieving commercial operation within 180 days of the completion of all interconnection facilities and network upgrades by the utility. Solar Energy Industries asserts that QFs would, upon satisfaction of these criteria, be legally entitled to negotiate with the purchasing utility to develop a PPA setting forth the terms and conditions of the purchase, including liability if the QF fails to perform. Projects that reach agreement will proceed according to the terms of the PPA and the purchasing utility can establish milestones with enough financial protection to ensure that ratepayers will not be harmed if the QF fails to begin operations. Operations.

- 671. American Dams argues that Interconnection Agreements are generally processed far too slowly, a problem that should be addressed by the Commission. 1006
- 672. Southeast Public Interest Organizations support the requirement of demonstrating site control, but state that requiring permits can be time-consuming and costly such that pre-financing QFs may not have the resources for the lengthy permitting process, and it is unreasonable to expect a QF to incur these expenses until it has secured a price for its output so that it can in turn secure financing for the project.¹⁰⁰⁷

¹⁰⁰⁴ *Id*.

¹⁰⁰⁵ *Id*.

¹⁰⁰⁶ American Dams Comments at 5-6.

¹⁰⁰⁷ Southeast Public Interest Organization Comments at 43-44.

b. Comments in Support

- 673. Numerous commenters support the NOPR's LEO proposal, asserting that state agencies are better positioned to develop criteria that reflect their unique operational circumstances, resource planning needs and risk appetite. Several commenters note that the proposed factors provide a reasonable balance between the planning needs of the connecting utility and certainty to QF developers. Several commenters assert that requiring QFs to demonstrate commercial viability and financial commitment will reduce the reliability or other risks a utility faces by having to plan for its system needs or resource adequacy around a QF that is never developed. 1010
- 674. Several commenters agree that the proposed regulations will provide certainty to host utilities and state commissions while decreasing systems impact and associated costs. 1011

¹⁰⁰⁸ Alaska Power Comments at 1-2; APPA Comments at 30; Chamber of Commerce at 8; Colorado Independent Energy Comments at 13; Connecticut Authority Comments at 24-25; Consumer Alliance Comments at 2; Consumers Energy Comments at 5; East Kentucky Comments at 3-4; East River at 2; El Paso Electric Comments at 6-7; Golden Valley Comments at 7-8; Indiana Municipal Comments at 11-12; Institute for Energy Research Comments at 2; Massachusetts DPU Comments at 10; NARUC Comments at 7-8; NIPPC, CREA, REC, and OSEIA Comments at 81; NRECA Comments at 21; North Carolina Commission Staff Comments at 6; Northern Laramie Range Alliance Comments at 3-4; Ohio Commission Energy Advocate Comments at 10; Oregon Commission at 6.

¹⁰⁰⁹ Alliant Energy Comments at 21; Industrial Energy Consumers Comments at 14-16.

¹⁰¹⁰ Duke Energy Comments at 19; EEI Comments at 37.

¹⁰¹¹ Alliant Energy Comments at 21-22; NRECA at 21; Northern Laramie Range Alliance Comments at 3-4.

675. Connecticut Authority supports the proposal arguing that the factors included in the NOPR will provide greater certainty and less risk to QF developers and purchasing utilities which is consistent with PURPA's goal of developing renewable resources. ¹⁰¹² The Chamber of Commerce argues that the proposed factors indicate a developer's goodfaith intention to ultimately develop its proposed QF. ¹⁰¹³ The Michigan Commission states that it supports the proposal, currently has a rulemaking and several cases pending regarding LEOs, and appreciates any additional clarity the Commission could provide. ¹⁰¹⁴

c. <u>Comments Requesting Modification</u>

676. NIPPC, CREA, REC, and OSEIA request that the Commission: (1) further define the terms "commercial viability" and "financial commitment" to avoid litigation; (2) clarify that any changes to the LEO rules will not affect the viability of any executed contract between a developer and utility, regardless of the facility's development status; and (3) clarify that the LEO rules will not preclude nor bar any utility from executing a PPA before the QF may be able to demonstrate compliance with the implementation of LEO rules. ¹⁰¹⁵

¹⁰¹² Connecticut Authority Comments at 24-25.

¹⁰¹³ Chamber of Commerce Comments at 8.

¹⁰¹⁴ Michigan Commission Comments at 7-8.

¹⁰¹⁵ NIPPC, CREA, REC, and OSEIA Comments at 81-83.

i. Studies

NorthWestern requests that the Commission require more than just the submission of an interconnection application prior to obtaining a LEO in order to demonstrate that the proposal is more than a speculative paper project. 1016 Portland General requests that the Commission allow states to require developers to have completed the first interconnection study. 1017 The South Dakota Commission states that developers should be required to have completed a transmission feasibility study or system impact study with a determination of the interconnection costs the OF would be required to pay prior to obtaining a LEO. 1018 Portland General requests that off-system QFs be required to have completed the first study milestone of the transmission service request. 1019 678. SC Solar Alliance requests that the Commission adopt a recent South Carolina Commission ruling that a QF should be able to establish a LEO after receiving a System Impact Study or within one year if a System Impact Study is not provided in a timely manner and that PPA in-service dates must be extended based on interconnection delays. 1020

¹⁰¹⁶ NorthWestern Comments at 15-16.

¹⁰¹⁷ Portland General Comments at 20.

¹⁰¹⁸ South Dakota Commission Comments at 2.

¹⁰¹⁹ Portland General Comments at 20.

¹⁰²⁰ SC Solar Alliance Comments at 15.

ii. Commercial Viability

679. Alliant Energy requests that the Commission consider requiring QF developers to have contracts in place with equipment suppliers and an analysis of interconnections needed. 1021

680. North Carolina Commission Staff requests that the Commission adopt a North Carolina Commission standard that QFs must (1) commit to sell their power via a written notice of commitment by the earlier of 105 days after submission of an interconnection request or upon receipt of the system impact study, (2) have filed a report of proposed construction, and (3) submitted an interconnection request under the state's interconnection protocol which requires the QF to demonstrate site control. Power argues that option contracts should be sufficient to demonstrate site control.

iii. Financial Viability

681. Portland General and sPower suggest requiring developers to pay a deposit to state commissions to demonstrate financial viability with the amount based on the capacity of the QF and released upon project completion. Portland General asserts that having to

¹⁰²¹ Alliant Energy Comments at 22.

¹⁰²² North Carolina Commission Staff Comments at 6.

¹⁰²³ sPower Comments at 15.

¹⁰²⁴ Portland General Comments at 15-16; sPower Comments at 14-15.

post a deposit encourages developers to perform sufficient due diligence prior to claiming a LEO. 1025

682. North Carolina Commission Staff argues that, in order to protect ratepayers from QFs gaming the process, any project that backs out of its notice of commitment should only receive as-available rates for two years. 1026

iv. Rejecting QF Purchases and Expanded Curtailment Rights

683. North Carolina Commission Staff suggests that the Commission update its regulations to allow curtailing QFs when it would be uneconomic for the utility to make such purchases. The Institute for Energy Research argues that the Commission should allow a utility to reject purchases from QFs if the utility has no need for additional capacity. The Institute for Energy Research states that such need could be determined separately, on an annual basis, a stand-alone basis, or as part of an IRP process. 1028

3. Commission Determination

684. In this final rule, we adopt the NOPR proposal to require QFs to demonstrate that a proposed project is commercially viable and that the QF has a financial commitment to construct the proposed project, pursuant to objective, reasonable, state-determined criteria

¹⁰²⁵ Portland General Comments at 20-21.

¹⁰²⁶ North Carolina Commission Staff Comments at 6.

¹⁰²⁷ *Id.* at 8.

¹⁰²⁸ Institute for Energy Research Comments at 2-3.

in order to be eligible for a LEO. 1029 We also affirm that the states have flexibility as to what constitutes an acceptable showing of commercial viability and financial commitment, albeit subject to the criteria being objective and reasonable. We find that requiring a showing of commercial viability and financial commitment, based on objective and reasonable criteria, will ensure that no electric utility obligation is triggered for those OF projects that are not sufficiently advanced in their development, and therefore, for which it would be unreasonable for a utility to include in its resource planning. At the same time, the criteria ensure that the purchasing utility does not unilaterally and unreasonably decide when its obligation arises. We believe this strikes the right balance for QF developers and purchasing utilities and should encourage development of QFs. 685. Examples of factors a state could reasonably require are that a QF demonstrate that it is in the process of at least some of the following prerequisites: (1) taking meaningful steps to obtain site control adequate to commence construction of the project at the proposed location and (2) filing an interconnection application with the appropriate entity. The state could also require that the OF show that it has submitted all applications, including filing fees, to obtain all necessary local permitting and zoning approvals. We note that the factors that the state requires must be factors that are within the control of the QF. Thus, we clarify that it is appropriate for states to require a QF to demonstrate that it is in the process of obtaining site control or has applied for all local permitting and zoning

¹⁰²⁹ NOPR, 168 FERC ¶ 61,184 at P 140.

approvals, rather than requiring a QF to show that it has obtained site control or secured local permitting and zoning.

686. We agree with Southeast Public Interest Organizations' concerns regarding requiring QFs to obtain permits in order to determine commercial viability. In some regions the permitting and zoning process can be lengthy and expensive, making obtaining the permits and zoning changes a condition to a LEO unreasonable. Therefore, instead of requiring a QF to have secured local permitting and zoning, states can require QFs to have applied for all of the necessary permits and zoning variances, including the payment of all necessary fees, as a factor in demonstrating the QF's commercial viability. States may require a showing that such applications have been submitted to the relevant regulatory bodies (including payment of the application fees).

687. Several commenters argue that requiring QFs to demonstrate financial viability prior to obtaining a LEO is problematic because QFs need a LEO to obtain financing. 1030 However, demonstrating the required financial commitment does not require a demonstration of having obtained financing. Requiring QFs to, for example, apply for all relevant permits, take meaningful steps to seek site control, or meet other objective and reasonable milestones in the QF's development can sufficiently demonstrate QF developers' financial commitment in the QF development and allows utilities to

¹⁰³⁰ NIPPC, CREA, REC, and OSEIA Comments at 81; Western Resource Council Comments at 144.

reasonably rely on the LEO in planning for system resource adequacy. Obtaining a PPA or financing cannot be required to show proof of financial commitment.

688. The intent of these factors is to provide a reasonable balance between providing QFs with objective and transparent milestones up front that are needed to obtain a LEO, allowing states the flexibility to establish factors that address the individual circumstances of each state, and increasing utilities' ability to accurately plan their systems. 1031 Establishing objective and reasonable factors is intended to limit the number of unviable QFs obtaining LEOs and unnecessarily burdening utilities that currently have to plan for QFs that obtain a LEO very early in the process but ultimately are never developed. ¹⁰³² In adopting this provision, the Commission is raising the bar to prevent speculative QFs from obtaining LEOs, and the associated burden on purchasing utilities, but is not establishing a barrier for financially committed developers seeking to develop commercially viable OFs. We disagree that establishing reasonable, transparent factors is an onerous barrier 689. or will cause a substantial reduction of OFs. The objective and reasonable criteria we have established will protect OFs against onerous requirements for a LEO that hinder financing, such as a requirement for a utility's execution of an interconnection

¹⁰³¹ Alliant Energy Comments at 21; Industrial Energy Consumers Comments at 14-16.

¹⁰³² Duke Energy Comments at 19; EEI Comments at 37.

agreement¹⁰³³ or power purchase agreement,¹⁰³⁴ or requiring that QFs file a formal complaint with the state commission,¹⁰³⁵ or limiting LEOs to only those QFs capable of supplying firm power,¹⁰³⁶ or requiring the QF to be able to deliver power in 90 days.¹⁰³⁷ We find that, by making clear that such conditions are not permitted, and by providing objective criteria to clarify when a LEO commences, the LEO provisions we have adopted will encourage the development of QFs.

690. For those commenters that requested that the Commission establish specific factors for the states to apply, or to establish a baseline for eligible factors, or to otherwise limit states' flexibility, we decline to do so. Since its inception, the Commission's PURPA Regulations have established rules and defined boundaries allowing states flexibility within those boundaries in implementing PURPA as appropriate for each state. As commenters noted, this allows states to address their unique circumstances and best address each states' needs. Furthermore, existing precedent establishes a baseline 1038 and

 $^{^{1033}}$ See, e.g., FLS Energy, Inc., 157 FERC ¶ 61,211, at P 26 (2016) (FLS) (stating that requiring signed interconnection agreement as prerequisite to LEO is inconsistent with PURPA Regulations).

¹⁰³⁴ See, e.g., Murphy Flat Power, LLC, 141 FERC ¶ 61,145, at P 24 (2012) (finding that requiring a signed and executed contract with an electric utility as a prerequisite to a LEO is inconsistent with PURPA Regulations.

¹⁰³⁵ See, e.g., Grouse Creek Wind Park, LLC, 142 FERC ¶ 61,187, at P 40 (2013).

¹⁰³⁶ Exelon Wind 1, L.L.C. v. Nelson, 766 F.3d 380, 400 (5th Cir. 2014).

¹⁰³⁷ Power Resource Group, Inc. v. Public Utility Com'n of Texas, 422 F.3d 231, (5th Cir. 2005).

¹⁰³⁸ For example, the Commission has held that requiring a fully-executed contract or executed interconnection agreement as a condition precedent to obtaining a LEO is

this final rule's requirement that states adopt objective and reasonable criteria for determining when a QF has obtained a LEO provides additional safeguards (in addition to that baseline) applicable to both QFs and utilities. Similarly, regarding Solar Energy Industries' proposed pre-requisites and factors, for the reasons stated above, we find that states are in the best position to determine what specific factors would best suit the specific circumstances of that state, so long as they are objective and reasonable, and we provide the suggested prerequisites above as examples of objective and reasonable factors. While Solar Energy Industries' proposed criteria may be reasonable, we decline to mandate specific terms for the entire country.

- 691. Contrary to Solar Energy Industries' assertions, nothing in this final rule limits a QF developer's or utility's ability to negotiate rates, terms or conditions. 1040
- 692. With regard to the argument that the NOPR's LEO proposal is unreasonable in states that do not disclose their avoided cost rate because it would require QFs to incur substantial expense to establish commercial viability without a reasonable understanding of the purchase rate, we find that such state-specific implementation issues can be addressed case-by-case. To the extent that entities believe that a particular state's avoided cost rates or rate setting methodologies do not provide sufficient transparency to support a

inconsistent with PURPA. See FLS, 157 FERC \P 61,211 at P 26; Cedar Creek Wind LLC, 137 FERC \P 61,006 at P 35.

¹⁰³⁹ See supra P 685.

¹⁰⁴⁰ See 18 CFR 292.301(b).

QF's ability to make reasonable commercial viability investment decisions, such entities could file a petition for enforcement against the state at the Commission and, if the Commission declines to act, later file a petition against the state in U.S. district court (pursuant to PURPA section 210(h)(2)(B)).

- 693. NIPPC, CREA, REC, and OSEIA request that we further define the terms commercial viability and financial commitment. We decline. As discussed above, we believe the best course is to allow states the flexibility (employing objective and reasonable factors) to determine what constitutes commercial viability and financial commitment relative to the unique conditions or circumstances in each state but also recognizing that existing Commission precedent establishes boundaries of what would be considered reasonable and not discriminatory limits for requirements in establishing a LEO. ¹⁰⁴¹
- 694. Additionally, we clarify that any changes to the LEO rules adopted herein do not affect the viability of any executed contract or LEO between a QF developer and utility in place as of the effective date of this final rule, regardless of the facility's development status. Further we clarify that nothing in the LEO rules adopted herein precludes any utility from choosing to execute a PPA before a QF has demonstrated compliance with the LEO rules adopted here.

 $^{^{1041}}$ See FLS, 157 FERC \P 61,211 at P 26; Cedar Creek Wind LLC, 137 FERC \P 61,006 at P 35.

Several commenters requested that the Commission require QFs to do more than just file an interconnection application; instead, for example, suggesting requiring completion of system impact study, interconnection or transmission feasibility study. 1042 We disagree. The approach taken here recognizes the need for a QF to demonstrate that its project is more than mere speculation, such that it is reasonable for a utility to consider the resource in its planning projections. A QF that has submitted an application for interconnection, as well as having taken meaningful steps to obtain site control and has applied for all relevant permits, while not a guarantee that the project will be completed, are all objective and reasonable indicators that the QF developer is seriously pursuing the project and has spent time and resources in developing the project to show a financial commitment.. As numerous commenters have explained, QFs need a LEO in order to obtain financing to complete the project, and we find that, as an illustrative example, requiring the submission of an interconnection request (as opposed to the completion of a system impact study or transmission feasibility study) as one criteria strikes an appropriate balance between the competing needs.

695. Moreover, it bears remembering that the concept of a LEO was specifically adopted to prevent utilities from circumventing the mandatory purchase requirement under PURPA by refusing to enter into contracts. The Commission thus has found that

¹⁰⁴² NorthWestern Comments at 15-16, Portland General Comments at 20, South Dakota Commission Comments at 2.

¹⁰⁴³ JD Wind 1, LLC, 129 FERC ¶ 61,148 at P 25, reh'g denied, 130 FERC ¶ 61,127 (citing Order No. 69 FERC Stats. & Regs. ¶ 30,128 at 30,880; see also Midwest

requiring a QF to have a utility-executed contract or interconnection agreement, or requiring the completion of a utility-controlled study places too much control over the LEO in the hands of the utility and defeats the purpose of a LEO and is inconsistent with PURPA. 1044 When reviewing factors to demonstrate commercial viability and financial commitment, states thus should place emphasis on those factors that show that the QF has taken meaningful steps to develop the QF that are within the QF's control to complete, and not on those factors that a utility controls. For example, requiring a QF to make a deposit as Portland General and sPower proposed or whether the QF has applied for system impact, interconnection or other needed studies are the types of factors that may show that the QF has taken meaningful steps to develop the QF that are within the QF's control and the type of objective and reasonable standards that states can consider in their implementation. 1045

696. Requests by parties to expand utilities' rights to curtail QF sales are outside the scope of this proceeding. Additionally, requests to allow a utility to reject purchases from QFs if a utility has no need for additional capacity are outside the scope of this proceeding.

Renewable Energy Projects, LLC, 116 FERC ¶ 61,017 (2006).

 $^{^{1044}}$ FLS, 157 FERC ¶ 61,211 at P 23 (finding such requirements "allows a utility to control whether and when a legally enforceable obligation exists – e.g. by delaying the facilities study.").

¹⁰⁴⁵ Portland General Comments at 15-16; sPower Comments at 14-15.

V. Information Collection Statement

The Paperwork Reduction Act¹⁰⁴⁶ requires each federal agency to seek and obtain 697. the Office of Management and Budget's (OMB) approval before undertaking a collection of information (including reporting, record keeping, and public disclosure requirements) directed to 10 or more persons or contained in a rule of general applicability. OMB regulations require approval of certain information collection requirements contemplated by proposed rules (including deletion, revision, or implementation of new requirements). 1047 Upon approval of a collection of information, OMB will assign an OMB control number and an expiration date. Respondents subject to the filing requirements of a rule will not be penalized for failing to respond to the collection of information unless the collection of information displays a valid OMB control number. **Public Reporting Burden:** The Commission is revising its regulations implementing PURPA. At the Notice of Proposed Rulemaking (NOPR) stage, the Commission stated the principal changes that affect information collection involved the FERC Form No. 556. 1048 In response to comments arguing that the NOPR proposals would cause additional reporting burdens, in this final rule we have analyzed whether there are

¹⁰⁴⁶ 44 U.S.C. 3501-21.

¹⁰⁴⁷ See 5 CFR 1320.11.

¹⁰⁴⁸ The change to the FERC-556 described by the NOPR was submitted under a temporary interim information collection no., FERC-556A (OMB Control No. 1902-0316) because another item for FERC-556 was pending OMB review at the time and only one item per OMB Control No. can be pending OMB review at a time. The final rule is being submitted to OMB under FERC-556.

additional incremental reporting burdens that result from other aspects of this final rule. As described further below, we find that there is one additional potential reporting burden arising from this final rule. It relates to reducing the PURPA section 210(m) rebuttable presumption regarding small power production QFs' nondiscriminatory access to certain markets from 20 MW to 5 MW. Specifically, this reporting burden would arise from electric utilities located in markets who choose to submit to the Commission a PURPA section 210(m) petition for termination of the PURPA mandatory purchase obligation (affecting information collection FERC-912) for small power production QFs between 20 MW and 5 MW.

698. With respect to the FERC Form No. 556, the Commission affirms that the relevant burdens derive from the change from the Commission's current "one-mile rule" for determining whether generation facilities should be considered to be at the same site for purposes of determining qualification as a qualifying small power production facility, to allowing an interested person or other entity challenging a QF certification the opportunity to file a protest, without a fee, to rebut the presumption that affiliated small power production QFs using the same energy resource and located more than one mile and less than 10 miles from the applicant facility are considered to be at separate sites.

Specifically, as more fully explained in section IV.F above, and as demonstrated by the revised Form No. 556 attached to this final rule (but not published in the Federal Register

or Code of Federal Regulations), ¹⁰⁴⁹ the Commission makes the following changes to the FERC Form No. 556 which affect the burden of the information collection:

- Allow an interested person or other entity challenging a QF certification the opportunity to file a protest, without a fee, to an initial certification (both self-certification and application for Commission certification) filed on or after the effective date of this final rule, or to a recertification (self-recertification or application for Commission recertification) that makes substantive changes to the existing certification that is filed on or after the effective date of this final rule.
- Require *all* applicants to report the applicant facility's geographic coordinates, rather than only for applications where there is no street address.
- Change the current requirement to identify *any* affiliated facilities with electrical generating equipment within one mile of the applicant facility's electrical generating equipment to instead require applicants to list only affiliated small power production QFs using the same energy resource one mile or less from the applicant facility.
- Additionally require applicants to list affiliated small power production QFs using
 the same energy resource whose nearest electrical generating equipment is greater
 than one mile and less than 10 miles from the electrical generating equipment of
 the applicant facility.

¹⁰⁴⁹ The Form 556 and instructions will be available in the Commission's eLibrary.

- Require the applicant to list the geographic coordinates of the nearest "electrical generating equipment" of both its own facility and the affiliated small power production QF in question based on the definitions adopted in this final rule.
- Provide space for the applicant to explain, if it chooses to do so, why the affiliated small power production QFs using the same energy resource, that are more than one mile and less than 10 miles from the electrical generating equipment of the applicant facility, should be considered to be at separate sites from the applicant's facility, considering the relevant physical and ownership factors identified in this final rule.

As explained in the body of this final rule, these changes in burden are appropriate because they are necessary to meet the statutory requirements contained in PURPA.

699. In this final rule, the Commission is revising its regulations implementing PURPA, which will affect the information collections for the FERC Form No. 556 and FERC-912.

Below, the first table includes estimated changes to the burden and cost of the FERC Form No. 556 due to the final rule. As demonstrated by the table, we believe that QFs will spend more time to identify any affiliated small power production QFs that are less than one mile, between one and 10 miles, and more than 10 miles, apart. The Commission expects that there will be an increase due to the revisions to the Commission's regulations, and that the changes to the "one-mile rule" and the ability to protest without a fee will affect self-certifications and applications for Commission certification.

FERC-556, Changes Due to Final Rule in Docket Nos. RM19-15-000 and AD16-16-000 ¹⁰⁵⁰							
Facility Type	Filing Type	Number of Respondents (1)	Annual Number of Responses per Respondent (2)	Total Number of Responses (1)*(2)=(3)	Increased Average Burden Hours & Cost Per Response (\$) (4)	Increased Total Annual Burden Hours & Total Annual Cost (\$) (3)*(4)=(5)	Increased Annual Cost per Respondent (\$) (5)÷(1)=(6)
Cogeneration and Small Power Production Facility ≤ 1 MW ¹⁰⁵¹	Self- certification	no change (692)	no change (1.25)	no change (865)	no change (1.5 hrs.); \$0	no change (1,297.5 hrs.); \$0	\$0
Cogeneration Facility > 1 MW	Self- certification	no change (63)	no change (1.25)	no change (78.75)	no change (1.5 hrs.); \$0	no change (118.125 hrs.); \$0	\$0
Cogeneration Facility > 1 MW	Application for FERC certification	no change (1)	no change (1.25)	no change (1.25)	no change (50 hrs.);	no change (62.5 hrs.); \$0	\$0
Small Power Production Facility > 1	Self- certification	no change (899) ¹⁰⁵²	no change (1.25)	no change (1,123.75)	2 hrs.; \$166	2,247.5 hrs.;	\$207.5

¹⁰⁵⁰ The figures in this table reflect estimated changes to the current OMB-approved inventory for the FERC Form No. 556 (approved by the Office of Management and Budget (OMB) on November 18, 2019).

Where "no change" is indicated, the current figure is included parenthetically for information only. Those parenthetical figures are not included in the final total for column 5.

Commission staff believes that the industry is similarly situated in terms of wages and benefits. Therefore, cost estimates are based on FERC's 2020 average hourly wage (and benefits) of \$83.00/hour. (The submittal to and approval of OMB in 2019 for FERC Form No. 556 was based on FERC's 2018 average annual wage hourly rate of \$79.00/hour. Because the change from the \$79.00 hourly rate to the current \$83.00 hourly rate was not due to the final rule, this chart does not depict this increase.)

¹⁰⁵¹ Not required to file.

¹⁰⁵² In the FERC Form No. 556 approved by OMB in 2019, for the category "Small Power Production Facility > 1 MW, Self-certification," we estimated the number of respondents at 2,698. We have now divided that category into three categories: "Small Power Production Facility > 1 MW, ≤ 1 Mile from Affiliated Small Power Production QF," "Small Power Production Facility > 1 MW, > 1 Mile, < 10 Miles from Affiliated Small Power Production QF," "Small Power Production Facility > 1 MW, ≥ 10 Miles from Affiliated Small Power Production QF." In this column, the numbers 899, 900, and

MW, ≤ 1 Mile from Affiliated Small Power Production QF						\$186,542.5	
Small Power Production Facility > 1 MW, ≤ 1 Mile from Affiliated Small Power Production QF	Application for FERC certification	no change (0)	no change (1.25)	no change	6 hrs.; \$498	no change (0 hrs.); \$0	\$0
Small Power Production Facility > 1 MW, > 1 Mile, < 10 Miles from Affiliated Small Power Production QF	Self- certification	no change (900)	no change (1.25)	no change (1,125)	8 hrs.; \$664	9,000 hrs.; \$747,000	\$830
Small Power Production Facility > 1 MW, > 1 Mile, < 10 Miles from Affiliated Small Power Production QF	Application for FERC certification	no change (0)	no change (1.25)	no change (0)	12 hrs.; \$996	no change (0 hrs.); \$0	\$0
Small Power Production Facility > 1 MW, ≥ 10 Miles from Affiliated Small Power Production QF	Self- certification	no change (899)	no change (1.25)	no change (1,123.75)	2 hrs.; \$166	2,247.5 hrs.; \$186,542.5	\$207.5
Small Power Production Facility > 1 MW, ≥ 10 Miles from Affiliated Small Power Production QF	Application for FERC certification	no change (0)	no change (1.25)	no change (0)	6 hrs.; \$498	no change (0 hrs.); \$0	\$0
FERC-556, TOTAL ADDITIONAL BURDEN AND COST DUE TO FINAL RULE		no change (3,454)		no change (4,317.5)		13,495 hrs.; \$1,120,085	

700. The table below reflects the additional estimated public reporting burdens associated with reducing the PURPA section 210(m) rebuttable presumption regarding small power production QFs' nondiscriminatory access to certain markets from 20 MW to 5 MW, which affects the FERC-912. The FERC-912 is optional, but if electric utilities

899 are a distribution of those same estimated 2,698 respondents across the three categories.

¹⁰⁵³ This information was not included in the burden estimates in the NOPR.

located in relevant markets choose to submit to the Commission a PURPA section 210(m) petition for termination of the PURPA mandatory purchase obligation for small power production QFs between 20 MW and 5 MW, then we would expect the following burdens and cost estimates to apply.

FERC-912, Changes Due to Final Rule in Docket Nos. RM19-15-000 and AD16-16-000						
(termination of obligation to purchase)	Number of Respondents (1)	Annual Number of Responses per Respondent (2)	Total Number of Responses (1)x(2)=(3)	Increased Average Hours & Cost Per Response (\$) (4)	Increased Total Annual Burden Hours & Total Annual Cost (\$) (3)*(4)=(5)	Increased Annual Cost Per Respondent (at \$83/hr.) (5)/(1)=(6)
Electric utility burden						
of reducing						
210(m)						
rebuttable presumption						
from 20 MW				12 hrs.;	360 hrs.;	
to 5 MW ¹⁰⁵⁴	30	1	30	\$996	\$29,880	\$996
Total	30	1	30	12 hrs.; \$996	360 hrs.; \$29,880	\$996

Title: FERC-556 (Certification of Qualifying Facility (QF) Status for a Small Power Production or Cogeneration Facility), and FERC-912 (PURPA Section 210(m) Notification Requirements Applicable to Cogeneration and Small Power Production Facilities).

¹⁰⁵⁴ The staff estimates a total of 90 discretionary responses may be submitted in Years 1-3, with an annual average of 30.

Action: Revisions to existing information collections FERC-556 and FERC-912.

OMB Control No.: 1902-0075 (FERC-556) and 1902-0237 (FERC-912).

Respondents: Facilities that are self-certifying their status as a cogenerator or small power producer or that are submitting an application for Commission certification of their status as a cogenerator or small power producer; electric utilities filing to terminate their obligation to purchase, at avoided cost rates, the output of small power production QFs between 5 MW and 20 MW.

Frequency of Information: Ongoing.

Necessity of Information: The Commission directs the changes in this final rule revising its implementation of PURPA in order to continue to meet PURPA's statutory requirements.

Internal Review: The Commission has reviewed the changes and has determined that such changes are necessary. These requirements conform to the Commission's need for efficient information collection, communication, and management within the energy industry.

701. Interested persons may obtain information on the reporting requirements by contacting the Federal Energy Regulatory Commission, 888 First Street, NE, Washington, DC 20426 [Attention: Ellen Brown, Office of the Executive Director], by email to DataClearance@ferc.gov or by phone (202) 502-8663].

Please send comments concerning the collection of information and the associated burden estimates to: Office of Information and Regulatory Affairs, Office of Management and Budget [Attention: Federal Energy Regulatory Commission Desk Officer]. Due to

security concerns, comments should be sent directly to

www.reginfo.gov/public/do/PRAMain. Comments submitted to OMB should be sent within 30 days of publication of this notice in the Federal Register and should refer to FERC-556 (OMB Control No. 1902-0075) and FERC-912 (OMB Control No. 1902-0237).

VI. Environmental Analysis

702. The Commission in the NOPR explained that it was not possible to determine the environmental effects of the changes proposed, given the numerous uncertainties regarding the potential effects of the changes proposed. The Commission in the NOPR stated that, given these uncertainties, the National Environmental Policy Act of 1969 (NEPA)¹⁰⁵⁵ does not require that the Commission conduct an environmental review of the proposed revised PURPA Regulations.¹⁰⁵⁶

A. Comments

703. Several commenters argue that the Commission erred in failing to conduct such a review. 1057

704. Biological Diversity asserts an urgent need to take measures to reduce greenhouse gas emissions to address climate change. Biological Diversity states that the

¹⁰⁵⁵ 42 U.S.C. 4321 et seq.

¹⁰⁵⁶ NOPR, 169 FERC ¶ 61,184 at PP 154-55.

¹⁰⁵⁷ Allco Comments at 21-22; Biological Diversity Comments at 14; NIPPC, CREA, REC, and OSEIA Comments at 83; Public Interest Organizations Comments at 21.

¹⁰⁵⁸ Biological Diversity Comments at 2-7.

Commission's rationale for revising the PURPA Regulations, namely the increased availability of "fossil gas," requires the Commission to consider the reasonably foreseeable impacts on climate and the environment, including on threatened and endangered species, in order to fulfill its responsibilities under NEPA and the Endangered Species Act (ESA). Biological Diversity includes a list of what it alleges are reasonably foreseeable impacts from increased use of "fossil gas." Biological Diversity maintains that the proposed revised PURPA Regulations would prevent renewable energy development and lock in "fossil gas" development and supply, thereby requiring the Commission to prepare an environmental impact statement and to obtain a biological opinion before proceeding to a final rule.

705. NIPPC, CREA, REC, and OSEIA state that "the Commission must, at a minimum, complete the requisite scoping and other process associated with an EA and then revise and reissue, or abandon, the NOPR after considering the issues developed in the EA." NIPPC, CREA, REC, and OSEIA argue that it would not be too speculative for the Commission to undertake a NEPA analysis. NIPPC, CREA, REC, and OSEIA state

¹⁰⁵⁹ *Id.* at 14.

¹⁰⁶⁰ *Id.* at 15-17.

¹⁰⁶¹ *Id.* at 17.

¹⁰⁶² NIPPC, CREA, REC, and OSEIA Comments at 83-85 (citing, e.g., 42 U.S.C. 4332(A); 18 CFR 380.5, 380.4, 380.11; 40 CFR 1500.1, 1502.5; LaFlamme v. FERC, 852 F.2d 389, 397 (9th Cir. 1988); Am. Bird Conservancy, Inc. v. FCC, 516 F.3d 1027, 1033-34 (D.C. Cir. 2008); N. Plains Res. Council, Inc. v. Surface Transp. Bd., 668 F.3d 1067, 1075 (9th Cir. 2011) (N. Plains Res. Council)).

¹⁰⁶³ NIPPC, CREA, REC, and OSEIA Comments at 92-94 (citing, e.g., Am. Bird

that it is possible to study the environmental effects of the NOPR proposals because the Commission undertook a NEPA analysis when it first implemented PURPA, imposing a moratorium on certifying cogeneration facilities as QFs until it completed an Environmental Impact Statement (EIS) and recognizing the environmental benefits from encouraging the development of QFs, and also studied the environmental impacts for Order No. 888. ¹⁰⁶⁴

706. Public Interest Organizations state that the Commission must prepare an Environmental Assessment (EA) in order to support its position that this rulemaking may not have any significant foreseeable environmental impacts. Public Interest Organizations describe the NOPR's "cursory treatment of the Commission's environmental review obligations" as undermining NEPA's purposes "that agencies give due consideration to environmental impacts when making major environmental decisions, and guaranteeing that the public is informed of such impacts." Public Interest Organizations argue that states' exercise of new flexibility granted by the proposed revised PURPA Regulations are reasonably foreseeable indirect and cumulative impacts that the Commission must study. Public Interest Organizations assert that the

Conservancy, Inc. v. FCC, 516 F.3d 1033); N. Plains Res. Council, 668 F.3d at 1076, 1078-79.

¹⁰⁶⁴ *Id*. at 94-96.

¹⁰⁶⁵ Public Interest Organizations Comments at 21.

¹⁰⁶⁶ *Id*.

impacts that will result from dismantling regulations that continue to play an important role in development of renewable generation resources across the country."¹⁰⁶⁷
707. NIPPC, CREA, REC, and OSEIA argue that the Commission has failed to explain how eliminating the market for at least 10% to 20% of renewable energy facilities would have no impact on the human environment. NIPPC, CREA, REC, and OSEIA contend that the Commission has failed to analyze how the proposals would impact regions like the Northwest that lack robust implementation of PURPA, the 21 states without renewable power standards (such as the Idaho, whose Legislature affirmatively refused to adopt a renewable power standard), or the one third of the country that is not located in an RTO or ISO. ¹⁰⁶⁹

708. Allco argues that it is reasonably foreseeable that the proposed revisions to the PURPA Regulations and resulting increased fossil fuels use could add significant levels of greenhouse gas emissions to the atmosphere and endanger the climate. The effects of such endangerment to the climate from fossil fuel use and reduced renewable energy QF generation, according to Allco, include mass extinction of species, in violation of the ESA. Allco contends that the Commission's failure to consult with the U.S. Fish and

¹⁰⁶⁷ *Id.* at 26.

¹⁰⁶⁸ NIPPC, CREA, REC, and OSEIA Comments at 86-87.

¹⁰⁶⁹ *Id.* at 87-88.

¹⁰⁷⁰ Allco Comments at 31.

¹⁰⁷¹ *Id*.

Wildlife Service and the National Marine Fisheries Service (collectively, the Services) prior to issuing the NOPR constituted a violation of its obligations under the ESA, "to insure that its actions are not likely to jeopardize the continued existence of endangered or threatened species, or result in the destruction or adverse modification of critical habitat."¹⁰⁷²

709. According to Allco, the PURPA NOPR triggered the ESA's consultation requirement because the proposed changes will increase fossil fuel generation that will, in turn, displace "over 2 [terawatts (TWs)] of solar generation over the next 20 years as compared to the baseline scenario of application and faithful adherence to existing PURPA rules." Allco alleges that increased fossil-fuel generation will "increase land and ocean temperatures above what they would have been, . . . resulting in increased pollution to the waters of the United States, and harming federally endangered and threatened species, including, without limitation, the Piping plover and the Right whale." 1074

B. Commission Determination

710. We find that no EA or EIS of the final rule is required. NEPA requires federal agencies to prepare a detailed statement on the environmental impact of "major Federal actions significantly affecting the quality of the human environment." The Council on

¹⁰⁷² Id. at 34 (quoting 16 U.S.C. 1536(a)(2)) (internal quotations omitted).

¹⁰⁷³ *Id*.

¹⁰⁷⁴ *Id.* at 34-35.

¹⁰⁷⁵ 42 U.S.C. 4332(C) (2018); see also Regulations Implementing the National

Environmental Quality's (CEQ) regulations implementing NEPA provide that federal agencies can comply with NEPA by preparing: (a) an Environmental Impact Statement (EIS); or (b) an Environmental Assessment (EA) to determine whether the proposed action significantly affects the quality of the human environment and requires the preparation of an EIS. 1076 CEQ regulations also state that federal agencies are not obligated to prepare either an EIS or an EA if they find that a categorical exclusion applies. 1077 Additionally, courts have held that an EIS or EA is not required under NEPA "unless there is a particular project that 'define[s] fairly precisely the scope and limits of the proposed development." 1078

711. No EA or EIS of the final rule is required because, as discussed below, the final rule does not propose or authorize, much less define, the scope and limits of any potential energy infrastructure and, as a result, there is no way to determine whether issuance of the rule will significantly affect the quality of the human environment. In the alternative, a

Environmental Policy Act, Order No. 486, FERC Stats. & Regs. ¶ 30,783 (1987) (cross-referenced at 41 FERC ¶ 61,284).

¹⁰⁷⁶ 40 CFR 1501.4 (2019).

¹⁰⁷⁷ CEQ regulations state that a categorical exclusion "means a category of actions which do not individually or cumulatively have a significant effect on the human environment and which have been found to have no such effect in procedures adopted by a federal agency in implementation of these regulations and for which, therefore, neither an environmental assessment nor an environmental impact statement is required." 40 CFR 1508.4 (2019).

¹⁰⁷⁸ Center for Biological Diversity v. Ilano, 928 F.3d 774, 780 (9th Cir. 2019) (Center for Biological Diversity) (quoting Kleppe v. Sierra Club, 427 U.S. 390, 402 (1976)).

categorical exclusion applies so that an EA or EIS need not be prepared. For similar reasons, there is no requirement that the Commission engage in consultation pursuant to the ESA with respect to this action.

1. No EIS or EA is Required

a. There is no Project that Defines the Scope and Limits of OF Development

712. In Center for Biological Diversity, the court held that no NEPA review was required with respect to actions taken by the United States Forest Service that were similar in all relevant respects to the action taken here by the Commission in promulgating the final rule. That case involved the designation by the Forest Service, pursuant to the Healthy Forests Restoration Act (HFRA), of certain forests as "landscape-scale areas." Such designation meant that specific treatments could be proposed to address insect infestation in those designated "landscape-scale areas." The court held that no NEPA review was required for the designations, noting that no specific projects were proposed for any of the landscape-scale areas and stating that "[i]n such circumstances, 'any attempt to produce an [EIS] would be little more than a study . . . containing estimates of potential development and attendant environmental consequences." The court concluded that "unless there is a particular project that 'define[s] fairly precisely the scope and limits of

¹⁰⁷⁹ Center for Biological Diversity, 928 F.3d at 778.

¹⁰⁸⁰ Id. at 780 (quoting Kleppe v. Sierra Club, 427 U.S. 390, 402 (1976)).

the proposed development of the region,' there can be 'no factual predicate for the production of an [EIS] of the type envisioned by NEPA.""1081

713. Similarly, here, the final rule does not authorize the development or construction of any facilities, but simply addresses the rates that QFs can charge and certain requirements under which proposed facilities may qualify as a QF. The final rule does not fund any particular QFs, or issue permits for their construction or operation (neither of which the Commission has jurisdiction to do). The Commission does not, in its regulations or in this final rule, authorize or prohibit the use of any particular technology or fuel, nor does it mandate or prohibit where QFs should be or are built. This final rule does not exempt QFs from any Federal, state, or local environmental, siting, or similar laws or regulatory requirements, (again something the Commission has no authority to do).

714. Even with respect to rates, while the Commission has established and here revises the factors and approaches that states can take into account when they set QF rates, it is ultimately the states and not the Commission that set those rates. The final rule continues to give states wide discretion and it is impossible to know what the states may choose to

¹⁰⁸¹ *Id.* (quoting *Kleppe*, 427 U.S. at 402); *see also Northcoast Environmental Center v. Glickman*, 136 F.3d 660, 668 (9th Cir. 1998) (citing *Kleppe* in support of its holding that NEPA does not require agency to complete environmental analysis where environmental effects are speculative or hypothetical).

¹⁰⁸² See Sugarloaf Citizens Ass'n v. FERC, 959 F.2d 508, 514 n.29 (4th Cir. 1992) (finding that in the QF certification context "FERC does little more than regulate the rates paid by utilities to the qualifying facility and does not control the financing, construction or operation of the project. Although the Facility receives an economic benefit, no direct federal funding or other substantial federal assistance is provided, and no licensing action is involved.").

do in response to this final rule, whether they will make changes in their current practices or not, and how those state choices would impact QF development and the environment in any particular state, let along any particular locale.

715. Moreover, the scope of this final rule is even less defined than the landscape-scale area designations at issue in the *Center for Biological Diversity* case. PURPA applies throughout the entire United States, and the revisions implemented by the final rule theoretically could affect future QF development anywhere in the country.

716. While courts have held that NEPA requires "reasonable forecasting," "NEPA does not require a 'crystal ball' inquiry." Further, an agency "is not required to engage in speculative analysis" or "to do the impractical, if not enough information is available to permit meaningful consideration" or to "foresee the unforeseeable." In that vein, "[i]n determining what effects are 'reasonably foreseeable,' an agency must engage in 'reasonable forecasting and speculation,' . . . with *reasonable* being the operative

¹⁰⁸³ Vt. Yankee Nuclear Power Corp. v. Nat. Res. Def. Council, Inc., 435 U.S. 519, 534 (1978) (quoting Nat. Res. Def. Council, Inc. v. Morton, 458 F.2d 827, 837 (D.C. Cir. 1972)).

¹⁰⁸⁴ N. Plains Res. Council v. Surface Transp. Board, 668 F.3d 1067, 1078-79 (9th Cir. 2011) (citation omitted).

¹⁰⁸⁵ Concerned About Trident v. Rumsfeld, 555 F.2d 817, 830 (D.C. Cir. 1976) (citation omitted).

word."1086 Environmental impacts are not reasonably foreseeable if the impacts would result only through a lengthy causal chain of highly uncertain or unknowable events. 1087 717. Commenters' allegations regarding potentially reduced QF development hinge on the claim that the NOPR proposed to "repeal" or "eliminate" critical PURPA Regulations, which is not true. The Commission proposed in the NOPR, which this final rule generally affirms, to clarify some existing PURPA regulations and modify other PURPA Regulations to make them consistent with the statute, based on changed circumstances since the time those regulations originally were promulgated. Any consideration of whether the revised rules could potentially result in significant new environmental impacts due to less QF development and increased development of coal, nuclear, and combined cycle natural gas plants, would be highly speculative, based on the difficulty in determining which additional flexibilities the final rule provides to the states that each state will adopt, if any; how such state rules would impact QF development going forward; and whether any reduction in OF renewables would be replaced by the much

¹⁰⁸⁶ Sierra Club v. U.S. Dep't of Energy, 867 F.3d 189, 198 (D.C. Cir. 2017) (emphasis in original) (citation omitted).

¹⁰⁸⁷ See Dep't of Transp. v. Pub. Citizen, 541 U.S. 752, 767 (2004) ("NEPA requires a 'reasonably close causal relationship' between the environmental effect and the alleged cause."); Metro. Edison Co. v. People Against Nuclear Energy, 460 U.S. 766, 774 (1983) (noting effects may not fall within section 102 of NEPA because "the causal chain is too attenuated").

greater amount of non-QF renewable resources with similar environmental characteristics. 1088

As was the case in *Center for Biological Diversity*, any attempt to evaluate the environmental effects of the final rule by necessity would involve nothing less than hypothesizing the potential development of QFs and the resultant environmental consequences. Indeed, any attempt by the Commission to estimate the potential environmental effects of the final rule would be considerably more speculative than the estimates of potential development and attendant environmental consequences that the court in Center for Biological Diversity held are not required under NEPA. That case involved limited zones in which some projects to treat insect infestation almost certainly would be proposed. Here, it simply is not possible to provide any reasonable forecast of the effects of the final rule on future QF development, whether any affected potential QF would be a renewable resource (such as solar or wind) or employ carbon-emitting technology (e.g., a fossil-fuel-burning cogenerator or a waste-coal-burning small power production facility). Moreover, environmental effects on land use, vegetation, water quality, etc. are all dependent on location, which are unknown and could be anywhere in the United States.

719. Because, even more so than in *Center for Biological Diversity*, the final rule does not authorize, or define any limit on the scope of, any potential QF or other infrastructure development, any attempt to prepare an analysis of the potential effects of the final rule on

¹⁰⁸⁸ See infra VI.B.2.

future QF development would be so speculative as to render meaningless any environmental analysis of these impacts. Therefore, no such analysis is required by NEPA.

b. A Categorical Exclusion Applies

720. There is a separate and independent alternative reason why no environmental analysis is warranted: the final rule falls within a categorical exclusion promulgated by the Commission pursuant to the CEQ's NEPA regulations. Specifically, the final rule falls within the categorical exclusion for rules that: (1) are clarifying in nature, (2) are corrective in nature, (3) are procedural in nature, or (4) do not substantially change the effect of the regulation being amended. Here, each of the revisions to the PURPA Regulations implemented by the final rule fits into one of these categories:

i. Changes that are Clarifying in Nature

721. Several of the changes to the PURPA Regulations are clarifying in nature. These include the changes clarifying how market prices can be used to set as-available energy rates, ¹⁰⁹¹ the changes clarifying how fixed energy rates in contracts or LEOs may be

¹⁰⁸⁹ CEQ regulations provide that agencies shall issue procedures that provide specific criteria for classes of action which "normally do not require either an environmental impact statement or an environmental assessment (categorical exclusion)". 40 CFR 1507.3 (2019).

¹⁰⁹⁰ See 18 CFR 380.4(a)(2)(ii) (categorical exclusion applies to "promulgation of rules that are clarifying, corrective, or procedural, or that do not substantially change the effect of . . . regulations being amended.").

¹⁰⁹¹ See Sections IV.B.2-5.

determined,¹⁰⁹² and the changes clarifying how competitive solicitations can be used to set avoided cost rates.¹⁰⁹³ Other non-rate related clarifying revisions in the final rule include a clarification regarding the relationship between avoided costs and decreases in a purchasing utility's load as a consequence of retail competition,¹⁰⁹⁴ a clarification as to how electric generating equipment should be defined for purposes of determining whether small power production facilities are located at the same site,¹⁰⁹⁵ and a clarification as to when a LEO is established.¹⁰⁹⁶

ii. Changes that are Corrective in Nature

722. The Commission interprets the categorical exclusion for changes to its regulations that are corrective in nature as including changes needed in order to ensure that a regulation conforms to the requirements of the statutory provisions being implemented by the regulation. To be clear, the Commission does not find that its existing PURPA

¹⁰⁹² See Section IV.B.6.

¹⁰⁹³ See Section IV.B.8.

¹⁰⁹⁴ See Section IV.C.

¹⁰⁹⁵ See Section IV.D.2.

¹⁰⁹⁶ See Section IV.H.

¹⁰⁹⁷ For example, the Commission relied on this categorical exclusion when it revised the PURPA Regulations in 2006 to comply with the amendments to PURPA enacted as part of EPAct 2005. See Revised Regulations Governing Small Power Production and Cogeneration Facilities, Order No. 671, 114 FERC P 61,102 at P 118. Further, this interpretation is also consistent with the Supreme Court's holding that NEPA review is not required when an agency's action is required by statute. See Dep't of Transp. v. Pub. Citizen, 541 U.S. 752, 770 (2004) ("where an agency has no ability to prevent a certain effect due to its limited statutory authority over the relevant actions, the agency cannot be considered a legally relevant "cause" of the effect [and] . . . under NEPA

Regulations were inconsistent with the statutory requirements of PURPA when promulgated. Rather, the Commission finds that the changes adopted in this final rule are required to ensure continued future compliance of the PURPA Regulations with PURPA, based on the changed circumstances found by the Commission in this final rule. 723. Three aspects of the final rule are corrective in nature. The first is the change allowing states to require variable energy rates in QF contracts. 1098 As the Commission explains above, this change is required based on the Commission's finding that, contrary to the Commission's expectation in 1980, there have been numerous instances where overestimates and underestimates of energy avoided costs used in fixed energy rate contracts have not balanced out, causing the contract rate to not violate the statutory avoided cost rate cap. Giving states the ability to require energy rates in QF contracts to vary based on the purchasing utility's avoided cost of energy at the time of delivery ensures that QF rates do not exceed the avoided cost rate cap imposed by PURPA. 1099 The second corrective aspect is the change in the PURPA Regulations regarding 724. the determination of what facilities are located at the same site for purposes of complying with the statutory 80 MW limit on small power production facilities located at the same

and the implementing CEQ regulations, the agency need not consider these effects in its EA."); see also Safari Club Intern. v. Jewell, 960 F.Supp.2d 17, 79-80 (D.D.C. 2013) (relying on Dep't of Transp. v. Pub. Citizen to hold that NEPA review is not required for an agency rule issued to comply with a statutory requirement).

¹⁰⁹⁸ See Section IV.B.7.

¹⁰⁹⁹ *Id*.

site.¹¹⁰⁰ As explained above, the Commission found, based on changed circumstances, that the current one-mile rule is inadequate to determine which facilities are located at the same site. Based on this finding, the Commission was obligated by PURPA to revise its definition of when facilities are located at the same site.¹¹⁰¹

725. The third corrective aspect of the final rule relates to the implementation of PURPA section 210(m). That statutory provision allows purchasing utilities to terminate their obligation to purchase from QFs that have nondiscriminatory access to certain statutorily-defined markets, which the Commission has determined to be the RTO/ISO markets. The final rule revises the presumption in the PURPA Regulations that QFs with a capacity of 20 MW or less do not have non-discriminatory access to such markets, reducing the threshold for such presumption to 5 MW.¹¹⁰²

726. The Commission has determined in the final rule that, since the 20 MW threshold was established in 2005, the RTO/ISO markets have matured and the industry has developed a better understanding of the mechanics of market participation. This determination has rendered inaccurate the presumption currently reflected in the PURPA Regulations that QFs 20 MW and below do not have non-discriminatory access to the relevant markets. Once the Commission made this determination, it was appropriate for

¹¹⁰⁰ See Section IV.D.

¹¹⁰¹ See Section IV.D.1.c.

¹¹⁰² See Section IV.G.1.

the Commission to update the 20 MW threshold to comply with the requirements of PURPA section 210(m). 1103

i. Changes that are Procedural in Nature

727. The remaining two revisions implemented by the final rule are procedural in nature. The first is a revision to the procedures that apply to QF certification. The second is a revision to the Commission's Form 556, used by QFs seeking certification. 1105

2. The NEPA Analysis for Promulgation of the Original PURPA Regulations in 1980 Cannot be Replicated Here

728. As commenters note, in 1980 the Commission conducted an EA and later an EIS for its initial rules implementing PURPA. Initially, the Commission found (and the Final EIS also found) that new diesel cogeneration, and dual-fuel cogeneration particularly, in New York City, could cause significant environmental effects on air quality. In Order No. 70-E, however, the Commission ultimately opted to treat such cogeneration the same as all other cogeneration given, among other things, that the PURPA Regulations were not the driving force behind the development of such cogeneration in New York City. In doing so, the Commission emphasized that QF status was not a license nor a permit to operate but instead only entitled the QF to a rate for purchases and to certain exemptions

¹¹⁰³ *Id*.

¹¹⁰⁴ See Section IV.E.

¹¹⁰⁵ See Section IV.F

¹¹⁰⁶ Final EIS at I-7a.

¹¹⁰⁷ See Order No. 70-E, 46 FR 33,025, 33,026 (June 18, 1981).

from regulation. Moreover, QFs were not exempted from any Federal, state, or local environmental, siting or other similar requirements. 1108

729. The original PURPA EA for the pre-existing PURPA Regulations was based on a market penetration study of PURPA-induced facilities. In order to carry out that market penetration study, the original PURPA EA had to make the simplifying assumption that the mere implementation of PURPA would necessarily result in the development and operation of certain types of generation facilities that would not otherwise be

The rules provide encouragement to the development of certain types of facilities. They do not prevent any facility which does not qualify from using cogeneration or small power production, or from using any type of fuel. The rules merely grant or deny certain benefits to certain facilities.

In this environmental assessment, the environmental effects of these rules are limited to the effects resulting from the construction and/or operation of facilities which occur as a result of the granting of these benefits, or from changes in the operating characteristics of existing facilities which results from the granting of these benefits. If a cogeneration or small power production facility would be constructed or operated without the incentives of these rules, the environmental effects resulting therefrom cannot properly be described as environmental effects of these rules. However, a technical and environmental discussion of each technology is provided whether or not its use is expected to be encouraged by these rules.

Small Power Production and Cogeneration Facilities--Environmental Findings; No Significant Impact and Notice of Intent To Prepare Environmental Impact Statement, 45 FR 23,661, 23,664 (Apr. 8, 1980) (Original PURPA EA).

¹¹⁰⁸ *Id.* The Commission stated in its EA that:

developed.¹¹⁰⁹ Based on these types of facilities, that EA identified specific resource conflicts related to each type of facility, which were nothing more than a generalized listing of potential impacts.¹¹¹⁰ That EA found that, because the various types of facilities operate differently, there would be no cumulative impacts and this finding, coupled with the geographic distribution of facility development from the market penetration study, resulted in a finding of no significant impact for all types of facilities except diesel and dual-fueled cogeneration facilities in the Mid-Atlantic, which that EA found could cause significant environmental impacts on air quality.¹¹¹¹

730. Subsequently, an EIS was prepared that addressed only air quality in New York City and the broader Mid-Atlantic region. The bulk of the EIS focused on how national, state, and local air pollution regimes would address air quality surrounding the construction and operation of such facilities.¹¹¹²

731. Several commenters cite to this previous NEPA analysis conducted in connection with the original PURPA Regulations to support their assertion that a NEPA analysis similarly should be possible for this rulemaking. However, those assertions are undermined by the fact that circumstances have changed significantly since the promulgation of the original PURPA Regulations in 1980. Prior to 1980, essentially no

¹¹⁰⁹ *Id.* at 23,665.

¹¹¹⁰ *Id.* at 23,675-82.

¹¹¹¹ *Id.* at 23,679, 23,682-83.

¹¹¹² Order No. 70-E, 46 FR at 33,026.

QF generation technologies or other independent generation facilities (other than those used to supply the loads of the owners rather than to sell at wholesale) had been constructed. By contrast, today QF generation technologies and other independent generation facilities are common, and they are predominantly built and operated outside of PURPA.¹¹¹³

- 732. Because there was virtually no QF or independent power development in 1980, the original PURPA EA could reasonably project that the incentives created by PURPA and the original PURPA Regulations would lead to increased development of power generated by QF technologies. The market penetration study conducted by the Commission, and the Commission's conclusion that the PURPA Regulations could lead to an increase in diesel-fired cogeneration in New York City, were based on these projections.
- 733. By contrast, it is not possible here to make simplifying assumptions that the mere implementation of the revised regulations necessarily would result in specific changes in the development of particular generation technologies compared to the status quo. First, the revisions to the PURPA regulations are premised on a finding that, even after the revisions, the PURPA regulations will continue to encourage QFs. Consequently, there is no way to estimate whether any reduction in QF development, as opposed to the status quo, will be focused on one or more of the many different types of QF technologies, some of which are renewable resources and some of which are fueled by fossil fuels¹¹¹⁴ and

¹¹¹³ See supra P 240.

¹¹¹⁴ This would include both cogeneration, which typically is fossil fueled, and those small power production facilities that are fueled by waste, which would include a

have emissions comparable to non-QF fossil fueled generators. Moreover, because the rule primarily increases state flexibility in setting QF rates, including giving states the option of not changing their current rate-setting approaches, there is no way to develop any estimate of the location or size of any hypothetical reduction in QF development.

734. In addition, as mentioned above, renewable generation technologies today are commonly, and even predominantly, built and operated outside of PURPA. Current projections show that most new generation construction will be of renewable resources. Indeed, the cost of renewables has declined so much that in some regions renewables are the most cost effective new generation technology available. Thus, even if the final rule was to result in reduced renewable QF development, there is little likelihood today that hypothetical, unbuilt QFs necessarily would be replaced by new conventional fossil fuel generation.

735. Alternatively, in the absence of these hypothetical, unbuilt QFs, existing generation units – whose current emissions, if any, would already be part of the baseline for any environmental analysis of the impacts of the final rule – might continue to operate without any change in their emissions; in sum, in the absence of these hypothetical, unbuilt QFs, emissions would remain at the baseline and might not increase at all. Indeed, in the

range of fossil fuel-based waste. See 18 CFR 292.202(b), 292.204(b)(1).

¹¹¹⁵ EIA, Annual Energy Outlook 2020, at tbl.9 (Jan. 29, 2020) (in table see rows labeled Cumulative Planned Additions and Cumulative Unplanned Additions in the reference case) (Annual Energy Outlook 2020), https://www.eia.gov/outlooks/aeo/.

¹¹¹⁶ See supra P 240.

current environment where stagnant load growth has prevailed in recent years, this would seem to be a more likely scenario than an alternative where these hypothetical, unbuilt QFs are replaced by brand new fossil fuel generation that would increase emissions over the baseline.

736. Given these facts, it would not be possible to perform a market penetration study of the effects of the final rule that would not be wholly speculative. Without such a study, there could be no analysis defining the types and geographic location of facilities that could serve as the basis for any NEPA analysis similar to that performed in 1980.

3. This Proceeding Does Not Trigger Any ESA Consultation Requirement

737. Similar to our finding that it would be nearly impossible to conduct a meaningful NEPA review, we disagree with Biological Diversity and Allco that either the PURPA NOPR or this final rule trigger any consultation requirement under the ESA.

The ESA requires that agencies consult with the Secretary of the Interior or the Secretary of Commerce to "insure that any action authorized, funded, or carried out by such agency . . . is not likely to jeopardize the continued existence of any endangered species or threatened species or result in the destruction or adverse modification of [critical] habitat of such species."¹¹¹⁷

¹¹¹⁷ 16 U.S.C. 1536(a)(2).

738. The ESA regulations require consultation only if the Commission determines that a proposed action may affect listed species or critical habitat. We find that there are no effects from the final rule for which the Commission could consult with the Services.

Under the ESA regulations, as recently revised, the effects of an agency's action are

all consequences to listed species and critical habitat that are caused by the proposed action. A consequence is caused by the proposed action if it would not occur but for the proposed action and *it is reasonably certain to occur*. ¹¹¹⁹

The ESA regulations also state that a consequence is not considered to be caused by a proposed action if "[t]he consequence is only reached through a lengthy causal chain that involves so many steps as to make the consequence not reasonably certain to occur." This determination must be made "based on clear and substantial information," and "should not be based on speculation or conjecture." In addition to the above, the same ESA regulation states that factors for the agency to consider when determining whether a consequence is not caused by the proposed agency action include: "(1) The consequence is so remote in time from the action under consultation that it is not reasonably certain to

¹¹¹⁸ 50 CFR 402.14(a).

¹¹¹⁹ 50 CFR 402.2 (emphasis added).

¹¹²⁰ 50 CFR 402.17(b)(3) (emphasis added).

¹¹²¹ *Id*

¹¹²² Endangered and Threatened Wildlife and Plants; Regulations for Interagency Cooperation, 84 FR 44976, 44993 (Aug. 27, 2019).

occur; or (2) [t]he consequence is so geographically remote from the immediate area involved in the action that it is not reasonably certain to occur[.]"¹¹²³

- 739. Because the NOPR was a *proposed* rule that in and of itself had no legal effect, the NOPR is not an agency "action" under the regulations implementing the ESA, which define agency action as the "the *promulgation* of regulations." Because the NOPR did not constitute agency action, the Commission was not required to engage in consultation under the ESA prior to the NOPR's issuance.
- 740. In this final rule, we are promulgating regulations, which does constitute agency action. Nevertheless, for the same reasons that an environmental review of the impacts of this final rule under NEPA would be impossible to conduct, there is similarly no basis to conclude that harm to endangered species is reasonably certain to occur as a result of this final rule.
- 741. We find that the effects on endangered and threatened species alleged by Allco are not reasonably certain to occur, not only because any such harm is completely speculative, but also because it could result only through a lengthy causal chain of highly uncertain or unknowable events, none of which are within the Commission's authority to authorize or preclude: (1) that the final rule causes a reduction in the aggregate amount of QF capacity constructed in the future; (2) that any reduction in renewable resource QFs would not be offset by increased construction of renewable resources outside of PURPA, resulting from

¹¹²³ 50 CFR 402.17(b).

¹¹²⁴ 50 CFR 402.2 (emphasis added).

either other incentive programs or simply the increased cost-competitiveness of such resources; (3) that construction of such non-QF renewable resources would yield an increase in carbon emissions resulting from the reduction in renewable resource OFs that is not offset by other renewable resources; and (4) that such increase in carbon emissions would have an adverse effect on endangered and threatened species. Furthermore, the consequences of this rule would be remote in time and geographically remote because it would require action by individual generators, OF or non-OF, to propose, site, permit, construct, and operate a facility, in underdetermined locations potentially anywhere in the United States. In addition, many of these generators, QF and non-QF, would be subject to state approval and permitting requirements over which the Commission has no control. 742. Further, there is no support in the record for Allco's claim that the changes proposed in the PURPA NOPR would displace over 2 TWs of solar generation over the next 20 years. 1125 Allco provides no citation or other support whatsoever for this assertion but simply makes the claim with no elaboration. We find that such speculation or conjecture provides no basis upon which to either initiate or conduct any meaningful consultation with the Services on the impacts to endangered species from this final rule.

VII. Regulatory Flexibility Act Certification

743. The Regulatory Flexibility Act of 1980 (RFA)¹¹²⁶ generally requires a description and analysis of rules that will have significant economic impact on a substantial number of

¹¹²⁵ Allco Comments at 34.

¹¹²⁶ 5 U.S.C. 601-12.

small entities. In lieu of preparing a regulatory flexibility analysis, an agency may certify that a rule will not have a significant economic impact on a substantial number of small entities. The Commission in the NOPR stated that the proposed rule would not significantly impact a substantial number of small entities. Some commenters argue otherwise. 1128

744. The Small Business Administration's (SBA) Office of Size Standards develops the numerical definition of a small business. The SBA size standard for electric utilities is based on the number of employees, including affiliates. Under SBA's current size standards, the threshold for a small entity (including its affiliates) is 250 employees for cogeneration and small power production applicants in the following NAICS tategories:

- NAICS code 221114 for Solar Electric Power Generation
- NAICS code 221115 for Wind Electric Power Generation
- NAICS code 221116 for Geothermal Electric Power Generation

¹¹²⁷ 5 U.S.C. 605(b).

¹¹²⁸ See Allco Comments at 33.

¹¹²⁹ 13 CFR 121.101.

¹¹³⁰ SBA final rule on "Small Business Size Standards: Utilities," 78 FR 77343 (Dec. 23, 2013).

¹¹³¹ The North American Industry Classification System (NAICS) is an industry classification system that Federal statistical agencies use to categorize businesses for the purpose of collecting, analyzing, and publishing statistical data related to the U.S. economy. United States Census Bureau, *North American Industry Classification System*, https://www.census.gov/eos/www/naics/ (accessed April 11, 2018).

- NAICS code 221117 for Biomass Electric Power Generation
- NAICS code 221118 for Other Electric Power Generation

The threshold for a small entity (including its affiliates) is 500 employees for NAICS code 221111 for Hydroelectric Power Generation.

745. This rule directly affects qualifying small power production facilities and cogeneration facilities, the majority of which the Commission estimates are small businesses. With respect to the changes related to the Form No. 556 and new protests allowed pursuant to this rule, as reflected in the burden and cost estimates provided above, the Commission does not anticipate that any additional reporting burden or cost imposed on QFs, regardless of their status as a small or large business, would be significant. Those revisions may result in additional information being submitted by some small power production QF applicants (especially those with affiliated small power production qualifying facilities using the same energy resource located over one and less than 10 miles away). The Commission estimates that less than 10 percent of QF applications and self-certifications meet these criteria.

746. In the final analysis, the other changes in this final rule¹¹³² largely impact payments to QFs by electric utilities. More accurate avoided cost rates may result in lower

¹¹³² I.e., use of locational marginal prices, competitive market price, and use of forecasted stream of market revenues for energy rate component of QF contracts or legally enforceable obligations; use of variable energy rates in QF contracts or legally enforceable obligations; use of competitive solicitations to set avoided energy and capacity rates; reducing the PURPA section 210(m) rebuttable presumption regarding access to markets from 20 MW to 5 MW; and the commercial viability and financial commitment to construct demonstration necessary to obtaining a legally enforceable obligation.

payments from certain electric utilities to certain QFs. In this regard, the final rule provides states greater flexibility than they have today to set the rate that electric utilities will pay QFs, but there is no way to know in advance which new flexibility state regulatory authorities and nonregulated electric utilities will exercise, or what impact that new flexibility might have given the different circumstances likely to apply to each determination of avoided cost. Under the final rule, additionally, states also have the discretion to continue setting the rate as they do today and not to adopt the Commission' proposed greater rate flexibilities. Therefore, it is not possible to estimate what the dollar impact might be. However, because of the way PURPA is structured, whatever the potential dollar impacts of these changes on small QFs may be, to the extent that they reduce the amounts paid to certain QFs, such reductions could be matched dollar-fordollar by savings experienced by purchasing electric utilities, which should be flowed through to their retail ratepayers, some of whom would also tend to qualify as small entities. 1133

impact of this final rule, the Small Business Administration Office of Advocacy encourages such indirect costs to be analyzed as well: "Although it is not required by the RFA, the Office of Advocacy believes that it is good public policy for the agency to perform a regulatory flexibility analysis even when the impacts of its regulation are indirect." SBA, Office of Advocacy, *A Guide for Government Agencies: How to Comply with the Regulatory Flexibility Act* at 23 (Aug. 2017), https://www.sba.gov/sites/default/files/advocacy/How-to-Comply-with-the-RFA-WEB.pdf. But see Mid-Tex Elec. Co-op., Inc. v. FERC, 773 F.2d 327, 343 (D.C. Cir. 1985) ("Congress did not intend to require that every agency consider every indirect effect that any regulation might have on small businesses in any stratum of the national economy.").

- 747. While Allco argues that the Commission should have attempted to minimize the impacts on small renewable energy producers and consider alternative structures, the fact is that these offsetting impacts result from changes that are necessary to ensure the Commission's regulations continue to meet PURPA's statutory requirements. For example, allowing states to use competitive prices may benefit small QFs inasmuch as the rate-setting process for purchases of energy from these entities would be more straightforward and efficient than the administrative processes currently in use.

 Furthermore, providing flexibility in setting energy rates may result in state entities approving longer duration contracts for capacity (at fixed rates) and energy. The impacts of these changes, therefore, are reasonable alternatives to the status quo while adhering to the requirements of PURPA.
- 748. This final rule establishes a rebuttable presumption that a qualifying small power production facility whose electrical generating equipment is more than one but less than 10 miles from affiliated electrical generating equipment using the same energy resource is at a separate site. The Commission finds that this rebuttable presumption imposes a lower burden than imposing a rule that any affiliated electrical generating equipment less than 10 miles apart is presumed to be at the same site. Similarly, the Commission, while removing the rebuttable presumption that qualifying small power production facilities more than 5 MW but under 20 MW lack nondiscriminatory access, has provided factors that such facilities could use to demonstrate lack of such access allowing them to retain the mandatory purchase obligation. The Commission estimates that annual additional compliance costs on industry (detailed above) will be approximately \$1,149,965 (or an

average additional burden and cost per response, of 3.187 hrs. and the corresponding \$264.51) to comply with these requirements. 1134

749. Accordingly, pursuant to section 605(b) of the RFA, the Commission certifies that this rule will not have a significant economic impact on a substantial number of small entities.

VIII. <u>Document Availability</u>

750. In addition to publishing the full text of this document in the Federal Register, the Commission provides all interested persons an opportunity to view and/or print the contents of this document via the Internet through the Commission's Home Page (http://www.ferc.gov). At this time, the Commission has suspended access to the Commission's Public Reference Room due to the President's March 13, 2020 proclamation declaring a National Emergency concerning the Novel Coronavirus Disease (COVID-19).

751. From the Commission's Home Page on the Internet, this information is available on eLibrary. The full text of this document is available on eLibrary in PDF and Microsoft Word format for viewing, printing, and/or downloading. To access this document in eLibrary, type the docket number excluding the last three digits of this document in the docket number field.

¹¹³⁴ Annual additional cost of \$1,149,965 [(\$1,120,085 for FERC-556)+(29,880 for FERC-912)] and average additional burden of 13,855 hours [(13,495 hrs. for FERC-556)+(360 hrs. for FERC-912)] divided by the number of affected responses of 4,347.5 [(4,317.5 for FERC-556)+(30 responses for FERC-912)].

752. User assistance is available for eLibrary and the Commission's website during normal business hours from the Commission's Online Support at 202-502-6652 (toll free at 1-866-208-3676) or email at ferc.gov, or the Public Reference Room at (202) 502-8371, TTY (202)502-8659. E-mail the Public Reference Room at public.referenceroom@ferc.gov.

IX. Effective Dates and Congressional Notification

753. These regulations are effective [INSERT DATE 120 DAYS AFTER THE DATE OF PUBLICATION IN THE FEDERAL REGISTER]. The Commission has determined, with the concurrence of the Administrator of the Office of Information and Regulatory Affairs of OMB, that this rule is not a "major rule" as defined in section 351 of the Small Business Regulatory Enforcement Fairness Act of 1996. This final rule is being submitted to the Senate, House, Government Accountability Office, and Small Business Administration.

List of subjects in 18 CFR Part 292

Electric power plants; Electric utilities, Reporting and recordkeeping requirements.

List of subjects in 18 CFR Part 375

Authority delegations (Government agencies); Seals and insignia; Sunshine Act.

By the Commission. Commissioner Glick is dissenting in part with a separate statement attached.

(SEAL)

Nathaniel J. Davis, Sr., Deputy Secretary. In consideration of the foregoing, the Commission proposes to amend Parts 292 and 375, Chapter I, Title 18, <u>Code of Federal Regulations</u>, as follows.

SUBCHAPTER K – REGULATIONS UNDER THE PUBLIC UTILITY REGULATORY POLICIES ACT OF 1978

* * * * *

PART 292 – REGULATIONS UNDER SECTIONS 201 AND 210 OF THE PUBLIC UTILITY REGULATORY POLICIES ACT OF 1978 WITH REGARD TO SMALL POWER PRODUCTION AND COGENERATION

- 1. The authority citation for part 292 continues to read as follows:

 Authority: 16 U.S.C. 791a-825r, 2601-2645; 31 U.S.C. 9701; 42 U.S.C. 7101-7352.
 - 2. Section 292.101 is revised to add paragraphs (12) through (16):§ 292.101 Definitions.

* * * * *

- (12) Locational marginal price means the price for energy at a particular location as determined in a market defined in § 292.309(e), (f), or (g).
 - (13) Competitive Price means a Market Hub Price or a Combined Cycle Price.
- (14) Market Hub Price means a price for as-delivered energy determined pursuant to § 292.304(b)(7)(i).
- (15) Combined Cycle Price means a price for as-delivered energy determined pursuant to § 292.304(b)(7)(ii).
 - (16) Competitive Solicitation Price means a price for energy and/or capacity

determined pursuant to § 292.304(b)(8).

3. Section 292.202 is revised to add paragraph (t):

§ 292.202 Definitions.

* * * * *

- (t) Electrical generating equipment means all boilers, heat recovery steam generators, prime movers (any mechanical equipment driving an electric generator), electrical generators, photovoltaic solar panels, inverters, fuel cell equipment and/or other primary power generation equipment used in the facility, excluding equipment for gathering energy to be used in the facility.
 - 4. Section 292.204(a) is revised to read:

§ 292.204 Criteria for qualifying small power production facilities.

- (a) Size of the facility—
- (1) *Maximum size*. Except as provided in paragraph (a)(4) of this section, the power production capacity of a facility for which qualification is sought, together with the power production capacity of any other small power production qualifying facilities that use the same energy resource, are owned by the same person(s) or its affiliates, and are located at the same site, may not exceed 80 megawatts.
 - (2) *Method of calculation*.
- (i) (A) For purposes of this paragraph, there is an irrebuttable presumption that affiliated small power production qualifying facilities that use the same energy resource and are located one mile or less from the facility for which qualification or recertification

is sought are located at the same site as the facility for which qualification or recertification is sought.

- (B) For purposes of this paragraph, for facilities for which qualification or recertification is filed on or after [INSERT DATE 120 DAYS AFTER THE DATE OF PUBLICATION IN THE FEDERAL REGISTER] there is an irrebuttable presumption that affiliated small power production qualifying facilities that use the same energy resource and are located 10 miles or more from the facility for which qualification or recertification is sought are located at separate sites from the facility for which qualification or recertification is sought.
- (C) For purposes of this paragraph, for facilities for which qualification or recertification is filed on or after [INSERT DATE 120 DAYS AFTER THE DATE OF PUBLICATION IN THE FEDERAL REGISTER], there is a rebuttable presumption that affiliated small power production qualifying facilities that use the same energy resource and are located more than one mile and less than 10 miles from the facility for which qualification or recertification is sought are located at separate sites from the facility for which qualification or recertification is sought.
- (D) For hydroelectric facilities, facilities are considered to be located at the same site as the facility for which qualification or recertification is sought if they are located within one mile of the facility for which qualification or recertification is sought and use water from the same impoundment for power generation.

- (ii) For purposes of making the determinations in clause (i), the distance between two facilities shall be measured from the edge of the closest electrical generating equipment for which qualification or recertification is sought to the edge of the nearest electrical generating equipment of the other affiliated small power production qualifying facility using the same energy resource.
- (3) *Waiver*. The Commission may modify the application of paragraph (a)(2) of this section, for good cause.
- (4) Exception. Facilities meeting the criteria in section 3(17)(E) of the Federal Power Act (16 U.S.C. 796(17)(E)) have no maximum size, and the power production capacity of such facilities shall be excluded from consideration when determining the size of other small power production facilities less than 10 miles from such facilities.

* * * * *

- 5. Section 292.207(a) and (b) is revised to read:
- § 292.207 Procedures for obtaining qualifying status.
 - (a) Self-certification.
- (1) FERC Form No. 556. The qualifying facility status of an existing or a proposed facility that meets the requirements of § 292.203 may be self-certified by the owner or operator of the facility or its representative by properly completing a FERC Form No. 556 and filing that form with the Commission, pursuant to § 131.80 of this chapter, and complying with paragraph (e) of this section.

- (2) Factors. For small power production facilities pursuant to § 292.204, the owner or operator of the facility or its representative may, when completing the FERC Form No. 556, provide information asserting factors showing that the facility for which qualification or recertification is sought is at a separate site from other facilities using the same energy resource and owned by the same person(s) or its affiliates.
- (3) Commission action. Self-certification and self-recertification are effective upon filing. If no protests to a self-certification or self-recertification are timely filed pursuant to § 292.207(c), no further action by the Commission is required for a selfcertification or self-recertification to be effective. If protests to a self-certification or selfrecertification are timely filed pursuant to § 292.207(c), a self-certification or selfrecertification will remain effective until the Commission issues an order revoking QF certification. The Commission will act on the protest within 90 days from the date the protest is filed; provided that, if the Commission requests more information from the protester, the entity seeking qualification or recertification, or both, the time for the Commission to act will be extended to 60 days from the filing of a complete answer to the information request. In addition to any extension resulting from a request for information, the Commission also may toll the 90-day period for one additional 60-day period if so required to rule on a protest. Authority to toll the 90-day period for this purpose is delegated to the Secretary or the Secretary's designee. Absent Commission action before the expiration of the tolling period, a protest will be deemed denied, and the selfcertification or self-recertification will remain effective.

- (b) Optional procedure—Commission certification.
- (1) Application for Commission certification. In lieu of the self-certification procedures in paragraph (a) of this section, an owner or operator of an existing or a proposed facility, or its representative, may file with the Commission an application for Commission certification that the facility is a qualifying facility. The application must be accompanied by the fee prescribed by part 381 of this chapter, and the applicant for Commission certification must comply with paragraph (c) of this section.
- (2) General contents of application. The application must include a properly completed FERC Form No. 556 pursuant to § 131.80 of this chapter. For small power production facilities pursuant to § 292.204, the owner or operator of the facility or its representative may, when completing the FERC Form No. 556, provide information asserting factors showing that the facility for which qualification is sought is at a separate site from other facilities using the same energy resource and owned by the same person(s) or its affiliates.

* * * * *

- (c) Protests and Interventions.
- (i) Filing a Protest. Any person, as defined in § 385.102(d) of this chapter, who opposes either a self-certification or self-recertification making substantive changes to the existing certification filed pursuant to § 292.207(a) or an application for Commission certification or Commission recertification making substantive changes to the existing certification filed pursuant to § 292.207(b) for which qualification or recertification is filed on or after [INSERT DATE 120 DAYS AFTER THE DATE OF PUBLICATION

IN THE FEDERAL REGISTER], may file a protest with the Commission. Any protest to and any intervention in a self-certification or self-recertification must be filed in accordance with §§ 385.211 and 385.214 of this chapter, on or before 30 days from the date the self-certification or self-recertification is filed. Any protestor must concurrently serve a copy of such filing pursuant to § 385.211 of this chapter. Any protest must be adequately supported, and provide any supporting documents, contracts, or affidavits to substantiate the claims in the protest.

- (ii) Limitations on protest. Protests may be filed to any initial self-certification or application for Commission certification filed on or after the effective date of this final rule, and to any self-recertification or application for Commission recertification that are filed on or after [INSERT DATE 120 DAYS AFTER THE DATE OF PUBLICATION IN THE FEDERAL REGISTER] that makes substantive changes to the existing certification. Once the Commission has certified an applicant's qualifying facility status either in response to a protest opposing a self-certification or self-recertification, or in response to an application for Commission certification or Commission recertification, any later protest to a self-recertification or application for Commission recertification making substantive changes to a qualifying facility's certification must demonstrate changed circumstances that call into question the continued validity of the certification.
- (d) *Response to protests*. Any response to a protest must be filed on or before 30 days from the date of filing of that protest and will be allowed under § 385.213(a)(2) of this chapter.

- (e) Notice requirements.
- (1) General. An applicant filing a self-certification, self-recertification, application for Commission certification or application for Commission recertification of the qualifying status of its facility must concurrently serve a copy of such filing on each electric utility with which it expects to interconnect, transmit or sell electric energy to, or purchase supplementary, standby, back-up or maintenance power from, and the State regulatory authority of each state where the facility and each affected electric utility is located. The Commission will publish a notice in the Federal Register for each application for Commission certification and for each self-certification of a cogeneration facility that is subject to the requirements of § 292.205(d).
- (2) Facilities of 500 kW or more. An electric utility is not required to purchase electric energy from a facility with a net power production capacity of 500 kW or more until 90 days after the facility notifies the facility that it is a qualifying facility or 90 days after the utility meets the notice requirements in paragraph (c)(1) of this section.
 - (f) Revocation of qualifying status.
- (1)(i) If a qualifying facility fails to conform with any material facts or representations presented by the cogenerator or small power producer in its submittals to the Commission, the notice of self-certification or Commission order certifying the qualifying status of the facility may no longer be relied upon. At that point, if the facility continues to conform to the Commission's qualifying criteria under this part, the cogenerator or small power producer may file either a notice of self-recertification of qualifying status pursuant to the requirements of paragraph (a) of this section, or an

application for Commission recertification pursuant to the requirements of paragraph (b) of this section, as appropriate.

- (ii) The Commission may, on its own motion or on the motion of any person, revoke the qualifying status of a facility that has been certified under paragraph (b) of this section, if the facility fails to conform to any of the Commission's qualifying facility criteria under this part.
- (iii) The Commission may, on its own motion or on the motion of any person, revoke the qualifying status of a self-certified or self-recertified qualifying facility if it finds that the self-certified or self-recertified qualifying facility does not meet the applicable requirements for qualifying facilities.
- (2) Prior to undertaking any substantial alteration or modification of a qualifying facility which has been certified under paragraph (b) of this section, a small power producer or cogenerator may apply to the Commission for a determination that the proposed alteration or modification will not result in a revocation of qualifying status. This application for Commission recertification of qualifying status should be submitted in accordance with paragraph (b) of this section.
- 6. Section 292.304(b), (d), and (e) is revised to read:
- § 292.304 Rates for purchases.

* * * * *

(b) Relationship to avoided costs.

* * *

- (6) Locational Marginal Price. There is a rebuttable presumption that a state regulatory authority or nonregulated electric utility may use a Locational Marginal Price as a rate for as-available qualifying facility energy sales to electric utilities located in a market defined in § 292.309(e), (f), or (g).
- (7) Competitive Price. A state regulatory authority or nonregulated electric utility may use a Competitive Price as a rate for as-available qualifying facility energy sales to electric utilities located outside a market defined in § 292.309(e), (f), or (g). A Competitive Price may be either a Market Hub Price or a Combined Cycle Price, determined as follows:
- (i) A *Market Hub Price* is a price established at a liquid market hub which a state regulatory authority or nonregulated electric utility determines represents an appropriate measure of the electric utility's avoided cost for as-available energy, and is a hub to which the electric utility has reasonable access, based on an evaluation by the state regulatory authority or nonregulated electric utility of the relevant factors, including but not limited to the following:
 - (A) whether the hub is sufficiently liquid that prices at the hub represent a competitive price;
 - (B) whether prices developed at the hub are sufficiently transparent;
 - (C) whether the electric utility has the ability to deliver power from such hub to its load, even if its load is not directly connected to the hub; and
 - (D) whether the hub represents an appropriate market to derive an energy

price for the electric utility's purchases from the relevant qualifying facility given the electric utility's physical proximity to the hub or other factors.

- (ii) A *Combined Cycle Price* is a price determined pursuant to a formula established by a state regulatory authority or nonregulated electric utility using published natural gas price indices, a proxy heat rate, and variable operations and maintenance costs for an efficient natural gas combined-cycle generating facility. Before establishing such a formula rate, a state regulatory authority or nonregulated electric utility must determine that the resulting Combined Cycle Price represents an appropriate measure of the purchasing electric utility's avoided cost for energy, based on its evaluation of the relevant factors, including but not limited to the following:
 - (A) whether the cost of energy from an efficient natural gas combined cycle generating facility represents a reasonable measure of a competitive price in the purchasing electric utility's region;
 - (B) whether natural gas priced pursuant to particular proposed natural gas price indices would be available in the relevant market;
 - (C) whether there should be an adjustment to the natural gas price to appropriately reflect the cost of transporting natural gas to the relevant market; and
 - (D) whether the proxy heat rate used in the formula should be updated regularly to reflect improvements in generation technology.
- (8) Competitive Solicitation Price. (i) A state regulatory authority or nonregulated electric utility may use a price determined pursuant to a competitive

solicitation process to establish qualifying facility energy and/or capacity rates for sales to electric utilities, provided that such competitive solicitation process is conducted pursuant to procedures ensuring the solicitation is conducted in a transparent and non-discriminatory manner including, but not limited to, the following:

- (A) the solicitation process is an open and transparent process that includes, but is not limited to, providing equally to all potential bidders substantial and meaningful information regarding transmission constraints, levels of congestion, and interconnections, subject to appropriate confidentiality safeguards;
- (B) solicitations are open to all sources, to satisfy that electric utility's capacity needs, taking into account the required operating characteristics of the needed capacity;
 - (C) solicitations are conducted at regular intervals;
- (D) solicitations are subject to oversight by an independent administrator; and
- (E) solicitations are certified as fulfilling the above criteria by the relevant state regulatory authority or nonregulated electric utility through a post-solicitation report.
- (ii) To the extent that the electric utility procures all of its capacity, including capacity resources constructed or otherwise acquired by the electric utility, through a competitive solicitation process conducted pursuant to subsection (8)(i), the electric utility shall be presumed to have no avoided capacity costs unless and until it determines to acquire capacity outside of such competitive solicitation process. However, the electric

utility shall nevertheless be required to purchase energy from qualifying small power producers and qualifying cogeneration facilities.

(iii) To the extent that the electric utility does not procure all of its capacity through a competitive solicitation process conducted pursuant to subsection (8)(i), then there shall be no presumption that the electric utility has no avoided capacity costs.

* * * * *

- (d) Purchases "as available" or pursuant to a legally enforceable obligation.
 - (1) Each qualifying facility shall have the option either:
- (i) To provide energy as the qualifying facility determines such energy to be available for such purchases, in which case the rates for such purchases shall be based on the electric utility's avoided cost for energy calculated at the time of delivery; or
- (ii) To provide energy or capacity pursuant to a legally enforceable obligation for the delivery of energy or capacity over a specified term, in which case the rates for such purchases shall, except as provided in subsection (d)(2) below, be based on either:
 - (A) The avoided costs calculated at the time of delivery; or
 - (B) The avoided costs calculated at the time the obligation is incurred.
- (iii) The rate for delivery of energy calculated at the time the obligation is incurred may be based on estimates of the present value of the stream of revenue flows of future locational marginal prices, or Competitive Prices during the anticipated period of delivery.
- (2) Notwithstanding paragraph (d)(1)(ii)(B), a state regulatory authority or nonregulated electric utility may require that rates for purchases of energy from a qualifying facility pursuant to a legally enforceable obligation vary through the life of the

obligation, and be set at the electric utility's avoided cost for energy calculated at the time of delivery.

- (3) Obtaining a legally enforceable obligation. A qualifying facility must demonstrate commercial viability and financial commitment to construct its facility pursuant to criteria determined by the state regulatory authority or nonregulated electric utility as a prerequisite to a qualifying facility obtaining a legally enforceable obligation. Such criteria must be objective and reasonable.
 - (e) Factors affecting rates for purchases.
- (1) A state regulatory authority or nonregulated electric utility may establish rates for purchases of energy from a qualifying facility based on a purchasing electric utility's locational marginal price calculated by the applicable market defined in § 292.309(e), (f), or (g), or the purchasing electric utility's applicable Competitive Price. Alternatively, a state regulatory authority or nonregulated electric utility may establish rates for purchases of energy and/or capacity from a qualifying facility based on a Competitive Solicitation Price. To the extent that capacity rates are not set pursuant to this section, capacity rates shall be set pursuant to subsection (2).
- (2) To the extent that a state regulatory authority or nonregulated electric utility does not set energy and/or capacity rates pursuant to subsection (1), the following factors shall, to the extent practicable, be taken into account in determining rates for purchases from a qualifying facility:
- (i) The data provided pursuant to § 292.302(b), (c), or (d), including State review of any such data;

- (ii) The availability of capacity or energy from a qualifying facility during the system daily and seasonal peak periods, including:
 - (A) The ability of the electric utility to dispatch the qualifying facility;
 - (B) The expected or demonstrated reliability of the qualifying facility;
- (C) The terms of any contract or other legally enforceable obligation, including the duration of the obligation, termination notice requirement and sanctions for non-compliance;
- (D) The extent to which scheduled outages of the qualifying facility can be usefully coordinated with scheduled outages of the electric utility's facilities;
- (E) The usefulness of energy and capacity supplied from a qualifying facility during system emergencies, including its ability to separate its load from its generation;
- (F) The individual and aggregate value of energy and capacity from qualifying facilities on the electric utility's system; and
- (G) The smaller capacity increments and the shorter lead times available with additions of capacity from qualifying facilities; and
- (iii) The relationship of the availability of energy or capacity from the qualifying facility as derived in paragraph (e)(2)(ii) of this section, to the ability of the electric utility to avoid costs, including the deferral of capacity additions and the reduction of fossil fuel use; and
- (iv) The costs or savings resulting from variations in line losses from those that would have existed in the absence of purchases from a qualifying facility, if the purchasing

electric utility generated an equivalent amount of energy itself or purchased an equivalent amount of electric energy or capacity.

* * * * *

- 7. Section 292.309(c), (d), (e), and (f) is revised to read as follows:
- § 292.309 Termination of obligation to purchase from qualifying facilities.

* * * * *

- (c) For purposes of § 292.309(a)(1), (2) and (3), with the exception of paragraph (d) of this section, there is a rebuttable presumption that a qualifying facility has nondiscriminatory access to the market if it is eligible for service under a Commission-approved open access transmission tariff or Commission-filed reciprocity tariff, and Commission-approved interconnection rules.
- (1) If the Commission determines that a market meets the criteria of § 292.309(a)(1), (2) or (3), and if a qualifying facility in the relevant market is eligible for service under a Commission-approved open access transmission tariff or Commission-filed reciprocity tariff, a qualifying facility may seek to rebut the presumption of access to the market by demonstrating, *inter alia*, that it does not have access to the market because of operational characteristics or transmission constraints.
- (2) For purposes of § 292.309(a)(1), (2), and (3), a qualifying small power production facility with a capacity between 5 megawatts and 20 megawatts may additionally seek to rebut the presumption of access to the market by demonstrating that it does not have access to the market in light of consideration of other factors, including, but not limited to:

- (i) specific barriers to connecting to the interstate transmission grid, such as excessively high costs and pancaked delivery rates;
- (ii) unique circumstances impacting the time or length of interconnection studies or queues to process the small power production facility's interconnection request;
- (iii) a lack of affiliation with entities that participate in the markets in § 292.309(a)(1),(2), and (3);
- (iv) the qualifying small power production facility has a predominant purpose other than selling electricity and should be treated similarly to qualifying cogeneration facilities;
- (v) The qualifying small power production facility has certain operational characteristics that effectively prevent the qualifying facility's participation in a market; or
- (vi) The qualifying small power production facility lacks access to markets due to transmission constraints. The qualifying small power production facility may show that it is located in an area where persistent transmission constraints in effect cause the qualifying facility not to have access to markets outside a persistently congested area to sell the qualifying facility output or capacity.
- (d)(1) For purposes of § 292.309(a)(1), (2), and (3), there is a rebuttable presumption that a qualifying cogeneration facility with a capacity at or below 20 megawatts does not have nondiscriminatory access to the market.
- (2) For purposes of § 292.309(a)(1), (2), and (3), there is a rebuttable presumption that a qualifying small power production facility with a capacity at or below 5 megawatts does not have nondiscriminatory access to the market.

- (3) Nothing in § 292.309 (d)(1)-(d)(3) affects the rights the rights or remedies of any party under any contract or obligation, in effect or pending approval before the appropriate State regulatory authority or non-regulated electric utility on or before [INSERT DATE 120 DAYS AFTER THE DATE OF PUBLICATION IN THE FEDERAL REGISTER], to purchase electric energy or capacity from or to sell electric energy or capacity to a small power production facility between 5 megawatts and 20 megawatts under this Act (including the right to recover costs of purchasing electric energy or capacity).
- (4) For purposes of implementing paragraphs (d)(1) and (d)(2) of this section, the Commission will not be bound by the standards set forth in § 292.204(a)(2).
- (e) Midcontinent Independent System Operator, Inc. (MISO), PJM Interconnection, L.L.C. (PJM), ISO New England Inc. (ISO-NE), and New York Independent System Operator, Inc. (NYISO) qualify as markets described in § 292.309(a)(1)(i) and (ii), and there is a rebuttable presumption that small power production facilities with a capacity greater than 5 megawatts and cogeneration facilities with a capacity greater than 20 megawatts have nondiscriminatory access to those markets through Commission-approved open access transmission tariffs and interconnection rules, and that electric utilities that are members of such regional transmission organizations or independent system operators (RTO/ISOs) should be relieved of the obligation to purchase electric energy from the qualifying facilities. A qualifying facility may seek to rebut this presumption by demonstrating, *inter alia*, that:
 - (1) The qualifying facility has certain operational characteristics that effectively

prevent the qualifying facility's participation in a market; or

- (2) The qualifying facility lacks access to markets due to transmission constraints.

 The qualifying facility may show that it is located in an area where persistent transmission constraints in effect cause the qualifying facility not to have access to markets outside a persistently congested area to sell the qualifying facility output or capacity.
- (f) The Electric Reliability Council of Texas (ERCOT) qualifies as a market described in § 292.309(a)(3), and there is a rebuttable presumption that small power production facilities with a capacity greater than five megawatts and cogeneration facilities with a capacity greater than 20 megawatts have nondiscriminatory access to that market through Public Utility Commission of Texas (PUCT) approved open access protocols, and that electric utilities that operate within ERCOT should be relieved of the obligation to purchase electric energy from the qualifying facilities. A qualifying facility may seek to rebut this presumption by demonstrating, *inter alia*, that:
- (1) The qualifying facility has certain operational characteristics that effectively prevent the qualifying facility's participation in a market; or
- (2) The qualifying facility lacks access to markets due to transmission constraints.

 The qualifying facility may show that it is located in an area where persistent transmission constraints in effect cause the qualifying facility not to have access to markets outside a persistently congested area to sell the qualifying facility output or capacity.

* * * * *

SUBCHAPTER W – REVISED GENERAL RULES

* * * * *

PART 375 – THE COMMISSION

- 1. The authority citation for part 375 continues to read as follows:
- Authority: 5 U.S.C. 551-557; 15 U.S.C. 717-717w, 3301-3432; 16 U.S.C. 791-825r, 2601-2645; 42 U.S.C. 7101-7352.
- 2. Section 375.302(v) is revised to read:
- § 375.302 Delegations to the Secretary.

* * * * *

(v) Toll the time for action on requests for rehearing, and toll the time for action on protested self-certifications and self-recertifications of qualifying facilities.

Note: The following appendix will not appear in the Code of Federal Regulations or the *Federal Register*.

Appendix A

List of Commenters and Acronyms

Commenter	Short Name/Acronym	
Advanced Energy Economy	Advanced Energy Economy	
Alaska Power Association	Alaska Power	
Allco Finance Limited, Allco Renewable Energy Limited, Windham Solar LLC, Winding Creek Solar LLC	Allco	
AllEarth Renewables, Inc.	AllEarth	
Alliant Energy Corporate Services, Inc.	Alliant Energy	
American Biogas Council	Biogas	
Americans for Limited Government – Richard Manning, President	Mr. Manning	
Americans for Tax Reform	Tax Reform	
American Public Power Association, Large Public Power Council	APPA	
Anthony O'Donnell – Montana Public Service Commissioner	Commissioner O'Donnell	
Ares EIF Management, LLC	Ares	
Arizona Corporation Commission	Arizona Commission	
Arizona Public Service Company	Arizona Public Service	
Basin Electric Power Cooperative	Basin	
Berkshire Hathaway Energy Company	Berkshire Hathaway	

Biomass Power Association	Biomass Power	
Bloom Energy Corporation	Bloom Energy	
BluEarth Renewables US LLC	BluEarth	
Borrego Solar Systems, Inc.	Borrego Solar	
Californians for Renewable Energy, Inc.	CARE	
California Public Utilities Commission	California Commission	
Center for Biological Diversity	Biological Diversity	
Center for Freedom and Prosperity	Freedom Center	
Center for Growth and Opportunity	Growth and Opportunity Center	
City of Boulder Colorado	Boulder	
Cogeneration Association of California	CA Cogeneration	
Colorado Independent Energy Association	Colorado Independent Energy	
Competitive Enterprise Institute	Competitive Enterprise	
Consolidated Edison Development, Inc.	Con Edison	
Connecticut Public Utilities Regulatory Authority	Connecticut Authority	
Conservative Action Project	Conservative Action	
Consumer Energy Alliance	Consumer Alliance	
Consumers Energy Company	Consumers Energy	
Covanta Energy, LLC	Covanta	
David J. Bardin	Mr. Bardin	
Distributed Sun LLC	Distributed Sun	
Distributed Wind Energy Association	Distributed Wind	

District of Columbia Public Service Commission	DC Commission
DTE Electric Company	DTE Electric
Duke Energy Corporation	Duke Energy
East Kentucky Power Cooperative, Inc.	East Kentucky
East River Electric Power Cooperative, Inc.	East River
Edison Electric Institute	EEI
EIM Entities	EIM Entities
El Paso Electric Company	El Paso Electric
ELCON, American Chemistry Council, American Forest & Paper Association	ELCON
Electric Power Supply Association	EPSA
Energy Recovery Council	Energy Recovery
Energy Storage Association	Energy Storage
ENGIE North America Inc.	ENGIE
Finadvice AG	Finadvice
FirstEnergy Utilities	FirstEnergy
Frontiers of Freedom	Frontiers of Freedom
Golden Valley Electric Association, Inc.	Golden Valley
Green Power Institute	Green Power
GridLab	GridLab
Harvard Electricity Law Initiative	Harvard Electricity Law
Idaho Hydroelectric Power Producers Trust	IdaHydro
Idaho Power Company	Idaho Power
Idaho Public Utilities Commission	Idaho Commission

Indiana Municipal Power Agency	Indiana Municipal	
Indiana Utility Regulatory Commission	Indiana Commission	
Industrial Energy Consumers of America	Industrial Energy Consumers	
Institute for Energy Research	Institute for Energy Research	
Institute for Liberty – Andrew Langer	Institute for Liberty	
J. Kenneth Blackwell	Mr. Blackwell	
Kentucky Public Service Commission	Kentucky Commission	
Louisville Gas and Electric Co. / Kentucky Utilities Co.	LG&E-KU	
Massachusetts Attorney General Maura Healey	Massachusetts AG	
Massachusetts Department of Public Utilities	Massachusetts DPU	
Michigan Public Service Commission	Michigan Commission	
Missouri River Energy Services	Missouri River Energy	
Montana Public Service Commission	Montana Commission	
Withitalia I dolle Service Commission		
Mr. and Mrs. Swecker	Mr. and Mrs. Swecker	
Mr. and Mrs. Swecker	Mr. and Mrs. Swecker	
Mr. and Mrs. Swecker Rebecca Kelly Slaughter – Federal Trade Commissioner National Association of Regulatory Utility	Mr. and Mrs. Swecker Commissioner Slaughter	
Mr. and Mrs. Swecker Rebecca Kelly Slaughter – Federal Trade Commissioner National Association of Regulatory Utility Commissioners	Mr. and Mrs. Swecker Commissioner Slaughter NARUC	
Mr. and Mrs. Swecker Rebecca Kelly Slaughter – Federal Trade Commissioner National Association of Regulatory Utility Commissioners National Hydropower Association	Mr. and Mrs. Swecker Commissioner Slaughter NARUC Hydropower Association	
Mr. and Mrs. Swecker Rebecca Kelly Slaughter – Federal Trade Commissioner National Association of Regulatory Utility Commissioners National Hydropower Association National Rural Electric Cooperative Association Natural Resources Defense Council, and the Sustainable	Mr. and Mrs. Swecker Commissioner Slaughter NARUC Hydropower Association NRECA	
Mr. and Mrs. Swecker Rebecca Kelly Slaughter – Federal Trade Commissioner National Association of Regulatory Utility Commissioners National Hydropower Association National Rural Electric Cooperative Association Natural Resources Defense Council, and the Sustainable FERC Project	Mr. and Mrs. Swecker Commissioner Slaughter NARUC Hydropower Association NRECA NRDC	

New England Small Hydro Coalition (New England Small Hydro)	New England Small Hydro
NextEra Energy, Inc. (NextEra)	NextEra
North American-Central, LLC	North American-Central
North Carolina Department of Justice	North Carolina DOJ
North Carolina Sustainable Energy Association	NC Sustainable Energy)
North Carolina Utilities Commission Public Staff	North Carolina Commission Staff
Northern Laramie Range Alliance	Northern Laramie Range Alliance
Northwest and Intermountain Power Producers Coalition, Community Renewable Energy Association, Renewable Energy Coalition, Oregon Solar Energy Industries Association	NIPPC, CREA, REC, and OSEIA
NorthWestern Corporation	NorthWestern
Ohio Consumers' Counsel	Ohio Consumers' Counsel
One Energy Enterprises LLC	One Energy
Oregon Public Utility Commission	Oregon Commission
Pennsylvania Public Utility Commission	Pennsylvania Commission
PJM Interconnection, L.L.C.	РЈМ
Portland General Electric Company	Portland General
Public Utilities Commission of Ohio's Office of the Federal Energy Advocate	Ohio Commission Energy Advocate
Progressive Policy Institute	Progressive Policy Institute
R Street Institute	R Street Institute
Resources for the Future	Resources for the Future

	1
SBE Council, Karen Kerrigan, President	SBE Council
Sierra Club, EarthJustice, Vote Solar, Sustainable FERC Project, Natural Resources Defense Council, Pace Energy and Climate Center, Southern Environmental Law Center, Environmental Law & Policy Center, North Carolina Sustainable Energy Association, Montana Environmental Information Center	Public Interest Organizations
Solar Energy Industries Association	Solar Energy Industries
Southern Company Services, Inc.	Southern
South Carolina Solar Business Alliance	SC Solar Alliance
South Dakota Public Utilities Commission	South Dakota Commission
Southern California Edison Company, Pacific Gas & Electric Company, San Diego Gas & Electric Company	California Utilities
Southern Environmental Law Center, North Carolina Sustainable Energy Association, Alabama Interfaith Power & Light, Alabama Solar Industry Association, Inc., Appalachian Voices, Energy Alabama, Georgia Interfaith Power & Light, Georgia Solar Energy Association, Greater-Birmingham Alliance to Stop Pollution, North Carolina Chapter of the Sierra Club, North Carolina Interfaith Power & Light, North Carolina Justice Center, South Carolina Coastal Conservation League, South Carolina Interfaith Power & Light, Southern Alliance for Clean Energy, Southface Institute, Tennessee Interfaith Power & Light, Upstate Forever, and Vote Solar	Southeast Public Interest Organizations
sPower Development Company, LLC	sPower
State Entities	State Entities
State of Idaho	Idaho
Stephen Moore	Mr. Moore
Steven Transeth	Mr. Transeth
	-

Subsurface Utility Engineering Association – John M, Palatiello	Subsurface Engineering Association
Taxpayers Protection Alliance	Taxpayers Protection Alliance
Terna Energy USA Holding Corporation	Terna Energy
Thomas Mattson	Mr. Mattson
Transmission Access Policy Study Group	TAPS
Two Dot Wind, LLC	Two Dot Wind
Union of Concerned Scientists	Union of Concerned Scientists
US Chamber of Commerce	Chamber of Commerce
We Stand for Energy - Project of Edison Electric Institute	We Stand
Western Organization of Resource Councils	Western Resource Councils
Xcel Energy Services Inc.	Xcel*

^{*}Out of Time comments were also filed by American Dams, Arizona Corporation Commission, Solar Energy Industries, and TerraForm Power Inc.

Note: The following appendix will not appear in the Code of Federal Regulations or the *Federal Register*.

Appendix B

REVISED FORM NO. 556

FEDERAL ENERGY REGULATORY COMMISSION WASHINGTON, DC

OMB Control # 1902-0075 Expiration XXXX

Form 556 Certification of Qualifying Facility (QF) Status for a Small Power Production or Cogeneration Facility

General

Questions about completing this form should be sent to Form556@ferc.gov. Information about the Commission's QF program, answers to frequently asked questions about QF requirements or completing this form, and contact information for QF program staff are available at the Commission's QF website, www.ferc.gov/QF. The Commission's QF website also provides links to the Commission's QF regulations (18 C.F.R. § 131.80 and Part 292), as well as other statutes and orders pertaining to the Commission's QF program.

Title 18, U.S.C. 1001 makes it a crime for any person knowingly and willingly to make to any Agency or Department of the United States any false, fictitious or fraudulent statements as to any matter within its jurisdiction.

Who Must File

Certification:

Any applicant seeking QF status for a generating facility that has a net power production capacity (as determined in lines 7a through 7g below) greater than 1 MW must file a self-certification or an application for Commission certification of QF status, which includes a properly completed Form 556. Any applicant seeking QF status for a generating facility with a net power production capacity 1 MW or less is exempt from the certification requirement and is therefore not required to complete or file a Form 556. See 18 C.F.R. § 292.203. This includes any applicant seeking small power production QF status for a generating facility that, together with any affiliated small power production QFs that use the same energy resource and are within one mile of the filing facility, has a net power production capacity 1 MW or less.

Recertification:

A QF must file a recertification whenever the qualifying facility "fails to conform with any material facts or representations presented ... in its submittals to the Commission." 18 C.F.R. § 292.207(f).

How to Complete the Form 556

This form is intended to be completed by responding to the items in the order they are presented, according to the instructions given. If you need to back-track, you may need to clear certain responses before you will be allowed to change other responses made previously in the form. If you experience problems, click on the nearest help button () for assistance, or contact Commission staff at Form556@ferc.gov.

Certain lines in this form will be automatically calculated based on responses to previous lines, with the relevant formulas shown. You must respond to all of the previous lines within a section before the results of an automatically calculated field will be displayed. If you disagree with the results of any automatic calculation on this form, contact Commission staff at Form556@ferc.gov to discuss the discrepancy before filing.

You must complete all lines in this form unless instructed otherwise. Do not alter this form or save this form in a different format. Incomplete or altered forms, or forms saved in formats other than PDF, will be rejected.

How to File a Completed Form 556

Applicants are required to file their Form 556 electronically through the Commission's eFiling website (see instructions on page 3). By filing electronically, you will reduce your filing burden, save paper resources, save postage or courier charges, help keep Commission expenses to a minimum, and receive a much faster confirmation (via an email containing the docket number assigned to your facility) that the Commission has received your filing.

If you are simultaneously filing both a waiver request and a Form 556 as part of an application for Commission certification, see the "Waiver Requests" section on page 4 for more information on how to file.

FERC Form 556 Page 2 - Instructions

Paperwork Reduction Act Notice

This form is approved by the Office of Management and Budget. Compliance with the information requirements established by the FERC Form No. 556 is required to obtain or maintain status as a QF. See 18 C.F.R. § 131.80 and Part 292. An agency may not penalize a person for not complying with a collection of information unless it displays a currently valid OMB control number.

The estimated total burden for completing the FERC Form No. 556, including gathering and reporting information, is as follows: 1.5 hours for self-certifications of facilities of 1 MW or less; 1.5 hours for self-certifications of a cogeneration facility over 1 MW; 50 hours for applications for Commission certification of a cogeneration facility; 3.5 hours for self-certifications of small power producers over 1 MW and less than a mile or more than 10 miles from affiliated small power production QFs that use the same energy resource; 56 hours for an application for Commission certification of a small power production facility over 1 MW and less than a mile or more than 10 miles from affiliated small power production QFs that use the same energy resource; 9.5 hours for self-certifications of small power producers over 1 MW with affiliated small power production QFs more than one but less than 10 miles that use the same energy resource; 62 hours for an application for Commission certification of a small power production facility over 1 MW with affiliated small power production QFs more than one but less than 10 miles that use the same energy resource.

Send comments regarding this burden estimate or any aspect of this collection of information, including suggestions for reducing this burden, to the following: Information Clearance Officer, Office of the Executive Director (ED-32), Federal Energy Regulatory Commission, 888 First Street N.E., Washington, DC 20426 (DataClearance@ferc.gov); and Desk Officer for FERC, Office of Information and Regulatory Affairs, Office of Management and Budget, Washington, DC 20503 through www.reginfo.gov/public/do/PRAMain. Include FERC-556 and the Control No. 1902-0075 in any correspondence.

Filing Fee

No filing fee is required if you are submitting a self-certification or self-recertification of your facility as a QF pursuant to 18 C.F.R. § 292.207(a).

A filing fee is required if you are filing either of the following:

- (1) an application for Commission certification or recertification of your facility as a QF pursuant to 18 C.F.R. § 292.207(b), or (2) a petition for declaratory order granting waiver pursuant to 18 C.F.R. §§ 292.204(a)(3) and/or 292.205(c).
- The current fees for applications for Commission certifications and petitions for declaratory order can be found by visiting the

The current fees for applications for Commission certifications and petitions for declaratory order can be found by visiting the Commission's QF website at www.ferc.gov/QF and clicking the Filing Fees link.

You will be prompted to submit your filing fee, if applicable, during the electronic filing process described on page 3.

FERC Form 556 Page 3 - Instructions

Electronic Filing (eFiling)

To electronically file your Form 556, visit the Commission's QF website at www.ferc.gov/QF and click the eFiling link.

If you are eFiling your first document, you will need to register with your name, email address, mailing address, and phone number. If you are registering on behalf of an employer, then you will also need to provide the employer name, alternate contact name, alternate contact phone number and and alternate contact email.

Once you are registered, log in to eFiling with your registered email address and the password that you created at registration. Follow the instructions. When prompted, select one of the following QF-related filing types, as appropriate, from the Electric or General filing category.

Filing category	Filing Type as listed in eFiling	Description
	(Fee) Application for Commission Cert. as Cogeneration QF	Use to submit an application for Commission certification or Commission recertification of a cogeneration facility as a QF.
	(Fee) Application for Commission Cert. as Small Power QF	Use to submit an application for Commission certification or Commission recertification of a small power production facility as a QF.
	Self-Certification Notice (QF, EG, FC)	Use to submit a notice of self- certification of your facility (cogeneration or small power production) as a QF.
Electric	Self-Recertification of Qualifying Facility (QF)	Use to submit a notice of self- recertification of your facility (cogeneration or small power production) as a QF.
	Self-Recertification of Qualifying Facility (QF) (Supplement or Correction)	Use to correct or supplement a Form 556 that was submitted with errors or omissions, or for which Commission staff has requested additional information. Do not use this filing type to report new changes to a facility or its ownership; rather, use a self-recertification or Commission recertification to report such changes.
General	(Fee) Petition for Declaratory Order (not under FPA Part 1)	Use to submit a petition for declaratory order granting a waiver of Commission QF regulations pursuant to 18 C.F.R. §§ 292.204(a) (3) and/or 292.205(c). A Form 556 is not required for a petition for declaratory order unless Commission recertification is being requested as part of the petition.

You will be prompted to submit your filing fee, if applicable, during the electronic submission process. Filing fees can be paid by check or by money order via ACH Credit transfer, Wire payment, courier, or mail.

 $During \ the \ eFiling \ process, you \ will \ be \ prompted \ to \ select \ your \ file(s) \ for \ upload \ from \ your \ computer.$

FERC Form 556 Page 4 - Instructions

Required Notice to Utilities and State Regulatory Authorities

Pursuant to 18 C.F.R. § 292.207(a)(ii), you must provide a copy of your self-certification or request for Commission certification to the utilities with which the facility will interconnect and/or transact, as well as to the State regulatory authorities of the states in which your facility and those utilities reside. Links to information about the regulatory authorities in various states can be found by visiting the Commission's QF website at www.ferc.gov/QF and clicking the Notice Requirements link.

What to Expect From the Commission After You File

An applicant filing a Form 556 electronically will receive an email message acknowledging receipt of the filing and showing the docket number assigned to the filing. Such email is typically sent within one business day, but may be delayed pending confirmation by the Secretary of the Commission of the contents of the filing.

An applicant submitting a self-certification of QF status should expect to receive no documents from the Commission, other than the electronic acknowledgement of receipt described above. Consistent with its name, a self-certification is a certification by the applicant itself that the facility meets the relevant requirements for QF status, and does not involve a determination by the Commission as to the status of the facility. An acknowledgement of receipt of a self-certification, in particular, does not represent a determination by the Commission with regard to the QF status of the facility. An applicant self-certifying may, however, receive a rejection, revocation or deficiency letter if its application is found, during periodic compliance reviews, not to comply with the relevant requirements.

An applicant submitting a request for Commission certification will receive an order either granting or denying certification of QF status, or a letter requesting additional information or rejecting the application. Pursuant to 18 C.F.R. § 292.207(b)(3), the Commission must act on an application for Commission certification within 90 days of the later of the filing date of the application or the filing date of a supplement, amendment or other change to the application.

Protests to the Filing

Pursuant to 18 C.F.R. § 292.207, an interested party has 30 days from the date of the filing of a self-certification or self-recertification to intervene or file a protest. Protests may be made to an initial certification (both self-certification and application for Commission certification) filed on or after [xxx effective date of this final rule], but only to a recertification (both self-recertification and application for Commission recertification) that makes substantive changes to the existing certification and that is filed on or after [xxx effective date of this final rule], as described in Order No. xxxx (accessible from the Commission's QF website at www.ferc.gov/QF). Substantive changes that may be subject to a protest may include, for example, a change in electrical generating equipment that increases power production capacity by the greater of 1 MW or 5% of the previously certified capacity of the QF, or a change in ownership in which an owner increases its equity interest by at least 10% from the equity interest previously reported. The protestor must concurrently serve a copy of such filing pursuant to 18 C.F.R. § 385.2011. Any response to a protest must be filed on or before 30 days from the date of filing of that protest.

Waiver Requests

18 C.F.R. § 292.204(a)(3) allows an applicant to request a waiver to modify the method of calculation pursuant to 18 C.F.R. § 292.204(a)(2) to determine if two facilities are considered to be located at the same site, for good cause. 18 C.F.R. § 292.205(c) allows an applicant to request waiver of the requirements of 18 C.F.R. §§ 292.205(a) and (b) for operating and efficiency upon a showing that the facility will produce significant energy savings. A request for waiver of these requirements must be submitted as a petition for declaratory order, with the appropriate filling fee for a petition for declaratory order. Applicants requesting Commission recertification as part of a request for waiver of one of these requirements should electronically submit their completed Form 556 along with their petition for declaratory order, rather than filling their Form 556 as a separate request for Commission recertification. Only the filling fee for the petition for declaratory order must be paid to cover both the waiver request and the request for recertification if such requests are made simultaneously.

18 C.F.R. § 292.203(d)(2) allows an applicant to request a waiver of the Form 556 filing requirements, for good cause. Applicants filing a petition for declaratory order requesting a waiver under 18 C.F.R. § 292.203(d)(2) do not need to complete or submit a Form 556 with their petition.

FERC Form 556 Page 5 - Instructions

Geographic Coordinates

Items 3c and 8a of the Form 556 require you to report your facility's (and certain neighboring facilities') geographic coordinates (latitude and longitude). Geographic coordinates may be obtained from several different sources. You can find links to online services that show latitude and longitude coordinates on online maps by visiting the Commission's QF webpage at www.ferc.gov/QF. You may also be able to obtain your geographic coordinates from a GPS device, Google Earth (available free at https://earth.google.com), a property survey, various engineering or construction drawings, a property deed, or a municipal or county map showing property lines.

Filing Privileged Data or Critical Energy Infrastructure Information in a Form 556

The Commission's regulations provide procedures for applicants to either (1) request that any information submitted with a Form 556 be given privileged treatment because the information is exempt from the mandatory public disclosure requirements of the Freedom of Information Act, 5 U.S.C. § 552, and should be withheld from public disclosure; or (2) identify any documents containing critical energy infrastructure information (CEII) as defined in 18 C.F.R. § 388.113 that should not be made public.

If you are seeking privileged treatment or CEII status for any data in your Form 556, then you must follow the procedures in 18 C.F.R. § 388.112. See www.ferc.gov/help/filing-guide/file-ceii.asp for more information.

Among other things (see 18 C.F.R. § 388.112 for other requirements), applicants seeking privileged treatment or CEII status for data submitted in a Form 556 must prepare and file both (1) a complete version of the Form 556 (containing the privileged and/or CEII data), and (2) a public version of the Form 556 (with the privileged and/or CEII data redacted). Applicants preparing and filing these different versions of their Form 556 must indicate below the security designation of this version of their document. If you are *not* seeking privileged treatment or CEII status for any of your Form 556 data, then you should not respond to any of the items on this page.

Non-Public: Applicant is seeking privileged treatment and/or CEII status for data contained in the Form 556 lines indicated below. This non-public version of the applicant's Form 556 contains all data, including the data that is redacted in the (separate) public version of the applicant's Form 556.
Public (redacted): Applicant is seeking privileged treatment and/or CEII status for data contained in the Form 556 lines indicated below. This public version of the applicants's Form 556 contains all data except for data from the lines indicated below, which has been redacted.
Privileged : Indicate below which lines of your form contain data for which you are seeking privileged treatment
Critical Energy Infrastructure Information (CEII): Indicate below which lines of your form contain data for which you are seeking CEII status

The eFiling process described on page 3 will allow you to identify which versions of the electronic documents you submit are public, privileged and/or CEII. The filenames for such documents should begin with "Public", "Priv", or "CEII", as applicable, to clearly indicate the security designation of the file. Both versions of the Form 556 should be unaltered PDF copies of the Form 556, as available for download from www.ferc.gov/QF. To redact data from the public copy of the submittal, simply omit the relevant data from the Form. For numerical fields, leave the redacted fields blank. For text fields, complete as much of the field as possible, and replace the redacted portions of the field with the word "REDACTED" in brackets. Be sure to identify above all fields which contain data for which you are seeking non-public status.

The Commission is not responsible for detecting or correcting filer errors, including those errors related to security designation. If your documents contain sensitive information, make sure they are filed using the proper security designation.

FEDERAL ENERGY REGULATORY COMMISSION WASHINGTON, DC

OMB Control # 1902-0075 Expiration xxxx

Form 556 Certification of Qualifying Facility (QF) Status for a Small Power Production or Cogeneration Facility

16	 Applicant street addre 	ess			
1c	City		1d State/provi	nce	
1e	Postal code	1f Country (if not United States)		1g Telephone number	
1h	Has the instant facility	ever previously been certified as a Q	F? Yes N	lo 📗	
1i	If yes, provide the dock	ket number of the last known QF filing	g pertaining to th	nis facility: QF	
1j	Under which certificati	on process is the applicant making th	is filing?		
[Notice of self-certific (see note below)	cation A fe	pplication for Co e; see "Filing Fee	mmission certification (requires filing " section on page 4)	
	Note: a notice of self-certification is a notice by the applicant itself that its facility complies with the requirements for QF status. A notice of self-certification does not establish a proceeding, and the Commission does not review a notice of self-certification to verify compliance. See the "What to Expect From the Commission After You File" section on page 4 for more information.				
1k	What type(s) of QF sta	tus is the applicant seeking for its fac	lity? (check all th	at apply)	
	Qualifying small por	wer production facility status 🔲 Q	ualifying cogene	eration facility status	
1l	What is the purpose an	nd expected effective date(s) of this fil	ing?		
	Original certification	n; facility expected to be installed by	ar	nd to begin operation on	
	Change(s) to a prev	iously certified facility to be effective	on		
	(identify type(s) of change(s) below, and describe change(s) in the Miscellaneous section starting on page 24) Name change and/or other administrative change(s)				
	Change in owner		ei 670		
	Change(s) affecti	ng plant equipment, fuel use, power	production capa	city and/or cogeneration thermal output	
	Supplement or correction to a previous filing submitted on				
	(describe the supple	ement or correction in the Miscellane	ous section starti	ng on page 24)	
1m	1m If any of the following three statements is true, check the box(es) that describe your situation and complete the form to the extent possible, explaining any special circumstances in the Miscellaneous section starting on page 24.				
	previously granted	complies with the Commission's QF d by the Commission in an order date ellaneous section starting on page 24	d	virtue of a waiver of certain regulations (specify any other relevant waiver	
		would comply with the Commission this application is granted	s QF requiremen	ts if a petition for waiver submitted	
	employment of ur		contemplated by	special circumstances, such as the the structure of this form, that make	

FE	RC Form 556		Page 7 - All Facilities
	2a Name of contact person		2b Telephone number
Contact Information	Employee of a company affiliat	oyee, owner or partner of applican ted with the applicant authorized t presentative authorized to represe (if applicant is an individual, check	t authorized to represent the applicant o represent the applicant on this matter ent the applicant on this matter here and skip to line 2e)
ප	2f City	2g Sta	ate/province
	2h Postal code	2i Country (if not United States)	
no	3a Facility name		
d Locatic	3b Street address (if a street address	s does not exist for the facility, chec	ck here and skip to line 3c)
Facility Identification and Location	places). Use the following formu	ıla to convert to decimal degrees fi 0) + (seconds/3600). See the "Gec	nates of the facility in degrees (to three decimal rom degrees, minutes and seconds: decimal ographic Coordinates" section on page 5 for help. dedegrees Choose +/-
lity Id	3d City (if unincorporated, check he	ere and enter nearest city) 🔲 3e	State/province
Faci	3f County (or check here for indepe	ndent city) 🗌 3g Count	ry (if not United States)
	Identify the electric utilities that are o	contemplated to transact with the t	facility.
lities	4a Identify utility interconnecting w	rith the facility	
ng Uti	4b Identify utilities providing wheel	ing service or check here if none	
Transacting Util	4c Identify utilities purchasing the u	seful electric power output or chec	ck here if none
Tran	4d Identify utilities providing supple service or check here if none	ementary power, backup power, m	aintenance power, and/or interruptible power

Page 8 - All Facilities

Full legal names of direct owners Tyes No Sequinteres Yes No Sequinteres	1 1	Direct ownership as of effective date or operation date: Identify all direct owners of the cercent equity interest. For each identified owner, also (1) indicate whether that ow defined in section 3(22) of the Federal Power Act (16 U.S.C. 796(22)), or a holding cor 262(8) of the Public Utility Holding Company Act of 2005 (42 U.S.C. 16451(8)), and (intities or holding companies, provide the percentage of equity interest in the facility litect owners hold at least 10 percent equity interest in the facility, then provide the wo direct owners with the largest equity interest in the facility.	ner is an e npany, as 2) for own sy held by required i	lectric utili defined in ers which a that owner nformation	ty, as section are electric r. If no n for the
1) 2) Yes No 3) Yes No 4) Yes No 5) Yes No 6) Yes No 7) Yes No 9) Yes No 10) Check here and continue in the Miscellaneous section starting on page 24 if additional space is needed 5b Upstream (i.e., indirect) ownership as of effective date or operation date: Identify all upstream (i.e., indirect) own of the facility that both (1) hold at least 10 percent equity interest in the facility, and (2) are electric utilities, as defined in section 3(22) of the Federal Power Act (16 U.S.C. 796(22)), or holding companies, as defined in section 1262(8) of the Public Utility Holding Company Act of 2005 (42 U.S.C. 16451(8)). Also provide the percentage of equity interest in the facility held by such owners. (Note that, because upstream owners may be subsidiaries of c another, total percent equity interest reported may exceed 100 percent.) Check here if no such upstream owners exist. Full legal names of electric utility or holding company upstream owners Yes No 9		Full legal names of direct owners	ho	ding	If Yes, % equity interest
2) 3) Yes No 4) Yes No 5) Yes No 6) Yes No 7) Yes No 9) 10) Check here and continue in the Miscellaneous section starting on page 24 if additional space is needed 5b Upstream (i.e., indirect) ownership as of effective date or operation date: Identify all upstream (i.e., indirect) own of the facility that both (1) hold at least 10 percent equity interest in the facility, and (2) are electric utilities, as defined in section 3(22) of the Federal Power Act (16 U.S.C. 796(22)), or holding companies, as defined in section 1262(8) of the Public Utility Holding Company Act of 2005 (42 U.S.C. 1645(8)). Also provide the percentage of equity interest in the facility held by such owners. (Note that, because upstream owners may be subsidiaries of c another, total percent equity interest reported may exceed 100 percent.) Check here if no such upstream owners exist. Full legal names of electric utility or holding company upstream owners 1) 2) 3) 4) 5) 6) 7) 8) 9)	1)	-			
3) 4) 4) 5) 6) 7) 8) 9) 10) Check here and continue in the Miscellaneous section starting on page 24 if additional space is needed 5b Upstream (i.e., indirect) ownership as of effective date or operation date: Identify all upstream (i.e., indirect) own of the facility that both (1) hold at least 10 percent equity interest in the facility, and (2) are electric utilities, as defined in section 3(22) of the Federal Power Act (16 U.S.C. 796(22)), or holding companies, as defined in section 126(8) of the public Utility Holding Company Act of 2005 (42 U.S.C. 1645(8)). Also provide the percentage of equity interest in the facility held by such owners. (Note that, because upstream owners may be subsidiaries of c another, total percent equity interest reported may exceed 100 percent.) Check here if no such upstream owners exist. Full legal names of electric utility or holding company upstream owners 1) 2) 3) 4) 5) 6) 7) 8) 9)	2)		-		8
5) 6) 7 Yes No 7 Yes No 7 Yes No 9) 10) Check here and continue in the Miscellaneous section starting on page 24 if additional space is needed 5b Upstream (i.e., indirect) ownership as of effective date or operation date: Identify all upstream (i.e., indirect) own of the facility that both (1) hold at least 10 percent equity interest in the facility, and (2) are electric utilities, as defined in section 3(22) of the Federal Power Act (16 U.S.C. 796(22)), or holding companies, as defined in section 1262(8) of the Public Utility Holding Company Act of 2005 (42 U.S.C. 16451(8)). Also provide the percentage of equity interest in the facility held by such owners. (Note that, because upstream owners may be subsidiaries of canother, total percent equity interest reported may exceed 100 percent.) Check here if no such upstream owners exist. Full legal names of electric utility or holding company upstream owners 1) 2) 3) 4) 5) 6) 77 8) 9)	3)				8
5) Yes No 6) Yes No 7) Yes No 8) Yes No 9) Yes No 10) Yes No 11) Yes No 126(8) of the Fublic Utility Holding Company Act of 2005 (42 U.S.C. 16451(8)). Also provide the percentage of equity interest in the facility held by such owners. (Note that, because upstream owners may be subsidiaries of canother, total percent equity interest reported may exceed 100 percent.) Check here if no such upstream owners exist. Full legal names of electric utility or holding company upstream owners 1) 2) 3) 4) 5) 6) 7) 8) 9)	4)				8
7) 8) 9) 10) Yes No 10) Check here and continue in the Miscellaneous section starting on page 24 if additional space is needed 5b Upstream (i.e., indirect) ownership as of effective date or operation date: Identify all upstream (i.e., indirect) own of the facility that both (1) hold at least 10 percent equity interest in the facility, and (2) are electric utilities, as defined in section 3(22) of the Federal Power Act (16 U.S.C. 796(22)), or holding companies as defined in section 1262(8) of the Public Utility Holding Company Act of 2005 (42 U.S.C. 16451(8)). Also provide the percentage of equity interest in the facility held by such owners. (Note that, because upstream owners may be subsidiaries of c another, total percent equity interest reported may exceed 100 percent.) Check here if no such upstream owners exist. Full legal names of electric utility or holding company upstream owners 1) 2) 3) 4) 5) 6) 7) 8) 9)	5)			No	8
8) 9) Yes No 10) Yes No Check here and continue in the Miscellaneous section starting on page 24 if additional space is needed 5b Upstream (i.e., indirect) ownership as of effective date or operation date: Identify all upstream (i.e., indirect) own of the facility that both (1) hold at least 10 percent equity interest in the facility, and (2) are electric utilities, as defined in section 3(22) of the Federal Power Act (16 U.S.C. 796(22)), or holding companies, as defined in section 1262(8) of the Public Utility Holding Company Act of 2005 (42 U.S.C. 16451(8)). Also provide the percentage of equity interest in the facility held by such owners. (Note that, because upstream owners may be subsidiaries of c another, total percent equity interest reported may exceed 100 percent.) Check here if no such upstream owners exist. Full legal names of electric utility or holding company upstream owners 1) 2) 3) 4) 5) 6) 7) 8) 9)	6)		Yes	No	8
9) 10) Yes No Check here and continue in the Miscellaneous section starting on page 24 if additional space is needed 5b Upstream (i.e., indirect) ownership as of effective date or operation date: Identify all upstream (i.e., indirect) own of the facility that both (1) hold at least 10 percent equity interest in the facility, and (2) are electric utilities, as defined in section 3(22) of the Federal Power Act (16 U.S.C. 796(22)), or holding companies, as defined in section 1262(8) of the Public Utility Holding Company Act of 2005 (42 U.S.C. 16451(8)). Also provide the percentage of equity interest in the facility held by such owners. (Note that, because upstream owners may be subsidiaries of canother, total percent equity interest reported may exceed 100 percent.) Check here if no such upstream owners exist. Full legal names of electric utility or holding company upstream owners 1) 9) 9) 6) 7) 8) 9)	7)		Yes	No	8
Check here and continue in the Miscellaneous section starting on page 24 if additional space is needed Check here and continue in the Miscellaneous section starting on page 24 if additional space is needed Check here and continue in the Miscellaneous section starting on page 24 if additional space is needed Check here and continue in the Miscellaneous section starting on page 24 if additional space is needed Check here in the facility had both (1) hold at least 10 percent equity interest in the facility, and (2) are electric utilities, as defined in section 3(22) of the Federal Power Act (16 U.S.C. 796(22)), or holding companies, as defined in section 1262(8) of the Public Utility Holding Company Act of 2005 (42 U.S.C. 16451(8)). Also provide the percentage of equity interest in the facility held by such owners. (Note that, because upstream owners may be subsidiaries of canother, total percent equity interest reported may exceed 100 percent.) Check here if no such upstream owners exist.	8)		Yes	No	8
Check here and continue in the Miscellaneous section starting on page 24 if additional space is needed 5b Upstream (i.e., indirect) ownership as of effective date or operation date: Identify all upstream (i.e., indirect) own of the facility that both (1) hold at least 10 percent equity interest in the facility, and (2) are electric utilities, as defined in section 3(22) of the Federal Power Act (16 U.S.C. 796(22)), or holding companies, as defined in section 1262(8) of the Public Utility Holding Company Act of 2005 (42 U.S.C. 16451(8)). Also provide the percentage of equity interest in the facility held by such owners. (Note that, because upstream owners may be subsidiaries of c another, total percent equity interest reported may exceed 100 percent.) Check here if no such upstream owners exist. Full legal names of electric utility or holding company upstream owners **wequ** Full legal names of electric utility or holding company upstream owners 1) 2) 3) 4) 5) 6) 7) 8) 9)	9)		Yes	No	%
Check here and continue in the Miscellaneous section starting on page 24 if additional space is needed 5b Upstream (i.e., indirect) ownership as of effective date or operation date: Identify all upstream (i.e., indirect) own of the facility that both (1) hold at least 10 percent equity interest in the facility, and (2) are electric utilities, as defined in section 3(22) of the Federal Power Act (16 U.S.C. 796(22)), or holding companies, as defined in section 1262(8) of the Public Utility Holding Company Act of 2005 (42 U.S.C. 16451(8)). Also provide the percentage of equity interest in the facility held by such owners. (Note that, because upstream owners may be subsidiaries of canother, total percent equity interest reported may exceed 100 percent.) Check here if no such upstream owners exist. Full legal names of electric utility or holding company upstream owners Full legal names of electric utility or holding company upstream owners 1) 2) 3) 4) 5) 6) 7) 8) 9)	10)		Yes	No	8
2) 3) 4) 5) 6) 7) 8) 9)	a	nother, total percent equity interest reported may exceed 100 percent.) heck here if no such upstream owners exist.	,	oe subsidia	ries of one % equity interest
3) 4) 5) 6) 7) 8) 9)	1)				98
4) 5) 6) 7) 8) 9)	2)				8
5) 6) 7) 8) 9)	3)				8
6) 7) 8) 9)	4)				98
7) 8) 9)	5)				8
8) 9)	6)				8
9)	7)				8
	8)				8
10)	9)				8
	10)				8
Check here and continue in the Miscellaneous section starting on page 24 if additional space is needed		Check here and continue in the Miscellaneous section starting on page 24 if addi	tional spa	ce is neede	ed

FFRC Form 556

Page 9 - All Facilities

6a Describe the primary energy input: (check one main category and, if applicable, one subcategory) Renewable resources (specify) Biomass (specify) Geothermal Landfill gas Fossil fuel (specify) Hydro power - river Manure digester gas Hydro power - tidal Coal (not waste) Municipal solid waste Hydro power - wave Fuel oil/diesel Natural gas (not waste) Sewage digester gas Solar - photovoltaic ■ Wood Solar - thermal Other fossil fuel (describe on page 24) Other biomass (describe on page 24) Wind Other renewable resource Other (describe on page 24) (describe on page 24) Waste (specify type below in line 6b) **6b** If you specified "waste" as the primary energy input in line 6a, indicate the type of waste fuel used: (check one) Waste fuel listed in 18 C.F.R. § 292.202(b) (specify one of the following) Anthracite culm produced prior to July 23, 1985 Anthracite refuse that has an average heat content of 6,000 Btu or less per pound and has an average ash content of 45 percent or more Bituminous coal refuse that has an average heat content of 9,500 Btu per pound or less and has an average ash content of 25 percent or more Top or bottom subbituminous coal produced on Federal lands or on Indian lands that has been determined to be waste by the United States Department of the Interior's Bureau of Land Management **Energy Input** (BLM) or that is located on non-Federal or non-Indian lands outside of BLM's jurisdiction, provided that the applicant shows that the latter coal is an extension of that determined by BLM to be waste Coal refuse produced on Federal lands or on Indian lands that has been determined to be waste by the BLM or that is located on non-Federal or non-Indian lands outside of BLM's jurisdiction, provided that applicant shows that the latter is an extension of that determined by BLM to be waste Lignite produced in association with the production of montan wax and lignite that becomes exposed as a result of such a mining operation Gaseous fuels (except natural gas and synthetic gas from coal) (describe on page 24) Waste natural gas from gas or oil wells (describe on page 24 how the gas meets the requirements of 18 C.F.R. § 2.400 for waste natural gas; include with your filing any materials necessary to demonstrate compliance with 18 C.F.R. § 2.400) Materials that a government agency has certified for disposal by combustion (describe on page 24) Heat from exothermic reactions (describe on page 24) Residual heat (describe on page 24) Used rubber tires Plastic materials Refinery off-gas Petroleum coke Other waste energy input that has little or no commercial value and exists in the absence of the qualifying facility industry (describe in the Miscellaneous section starting on page 24; include a discussion of the fuel's lack of commercial value and existence in the absence of the qualifying facility industry) 6c Provide the average energy input, calculated on a calendar year basis, in terms of Btu/h for the following fossil fuel energy inputs, and provide the related percentage of the total average annual energy input to the facility (18 C.F.R. § 292.202(j)). For any oil or natural gas fuel, use lower heating value (18 C.F.R. § 292.202(m)). Annual average energy Percentage of total Fue input for specified fuel annual energy input Natural gas Btu/h % Oil-based fuels Btu/h % Coal Btu/h 0/0

FERC Form 556 Page 10 - All Facilities

	Indicate the maximum gross and maximum net electric power production capacity of the facility at the point(s) of delivery by completing the worksheet below. Respond to all items. If any of the parasitic loads and/or losses identified in lines 7b through 7e are negligible, enter zero for those lines.						
	7a The maximum gross power production capacity at the terminals of the individual generator(s) under the most favorable anticipated design conditions	kW					
	7b Parasitic station power used at the facility to run equipment which is necessary and integral to the power production process (boiler feed pumps, fans/blowers, office or maintenance buildings directly related to the operation of the power generating facility, etc.). If this facility includes non-power production processes (for instance, power consumed by a cogeneration facility's thermal host), do not include any power consumed by the non-power production activities in your reported parasitic station power.	kW					
	7c Electrical losses in interconnection transformers	kW					
	7d Electrical losses in AC/DC conversion equipment, if any	kW					
	7e Other interconnection losses in power lines or facilities (other than transformers and AC/DC conversion equipment) between the terminals of the generator(s) and the point of interconnection with the utility	kW					
Technical Facility Information	7f Total deductions from gross power production capacity = $7b + 7c + 7d + 7e$	o kW					
	7g Maximum net power production capacity = 7a - 7f	o kW					
	7h Description of facility and primary components: Describe the facility and its operation. Identify all boilers, heat recovery steam generators, prime movers (any mechanical equipment driving an electric generator), electrical generators, photovoltaic solar equipment, fuel cell equipment and/or other primary power generation equipment used in the facility. Descriptions of components should include (as applicable) specifications of the nominal capacities for mechanical output, electrical output, or steam generation of the identified equipment. For each piece of equipment identified, clearly indicate how many pieces of that type of equipment are included in the plant, and which components are normally operating or normally in standby mode. Provide a description of how the components operate as a system. Applicants for cogeneration facilities do not need to describe operations of systems that are clearly depicted on and easily understandable from a cogeneration facility's attached mass and heat balance diagram; however, such applicants should provide any necessary description needed to understand the sequential operation of the facility depicted in their mass and heat balance diagram. If additional space is needed, continue in the Miscellaneous section starting on page 24.						
⊢							

Information Required for Small Power Production Facility

If you indicated in line 1k that you are seeking qualifying small power production facility status for your facility, then you must respond to the items on this page. Otherwise, skip pages 11 through 15.

Pursuant to 18 C.F.R. § 292.204(a), the power production capacity of any small power production facility, together with the power production capacity of any other small power production facilities that use the same energy resource, are owned by the same person(s) or its affiliates, and are located at the same site, may not exceed 80 megawatts. To demonstrate compliance with this size limitation, or to demonstrate that your facility is exempt from this size limitation under the Solar, Wind, Waste, and Geothermal Power Production Incentives Act of 1990 (Pub. L. 101-575, 104 Stat. 2834 (1990) as amended by Pub. L. 102-46, 105 Stat. 249 (1991)), respond to lines 8a through 8f below (as applicable).

Electric Generating Equipment

Electrical generating equipment will refer to all boilers, heat recovery steam generators, prime movers (any mechanical equipment driving an electric generator), electrical generators, photovoltaic solar panels, inverters, fuel cell equipment and/or other primary power generation equipment used in the facility, excluding equipment for gathering energy to be used in the facility. Each wind turbine on a wind farm and each solar panel in a solar facility is considered electrical generating equipment because each wind turbine and each solar panel is independently capable of producing electric energy.

Distance

Certification of Compliance

with Size Limitations

The distance between two facilities is to be measured from the edge of the closest electrical generating equipment for which qualification or recertification is sought to the edge of the nearest electrical generating equipment of the other affiliated small power production qualifying facility using the same energy resource. An affiliated small power production QF located one mile or less from the instant facility is irrebuttably presumed to be at the same site. An affiliated small power production QF located more than one mile and less than 10 miles from the instant facility is rebuttably presumed to be at a separate site. An affiliated small power production QF located 10 miles or more from the instant facility is irrebuttably presumed to be located at a separate site.

8a Identify affiliated small power production QFs located less than 10 miles from the electrical generating equipment of the instant facility that use the same energy resource and are held (with at least a 5 percent equity interest) by any of the entities identified in lines 5a or 5b or their affiliates. Specify the latitude and longitude coordinates for both the applicant and the affiliate small power production QF based on the nearest electrical generating equipment for each facility. Report coordinates in degrees (to three decimal places) as a positive number for east and north or a negative number for west and south. Use the following formula to convert to decimal degrees from degrees, minutes and seconds: decimal degrees = degrees + (minutes/60) + (seconds/3600). See the "Geographic Coordinates" section on page 5 for help obtaining coordinates. The distances for each facility listed below will be automatically calculated from the reported coordinates. See www.ferc.gov/QF for more information on how this form calculates distance.

Check here if no such facilities exist.



	Facility location (city or county, state)	Ro	oot docket # (if any)		m net power ion capacity	Co	ommon owner(s)
		QF			kW			
	Coordinates (in degrees) and Distan	ice (m	iles):					
1)	Closest electrical generating equipr	nent f	or applicant's	s facility:				
	Latitude Choose +/-	L	ongitude		Choose +/-			
	Closest electrical generating equipr	nent f	or affiliate's f	acility:		1	Distance	
	Latitude Choose +/-	L	ongitude		Choose +/-	0		miles



FERC F	_	Continued		Fagi	e 12 - Small Power Production
		Facility location (city or county, state)	Root docket # (if any) QF -	Maximum net power production capacity kW	Common owner(s)
		Coordinates (in degrees) and Distar		KVV	
	2)	Closest electrical generating equipr		facility:	
		Latitude Choose +/-	Longitude	Choose +/-	
		Closest electrical generating equipr	ment for affiliate's fa	acility:	Distance
		Latitude Choose +/-	Longitude	Choose +/-	0 miles
		Facility location (city or county, state)	Root docket # (if any)	Maximum net power production capacity	Common owner(s)
			QF	kW	
e C	3)	Coordinates (in degrees) and Distan			
lian ns		Closest electrical generating equipment Latitude		Choose +/-	
mpl atio		Closest electrical generating equipr	ment for affiliate's fa	acility:	Distance
fCo		Latitude Choose +/-		Choose +/-	Distance 0 miles
Certification of Compliance with Size Limitations		- 100			
catic h Si		Facility location (city or county, state)	Root docket # (if any)	Maximum net power production capacity	Common owner(s)
rtific			QF	kW	·
<u>e</u>	4)	Coordinates (in degrees) and Distan		6-206	
	7)	Closest electrical generating equipment Latitude		Choose +/-	
		Closest electrical generating equipr			51.
		Latitude Choose +/-		Choose +/-	Distance miles
		- 1114			·
		Facility location (city or county, state)	Root docket # (if any)	Maximum net power production capacity	Common owner(s)
			QF	kW	
	5)	Coordinates (in degrees) and Distar			
		Closest electrical generating equipr		Choose +/-	
		Closest electrical generating equipr	ment for affiliate's fa	acility:	Dietamas
		Latitude Choose +/-		Choose +/-	Distance 0 miles
		<u> </u>			· · · · · · · · · · · · · · · · · · ·

FERC Form 556 Page 13 - Small Power Production 8a Continued Facility location Root docket # Maximum net power (city or county, state) Common owner(s) (if any) production capacity QF kW Coordinates (in degrees) and Distance (miles): Closest electrical generating equipment for applicant's facility: Choose +/-Longitude Choose +/-Latitude Closest electrical generating equipment for affiliate's facility: Distance Latitude Choose +/-Longitude Choose +/miles Facility location Root docket # Maximum net power (city or county, state) (if any) production capacity Common owner(s) Coordinates (in degrees) and Distance (miles): Certification of Compliance Closest electrical generating equipment for applicant's facility: with Size Limitations Latitude Choose +/- Longitude Choose +/-Closest electrical generating equipment for affiliate's facility: Distance Choose +/-Choose +/-Longitude miles Maximum net power Facility location Root docket # (city or county, state) (if any) production capacity Common owner(s) kW Coordinates (in degrees) and Distance (miles): Closest electrical generating equipment for applicant's facility: Choose +/-Longitude Choose +/-Latitude Closest electrical generating equipment for affiliate's facility: Distance Latitude Choose +/-Longitude Choose +/miles Facility location Root docket # Maximum net power (city or county, state) (if any) production capacity Common owner(s) QF kW Coordinates (in degrees) and Distance (miles): Closest electrical generating equipment for applicant's facility: Latitude Choose +/-Longitude Choose +/-Closest electrical generating equipment for affiliate's facility: Distance Choose +/-Choose +/-Latitude Longitude 0 miles

Certification of Compliance

Page 14 - Small Power Production

	Continued					
		location unty, state)	Root docket # (if any)	Maximum net power production capacity	Common	n owner(s)
			QF	kW		
	Coordinates (in c	legrees) and Distar	nce (miles):		<u> </u>	
10)	Closest electrical	generating equipr	ment for applicant's	facility:	-	
	Latitude	Choose +/-	Longitude	Choose +/-		
	Closest electrical	generating equipr	ment for affiliate's fa	acility:	Dist	tance
	Latitude	Choose +/-	Longitude	Choose +/-	0	mile
Use deg cooi	the following forn rees + (minutes/60 rdinates. The dista	nula to convert to o 0) + (seconds/3600 ances for each facili	decimal degrees fro). See the "Geograp ity listed below will	ast and north or a negative or degrees, minutes and so whic Coordinates" section be automatically calculate on how this form calculate	econds: decim on page 5 for h ed from the rep	al degrees = elp obtaining
(Closest electrical g	enerating equipme	ent for applicant's f	acility (degrees):		
	Latitude	Choose +/-	Longitude	Choose +/-		
(Closest electrical g	enerating equipme	ent for affiliate's fac	ility (degrees):	Dist	tance

Page 15 - Small Power Production

	8b Continued
	in the same location, placed into service within 12 months of an affiliated small power production QF project's
	commercial operation date as specified in the power sales agreement, or sharing engineering or procurement
	contracts.
9	
Certification of Compliance with Size Limitations	
tification of Complia with Size Limitations	
m ati	
S E	
Ę. ď	
on Ze	
ati o Si	
fi	
irti	8c The Solar, Wind, Waste, and Geothermal Power Production Incentives Act of 1990 (Incentives Act) provides
Ü	exemption from the size limitations in 18 C.F.R. § 292.204(a) for certain facilities that were certified prior to 1995.
	Are you seeking exemption from the size limitations in 18 C.F.R. § 292.204(a) by virtue of the Incentives Act?
	Yes (continue at line 8d below) No (skip lines 8d through 8f)
	8d Was the original notice of self-certification or application for Commission certification of the facility filed on or before December 31, 1994? Yes No
	CONTRACTOR
	8e Did construction of the facility commence on or before December 31, 1999? Yes No
	8f If you answered No in line 8e, indicate whether reasonable diligence was exercised toward the completion of
	the facility, taking into account all factors relevant to construction? Yes No If you answered Yes, provide a brief narrative explanation in the Miscellaneous section starting on page 24 of the construction timeline (in
	particular, describe why construction started so long after the facility was certified) and the diligence exercised
	toward completion of the facility.
ts e	Pursuant to 18 C.F.R. § 292.204(b), qualifying small power production facilities may use fossil fuels, in minimal
Compliance equirements	amounts, for only the following purposes: ignition; start-up; testing; flame stabilization; control use; alleviation or prevention of unanticipated equipment outages; and alleviation or prevention of emergencies, directly affecting
olici en	the public health, safety, or welfare, which would result from electric power outages. The amount of fossil fuels
E i	used for these purposes may not exceed 25 percent of the total energy input of the facility during the 12-month period beginning with the date the facility first produces electric energy or any calendar year thereafter.
ပ မြ	
~ ∝	9a Certification of compliance with 18 C.F.R. § 292.204(b) with respect to uses of fossil fuel:
on Jse	Applicant certifies that the facility will use fossil fuels <i>exclusively</i> for the purposes listed above.
Certification of with Fuel Use R	9b Certification of compliance with 18 C.F.R. § 292.204(b) with respect to amount of fossil fuel used annually:
fic	Applicant certifies that the amount of fossil fuel used at the facility will not, in aggregate, exceed 25
∓ ⊂	
1 to 1	percent of the total energy input of the facility during the 12-month period beginning with the date the facility first produces electric energy or any calendar year thereafter.

Page 16 - Cogeneration Facilities

Information Required for Cogeneration Facility

If you indicated in line 1k that you are seeking qualifying cogeneration facility status for your facility, then you must respond to the items on pages 16 through 18. Otherwise, skip pages 16 through 18.

100			ter entermor, surp pugges to time u.g. ter
		energy (such as heat or suse of energy. Pursuant cycle cogeneration facilithermal application or p	92.202(c), a cogeneration facility produces electric energy and forms of useful thermal steam) used for industrial, commercial, heating, or cooling purposes, through the sequential to 18 C.F.R. § 292.202(s), "sequential use" of energy means the following: (1) for a toppingty, the use of reject heat from a power production process in sufficient amounts in a rocess to conform to the requirements of the operating standard contained in 18 C.F.R. § obtoming-cycle cogeneration facility, the use of at least some reject heat from a thermal or power production.
		10a What type(s) of cog	eneration technology does the facility represent? (check all that apply)
		Topping-cycle	e cogeneration Bottoming-cycle cogeneration
		other requirements balance diagram de meet certain requir	te the sequential operation of the cogeneration process, and to support compliance with s such as the operating and efficiency standards, include with your filing a mass and heat epicting average annual operating conditions. This diagram must include certain items and rements, as described below. You must check next to the description of each requirement at you have complied with these requirements.
		Check to certify	
		compliance with indicated requirement	Paguiroment
		indicated requirement	Requirement
ration	Information		Diagram must show orientation within system piping and/or ducts of all prime movers, heat recovery steam generators, boilers, electric generators, and condensers (as applicable), as well as any other primary equipment relevant to the cogeneration process.
gene			Any average annual values required to be reported in lines 10b, 12a, 13a, 13b, 13d, 13f, 14a, 15b, 15d and/or 15f must be computed over the anticipated hours of operation.
General Cogeneration			Diagram must specify all fuel inputs by fuel type and average annual rate in Btu/h. Fuel for supplementary firing should be specified separately and clearly labeled. All specifications of fuel inputs should use lower heating values.
ene			Diagram must specify average gross electric output in kW or MW for each generator.
ğ			Diagram must specify average mechanical output (that is, any mechanical energy taken off of the shaft of the prime movers for purposes not directly related to electric power generation) in horsepower, if any. Typically, a cogeneration facility has no mechanical output.
			At each point for which working fluid flow conditions are required to be specified (see below), such flow condition data must include mass flow rate (in lb/h or kg/s), temperature (in °F, R, °C or K), absolute pressure (in psia or kPa) and enthalpy (in Btu/lb or kJ/kg). Exception: For systems where the working fluid is <i>liquid only</i> (no vapor at any point in the cycle) and where the type of liquid and specific heat of that liquid are clearly indicated on the diagram or in the Miscellaneous section starting on page 24, only mass flow rate and temperature (not pressure and enthalpy) need be specified. For reference, specific heat at standard conditions for pure liquid water is approximately 1.002 Btu/ (lb*R) or 4.195 kJ/(kg*K).
			Diagram must specify working fluid flow conditions at input to and output from each steam turbine or other expansion turbine or back-pressure turbine.
			Diagram must specify working fluid flow conditions at delivery to and return from each thermal application.
			Diagram must specify working fluid flow conditions at make-up water inputs.

the next page at line 11g.

EPAct 2005 Requirements for Fundamental Use of Energy Output from Cogeneration Facilities

FERC Fo	rm 556 Page 17 - Cogeneration Facilities	
	EPAct 2005 cogeneration facilities: The Energy Policy Act of 2005 (EPAct 2005) established a new section 210(n) of the Public Utility Regulatory Policies Act of 1978 (PURPA), 16 USC 824a-3(n), with additional requirements for any qualifying cogeneration facility that (1) is seeking to sell electric energy pursuant to section 210 of PURPA and (2) was either not a cogeneration facility on August 8, 2005, or had not filed a self-certification or application for Commission certification of QF status on or before February 1, 2006. These requirements were implemented by the Commission in 18 C.F.R. § 292.205(d). Complete the lines below, carefully following the instructions, to demonstrate whether these additional requirements apply to your cogeneration facility and, if so, whether your facility complies with such requirements.	
	11a Was your facility operating as a qualifying cogeneration facility on or before August 8, 2005? Yes No	i
	11b Was the initial filing seeking certification of your facility (whether a notice of self-certification or an application for Commission certification) filed on or before February 1, 2006? Yes No	i
S	If the answer to either line 11a or 11b is Yes, then continue at line 11c below. Otherwise, if the answers to both lines 11a and 11b are No, skip to line 11e below.	
acilities	11c With respect to the design and operation of the facility, have any changes been implemented on or after February 2, 2006 that affect general plant operation, affect use of thermal output, and/or increase net power production capacity from the plant's capacity on February 1, 2006?	i
η	Yes (continue at line 11d below)	
of Energy Output from Cogeneration Facilities	No. Your facility is not subject to the requirements of 18 C.F.R. § 292.205(d) at this time. However, it may be subject to to these requirements in the future if changes are made to the facility. At such time, the applicant would need to recertify the facility to determine eligibility. Skip lines 11d through 11j.	
	11d Does the applicant contend that the changes identified in line 11c are not so significant as to make the facility a "new" cogeneration facility that would be subject to the 18 C.F.R. § 292.205(d) cogeneration requirements?	i
	Yes. Provide in the Miscellaneous section starting on page 24 a description of any relevant changes made to the facility (including the purpose of the changes) and a discussion of why the facility should not be considered a "new" cogeneration facility in light of these changes. Skip lines 11e through 11j.	
	No. Applicant stipulates to the fact that it is a "new" cogeneration facility (for purposes of determining the applicability of the requirements of 18 C.F.R. § 292.205(d)) by virtue of modifications to the facility that were initiated on or after February 2, 2006. Continue below at line 11e.	
0	11e Will electric energy from the facility be sold pursuant to section 210 of PURPA?	i
nerg	Yes. The facility is an EPAct 2005 cogeneration facility. You must demonstrate compliance with 18 C.F.R. § 292.205(d)(2) by continuing at line 11f below.	
of Er	No. Applicant certifies that energy will <i>not</i> be sold pursuant to section 210 of PURPA. Applicant also certifies its understanding that it must recertify its facility in order to determine compliance with the requirements of 18 C.F.R. § 292.205(d) <i>before</i> selling energy pursuant to section 210 of PURPA in the future. Skip lines 11f through 11j.	
	11f Is the net power production capacity of your cogeneration facility, as indicated in line 7g above, less than or equal to 5,000 kW?	i
	Yes, the net power production capacity is less than or equal to 5,000 kW. 18 C.F.R. § 292.205(d)(4) provides a rebuttable presumption that cogeneration facilities of 5,000 kW and smaller capacity comply with the requirements for fundamental use of the facility's energy output in 18 C.F.R. § 292.205(d)(2). Applicant certifies its understanding that, should the power production capacity of the facility increase above 5,000 kW, then the facility must be recertified to (among other things) demonstrate compliance with 18 C.F.R. § 292.205(d)(2). Skip lines 11g through 11j.	
	No, the net power production capacity is greater than 5,000 kW. Demonstrate compliance with the	

requirements for fundamental use of the facility's energy output in 18 C.F.R. § 292.205(d)(2) by continuing on

Page 18 - Cogeneration Facilities

Lines 11g through 11k below guide the applicant through the process of demonstrating compliance with the requirements for "fundamental use" of the facility's energy output. 18 C.F.R. § 292.205(d)(2). Only respond to the lines on this page if the instructions on the previous page direct you to do so. Otherwise, skip this page.

18 C.F.R. § 292.205(d)(2) requires that the electrical, thermal, chemical and mechanical output of an EPAct 2005 cogeneration facility is used fundamentally for industrial, commercial, residential or institutional purposes and is not intended fundamentally for sale to an electric utility, taking into account technological, efficiency, economic, and variable thermal energy requirements, as well as state laws applicable to sales of electric energy from a qualifying facility to its host facility. If you were directed on the previous page to respond to the items on this page, then your facility is an EPAct 2005 cogeneration facility that is subject to this "fundamental use" requirement.

The Commission's regulations provide a two-pronged approach to demonstrating compliance with the requirements for fundamental use of the facility's energy output. First, the Commission has established in 18 C.F.R. § 292.205(d)(3) a "fundamental use test" that can be used to demonstrate compliance with 18 C.F.R. § 292.205(d)(2). Under the fundamental use test, a facility is considered to comply with 18 C.F.R. § 292.205(d)(2) if at least 50 percent of the facility's total annual energy output (including electrical, thermal, chemical and mechanical energy output) is used for industrial, commercial, residential or institutional purposes.

Second, an applicant for a facility that does not pass the fundamental use test may provide a narrative explanation of and support for its contention that the facility nonetheless meets the requirement that the electrical, thermal, chemical and mechanical output of an EPAct 2005 cogeneration facility is used fundamentally for industrial, commercial, residential or institutional purposes and is not intended fundamentally for sale to an electric utility, taking into account technological, efficiency, economic, and variable thermal energy requirements, as well as state laws applicable to sales of electric energy from a qualifying facility to its host facility.

Complete lines 11g through 11j below to determine compliance with the fundamental use test in 18 C.F.R. § 292.205(d)(3). Complete lines 11g through 11j even if you do not intend to rely upon the fundamental use test to demonstrate compliance with 18 C.F.R. § 292.205(d)(2).

11g Amount of electrical, thermal, chemical and mechanical energy output (net of internal generation plant losses and parasitic loads) expected to be used annually for industrial, commercial, residential or institutional purposes and not sold to an electric utility

11h Total amount of electrical, thermal, chemical and mechanical energy expected to be sold to an electric utility

MWh

11i Percentage of total annual energy output expected to be used for industrial, commercial, residential or institutional purposes and not sold to a utility

= 100 * 11g /(11g + 11h)

4

11j Is the response in line 11i greater than or equal to 50 percent?

Yes. Your facility complies with 18 C.F.R. § 292.205(d)(2) by virtue of passing the fundamental use test provided in 18 C.F.R. § 292.205(d)(3). Applicant certifies its understanding that, if it is to rely upon passing the fundamental use test as a basis for complying with 18 C.F.R. § 292.205(d)(2), then the facility must comply with the fundamental use test both in the 12-month period beginning with the date the facility first produces electric energy, and in all subsequent calendar years.

No. Your facility does not pass the fundamental use test. Instead, you must provide in the Miscellaneous section starting on page 24 a narrative explanation of and support for why your facility meets the requirement that the electrical, thermal, chemical and mechanical output of an EPAct 2005 cogeneration facility is used fundamentally for industrial, commercial, residential or institutional purposes and is not intended fundamentally for sale to an electric utility, taking into account technological, efficiency, economic, and variable thermal energy requirements, as well as state laws applicable to sales of electric energy from a QF to its host facility. Applicants providing a narrative explanation of why their facility should be found to comply with 18 C.F.R. § 292.205(d)(2) in spite of non-compliance with the fundamental use test may want to review paragraphs 47 through 61 of Order No. 671 (accessible from the Commission's QF website at www.ferc.gov/QF), which provide discussion of the facts and circumstances that may support their explanation. Applicant should also note that the percentage reported above will establish the standard that that facility must comply with, both for the 12-month period beginning with the date the facility first produces electric energy, and in all subsequent calendar years. See Order No. 671 at paragraph 51. As such, the applicant should make sure that it reports appropriate values on lines 11g and 11h above to serve as the relevant annual standard, taking into account expected variations in production conditions.

Information Required for Topping-Cycle Cogeneration Facility

If you indicated in line 10a that your facility represents topping-cycle cogeneration technology, then you must respond to the items on pages 19 and 20. Otherwise, skip pages 19 and 20.

The thermal energy output of a topping-cycle cogeneration facility is the net energy made available to an industrial or commercial process or used in a heating or cooling application. Pursuant to sections 292.202(c), (d) and (h) of the Commission's regulations (18 C.F.R. §§ 292.202(c), (d) and (h)), the thermal energy output of a qualifying toppingcycle cogeneration facility must be useful. In connection with this requirement, describe the thermal output of the topping-cycle cogeneration facility by responding to lines 12a and 12b below. 12a Identify and describe each thermal host, and specify the annual average rate of thermal output made available to each host for each use. For hosts with multiple uses of thermal output, provide the data for each use in separate rows. Average annual rate of thermal output attributable to use (net of Name of entity (thermal host) Thermal host's relationship to facility; heat contained in process taking thermal output Thermal host's use of thermal output return or make-up water) Select thermal host's relationship to facility 1) Select thermal host's use of thermal output Btu/h Select thermal host's relationship to facility 2) Select thermal host's use of thermal output Btu/h Select thermal host's relationship to facility 3) Select thermal host's use of thermal output Btu/h Select thermal host's relationship to facility 4) Select thermal host's use of thermal output Btu/h Select thermal host's relationship to facility 5) Select thermal host's use of thermal output Btu/h Select thermal host's relationship to facility Select thermal host's use of thermal output Btu/h Check here and continue in the Miscellaneous section starting on page 24 if additional space is needed 12b Demonstration of usefulness of thermal output: At a minimum, provide a brief description of each use of the thermal output identified above. In some cases, this brief description is sufficient to demonstrate usefulness, However, if your facility's use of thermal output is not common, and/or if the usefulness of such thermal output is not reasonably clear, then you must provide additional details as necessary to demonstrate usefulness. Your application may be rejected and/or additional information may be required if an insufficient showing of usefulness is made. (Exception: If you have previously received a Commission certification approving a specific use of thermal

output related to the instant facility, then you need only provide a brief description of that use and a reference by date and docket number to the order certifying your facility with the indicated use. Such exemption may not be used if any change creates a material deviation from the previously authorized use.) If additional space is needed,

continue in the Miscellaneous section starting on page 24.

Usefulness of Topping-Cycle Thermal Output

FERC Form 556 Page 20 - Topping	-Cycle Cogeneration Facilities
Applicants for facilities representing topping-cycle technology must demonstrate comcycle operating standard and, if applicable, efficiency standard. Section 292.205(a)(1) regulations (18 C.F.R. § 292.205(a)(1)) establishes the operating standard for topping-cycle useful thermal energy output must be no less than 5 percent of the total energy of (18 C.F.R. § 292.205(a)(2)) establishes the efficiency standard for topping-cycle cogene installation commenced on or after March 13, 1980: the useful power output of the fact thermal energy output must (A) be no less than 42.5 percent of the total energy input facility; and (B) if the useful thermal energy output is less than 15 percent of the total ebe no less than 45 percent of the total energy input of natural gas and oil to the facility compliance with the topping-cycle operating and/or efficiency standards, or to demor exempt from the efficiency standard based on the date that installation commenced, it is also below.	of the Commission's ycle cogeneration facilities: utput. Section 292.205(a)(2) ration facilities for which cility plus one-half the useful of natural gas and oil to the energy output of the facility, v. To demonstrate that your facility is
If you indicated in line 10a that your facility represents <i>both</i> topping-cycle and bottom technology, then respond to lines 13a through 13l below considering only the energy attributable to the topping-cycle portion of your facility. Your mass and heat balance which mass and energy flow values and system components are for which portion (top cogeneration system.	inputs and outputs diagram must make clear
13a Indicate the annual average rate of useful thermal energy output made available to the host(s), net of any heat contained in condensate return or make-up water	Btu/h
C 13b Indicate the annual average rate of net electrical energy output	kW
2 to convert from kW to Btu/h	O Btu/h
13b Indicate the annual average rate of net electrical energy output 13c Multiply line 13b by 3,412 to convert from kW to Btu/h 13d Indicate the annual average rate of mechanical energy output taken directly off of the shaft of a prime mover for purposes not directly related to power production (this value is usually zero) 13e Multiply line 13d by 2,544 to convert from hp to Btu/h 13f Indicate the annual average rate of energy input from natural gas and oil 13g Topping-cycle operating value = 100 * 13a / (13a + 13c + 13e) 13h Topping-cycle efficiency value = 100 * (0.5*13a + 13c + 13e) / 13f	hp
13e Multiply line 13d by 2,544 to convert from hp to Btu/h	0 Btu/h
13f Indicate the annual average rate of energy input from natural gas and oil	Btu/h
13g Topping-cycle operating value = 100 * 13a / (13a + 13c + 13e)	
13h Topping-cycle efficiency value = 100 * (0.5*13a + 13c + 13e) / 13f	0 %
13i Compliance with operating standard: Is the operating value shown in line 13g gre	
Yes (complies with operating standard) No (does not comply wi	ith operating standard)
13j Did installation of the facility in its current form commence on or after March 13, 1	- 18 - 9 (CT C C C C C C C C C C C C C C C C C C

compliance with the efficiency requirement by responding to line 13k or 13l, as applicable, below. No. Your facility is exempt from the efficiency standard. Skip lines 13k and 13l.

13k Compliance with efficiency standard (for low operating value): If the operating value shown in line 13g is less than 15%, then indicate below whether the efficiency value shown in line 13h greater than or equal to 45%:


Yes (complies with efficiency standard) No (does not comply with efficiency standard)

13I Compliance with efficiency standard (for high operating value): If the operating value shown in line 13g is greater than or equal to 15%, then indicate below whether the efficiency value shown in line 13h is greater than or equal to 42.5%:

Yes (complies with efficiency standard) No (does not comply with efficiency standard)

Information Required for Bottoming-Cycle Cogeneration Facility

If you indicated in line 10a that your facility represents bottoming-cycle cogeneration technology, then you must respond to the items on pages 21 and 22. Otherwise, skip pages 21 and 22.





Page 22 - Bottoming-Cycle Cogeneration Facilities

Applicants for facilities representing bottoming-cycle technology and for which installation commenced on or after March 13, 1990 must demonstrate compliance with the bottoming-cycle efficiency standards. Section 292.205(b) of the Commission's regulations (18 C.F.R. § 292.205(b)) establishes the efficiency standard for bottoming-cycle cogeneration facilities: the useful power output of the facility must be no less than 45 percent of the energy input of natural gas and oil for supplementary firing. To demonstrate compliance with the bottoming-cycle efficiency standard (if applicable), or to demonstrate that your facility is exempt from this standard based on the date that installation of the facility began, respond to lines 15a through 15h below. If you indicated in line 10a that your facility represents both topping-cycle and bottoming-cycle cogeneration technology, then respond to lines 15a through 15h below considering only the energy inputs and outputs attributable to the bottoming-cycle portion of your facility. Your mass and heat balance diagram must make clear **Bottoming-Cycle Operating and** which mass and energy flow values and system components are for which portion of the cogeneration system **Efficiency Value Calculation** (topping or bottoming). 15a Did installation of the facility in its current form commence on or after March 13, 1980? Yes. Your facility is subject to the efficiency requirement of 18 C.F.R. § 292.205(b). Demonstrate compliance with the efficiency requirement by responding to lines 15b through 15h below. No. Your facility is exempt from the efficiency standard. Skip the rest of page 22. 15b Indicate the annual average rate of net electrical energy output kW 15c Multiply line 15b by 3,412 to convert from kW to Btu/h Btu/h 15d Indicate the annual average rate of mechanical energy output taken directly off of the shaft of a prime mover for purposes not directly related to power production (this value is usually zero) hp 15e Multiply line 15d by 2,544 to convert from hp to Btu/h 0 Btu/h 15f Indicate the annual average rate of supplementary energy input from natural gas Btu/h 15g Bottoming-cycle efficiency value = 100 * (15c + 15e) / 15f 15h Compliance with efficiency standard: Indicate below whether the efficiency value shown in line 15g is greater than or equal to 45%: Yes (complies with efficiency standard) No (does not comply with efficiency standard)

FERC Form 556 Page 23 - All Facilities

Certificate of Completeness, Accuracy and Authority

Applicant must certify compliance with and understanding of filing requirements by checking next to each item below and

signing at the bottom of this section. Forms with incomplete Certificates of Completeness, Accuracy and Authority will be rejected by the Secretary of the Commission.							
Signer identified below certifies the following: (check all items and applicable subitems)							
He or she has read the filing, including any information contained in any attached documents, such as cogeneration mass and heat balance diagrams, and any information contained in the Miscellaneous section starting on page 24, and knows its contents.							
	He or she has provided all of the required information for certification, and the provided information is true as stated, to the best of his or her knowledge and belief.						
	He or she possess full power and authority to sign the filing; as required by Rule 2005(a)(3) of the Commission's Rules of Practice and Procedure (18 C.F.R. § 385.2005(a)(3)), he or she is one of the following: (check one)						
The person on whose behalf t	the filing is made						
An officer of the corporation,	trust, association, or other organized group on beha	alf of which the filing is made					
An officer, agent, or employe filing is made	of the governmental authority, agency, or instrume	ntality on behalf of which the					
	practice before the Commission under Rule 2101 of F.R. § 385.2101) and who possesses authority to sign						
He or she has reviewed all automatic Miscellaneous section starting on page	calculations and agrees with their results, unless oth	nerwise noted in the					
interconnect and transact (see lines 4	Form 556 and all attachments to the utilities with w a through 4d), as well as to the regulatory authoritie the Required Notice to Public Utilities and State Reg	es of the states in which the					
Procedure (18 C.F.R. § 385.2005(c)) provide	ture date below. Rule 2005(c) of the Commission's les that persons filing their documents electronically led documents. A person filing this document elected below.	may use typed characters					
Your Signature	Your address	Date					
Audit Notes							
Commission Staff Use Only:							

FERC Form 556 Page 24 - All Facilities

Miscellaneous

Use this space to provide any information for which there was not sufficient space in the previous sections of the form to provide. For each such item of information *clearly identify the line number that the information belongs to*. You may also use this space to provide any additional information you believe is relevant to the certification of your facility.

Your response below is not limited to one page. Additional page(s) will automatically be inserted into this form if the length of your response exceeds the space on this page. Use as many pages as you require.

FERC Form 556	Page 25 - All Facilities
Miscellaneous (continued)	

UNITED STATES OF AMERICA FEDERAL ENERGY REGULATORY COMMISSION

Qualifying Facility Rates and Requirements Implementation Issues Under the Public Utility Regulatory Policies Act of 1978

Docket Nos. RM19-15-000

AD16-16-000

(Issued July 16, 2020)

GLICK, Commissioner, dissenting in part:

- 1. I dissent in part from today's final rule (Final Rule¹) because it effectively guts the Commission's implementation of the Public Utility Regulatory Policies Act (PURPA).² The Commission's basic responsibilities under PURPA are three-fold: (1) to encourage the development of qualifying facilities (QFs); (2) to prevent discrimination against QFs by incumbent utilities; and (3) to ensure that the resulting rates paid by electricity customers remain just and reasonable, in the public interest, and do not exceed the incremental costs to the utility of alternative energy.³ I do not believe that today's Final Rule satisfies those responsibilities. Instead, the Final Rule raises as many questions as it answers, not least of which is the long-term legal viability of an approach that does so little to encourage QF development.
- 2. Although I have concerns about many of the individual changes imposed by the Final Rule, I remain, on a broader level, dismayed that the Commission is attempting to accomplish via administrative fiat what Congress has repeatedly declined to do via legislation. I am especially disappointed because Congress expressly provided the

¹ Qualifying Facility Rates and Requirements Implementation Issues Under the Public Utility Regulatory Policies Act of 1978, Order No. 872, 172 FERC ¶ 61,041 (2020) (Final Rule).

² Pub. L. No. 95-617, 92 Stat. 3117 (1978).

³ See 16 U.S.C. § 824a-3(a)-(b) (2018).

⁴ Notwithstanding those concerns, I support certain aspects of this Final Rule. First and foremost, I agree with the update to the "one-mile" rule, which prior to today provided an irrebuttable presumption that resources located more than one mile apart are separate QFs. In addition, I support requiring that QFs demonstrate commercial viability before securing a legally enforceable obligation with the relevant utility. Finally, I also support the revision to allow stakeholders to protest a QF's self-certification.

Commission with a different avenue for "modernizing" our administration of PURPA. The Energy Policy Act of 2005 gave the Commission the authority to excuse utilities from their obligations under PURPA where QFs have non-discriminatory access to competitive wholesale markets.⁵ Had we pursued reforms based on those provisions, rather than gutting our longstanding regulations, I believe we could have reached a durable, consensus solution that would ultimately have done more for all interested parties, even those that may celebrate the immediate effects of this Final Rule.

I. PURPA's Continuing Relevance Is an Issue for Congress to Decide

- 3. This proceeding began with a bang. My colleagues championed the proposed rule as a "truly significant" action that would fundamentally overhaul the Commission's implementation of PURPA.⁶ And so it was. The NOPR proposed to alter almost every significant aspect of the Commission's PURPA regulations, thereby transforming the foundation on which the Commission had carried out its statutory responsibility to "encourage" the development of QFs.
- 4. I dissented from the NOPR in large part because I believe that it is not the Commission's role to sit in judgment of a duly enacted statute and determine whether it has outlived its usefulness. As I explained, "almost from the moment PURPA was passed, Congress began to hear many of the arguments being used today to justify scaling the law back." Congress, however, has seen fit to significantly amend PURPA only once in its more-than-forty-year lifespan. As part of the Energy Policy Act of 2005, Congress amended PURPA, leaving in place the law's basic framework, while adding a series of provisions that allowed the Commission to excuse utilities from its requirements in regions of the country with sufficiently competitive wholesale energy markets. And while Congress considered numerous proposals to further reform the law, it never saw fit to act on them. Against that background, I could not support my colleagues' willingness to "remove[] an important debate from the halls of Congress and isolate[] it within the Commission." Whatever your position on PURPA—and I recognize views vary

⁵ Pub. L. No. 109-58, § 1253, 119 Stat. 594 (2005).

⁶ Sept. 2019 Commission Meeting Tr. at 8.

⁷ Qualifying Facility Rates and Requirements Implementation Issues Under the Public Utility Regulatory Policies Act of 1978, Notice of Proposed Rulemaking, 168 FERC ¶ 61,184 (2019) (NOPR) (Glick, Comm'r, dissenting in part at P 3).

⁸ Pub. L. No. 109-58, § 1253, 119 Stat. 594 (2005).

⁹ See Solar Energy Industries Association (SEIA) Comments at 11.

¹⁰ NOPR, 168 FERC ¶ 61,184 (Glick, Comm'r, dissenting in part at P 4).

widely—"what should concern all of us is that resolving these sorts of questions by regulatory edict rather than congressional legislation is neither a durable nor desirable approach for developing energy policy."¹¹

- 5. Today's Final Rule retreats from much of the original rationale used to support the NOPR, but the effect is the same: The Commission is administratively gutting PURPA. Make no mistake, although the Commission has dropped much of the NOPR preamble's opening screed against PURPA's continuing relevance, this Final Rule is a full-throated endorsement of the conclusion that PURPA has outlived its usefulness. And while walking back the argument that PURPA is antiquated may reduce the risk that this Final Rule is overturned on appeal, that does not change the fact that today's Final Rule usurps what should be Congress's proper role.
- 6. Throughout this proceeding, the Commission has been quick to point to Congress's directive to from time to time amend our regulations implementing PURPA.¹² This Final Rule, however, is a wholesale overhaul of the Commission's PURPA regulations that reflects a deep skepticism of the need for the law we are charged with implementing. I doubt that is what Congress had in mind when it gave us responsibility for periodically updating our implementing regulations.

II. The Commission's Proposed Reforms Are Inconsistent with Our Statutory Mandate

7. PURPA directs the Commission to adopt such regulations as are "necessary to encourage" QFs, ¹³ including by establishing rates for sales by QFs that are just and reasonable and by ensuring that such rates "shall not discriminate" against QFs. ¹⁴ As explained below, many of the changes adopted by the Commission in the Final Rule fail to meet that standard. In addition, many of the reforms are unsupported—or, in many cases, contradicted—by the evidence in the record. ¹⁵ Accordingly, I believe today's Final Rule is not just poor public policy, but also arbitrary and capricious agency action.

¹¹ *Id*

 $^{^{12}}$ Final Rule, 172 FERC \P 61,041 at PP 24, 48, 54, 67, 296, 628; NOPR, 168 FERC \P 61,184 at PP 4, 16, 29, 155.

¹³ A QF is a cogeneration facility or a small power production facility. *See* 18 C.F.R. § 292.101(b)(1) (2019).

¹⁴ 16 U.S.C. § 824a–3(a)-(b).

¹⁵ Genuine Parts Co. v. EPA, 890 F.3d 304, 312 (D.C. Cir. 2018) ("[A]n agency cannot ignore evidence that undercuts its judgment; and it may not minimize such evidence without adequate explanation.") (citations omitted); *id*. ("Conclusory

A. Avoided Cost

8. The Final Rule adopts two fundamental changes to how QF rates are determined. First, and most importantly, it eliminates the requirement that a utility must afford a QF the option to enter a contract at a rate for energy that is either fixed for the duration of the contract or determined at the outset—e.g., based on a forward curve reflecting estimated prices over the term of the contract. Second, it presumptively allows states to set the rate for as-available energy at the relevant locational marginal price (LMP) or a similarly "competitive market price." The record in this proceeding does not support either of those changes.

i. Elimination of Fixed Energy Rate

- 9. Prior to today's Final Rule, a QF generally had two options for selling its output to a utility. Under the first option, the QF could sell its energy on an as-available basis and receive an avoided cost rate calculated at the time of delivery. This is generally known as the as-available option. Under the second option, a QF could enter into a fixed-duration contract at an avoided cost rate that was fixed either at the time the QF established a legally enforceable obligation (LEO) or at the time of delivery. This is generally known as the contract option. The ability to choose between both types of sale options played an important role in fostering the development of a variety of QFs. For example, the asavailable option provided a way for QFs whose principal business was not generating electricity, such as industrial cogeneration facilities, to monetize their excess electricity generation. The contract option, by contrast, provided QFs who were principally in the business of generating electricity, such as small renewable electricity generators, a stable option that would allow them to secure financing. Together, the presence of these two options allowed the Commission to satisfy its statutory mandate to encourage the development of OFs and ensured that the rates they received were non-discriminatory.
- 10. The Final Rule eliminates the requirement that states provide a contract option that includes a fixed energy rate. 18 Prior to this proceeding, the Commission recognized time

explanations for matters involving a central factual dispute where there is considerable evidence in conflict do not suffice to meet the deferential standards of our review." (quoting *Int'l Union, United Mine Workers v. Mine Safety & Health Admin.*, 626 F.3d 84, 94 (D.C. Cir. 2010)).

¹⁶ Final Rule, 172 FERC ¶ 61,041 at P 253.

¹⁷ *Id.* PP 151, 189, 211.

¹⁸ *Id.* P 253.

and again that fixed-price contracts play an essential role in the financing of QF facilities, making them a necessary element of any effort to encourage QF development, at least in certain regions of the country. ¹⁹ In addition, fixed-price contracts have helped prevent discrimination against QFs by ensuring that they are not structurally disadvantaged relative to vertically integrated utilities that are guaranteed to recover the costs of their prudently incurred investments through retail rates. ²⁰

1. 20 See, e.g., ELCON Comments at 21-22 ("More variable avoided cost rates will result in unintended consequences that result in less competitive conditions and may leave consumers worse off, as utility self-builds do not face the same market risk exposure. Pushing more market risk to QFs while utility assets remain insulated from markets creates an investment risk asymmetry. This puts QFs at a competitive disadvantage"); South Carolina Solar Business Association Comments at 8 ("[A]s-available rates for QFs in vertically-integrated states therefore discriminate against QFs by requiring QFs to enter into contracts at substantially and unjustifiably different terms than incumbent utilities."); Southern Environmental Law Center Supplement Comments, Docket No. AD16-16-000, at 6-8 (Oct. 17, 2018) (explaining that vertically integrated utilities in Indiana, Alabama, Virginia and Tennessee only offer short-term rates to QFs);

Implementing Section 210 of the Public Utility Regulatory Policies Act of 1978, Order No. 69, FERC Stats. & Regs. ¶ 30,128, at 30,880, order on reh'g sub nom. Order No. 69-A, FERC Stats. & Regs. ¶ 30,160 (1980), aff'd in part vacated in part, Am. Elec. Power Serv. Corp. v. FERC, 675 F.2d 1226 (D.C. Cir. 1982), rev'd in part sub nom. Am. Paper Inst. v. Am. Elec. Power Serv. Corp., 461 U.S. 402 (1983). (justifying the rule on the basis of "the need for certainty with regard to return on investment in new technologies"); NOPR, 168 FERC ¶ 61,184 at P 63 ("The Commission's justification for allowing QFs to fix their rate at the time of the LEO for the entire term of a contract was that fixing the rate provides certainty necessary for the QF to obtain financing."); Windham Solar LLC, 157 FERC ¶ 61,134, at P 8 (2016).

11. If anything, the record before us confirms the continuing importance of fixed-price contracts. Numerous entities with experience financing and developing QFs explain that a fixed revenue stream of some sort is necessary to obtain the financing needed to develop a new QF.²¹ The fixed revenue stream is particularly important because QFs are overwhelmingly developed outside of the organized markets, meaning that developers cannot necessarily obtain hedging contracts to create the revenue predictability needed to obtain financing.²² And that is why the Final Rule's parade of statistics about the growth of renewables misses the point.²³ It is true that, primarily in organized markets, independently developed renewables are able to develop without the entitlement to a fixed-price contract for energy from the relevant utility.²⁴ But the growth of renewables

sPower Comments at 13; *see also* Statement of Travis Kavulla, Docket No. AD16-16-000, at 2 (June 29, 2016).

²¹ See, e.g., SEIA Comments at 29; North Carolina Attorney General's Office Comments at 5; Con Ed Development Comments at 3; South Carolina Solar Business Association Comments at 6; sPower Comments at 11; Resources for the Future Comments at 6-7.

²² See, e.g., SEIA Comments at 29-30 ("As both Mr. Shem and Mr. McConnell explain, financial hedge products are not available outside of ISO/RTO markets."); Resources for the Future Comments at 6-7 ("[W]hile hedge products do support wind and solar project financing, they would not be suited for most QF projects. To hedge energy prices, wind projects have used three products: bank hedges, synthetic power purchase agreements (synthetic PPAs), and proxy revenue swaps. . . . From US project data for 2017 and 2018, the smallest wind project securing such a hedge was 78 MW, and most projects were well over 100 MW. Additionally, as hedges rely on wholesale market access and liquid electricity trading, all of the projects were in ISO regions.") (emphasis added).

²³ Harvard Electricity Law Comments at 22 (referring to a similar statistical parade in the NOPR and observing that "[a]ll [the Commission] can actually conclude from this loosely connected array of facts, data, and speculation is that some non-QF generators are developed with variable-rate energy contracts. That unremarkable conclusion has no bearing on whether repeal will discourage QF development by 'materially affect[ing] the ability of QFs to obtain financing." (citing NOPR, 168 FERC ¶ 61,184 at P 69)); SEIA Comments at 30.

²⁴ See Final Rule, 172 FERC ¶ 61,041 at P 340 ("EIA data demonstrates that net generation of energy by non-utility owned renewable resources in the United States grew by almost 700% between 2005 and 2018."). Although independent power producers, renewable or otherwise, within the RTO/ISO markets are not entitled to fixed price

and their financeability in organized markets tells us almost nothing about what is required to sufficiently encourage QFs outside those markets.²⁵

12. It would be one thing to eliminate the requirement to provide a fixed-price option for energy rates for QFs that are entitled to a fixed price for capacity. Although reasonable minds might disagree about whether a fixed price for capacity alone is sufficient encouragement, combining one with a variable price for energy would provide at least some guaranteed revenue stream with which to finance new development. Indeed, much of the Commission's justification for eliminating the fixed-price contract option for energy rests on the availability of a fixed-price contract option for capacity. Commission precedent, however, permits utilities to offer a capacity rate of zero to QFs

contracts for energy as a matter of law, they generally do rely on alternative tools, such as commodity hedges, to lock-in energy revenue streams. *See, e.g.*, EEI Comments at 36; sPower Comments at 12.

²⁵ In the logical leap of the year, the Commission notes that in some areas of the country, unspecified resources are developed with a fixed-price contract for capacity and a variable price for energy and, separately, that renewables have grown nationwide more than seven-fold between 2005 and 2018. Final Rule, 172 FERC ¶ 61,041 at P 340. From those disparate observations, the Commission concludes that "renewable resources are able to acquire financing even without the right to require long-term fixed energy rates." *Id.* But nothing in the record suggests that that phenomenal growth in renewables was at all the result of that bifurcated contract structure. That, it should be clear, is not reasoned decisionmaking. *Cf. Nat'l Ass'n of Recycling Indus., Inc. v. Fed. Mar. Comm'n*, 658 F.2d 816, 820 n.10 (D.C. Cir. 1980) ("We do not want, after all, blithely to compare apples and oranges. Likewise, an agency should also avoid unavailing comparisons of nonsubstitutes."); *see also* Commissioner Slaughter Comments at 4 (noting the "widespread geographic differentiation" in renewable energy progress and "barriers to independent renewable energy-based power producers").

²⁶ See, e.g., SEIA Comments at 29 ("While securing financing based on an As-Available Energy rate and a fixed capacity rate may be a rare possibility in a few submarkets across the country, as Mr. Shem explains, it certainly is not the case in any state that does not participate in an ISO/RTO market.").

²⁷ See Final Rule, 172 FERC ¶ 61,041 at P 36 ("This assertion that the Commission has eliminated fixed rates for QFs is not correct. . . . The NOPR thus made clear: under the proposed revisions to § 292.304(d), a QF would continue to be entitled to a contract with avoided *capacity* costs calculated and fixed at the time the LEO is incurred.") (internal quotation marks omitted); *id.* P 237 ("The Commission stated that these fixed capacity and variable energy payments have been sufficient to permit the financing of significant amounts of new capacity in the RTOs and ISOs.").

when the utility does not need incremental capacity.²⁸ That means that, as a result of this Final Rule, QF developers will face the very real prospect of not receiving any fixed revenue stream, whether for energy or capacity, in areas where they also cannot secure hedging products or other mechanisms needed to finance a new QF.²⁹ It is hard for me to understand how the Commission can, with a straight face, claim to be encouraging QF development while at the same time eliminating the conditions necessary to develop QFs in the regions where they are being built.³⁰

- 13. The Commission sidesteps this point in responding that PURPA does not require that QFs be financeable. That is true in a literal sense; nothing in PURPA directs the Commission to ensure that at least some QFs be financeable. But it does require the Commission to encourage their development, which we have previously equated with financeability.³¹ If the Commission is going to abandon that standard, it must then explain why what is left of its regulations provides the requisite encouragement—an explanation that is lacking from this Final Rule, notwithstanding the Commission's repeated assertions to the contrary.
- 14. The Commission also does not sufficiently explain how eliminating the fixed-price contract requirement is consistent with PURPA's requirement that rates "shall not discriminate against" QFs.³² Vertically integrated utilities effectively receive guaranteed

²⁸ See, e.g., id. P 422 (citing to City of Ketchikan, Alaska, 94 FERC ¶ 61,293, at 62,061 (2001)).

²⁹ See, e.g., Resources for the Future Comments at 6; SEIA Comments at 30; Southeast Public Interest Organizations Comments at 12.

³⁰ See Public Interest Organizations Comments at 10-11 ("Obviously, rules that have an effect of *discouraging* QFs cannot be 'necessary to' encouraging them."); see also Massachusetts Attorney General Maura Healey Comments at 6 ("This action may reduce investor confidence and discourage future development. That outcome is a negative one for the Commonwealth and its ratepayers.").

³¹ See, e.g., Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,880 (justifying the rule on the basis of "the need for certainty with regard to return on investment in new technologies"); NOPR, 168 FERC ¶ 61,184 at P 63 ("The Commission's justification for allowing QFs to fix their rate at the time of the LEO for the entire term of a contract was that fixing the rate provides certainty necessary for the QF to obtain financing.").

³² 16 U.S. Code § 824a–3(b)(2). Unlike provisions of the Federal Power Act, PURPA prohibits any discrimination against QFs, not just undue discrimination. *See* ELCON Comments at 21-22; South Carolina Solar Business Alliance Comments at 7-8; sPower Comments at 13.

fixed-price contracts through their rights to recover prudently incurred investments. The equivalent right to receive fixed-price contracts has to date proved an integral element of the Commission's ability to satisfy PURPA's prohibition on discriminatory rates.³³

- 15. And yet this Final Rule fails to explain how eliminating the fixed-price option is consistent with that prohibition or, moreover, how permitting QFs to receive variable contract rates while vertically integrated utilities receive fixed ones is consistent with the Commission's obligation to promote QFs.³⁴ Instead, the Commission notes that, through so-called fuel adjustment clauses, vertically integrated utilities' rates change as the price of fuel changes.³⁵ The idea that those clauses, which ensure that utilities recover a specific variable cost (i.e., their cost of fuel), is the same thing as having your entire revenue exposed to variations in prevailing market conditions is hogwash. The presence of fuel adjustment clauses in no way suggests that vertically integrated utilities are subject to anything remotely close to the level of revenue variation contemplated in this Final Rule.
- 16. Finally, the Commission fails to explain why allegations of QF rates exceeding a utility's actual avoided cost requires us to abandon the Commission's long-held principles regarding certainty and financing.³⁶ As an initial matter, the Commission has recognized that QF rates may exceed actual avoided costs, but, at the same time, recognized that avoided cost rates might also turn out to be lower than the electric utility's avoided costs over the course of the contract. The Commission has reasoned that, "in the long run, 'overestimations' and 'underestimations' of avoided costs will balance out."³⁷ However, when presented with a couple allegations that avoided costs were overestimated,³⁸ the Commission now concludes that that possibility suggests it must abandon the fixed-energy rate contract altogether. The Commission, however, makes no effort to validate these

3.

³³ See supra n.20; Commissioner Slaughter Comments at 4.

³⁴ Public Interest Organizations Comments at 51 ("[L]imiting QFs to contracts providing no price certainty for energy values, while non-QF generation regularly obtains fixed price contracts and utility-owned generation receives guaranteed cost recovery from captive ratepayers, constitutes discrimination.").

^{2. &}lt;sup>35</sup> Final Rule, 172 FERC ¶ 61,041 at P 122.

³⁶ See supra n.19.

³⁷ Order No. 69, FERC Stats. & Regs. ¶ 30,128 at 30,880.

³⁸ Final Rule, 172 FERC ¶ 61,041 at PP 265, 268.

allegations,³⁹ or assess whether the overestimations of avoided cost were, in fact, balanced out.⁴⁰ It is arbitrary and capricious to point to only half the picture in abandoning a forty-year-old principle.

ii. Rebuttable Presumption for Setting Avoided Cost at LMP and Similar Measures

- 17. I also do not support the Commission's decision to treat LMP or other "competitive market prices" as a presumptively reasonable measure of an as-available avoided cost for energy. Liquid price signals can be useful and transparent inputs and ought to be considered in calculating an appropriate avoided-cost figure. But considering those price signals in setting avoided cost is not the same thing as presuming that LMP or similar measures are alone sufficient to establish avoided cost. Many regions of the country—often the same regions where the debates about PURPA are most heated—have not established sufficiently competitive markets. In these regions it is not clear from the record that the prices in, for example, a neighboring RTO, are a representative measure of a utility's avoided cost. In those less competitive markets, it simply does not make sense to presume that LMP or other "competitive market prices" are a representative measure of avoided cost, rather than one of many criteria that should go into that determination. Lavored to the competitive market prices are a representative measure of avoided cost, rather than one of many criteria that should go into that determination.
- 18. For similar reasons, I share the concern of many commenters that short-term or spot prices, such as LMP, may not reflect the long-term marginal energy costs avoided by

³⁹ *Id.* PP 291, 293.

⁴⁰ The Commission is quick to point to "the precipitous decline in natural gas prices" starting in 2008 that may have caused QF contracts fixed prior to that period to underestimate the actual cost of energy. *See, e.g.*, Final Rule, 172 FERC ¶ 61,041 at P 287). However, PURPA has been in place for forty years, and the Commission does not wrestle with the magnitude of potential savings conveyed to consumers from the fixed-price energy contracts that locked-in low rates for consumers during the decades prior when natural gas prices were several times higher. *See* Energy Information Administration Total Energy, tbl. 9.10 (last viewed July 15, 2020), https://www.eia.gov/totalenergy/data/browser/.

⁴¹ Final Rule, 172 FERC ¶ 61,041 at PP 151, 189, 211.

⁴² Congress itself seems to have contemplated that states would not rely solely on spot market prices when establishing avoided cost. H.R. Rep. No. 95-1750, at 7833 (1978) ("In interpreting the term 'incremental cost of alternative energy,' the conferees expect that the Commission and the states may look beyond the cost of alternative sources which are instantaneously available to the utility.").

purchasing utilities, especially outside of organized markets.⁴³ Although the Commission revises the NOPR's *per se* rule to be a rebuttable presumption, it nevertheless plows ahead with the conclusion that LMP, and similar measures, reflect a utility's avoided cost of energy. Where there is good reason to believe that those measures do not actually reflect the long-term value of energy that they are supposed to represent, it makes no sense to put the burden on QFs to prove the point,⁴⁴ rather than leaving the burden with the proponents of using such measures.

19. The Commission's presumptive approval of LMP and similar measures is even more problematic when combined with the decision to allow utilities to eliminate the fixed-price contract option. Following this Final Rule, QFs may be reduced to relying solely on some synthetic and highly variable measure of what spot prices *should* be in a competitive market based on gas prices and heat rates, all while the utilities whose costs the QF is avoiding recovers an effectively guaranteed rate potentially in excess of this representative "competitive market price." I am not persuaded that this approach will satisfy our obligation to encourage QFs and to do so using rates that are non-discriminatory across all regions of the country.

B. Rebuttable Presumption 20 MW to 5 MW

20. Following the Energy Policy Act of 2005, the Commission established a rebuttable presumption that QFs with a capacity greater than 20 MW operating in RTOs and ISOs have non-discriminatory access to competitive markets, eliminating utilities' must-

⁴³ Final Rule, 172 FERC ¶ 61,041 at n.163; Hydro Comments at 11; Southeast Public Interest Organizations Comments at 19; NIPPC, CREA, REC, and OSEIA Comments at 52, 55; Union of Concerned Scientists Comments at 6. Take, for example, the Commission's approval of the Mid-Columbia market hub price as presumptively reflecting a utility's avoided cost for energy. See Final Rule, 172 FERC ¶ 61,041 at PP 180, 189. Notwithstanding explicit support for this approach from the regulated utility industry, the Washington Utilities and Transportation Commission which, when addressing Puget Sound Energy's plan to increase wholesale purchases from the Mid-Columbia market "liquid hub" to 1,600 MW, expressed a concern about the regulated utility's overreliance on such wholesale market pricing and directed them to pursue an alternative plan to eliminate this "excessive risk." That is the exact type of tension conveyed in the record—i.e, that such competitive market prices may not accurately reflect a utility's avoided cost, as approved by regulators. See Washington UTC, Acknowledgment Letter Attachment, Puget Sound Energy's 2017 Electric and Natural Gas Integrated Resource Plan, Wash. UTC Docket Nos. UE-160918, UG-160919 (Revised June 19, 2018); see NIPPC, CREA, REC, and OSEIA Comments at 56.

⁴⁴ Final Rule, 172 FERC ¶ 61,041 at P 152.

purchase obligation from those resources.⁴⁵ The Final Rule reduces the threshold for that presumption from 20 MW to 5 MW. ⁴⁶ That is an improvement over the NOPR, which—without any support whatsoever—proposed to lower that threshold to 1 MW. ⁴⁷ But, even so, the reduced 5 MW threshold is unsupported by the record and inadequately justified in today's Final Rule.

- 21. When it originally established the 20 MW threshold, the Commission pointed to an array of barriers that prevented resources below that level from having truly non-discriminatory access to RTO/ISO markets. Those barriers included complications associated with accessing the transmission system through the distribution system (a common occurrence for such small resources), challenges with reaching distant off-takers, as well as "jurisdictional differences, pancaked delivery rates, and additional administrative procedures" that complicate those resources' ability to participate in those markets on a level playing field. In just the last few years, the Commission has recognized the persistence of those barriers "that gave rise to the rebuttable presumption that smaller QFs lack nondiscriminatory access to markets."
- 22. Nevertheless, the Final Rule abandons the 20 MW threshold based on the conclusory assertion that "it is reasonable to presume that access to RTO/ISO markets has improved" and it is, therefore, "appropriate to update the presumption." No doubt markets have improved. But a borderline-truism about maturing markets does not explain how the barriers arrayed against small resources have dissipated, why it is reasonable to "presume" that the remaining barriers do not inhibit non-discriminatory access, or why 5 MW is an appropriate new threshold for that presumption.

⁴⁵ New PURPA Section 210(m) Regulations Applicable to Small Power Production and Cogeneration Facilities, Order No. 688, 117 FERC ¶ 61,078, at P 72 (2006), order on reh'g, Order No. 688-A, 119 FERC ¶ 61,305 (2007), aff'd sub nom. Am. Forest & Paper Ass'n v. FERC, 550 F.3d 1179 (D.C. Cir. 2008); see 16 U.S.C. § 824a-3(m).

⁴⁶ Final Rule, 172 FERC ¶ 61,041 at P 625.

⁴⁷ NOPR, 168 FERC ¶ 61,184 at P 126.

⁴⁸ Order No. 688-A, 119 FERC ¶ 61,305 at PP 96, 103.

⁴⁹ E.g., N. States Power Co., 151 FERC ¶ 61,110, at P 34 (2015).

⁵⁰ Final Rule, 172 FERC ¶ 61,041 at P 629 ("Over the last 15 years, the RTO/ISO markets have matured, market participants have gained a better understanding of the mechanics of such markets and, as a result, we find that it is reasonable to presume that access to the RTO/ISO markets has improved and that it is appropriate to update the presumption for smaller production facilities.").

- 23. Instead of any such evidence, the Final Rule notes that the Commission uses the 5 MW as a demarcating line for other rules applying to small resources. Specifically, it points to the fact that resources below 5 MW can use a "fast-track" interconnection process, whereas larger ones must use the large generator interconnection procedures.⁵¹ But the fact that the Commission used 5 MW as the cut off in another context hardly shows that it is the right cut off to use in this context.
- 24. Lacking substantial evidence to support the 5 MW threshold, the Commission falls back on a deferential standard of review. But while judicial review of agency policymaking is deferential, it is not toothless. The same cases on which the Commission relies require that, when an agency's policy reversal "rests upon factual findings that contradict those which underlay its prior policy," the agency must "provide a more detailed justification than what would suffice for a new policy created on a blank slate." That is because reasoned decisionmaking requires that, when an agency changes course, it must provide "a reasoned explanation . . . for disregarding facts and circumstances that underlay or were engendered by the prior policy." For the foregoing reasons, the Commission has failed to produce any such explanation, making its change of course arbitrary and capricious.

III. Environmental Review under the National Environmental Policy Act

25. In contrast to the Commission's crowing over the significance of its PURPA overhaul, the Final Rule describes the changes adopted as merely corrective and clarifying in nature when it comes to conducting an environmental review.⁵⁵ In particular, the Commission contends that "the changes adopted in this final rule are required to ensure continued future compliance of the PURPA Regulations with PURPA, based on the

⁵¹ *Id.* P 630.

⁵² *Id.* P 637 (citing *FCC v. Fox Television*, 556 U.S. 502, 515 (2009), for the proposition that an agency "need not demonstrate to a court's satisfaction that the reasons for the new policy are better than the reasons for the old one; it suffices that the new policy is permissible under the statute, that there are good reasons for it, and that the agency *believes* it to be better, which the conscious change of course adequately indicates.").

⁵³ Fox Television, 556 U.S. at 515; Advanced Energy Economy Comments at 6.

⁵⁴ Fox Television, 556 U.S. at 516; Advanced Energy Economy Comments at 6-7.

⁵⁵ Under the National Environmental Policy Act (NEPA), the Commission must consider whether its action associated with rulemakings will have a significant impact on the environment. *See* 42 U.S.C. §§ 4321 *et seq*.

changed circumstances found by the Commission in this final rule."⁵⁶ In other words, because the Commission believes that the changes adopted are necessary to conform with the statute, they are mere corrective changes, which, in turn, qualifies them for the categorical exemption from any environmental review under NEPA, or so the argument goes.

26. But by that logic, any Commission action needed to comply with our various statutory mandates—whether "just and reasonable" or the "public interest"—would be deemed corrective in nature and, therefore, excluded from environmental review. The Commission, however, fails to point to any evidence suggesting that is what the Council on Environmental Quality contemplated when it allowed for categorical exemptions.

IV. The Way to Revise PURPA Is to Create More Competition, Not Less

- 27. It didn't have to be this way. When Congress reformed PURPA in the 2005 Energy Policy Act amendments, it indicated an unmistakable preference for using market competition as the off-ramp for utilities seeking relief from their PURPA obligations.⁵⁷ Those reforms directed the Commission to excuse utilities from those obligations where QFs had non-discriminatory access to RTO/ISO markets or other sufficiently competitive constructs.⁵⁸
- 28. This record contains numerous comments explaining how the Commission could use those amendments as a way to "modernize" PURPA in a manner that both promotes *actual* competition and reflects Congress's unambiguous intent.⁵⁹ For example, in a white paper released prior to the NOPR, the National Association of Regulatory Utility Commissioners (NARUC) urged the Commission to give meaning to the 2005 amendments by establishing criteria by which a vertically integrated utility outside of an RTO or ISO could apply to terminate the must-purchase obligation if it conducts sufficiently competitive solicitations for energy and capacity.⁶⁰ Other groups, including

⁵⁶ Final Rule, 172 FERC ¶ 61,041 at P 722.

⁵⁷ 16 U.S.C. § 824a-3(m).

⁵⁸ See Order No. 688, 117 FERC ¶ 61,078 at P 8.

⁵⁹ See Advanced Energy Economy Comments at 13; Industrial Energy Consumers Comments at 13-14; EPSA Comments at 16.

⁶⁰ National Association of Regulatory Utility Commissioners Supplemental Comments, Docket No. AD16-16-00, Attach. A, at 8 (Oct. 17, 2018); *id.* (proposing the Commission's *Edgar-Allegheny* criteria as a basis for evaluating whether a proposal was adequately competitive).

representatives of QF interests, submitted additional comments on how an approach along those lines might work.⁶¹ Several parties commented on those proposals.⁶²

29. It is a shame that the Commission has elected to administratively gut its long-standing PURPA implementation regime, rather than pursuing reform rooted in PURPA section 210(m), such as the NARUC proposal. Pursuing an option along those lines could have produced a durable, consensus solution to the issues before us. I continue to believe that the way to modernize PURPA is to promote real competition, not to gut the provisions that the Commission has relied on for decades out of frustration that Congress has repeatedly failed to repeal the statute itself.

For these reasons, I respectfully dissent in part.

Richard Glick Commissioner

⁶¹ See, e.g., SEIA Supplemental Comments, Docket No. AD16-16-000 (Aug. 28, 2019).

⁶² See, e.g., Advanced Energy Economy Comments at 12; APPA Comments at 29; Colorado Independent Energy Comments at 7; ELCON Comments at 19; Public Interest Organizations Comments at 90; SEIA Comments at 24; Xcel Comments at 11.

172 FERC ¶ 61,042 UNITED STATES OF AMERICA FEDERAL ENERGY REGULATORY COMMISSION

Before Commissioners: Neil Chatterjee, Chairman;

Richard Glick, Bernard L. McNamee,

and James P. Danly.

New England Ratepayers Association

Docket No. EL20-42-000

ORDER DISMISSING PETITION FOR DECLARATORY ORDER

(Issued July 16, 2020)

1. On April 14, 2020, pursuant to Rule 207 of the Commission's Rules of Practice and Procedure, New England Ratepayers Association (NERA) filed a petition for declaratory order, requesting that the Commission (1) declare that there is exclusive federal jurisdiction over wholesale energy sales from generation sources located on the customer side of the retail meter and (2) order that the rates for such sales be priced in accordance with the Federal Power Act (FPA)² or Public Utility Regulatory Policies Act of 1978 (PURPA),³ as applicable (Petition). As discussed below, we dismiss the Petition.

I. Petition

2. NERA asks the Commission to declare that it has jurisdiction over energy sales from rooftop solar facilities and other distributed generation located on the customer side of the retail meter (1) whenever the output of such generators exceeds the customer's demand or (2) where the energy from such generators is designed to bypass the customer's load and therefore is not used to serve demand behind the customer's meter. NERA argues that, in these circumstances, energy is delivered to the local utility for resale to the utility's retail customers for compensation, making the transactions wholesale sales in interstate commerce, which should be priced at the utility's avoided cost of energy if the sale is made pursuant to PURPA or a just and reasonable wholesale rate if the sale is made pursuant to the FPA.

¹ 18 C.F.R. § 385.207(a)(2) (2019).

² 16 U.S.C. § 824 et seq. (2018).

³ Id. § 824a-3.

⁴ Petition at 6.

NERA states that its Petition concerns "full net metering," which it describes as a 3. practice through which an electricity consumer produces electric energy from a generation source (most often solar panels) that is located on the same side of the retail meter as the customer's load.⁵ NERA states that the generation and load are connected to a bidirectional retail meter that measures the total amount of energy produced and used by the customer. NERA explains that, when the customer consumes more energy than it produces, the interconnected utility supplies the difference, and the meter runs forward to measure the amount of retail service sold to the customer. NERA further explains that, when the customer produces more energy than it consumes, the customer is delivering energy to the interconnected utility, and the meter runs backwards. NERA states that the amount of energy the customer produces is netted, usually on a monthly basis, against the amount of energy the customer consumes. 6 NERA states that, to the extent that the customer consumes more than it produced in the month, it is billed for retail electric service based on the net amount of energy the utility delivered to the customer over the course of the month. NERA adds that this billing process results in the customer being compensated for all of the energy it produced behind the meter, including the energy it delivered to the interconnected utility for resale, at the bundled retail electric rate or, in some cases, at a close proxy thereof.⁷ For purposes of this order, we will refer to this practice as Net Energy Metering.8

⁵ Id. at 2.

⁶ Id. at 3.

⁷ *Id.* (citing N.H. Rev. Stat. § 362-A:9 (2019); *Connecticut Net Metering*, https://www.eversource.com/content/ct-c/about/about-us/doing-business-with-us/builderscontractors/interconnections/connecticut-net-metering; Rhode Island, *Net Metering Provision*, https://ngus.force.com/servlet/servlet.FileDownload?file= 0150W00000ETJ1t; Massachusetts, *Net Metering Guide*, https://www.mass.gov/guides/net-metering-guide#-2.-net-metering-creditcalculation-and-billing).

⁸ NERA notes that some states have adopted variations to Net Energy Metering, such as virtual or community net metering programs, which allow multiple consumers to share billing credits from a common generating facility. *Id.* NERA states that its Petition focuses on the more common form of net metering described above because that was the subject of the Commission's prior rulings. *Id.* However, NERA states that, to the extent these net metering variations result in energy being delivered to the interconnected utility for resale, then the principles set forth in its Petition would apply fully to those net metering variations. *Id.*

- 4. NERA states that Net Energy Metering transactions are currently treated as if they are retail transactions subject to regulation by various states. NERA further states that, in many cases, the energy produced behind the meter that exceeds the customer's demand or is designed to bypass the customer's load is sold to the local utility for resale to the utility's other customers. NERA argues that the sales at issue are wholesale sales, subject to the Commission's jurisdiction, because the energy is sold to the utility's retail load or for resale by an Independent System Operator or Regional Transmission Organization. 11
- 5. NERA argues that the Commission previously erred in disclaiming jurisdiction over most Net Energy Metering sales based upon a theory that the net flow over the retail meter aggregated over a full retail billing cycle determines jurisdiction. NERA asserts that the Commission should not have netted separate services with different cost structures and service characteristics to determine whether a jurisdictional sale occurred. NERA contends that the power flowing over the retail meter to the customer is firm retail requirements service while the power generated behind the retail meter is non-firm energy. NERA also argues that the Commission should not have allowed netting to occur over a full retail billing cycle because the Commission does not permit sellers to net transactions when engaging in simultaneous purchase and sale transactions, even when the simultaneous transactions are for the same service, ¹³ and consistently requires that wholesale sales be measured on an hourly or shorter-term basis. ¹⁴
- 6. NERA argues that the U.S. Court of Appeals for the District of Columbia Circuit (D.C. Circuit) has rejected the Commission's reasoning by holding, in the context of station power, that the Commission cannot determine jurisdiction based on monthly or any other netting of injections into and withdrawals from the electric grid. NERA claims that, in SoCal Edison and Calpine, the court rejected the premise that it is

⁹ Id. at 6.

¹⁰ Id. at 6-7.

¹¹ Id. at 7.

¹² Id. at 11-12 (citing Sun Edison LLC, 129 FERC ¶ 61,146 (2009); MidAmerican Energy, 94 FERC ¶ 61,340 (2001)).

¹³ Id. at 12, 19, 22-23.

¹⁴ Id. at 19, 26-30.

¹⁵ Id. at 12-13 (citing S. Cal. Edison v. FERC, 603 F.3d 996 (D.C. Cir. 2010) (SoCal Edison); Calpine Corp. v. FERC, 702 F.3d 41 (D.C. Cir. 2012) (Calpine)).

reasonable to determine the jurisdiction over a sale based on the length of a netting period. ¹⁶ NERA asserts that the law is clear that, whenever the amount of energy generated exceeds the retail load behind the meter, regardless of the duration of the excess, state law may not govern the rates for net energy sales and the price of energy must be determined in accordance with federal law. ¹⁷

7. NERA states that the FPA includes within the Commission's exclusive jurisdiction "the sale of electric energy at wholesale in interstate commerce," which occurs whenever energy is delivered from one entity to another for compensation. NERA states that a sale of electric energy is made at wholesale whenever it is made to any person for resale. NERA asserts that the sale is made in interstate commerce if the energy is delivered to a utility that merges and commingles the energy with other energy sources on the interstate electric grid. NERA adds that the FPA does not recognize a de minimis exception with regard to the Commission's jurisdiction over the rates for wholesale sales. NERA argues that, once the Commission's jurisdiction is established

¹⁶ Id. at 16 (citing S. Cal. Edison v. FERC, 603 F.3d 996).

¹⁷ *Id.* at 8; 18-19.

¹⁸ Id. at 19 (citing 16 U.S.C. § 824(b)(1); FPC v. S. Cal. Edison Co., 376 U.S. 205 (1964) (Colton)).

¹⁹ Id. at 19-20 (citing *PJM Interconnection, L.L.C.*, 94 FERC ¶ 61,251, at 61,889 (2001) (defining a sale as "transaction between two parties, with one party using resources of another party for some form of consideration")).

²⁰ Id. (citing 16 U.S.C. § 824(d)).

²¹ Id. (citing FPC v. Fla. Power & Light Co., 404 U.S. 453, 457-58 (1972)).

²² Id. (citing Prior Notice and Filing Requirements Under Part II of the Federal Power Act, 64 FERC ¶ 61,139, at 61,995 (1993) ("The FPA makes no mention of a 'de minimis' exception for otherwise jurisdictional transactions. Moreover, the courts have rejected the notion.") (emphasis in original); FPC v. Texaco Inc., 417 U.S. 380, 394 (1974) (holding that the Commission may not, on de minimis grounds, exempt a class of utilities from regulation.); Conn. Light & Power Co. v. FPC, 324 U.S. 515, 536 (1945) ("We do not find that Congress has conditioned the jurisdiction of the Commission upon any particular volume or proportion of interstate energy involved, and we do not think it would be appropriate to supply such a jurisdictional limitation by construction.").

under the FPA, the Commission must exercise its jurisdiction and has no discretion to allow the states to regulate in areas within exclusive federal authority.²³

- NERA asserts that, even if the Commission has discretion to exercise its 8. jurisdiction, it is inappropriate for the Commission to decline to exercise jurisdiction here due to Net Energy Metering's adverse public policy impacts.²⁴ NERA contends that the generators favored by Net Energy Metering are typically much less efficient than their disfavored competitors and impose significant additional costs on the electric system due to their intermittent nature. 25 NERA also alleges that Net Energy Metering provides perverse incentives for sellers not to invest in storage or other technologies because they are already compensated as if they were supplying a firm, load-following service. NERA claims that the overpayment from Net Energy Metering through compensation at retail rates results in over-investment in the production of less efficient and reliable energy, with a corresponding reduction in investment in both grid-based renewable generation and resources that provide the dispatchable firm power required for reliable operations.²⁶ NERA also contends that Net Energy Metering will make it more difficult to achieve renewable energy goals because electric consumers are forced to pay the bundled retail rate for one form of variable renewable energy, even though energy with all of the same environmental attributes can be purchased at a fraction of that amount from the grid. NERA argues that, therefore, Net Energy Metering increases utility costs and shifts those costs in an inequitable manner to lower income consumers.²⁷
- 9. NERA also argues that, because nearly all Net Energy Metering sellers are Qualifying Facilities (QFs) pursuant to PURPA because they are behind the retail meter generators that are smaller than 1 MW and utilize renewable or other qualifying energy sources such as rooftop solar, their sales must be priced at the avoided cost rate in accordance with PURPA.²⁸ NERA claims that Net Energy Metering pricing produces a rate for QF-generated energy that substantially exceeds the purchasing utility's avoided

 $^{^{23}}$ Id. at 24-25 (citing Colton, 376 U.S. 205 at 209 n.5; Florida Power & Light Co., 29 FERC ¶ 61,140, at 61,292 (1984)).

²⁴ Id. at 44.

²⁵ Id. at 37.

²⁶ *Id.* at 37-38.

²⁷ Id. at 40-43.

²⁸ Id. at 30-32 (citing PURPA § 210, 16 U.S.C. § 824a-3(a) and (b) ("No such rule. . . [shall] provide for a rate which exceeds the incremental cost to the electric utility of alternative electric energy.")).

cost because the QF is compensated at the bundled retail rate but is not supplying a firm power product or avoiding the need for utility transmission or distribution and other fixed costs included in the bundled rate.²⁹ NERA asserts that the need to re-allocate unrecovered costs to other customers means that the rate charged by the QF exceeds the utility's avoided cost.³⁰ NERA further argues that PURPA section 111(d) provides an offset for energy only, which "infers" that the offset is equal to the avoided cost of energy.³¹ NERA claims that, in the few cases in which Net Energy Metering sales from behind a retail meter are not subject to PURPA (i.e., the seller is not eligible to be a QF or is eligible but larger than one megawatt and does not self-certify), the seller is required under the FPA to have a rate approved and on file with the Commission, together with a contract or tariff under which the wholesale purchaser has agreed to purchase its energy at that rate.³² NERA asserts that, in that case, the rate should be the applicable just and reasonable rate for non-firm energy.

II. Notice of Filing and Responsive Pleadings

- 10. Notice of NERA's petition was published in the *Federal Register*, 85 Fed. Reg. 22,416 (Apr. 22, 2020), with interventions and protests due on or before June 15, 2020.³³
- 11. Numerous entities filed notices of intervention and timely motions to intervene; some of those entities also filed comments.³⁴ Numerous individuals also filed comments.³⁵
- 12. Environmental Defense Fund; Lincoln Electric System; Maine Governor's Energy Office; and Office of the Nevada Attorney General filed motions to intervene out of time.

²⁹ Id. at 32-33.

³⁰ Id. at 33.

³¹ Id. at 35-37 (citing 16 U.S.C. § 2621(d)(11))(2018).

³² Id. at 9.

³³ On May 4, 2020, the comment period was extended from May 14, 2020 to June 15, 2020. *See Notice of Extension of Time*, Docket No. EL20-42-000 (May 4, 2020).

³⁴ See Appendix A.

³⁵ See id.

13. Allco Renewable Energy Limited; Colorado Energy Office; New Energy Equity, LLC.; Organization of MISO States, Inc. and Organization of PJM States Inc.; Public Citizen; and WWALS Watershed Coalition, Inc. filed motions to dismiss or deny. ³⁶ On June 30, 2020, the Michigan Commission filed an answer to the comments supporting the Petition, and the Oxenhams filed an answer supporting Public Citizen's motion to dismiss. On that same date, NERA filed an answer to the protests and motions to dismiss. On July 1, 2020, Public Citizen filed an answer to NERA's answer.

A. Comments in Support

- 14. Americans for Tax Reform, Californians for Green Nuclear Power, Inc., CAlifornians for Renewable Energy, Inc., Citizens Against Government Waste, Competitive Enterprise Institute, and Heartland Institute support the Petition.³⁷
- 15. Citizens Against Government Waste argue that granting the Petition would result in fair competition in the energy sector by instituting more energy-efficient practices and would save ratepayers billions of dollars.³⁸ Heartland Institute asserts that the costs of installing and maintaining resources subject to net metering laws are paid by ratepayers in general, rather than the customers or companies who installed or operate the resources, which results in regressive cost-shifting because rooftop solar owners generally have higher incomes than others so lower income ratepayers end up subsidizing higher-income customers. For this reason, Heartland Institute argues that owners of these resources should be paid at the same rate conventional sources are paid, reflecting the true wholesale cost of electricity.³⁹
- 16. Competitive Enterprise Institute similarly contends that net metering is unfair because it results in a windfall to participants at the expense of other consumers.⁴⁰ Competitive Enterprise Institute argues that the Commission has jurisdiction over net

³⁶ On June 15, 2020, CAlifornians for Renewable Energy, Inc., Michael Boyd, and QF03-76-000 filed a request for joinder. It is unclear which proceedings the entity seeks consolidated or joined; therefore, we are not able to act upon this request.

³⁷ Institute for Energy Research does not explicitly state that it supports the Petition but contends that net metering programs replace cheap, efficient existing generation capacity with high cost, inefficient rooftop generation, while shifting costs to low-income households. *See* Institute for Energy Research Comments at 1.

³⁸ Citizens Against Government Waste Comments at 3.

³⁹ Heartland Institute Comments at 1-3.

⁴⁰ Competitive Enterprise Institute Comments at 2-6.

metering transactions because they are wholesale sales and due to the inherently interstate nature of any electric energy delivered to a utility that merges and commingles the energy with other energy sources on the interstate electric grid. Americans for Tax Reform support the Petition because they assert that the regressive cost-shifting associated with net metering benefits wealthy homeowners to the detriment of lower income consumers and provides subsidies that distort competitive markets and conflicts with federal law. Californians for Green Nuclear Power, Inc. supports the Petition because it believes that net metering policies should reimburse wholesale rates instead of retail rates to a solar generation facility owner. CAlifornians for Renewable Energy, Inc. supports the Petition "with the modification that the Commission already has 'exclusive federal jurisdiction over wholesale energy [and capacity] sales from generation sources located on the customer side of the retail meter."

B. <u>Comments in Opposition</u>

- 17. Commenters oppose the Petition for several reasons.
- 18. First, commenters request that the Commission dismiss the Petition for a variety of procedural defects. 45 Commenters argue that NERA does not disclose its constituent members or the interests it represents; therefore, NERA has not demonstrated that it will be subject to harm based on the outcome of the Petition or that it has an identifiable interest in the proceedings. 46 Commenters allege that NERA mounts broad policy

⁴¹ *Id.* at 6-7.

⁴² Americans for Tax Reform Comments at 1.

⁴³ Californians for Green Nuclear Power, Inc. Comments at 1.

⁴⁴ CAlifornians for Renewable Energy, Inc. Comments at 2.

⁴⁵ These commenters include entities such as the following: APPA; Berkshire Environmental Action Team; Coalition for Community Solar Access; Colorado Energy Office; CT/NY State Intervenors; Distributed Energy Coalition; Eastern New England Consumer-Owned Systems; Electricity Regulation Scholars; NARUC; National Association of State Utility Consumer Advocates; New England Small Hydro Coalition; NH State Rep. Kat McGhee; Pennsylvania Public Utility Commission; Public Citizen; Public Interest Organizations; Public Utility Commission of Oregon; Public Utility Commission of Texas; Solar Energy Industries Association; and Western Way.

⁴⁶ See, e.g., Eastern New England Consumer-Owned Systems Comments; Public Citizen Motion to Dismiss.

arguments without reference to specific parties or factual circumstances. To instance, Pennsylvania Public Utility Commission asserts that the net metering regulatory scheme is already well established and the Petition fails to identify a specific state net metering scheme that is at issue, even though the Commission requires a concrete case or controversy with limited exceptions. Commenters also claim that Commission's net metering precedent is sound and there is no controversy or uncertainty to resolve. APPA points to the fact that (1) the Commission has reaffirmed its precedent on retail net metering jurisdiction in a number of contexts, (2) the precedent is consistent with PURPA section 111(d)(11), and (3) NERA does not cite any particular case or controversy from which the issues addressed in the Petition are alleged to have arisen, let alone a case that raises new or unsettled issues. Commenters also assert that the Petition would create a controversy rather than resolve one. Commenters also contend that the Petition should have been filed as a complaint or as a petition for enforcement under PURPA.

19. Second, commenters argue that the Commission should defer net metering to the states because states should establish standards whenever possible and not expressly prohibited by law.⁵³ Commenters contend that states are appropriately implementing net metering and that the Commission's assertion of jurisdiction would initiate a "slippery slope" toward federal control of retail rates.⁵⁴ Coalition for Community Solar Access argues that the Commission should defer jurisdiction to the states because federal

⁴⁷ See, e.g., AEE Comments at 7-10; Electricity Regulation Scholars Comments at 4-5; NARUC Comments at 12-16.

⁴⁸ Pennsylvania Public Utility Commission Comments at 2-3.

⁴⁹ See, e.g., APPA Comments at 4-5; Electricity Regulation Scholars Comments at 5-8; New England Small Hydro Coalition Comments at 4.

⁵⁰ APPA Comments at 5.

⁵¹ See, e.g., APPA Comments at 5-6; Colorado Energy Office Comments at 7-12; Electricity Regulation Scholars Comments at 8; NARUC Comments at 13-15; Solar Energy Industries Association Comments at 6-7.

⁵² See, e.g., Electricity Regulation Scholars Comments at 7; NESCOE Comments at 14; Public Interest Organizations Comments at 9-10.

⁵³ See, e.g., Conservatives for Responsible Stewardship Comments at 1-2.

⁵⁴ See, e.g., Clean Coalition Comments at 6; Conservative Energy Network Comments at 4.

jurisdiction would likely fail to effectively take regional variability in state net metering programs into account. 55

- 20. Third, commenters contend that granting the Petition will unravel years of long-settled state net metering policies that consumers and businesses have relied upon to make investments, which would result in severe disruption to the energy industry and state environmental and clean energy goals. For instance, NARUC asserts that granting the Petition will disrupt the significant and long-term investments in rooftop solar made by millions of retail customers. Commenters claim that granting the Petition will cause significant economic harm by increasing costs to consumers, putting solar industry jobs at risk, and decreasing investment in renewable energy resources like rooftop solar. Se
- 21. National Fuel Cell Research Center contends that granting the Petition would undermine state economic policies and constitute a *de facto* repeal of net metering. National Fuel Cell Research Center points to Nevada and Maine as examples of how the repeal of net metering has devastated other distributed generation industries. ⁵⁹ Rural Nebraskans argue that net metering policy, which is designed to capture the economic benefits of distributed generation, should be left to local policymakers, ratepayers, and customer-generators. Organization of MISO States, Inc. and Organization of PJM States, Inc. contend that their members, nearly all of which have some form of net metering based on local conditions and policy goals, should be allowed to exercise their jurisdiction over net metering "based on state policy, utility and stakeholder goals, and/or other considerations under state and retail jurisdiction." ⁶⁰ Commenters also claim that a jurisdictional shift on issues related to the value of net metering, cross-subsidization, and

⁵⁵ Coalition for Community Solar Access Comments, Affidavit at 12.

⁵⁶ See, e.g., 31 State Attorneys General Comments at 2; AEE Comments at 25; Berkshire Environmental Action Team Comments at 2-3; NARUC Comments at 43.

⁵⁷ NARUC Comments at 43.

⁵⁸ See, e.g., Center for Rural Affairs Comments at 1-2; Coalition for Community Solar Access Comments at 8; New Energy Equity LLC Comments at 4-6; Ohio Environmental Council Comments at 2.

⁵⁹ National Fuel Cell Research Center Comments at 1.

⁶⁰ Organization of MISO States, Inc. and Organization of PJM States, Inc. Comments at 15.

technical considerations, which are within state jurisdiction, would be detrimental to the long-term investments made under the retail ratemaking process. ⁶¹

- 22. Fourth, commenters argue that net metering is an integral element of retail billing, which is strictly a state jurisdictional issue, and not a sale for resale.⁶² Electricity Regulation Scholars assert that the Commission does not have authority to require states to adopt a methodology for calculating retail sales or allocating costs of retail service among ratepayers because it is "widely understood that net metering is a component of retail service." AEE and NARUC claim that NERA has failed to provide any evidence of a sale for resale, such as taxation, transfer of title, a utility recording the cost of an acquisition, engineering data, power flow data, accounting studies, or some other proof of sale, which AEE argues NERA has the burden to prove.⁶⁴ New Jersey Board of Public Utilities contends that, because it prohibits generation from exceeding demand over the netting interval, no sale could ever occur under NERA's reasoning.⁶⁵
- 23. APPA asserts that net metering transactions are local by effect and in nature because net metering concerns "the relationship between the retail customer and the local utility, how to measure the quantity of energy provided by the utility, the amount due for that retail service, and the terms of that service." Charles J. Cicchetti & Jon Wellinghoff contend that a part of the determination of what constitutes a sale for resale depends on the intent of the parties, noting that there is a distinction between the intent of a party participating in net metering who infrequently injects power into the grid and the intent of traditional generators who compete in wholesale markets. Commenters claim that a finding that net metering is a sale for resale would upset related precedent (i.e.,

⁶¹ See, e.g., id.

⁶² See, e.g., NARUC Comments at 19-22 (also distinguishing net metering as "flows," not sales); see also Electricity Regulation Scholars Comments at 15 (describing an accounting method for retail service); Charles J. Cicchetti & Jon Wellinghoff Comments at 7 (describing net metering as "a credit," a "wash trade," or a "retail swap").

⁶³ Electricity Regulation Scholars Comments at 13-18.

⁶⁴ AEE Comments at 20; NARUC Comments at 20.

⁶⁵ New Jersey Board of Public Utilities Comments at 18.

⁶⁶ APPA Comments at 13-14.

⁶⁷ Charles J. Cicchetti & Jon Wellinghoff Comments at 8.

disclaimed jurisdiction in sub-metering agreements, ⁶⁸ certain *de minimis* contracts, ⁶⁹ and interconnection procedures) and create uncertainty regarding the regulatory framework for energy storage resources. ⁷⁰

- 24. Finally, commenters assert that the Commission does not have jurisdiction over net metering, which they contend is an intrastate transaction, because, under the FPA, the Commission has jurisdiction over only transactions in interstate commerce, and all other transactions fall under state jurisdiction, regardless if a sale for resale occurs. Maryland Energy Administration contends that net metering is wholly intrastate because no commingling of energy occurs on the interstate transmission grid. NARUC asserts that, contrary to NERA's assertion, even if there were commingling of a retail customer's generation onto a local distribution network containing energy that flowed in interstate commerce, Commission jurisdiction does not attach to net metering if the customer's generation does not subsequently flow across state lines, which NARUC asserts it does not. AEE contends that, even if commingling does occur, NERA has the burden to support that assertion, which it fails to do.
- 25. Maryland Energy Administration also argues that, according to the test used to determine whether net metering is in interstate commerce (i.e., the seven-factor test in Order No. 888 used to determine whether a facility is local distribution), the Commission

⁶⁸ E.g., Distributed Energy Coalition Comments at 10-11.

⁶⁹ E.g., NESCOE Comments at 16-17.

⁷⁰ E.g., APPA Comments at 15.

⁷¹ See, e.g., Indiana Utility Regulatory Commission Comments at 14-16; Maryland Energy Administration Comments at 3-4; NARUC Comments at 37-41; New Jersey Board of Public Utilities Comment at 22.

⁷² Maryland Energy Administration Comments at 3-4.

⁷³ NARUC Comments at 37-41 (distinguishing wholesale and transmission jurisdiction as described in *Florida Power & Light* and noting that unintended flow that crossed state boundaries was "too remote" in character, as described in *Superior Oil Co. v. Miss. ex rel. Knox*, 280 U.S. 390 (1930), and that *U.S. v. Pub. Util. Comm'n of Cal.*, 345 U.S. 295 (1953) among others upholds and reinforces this distinction about interstate character of transactions based on intent and knowledge of interstate nature).

⁷⁴ AEE Comments at 20; Coalition for Community Solar Access Comments at 16.

would not have jurisdiction over net metering.⁷⁵ Separately, APPA asserts that regulating net metering would regulate the wires within homes and result in improper use of the interstate commerce clause.⁷⁶

C. Answers

- 26. The Oxenhams support Public Citizen's motion to dismiss and argue that NERA's failure to disclose the nature of its interest in the Petition's subject matter warrants dismissing the Petition.⁷⁷
- 27. In response to commenters supporting the Petition, the Michigan Commission asserts that their policy rationales do not justify the requested relief and fail to recognize the diversity of state policies regarding net metering. The Michigan Commission objects to arguments that net metering programs overcompensate customers for the excess electricity, subsidize rooftop solar electricity generation, and cost shift from higher-income customers to lower-income customers, arguing that these criticisms are not applicable to the programs in Michigan. The Michigan Commission further argues that states have jurisdiction over distributed generation resources and local net metering programs. The Michigan Commission contends that net metering programs do not interfere with interstate commerce or set wholesale rates and that, as the Commission's *MidAmerican* and *SunEdison* orders and the D.C. Circuit's *SoCal Edison* and *Calpine* opinions reveal, state net metering programs are not preempted. 80
- 28. In its answer, NERA responds to arguments that the Commission cannot or should not rule on the merits of the Petition. NERA contends that it appropriately filed its Petition under Rule 207(a)(2), asking the Commission to resolve a key jurisdictional issue under the FPA and a controversy affecting the efficiency of wholesale markets and the rates paid by millions of retail electric consumers.⁸¹ NERA states that the Commission has previously confirmed that subject matters involving questions relating to

⁷⁵ Maryland Energy Administration Comments at 3.

⁷⁶ APPA Comments at 15.

⁷⁷ Oxenhams Answer at 2-18.

⁷⁸ Michigan Commission Answer at 4-9.

⁷⁹ *Id.* at 9-19.

⁸⁰ Id. at 20.

⁸¹ NERA Answer at 12-13.

its jurisdiction are particularly appropriate to be addressed in petitions for declaratory orders. NERA further argues that its Petition raises the concrete and narrow issue of "monthly netting" and that the Commission's rules do not require that NERA challenge a specific state's net metering program. NERA claims that the Commission has both the right and the obligation to fix its errors. 85

29. In response to arguments about NERA's failure to disclose its membership, NERA states that it is a non-profit organization incorporated in the Commonwealth of Massachusetts and, thus, considered "a person" eligible to file a petition for declaratory order under Rule 207. RERA asserts that Rule 207 does not require that a person have "standing" before filing a petition for declaratory order. RERA notes that the Commission granted NERA's petition for declaratory order last year in Docket

⁸² Id. at 13-14 & n.23 (citing Obtaining Guidance on Regulatory Requirements, 123 FERC ¶ 61,157, at PP 18-19 (2008) (stating that because petitions for declaratory orders are subject to a public comment process, it is formal, binding and "the most reliable form of guidance available from the Commission"); PennEast Pipeline Co., LLC, 170 FERC ¶ 61,064, at P 16 (2020) (granting a petition for declaratory order based upon a finding of uncertainty as to the proper role of the Commission in condemnation proceedings); ITC Grid Dev., LLC, 154 FERC ¶ 61,206, at P 42 (2016) (stating that the determinations that the Commission makes in a declaratory order are "generally legal in nature" and encompass a broad range of issues, including "jurisdictional issues" arising "under the statutes that the Commission administer[s]")).

⁸³ Id. at 6-7.

⁸⁴ Id. at 14 (citing Advanced Energy Econ., 161 FERC ¶ 61,245, at P 58 (2017) (rejecting various procedural arguments in opposition to a petition for declaratory order concerning energy efficiency resources and holding it appropriate to address the merits of the petition because "the novel issues of federal and state jurisdiction presented . . . warrant Commission guidance"), reh'g order, 163 FERC ¶ 61,030 (2018); Cal. Indep. Sys. Operator Corp., 119 FERC ¶ 61,061, at P 92 (2007) ("Providing general guidance on policy issues is precisely the function of this Commission in ruling on a petition for declaratory order.")).

⁸⁵ Id. (citing FCC v. Fox Television Stations, 556 U.S. 502, 513 (2009)).

⁸⁶ Id. at 15 (citing 18 C.F.R. 385.102(d) (2019)).

⁸⁷ Id. (citing Enbridge Offshore Facilities, LLC, 116 FERC ¶ 61,001, at P 16 (2006); SFPP, L.P., 102 FERC ¶ 61,089, at P 11 (2003); Proteus Oil Pipeline Co., LLC, 102 FERC ¶ 61,333, at P 30 (2003); Caesar Oil Pipeline Co., LLC, 102 FERC ¶ 61,339, at P 32 (2003); Express Pipeline P'ship, 75 FERC ¶ 61,303 (1996)).

No. EL19-10-000 and, although unnecessary, it is voluntarily attaching an affidavit from one of its members confirming that the member's interests as a ratepayer will be directly affected by the outcome of this proceeding.⁸⁸

- 30. NERA also responds to protests challenging the merits of the Petition. NERA argues that protestors' assertion that the Commission does not have jurisdiction over sales subject to net metering programs under FPA section 201(b) because there is no wholesale sale of electric energy is contrary to the plain language of FPA section 201(b) and constitute collateral attacks on the Commission's decisions in *MidAmerican* and *Sun Edison*. NERA disagrees that Net Energy Metering transactions are in intrastate commerce, arguing that, consistent with Supreme Court precedent, the Commission has consistently and uniformly held that wholesale sales from power generated on the distribution system, including from behind the retail meter, are jurisdictional sales in interstate commerce. NERA also contends that protesters' arguments seek to overturn *MidAmerican* and *Sun Edison* on grounds not asserted by NERA.
- 31. NERA argues that protestors incorrectly assert that the Commission has the discretion to decline its jurisdiction under the FPA. NERA states that, while the Commission must provide a clear explanation for changing its interpretation of its jurisdiction and has not done so often, there is no law prohibiting the Commission from doing so. NERA disagrees with protestors' characterization of the decisions in SoCal Edison and Calpine. NERA asserts that section 1251 of the Energy Policy Act 2005, which amends PURPA section 111(d), does not change the Commission's jurisdiction over net metered wholesale sales. NERA also responds to other protestors' concerns: policy arguments; universality of net metering programs in states; technical feasibility of using wholesale market prices to price the sales of excess energy from net metered transactions; reference to net metering as a billing convention; reliance on the seven-factor test adopted in Order No. 888; the applicability of the enforcement framework in PURPA section 210; contention that the pricing of energy delivered to the distribution

⁸⁸ Id. at 16.

⁸⁹ Id. at 17-21.

⁹⁰ Id. at 21-30.

⁹¹ Id. at 31-34.

⁹² Id. at 34-35.

⁹³ Id. at 38-39.

⁹⁴ Id. at 39-42.

utility is a sale at a valid avoided cost rate under PURPA; use of federalism principles to reject the Petition or find that preemption is not warranted; and argument that NERA asks the Commission to construe its FPA jurisdiction in a manner that raises questions under the Tenth Amendment.⁹⁵

32. In its answer to NERA's answer, Public Citizen contends that NERA is not a ratepayer group, but rather a trade association representing energy interests, as confirmed by the affidavit of Geoffrey Mitchell.⁹⁶ Public Citizen argues that, by claiming Mr. Mitchell is a ratepayer and member but omitting that Mr. Mitchell is President of Brant Energy Inc. and aligned with the financial interests of electric utilities, NERA intentionally mischaracterizes itself as a ratepayer organization to shield the true economic interests motivating the Petition.⁹⁷ Public Citizen also argues that NERA has a sister organization, the Ratepayers Legal Defense Fund, Inc., and that any Commission action to require disclosure of NERA's membership should also apply to that organization.⁹⁸

III. Discussion

A. Procedural Matters

- 33. Pursuant to Rule 214 of the Commission's Rules of Practice and Procedure, 18 C.F.R. § 385.214 (2019), the notices of intervention and timely, unopposed motions to intervene serve to make the entities that filed them parties to this proceeding. Pursuant to Rule 214(d) of the Commission's Rules of Practice and Procedure, 18 C.F.R. § 385.214(d), we grant Environmental Defense Fund's, Lincoln Electric System's, Maine Governor's Energy Office's, and Office of the Nevada Attorney General's late-filed motions to intervene given their interest in the proceeding, the early stage of the proceeding, and the absence of undue prejudice or delay. 99
- 34. Rule 213(a)(2) of the Commission's Rules of Practice and Procedure, 18 C.F.R. § 385.213(a)(2) (2019), prohibits answers to protests and answers to answers unless

⁹⁵ Id. at 42-46.

⁹⁶ Public Citizen Answer at 1.

⁹⁷ Id. at 1-2.

⁹⁸ Id. at 2.

⁹⁹ The entities and individuals that filed comments but did not file motions to intervene are not parties to this proceeding. *See* 18 C.F.R. §§ 385.102(c)(3), 385.214(a)(3) (2019).

otherwise ordered by the decisional authority. We accept the Michigan Commission's, NERA's, and Public Citizen's answers because they have provided information that assisted us in our decision-making process. Answers to motions are permitted. 100

B. Substantive Matters

- 35. Declaratory orders to terminate a controversy or remove uncertainty¹⁰¹ are discretionary.¹⁰² We find that the issues presented in the Petition do not warrant a generic statement from the Commission at this time. Therefore, we exercise our discretion to decline to address the issues set forth in the Petition, and, accordingly, we dismiss the Petition.
- 36. The manner in which the Commission addresses a petition for declaratory order depends on the "specific facts and circumstances" presented to the Commission. ¹⁰³ NERA in its Petition makes general assertions that Net Energy Metering policies adopted by various states improperly intrude on the Commission's authority under the FPA and PURPA. NERA states that "it is in the public interest for the Commission to address this Petition promptly so that the pricing of [Net Energy Metering] sales becomes settled and

¹⁰⁰ See 18 C.F.R. § 385.213(a)(3) (an answer may be made to any pleading, if not prohibited by paragraph (a)(2) of that section); 18 C.F.R. § 385.202 (2019) (a motion is a type of pleading).

¹⁰¹ 18 C.F.R. § 385.207(a)(2).

Procedure Act, the "agency, with like effect as in the case of other orders, and in its sound discretion, may issue a declaratory order to terminate a controversy or remove uncertainty"); Continental Oil Co. v. FPC, 285 F.2d 527, 527 (5th Cir. 1961) (per curiam); Stowers Oil & Gas Co., 27 FERC ¶ 61,001, at 61,001 (1984) (noting that "there is ample authority for the proposition that Commission action on petitions for declaratory order is discretionary with the agency"); accord Morgan Stanley Capital Group, Inc., 119 FERC ¶ 61,298, at P 17 (2007) (Commission "has discretion as to whether to issue a declaratory order in particular circumstances in order to terminate a controversy or remove uncertainty"); Ark. Power & Light Co., 35 FERC ¶ 61,358, at 61,818 (1986) (granting of petition for declaratory order "is a matter of agency discretion").

¹⁰³ ITC Grid Dev., LLC, 154 FERC ¶ 61,206 at PP 44-45 & n.72 (quoting Puget Sound Energy Inc., 139 FERC ¶ 61,241, at P 12 (2012)); accord Sharyland Utils., L.P., 121 FERC ¶ 61,006, at P 23 (2007) (granting petition for declaratory order "[b]ased on the specific facts presented. . . .").

affected parties can make appropriate decisions." NERA further states that the Petition "focuses on the more common form of [Net Energy Metering] described above, as that was the subject of the Commission's prior rulings in *MidAmerican* and *Sun Edison*." The Petition, however, does not identify a specific controversy or harm that the Commission should address in a declaratory order to terminate a controversy or to remove uncertainty. In contrast, *MidAmerican* and *SunEdison* related to the implementation of specific net metering programs or the participation in such programs by specific parties. For this separate reason as well, we decline to issue the requested order.

37. Lastly, to the extent that NERA is concerned that certain state regulatory authorities in New England are not pricing sales from QFs in accordance with PURPA, ¹⁰⁷ we find the Petition does not meet the requirements for enforcement under PURPA section 210(h). ¹⁰⁸

¹⁰⁴ See Petition at 2.

¹⁰⁵ Id. at 5 n.11.

¹⁰⁶ See Sun Edison LLC, 129 FERC ¶ 61,146 at P 1 (seeking a declaratory order confirming that certain of its subsidiaries' sales to end-use customers do not constitute the sale of electric energy at wholesale in interstate commerce or the transmission of electric energy in interstate commerce for purposes of the Federal Power Act); MidAmerican, 94 FERC ¶ 61,340 at P 1 (objecting to the Iowa Utilities Board's implementation of final orders issued pursuant to Iowa's Alternate Energy Production Statute and § 199-15.11(5) of the regulations thereunder, directing MidAmerican to interconnect with three Alternate Energy facilities and to offer net billing arrangements to those facilities).

¹⁰⁷ See 16 U.S.C. § 824a-3(b). NERA states that "[i]n the case of behind the retail meter generators utilizing renewable or other qualifying energy sources (such as rooftop solar), the sellers are virtually always QFs pursuant to PURPA" and that "[t]he Commission's prior disclaimer of jurisdiction has permitted states to employ [full net metering] in order to price these QF sales significantly above avoided cost in violation of PURPA." Petition at 8.

¹⁰⁸ Section 210(h) of PURPA specifies that only electric utilities, qualifying small power production facilities and qualifying cogeneration facilities may petition for enforcement of PURPA. 16 U.S.C. § 824a-3(h)(2)(B). NERA does not appear to fall within any of those categories.

The Commission orders:

NERA's Petition is hereby dismissed, as discussed in the body of this order.

By the Commission. Commissioner McNamee is concurring with a separate statement attached.

Commissioner Danly is concurring with a separate statement attached.

(SEAL)

Kimberly D. Bose, Secretary.

Appendix A

Intervention Only

- 1. Acadia Center
- 2. Allegheny Electric Cooperative, Inc.
- 3. Alliant Energy Corporate Services, Inc.
- 4. Ameren Services Company
- 5. American Electric Power Service Corporation
- 6. American Wind Energy Association
- 7. Appalachian Voices
- 8. Arkansas Electric Cooperative Corporation
- 9. Arkansas Public Service Commission
- 10. Avista Corporation
- 11. Berkshire Environmental Action Team, Inc.
- 12. Borrego Solar Systems, Inc.
- 13. California Justice Department
- 14. California Municipal Utilities Association
- 15. CAlifornians for Renewable Energy, Inc.
- 16. Calpine Corporation
- 17. Central Hudson Gas & Electric Corporation, Consolidated Edison Company of New York, Inc., Orange and Rockland Utilities, Inc., New York Power Authority, Niagara Mohawk d/b/a/ National Grid, New York State Electric & Gas Corporation, Rochester Gas and Electric Corporation, Long Island Lighting Company d/b/a Power Supply Long Island, Long

- Island Power Authority (New York Transmission Owners)
- 18. Cities of Anaheim, Azusa, Banning, Colton, Pasadena, and Riverside, California
- 19. Citizens Energy Corporation
- 20. Citizens Utility Board of Illinois
- 21. City of Farmington, New Mexico, d/b/a Farmington Electric Utility System
- 22. City of New York
- 23. Clean Wisconsin
- 24. Clearway Energy Group LLC
- 25. Cogentrix Energy Power Management, LLC
- 26. Connecticut Consumer Counsel
- 27. Connecticut Department of Energy and Environmental Protection
- 28. Connecticut Public Utilities Regulatory Authority
- 29. Conservation Law Foundation
- 30. Consolidated Edison Development, Inc.
- 31. Consumer Energy Alliance
- 32. Consumers Energy Company
- 33. Convergent Energy and Power LP
- 34. Cooperative Energy
- 35. CPV Power Holdings, LP
- 36. Direct Energy Services, LLC and Direct Energy Business, LLC
- 37. Dominion Energy Services, Inc.
- 38. Duke Energy Corporation
- 39. East Kentucky Power Cooperative, Inc.
- 40. Eastern Generation, LLC
- 41. Edison Electric Institute

- 42. El Paso Electric Company
- 43. Electric Power Supply Association
- 44. Energy New England, LLC
- 45. Energy Storage Association
- 46. EnergySage
- 47. ENGIE North America Inc.
- 48. Entergy Services, LLC; Entergy Louisiana, LLC; Entergy Mississippi, LLC; Entergy New Orleans, LLC; Entergy Texas, Inc.; Entergy Arkansas, LLC
- 49. Environmental Law and Policy Center
- 50. Exelon Corporation
- 51. FirstEnergy Service Company
- 52. FirstLight Power Inc.
- 53. Georgia Interfaith Power & Light, North Carolina Interfaith Power & Light, South Carolina Interfaith Power & Light
- 54. Gravity Renewables, Inc.
- 55. Harvard Electricity Law Initiative
- 56. Helix Maine Wind Development, LLC, et. al.
- 57. Helix Ravenswood LLC
- 58. Idaho Conservation League
- 59. Idaho Power Company
- 60. Illinois Commerce Commission
- 61. Illinois Municipal Electric Agency
- 62. Imperial Irrigation District
- 63. Independent Market Monitor for PJM
- 64. Indiana Utility Regulatory Commission
- 65. Iowa Attorney General and Iowa Office of Consumer Advocate
- 66. Iowa Environmental Council
- 67. Iowa Office of Consumer Advocate
- 68. Iowa Solar Energy Trade Association

- 69. James J. Apple
- 70. Joy Loving
- 71. Kathleen Jennings, Attorney General for the State of Delaware
- 72. Los Angeles Department of Water and Power
- 73. Louisiana Public Service Commission
- 74. Louisville Gas and Electric Co./ Kentucky Utilities Co.
- 75. Maine Public Utilities Commission
- 76. Marin Clean Energy
- 77. Massachusetts Attorney General Maura Healey
- 78. Massachusetts Department of Public Utilities
- 79. Massachusetts Municipal Wholesale Electric Company
- 80. Michigan Attorney General
- 81. Michigan Public Power Agency
- 82. Michigan Public Service Commission (Michigan Commission)
- 83. Minnesota Attorney General's Office
- 84. MISO Transmission Owners
- 85. Modern Energy Resources, LLC
- 86. National Grid
- 87. NC WARN
- 88. NEPOOL Participants Committee
- 89. New England Power Generators Association, Inc.
- 90. New Hampshire Electric Cooperative, Inc.
- 91. New Hampshire Public Utilities Commission
- 92. New Jersey Division of Rate Counsel
- 93. New Jersey Office of Attorney General

- 94. New York State Attorney General's Office
- 95. New York State Energy Research and Development Authority
- 96. New York State Public Service Commission
- 97. NextEra Energy, Inc.
- 98. North Carolina Attorney General's Office
- 99. North Carolina Sustainable Energy Association
- 100. North Carolina Utilities Commission
- 101. NRG Power Marketing LLC
- 102. Office of the Attorney General for the District of Columbia
- 103. Office of the Attorney General of Maryland
- 104. Old Dominion Electric Cooperative
- 105. Omaha Public Power District
- 106. Oncor Electric Delivery Company LLC
- 107. Organization of MISO States, Inc.
- 108. Pacific Gas & Electric Company
- 109. Peninsula Clean Energy Authority
- 110. Pennsylvania Office of Consumer Advocate
- 111. PJM Interconnection, L.L.C.
- 112. Portland General Electric Company
- 113. PPL Electric Utilities Corporation
- 114. PSEG Companies
- 115. Public Service Commission of Kentucky

- 116. Public Utilities Commission of Ohio
- 117. Public Utilities Commission of The State of California
- 118. Public Utility District No. 1 of Snohomish County, Washington
- 119. Renew Wisconsin
- 120. Rhode Island Attorney General
- 121. Rhode Island Division of Public Utilities and Carriers
- 122. Sacramento Municipal Utility District
- 123. Safari Energy, LLC
- 124. Salt River Project Agricultural Improvement & Power District
- 125. San Diego Gas & Electric Company
- 126. Solar United Neighbors
- 127. South Carolina Coastal Conservation League
- 128. Southern Alliance for Clean Energy
- 129. State of New Hampshire
- 130. State of Washington
- 131. Sunrun Inc.
- 132. Sustainable FERC Project and Natural Resources Defense Council
- 133. Talen Energy Corporation
- 134. TerraForm Power, Inc.
- 135. The Heartland Institute
- 136. The People of the State of Illinois
- 137. Upstate Forever
- 138. William Tong, Attorney General for the State of Connecticut
- 139. Xcel Energy Services Inc.

Comments Only

- 1. Alex Pouliot
- 2. Alice Lentz
- 3. Alice Trexler
- 4. Amanda Levesque
- 5. American Biogas Council
- 6. Americans for Tax Reform
- 7. Amicus Solar Cooperative
- 8. Amy Allen
- 9. Amy Gortler
- 10. Andrea Sreiber
- 11. Andreas Glatz
- 12. Andrew Bossi
- 13. Ann Boland
- 14. Ann W. Woll
- 15. Anne E. Huberman
- 16. Art Mandler
- 17. Artem Treyger
- 18. Arthur Fovargue
- 19. Ashwani Vasishth
- 20. Becky Brown
- 21. Belle Gironda
- 22. Benjamin Hollifield
- 23. Berkshire Environmental Action Team and No Fracked Gas in Mass
- 24. Bernard Jones
- 25. Bill Thunberg
- 26. Bob Steinburg
- 27. Bradley Pischea, Land & Liberty Coalition
- 28. Brent Whelan
- 29. Bridget J. Dunford
- 30. Brittany Zwierzchowski Tisler
- 31. Broward, Miami-Dade, and Palm Beach Counties, Florida
- 32. Bruce Davis
- 33. Bryan J. Siever
- 34. Caleb Pusey
- 35. CAlifornians for Renewable Energy, Inc. and Michael Boyd
- 36. Calpine Corporation; Eastern Generation, LLC; Competitive

- Power Ventures Holdings, LLC; Cogentrix Energy Power
- Management, LLC
- 37. Carl A. Querfurth
- 38. Carolyn Appen
- 39. Carolyn Lewellen
- 40. Carrie Blair
- 41. Catherine Koning
- 42. Center for Rural Affairs
- 43. Chad Forcey, Pennsylvania Conservative Energy Forum Executive Director
- 44. Charles J. Cicchetti, Ph.D. and Jon Wellinghoff (Cicchetti/Wellinghoff)
- 45. Charlotte Watson
- 46. Cheryl D. Rose
- 47. Chris Tiedeman
- 48. Christina Wolfe
- 49. Christine Cournoyer
- 50. Christine Enochs
- 51. Christopher and Lynne Gilbert
- 52. Christopher Lish
- 53. Cindy Callaway
- 54. Citizens Against Government Waste
- 55. City of Keene, NH
- 56. Clean Coalition
- 57. Competitive Enterprise Institute
- 58. Conservative Energy Network
- 59. Conservative Energy Network's Southeast Regional Director
- 60. Conservative Texans for Energy Innovation
- 61. Conservatives for a Clean Energy Future
- 62. Conservatives for Responsible Stewardship
- 63. Curt Newton
- 64. Cynthia L. Bainton
- 65. Daniel Glidden

- 66. Danny van Leeuwen
- 67. Dave Newbold
- 68. David Curtis
- 69. David Gordon
- 70. David Greenberg
- 71. David Kroop
- 72. David Oman
- 73. David R. Miera
- 74. David Voorhees
- 75. Devon Hutton
- 76. Diane Martin
- 77. Dianne Brown
- 78. Distributed Energy Coalition
- 79. Donald W. Harrod, Village Administrator
- 80. Dorothy Barnett
- 81. Ed Haser
- 82. Edward Loechler
- 83. Edward Rivet II, Michigan Conservative Energy Forum
- 84. Edwin Morris
- 85. Elise D. Matz
- 86. Emily Pallarito
- 87. Environment America
- 88. Eric M. Crane
- 89. Fuel Cell and Hydrogen Energy Association
- 90. George Riley
- 91. Gerald Beck
- 92. Geri Conley
- 93. Giff Carpenter, Conservatives for Clean Energy South Carolina State Director
- 94. Gina DeBreto
- 95. Ginger Ryan
- 96. Glenn R. Davis, Jr.
- 97. Governor Kim Reynolds, State of Iowa
- 98. Governor Mills, State of Maine
- 99. Green America
- 100. Greg Brophy
- 101. Greg Dotson, Assistant Professor of Law

- 102. Gregg Ferry
- 103. H. Scott Rosenbush and Cindy Zimmerman
- 104. Handy Law, LLC
- 105. Hannah Stuart
- 106. Hathaway Strategies
- 107. Heidi Swann
- 108. Henry J. Rose
- Indiana Conservative Alliance for Energy
- 110. Indiana Utility Regulatory
 Commission and the Indiana
 Office of Energy Development
- 111. Institute for Energy Research
- 112. Jack Grup
- 113. Jackson G. Keith
- 114. Jacob Winslow
- 115. Jacqueline Callas
- 116. Jake Ketzner
- 117. James and Mary Powell
- 118. James Schall
- 119. James Schwarber
- 120. James Seidel, Minnesota Conservative Energy Forum
- 121. Jan Onan
- 122. Jane Cook
- 123. Jason D. Yust
- 124. Jason Shaw, Georgia Public Service Commissioner
- 125. Jay Marlow
- 126. Jayne Abbot
- 127. Jean Cummings
- 128. Jeffrey C. Dickler
- 129. Jim Richardson
- 130. Jim Rossi
- 131. Joan B. Panek
- 132. Joan Ellersick
- 133. Joanna Lewis, Conservative Energy Network
- 134. Joanne Osborne, Arizona State Representative
- 135. Joel A. Huberman
- 136. John Bromer

- 137. John Feltenberger
- 138. John Gage
- 139. John K. Hansen
- 140. Jonathan Appelbaum
- 141. Jonathan Grucci
- 142. Jonathan Kopp
- 143. Jordan Ohler
- 144. JR Miller, Michigan Conservative Energy Forum
- 145. Judith Durand
- 146. Julie Lehman
- 147. Julie Taberman
- 148. Karen Crutchfield
- 149. Kate O'Connor
- 150. Katharine K. DuVivier
- 151. Katherine Bowditch
- 152. Katherine Early
- 153. Kathy McGhee
- 154. Kathy Pearson
- 155. Kayla A. Ventura
- 156. Kentucky Solar Industries Association
- 157. Kevin Priola, Colorado State Senator
- 158. Kurt Dieringer, Ecohouse Solar (Ohio)
- 159. Land & Liberty Coalition
- 160. Landon Stevens
- 161. Larry A. Etkin
- 162. Larry J. Ward
- 163. Larry Lambert
- 164. Laura Boggess
- 165. Laura Byrch
- 166. Lenore Madeleine
- 167. Lewis W. Weatherspoon
- 168. Linda Shaffer
- 169. Linda Terwilliger
- 170. Lois Clement
- 171. Longroad Energy Management, LLC
- 172. Louise J. Bowditch
- 173. Lynda Armona
- 174. Marcianna Caplis

- 175. Margery M. Hamlen
- 176. Margery W. Davies
- 177. Marjorie Shepardson
- 178. Mark Byington
- 179. Mark H. Follansbee
- 180. Martha Spencer
- 181. Mary Goodkind
- 182. Mary Summers
- 183. Mary Worrell
- 184. Massachusetts Executive Office of Energy and Environmental Affairs
- 185. Matthew D. Johnson, Land & Liberty Coalition
- 186. Max Hunter
- 187. Medical Society Consortium on Climate and Health
- 188. Meline Price
- 189. Melody Pajak
- 190. Michael Boyd
- 191. Michael E. Loos
- 192. Michael Fleming
- 193. Michael Franklin
- 194. Michael Hartley
- 195. Michael Tousey
- 196. Michele Hathcock
- 197. Mississippi Public Service Commission
- 198. Montana Department of Environmental Quality
- 199. NAACP North San Diego County Branch
- 200. NAACP San Diego Branch
- 201. Nancy Kelley-Gillard
- 202. Nancy Pellegrini
- 203. Nathan Wheeland
- 204. National Caucus of Environmental Legislators
- 205. National Fuel Cell Research Center
- 206. Neva R. Goodwin
- 207. Nevada Governor's Office of Energy

- 208. New Hampshire House of Representatives Science, Technology & Energy Committee
- 209. New Mexico Public Regulation Commission
- 210. NH State Rep. Kat McGhee
- 211. Nick Boeyink
- 212. Norm Hill
- 213. Norman P. Olson
- 214. Northeast Clean Energy Council
- 215. PACENation
- 216. Pat Momich
- 217. Patricia A. Martin
- 218. Pavel Balga
- 219. Peninsula Clean Energy Authority, Marin Clean Energy, California Joint Powers Authority, Sonoma Clean Power Authority
- 220. Pennsylvania Conservative Energy Forum
- 221. Pete Jeffries, Iowa Conservative Energy Forum
- 222. Peter F. Somssich
- 223. Peter Sinclair
- 224. Pravin Lewis
- 225. Randy Bernard
- 226. Ray Gaesser of Gaesser Farms and Chairman of Iowa Conservative Energy Forum
- 227. Rebecca Morris
- 228. Representative Nathan Ballentine
- 229. Richard Bobb
- 230. Richard Hybil
- 231. Richard L. Cohen
- 232. Rick Donohoe
- 233. Robert K. Triest
- 234. Robert M. Spiller, Jr.
- 235. Robert W. Bussewitz
- 236. Roger T. Panek
- 237. Ruck Julien
- 238. Ruth M. Amundsen
- 239. Ryan Negro
- 240. S. Hatch & Sons Landscaping

- 241. S. Nam
- 242. Sally Wright
- 243. San Diego Unified School District
- 244. Sarah Thorne
- 245. School Energy Coalition
- 246. Senator Margaret Wood Hassan
- 247. Senator Wiley R. Robertson
- 248. Solar Energy Business Association of New England
- 249. South Carolina Small Business Chamber of Commerce
- 250. Southern Environmental Law Center, on behalf of the Southeast Public Interest Organizations
- 251. Stephen Handy, Utah State Representative
- 252. Stephen Schmeiser
- 253. Sue Jenkins
- 254. Sue Stafford
- 255. Susan Bean
- 256. Susan Purser
- 257. Susan Richman
- 258. Suzanne Butcher
- 259. Suzanne M. Humer for CleanEarth4Kids.org
- 260. Taylor J. Christian, Land & Liberty Coalition
- 261. Terry M. Clark
- 262. Tex Fischer
- 263. The Heartland Institute, James
 Madison Institute, Leadership
 Institute, Mississippi Center for
 Public Policy, Nevada Policy
 Research Institute, Rio Grande
 Foundation, Roughrider Policy
 Center, Science & Environment
 Policy Project, Caesar Rodney
 Institute, Center of the American
 Experiment, Center for
 Independent Thought, CO2
 - Coalition, Committee for a
 - Constructive Tomorrow, the
 - Cornwall Alliance, and Energy &

- Environment Legal Institute (Heartland Institute)
- 264. The Western Way
- 265. Thomas B. Tutor
- 266. Thomas G. McLaughlin, Jr.
- 267. Thomas Karvonen
- 268. Thomas Tanton
- 269. Tim Andrews, Taxpayers Protection Alliance
- 270. Tim Echols, Georgia Public Service Commissioner
- 271. Todd Johnson
- 272. Tom Barrett and the undersigned Michigan legislators
- 273. Tom Chapin
- 274. Tom Roberts, Nevada State Assemblyman
- 275. Tomas J. Kloc
- 276. Tracie Burns
- 277. Tyler M. Duvelius, Ohio Conservative Energy Forum
- 278. US House of Representatives Pingree, Pocan, Tonko, Kuster, Haaland, Gohmert, Biggs, Roy, Gosar, Schweikert, Quigley, Golden, Pappas, and Welch
- 279. Virginia Department of Mines, Minerals and Energy
- 280. Virginia Distributed Solar Alliance
- 281. Virginia Marcotte
- 282. Walker L. Wright
- 283. Western Colorado Alliance
- 284. Western Organization of Resource Councils
- 285. William Everett
- 286. William Goldsmith
- 287. Wisconsin Conservative Energy Forum
- 288. Zachary R. Upton

Intervention and Comments

- 1. 31 State Attorneys General
- 2. Achim Ginsberg-Klemmt
- 3. Advanced Energy Economy (AEE)
- 4. Allco Renewable Energy Limited
- 5. American Green Bank Consortium
- 6. American Municipal Power, Inc.
- 7. American Public Power Association (APPA)
- 8. Ares EIF Management LLC; Heelstone Renewable Energy, LLC; Navisun LLC; Nexamp, Inc.; True Green Capital Management LLC; The Wunder Company; Dimension Energy LLC (Solar Generation Investors)
- 9. Arizona Corporation Commission
- 10. Californians for Green Nuclear Power, Inc.
- 11. Center for Biological Diversity
- 12. Coalition for Community Solar Access
- 13. Colorado Energy Office
- 14. Colorado Public Utilities Commission
- 15. Delaware Division of the Public Advocate
- 16. Delaware Public Service Commission
- 17. Dirigo Community Solar Group, Inc.; Crystal Spring Farm Community Solar Association; Solar Energy Association of Maine
- 18. Eastern New England Consumer-Owned Systems
- 19. Electricity Consumers Resource Council
- 20. Electricity Regulation Scholars
- 21. Florida Public Service Commission
- 22. Institute for Policy Integrity, New York University School of Law
- 23. Kansas Corporation Commission
- 24. Large Public Power Council
- 25. Lee Oxenham and Evan Oxenham (Oxenhams)
- 26. Maine Office of the Public Advocate
- 27. Maryland Energy Administration
- 28. Maryland Public Service Commission
- 29. Maura Healey, the Attorney General of the Commonwealth of Massachusetts, together with the state attorneys general of California, Connecticut, Delaware, the District of Columbia, Illinois, Maryland, Michigan, Minnesota, New Mexico, New York, North Carolina, Oregon, Rhode Island, Washington, and Wisconsin, the California Energy Commission, the California Public Utilities Commission, and the Rhode Island Division of Public Utilities and Carriers
- 30. MD-DC-VA Solar Energy Industry Association
- 31. National Association of Regulatory Utility Commissioners (NARUC)

- 32. National Association of State Energy Officials
- 33. National Association of State Utility Consumer Advocates
- 34. National Rural Electric Cooperative Association
- 35. New Energy Equity LLC
- 36. New England Small Hydro Coalition
- 37. New England States Committee on Electricity (NESCOE)
- 38. New Jersey Board of Public Utilities
- 39. New York State Public Service Commission, New York State Energy Research and Development Authority, Connecticut Department of Energy and Environmental Protection, Connecticut Public Utilities Regulatory Authority (State Intervenors)
- 40. Ohio Environmental Council
- 41. One Energy Enterprises LLC
- 42. Oregon Solar Energy Industries Association
- 43. Organization of MISO States, Inc. and Organization of PJM States, Inc.
- 44. Organization of PJM States, Inc.
- 45. Pennsylvania Office of Attorney General and Pennsylvania Department of Environmental Protection
- 46. Pennsylvania Office of Consumer Advocate, New Jersey Division of Rate Counsel, Office of People's Counsel for the District of Columbia, Maryland Office of People's Counsel, and Iowa Office of Consumer Advocate
- 47. Pennsylvania Public Utility Commission
- 48. Public Citizen, Inc
- 49. Public Service Commission of the District of Columbia
- 50. Public Service Commission of West Virginia
- 51. Public Utility Commission of Oregon
- 52. Public Utility Commission of Texas
- 53. R Street Institute
- 54. Sierra Club
- 55. Sierra Club, Vote Solar, Acadia Center, Clean Wisconsin Climate + Energy Project, Conservation Law Foundation, Environmental Defense Fund, Environmental Law & Policy Center, Idaho Conservation League, National Audubon Society, Natural Resources Defense Council, Western Grid Group, Sustainable FERC Project, Solar United Neighbors, Renew Wisconsin, Renewable Northwest, Public Citizen, North Carolina Sustainable Energy Association (Public Interest Organizations)
- 56. Solar Energy Industries Association
- 57. Solar United Neighbors and Vote Solar
- 58. SunPower Corporation
- 59. Virginia Office of the Attorney General

- 60. Virginia State Corporation Commission
- 61. Vote Solar
- 62. William Tong, Attorney General for the State of Connecticut, and the Connecticut Office of Consumer Counsel
- 63. WWALS Watershed Coalition, Inc.

UNITED STATES OF AMERICA FEDERAL ENERGY REGULATORY COMMISSION

New England Ratepayers Association

Docket No.

EL20-42-000

(Issued July 16, 2020)

McNAMEE, Commissioner, concurring:

- 1. Though I support the Commission's Order dismissing, on procedural grounds, New England Rate Payers Association's (NERA) Petition for Declaratory Order (Petition) concerning net metering, I write separately to make clear that today's Order does not address any of the important, substantive issues underlying the Petition.
- 2. To that end, the Commission's Order is not a decision on whether the Commission lacks jurisdiction over the energy sales made through net metering; nor is it a decision on the merits of the issues raised by and contained in the Petition. I also note, that as a general proposition, I think it is best to decide important legal and jurisdictional

¹ Since the Petition was filed, the U.S. Court of Appeals for the District of Columbia issued its opinion on the petitions for review of Commission Order Nos. 841 and 841-A, regarding electric storage resources (ESR). *NARUC*, *et al. v. FERC*, --- F.3d ---, 2020 WL 3886199 (D.C. Cir. July 10, 2020). The Court affirmed the Commission's authority over the ESR practices at issue in those Commission orders, which practices the Court acknowledged directly affect wholesale rates regardless of whether they occur on the distribution system or behind-the-meter. *Id.* at *5; *cf. Elec. Storage Participation in Mkts. Operated by Reg'l Transmission Orgs. & Indep. Sys. Operators*, Order No. 841-A, 167 FERC ¶ 61,154 (2019) (McNamee, Comm'r, *concurring in part and dissenting in part*), (arguing that the Commission exceeded its jurisdictional authority by requiring local utilities and the state entities that regulate them to allow ESRs connected to the distribution system or behind-the-meter to use those the distribution systems to sell power into wholesale electric markets).

questions, like the ones raised in in the Petition, when applying the law to a specific set of facts, such as in a Section 206 complaint, or through a rulemaking proceeding.

For these reasons, I respectfully concur.

Bernard L. McNamee Commissioner

UNITED STATES OF AMERICA FEDERAL ENERGY REGULATORY COMMISSION

New England Ratepayers Association

Docket No.

EL20-42-000

(Issued July 16, 2020)

DANLY, Commissioner, concurring:

- 1. I vote for today's order for one reason—I believe that the Commission has discretion to dismiss this petition on procedural grounds. I write separately because I have concerns about the consequences of this decision.
- 2. The petition for a declaratory order filed by New England Ratepayers Association (NERA) raises difficult legal questions regarding the regulatory treatment of facilities (like rooftop solar) used by retail customers primarily, but not exclusively, to serve their own electricity requirements. These questions not only include the rate treatment for excess generation but, more importantly, the boundary between federal and state jurisdiction to address such rate treatment.
- 3. I have yet to reach any conclusion regarding either rate treatment or jurisdictional boundaries, but I am certain that these are questions of profound importance and the Commission will eventually have to address them.
- 4. I am concerned that dismissing the petition on procedural grounds may well result in a patchwork quilt of conflicting decisions if the questions raised in the petition are instead presented to federal district courts across the country. While the federal courts are more than capable of adjudicating preemption claims, they are not steeped in the history of the Federal Power Act nor in matters of national energy policy. Confusion, delay and inconsistent rules—some of which will apply to individual states or parts of states—will be the inevitable result.

For these reasons, I respectfully concur.

¹ See 5 U.S.C. § 554(e) (2018) ("The agency, with like effect as in the case of other orders, and in its sound discretion, may issue a declaratory order to terminate a controversy or remove uncertainty."); 18 C.F.R. § 385.207(a)(2) (2019) (providing for the filing of a petition for "[a] declaratory order or rule to terminate a controversy or remove uncertainty").

James P. Danly Commissioner Print page

PPL Newsroom

International magazine names LG&E and KU among 'Top 20' U.S. utilities

Honor recognizes utilities for economic development success

(LOUISVILLE, Ky.) – Site Selection Magazine, an international publication focused on economic development, has named Louisville Gas and Electric and Kentucky Utilities Company among an elite group of the Top 20 utilities in the U.S. for corporate facility investment and job creation in 2019. The evaluation included a field of approximately 3,300 electric utilities across the country.

"It's an honor to be named a top utility for our company's commitment to economic development in the communities we serve," said Eileen Saunders, LG&E and KU vice president, Customer Services. "Through innovative programs and incentives, along with the tireless efforts of our Business and Economic Development team, we're proud to help empower business growth and expansion throughout Kentucky."

Site Selection Magazine recognized LG&E and KU for several significant efforts to promote economic development in 2019, which led to customers announcing more than \$2.8 billion in capital investment and the creation of more than 5,700 jobs.

Some of LG&E and KU's efforts include working with communities to identify the possibility of new industrial and commercial sites throughout its service territories, while also helping to evaluate existing sites to determine if additional investment may increase exposure to local communities. The company is also developing a grant program to provide incentives for communities to make proactive investments in product readiness and development.

"It's our employees who drive economic prosperity across the state, and we're really all on the economic development team," said John Bevington, LG&E and KU's director of Business and Economic Development. "This award honors the commitment we have to our core strengths, the servant leadership that we provide to our communities, and the relationships we build with customers and prospects."

For more details, visit siteselection.com.

###

Louisville Gas and Electric Company and Kentucky Utilities Company, part of the PPL Corporation (NYSE: PPL) family of companies, are regulated utilities that serve nearly 1.3 million customers and have consistently ranked among the best companies for customer service in the United States. LG&E serves 329,000 natural gas and 418,000 electric customers in Louisville and 16 surrounding counties. KU serves 558,000 customers in 77 Kentucky counties and five counties in Virginia. More information is available at www.lge-ku.com and www.pplweb.com.

For further information: call the LG&E and KU media hotline at 502–627–4999.

https://pplweb.mediaroom.com/news-releases?item=137652

Barnes Cross Examination Exhibit 1

Scenario 1

Year	Need for Additional Generation Capacity
2022	None
2023	None
2024	None
2025	None
2026	None
2027	None
2028	None
2029	None
2030	None
2031	None
2032	None
2033	None
2034	Yes
2035	Yes
2036	Yes
2037	Yes
2038	Yes
2039	Yes
2040	Yes
2041	Yes

Scenario 2

Year	Need for Additional Generation Capacity
2022	None
2023	None
2024	None
2025	None
2026	None
2027	None
2028	Yes
2029	Yes
2030	Yes
2031	Yes
2032	Yes
2033	Yes
2034	Yes
2035	Yes
2036	Yes
2037	Yes
2038	Yes
2039	Yes
2040	Yes
2041	Yes

Scenario 3

Year	Need for Additiona Generation Capacit
2022	Yes
2023	Yes
2024	Yes
2025	Yes
2026	Yes
2027	Yes
2028	Yes
2029	Yes
2030	Yes
2031	Yes
2032	Yes
2033	Yes
2034	Yes
2035	Yes
2036	Yes
2037	Yes
2038	Yes
2039	Yes
2040	Yes
2041	Yes

278.465 Definitions for KRS 278.465 to 278.468.

As used in KRS 278.465 to 278.468:

- (1) "Eligible customer-generator" means a customer of a retail electric supplier who owns and operates an electric generating facility that is located on the customer's premises, for the primary purpose of supplying all or part of the customer's own electricity requirements;
- (2) "Eligible electric generating facility" means an electric generating facility that:
 - (a) Is connected in parallel with the electric distribution system;
 - (b) Generates electricity using:
 - 1. Solar energy;
 - 2. Wind energy;
 - 3. Biomass or biogas energy; or
 - 4. Hydro energy; and
 - (c) Has a rated capacity of not greater than forty-five (45) kilowatts;
- (3) "Kilowatt hour" means a measure of electricity defined as a unit of work of energy, measured as one (1) kilowatt of power expended for one (1) hour; and
- (4) "Net metering" means the difference between the:
 - (a) Dollar value of all electricity generated by an eligible customer-generator that is fed back to the electric grid over a billing period and priced as prescribed in KRS 278.466; and
 - (b) Dollar value of all electricity consumed by the eligible customer-generator over the same billing period and priced using the applicable tariff of the retail electric supplier.

Effective: January 1, 2020

History: Amended 2019 Ky. Acts ch. 101, sec. 1, effective January 1, 2020. -- Amended 2008 Ky. Acts ch. 138, sec. 1, effective July 15, 2008. -- Created 2004 Ky. Acts ch. 193, sec. 1, effective July 13, 2004.

- 278.466 Availability of net metering -- Type, expense, and installation of meter -- Compensation to eligible customer-generators for electricity fed back into grid -- Commission to set compensation rate -- Excess generation credits nonrefundable -- Twenty-five year cap on preexisting net metering tariff provisions -- Safety and power quality standards -- Transferability of installation at same premises.
- (1) Each retail electric supplier shall make net metering available to any eligible customer-generator that the supplier currently serves or solicits for service. If the cumulative generating capacity of net metering systems reaches one percent (1%) of a supplier's single hour peak load during a calendar year, the supplier shall have no further obligation to offer net metering to any new customer-generator at any subsequent time.
- (2) Each retail electric supplier serving a customer with eligible electric generating facilities shall use a standard kilowatt-hour meter capable of registering the flow of electricity in two (2) directions. Any additional meter, meters, or distribution upgrades needed to monitor the flow in each direction shall be installed at the customer-generator's expense. If additional meters are installed, the net metering calculation shall yield the same result as when a single meter is used.
- (3) A retail electric supplier serving an eligible customer-generator shall compensate that customer for all electricity produced by the customer's eligible electric generating facility that flows to the retail electric supplier, as measured by the standard kilowatt-hour metering prescribed in subsection (2) of this section. The rate to be used for such compensation shall be set by the commission using the ratemaking processes under this chapter during a proceeding initiated by a retail electric supplier or generation and transmission cooperative on behalf of one (1) or more retail electric suppliers.
- (4) Each billing period, compensation provided to an eligible customer-generator shall be in the form of a dollar-denominated bill credit. If an eligible customer-generator's bill credit exceeds the amount to be billed to the customer in a billing period, the amount of the credit in excess of the customer's bill shall carry forward to the customer's next bill. Excess bill credits shall not be transferable between customers or premises. If an eligible customer-generator closes his or her account, no cash refund for accumulated credits shall be paid.
- (5) Using the ratemaking process provided by this chapter, each retail electric supplier shall be entitled to implement rates to recover from its eligible customer-generators all costs necessary to serve its eligible customer-generators, including but not limited to fixed and demand-based costs, without regard for the rate structure for customers who are not eligible customer-generators.
- (6) For an eligible electric generating facility in service prior to the effective date of the initial net metering order by the commission in accordance with subsection (3) of this section, the net metering tariff provisions in place when the eligible customergenerator began taking net metering service, including the one-to-one (1:1) kilowatt-hour denominated energy credit provided for electricity fed into the grid, shall remain in effect at those premises for a twenty-five (25) year period, regardless

of whether the premises are sold or conveyed during that twenty-five (25) year period. For any eligible customer-generator to whom this subsection applies, each net metering contract or tariff under which the customer takes service shall be identical, with respect to energy rates, rate structure, and monthly charges, to the contract or tariff to which the same customer would be assigned if the customer were not an eligible customer-generator.

- (7) Electric generating systems and interconnecting equipment used by eligible customer-generators shall meet all applicable safety and power quality standards established by the National Electrical Code (NEC), Institute of Electrical and Electronics Engineers (IEEE), and accredited testing laboratories such as Underwriters Laboratories.
- (8) An eligible customer-generator installation is transferable to other persons at the same premises upon notification to the retail electric supplier and verification that the installation is in compliance with the applicable safety and power quality standards in KRS 278.467 and in subsection (7) of this section.
- (9) Any upgrade of the interconnection between the retail electric supplier and the customer-generator that is required by commission-approved tariffs for the purpose of allowing net metering shall be made at the expense of the customer-generator.

Effective: January 1, 2020

History: Amended 2019 Ky. Acts ch. 101, sec. 2, effective January 1, 2020. -- Amended 2008 Ky. Acts ch. 138, sec. 2, effective July 15, 2008. -- Created 2004 Ky. Acts ch. 193, sec. 2, effective July 13, 2004.

LG&E and KU request bids for energy to continue to reliably serve customers

January 7, 2021

Utilities' aging coal-fired generating units nearing end of economic life

(LOUISVILLE, Ky.) – Louisville Gas and Electric Company and Kentucky Utilities Company issued a request for proposal today for generation capacity to meet a potential energy shortfall being created by the expected retirements of Mill Creek Units 1 and 2 and E.W. Brown Unit 3 later this decade.

The coal-fired Mill Creek Units 1 and 2 and E.W. Brown Unit 3 are reaching the end of their economic lives and the utilities are starting the process to evaluate all available generation options in order to implement the best generation plan for the future. The utilities are seeking from 300 to 900 megawatts beginning in 2025 to 2028. Proposals must be for at least 100 megawatts and must be delivered to the utilities' transmission system. Additionally, the utilities are asking for proposals for at least 100 megawatts of battery storage on their system.

"These units have enabled us to deliver safe, reliable power to our customers for decades, but they are nearing the end of their life cycles. Keeping them operating would require costly investments, and given their age, it would not be in the best interest of our customers to further invest in these units," said David Sinclair, LG&E and KU's vice president of Energy Supply and Analysis. "The request for proposal will allow us the opportunity to evaluate a number of options to ensure that we continue to serve our customers energy needs in the most reliable, least-cost fashion without committing LG&E and KU to any particular business decision."

At the time of their anticipated retirements, the Mill Creek units will be more than 50 years old and Brown Unit 3 will be nearly 60 years old. Mill Creek Unit 1, built in 1972, has 300 megawatts of capacity and is expected to be retired in 2024. Both Mill

PSC STAFF EXHIBIT 7

Creek Unit 2, a 297-megawatt unit built in 1974, and Brown Unit 3, a 412-megwatt unit built in 1971, are expected to be retired by 2028.

As part of the long-term planning process, the utilities evaluate a range of factors including the impact of potential stricter environmental regulations, fuel price scenarios, the cost of replacement generation, continued operations and major maintenance costs and the risk of major equipment failures in determining when to retire generation.

Since there are several years before the units may be taken out of service, any workforce reductions are expected to occur as part of normal retirements, attrition and transfer opportunities.

Visit Ige-ku.com/rfp to access the request. All proposals are due by March 31. The utilities anticipate making a decision by the middle of the year and possibly seeking applicable regulatory approvals starting in early 2022.

###

Louisville Gas and Electric Company and Kentucky Utilities Company, part of the PPL Corporation (NYSE: PPL) family of companies, are regulated utilities that serve more than 1.3 million customers and have consistently ranked among the best companies for customer service in the United States. LG&E serves 329,000 natural gas and 418,000 electric customers in Louisville and 16 surrounding counties. KU serves 558,000 customers in 77 Kentucky counties and five counties in Virginia. More information is available at www.lge-ku.com and www.pplweb.com.

P.S.C. No. 19, Original Sheet No. 97

Terms and Conditions Customer Responsibilities

APPLICATION FOR SERVICE

A written, in-person, electronic, or oral application or contract, properly executed, will be required before Company is obligated to render electric service. Company may require any party applying for service to provide some or all of the following information for the party desiring service: full legal name, address, full Social Security Number or other taxpayer identification number, date of birth (if applicable), relationship of the applying party to the party desiring service, and any other information Company deems necessary for legal, business, or debt-collection purposes. Company shall have the right to reject for valid reasons any such application or contract, including the applying party's refusal to provide requested information.

All applications for service shall be made in the legal name of the party desiring the service.

Where an unusual expenditure for construction or equipment is necessary or where the proposed manner of using electric service is clearly outside the scope of Company's rate schedules, Company may establish special contracts giving effect to such unusual circumstances. Customer accepts that non-standard service may result in the delay of required maintenance or, in the case of outages, restoration of service.

TRANSFER OF APPLICATION

Applications for electric service are not transferable and new occupants of premises will be required to make application for service before commencing the use of electricity. Customers who have been receiving electric service shall notify Company when discontinuance of service is desired, and shall pay for all electric service furnished until such notice has been given and final meter readings made by Company.

CONTRACTED DEMANDS

For rate applications where billing demand minimums are determined by the Contract Demand Customer shall execute written Contract prior to rendering of service. At Company's sole discretion, in lieu of a written contract, a completed load data sheet or other written load specification, as provided by Customer, can be used to determine the maximum load on Company's system for determining Contract Demand minimum.

If Company or Customer terminates Customer's service under a rate schedule that contains demand charges and Customer subsequently applies to Company to reestablish service to the same premise or facility. Company must determine monthly billing demand for the reestablished service as though Customer had continuously taken service from the time of service termination through the reestablishing of service to Customer. For the purpose of determining the monthly billing demand described in the preceding sentence, the demand to be used for the period during which Customer did not take service from Company shall be the actually recorded demand, if any, for the premise or facility during that period. The preceding two sentences will not apply if Company determines, in its sole discretion, that material changes to Customer's facilities, processes, or practices justify establishing a new Contract Demand for the reestablished service.

DATE OF ISSUE:

May 14, 2019

DATE EFFECTIVE: With Service Rendered On and After May 1, 2019

ISSUED BY:

/s/ Robert M. Conroy, Vice President

State Regulation and Rates

Lexington, Kentucky

Issued by Authority of an Order of the Public Service Commission in Case No. 2018-00294 dated April 30, 2019

KENTUCKY PUBLIC SERVICE COMMISSION

> Gwen R. Pinson **Executive Director**

> > **EFFECTIVE**

5/1/2019

Steven R. Punso

PURSUANT TO 807 KAR 5:011 SECTION 9 (1)

PSC STAFF EXHIBIT 8

T

P.S.C. No. 20, Original Sheet No. 97

Terms and Conditions Customer Responsibilities

APPLICATION FOR SERVICE

A written, in-person, electronic, or oral application or contract, properly executed, will be required before Company is obligated to render electric service. Company may require any party applying for service to provide some or all of the following information for the party desiring service; full legal name, address, full Social Security Number or other taxpayer identification number, date of birth (if applicable), relationship of the applying party to the party desiring service, and any other information. Company deems necessary for legal, business, or debt-collection purposes. Company shall have the right to reject for valid reasons any such application or contract, including the applying party's refusal to provide requested information.

All applications for service shall be made in the legal name of the party desiring the service.

Where an unusual expenditure for construction or equipment is necessary or where the proposed manner of using electric service is clearly outside the scope of Company's rate schedules, Company may establish special contracts giving effect to such unusual circumstances. Customer accepts that non-standard service may result in the delay of required maintenance or, in the case of outages, restoration of service.

TRANSFER OF APPLICATION

Applications for electric service are not transferable and new occupants of premises will be required to make application for service before commencing the use of electricity. Customers who have been receiving electric service shall notify Company when discontinuance of service is desired, and shall pay for all electric service furnished until such notice has been given and final meter readings made by Company.

CONTRACTED DEMANDS

For rate applications where billing demand minimums are determined by the Contract Demand Customer shall execute written Contract prior to rendering of service. At Company's sole discretion, in lieu of a written contract, a completed load data sheet or other written load specification, as provided by Customer, can be used to determine the maximum load on Company's system for determining Contract Demand minimum.

If Company or Customer terminates Customer's service under a rate schedule that contains demand charges and Customer subsequently applies to Company to reestablish service to the same premise or facility, Company must determine monthly billing demand for the reestablished service as though Customer had continuously taken service from the time of service termination through the reestablishing of service to Customer. For the purpose of determining the monthly billing demand described in the preceding sentence, the demand to be used for the period during which Customer did not take service from Company shall be the actually recorded demand, if any, for the premise or facility during that period. The preceding two sentences will not apply if Company determines, in its sole discretion, that material changes to Customer's facilities, processes, or practices justify establishing a new Contract Demand for the reestablished service.

DATE OF ISSUE: November 25, 2020

DATE EFFECTIVE: With Service Rendered

On and After May 1, 2019

ISSUED BY:

/s/ Robert M. Conroy, Vice President

State Regulation and Rates

Lexington, Kentucky

Issued by Authority of an Order of the Public Service Commission in Case No. 2018-00294 dated April 30, 2019

Louisville Gas and Electric Company

P.S.C. Electric No. 12, Original Sheet No. 97

Terms and Conditions Customer Responsibilities

APPLICATION FOR SERVICE

A written, in-person, electronic, or oral application or contract, properly executed, will be required before Company is obligated to render electric service. Company may require any party applying for service to provide some or all of the following information for the party desiring service: full legal name, address, full Social Security Number or other taxpayer identification number, date of birth (if applicable), relationship of the applying party to the party desiring service, and any other information Company deems necessary for legal, business, or debt-collection purposes. Company shall have the right to reject for valid reasons any such application or contract, including the applying party's refusal to provide requested information.

All applications for service shall be made in the legal name of the party desiring the service.

Where an unusual expenditure for construction or equipment is necessary or where the proposed manner of using electric service is clearly outside the scope of Company's rate schedules, Company may establish special contracts giving effect to such unusual circumstances. Customer accepts that non-standard service may result in the delay of required maintenance or, in the case of outages, restoration of service.

TRANSFER OF APPLICATION

Applications for electric service are not transferable and new occupants of premises will be required to make application for service before commencing the use of electricity. Customers who have been receiving electric service shall notify Company when discontinuance of service is desired, and shall pay for all electric service furnished until such notice has been given and final meter readings made by Company.

CONTRACTED DEMANDS

For rate applications where billing demand minimums are determined by the Contract Demand Customer shall execute written Contract prior to rendering of service. At Company's sole discretion, in lieu of a written contract, a completed load data sheet or other written load specification, as provided by Customer, can be used to determine the maximum load on Company's system for determining Contract Demand minimum.

If Company or Customer terminates Customer's service under a rate schedule that contains demand charges and Customer subsequently applies to Company to reestablish service to the same premise or facility, Company must determine monthly billing demand for the reestablished service as though Customer had continuously taken service from the time of service termination through the reestablishing of service to Customer. For the purpose of determining the monthly billing demand described in the preceding sentence, the demand to be used for the period during which Customer did not take service from Company shall be the actually recorded demand, if any, for the premise or facility during that period. The preceding two sentences will not apply if Company determines, in its sole discretion, that material changes to Customer's facilities, processes, or practices justify establishing a new Contract Demand for the reestablished service.

DATE OF ISSUE:

May 14, 2019

DATE EFFECTIVE: With Service Rendered

On and After May 1, 2019

ISSUED BY:

/s/ Robert M. Conroy, Vice President

State Regulation and Rates

Louisville, Kentucky

Issued by Authority of an Order of the Public Service Commission in Case No. 2018-00295 dated April 30, 2019

KENTUCKY PUBLIC SERVICE COMMISSION

Gwen R. Pinson

Executive Director Liven R. Runson

EFFECTIVE

5/1/2019

PURSUANT TO 807 KAR 5:011 SECTION 9 (1)

PSC STAFF EXHIBIT 10

T

P.S.C. Electric No. 13, Original Sheet No. 97

Terms and Conditions Customer Responsibilities

APPLICATION FOR SERVICE

A written, in-person, electronic, or oral application or contract, properly executed, will be required before Company is obligated to render electric service. Company may require any party applying for service to provide some or all of the following information for the party desiring service: full legal name, address, full Social Security Number or other taxpayer identification number, date of birth (if applicable), relationship of the applying party to the party desiring service, and any other information Company deems necessary for legal, business, or debt-collection purposes. Company shall have the right to reject for valid reasons any such application or contract, including the applying party's refusal to provide requested information.

All applications for service shall be made in the legal name of the party desiring the service.

Where an unusual expenditure for construction or equipment is necessary or where the proposed manner of using electric service is clearly outside the scope of Company's rate schedules, Company may establish special contracts giving effect to such unusual circumstances. Customer accepts that non-standard service may result in the delay of required maintenance or, in the case of outages, restoration of service.

TRANSFER OF APPLICATION

Applications for electric service are not transferable and new occupants of premises will be required to make application for service before commencing the use of electricity. Customers who have been receiving electric service shall notify Company when discontinuance of service is desired, and shall pay for all electric service furnished until such notice has been given and final meter readings made by Company.

CONTRACTED DEMANDS

For rate applications where billing demand minimums are determined by the Contract Demand Customer shall execute written Contract prior to rendering of service. At Company's sole discretion, in lieu of a written contract, a completed load data sheet or other written load specification, as provided by Customer, can be used to determine the maximum load on Company's system for determining Contract Demand minimum.

If Company or Customer terminates Customer's service under a rate schedule that contains demand charges and Customer subsequently applies to Company to reestablish service to the same premise or facility, Company must determine monthly billing demand for the reestablished service as though Customer had continuously taken service from the time of service termination through the reestablishing of service to Customer. For the purpose of determining the monthly billing demand described in the preceding sentence, the demand to be used for the period during which Customer did not take service from Company shall be the actually recorded demand, if any, for the premise or facility during that period. The preceding two sentences will not apply if Company determines, in its sole discretion, that material changes to Customer's facilities, processes, or practices justify establishing a new Contract Demand for the reestablished service.

DATE OF ISSUE: November 25, 2020

DATE EFFECTIVE: With Service Rendered

On and After May 1, 2019

ISSUED BY:

/s/ Robert M. Conroy, Vice President

State Regulation and Rates

Louisville, Kentucky

Issued by Authority of an Order of the Public Service Commission in Case No. 2018-00295 dated April 30, 2019

*Honorable Allyson K Sturgeon Managing Senior Counsel - Regulatory & LG&E and KU Energy LLC 220 West Main Street Louisville, KENTUCKY 40202 *Emily W Medlyn General Attorney U.S. Army Legal Services Agency Regul 9275 Gunston Road Fort Belvoir, VIRGINIA 22060 *John Horne
Office of the Attorney General Office of Rate
700 Capitol Avenue
Suite 20
Frankfort, KENTUCKY 40601-8204

*Angela M Goad Assistant Attorney General Office of the Attorney General Office of Rate 700 Capitol Avenue Suite 20 Frankfort, KENTUCKY 40601-8204 *Thomas J FitzGerald Counsel & Director Kentucky Resources Council, Inc. Post Office Box 1070 Frankfort, KENTUCKY 40602 *Honorable Kurt J Boehm Attorney at Law Boehm, Kurtz & Lowry 36 East Seventh Street Suite 1510 Cincinnati, OHIO 45202

*Barry Alan Naum Spilman Thomas & Battle, PLLC 1100 Brent Creek Blvd., Suite 101 Mechanicsburg, PENNSYLVANIA 17050 *G. Houston Parrish Labor Law Attorney Office of the Staff Judge Advocate, B 50 3rd Avenue Fort Knox, KENTUCKY 40121 *Honorable Kendrick R Riggs Attorney at Law Stoll Keenon Ogden, PLLC 2000 PNC Plaza 500 W Jefferson Street Louisville, KENTUCKY 40202-2828

*Clay A. Barkley Strobo Barkley PLLC 239 South 5th Street Ste 917 Louisville, KENTUCKY 40202 *Jeff Derouen 200 S. 5th St. Suite 200 N Louisville, KENTUCKY 40202 *Larry Cook Assistant Attorney General Office of the Attorney General Office of Rate 700 Capitol Avenue Suite 20 Frankfort, KENTUCKY 40601-8204

*Carrie H Grundmann Spilman Thomas & Battle, PLLC 110 Oakwood Drive, Suite 500 Winston-Salem, NORTH CAROLINA 27103 *James W Gardner Sturgill, Turner, Barker & Moloney, PLLC 333 West Vine Street Suite 1400 Lexington, KENTUCKY 40507 *Lauren Givhan 200 S. 5th St. Suite 200 N Louisville, KENTUCKY 40202

*Don C A Parker Spilman Thomas & Battle, PLLC 1100 Brent Creek Blvd., Suite 101 Mechanicsburg, PENNSYLVANIA 17050 *Jody M Kyler Cohn Boehm, Kurtz & Lowry 36 East Seventh Street Suite 1510 Cincinnati, OHIO 45202 *Matt Partymiller
President
Kentucky Solar Industries Association
1038 Brentwood Court
Suite B
Lexington, KENTUCKY 40511

*Honorable David Edward Spenard Strobo Barkley PLLC 239 South 5th Street Ste 917 Louisville, KENTUCKY 40202 *Joe F. Childers Childers & Baxter PLLC 300 Lexington Building, 201 West Sho Lexington, KENTUCKY 40507 *Matthew Miller Sierra Club 50 F Street, NW, Eighth Floor Washington, DISTRICT OF COLUMBIA 20001 *J. Michael West Office of the Attorney General Office of Rate 700 Capitol Avenue Suite 20 Frankfort, KENTUCKY 40601-8204

*Louisville Gas and Electric Company 220 W. Main Street P. O. Box 32010 Louisville, KY 40232-2010

*Honorable Michael L Kurtz Attorney at Law Boehm, Kurtz & Lowry 36 East Seventh Street Suite 1510 Cincinnati, OHIO 45202 *M. Todd Osterloh Sturgill, Turner, Barker & Moloney, PLLC 333 West Vine Street Suite 1400 Lexington, KENTUCKY 40507

*Rick LoveKamp Kentucky Utilities Company 220 W. Main Street P. O. Box 32010 Louisville, KY 40202

*Honorable Robert C Moore Attorney At Law Stites & Harbison 421 West Main Street P. O. Box 634 Frankfort, KENTUCKY 40602-0634

*Robert Conroy Vice President, State Regulation and Rates LG&E and KU Energy LLC 220 West Main Street Louisville, KENTUCKY 40202

*Randal A. Strobo Strobo Barkley PLLC 239 South 5th Street Ste 917 Louisville, KENTUCKY 40202

*Sara Judd Senior Corporate Attorney LG&E and KU Energy LLC 220 West Main Street Louisville, KENTUCKY 40202