

Form for filing rate schedules

FOR: ENTIRE TERRITORY SERVED
P.S.C. KY. NO. 5

SOUTH KENTUCKY R.E.C.C.
SOMERSET, KENTUCKY 42501

* APPENDIX A *

UNDERGROUND COST DIFFERENTIAL

A Sub-division of which 113 lots are served Underground.

The line designed at 7.2 KV Primary Voltage, using loop feed:

Underground Cost per Foot	\$8.78
Overhead Cost per Foot	2.70

Average Cost Differential	\$6.08
	=====

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

MAY 01 1987

UNDERGROUND COST COMPUTATION

PURSUANT TO 207 KAR 5:011,
SECTION 9 (1)

BY: *J. Slaghegan*

	Footage	Material	Estimated: Trench, Sand Backfill, Backhoe	Initial Labor & overhead	Total Cost
Job	-----	-----	-----	-----	-----
Totals	33,518	\$95,861.48	\$69,294.93	\$129,044.30	\$294,200.71
Cost per Foot		2.86	2.07	3.85	8.78

TYPICAL ROCK CLAUSE: An additional \$47.67 per linear trench foot shall be charged where extreme rock conditions are encountered, such conditions being defined as limestone or other hard stratified material in a continuous volume of at least one cubic yard or more which cannot be removed using ordinary excavation equipment.

DATE OF ISSUE: MAY 29, 1987

DATE EFFECTIVE: MAY 1, 1987

ISSUED BY: *J. Keith Sloan*, MANAGER
SOUTH KENTUCKY R.E.C.C., P. O. BOX 910, SOMERSET, KENTUCKY 42501

C 3-89