

SO₃ Mitigation Study for

Ghent 1, 3, & 4

Mill Creek 3 & 4

Trimble County 1

Steve Katzberger

Study Manager
(312) 269-6672
(312) 269-2499 – Fax
steve.m.katzberger@sargentlundy.com

March 29, 2006

LG&E/KU

FINAL REPORT SL-008736 – Revision 2
SO₃ Mitigation Study
Ghent 1,3&4, Mill Creek 3&4,
and Trimble County 1


Pam Orlando, PE
Senior Mechanical Engineer II
Generation Services
Kentucky Utilities Company
One Quality Street
Lexington, Kentucky 40507

Dear Ms. Orlando:

Attached, for your use, is Sargent & Lundy's FINAL SO₃ Mitigation Study Report for Ghent – Units 1,3&4, Mill Creek – Units 3&4, and Trimble County – Unit 1, Rev. 2. We have revised the report to include an additional table per your comments. There were no revisions made to any of the report attachments, therefore I am not re-sending them.

Please contact me at (312) 269-6672 if you have any questions regarding this work. We appreciate this opportunity to provide our services to LG&E/KU.

Yours very truly,



Steve M. Katzberger
Study Manager

SMK:ljr
Enclosures - All
Copies:
R. Presnak
W. DePriest
Project File

K:\LG&E Energy WKES03 MITIGATION STUDY\final report\SO3 Mitigation Study-Final Report-Transmittal Ltr 032906 .doc

**SO₃ Mitigation Study –
Ghent – Units 1, 3&4, Mill Creek – Units 3&4,
and Trimble County – Unit 1**

Prepared for:

Louisville Gas & Electric Company/Kentucky Utilities Company

Subsidiaries of:



REPORT SL-008736

March 29, 2006



55 East Monroe Street
Chicago, IL 60603-5780
United States of America




LEGAL NOTICE

This report was prepared by Sargent & Lundy^{LLC}, hereafter referred to as Sargent & Lundy, expressly for LG&E/KU. Neither Sargent & Lundy nor any person acting on their behalf (a) makes any warranty, express or implied, with respect to the use of any information or methods disclosed in this report or (b) assumes any liability with respect to the use of any information or methods disclosed in this report.


APPROVAL PAGE

Preparer: 
S. Dave

Date: 03-29-06
03-29-06

Reviewer: 
S. M. Katzberger

Date: 3-29-06
03-29-06

Approver: 
R. Presnak

Date: 3-29-06
03-29-06





Table of Contents

1.	INTRODUCTION.....	1
1.1	BACKGROUND.....	1
1.2	SO ₃ FORMATION.....	2
2.	DESIGN BASIS.....	4
2.1	DESIGN PARAMETERS.....	4
3.	TECHNICAL DESCRIPTIONS.....	9
3.1	INTRODUCTION.....	9
3.2	ALKALINE ADDITIVES ON THE COAL BELT.....	9
3.3	SORBENT INJECTION.....	10
3.3.1	Ammonia.....	11
3.3.2	Humidification Water.....	12
3.3.3	Hydrated Lime.....	13
3.3.4	Magnesium Hydroxide.....	14
3.3.5	Magnesium Oxide.....	15
3.3.6	Micronized Limestone.....	15
3.3.7	Sodium Bisulfite.....	16
3.3.8	Soda Ash.....	17
3.3.9	Trona.....	17
3.4	WET ELECTROSTATIC PRECIPITATOR (ESP).....	18
3.4.1	Horizontal Flow - Wet ESP Supported from Grade.....	19
3.4.2	Vertical Flow - Wet ESP on Absorber Tower.....	20
3.5	LOW CONVERSION CATALYST.....	21
3.6	COMBINATIONS OF SORBENT INJECTION TECHNOLOGIES.....	22
4.	RISK ASSESSMENT.....	24
4.1	IMPACT ON ESP PERFORMANCE.....	24



4.2	IMPACTS OF SORBENTS ON FLY ASH SALABILITY.....	25
4.3	IMPACTS ON GYPSUM SALABILITY	25
4.4	SUMMARY OF POTENTIAL RISKS FOR EACH TECHNOLOGY	25
5.	COST ANALYSES.....	30
5.1	INTRODUCTION.....	30
5.2	ECONOMIC PARAMETERS	30
5.3	ESTIMATED COST BASES.....	31
5.3.1	Structural Basis	31
5.3.2	Electrical Basis.....	32
5.3.3	Mechanical Basis.....	34
5.4	ESTIMATED FIRST YEAR O&M COSTS.....	36
6.	CONCLUSIONS AND RECOMMENDATIONS.....	38
7.	EXHIBITS.....	40
7.1	EQUIPMENT LIST	40
7.2	FLOW DIAGRAMS	40
7.3	ESP DESIGN DATA	40
8.	APPENDICES.....	41
8.1	CAPITAL COST ESTIMATES.....	41
8.2	ANNUAL O&M COSTS	41
9.	DRAWINGS	42



1. INTRODUCTION

1.1 BACKGROUND

Louisville Gas & Electric/Kentucky Utilities (LG&E/KU) authorized Sargent & Lundy^{LLC} to prepare a study for the mitigation of sulfur trioxide (SO₃) at Ghent 1,3&4, Mill Creek 3&4, and Trimble County 1. Ghent Power Plant includes four pulverized coal units. Units 1,3&4 are each rated at 511 MW_{net}. An FGD system is currently being installed for Unit 3, with future FGD installations for Units 1&4 in the planning stages. The existing FGD system on Unit 1 will be switched to serve Unit 2. Units 1,3&4 each have SCR systems installed and operating. Ghent – Unit 2, which does not have an SCR or FGD system, was excluded from the study. Mill Creek Power Plant includes four pulverized coal units. Unit 3 is rated at 386 MW_{net}, while Unit 4 is rated at 490 MW_{net}. Both units currently have FGD systems and SCR systems installed and operating. Trimble County Power Plant includes one pulverized coal unit, with a future unit in the planning stages. Unit 1 is rated at 495 MW_{net} and currently has FGD and SCR systems installed. The FGD systems will allow these units to burn high sulfur coal, while still meeting sulfur dioxide (SO₂) emission limits. The high sulfur coal, combined with the recently installed Selective Catalytic Reduction (SCR) systems, will produce higher levels of sulfur trioxide. While the SCR systems are currently operated during the ozone season (May-November), they will be required to operate year round starting in 2009.

Ghent 3&4 are equipped with hot-side electrostatic precipitators (ESPs). The other units all have cold-side ESPs. The hot-side ESPs potentially limit the sorbent injection options for Ghent 3&4 to injection in the furnace or upstream of the ESP. However, there are emerging strategies, such as hydrated lime injection downstream of a hot-side ESP with collection of reaction products and excess sorbent in the FGD system. These methodologies are unproven and the results of testing are as yet unpublished.

The SO₃, combined with moisture in the flue gas, produces sub-micron size sulfuric acid (H₂SO₄) particles, which cause higher visible opacity. The sulfuric acid aerosol particles cause increased corrosion of the air preheater, electrostatic precipitator and the flue gas and combustion air ductwork downstream of the air preheater. They also produce a denser, more visible, more persistent plume which may have a blue color



(blue plume) or orange-brown color depending on sky conditions. The sulfuric acid particles may also increase the tendency of the plume to touch down near the plant.

For this study, S&L investigated currently available SO₃ control technologies and their potential application at each unit. Station staff provided plant conditions (flue gas flow rates, coal firing rates, SCR design parameters, ESP design parameters, flue gas temperatures, coal analyses, etc.). This study combines a review of the technical feasibility of each technology with estimated capital costs of the feasible alternatives to provide technical and cost data which LG&E/KU can use to evaluate life cycle cost and select the most cost-effective SO₃ mitigation technologies for each unit.

1.2 SO₃ FORMATION

The oxidation of SO₂ to SO₃ occurs in two phases: 1) homogeneous gas phase reaction with oxygen radicals in the furnace, and 2) heterogeneous reaction with oxygen aided by the SCR catalyst. Higher sulfur coals produce more SO₂ and consequently higher SO₃ than low-to-medium sulfur coals. During combustion, a small percentage (~1-1.4% for the LG&E/KU units) of the SO₂ produced during combustion reacts further with oxygen radicals to form SO₃ in the furnace. Additional SO₃ is produced when SO₂ is oxidized by the catalyst in the SCR. The rate of oxidation of SO₂ to SO₃ is guaranteed by the catalyst supplier. The total oxidation by the SCR catalyst increases as additional catalyst layers are added. LG&E/KU's SCR catalysts have relatively high oxidation rates.

Virtually all of the sulfur trioxide gas combines with available water vapor in the flue gas to create both vapor-phase and condensed sulfuric acid (H₂SO₄) as the flue gas is cooled in the air preheater. At high SO₃ levels in the flue gas, significant amounts of H₂SO₄ can condense in the air preheater. The quantity of visible sulfuric acid droplets, which increase opacity, is dependent on both the acid dew point temperature and the concentration of H₂SO₄ in the flue gas. Relatively high concentrations of sulfuric acid in the flue gas from the air preheater to the stack may also cause corrosion, fouling, and plugging, all of which may require changes in operation or additional equipment to reduce the sulfuric acid concentration to a tolerable level. The rapid quenching of flue gas temperature in the FGD system forms sub-micron aerosol H₂SO₄ particles that are difficult to capture in the FGD system. In addition to increased equipment degradation,



condensed sulfuric acid particles increase opacity and can create a visible blue or orange-brown plume upon leaving the stack.



2. DESIGN BASIS

2.1 DESIGN PARAMETERS

A design basis was established jointly between S&L, LG&E/KU and station personnel for the SO₃ mitigation study. Information provided by LG&E/KU indicated expected SO₃ concentrations leaving the existing air preheaters of 46-69 ppmdv and leaving the FGD systems (existing and planned) at 31-51 ppmdv. The target SO₃ concentration at the stack exit was set at 5 ppm, which is the recommended level for low stack opacity (no visible plume). Below 5 ppm SO₃, the existing cold-side ESPs may exhibit performance degradation. The study basis includes a 1% conversion of SO₂ to SO₃ in the furnace (1.39% for Trimble County – Unit 1) and another 1.2% (2 layers) to 2.1% (3 layers) conversion in the SCR catalyst. Approximately 30-40% reduction of SO₃ across the air preheater for units with cold-side ESPs, depending on the air heater exit temperature, and 10% for units with hot-side ESPs, 25% reduction of SO₃ in the FGD system and a 5 ppm reduction of SO₃ in the existing electrostatic precipitators. The sorbent injection technologies typically take credit for any SO₃ reduction occurring in the air preheater (for upstream injection) and the electrostatic precipitator. The study is based on year round operation of the SCR and the SO₃ mitigation technology. The design basis included ambient conditions, current and future coal and flyash analyses, heat balance information (heat rate, coal firing rate, heat input, etc.), design conditions (temperature and pressures), catalyst oxidation rates and other pertinent data as shown in Table 2.1. The majority of design basis data was obtained from the recent SCR program design data.

Table 2.1: Design Parameters

	Heat Input to Boiler, MBtu/hr	SO ₂ Inlet, lb/MBtu
Ghent 1	5,132	6.25
Ghent 3	5,132	6.25
Ghent 4	5,132	6.25
Mill Creek 3	4,175	6.80
Mill Creek 4	4,857	6.80
Trimble County 1	5,172	5.55
SO ₃ in-furnace conversion - %	1.00	All xc TC1
SO ₃ in-furnace conversion - %	1.39	%, Trimble County 1
Catalyst SO ₂ to SO ₃ Oxidation, %	1.90	Ghent 1
Catalyst SO ₂ to SO ₃ Oxidation, %	1.50	Ghent 3
Catalyst SO ₂ to SO ₃ Oxidation, %	1.50	Ghent 4



Catalyst SO ₂ to SO ₃ Oxidation, %	1.40	Mill Creek 3
Catalyst SO ₂ to SO ₃ Oxidation, %	1.20	Mill Creek 4
Catalyst SO ₂ to SO ₃ Oxidation, %	2.10	Trimble County 1
ESP SO ₃ reduction, ppm	5.00	All Units
Air Heater SO ₃ reduction, %	30	Ghent 1 and Trimble County 1
Air Heater SO ₃ reduction, %	10	Ghent 3&4
Air Heater SO ₃ reduction, %	40	Mill Creek 3&4
FGD SO ₃ reduction, %	25	All units



Table 2.1: Design Parameters (Continued)

Unit Size	Units	Ghent 1	Ghent 3	Ghent 4	Mill Creek 3	Mill Creek 4	Trimble County 1
Gas Flow	MW _{net}	511	511	511	386	490	495
Economizer Outlet	lb/hr (wet)	5,500,005	5,400,570	5,400,570	4,286,387	4,998,217	5,133,120
Air Heater Outlet	lb/hr	5,900,104	6,085,092	6,085,092	4,848,383	5,639,781	5,435,000
SO₂ to SO₃ Conv.							
Furnace	%	1.00	1.00	1.00	1.00	1.00	1.39
SCR Catalyst	%	1.90	1.50	1.50	1.40	1.20	2.10
SO₃ Concentration							
Economizer Outlet	lb/hr	401	401	401	355	413	499
	ppm	32.0	32.0	32.0	34.8	34.8	39.5
SCR Inlet	lb/hr	401	338	338	355	413	499
	ppm	32.0	27.0	27.0	34.8	34.8	39.5
SCR Outlet	lb/hr	1,163	940	940	852	908	1,252
	ppm	92.8	75.0	75.0	83.6	76.6	99.2
Air Heater Outlet	lb/hr	814	846	846	511	545	877
	ppm	65.0	67.5	67.5	50.1	46.0	69.4
FGD Inlet	lb/hr	751	846	846	460	486	813
	ppm	60.0	67.5	67.5	45.1	41.0	64.4
FGD Outlet	lb/hr	563	634	634	345	364	610
	ppm	45.0	50.6	50.6	33.9	30.7	48.3
Sorbent							
Ammonia							
Stoich. Ratio	1.25:1						
Feed rate	lb/hr	194	202	202	118	124	351
10-day Tank Size	ft (1:1.2)	11.3	11.5	11.5	9.6	9.7	13.8
Hydrated Lime							
Stoich. Ratio	10:1						
Feed rate	lb/hr	6,765	7,060	7,060	4,104	4,315	12,240
10-day Silo Size	ft (1:1.4)	15.8	16.1	16.1	13.4	13.6	19.3




	Units	Ghent 1	Ghent 3	Ghent 4	Mill Creek 3	Mill Creek 4	Trimble County 1
Mag. Hydroxide (Blr.)							
Stoich. Ratio	7:1						
Feed rate	lb/hr	3,726	3,888	3,888	2,260	2,377	6,741
10-day Tank Size	ft (1:1.2)	22.6	22.9	22.9	19.1	19.4	27.5
Sec. Containment.	ft. x ft.	41.4 x 5.5	42.3 x 5.5	42.3 x 5.5	32.3 x 5.5	33.1 x 5.5	43.1 x 5.5
Mag. Oxide							
Stoich. Ratio	7:1						
Feed rate	lb/hr	2,575	2,688	2,688	1,562	1,643	4,660
10-day Silo Size	ft (1:4)	9.9	10.1	10.1	8.4	8.5	12.1
Micronized Limestone							
Stoich. Ratio	7:1						
Feed rate	lb/hr	6,397	6,676	6,676	3,881	4,081	11,575
10-day Silo Size	ft (1:4)	15.0	15.2	15.2	12.7	12.9	18.3
Sodium Bisulfite							
Stoich. Ratio	2:1						
Feed rate	lb/hr	1,901	1,984	1,984	1,153	1,213	3,439
10-day Tank Size	ft (1:1.2)	20.1	20.4	20.4	17	17.3	24.5
Sec. Containment.	ft. x ft.	29.6 x 5.5	30.2 x 5.5	30.2 x 5.5	23.0 x 5.5	23.6 x 5.5	30.8 x 5.5
Trona							
Stoich. Ratio	3:1						
Feed rate	lb/hr	6,190	6,460	6,460	3,755	3,949	11,200
10-day Silo Size	ft (1:4)	16.0	16.3	16.3	13.6	13.8	19.6
Soda Ash							
Stoich. Ratio	1:1						
Feed rate	lb/hr	968	1,010	1,010	587	617	1,751
10-day Tank Size	ft (1:1.2)	15.2	15.4	15.4	12.8	13.1	18.5
Sec. Containment.	ft. x ft.	21.1 x 5.5	21.6 x 5.5	21.6 x 5.5	16.4 x 5.5	16.9 x 5.5	22.0 x 5.5

Secondary containment is required for all tanks; dimensions shown are length of the side of a square by the depth of the liquid. Wall heights are six (6) inches greater than the specified depth.



For the purposes of this study, the SO₃/H₂SO₄ in the flue gas will need to be reduced to 5 ppm or less to mitigate the “blue” plume phenomenon. Although limited data exists on the relationship between SO₃/H₂SO₄ concentration and plume visibility, a level of 5 ppm was selected, as it would eliminate the visible plume under most atmospheric conditions. Additional published data indicates that below 5 ppm H₂SO₄ in the flue gas, cold-side ESP performance may degrade. EPRI published a technical report, which includes a graph of the H₂SO₄ concentration in flue gas versus predicted opacity. The graph is reproduced here:



Source: EPRI SO₃ Mitigation Guide (TR-104424)

3. TECHNICAL DESCRIPTIONS

3.1 INTRODUCTION

The following are technical descriptions of the SO₃ mitigation technologies studied for use at Ghent – Units 1,3&4, Mill Creek – Units 3&4 and Trimble County – Unit 1. Four types of SO₃ mitigation technology options were considered:

- Alkaline additives on the coal belt
- Wet or dry sorbent injection
- Wet electrostatic precipitators (ESP)
- Switching to a low SO₂-to-SO₃ conversion SCR catalyst

The basic premise of the alkaline additive and sorbent injection options is to either condense the SO₃/H₂SO₄ on to the sorbent particles and flyash and collect it in the existing dry ESP or convert the SO₃/H₂SO₄ into a salt and collect the salts in the dry ESP. A wet ESP placed after the existing or proposed wet flue gas desulfurization (FGD) system collects acid mist and much of the remaining solid particles. A replacement low conversion rate catalyst used in the SCR will convert a smaller percentage of the SO₂ to SO₃ with the goal of staying under the visible plume threshold. Some SO₃ is normally condensed in the air preheater, on the fly ash in the precipitator and in the wet FGD system

3.2 ALKALINE ADDITIVES ON THE COAL BELT

Low sulfur coals with alkaline ash neutralize more SO₃ than coals with acidic ash. The SO₃ reacts with the alkaline components in the fly ash forming sulfates, which are then captured in the electrostatic precipitator (ESP). The use of alkaline additives on the coal belt introduces additional alkaline material in the furnace that then reacts with SO₃. Various alkaline materials including lime, limestone, dolomite, magnesium carbonate and proprietary products such as OmniClear™ from Omni Materials, Inc., may be added on the coal belt as it goes to the coal silos. OmniClear™ was tested at Cinergy's Gibson station.

The calcium-based materials are more likely to form hard deposits and have a negative impact on ESP performance. Calcium compounds have a co-benefit in tying up vapor-phase arsenic, which is a known catalyst poison. Magnesium-based materials are generally more effective at capturing SO₃ and form more friable, water-soluble deposits. Sodium and potassium compounds are catalyst poisons, so they are not used upstream of the catalyst.

The calcium- and magnesium-based alkaline materials are either added on the coal belt or pneumatically injected into the furnace through idle burners. The stoichiometries required can be as high as 30 to 40:1. Adding alkaline materials to the coal belt is a low capital cost option, which uses the coal mills to grind the sorbent to a fine powder. All of these materials mainly capture furnace-generated SO₃ and are not effective at capturing SCR-generated SO₃. In addition, alkaline additives may also modify the slagging and fouling tendencies of the coal ash and in some cases have produced unacceptable increases in slagging, increased LOI (burner injection) and increased furnace exit gas temperature. Higher furnace exit gas temperature increases the SCR catalyst activity, which increases the SO₂ to SO₃ conversion rate. For the above reasons, coal belt additives will not be considered in this study.

3.3 SORBENT INJECTION

Another method of SO₃ mitigation is sorbent injection. There are a variety of sorbents that can be added at various points in the flue gas path to remove SO₃ and reduce or eliminate the visible plume from the stack. The following sorbent injection technologies were considered in the study:

- Ammonia
- Humidification Water
- Hydrated Lime
- Magnesium Hydroxide
- Magnesium Oxide
- Micronized Limestone
- Sodium Bisulfite (SBS)

- Soda Ash
- Trona

All sorbent injection technologies, except furnace-injected Magnesium Hydroxide will be limited at Ghent Units 3&4 due to the existing hot-side ESPs, which are located upstream of the SCR. Injection of sorbents downstream of the ESPs adds particulate to the flue gas with only the wet FGD system remaining to capture the dust. As such, the quantity of sorbent which can be injected is limited by the FGD system's ability to collect particulate and remain in compliance with the particulate emission limit.

3.3.1 Ammonia

Ammonia injection into the flue gas upstream of the ESP will reduce SO₃, forming ammonia salts, mainly ammonium sulfate [(NH₄)₂SO₄] and ammonium bisulfate [NH₄HSO₄], depending on the reagent stoichiometric ratio applied. If the stoichiometric ratio of NH₃ to SO₃ is below one, the salts formed will generally be NH₄HSO₄, which is a sticky material known to cause air preheater and ESP fouling and plugging. The SCR systems can also cause this type of fouling, which is controlled by limiting ammonia slip to less than 2 ppm. Ammonia injection for SO₃ mitigation at stoichiometric ratios of between one and two tend to form predominantly (NH₄)₂SO₄ particles, which are not sticky and are collected in the ESP. Ammonia injection (at higher stoichiometries) upstream of the air preheater has a co-benefit of reducing air preheater fouling and the frequency and duration of air preheater washing.

The ammonia would be injected as an air/ammonia vapor mixture through a grid of nozzles in the ductwork entering or exiting the air preheater. Ammonia injection rates at NH₃:SO₃ molar ratios of 1.5:1 to 2.0:1 can theoretically achieve SO₃ reduction of 90% to 95%. The primary drawback of this technology is that if ammonia in the flyash or gypsum exceeds threshold values, neither may meet salability/reusability quality requirements. In addition, off-gassing of ammonia from the flyash can become a nuisance in the ash handling and disposal operations as the human nose can detect ammonia at levels as low as 5 ppm. If the levels of SO₃/H₂SO₄ being removed are too large (≥30 ppmv), then additional treatment may be required to reduce ammonia and decrease pH in the holding ponds where the flyash is disposed. Short term use of ammonia injection at plants with wet ash ponds could be investigated. The detrimental effects on the ash

pond depend on the rate and duration of ammonia feed, the volume of the ash pond and the starting chemistry of the ash pond. Acid addition could be used to control pH in the ash pond. This type of evaluation is beyond the scope of the present study.

This particular SO₃ mitigation technique is most practical where an existing SCR is in operation (NH₃ is already on-site), where the SO₃ concentration reduction required is under 30 ppmv, and the flyash is not sold, but rather is collected dry and landfilled. Ammonia alone may not be able to reduce the SO₃ concentration to the desired level at the stack exit without causing a nuisance for the plant ash handling and disposal operations. Ammonia injection is currently being used at AEP Cardinal - Units 1&2, but the units are currently burning a lower sulfur coal with no FGD. Ammonia alone is not a viable technology for reducing SO₃ from the levels estimated for the LG&E/KU sites to 5 ppmv, or less, at the stack exit due to the attendant side effects. At typical injection stoichiometries of 1.25:1, ammonia is capable of reducing 70% of SO₃ emissions at the stack, which is insufficient for the cases investigated in this study. The ammonia injection option will not be developed further in this study.

3.3.2 Humidification Water

Humidifying the flue gas upstream of the SCR or upstream of the air preheater with water injection can reduce SO₃ as follows: 1) injection upstream of the SCR reduces flue gas temperature entering the SCR and lowers the oxidation rate of the catalyst, or 2) injection upstream of the air preheater can lower the flue gas temperature below the acid dew point. This causes the sulfuric acid to condense on the sorbent particles (if used with sorbent injection) and flyash particles that can then be collected in the ESP or further downstream in the FGD system. The sorbent and flyash particles present in the flue gas provide surface area on which the sulfuric acid condenses. The sub-five micron sized particles provide a large surface area for sulfuric acid condensation.

Water injection upstream of the SCR may cause flyash to drop out in the ductwork or plug the catalyst and if not carefully controlled, at low loads, liquid water may damage the catalyst. Humidification upstream of the air preheater can cause corrosion or plugging of the air preheater and the downstream equipment due to



increased condensed sulfuric acid. Water injection upstream of the catalyst was tested at AEP Gavin Station, but discontinued due to flyash dropout in the ductwork. Humidification upstream of the electrostatic precipitator was tested by EPRI at the ECTC, but no results were reported. To date, no stations are using humidification water for SO₃ mitigation. Water injection alone will not reduce the SO₃ concentration enough to meet the desired SO₃ levels at the stack exit, with an expected maximum SO₃ reduction capability of 30%. Humidification was not considered in this study.

3.3.3 Hydrated Lime

Hydrated lime (Ca(OH)₂), injected pneumatically as a dry powder into the flue gas ductwork upstream of the existing cold-side, dry ESP, will react with SO₃ vapor and condensed sulfuric acid to form calcium sulfate salts that can be removed by the ESP. Injection rates vary between 1 lb/hr per 1,000 acfm with humidification to 2 lb/hr per 1,000 acfm without humidification to achieve 80%-85% reduction and as much as 5.6 lb/hr per 1,000 acfm for 95% reduction. This study used a sorbent injection molar ratio of 10:1 for 90% SO₃ reduction using a typical hydrated lime. Specially prepared hydrated limes having increased porosity may have lower stoichiometries. This option has certain drawbacks as the by-products increase fly ash resistivity, it requires a high stoichiometric ratio, and it needs long duct runs for reagent mixing. This option was used at AEP Gavin, but the maximum lime injection quantities (~2.5 tph) were limited by ESP performance.

Hydrated lime has high surface area per unit volume for better reaction with SO₃. However, hydrated limes vary greatly in surface area based on the characteristics of the limestone used to make the lime and the methods used to pressure hydrate the lime. Chemical Lime Company is now offering a specially prepared hydrated lime, called Sorbacal H™, which has very high surface area and excellent reactivity with SO₃. The cost of this product is also higher than a typical hydrated lime.

The use of a typical hydrated lime also exhibits some of the highest stoichiometric ratios required to achieve the desired removal, relative to other sorbents. Finally, because hydrated lime injection occurs after the air preheater, none of the potential air preheater corrosion issues would be eliminated. However, this would eliminate possible plugging of the air preheater caused by sulfate salts. Barring ESP limitations,

hydrated lime, alone, should be capable of reducing SO₃ to acceptable levels at the Mill Creek and Trimble County stations as well as Ghent Unit 1.

Injection of hydrated lime upstream of the wet FGD system at units with hot-side ESPs, such as Ghent 3&4, depends on capture of the added dust and reaction products in the wet FGD. This is reported to be used at Cinergy's East Bend – Unit 2. A wet FGD system has a limited capability for collection of particulate so the amount of hydrated lime injected would also be limited to avoid exceeding the particulate emission limit.

3.3.4 Magnesium Hydroxide

Magnesium hydroxide (Mg(OH)₂) is a magnesium compound injected as a slurry into the upper furnace for SO₃ control. Mg(OH)₂ loses its water of hydration in the furnace to become MgO that reacts with SO₃ to form magnesium sulfate which is collected by the dry ESP. This is a proven technology for SO₃ mitigation on oil-fired units, with the first full-scale installation over 30 years ago. Due to the injection location in the furnace, Mg(OH)₂ is most effective at reducing furnace-generated SO₃. It is less effective at reducing SO₃ emissions resulting from SCR oxidation. Alkali addition in the furnace also limits the amount of corrosion and other negative effects associated with having higher quantities of SO₃/H₂SO₄ in the system. Mg(OH)₂ is injected at Mg:SO₃ molar ratios of 4.5:1 based on the furnace outlet SO₃ concentration to achieve 90% reduction of furnace-generated SO₃. High ash resistivity may be a problem at high injection rates. Typically, this method of SO₃ removal is effective up to the range of 40% - 80% overall. A stoichiometry of 7:1 would be required to achieve 90% overall reduction of both furnace and SCR generated SO₃. The SO₃ mitigation efficiency is sensitive to the location and elevation of the injection into the boiler. Magnesium Hydroxide has been used at Bruce Mansfield 3, Gavin 1 and at Zimmer. Due to the high SO₂ concentration in the flue gas and the guaranteed conversion rate of the catalyst, it is unlikely that magnesium hydroxide injection into the furnace, alone, will reduce SO₃ to the desired concentrations at the stack outlet. Magnesium hydroxide may be a viable choice for Ghent – Units 3&4, the units equipped with hot-side ESPs.

3.3.5 Magnesium Oxide

Magnesium oxide (MgO) is pneumatically injected as a dry powder upstream of the air preheater, reacting with the SO₃/H₂SO₄ to create magnesium sulfate salts that are then collected by the cold-side ESP. Magnesium oxide has been tested at only a few power plants, although one supplier does cite examples of up to 80% removal at approximately a 7:1 stoichiometric ratio. High ash resistivity could be a problem for these salts, as this same problem is seen with the Mg(OH)₂ injection in the boiler when attempting high SO₃/H₂SO₄ removal efficiencies. The use of MgO injection alone for SO₃ mitigation may be limited by resistivity impacts on the ESP. MgO was not considered further in this study.

3.3.6 Micronized Limestone

Marsulex markets a technology called CleanStack™, which uses micronized limestone. The micronized limestone particles injected upstream of the air preheater, serve the dual purpose of reacting with the SO₃/H₂SO₄ to form calcium salts and providing additional surface area on which the acid mist can condense. This option would require modifications to the air preheater to lower the flue gas outlet temperature below the sulfuric acid dew point. The reacted and condensed upon particles are collected by the dry ESP and removed from the system. The major benefit of using micronized limestone is the lower sorbent cost of limestone compared to lime, magnesium compounds or sodium compounds. A co-benefit of lowering the air preheater exit temperature is an improvement in unit heat rate. Micronized limestone has resistivity limitations similar to that of lime as both produce calcium sulfate reaction products which will increase flyash resistivity. Micronized limestone depends on small particle size to create surface area where hydrated lime has high porosity as well as small particle size.

There is no field experience with micronized limestone for SO₃ mitigation. A demonstration system is being installed at Dominion Energy's Chesterfield – Unit 5 for start-up in the first quarter of 2006. This technology was modeled based on measured SO₃ data from a 315 MW unit. In addition to lowering the exit temperature of the air preheater to below the acid dewpoint, additional proprietary modifications to the air preheater must be performed including the installation of Alstom's ClearFlow™ heat transfer elements. This includes converting the cold-end and intermediate layers of the air preheater to a combined cold-end

layer, changing the profile of the cold-end elements, using enamel coated elements and removing some element support grids. Due to the absence of a full scale demonstration of micronized limestone, it is unknown whether this technology, used alone, or in conjunction with humidification water, will reduce SO₃ concentrations to the desired levels. Expected SO₃ removal efficiencies for this technology are 70% based upon injection stoichiometric ratios of 7:1. This option was not considered further in this study.

3.3.7 Sodium Bisulfite

Sodium Bisulfite (SBS) can be injected into the flue gas stream upstream or downstream of the air preheater, or upstream of an FGD system as a 10 wt% solution using dual fluid atomizers. The SBS reacts with the SO₃ present in the flue gas to form sodium salts, which are then collected by the existing dry ESP or in the FGD system. SBS has been used at three commercial installations, First Energy's Bruce Mansfield Station, Tennessee Valley Authority's (TVA) Widows Creek Unit 7, and Cinergy's Gibson Station as well as in full-scale testing at Vectren Corporation's A. B. Brown Station and in one duct at AEP's Gavin Unit 1.

The full-scale testing indicates SO₃/H₂SO₄ removal capability down to approximately 2 ppm to 10 ppm with reagent stoichiometry of 1.5:1 to 2.0:1. For this study, a sorbent injection molar ratio of 2.0 was used. Air preheater fouling and dust dropout in the ductwork have been reported by the operating facilities. Weekly cleaning of the dual fluid atomizers is required. The SBS is a byproduct of the double alkali scrubber at Vectren's A. B. Brown Station. The SBS process is patented by URS/Codan Associates. An annual licensing payment of \$200/MW/year has been included in the O&M costs associated with this option. The byproduct SBS currently comes from a single source of supply although commercial sodium sulfite or soda ash can be used in its place. Sodium sulfite is a more costly sorbent than SBS.

The sodium-based sorbents have no detrimental impact on cold-side ESPs. The lower stoichiometries of sodium-based sorbents result in less total dust added than the calcium or magnesium sorbents and sodium is an ESP conditioning agent.



SBS could be injected upstream of the FGD systems at Ghent – Units 3&4 with the reaction products being collected in the scrubber. Because SBS has a lower stoichiometry than calcium and magnesium sorbents, the total dust load to the FGD would be smaller. Testing would be needed at Ghent to demonstrate the effectiveness of SBS injection upstream of the FGD before being permanently installed.

3.3.8 Soda Ash

URS/Codan recently developed another means of producing SBS in-situ by injecting soda ash (Na₂CO₃) solution into the ductwork through dual fluid atomizers. Within the flue gas ductwork, the soda ash combines with SO₂ to produce SBS and sodium sulfite. Both of these products react with SO₃ molecules present to form sodium bisulfate. The dual sorbent process is installed at Cinergy's Gibson Units 1-5. Tests at the Gibson Station indicate 40%+ removal, with the SCR in service, at stoichiometric ratios of 1.5:1. This system has also been installed at Pennsylvania Power & Light's Montour Station, Units 1&2. Because either SBS or soda ash can be injected in this system, while still meeting desired outlet concentrations, this system is more flexible than many of the other sorbent injection systems. This process would also include an annual licensing fee of \$200/MW/year.

3.3.9 Trona

Sodium sesquicarbonate (Na₂CO₃•NaHCO₃•2H₂O) or "Trona" is a naturally occurring mineral which is commercially known as Solvair Select 200 (minus 200 mesh particle size) and is supplied as a powder that is pneumatically injected into the ductwork upstream of the air preheater through a grid of injection nozzles (Section 7.2.3). The Trona reacts with the SO₃/H₂SO₄ and creates sodium salts that are collected in the existing dry ESP. SO₃ reduction of up to 90% is achievable at molar ratios of 3.0:1. Trona is being used at AEP's Gavin Unit 1 and has been tested at AEP Zimmer with promising results. Trona has had no detrimental effects and may even have had a slight beneficial effect on the performance of the existing ESPs. Some drop out and accumulation of solids in the ductwork has occurred at Gavin. The solids deposits are friable, so soot blowers or acoustic horns may be needed to break up and re-entrain these deposits. Trona is mined in the Green River, Wyoming area and would be shipped by rail to the site or to a central point in the Louisville area where the Trona could be transferred from rail to truck for delivery to



the sites. Trimble County has no rail capability. A shortage of locomotives was reported to be a problem in obtaining shipments of Trona to the Zimmer site. While there are several companies mining Trona from the Green River area to produce soda ash, only one (Solvay Chemicals) currently produces Trona with the required particle size needed for SO₃ capture.

If Trona is selected for use at multiple LG&E/KU sites, a central rail delivery point could be considered for long term storage with truck distribution to each site. The study did not include the cost of a central storage and transfer facility. AEP has applied for a patent on this process, so a licensing fee may also be required.

Preliminary testing has been conducted at Mirant's Potomac River Station to test the effectiveness of Trona injected upstream of the hot-side precipitator. These tests, whose results were published in January 2006, were done to test the removal of SO₂ and did not include measures to test SO₃ removal. Additionally, the Potomac River Station does not currently have an SCR installed and is running a dry stack. Future testing is planned and will include testing for SO₃ removal.

3.4 WET ELECTROSTATIC PRECIPITATOR (ESP)

A wet ESP is typically installed between the FGD absorber and the stack, removing most of the remaining flyash as well as the condensed sulfuric acid. The wet ESP may be supported independently from grade for horizontal gas flow or mounted on the top of the absorber for vertical gas flow. The deciding factor on whether to use a horizontal or vertical flow lies in the tradeoff between the extra ductwork and footprint needed to install the wet ESP supported from grade and the structural and foundation alterations necessary to put the wet ESP on top of the FGD absorber. In either arrangement the wet ESP can very effectively capture sulfuric acid aerosols (90+%). Wet ESPs have been used for many years in the metallurgical and other non-utility industries, at the AES Deepwater cogeneration plant in Houston since 1986 and at Xcel Energy's Sherbourne County Station. A wet ESP was installed on top of an FGD absorber at New Brunswick Power's Coleson Cove and Dalhousie plants, started up in 2004, and Wisconsin Energy recently selected wet ESPs for their new plant, the 1,000 MW Elm Road project.



Wet ESPs operate in a three-step process that includes charging the entering particles, collection of the particles on oppositely charged plates, and cleaning the collection surfaces. While a dry ESP uses mechanical cleaning (rapping) of the collecting plates, a wet ESP uses either an intermittent or continuous water wash. The advantages of a wet ESP include an increased power level (2 W/acfm as opposed to 0.1 to 0.5 W/acfm with a dry ESP) and reduced particle re-entrainment because a wet ESP does not need rapping of the collecting plates. In addition to the auxiliary power used, the wet ESP uses clean water for washing the plates and may use MgO to neutralize the wash water for reuse or consume some of the FGD reagent (limestone) if drained to the FGD system. The wet ESP also has potential co-benefits in the collection of fine fly ash particles and particulate mercury. Wet ESPs require the use of costly acid-resistant materials of construction for ductwork and ESP internals. The vertical flow wet ESPs typically require more corrosion resistant materials than horizontal flow wet ESPs because they are washed intermittently rather than continuously. Ghent – Units 3&4 are good candidates for wet ESPs based on the limited applicability of sorbent injection alternatives since these units have existing hot-side ESPs.

3.4.1 Horizontal Flow - Wet ESP Supported from Grade

The horizontal flow wet ESP would be supported from grade between the FGD absorber and the stack. Additional ductwork is necessary between the FGD absorber and the wet ESP and again between the wet ESP and the stack. The horizontal flow wet ESP can be elevated above access roads, for example, to alleviate the larger footprint required, but the cost of support steel, foundations and piles would be higher. In the horizontal flow wet ESP, a conventional plate and wire configuration is used. The wastewater from the wet ESP can be added to an existing wastewater treatment system, treated with MgO and recycled or sent to the ash pond or added to the FGD reaction tank. The horizontal flow wet ESP takes considerable footprint area on site, which is limited at Ghent and Mill Creek. The horizontal flow wet ESP for each unit is 90% efficient, with 230,000 sq. ft. of collecting area, three fields in series, 12 transformers, horizontal inlet and horizontal outlet in a double deck arrangement. Ductwork from the top of the absorber is included. The ESP casing, roof, and sidewalls, inlet and outlet nozzles, collecting plate assemblies and water wash collection pans are constructed of A2205 stainless steel. External stiffeners and support steel are constructed of A572 grade 50 steel. Water spray nozzles are polypropylene plastic. Mill Creek – Units



3&4 and Trimble County – Unit 1 are good candidates for a horizontal flow wet ESP. These units each have multiple FGD absorbers, so they are not easily equipped with vertical flow wet ESPs. Arrangement drawings are attached in Appendix 8. The layouts shown for Ghent – Units 1&4 horizontal wet ESPs included moving the location of the chimneys to make room for the wet ESP between the FGD and the chimney. Because the FGDs and chimneys have not been purchased yet, no costs were added for moving the chimneys.

3.4.2 Vertical Flow - Wet ESP on Absorber Tower

The vertical flow wet ESP would be built directly on top of the FGD absorber. It can be supported by the absorber structure (future Ghent – Units 1&4 FGD) or supported from a separate steel structure above the absorber (Ghent – Unit 3). In a vertical flow design, bundles of tubes would serve as the collection area while a wire running down the center of each tube would provide the necessary electrical discharge. The use of water in the wet ESP reduces particle re-entrainment and solves the limitation present in the dry ESP. Due to the rapid cooling and humidification of the flue gas in the FGD system, the remaining sub-micron H₂SO₄ mist in the flue gas not captured by the FGD system is collected in the wet ESP. In addition to the sulfuric acid mist, the wet ESP can remove much of the flyash remaining in the flue gas as well as any scrubber carryover. One drawback to the system is that the liquid waste will be drained through collection troughs and piping to the FGD reaction tank, adding a small amount of acid that would require neutralization as well as a small quantity of trace metals and flyash, which may alter process chemistry.

Due to the extra weight of the system, the foundation and structural steel for the scrubber would have to be designed to carry this load as well as that of the scrubber. Also, the chimney would have to include a breeching opening at a higher elevation to accept the outlet duct from the wet ESP. The chimney liner would be about 60 feet shorter due to the higher breeching opening. However, this design also greatly reduces the quantity of ductwork required, as opposed to the horizontal flow design wet ESP. This process is simplified for Ghent Units 1&4 in that the FGD towers are not yet designed or constructed, so the wet ESP can be planned and engineered for from the beginning. For Ghent - Unit 3, the foundation for the absorber has been designed to support the load of a future WESP, but would require significant structural

steel as the FGD tower was not designed to support the load. The cost of independent structural steel support, foundations and piles were included, as applicable. Arrangement drawings are attached in Appendix 8.

The vertical wet ESP for each unit is 90% efficient, with four chambers (each field is divided into four quadrants of the circular cross section casing) and three collection fields in series. Because the vertical wet ESP is washed intermittently rather than continuously like the horizontal wet ESP, the collecting electrodes will be constructed of C-276 for all fields. The discharge electrode frames, top suspension frames, lower alignment frames and wash water piping will be constructed of C-276 for the first field and 6% moly stainless steel for the remaining fields. The insulator compartments will be 304 stainless steel. The vertical wet ESP will be equipped with 12 transformer/rectifier sets each rated at 110kV peak and 1,250 mA. The cost of the vertical flow wet ESP is higher due to the use of C-276 for all three fields. If lesser alloys are used for fields two and three, the cost could be reduced.

3.5 LOW CONVERSION CATALYST

Another option for reducing the levels of SO₃ in the flue gas leaving the SCR is to change to a catalyst with a lower conversion (oxidation) rate of SO₂ to SO₃. The catalyst could be replaced all at once or one layer at a time as part of the current catalyst management system. SO₂ oxidation increases with the Vanadium content of the catalyst and the operating temperature of the catalyst. Haldor-Topsoe, a catalyst supplier, also reports that the presence of iron in the fly ash increases the oxidation of SO₂ to SO₃. In addition, other impurities in the catalyst can increase oxidation. The LG&E/KU SCRs have relatively high conversion rate catalysts, ranging from 1.2% to 2.1% with all catalyst layers installed.

The catalyst manufacturers have been developing low conversion rate catalysts. One supplier quoted rates as low as 0.2% with zero dust, but the conversion rate is highly temperature dependent. Haldor-Topsoe reports low conversion rates for their catalyst at Harrison (<0.3%), Cayuga (<0.5%) and at Elmer Smith (<0.3%).



The use of low conversion rate catalyst at Ghent – Units 3&4 is an option that must be considered because the hot-side ESPs preclude injecting large quantities of sorbent after the ESP. If Mg(OH)₂ were injected in the furnace to remove 90% of the furnace generated SO₃ and a 0.6% or less conversion rate catalyst was installed, SO₃ could be reduced to 5.6 to 8.5 ppm at the stack.

The low conversion catalyst is also a less active catalyst for NO_x reduction. This means that more catalyst volume (~15%) may be needed, or the catalyst life may be shorter and a cost would be incurred for both the initial purchase and more frequent replacement cost. The low conversion catalyst is also not able to achieve the required outlet SO₃ concentration by itself since some SO₃ is generated in the boiler prior to the SCR. So, a sorbent injection system would be needed anyway. A low conversion catalyst used in conjunction with a sorbent injection technology may be the lowest cost option. The study did not estimate the cost of catalyst replacement because LG&E/KU has recent pricing for replacement catalyst.

3.6 COMBINATIONS OF SORBENT INJECTION TECHNOLOGIES

Several of the sorbent injection technologies have limitations such as fly ash resistivity which prevent a single approach to achieving the goal of reducing SO₃ from estimated levels to 5 ppm or less. As such, combinations of technologies should be considered to achieve the desired SO₃ reduction. For example, Mg(OH)₂ injection in the furnace combined with hydrated lime or Trona injection ahead of the cold-side ESP may also be considered. However, the use of combinations of technologies increases the capital costs for multiple storage and injection systems. In addition, on-site space limitations may preclude multiple storage and injection systems. A combination of Mg(OH)₂ injection in the furnace and replacement of the SCR catalyst with a low SO₂ to SO₃ conversion catalyst and SBS injection upstream of the FGD system could also be considered for Ghent – Units 3&4. A table is included below summarizing the technology combinations which are likely to reduce SO₃ emissions at the stack outlet to the desired levels.

Table 3.1 Summary of SO₃ Mitigation Technology Efficiencies

Mitigation Technology (Stoich. Ratio)	Expected SO₃ Reduction Percentage
Ammonia 1.25:1	70%
Humidification Water ---	27%
Hydrated Lime 10:1	90%



Mitigation Technology (Stoich. Ratio)		Expected SO₃ Reduction Percentage
Magnesium Hydroxide (Blr.)	7:1	90% (Boiler-generated SO ₃)/40-60% overall
Magnesium Oxide	7:1	80%
Micronized Limestone	7:1	70%
Sodium Bisulfite	2:1	90%
Soda Ash	1:1	90%
Trona	3:1	90%
Wet ESP	---	90%
Low Conversion Catalyst	---	28-43% for LG&E/KU Sites
Combinations of Technologies		
Sorb. Inj. (US of AH) + Low Conv. Catalyst		95%
Mag. Hydroxide + Sorb. Inj. (US of AH)		95%
Wet ESP + Sorb. Inj. (US of AH)		95%
Wet ESP + Mag. Hydroxide		95%
Wet ESP + Low Conversion Catalyst		95%

Unit	Required SO ₃ Removal (%)
Ghent 1	90%
Ghent 3	90%
Ghent 4	90%
Mill Creek 3	87%
Mill Creek 4	85%
Trimble County 1	90%

4. RISK ASSESSMENT

The science and technology of SO₃ mitigation for power plants burning high sulfur coal equipped with SCR and wet FGD systems is currently evolving. Each of the technology options considered in this study has varying degrees of risk associated with it. The sorbent injection technologies can produce deposits in the ductwork, air preheater, and on turning vanes and internal struts and bracing. The dry sorbents typically produce dry deposits that should be controllable by soot blowers or acoustic horns. The wet sorbent technologies like SBS can produce harder deposits in both the air preheater and ductwork. Injection nozzles require regular inspection and cleaning. This adds a risk of increased maintenance, unplanned outages for cleaning and increased fan power. The low SO₂-to-SO₃ conversion rate catalyst option includes the risk of shorter catalyst life and increased long term catalyst replacement costs.

The process scale-up risk applies mainly to the sorbent injection technologies. The key parameters that must be demonstrated in a full-scale application include: the ability to adequately distribute and mix the sorbent in the furnace or ductwork for contact with the SO₃; the molar ratio of sorbent to SO₃ versus percent removal; undesirable side effects such as: dust dropout, buildup, air preheater plugging, ESP performance degradation, contamination of byproducts, increased furnace slagging and fouling, and regular maintenance of the injection nozzles; and the capital and O&M costs of the process at full scale. Some of the technologies have been demonstrated at full scale; others have not.

4.1 IMPACT ON ESP PERFORMANCE

A review of the existing ESPs and the original design parameters indicates that the concerns of increased fly ash resistivity and ESP performance degradation resulting from sorbent injection must be considered. The relative amount of sorbent added compared to the fly ash in the coal is very small. The existing ESPs were designed for much higher inlet grain loading than would result from any of the sorbent injection options. There will be adequate SO₃ in the flue gas to the ESPs to condition the ash and lower resistivity. SO₃ is a commonly used conditioning agent. There is a moderate risk associated with calcium-based sorbents, a lower risk with magnesium-based sorbents and very low risk with sodium-based sorbents. The

greatest risk of ESP performance degradation is for those ESPs with the smallest specific collecting areas (SCA). Only Trimble County – Unit 1 has a relatively large SCA.

4.2 IMPACTS OF SORBENTS ON FLY ASH SALABILITY

The calcium- and magnesium-based sorbents will have no significant impact on fly ash chemistry and its marketability. Sodium-based sorbents add water soluble sodium compounds to the fly ash, but not enough to affect its salability. Ammonia will definitely affect salability of the fly ash due to the ammonia odor imparted.

4.3 IMPACTS ON GYPSUM SALABILITY

The calcium-based sorbents are compatible with a commercial grade gypsum product. The gypsum buyers have established limits on the minimum CaSO₄ content and maximum CaCO₃ and MgCO₃ in the product. Very large quantities of limestone or magnesium compounds could dilute the gypsum purity or exceed the limits set on CaCO₃ or MgCO₃, but most of the sorbent will be captured by the existing ESP. Sodium and magnesium-based compounds are water soluble and will be washed out of the gypsum. Ammonia will be collected in the wet FGD system and appear in the gypsum. Some of the ammonia will be washed out of the gypsum, but if more than 5 ppm remains, salability will be negatively affected.

4.4 SUMMARY OF POTENTIAL RISKS FOR EACH TECHNOLOGY

Ammonia: The potential revenue loss due to fly ash and gypsum salability, ammonium salt formation, byproduct reuse and disposal, landfill disposal, odor nuisance, and fly ash pond treatment costs are the major drawbacks of this technology. In addition to these drawbacks, this technology will only meet the target SO₃ reduction rate at very high injection rates.

Humidification: Humidification upstream of the SCR can produce ash deposits in the ductwork and could plug or damage the catalyst. There is a risk of increased maintenance cost and the cost of premature catalyst replacement. In addition, humidification alone will reduce SO₃ emissions by about 27%, which does not meet the target SO₃ reduction.



Hydrated Lime: The data presented in the literature for this technology is old, and full scale results from any utility are not documented to serve as the basis for performance estimates. The dry sorbent storage and delivery system is subject to moisture, plugging and erosion problems. The effectiveness of the hydrated lime sorbent depends on high surface area, which varies between lime sources. Fly ash resistivity increases may result in ESP performance degradation.

Magnesium Hydroxide: The sorbent is available as a commercial product and as a byproduct from the Thiosorbic™ Lime FGD system operation. The cost of the commercial product is significantly more than the byproduct material. There is currently a limited supply of the byproduct Mg(OH)₂. The data presented in the literature for this technology is recent, and the full scale results from several plants are documented to serve as the basis for performance estimates. The furnace sorbent injection of Mg(OH)₂ could cause increased furnace and convection pass fouling. Fly ash resistivity increases may result in ESP performance degradation.

Magnesium Oxide: Since MgO is produced by a limited number of suppliers, the cost will be dependent on the delivery cost based on the transportation distance to the plant. The dry sorbent storage and delivery is subject to moisture, plugging and erosion problems. Magnesium oxide alone cannot achieve 90% SO₃ removal.

Micronized Limestone: This technology has not been pilot tested at any power plant, but the supplier is willing to share the cost with any utility who will allow them to install a slip stream pilot plant. There is a risk of fouling, scaling of byproduct in the ductwork, air preheater, and resistivity problems in the electrostatic precipitator. The cost of technology development and demonstrating the stoichiometry are added risks.

Sodium Bisulfite: In addition to the proprietary technology, single source of supply, the yearly licensing fee, and the reagent (sodium bisulfite powder) delivered cost, the major drawback of this technology is O&M cost. The cost of the project installed at Gibson Station increased significantly from start to finish. While byproduct SBS is a less costly sorbent, Vectren may not continue to produce the material.



Soda Ash: In addition to the proprietary technology, this sorbent injection technology requires longer duct residence time due to the multiple reactions which need to take place and does not have the experience level of SBS. Injection of soda ash upstream of the air preheater is not feasible for the LG&E/KU plants due to residence time requirements.

Trona (Sodium sesquicarbonate): Trona is an expensive reagent with a long shipping distance from Green River, Wyoming and has been limited by transportation availability at Zimmer Station. Typically shipped by rail, the Trona would have to be transferred to trucks at a centrally located storage and transfer facility. In addition, there is currently only one source of supply. AEP has applied for a patent for this technology, so a licensing fee may apply.

Transportation and Fuel Cost Risks: All of the sorbents are subject to risks associated with transporting material over varying distances as well as the risk of fuel cost increases. Some sorbents, such as Trona, may be affected by natural gas price volatility.

Wet ESP: It is a mature, proven, well-demonstrated technology to reduce SO₃ emissions in industrial plants, but there is little data available from any power plant firing high sulfur coal, with SCR in service, and limestone forced oxidation FGD installed downstream of the dry ESP. Wet ESPs are installed in Europe and Japan. In North America, five power plants installed Wet ESPs, AES Deepwater, Xcel Energy's Sherco Station, New Brunswick Power's Dalhousie and Coleson Cove stations, and Dakota Gasification Co. The wet ESP options require a large capital investment in equipment which is subject to a very corrosive environment. The costs of the corrosion-resistant alloys needed for wet ESPs are currently very volatile so there is a cost escalation risk. The corrosive environment also presents a risk of periodic repair and/or replacement cost. Additionally, the wet ESP typically increases the pressure drop across the system by 3-5 in W.G., depending on the arrangement. Fan curves provided by LG&E/KU indicate that Ghent – Unit 1 and Mill Creek – Unit 3 may be at or near test block conditions with three complete layers of catalyst and may not have sufficient margin for the additional pressure drop associated with a wet ESP.



Purchasing the Ghent – Units 1&4 FGD and wet ESP from the same supplier would eliminate some of the commercial risk and place performance guarantee responsibility with one Contractor. For the vertical wet ESP it would also allow an integrated absorber – wet ESP design. Purchasing the wet ESP separately introduces an interface between the vendors, both a physical interface and a process interface which affects performance guarantees. However, the wet ESP can be purchased separately through competitive bidding with good definition of the process requirements to minimize commercial and performance guarantee risks.

Low Conversion Catalyst: Low conversion catalyst is a proven commodity in reducing SO₃ emissions at the stack outlet. Low conversion catalysts are available with typical guaranteed SO₂ to SO₃ conversion percentages between 0.6-0.8% for three layers of catalyst. This also comes at a cost as the NO_x reduction capability of the catalyst is also reduced, thereby requiring more catalyst volume and more frequent catalyst replacement to replicate the NO_x reduction efficiency of the existing catalyst. The use of the low conversion catalyst does have limitations, however, as this technology only reduces SCR generated SO₃. This can have profound effects, for example, by completely switching to three layers of low conversion catalyst, Trimble County – Unit 1 SO₃ emissions can be reduced 43%, but this is still considerably higher than the target 5 ppm stack outlet concentration (90% SO₃ reduction).

Based on the capital costs, reagent costs, performance, reliability and operational impacts, the following risk ranking has been assigned for each technology.

Table 4-1: Risk Assessment Summary

Technology	Capital Cost	O&M Cost	Performance	Reliability	Overall
Alkaline Additives on Coal Belt	Low	Low	High	Low	High
Ammonia	Low	Low	High	Low	High
Humidification	Low	Low	High	Medium	High
Hydrated Lime	Low	Medium	Medium	Medium	Medium
Magnesium Hydroxide	Medium	Medium	Medium	Medium	Medium
Magnesium Oxide	Medium	Medium	High	Medium	High
Micronized Limestone	High	Medium	High	Medium	High
Sodium Bisulfite (SBS)	Low	Medium	Low	Medium	Low to Medium
Soda Ash	Low	Medium	Low	Medium	Low to Medium
Trona	Low	High	Low	Medium	Low to Medium
Vertical Wet ESP	High	Medium	Low	Medium	High
Horizontal Wet ESP	High	Medium	Low	Medium	High
Low Conversion Catalyst	Low	Low	Low	Low	Low



5. COST ANALYSES

5.1 INTRODUCTION

The alternatives considered for SO₃ mitigation at the LG&E/KU sites included several sorbent injection technologies, two options for wet electrostatic precipitators and replacement of the SCR catalyst with a low SO₂ to SO₃ conversion rate type of catalyst. The wet electrostatic precipitator options are high capital cost/low operating cost options. The sorbent injection technologies are low-to-medium capital cost/medium-to-high operating cost options (depending on the chemical chosen and its delivered cost). The low conversion rate SCR catalyst is a high cost option if a complete replacement of catalyst is made before the existing catalyst activity is exhausted. SCR catalyst replacement occurs periodically as a part of an overall catalyst management plan. If catalyst is only replaced on the schedule of the catalyst management plan, then the cost of low conversion rate catalyst would be an incremental cost premium above that of the original catalyst. The cost per cubic meter of low conversion rate catalyst is about the same as high conversion rate catalyst, but as much as 15% more low conversion catalyst volume is required to achieve the same NO_x reduction efficiency.

5.2 ECONOMIC PARAMETERS

LG&E/KU will use the capital costs, sorbent costs, and operating parameters to evaluate the life cycle costs of the various alternatives. Below is a table summarizing the economic basis.

Table 5.1: Economic Basis

Cost Item		
Auxiliary Power ⁵	\$/MW-h	LG&E/KU
Estimated Outage Penalty ²	\$/day	LG&E/KU
Estimated Outage Penalty	\$/MW-h	LG&E/KU
Anhydrous Ammonia – Delivered	\$/ton	\$300.00
Dry Hydrated Lime – Delivered	\$/ton	\$109.00
Dry Sorbacal H™ - Delivered	\$/ton	\$120.00 ⁷
Magnesium Hydroxide Slurry - Delivered	\$/ton	\$210.00
Dry Magnesium Oxide - Delivered	\$/ton	\$450.00
Dry Micronized Limestone - Delivered	\$/ton	\$30.00
30wt% Sodium Bisulfite - Delivered	\$/ton	\$300.00
Dry Trona – Delivered ⁶	\$/ton	\$205.00
Dry Soda Ash – Delivered	\$/ton	\$220.00
Dry Sodium Sulfite – Delivered	\$/ton	\$350.00



Cost Item		
SBS or Soda Ash Licensing Fee	\$/MW/year	\$200.00
Low Conversion Catalyst	\$/m ³	LG&E/KU
Softened Water	\$/kgal	\$0.06
O&M Personnel	\$/man-hour	LG&E/KU
Estimated Gypsum Byproduct (Sale) ¹	\$/ton	\$2.00
Estimated Gypsum Disposal (Landfill) ^{1,4}	\$/ton	
Labor Escalation Rate	%/yr	
Discount Rate	%/yr	
Economic Life	years	25
Estimated Capacity Factor ^{3,4}	% full load	LG&E/KU
Estimated Make-up Water Cost	\$/1,000 gal	LG&E/KU
Estimated FGD Purge Treatment Cost	\$/1,000 gal	LG&E/KU
Equipment and Material Escalation Rates		
2006	%/yr	2.45%
2007	%/yr	2.33%
2008 and after	%/yr	2.32%

Notes:

- 1 - Assumes local landfill. Cost to load, haul, and place only.
- 2 - Assumes typical spring or fall day.
- 3 - Assumes emissions control equipment is installed and operating.
- 4 - Assumes the unit capacity factor is constant for the entire 25-yr life cycle.
- 5 - For the cost impact of lost generation, add together the auxiliary power cost (\$/MW-h) and the outage penalty cost (\$/MW-h). This would be the cost for year one of the analysis.
- 6 - Rail delivery of Trona is \$160/ton with \$40/ton added for transferring from rail to truck for delivery to each site.
- 7 - Chemical Lime Company plans to build a hydrator in the Louisville area and projects the cost of Sorbacal H™ to be \$95-100/ton delivered.

5.3 ESTIMATED COST BASES

5.3.1 Structural Basis

Foundations sizes were determined based on estimated equipment sizes and representative soil data available for the Ghent and Mill Creek stations. For the purposes of this estimate, the soil conditions at Trimble County are assumed to be similar to those at Mill Creek.

Major structures and silos are assumed to be pile supported. Lighter structures are assumed to be supported on either mat foundations or on spread footings. Where pile foundations are used, the estimates assume the use of 18" diameter augered cast in place (ACIP) piles drilled to a depth of 50 feet at Ghent and 16" diameter ACIP piles drilled to a depth of 100 feet at the Mill Creek and Trimble County stations.



Structural steel quantities are based on the proposed arrangements of the wet precipitator and ductwork. The estimates are for new structural framing and do not include demolition or modifications to existing structures.

Concrete walls were included for containment around all liquid sorbent storage tanks based on a six foot wall height and a square area to provide a volume equal to the 10-day storage tank volume. Concrete lining of the containment area was also included.

5.3.2 Electrical Basis

5.3.2.1 Mill Creek Unit 3

Sorbent injection:

Expected loading will be approximately 800KVA total, This loading could be supplied for a single 4kV/480V Transformer feed from the 4kV Swgr 3B1. The other option would be to split the load between two new MCCs which are supplied from the 480V Power Centers (one for the A bus and the other from the B bus).

Wet ESP:

With the expected loading for the Wet ESP of 1800KVA/bus or 3600kVA total, there would be a 480V double-ended switchgear located at the new ESP. This bus would be supplied power from the 4kV Bus 3A1 and 3B2.

5.3.2.2 Mill Creek Unit 4

Unit 4 would be similar to Unit 3 in its requirements.

Sorbent injection:

Expected Loading will be approximately 800KVA total, This loading could be supplied for a single 4kV/480V Transformer feed from the 4kV Swgr 4B1. The other option would be to split the load between two new MCCs which are supplied from the 480V Power Centers (one for the A bus and the other from the B bus).



Wet ESP:

With the expected loading for the Wet ESP of 1800KVA/bus or 3600kVA total, there would be a 480V double-ended switchgear located at the new ESP. This bus would be supplied power from the 4kV Bus 4A1 and 4B2.

5.3.2.3 Ghent Unit 1

Sorbent injection:

Expected Loading will be approximately 800KVA total, This loading could be supplied for a single 4kV/480V Transformer feed from the Medium Voltage Swgr 1A or 1B. The other option would be to split the load between two new MCCs which are supplied from the 480V Power Centers (one for the A bus and the other from the B bus).

Wet ESP:

With the expected loading for the Wet ESP of 1800KVA/bus or 3600kVA total, there would be a 480V double-ended switchgear located at the new ESP. This bus would be supplied power from the new FGD Medium Voltage Switchgear that would be supplied as part of the new FGD installation.

5.3.2.4 Ghent Unit 3

Sorbent injection:

Expected Loading will be approximately 800KVA total, This loading could be supplied for a single 4kV/480V Transformer feed from the Medium Voltage Swgr 3A or 3B. The other option would be to split the load between two new MCCs which are supplied from the 480V Power Centers (one for the A bus and the other from the B bus).

Wet ESP:

With the expected loading for the Wet ESP of 1800KVA/bus or 3600kVA total, there would be a 480V double-ended switchgear located at the new ESP. This bus would be supplied power from the new FGD Medium Voltage Switchgear that would be supplied as part of the new FGD installation.



5.3.2.5 Ghent Unit 4

Sorbent injection:

Expected Loading will be approximately 800KVA total, This loading could be supplied for a single 4kV/480V Transformer feed from the Medium Voltage Swgr 4A or 4B. The other option would be to split the load between two new MCCs which are supplied from the 480V Power Centers (one for the A bus and the other from the B bus).

Wet ESP:

With the expected loading for the Wet ESP of 1800KVA/bus or 3600kVA total, there would be a 480V double-ended switchgear located at the new ESP. This bus would be supplied power from the new FGD Medium Voltage Switchgear that would be supplied as part of the new FGD installation.

5.3.2.6 Trimble County Unit 1

Sorbent injection:

Expected Loading will be approximately 800KVA total, This loading could be supplied for a single 7kV/480V Transformer feed from the SDRS 7kV Swgr 1A1 or 1B1. The other option would be to split the load between two new MCCs which are supplied from the 480V Precipitator Power Centers (one for the A bus and the other from the B bus).

Wet ESP:

With the expected loading for the Wet ESP of 1800KVA/bus or 3600kVA total, there would be a 480V double-ended switchgear located at the new ESP. This bus would be supplied power from the SDRS 7kV Swgr 1A1 or 1B1.

5.3.3 Mechanical Basis

Based on the attached flow diagrams (Exhibit 7.2) and equipment layout drawings (Section 9.0), an equipment list (Exhibit 7.1) was derived for each of the SO₃ mitigation options. Silo and tank sizing is based on the known density of the reagent material/slurry and the required storage time. The horsepower and related power requirements for the mechanical equipment (blowers, compressors, pumps, feed drives,



and jet mills) were based on both available vendor information and calculations based on the required flow rates of reagent. Air preheater basket replacement with enamel-coated baskets was included for the micronized limestone alternative.

Using the design basis table in section 4.2, the economic parameters discussed in section 4.1 and the estimated cost bases discussed in section 4.3, total levelized costs can be estimated by LG&E/KU for all SO₃ mitigation options. This will include a calculation of the estimated reagent cost, purchase and erection of the necessary equipment, as well as estimated costs for water usage and power loss. Below is a summary table of the capital costs for each SO₃ mitigation option. The complete cost estimates are attached in Section 8. For cost estimation purposes, Ghent – Units 3&4 and Mill Creek – Units 3&4 include long-term storage silos and mixing tanks that serve two units. Half of the cost of the two-unit equipment is included in the estimate to calculate the cost of a single unit.

Table 5.2: Total Installed Capital Cost

		Ghent 1	Ghent 3 ¹	Ghent 4 ¹	Mill Creek 3	Mill Creek 4	Trimble County 1
Option 1 – Hydrated Lime Injection	Total Installed Capital Cost (\$)	\$5,326,070	\$5,343,160	\$5,343,160	\$5,030,150	\$5,343,160	\$4,941,540
	Cost (\$)/kW	\$10.42	\$10.46	\$10.46	\$13.03	\$10.90	\$9.98
Option 2 – Mag. Hydroxide Injection	Total Installed Capital Cost (\$)	\$8,286,000	\$8,343,500	\$8,115,300	\$8,125,400	\$8,308,500	\$8,438,600
	Cost (\$)/kW	\$16.22	\$16.33	\$15.88	\$21.05	\$16.96	\$17.05
Option 3 – Soda Ash Injection ²	Total Installed Capital Cost (\$)	\$5,948,600	\$6,630,900	\$6,716,700	\$6,060,800	\$6,249,600	\$5,926,000
	Cost (\$)/kW	\$11.64	\$12.98	\$13.14	\$15.70	\$12.75	\$11.97
Option 4 – SBS Injection ²	Total Installed Capital Cost (\$)	\$7,699,200	\$6,621,400	\$6,798,000	\$7,565,600	\$7,921,800	\$7,843,800
	Cost (\$)/kW	\$15.07	\$12.96	\$13.30	\$19.60	\$16.17	\$15.85
Option 5 – Trona Injection	Total Installed Capital Cost (\$)	\$5,267,900	\$4,932,800	\$5,194,700	\$5,353,600	\$4,745,800	\$4,617,400
	Cost (\$)/kW	\$10.31	\$9.65	\$10.17	\$13.87	\$9.69	\$9.33
Option 6 – Vertical WESP	Total Installed Capital Cost (\$)	\$56,060,000	\$53,453,500	\$53,453,500	N/A	N/A	N/A
	Cost (\$)/kW	\$109.71	\$104.61	\$104.61	N/A	N/A	N/A



		Ghent 1	Ghent 3 ¹	Ghent 4 ¹	Mill Creek 3	Mill Creek 4	Trimble County 1
Option 7 – Horizontal WESP	Total Installed Capital Cost (\$)	\$70,013,100	\$69,859,600	\$71,281,600	\$71,460,000	\$71,281,600	\$69,854,700
	Cost (\$)/kW	\$137.01	\$136.71	\$139.49	\$185.13	\$145.47	\$141.12

Notes:

1 - This cost is for one unit, with a long-term, two-unit storage silo for dry sorbents, or a two-unit storage tank for wet sorbents, where applicable.

2 - Sodium bisulfite or soda ash injection capital cost does not include the annual licensing fee of \$200/MW/year.

5.4 ESTIMATED FIRST YEAR O&M COSTS

In addition to the equipment procurement and erection costs shown above, there are also the operating costs that are expected. These include the cost of sorbent; auxiliary power requirements; softened water for dilution of magnesium hydroxide, SBS, or soda ash; and O&M labor required for maintenance of the mitigation technologies. The delivered cost of each sorbent is detailed above. Auxiliary power requirements have been estimated based upon the equipment required for each mitigation strategy. Labor required for O&M of the mitigation technology is based upon the experiences from the Cinergy Gibson Station, which indicates expected labor required for maintenance of these sorbent injection systems. This primarily consists of weekly cleaning of the injection nozzles, which requires 8-16 man-hours per week, depending on the injection strategy. Softened water is required to dilute the magnesium hydroxide from 60% by weight to the desired 15% by weight desired for injection or to dilute the SBS or soda ash to 10% by weight. The softened water system requires salt and resin, which are itemized in the O&M cost tables included as Section 8.2. The salt must be added daily, while the resin requires replacement once every seven years, regardless of the softened water demand. A summary table indicating expected fist-year O&M costs is included below.



Table 5.3: First Year Operating Costs

Subtotal Cost	Ammonia	Humid. Water	Hydrated Lime	Magnesium Hydroxide	Magnesium Oxide	Micronized Limestone	Sodium Bisulfite ¹	Trona	Soda Ash ¹	Wet ESP
Ghent 1	\$224,412	\$2,625,930	\$2,625,930	\$2,805,281	\$4,070,384	\$755,580	\$1,765,502	\$4,534,163	\$898,534	\$908,716
Ghent 3	\$233,342	\$2,739,076	\$2,739,076	\$2,924,756	\$4,246,892	\$784,998	\$1,836,147	\$4,728,868	\$931,220	\$944,195
Ghent 4	\$233,342	\$2,739,076	\$2,739,076	\$2,924,756	\$4,246,892	\$784,998	\$1,836,147	\$4,728,868	\$931,220	\$944,195
Mill Creek 3	\$144,160	\$1,609,161	\$1,609,161	\$1,731,633	\$2,484,219	\$491,219	\$1,105,652	\$2,784,472	\$579,806	\$788,198
Mill Creek 4	\$150,551	\$1,690,140	\$1,690,140	\$1,817,143	\$2,610,548	\$512,274	\$1,177,014	\$2,923,825	\$624,000	\$804,672
Trimble County 1	\$241,813	\$2,846,389	\$2,846,389	\$3,038,072	\$4,414,301	\$812,899	\$1,899,951	\$4,913,536	\$959,021	\$933,490

Notes:

1 - The cost of the licensing fee for SBS and soda ash has been included in the first-year operating costs shown above.



6. CONCLUSIONS AND RECOMMENDATIONS

LG&E/KU's choice of an SO₃ mitigation action plan for each of the LG&E/KU units should not be made on capital cost alone. LG&E/KU has agreed to prepare a life cycle cost analysis based on the data presented in this report. The least cost approach may be ammonia injection, but it will not reduce SO₃ sufficiently without detrimental effects on fly ash and gypsum sales and ash handling and disposal operations. The calcium-based sorbents are limited by resistivity impacts on the precipitators. Magnesium hydroxide injected in the furnace and the sodium-based sorbents, SBS and Trona, are more effective at mitigating SO₃, at a higher operating cost than the calcium-based sorbents. The wet ESP technology has a long track record in other industries and good experience to date in the power industry, and also has co-benefits in reduction of fine particulates and mercury. However, the initial capital investment for the wet ESP is very high.

The combination of magnesium hydroxide injection in the furnace with hydrated lime or Trona injection downstream of the air preheater is a lower capital cost option with a good probability of success. The combination of a low SO₂ to SO₃ conversion catalyst and sodium bisulfite injection downstream of the air preheater is also promising. Either of these two sorbent injection options, combined with SO₃ reduction across existing (or planned future) equipment, will reduce the level at the stack exit to 5 ppm for Mill Creek – Units 3&4 or Ghent – Unit 1.

Due to the high SO₂ to SO₃ oxidation rate on the surface of the catalyst at Trimble County – Unit 1, a complete change-out of the current catalyst and replacement with low-conversion catalyst is recommended. This will alleviate much of the existing SO₃ emission concerns and the target emissions can be met through the use of sorbent injection upstream of the ESP. By changing out the catalyst completely, it can be assured that the plant will meet the target SO₃ emissions during periods when the fired coal is closer to the maximum indicated sulfur concentration (8.90lb/MBtu) without requiring additional mitigation technologies.

Units 3&4 at Ghent have existing hot-side ESPs, which limit the use of sorbent injection downstream of the air preheater. The FGD system particulate collection capability may allow some sorbent injection. As such, Ghent – Units 3&4 will likely require a wet ESP to reduce stack SO₃ emissions to 5 ppm or a combination



of Mg(OH)₂ injection in the furnace, replacement of all catalyst with low conversion catalyst and some sorbent injection such as SBS or hydrated lime upstream of the FGD system.

Shown below is a table summarizing the applicability of each technology investigated for SO₃ mitigation at each of the LG&E/KU sites. This table reflects published results of recent testing only.

Table 6-1: Summary of Technology Applicability

	Ghent 1	Ghent 3	Ghent 4	Mill Creek 3	Mill Creek 4	Trimble County 1
Ammonia Injection	No	No	No	No	No	No
Flue Gas Humidification	No	No	No	No	No	No
Hydrated Lime Injection	Yes	Yes ¹	Yes ¹	Yes	Yes	Yes
Mag. Hydroxide Injection	No	Yes	Yes	No	No	Yes
Magnesium Oxide Injection	No	No	No	No	No	No
Micronized Limestone Injection	No	No	No	No	No	No
OmniClear System	No	No	No	No	No	No
Soda Ash Injection	Yes	Yes ¹	Yes ¹	Yes	Yes	Yes
SBS Injection	Yes	Yes ¹	Yes ¹	Yes	Yes	Yes
Trona Injection	Yes	Yes ¹	Yes ¹	Yes	Yes	Yes
Vertical WESP	Yes	Yes	Yes	No	No	No
Horizontal WESP	No	No	No	Yes	Yes	Yes
Low Conversion Catalyst	Yes	Yes	Yes	Yes	Yes	Yes

Note: 1. The quantity of sorbent injected downstream of the hot-side ESP is limited by the ability of the Wet FGD system to collect particulate matter. One of these technologies could be combined with Low Conversion Catalyst and/or Magnesium Hydroxide injection in the furnace. Testing of Trona injection upstream of the ESP and hydrated lime injection upstream of the wet FGD is planned for Ghent – Unit 1.



7. EXHIBITS

- 7.1 EQUIPMENT LIST
- 7.2 FLOW DIAGRAMS
- 7.3 ESP DESIGN DATA



8. APPENDICES

8.1 CAPITAL COST ESTIMATES

8.2 FIRST YEAR O&M COSTS



9. DRAWINGS



7.1: Equipment List

Exhibit 7.1: Equipment List

	Ghent 1	Ghent 3	Ghent 4
Hydrated Lime			
<u>Equipment</u>	<u>Description</u>	<u>Description</u>	<u>Description</u>
Air Blowers (5 Qty)	150 HP each (Moving -7,605 lb/hr of Solid Material to the Injection Manifold)	150 HP each (Moving -8,397 lb/hr of Solid Material to the Injection Manifold)	150 HP each (Moving -8,397 lb/hr of Solid Material to the Injection Manifold)
VFD Rotary Feeder (3 Qty)	3 HP - Stainless Steel	3 HP - Stainless Steel	3 HP - Stainless Steel
Long-Term Storage Silo (10 Days)	1,623,700 lb full - 12,467 ft ³ - D=15.8' - H=63.3' - CS Silo - SS Hopper	1,694,400 lb full - 13,011 ft ³ - D=16.1' - H=64.2' - CS Silo - SS Hopper	1,694,400 lb full - 13,011 ft ³ - D=16.1' - H=64.2' - CS Silo - SS Hopper
Long-Term Storage Silo (10 Days) (Common Tanks)		3,388,800 lb full - 26,021 ft ³ - D=20.2' - H=80.9' - CS Silo - SS Hopper	
Short-Term Storage Silo (24 Hours)	162,400 lb full - 1,247 ft ³ - D=7.3' - H=29.4' - CS Silo - SS Hopper	169,500 lb full - 1301 ft ³ - D=7.5' - H=30.0' - CS Silo - SS Hopper	169,500 lb full - 1301 ft ³ - D=7.5' - H=30.0' - CS Silo - SS Hopper
Short-Term Storage Silo (24 Hours) (Common Tanks)		338,900 lb full - 2,602 ft ³ - D=9.4' - H=37.6' - CS Silo - SS Hopper	
Injection Manifold (2 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Injection Nozzles (50 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Piping	L=450' - D=8" - CS	L=450' - D=8" - CS	L=450' - D=8" - CS
Magnesium Hydroxide			
<u>Equipment</u>	<u>Description</u>	<u>Description</u>	<u>Description</u>
VFD Rotary Feeder (1 Qty)	3 HP - Stainless Steel	3 HP - Stainless Steel	3 HP - Stainless Steel
Storage Tank (10 days)	894,200 lb full - 10,842 ft ³ - D=22.6' - H=27.1' - CS Silo - SS Hopper	933,160 lb full - 11,314 ft ³ - D=22.9' - H=27.5' - CS Silo - SS Hopper	933,160 lb full - 11,314 ft ³ - D=22.9' - H=27.5' - CS Silo - SS Hopper
Storage Tank (10 days) (Common Tank)		1,866,320 lb full - 22,630 ft ³ - D=28.8' - H=34.6' - CS Silo - SS Hopper	
Air Compressors (2 Qty)	2 x 100% - 75 HP	2 x 100% - 75 HP	2 x 100% - 75 HP
Mixing Tank (24 Hours)	89,420 lb full - 8,249 ft ³ - D=17.4' - H=20.9' - CS	93,160 lb full - 8,608 ft ³ - D=20.9' - H=25.1' - CS	93,160 lb full - 8,608 ft ³ - D=20.9' - H=25.1' - CS
Mixing Tank (24 Hours) (Common Tank)		186,700 lb full - 17,219 ft ³ - D=26.3' - H=31.6' - CS Silo - SS Hopper	
Mixing Tank Agitator (1 Qty)	CS Shaft - 20 HP	CS Shaft - 20 HP	CS Shaft - 20 HP
Slurry/Water Pumps (6 Qty)	CS - 5.0 HP (possibly positive displacement or turbine pumps)	CS - 5.0 HP (possibly positive displacement or turbine pumps)	CS - 5.0 HP (possibly positive displacement or turbine pumps)
3	Stainless Steel	Stainless Steel	Stainless Steel
Dual Fluid Injection Nozzles (20 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Piping (Insulation and Lagging)	L=50' - D=6" - CS / L=300' - D=2" - CS	L=50' - D=6" - CS / L=300' - D=2" - CS	L=50' - D=6" - CS / L=300' - D=2" - CS

Exhibit 7.1: Equipment List

	Ghent 1	Ghent 3	Ghent 4
Sodium Bisulfite (SBS)			
<u>Equipment</u>	<u>Description</u>	<u>Description</u>	<u>Description</u>
Pumps (6 Qty)	2 - CS Internals - 2.0 HP / 4 - SS Internals - 1.0 HP	2 - CS Internals - 2.0 HP / 4 - SS Internals - 1.0 HP	2 - CS Internals - 2.0 HP / 4 - SS Internals - 1.0 HP
SBS Solution Tank (10 Days)	456,195 lb full - 7,643 ft ³ - D=20.1' - H=24.1' - SS	476,070 lb full - 7,664 ft ³ - D=20.4' - H=24.5' - SS	476,070 lb full - 7,664 ft ³ - D=20.4' - H=24.5' - SS
SBS Solution Tank (10 Days) (Common Tank)	952,140 lb full - 15,952 ft ³ - D=25.7' - H=30.8' - SS		
Agitator (1 Qty)	SS Shaft - 20 HP	SS Shaft - 20 HP	SS Shaft - 20 HP
Air Compressors (2 Qty)	2 x 100% - 50 HP	2 x 100% - 50 HP	2 x 100% - 50 HP
Injection Manifold (2 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Dual Fluid Injection Nozzles (100 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Piping (Insulation, Lagging, and Heat Tracing)	L=250' - D=6" - SS / L=50' - D=6" - CS / L=50' - D=4" - SS	L=250' - D=6" - SS / L=50' - D=6" - CS / L=50' - D=4" - SS	L=250' - D=6" - SS / L=50' - D=6" - CS / L=50' - D=4" - SS
Soda Ash			
<u>Equipment</u>	<u>Description</u>	<u>Description</u>	<u>Description</u>
Pumps (6 Qty)	2 - CS Internals - 2.0 HP / 4 - SS Internals - 1.0 HP	2 - CS Internals - 2.0 HP / 4 - SS Internals - 1.0 HP	2 - CS Internals - 2.0 HP / 4 - SS Internals - 1.0 HP
Soda Ash Solution Tank (10 Days)	232,260 lb full - 3,293 ft ³ - D=15.2' - H=18.2' - SS	242,380 lb full - 3,436 ft ³ - D=15.4' - H=18.5' - SS	242,380 lb full - 3,436 ft ³ - D=15.4' - H=18.5' - SS
Soda Ash Solution Tank (10 Days) (Common Tank)	484,760 lb full - 6,872 ft ³ - D=19.4' - H=23.3' - SS		
Agitator (1 Qty)	SS Shaft - 20 HP	SS Shaft - 20 HP	SS Shaft - 20 HP
Air Compressors (2 Qty)	2 x 100% - 50 HP	2 x 100% - 50 HP	2 x 100% - 50 HP
Injection Manifold (2 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Dual Fluid Injection Nozzles (100 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Piping (Insulation, Lagging, and Heat Tracing)	L=250' - D=6" - SS / L=50' - D=6" - CS / L=50' - D=4" - SS	L=250' - D=6" - SS / L=50' - D=6" - CS / L=50' - D=4" - SS	L=250' - D=6" - SS / L=50' - D=6" - CS / L=50' - D=4" - SS
Trona			
<u>Equipment</u>	<u>Description</u>	<u>Description</u>	<u>Description</u>
Air Blowers (6 Qty)	150 HP each (Moving ~5,958 lb/hr of Solid Material to the Injection Manifold)	150 HP each (Moving ~7,683 lb/hr of Solid Material to the Injection Manifold)	150 HP each (Moving ~7,683 lb/hr of Solid Material to the Injection Manifold)
VFD Rotary Feeder (3 Qty)	3 HP - Stainless Steel	3 HP - Stainless Steel	3 HP - Stainless Steel
Long-Term Storage Silo (10 Days)	1,485,585 lb full - 12,976 ft ³ - D=16.0' - H=64.2' - CS Silo - SS Hopper	1,550,313 lb full - 13,541 ft ³ - D=16.3' - H=65.1' - CS Silo - SS Hopper	1,550,313 lb full - 13,541 ft ³ - D=16.3' - H=65.1' - CS Silo - SS Hopper
Long-Term Storage Silo (10 Days) (Common Tanks)	3,100,625 lb full - 27,082 ft ³ - D=20.5' - H=82.0' - CS Silo - SS Hopper		
Short-Term Storage Silo (24 Hours)	148,558 lb full - 1,300 ft ³ - D=7.4' - H=29.8' - CS Silo - SS Hopper	155,031 lb full - 1,354 ft ³ - D=7.6' - H=30.2' - CS Silo - SS Hopper	155,031 lb full - 1,354 ft ³ - D=7.6' - H=30.2' - CS Silo - SS Hopper
Short-Term Storage Silo (24 Hours) (Common Tanks)	310,065 lb full - 2,708 ft ³ - D=9.5' - H=38.1' - CS Silo - SS Hopper		
Injection Manifold (2 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Injection Nozzles (50 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Piping	L=450' - D=8" - CS	L=450' - D=8" - CS	L=450' - D=8" - CS
Valving, instrumentation, controls, auxiliary power equipment, DCS, and foundation requirements are not included. All equipment is on a per unit basis except for the long-term storage silos/tanks.			

Exhibit 7.1: Equipment List

	Mill Creek 3	Mill Creek 4	Trimble County 1
Hydrated Lime			
Equipment	Description	Description	Description
Air Blowers (6 Qty)	150 HP each (Moving ~4,104 lb/hr of Solid Material to the Injection Manifold)	150 HP each (Moving ~4,315 lb/hr of Solid Material to the Injection Manifold)	150 HP each (Moving ~12,240 lb/hr of Solid Material to the Injection Manifold)
VFD Rotary Feeder (3 Qty)	3 HP - Stainless Steel	3 HP - Stainless Steel	3 HP - Stainless Steel
Long-Term Storage Silo (10 Days)	985,000 lb full - 7,563 ft ³ - D=13.4' - H=53.6' - CS Silo - SS Hopper	1,035,800 lb full - 7,953 ft ³ - D=13.6' - H=54.5' - CS Silo - SS Hopper	1,761,500 lb full - 13,526 ft ³ - D=16.3' - H=65.1' - CS Silo - SS Hopper
Long-Term Storage Silo (10 Days) (Common Tanks)	2,020,600 lb full - 15,516 ft ³ - D=17.0' - H=68.1' - CS Silo - SS Hopper		
Short-Term Storage Silo (24 Hours)	98,500 lb full - 756 ft ³ - D=6.2' - H=24.9' - CS Silo - SS Hopper	103,580 lb full - 795 ft ³ - D=6.3' - H=25.3' - CS Silo - SS Hopper	176,150 lb full - 1353 ft ³ - D=7.6' - H=30.2' - CS Silo - SS Hopper
Short-Term Storage Silo (24 Hours) (Common Tanks)	202,060 lb full - 1,552 ft ³ - D=7.9' - H=31.6' - CS Silo - SS Hopper		
Injection Manifold (2 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Injection Nozzles (50 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Piping	L=450' - D=8" - CS	L=450' - D=8" - CS	L=450' - D=8" - CS
Magnesium Hydroxide			
Equipment	Description	Description	Description
VFD Rotary Feeder (1 Qty)	3 HP - Stainless Steel	3 HP - Stainless Steel	3 HP - Stainless Steel
Storage Tank (10 days)	542,448 lb full - 6,577 ft ³ - D=19.1' - H=22.9' - CS Silo - SS Hopper	570,405 lb full - 6,916 ft ³ - D=19.4' - H=23.3' - CS Silo - SS Hopper	970,120 lb full - 11,762 ft ³ - D=23.2' - H=27.8' - CS Silo - SS Hopper
Storage Tank (10 days) (Common Tank)	1,112,852 lb full - 13,493 ft ³ - D=24.3' - H=29.1' - CS Silo - SS Hopper		
Air Compressors (2 Qty)	2 x 100% - 75 HP	2 x 100% - 75 HP	2 x 100% - 75 HP
Mixing Tank (24 Hours)	54,245 lb full - 5,004 ft ³ - D=17.4' - H=20.9' - CS	57,041 lb full - 5,262 ft ³ - D=17.7' - H=21.3' - CS	97,012 lb full - 8,950 ft ³ - D=21.2' - H=25.4' - CS
Mixing Tank (24 Hours) (Common Tank)	111,285 lb full - 10,266 ft ³ - D=22.2' - H=26.6' - CS Silo - SS Hopper		
Mixing Tank Agitator (1 Qty)	CS Shaft - 20 HP	CS Shaft - 20 HP	CS Shaft - 20 HP
Slurry/Water Pumps (6 Qty)	CS - 5.0 HP (possibly positive displacement or turbine pumps)	CS - 5.0 HP (possibly positive displacement or turbine pumps)	CS - 5.0 HP (possibly positive displacement or turbine pumps)
3	Stainless Steel	Stainless Steel	Stainless Steel
Dual Fluid Injection Nozzles (20 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Piping (Insulation and Lagging)	L=50' - D=6" - CS / L=300' - D=2" - CS	L=50' - D=6" - CS / L=300' - D=2" - CS	L=50' - D=6" - CS / L=300' - D=2" - CS

Exhibit 7.1: Equipment List

	Mill Creek 3	Mill Creek 4	Trimble County 1
Sodium Bisulfite (SBS)			
Equipment	Description	Description	Description
Pumps (6 Qty)	2 - CS Internals - 2.0 HP / 4 - SS Internals - 1.0 HP	2 - CS Internals - 2.0 HP / 4 - SS Internals - 1.0 HP	2 - CS Internals - 2.0 HP / 4 - SS Internals - 1.0 HP
SBS Solution Tank (10 Days)	276,740 lb full - 4,637 ft ³ - D=17.0' - H=20.4' - SS	291,003 lb full - 4,876 ft ³ - D=17.3' - H=20.8' - SS	494,925 lb full - 8,292 ft ³ - D=20.6' - H=24.8' - SS
SBS Solution Tank (10 Days) (Common Tank)	567,743 lb full - 9,512 ft ³ - D=21.6' - H=25.9' - SS		
Agitator (1 Qty)	SS Shaft - 20 HP	SS Shaft - 20 HP	SS Shaft - 20 HP
Air Compressors (2 Qty)	2 x 100% - 50 HP	2 x 100% - 50 HP	2 x 100% - 50 HP
Injection Manifold (2 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Dual Fluid Injection Nozzles (100 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Piping (Insulation, Lagging, and Heat Tracing)	L=250' - D=6" - SS / L=50' - D=6" - CS / L=50' - D=4" - SS	L=250' - D=6" - SS / L=50' - D=6" - CS / L=50' - D=4" - SS	L=250' - D=6" - SS / L=50' - D=6" - CS / L=50' - D=4" - SS
Soda Ash			
Equipment	Description	Description	Description
Pumps (6 Qty)	2 - CS Internals - 2.0 HP / 4 - SS Internals - 1.0 HP	2 - CS Internals - 2.0 HP / 4 - SS Internals - 1.0 HP	2 - CS Internals - 2.0 HP / 4 - SS Internals - 1.0 HP
Soda Ash Solution Tank (10 Days)	140,896 lb full - 1,997 ft ³ - D=12.8' - H=15.4' - SS	148,157 lb full - 2,100 ft ³ - D=13.1' - H=15.7' - SS	2251,980 lb full - 3,572 ft ³ - D=15.6' - H=18.7' - SS
Soda Ash Solution Tank (10 Days) (Common Tank)	289,053 lb full - 4,100 ft ³ - D=16.3' - H=19.6' - SS		
Agitator (1 Qty)	SS Shaft - 20 HP	SS Shaft - 20 HP	SS Shaft - 20 HP
Air Compressors (2 Qty)	2 x 100% - 50 HP	2 x 100% - 50 HP	2 x 100% - 50 HP
Injection Manifold (2 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Dual Fluid Injection Nozzles (100 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Piping (Insulation, Lagging, and Heat Tracing)	L=250' - D=6" - SS / L=50' - D=6" - CS / L=50' - D=4" - SS	L=250' - D=6" - SS / L=50' - D=6" - CS / L=50' - D=4" - SS	L=250' - D=6" - SS / L=50' - D=6" - CS / L=50' - D=4" - SS
Trona			
Equipment	Description	Description	Description
Air Blowers (6 Qty)	150 HP each (Moving ~3,755 lb/hr of Solid Material to the Injection Manifold)	150 HP each (Moving ~3,949 lb/hr of Solid Material to the Injection Manifold)	150 HP each (Moving ~11,200 lb/hr of Solid Material to the Injection Manifold)
VFD Rotary Feeder (3 Qty)	3 HP - Stainless Steel	3 HP - Stainless Steel	3 HP - Stainless Steel
Long-Term Storage Silo (10 Days)	901,199 lb full - 7,871 ft ³ - D=13.6' - H=54.3' - CS Silo - SS Hopper	947,646 lb full - 8,277 ft ³ - D=13.8' - H=55.2' - CS Silo - SS Hopper	1,611,715 lb full - 14,077 ft ³ - D=16.5' - H=65.9' - CS Silo - SS Hopper
Long-Term Storage Silo (10 Days) (Common Tanks)	1,848,845 lb full - 16,150 ft ³ - D=17.3' - H=69.0' - CS Silo - SS Hopper		
Short-Term Storage Silo (24 Hours)	90,120 lb full - 787 ft ³ - D=6.3' - H=25.2' - CS Silo - SS Hopper	94,765 lb full - 828 ft ³ - D=6.4' - H=25.6' - CS Silo - SS Hopper	161,172 lb full - 1,410 ft ³ - D=7.7' - H=30.6' - CS Silo - SS Hopper
Short-Term Storage Silo (24 Hours) (Common Tanks)	184,885 lb full - 1,615 ft ³ - D=8.0' - H=32.0' - CS Silo - SS Hopper		
Injection Manifold (2 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Injection Nozzles (50 Qty)	Stainless Steel	Stainless Steel	Stainless Steel
Piping	L=450' - D=8" - CS	L=450' - D=8" - CS	L=450' - D=8" - CS
Valving, instrumentation, controls, auxiliary power equipment, DCS, and foundation requirements are not included. All equipment is on a per unit basis except for the long-term storage silos/tanks.			



7.2: Flow Diagrams

Exhibit 7.2: Mitigation Technology Entry Points




Exhibit 7.2.1: Ammonia Injection




Exhibit 7.2.2: Flue Gas Humidification




Exhibit 7.2.3: Dry Sorbent Injection (Cold-Side ESP)

(Hydrated Lime, Magnesium Oxide, Micronized Limestone, Trona)




Exhibit 7.2.3: Dry Sorbent Injection (Hot-Side ESP)

(Hydrated Lime, Trona)




Exhibit 7.2.4: Magnesium Hydroxide Injection




Exhibit 7.2.5: Sodium Bisulfite (SBS) or Soda Ash




Exhibit 7.2.6: Stand-Alone Wet ESP - Horizontal Flow




Exhibit 7.2.7: Absorber-Mounted Wet ESP - Vertical Flow





Exhibit 7.2.8: Alkaline Additives to the Coal Belt





7.3: ESP Design Data

LOUISVILLE GAS & ELECTRIC, VARIOUS UNITS
ELECTROSTATIC PRECIPITATOR DESIGN DATA (2005)

LINE NO.	DESCRIPTION	MILL CREEK # 3	MILL CREEK # 4	GHENT # 1	GHENT # 3	GHENT # 4	TRIMBLE COUNTY # 1
1	UNIT RATING, MW _{net}	386	490	511	511	511	495
2	PLATE HEIGHT	33	35	30	36	36	49
3	NUMBER OF MECHANICAL FIELDS	4	4	4	4	4	4
4	NUMBER OF ELECTRICAL FIELDS	4	4	4	4	4	5
5	LENGTH OF FIRST ELECTRICAL FIELD, (FT)	8.23	9.88	6.75	3.00	3.00	11.20
6	LENGTH OF SECOND ELECTRICAL FIELD, (FT)	8.23	9.88	6.75	3.00	3.00	11.20
7	LENGTH OF THIRD ELECTRICAL FIELD, (FT)	8.23	8.23	6.75	3.00	3.00	11.20
8	LENGTH OF FOURTH ELECTRICAL FIELD, (FT)	8.23	8.23	6.75	3.00	3.00	11.20
9	LENGTH OF FIFTH ELECTRICAL FIELD, (FT)	0.00	0.00	0.00	3.00	3.00	11.20
10	TOTAL PLATE LENGTH	32.92	36.21	27.00	42.00	42.00	55.99
11	NUMBER OF PRECIPITATOR BOXES	2	2	2	2	2	2
12	NO. OF CELLS IN WIDTH	2	4	6	6	6	4
13	PLATE LENGTH EACH ELECTRICAL FIELD	8.23	9.05	6.75	10.50	10.50	11.20
13	PLATE SPACING (INCH)	12	12	12	9	9	12
14	NUMBER OF GAS PASSAGES (EACH BOX)	72	96	84	192	192	92
15	TOTAL NUMBER OF PLATES (ALL BOXES)	584	776	680	1,544	1,544	744
16	EFFECTIVE PRECIPITATOR WIDTH (ALL BOXES)	144	192	168	288	288	184
17	PLATE AREA (BOTH SIDES)	543	634	405	756	756	1,097
18	PRECIPITATOR WIDTH CASING TO CASING	168.5	168.5	168.5	168.5	168.5	168.5
19	TOTAL PLATE AREA, ALL CHAMBERS	312,840	486,640	272,160	1,161,216	1,161,216	1,009,604
20	TOTAL NO. OF T/R SETS	16	16	16	16	16	40
21	PLATE AREA EACH T/R SET	19,553	30,415	17,010	72,576	72,576	25,240
22	TOTAL FLUE GAS VOLUME (acfm)	1,670,000	2,100,000	1,900,000	3,395,652	3,395,652	2,275,000
23	GAS TEMPERATURE	300	320	325	750	750	320
24	GAS VELOCITY, FT/SEC	5.86	5.21	6.28	5.46	5.46	4.21
25	RESIDENCE TIME, SEC	5.62	6.95	4.30	7.69	7.69	13.31
26	SPECIFIC COLLECTION AREA @ 12" SPACING (SCA)	187	232	143	256	256	444
27	SPECIFIC COLLECTION AREA @ 9" SPACING (SCA)	250	309	191	342	342	592

EXHIBIT 7.3

LOUISVILLE GAS & ELECTRIC, VARIOUS UNITS
ELECTROSTATIC PRECIPITATOR DESIGN DATA (2005)

LINE NO.	DESCRIPTION	MILL CREEK # 3	MILL CREEK # 4	GHEHT # 1	GHEHT # 3	GHEHT # 4	TRIMBLE COUNTY # 1
27	HEAT INPUT TO BOILER (BTU/HR)	4.18E+09	4.86E+09	5.13E+09	5.13E+09	5.13E+09	5.17E+09
28	COAL HHV (BTU/LB)	10,906	10,906	11,749	11,749	11,749	10,640
29	ASH IN COAL (%)	12.60	12.60	11.70	11.70	11.70	14.00
30	COAL FEED RATE (TONS/HR)	191	223	218	218	218	243
31	FLY ASH CARRY OVER (%)	85	85	85	85	85	85
32	FLY ASH INLET GRAIN LOADING (GR/ ACF)	2.86	2.65	2.67	1.49	1.49	2.97
33	SORBENT GRAIN LOADING (GR/ ACF)	0.004	0.003	0.007	0.004	0.004	0.01
34	TOTAL INLET GRAIN LOADING (GR/ ACF)	2.87	2.65	2.67	1.50	1.50	2.98
35	FLY ASH INLET LOADING (LB/MMBTU)	9.82	9.82	8.46	8.46	8.46	11.18
	NOTES:						
	1) The estimated plate area for Ghent 3 and 4 Electrostatic Precipitators requires confirmation, will be revised after confirmation from LG&E.						
	2) The sorbent grain loading is based on worst case scenario of using Hydrated lime injection (Option 1).						

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 1 - Hydrated Lime Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21998B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
DUCTWORK MODIFICATIONS																									
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																								
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800							
	INSULATION & LAGGING	3 1/2" INSUL	Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900							
DW-2	DUCTWORK SUPPORT STRUCTURES																								
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400							
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000							
DW-4	DUCTWORK SUBTOTAL						26,355				329			24,650				51,100							
Injection System																									
EQUIPMENT/COMPONENTS																									
	Air Blowers	150 hp each	Est	5	EA	55,125.00	275,625		105.00	525	525	PUMP	65.83	34,561				310,200							
	VFD Rotary Feeder	3 hp - Stainless Steel	Est	3	EA	10,500.00	31,500		30.00	90	90	TANK	65.78	5,920				37,400							
	Long-Term Storage Silo - 1 Unit (10 Days)	2,937,600 lb full - 19,615 ft ³ - D=15.1' - H=82.0' - CS Silo - SS Hopper	Est	1	EA	797,000.00	797,000		2545.52	2,546	2,546	TANK	65.78	167,444				964,400							
	Short-Term Storage Silo - (24 Hours)	293,760 lb full - 1,920 ft ³ - D=8.5' - H=38.0' - CS Silo - SS Hopper	Est	1	EA	200,000.00	200,000		764.00	764	764	TANK	65.78	50,256				250,300							
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100							
	Injection Nozzles (50 Qty)	Stainless Steel	Est	1	LT	10,500.00	10,500		240.00	240	240	MECH	66.86	16,046				26,500							
	System Piping																								
	8" - CS	Includes fitting allowance	Est	350	LF	18.48	6,468		0.46	161	161	SPNG	70.4	11,334				17,800							
	Piping Insulation & Lagging		Est	0	LF	6.62	0		0.14	0	0	INSUL	53.39	0				0							
	Heat Tracing		Est	0	LF	0.00	0		0.00	0	0	WIRE	69.06	0				0							
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800							
	Supply Piping																								
	Water Supply	Allowance	Est	0	LS	840.00	0		100.00	0	0	SPNG	70.4	0				0							
	Air Supply	Allowance	Est	0	LS	525.00	0		80.00	0	0	SPNG	70.4	0				0							
	Piping Supports	Allowance	Est	1	LS	1,575.00	1,575		60.00	60	60	SPNG	70.4	4,224				5,800							
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800							
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	50	CY	157.50	7,875		7.00	350	350	COMP	52.91	18,519				26,400							
IS-3	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800							
IS-4	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700							
IS-5	IS SYSTEM SUBTOTAL						1,418,593				6,704			464,542				1,883,000							
MATERIAL UNLOADING SYSTEM																									
	TRUCK DELIVERY	INCLUDED IN SILO	Est	0	Set	315,000.00	0		1753.67	0	0	SPNG	70.4	0				0							
	AUXILIARY POWER SUPPLY SYSTEM/I&C																								
AP-1	POWER SOURCE																								

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 1 - Hydrated Lime Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21998B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:						
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Labor Productivity =		Louisville, KY 1				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
MISCELLANEOUS		NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,150.00	3,150		1170.00	1,170	1,170	PNTR	55.58	65,029				68,200
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	0	LS	7,350.00	0		300.00	0	0	YDRN	51.97	0				0
MISC-4	OTHER																	
	BLOWER HOUSE																	
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	COMP	52.91	9,259				13,200
	PREFAB BLDG. 15'X20'		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
MISC-5	CFD MODEL STUDY		Est	1	LS	30,000.00	30,000		40.00	40	40	STST	86.46	3,458				33,500
-6	TANK BERM		Est	1	LS	0.00	0		260.00	260	260	STST	86.46	22,480				22,500
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	0.00	0		60.00	60	60	STST	86.46	5,188				5,200
MISC-5	MISC. SUBTOTAL						75,088				1,835			116,653				191,800
GENERAL SUPPORT																		
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							150,000				150,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			150,000				150,000
SUBTOTAL							2,391,574				0			12,238				3,335,900
	Craft Support During Startup	At 3% of Total Manhours									367	MECH	66.86	24,548				24,500
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																166,800
	Erection Contractor's Profit	At 8% of Material and Labor Costs																266,900
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																12,000
	Freight To Site	At 4.5% of Equipment/Material Cost																107,600
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included

Sargent & Lundy ^{LLC} Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 1 - Hydrated Lime Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21998B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:						
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Louisville, KY						
												Labor Productivity = 1						
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	12,606			968,806				3,913,700
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								391,370
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								871,000
	CLIENT INTERNAL COST	Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								5,326,070

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21999B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:						
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Labor Productivity =		Louisville, KY 1				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																	
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	INSULATION & LAGGING	6" THICK INSULATION	Est	200	SF	21.00	4,200		0.27	54	54	DINS	59.32	3,203				7,400
DW-4	DUCTWORK SUPPORT STRUCTURES																	
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
DW-6	BOILER MODS																	
	WALL AND TUBE MODS		Est	2	TN	2,625.00	5,250		35.00	70	70	FLDU	89.66	6,276				11,500
DW-7	DUCTWORK SUBTOTAL						34,125				399			30,926				65,100
Injection System																		
IS-1	EQUIPMENT/COMPONENTS																	
	Air Blowers	Not required	Est	3	EA	21,000.00	63,000		40.00	120	120	MECH	66.86	8,023				71,000
	VFD Rotary Feeder	Not required	Est	1	EA	10,500.00	10,500		30.00	30	30	MECH	66.86	2,006				12,500
	Long-Term Storage Tank - 1 Unit (10 Days)	1,617,900 lb full - 17,060 ft3 - D=26.3' - H=31.6' - CS Silo - SS Hopper	Est	1	EA	151,000.00	151,000		580.00	580	580	TANK	65.78	38,152				189,200
	Short-Term Storage Silo - (24 Hours)	Not required	Est	0	EA	0.00	0		60.00	0	0	TANK	65.78	0				0
	Air Compressors (2 Qty)	50 hp - 2 X 100% 808,320 lb full - 8,520 ft3 - D=20.8' - H=25.0' - CS Silo - SS Hopper	Est	2	EA	21,000.00	42,000		80.00	160	160	MECH	66.86	10,698				52,700
	Mixing Tank - 1 Unit - (24 Hours)	20 hp - CS Shaft	Est	1	EA	76,500.00	76,500		880.00	880	880	TANK	65.78	57,886				134,400
	Mixing Tank Agitator (1 Qty)	125,000 lb full - 2,000 ft3 - D=13.7' - H=13.7' - CS	Est	2	EA	21,000.00	42,000		30.00	60	60	MECH	66.86	4,012				46,000
	Water Storage Tank - 1 Unit (24 Hrs)	2 hp - CS	Est	1	EA	115,500.00	115,500		880.00	880	880	TANK	65.78	57,886				173,400
	Slurry/Water Pumps (6 Qty)	2 hp - CS	Est	6	EA	5,250.00	31,500		20.00	120	120	PUMP	65.83	7,900				39,400
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100
	Dual Fluid Injection Nozzles (20 Qty)	Stainless Steel	Est	1	LT	42,000.00	42,000		96.00	96	96	MECH	66.86	6,419				48,400
	System Piping																	
	1" - CS	Includes fitting allowance	Est	300	LF	2.27	680		0.16	49	49	SPNG	70.4	3,464				4,100
	4" - CS	Includes fitting allowance	Est	50	LF	9.28	464		0.33	17	17	SPNG	70.4	1,162				1,600
	Piping Insulation & Lagging		Est	350	LF	2.99	1,047		0.08	26	26	INSUL	53.39	1,402				2,400
	Heat Tracing		Est	350	LF	21.00	7,350		0.31	109	109	WIRE	69.06	7,493				14,800
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800
	Supply Piping																	
	Water Supply	Allowance	Est	200	LS	840.00	168,000		100.00	20,000	20,000	SPNG	70.4	1,408,000				1,576,000
	Air Supply	Allowance	Est	200	LS	525.00	105,000		80.00	16,000	16,000	SPNG	70.4	1,126,400				1,231,400
	Piping Supports	Allowance	Est	1	LS	2,100.00	2,100		40.00	40	40	SPNG	70.4	2,816				4,900
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	110	CY	157.50	17,325		7.00	770	770	CONP	52.91	40,741				58,100

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21999B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:						
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Labor Productivity =		Louisville, KY 1				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
IS-3	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-4	AUGER CAST PILES (120 TON CAPACITY)	90 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0
IS-5	IS SYSTEM SUBTOTAL						942,017				40,761			2,845,961				3,787,800
MATERIAL UNLOADING SYSTEM																		
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000				1,254			88,282				193,300
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1 MVA, 6.9-480V XFMR's																
	SWITCHGEAR		Est	1	EA	460,000.00	460,000		500.00	500	500	EHEA	53.92	26,960				487,000
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA						63,000
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE						
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE						
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	300	LF	0.76	227	Routed in 3/4" Conduit	0.05	16	16	WIRE	69.06	1,098				1,300
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	150	LF	1.58	236	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				800
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	0	LF	2.12	0	Routed in 1-1/2" Conduit	0.09	0	0	WIRE						
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	100	LF	2.67	267	Routed in 1-1/2" Conduit	0.35	35	35	WIRE						
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	50	LF	3.58	179	Routed in 2" Conduit	0.35	18	18	WIRE	69.06	1,209				1,400
	Control Cables - Pumps	5/C #14, 600V	Est	300	LF	0.67	202	Routed in 3/4" Conduit	0.03	10	10	WIRE	69.06	663				900
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE						
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,500	LF	2.06	5,145		0.19	485	485	ECND						
	1-1/2" Conduit		Est	100	LF	4.67	467		0.28	28	28	ECND						
	2" Conduit		Est	50	LF	6.25	312		0.35	18	18	ECND						
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND						
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND						

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 21999B	Project No.: 10584-022	Date: 12/20/2005	Rev Date: 1/27/2006	Run Date: 1/27/2006	Preparer:	Reviewer:
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost				
AP-5	DCS SYSTEM ADDITIONS Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA										
AP-8	DCS PROGRAMMING/INTERFACE Interface Hardware Programming /Interface		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC										
			Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0						5,300		
AP-9	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL										
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						689,199				2,615			80,761						709,200		
	REINFORCING OF EXISTING EQUIPMENT	NONE																				
	DEMOLITION / RELOCATIONS	NONE																				
	MISCELLANEOUS	NONE																				
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	5,250.00	5,250		1550.00	1,550	1,550	PNTR	55.58	86,149						91,400		
MISC-2	ROADWORK	Not Required	Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0						0		
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591						22,900		
MISC-4	OTHER																					
	PUMP HOUSE 15' X 20'																					
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259						13,200		
	PREFAB BLDG.		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240						49,200		
MISC-5	CFD MODEL STUDY		Est	1	LS	100,000.00	100,000		40.00	40	40	STST	86.46	3,458						103,500		
MISC-6	TANK BERM		Est	1	LS	76,000.00	76,000		260.00	260	260	STST	86.46	22,480						98,500		
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	34,000.00	34,000		60.00	60	60	STST	86.46	5,188						39,200		
MISC-5	MISC. SUBTOTAL						54,538				2,155			122,239						176,700		
	GENERAL SUPPORT																					
	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000						100,000		
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000						100,000		
	SUBTOTAL						2,034,879				0			3,299,294						5,273,300		

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 21999B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Craft Support During Startup	At 3% of Total Manhours									1,426	MECH	66.86	95,364				95,400
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																263,700
	Erection Contractor's Profit	At 8% of Material and Labor Costs																421,900
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																10,200
	Freight To Site	At 4.5% of Equipment/Material Cost																91,600
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	48,970			3,394,658				6,156,100
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team																615,600
	PERMITTING, MODELING, ETC.																	0
	STARTUP, TESTING AND REAGENT (15 DAYS)																	50,000
	CONTINGENCY	At 20% of Total																1,364,300
	CLIENT INTERNAL COST	To Be Furnished by Owner																100,000
	SPARE PARTS																	Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								8,286,000

Louisville Gas & Electric																	Estimate No.:	22000B
Ghent Unit 1																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 3 - Soda Ash																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Reviewer:	
Labor Productivity =																	1	
Louisville, KY																		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																	
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	INSULATION & LAGGING	3 1/2" INSUL	Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
DW-4	DUCTWORK SUPPORT STRUCTURES																	
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
DW-9	DUCTWORK SUBTOTAL						26,355				329			24,650				51,100
Injection System																		
EQUIPMENT/COMPONENTS																		
	Process Technology Package (PTP) by URS		Est	1	EA	1,800,000.00	1,800,000		20.00	20	20	PUMP	65.83	1,317				1,801,300
	Pumps (6 Qty)	4 - CS internals - 2.0 HP / 4 - SS internals - 1.0 HP	Est	0	EA	2,100.00	0		20.00	0	0	PUMP	65.83	0				0
	Soda Ash Solution Tank - 1 Unit (10 Days)	420,250 lb full - 5,180 ft³ - D=17.6' - H=21.2' - SS	Est	1	EA	133,000.00	133,000		535.21	535	535	TANK	65.78	35,206				168,200
	Soft H₂O Storage Tank - 1 Unit - (24 Hours)	309,312 lb full - 4,957 ft³ - D=18.48' - H=18.48' - CS	Est	1	EA	129,000.00	129,000		489.52	490	490	TANK	65.78	32,201				161,200
	Agitator (1 Qty)	SS Shaft - 20 HP	Est	1	EA	21,000.00	21,000		30.00	30	30	MECH	66.86	2,006				23,000
	Air Compressors (2 Qty)	2 x 100% - 50 HP	Est	2	EA	21,000.00	42,000		80.00	160	160	MECH	66.86	10,698				52,700
	Injection Manifold (2 Qty)	Stainless Steel	Est	0	EA	10,500.00	0		240.00	0	0	MECH	66.86	0				0
	Dual Fluid Injection Nozzles (100 Qty)	Stainless Steel	Est	0	LT	21,000.00	0		480.00	0	0	MECH	66.86	0				0
	System Piping	L=250' - D=4" - SS / L=50' - D=4" - CS / L=50' - D=2" - SS																
	6" - SS	Includes fitting allowance	Est	250	LF	30.61	7,652		0.42	105	105	SPNG	70.4	7,392				15,000
	6" - CS	Includes fitting allowance	Est	50	LF	11.89	594		0.42	21	21	SPNG	70.4	1,478				2,100
	4" - SS	Includes fitting allowance	Est	50	LF	24.89	1,244		0.33	17	17	SPNG	70.4	1,162				2,400
	Piping Insulation & Lagging		Est	350	LF	9.14	3,197		0.17	60	60	INSUL	53.39	3,177				6,400
	Heat Tracing		Est	350	LF	21.00	7,350		0.31	109	109	WIRE	69.06	7,493				14,800
	Valves	Allowance	Est	1	LS	2,520.00	2,520		48.00	48	48	SPNG	70.4	3,379				5,900
	Supply Piping																	
	Water Supply	Allowance	Est	1	LS	840.00	840		100.00	100	100	SPNG	70.4	7,040				7,900
	Air Supply	Allowance	Est	1	LS	525.00	525		80.00	80	80	SPNG	70.4	5,632				6,200
	Piping Supports	Allowance	Est	1	LS	2,940.00	2,940		112.00	112	112	SPNG	70.4	7,885				10,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	75	CY	157.50	11,813		7.00	525	525	CONP	52.91	27,778				39,600
	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
	AUGER CAST PILES (125 TON CAPACITY)	100 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0
IS-3	ROYALTY FEE		0 Est	0	LF									0				0

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 22000B	Project No.: 10584-022	Date: 12/20/2005	Rev Date: 1/27/2006	Run Date: 1/27/2006	Preparer:	Reviewer:
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost				
IS-4	IS SYSTEM SUBTOTAL						2,207,675				2,730			181,509					2,389,100			
	MATERIAL UNLOADING SYSTEM																					
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300				
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000				1,254			88,282				193,300				
	AUXILIARY POWER SUPPLY SYSTEM/I&C																					
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1MVA, 6.9-480V XFMR's																				
	SWITCHGEAR		Est	1	EA	460,000.00	460,000		500.00	500	500	EHEA	53.92	26,960				487,000				
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400				
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600				
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600				
AP-2	GROUNDING																					
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100				
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400				
AP-3	CABLE																					
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0				
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600				
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0				
								Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0				
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 3/4" Conduit	0.05	11	11	WIRE	69.06	732				900				
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	200	LF	0.76	151	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0				
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 1-1/2" Conduit	0.09	5	5	WIRE	69.06	311				400				
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	50	LF	2.12	106	Routed in 1-1/2" Conduit	0.35	35	35	WIRE	69.06	2,417				2,700				
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	100	LF	2.67	267	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0				
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	0	LF	3.58	0	Routed in 3/4" Conduit	0.03	6	6	WIRE	69.06	387				500				
	Control Cables - Pumps	5/C #14, 600V	Est	175	LF	0.67	118	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0				
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800				
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400				
	Data Highway Cable		Est	1,000	LF	3.15	3,150															
AP-4	RACEWAY																					
	3/4" Conduit		Est	2,125	LF	2.06	4,373		0.19	412	412	ECND	49.67	20,477				24,800				
	1-1/2" Conduit		Est	150	LF	4.67	701		0.28	43	43	ECND	49.67	2,116				2,800				
	2" Conduit		Est	0	LF	6.25	0		0.35	0	0	ECND	49.67	0				0				
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND	49.67	8,009				11,300				
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0				
AP-5	DCS SYSTEM ADDITIONS																					
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700				
AP-8	DCS PROGRAMMING/INTERFACE																					

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22000B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800							
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300							
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800							
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						693,130				2,558			143,552				836,900							
	REINFORCING OF EXISTING EQUIPMENT	NONE																							
	DEMOLITION / RELOCATIONS	NONE																							
	MISCELLANEOUS	NONE																							
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,675.00	3,675		1250.00	1,250	1,250	PNTR	55.58	69,475				73,200							
-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0							
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900							
MISC-4	OTHER																								
	PUMP HOUSE 15' X 20'																								
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200							
	PREFAB BLDG.		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200							
MISC-5	MISC. SUBTOTAL						52,963				1,855			105,565				158,500							
	GENERAL SUPPORT																								
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000							
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000							
	SUBTOTAL						3,085,123				8,727			643,559				3,728,900							
	Craft Support During Startup	At 3% of Total Manhours									262	MECH	66.86	17,504				17,500							
	Allowance for Premium Time Labor																	Not Included							
	Productivity Loss Due To Overtime																	Not Included							
	Per Diem Expense																	Not Included							
	Project Wrap (Efficacy) Insurance																	Not Included							
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																186,400							
	Erection Contractor's Profit	At 8% of Material and Labor Costs																298,300							
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs							

Louisville Gas & Electric																	Estimate No.:	22000B
Ghent Unit 1																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 3 - Soda Ash																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
																	Reviewer:	
																	Wage Rates Based on:	Louisville, KY
																	Labor Productivity =	1
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Special Tools	Included wEquipment Costs																Included wEquipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																15,400
	Freight To Site	At 4.5% of Equipment/Material Cost																138,800
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	8,988			661,062				4,385,300
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								438,500
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								974,800
	VT INTERNAL COST	Furnished by Owner								0								100,000
	IE PARTS									0								Not Included
	ESCALATION	Not Included								0								0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0								0
	PROJECT TOTAL :									0								5,948,600

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22001B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
DUCTWORK MODIFICATIONS																									
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																								
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800							
	INSULATION & LAGGING	3 1/2" INSUL	Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900							
DW-4	DUCTWORK SUPPORT STRUCTURES																								
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400							
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000							
DW-9	DUCTWORK SUBTOTAL						26,355				329			24,650				51,100							
Injection System																									
EQUIPMENTS/COMPONENTS																									
	Process Technology Package (URS). The cost shown here is on a single unit basis, multi-contract or economies of scale is not included.	P&ID, Control Logic, Injection and metering pump skids, Proprietary injection lances	Budget	1	EA	1,800,000.00	1,800,000		300.00	300	300	MISC	65.83	19,749				1,819,700							
	Pumps (6 Qty)	4 - CS internals - 2.0 HP / 4 - SS internals - 1.0 HP	Est	6	EA	2,100.00	12,600		20.00	120	120	PUMP	65.83	7,900				20,500							
	SBS Solution Tank - 1 Unit (10 Days)	57,000 gallons - D=19.2' - H=28.0' - SS	Est	1	EA	167,000.00	167,000		1064.00	1,064	1,064	TANK	65.78	69,990				237,000							
	Soft H ₂ O Storage Tank - 1 Unit - (24 Hours)	Included in Soft water supply system	Est	0	EA	0.00	0		489.52	0	0	TANK	65.78	0				0							
	Agitator (1 Qty)	SS Shaft - 20 HP	Est	1	EA	21,000.00	21,000		30.00	30	30	MECH	66.86	2,006				23,000							
	Air Compressors (2 operating, 1 standby, Cost is divided between units 1,2,3 & 4)	3 x 100% - 100 HP	Est	3	EA	225,000.00	675,000		1046.96	3,141	3,141	MECH	66.86	210,000				885,000							
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100							
	System Piping	L=500' - D=6" - SS / L=150' - D=6" - CS / L=100' - D=4" - SS																							
	6" - SS	Includes fitting allowance	Est	500	LF	30.61	15,304		0.42	210	210	SPNG	70.4	14,784				30,100							
	6" - CS	Includes fitting allowance	Est	150	LF	11.89	1,783		0.42	63	63	SPNG	70.4	4,435				6,200							
	4" - SS	Includes fitting allowance	Est	100	LF	24.89	2,489		0.33	33	33	SPNG	70.4	2,323				4,800							
	Piping Insulation & Lagging		Est	500	LF	9.14	4,568		0.17	85	85	INSUL	53.39	4,538				9,100							
	Heat Tracing		Est	500	LF	21.00	10,500		0.31	155	155	WIRE	69.06	10,704				21,200							
	Valves	Allowance	Est	1	LS	7,560.00	7,560		48.00	48	48	SPNG	70.4	3,379				10,900							
	Supply Piping																								
	Water Supply	Allowance	Est	1	LS	840.00	840		100.00	100	100	SPNG	70.4	7,040				7,900							
	Air Supply	Allowance	Est	1	LS	525.00	525		80.00	80	80	SPNG	70.4	5,632				6,200							
	Piping Supports	Allowance	Est	1	LS	2,940.00	2,940		112.00	112	112	SPNG	70.4	7,885				10,800							
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800							
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	90	CY	157.50	14,175		7.00	630	630	CONP	52.91	33,333				47,500							
IS-1	STRUCTURAL STEEL	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800							
IS-3	AUGER CAST PILES (125 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700							

Sargent & Lundy LLC Chicago			Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22001B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:					
Cost Type: Est = Estimated, Bid = Vendor quote			Wage Rates Based on: Labor Productivity =										Louisville, KY 1					
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip/ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
IS-4	ROYALTY FEE	Not Included, \$ per MW, to be negotiated with Vendor	Est	0	LF									0				0
IS-5	IS SYSTEM SUBTOTAL										7,815			538,444				3,381,300
	MATERIAL UNLOADING SYSTEM																	
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000				1,254			88,282				193,300
	AUXILIARY POWER SUPPLY SYSTEM/I&C																	
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1 MVA, 6.9-480V XFMR's																
	SWITCHGEAR		Est	1	EA	460,000.00	460,000		500.00	500	500	EHEA	53.92	26,960				487,000
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	200	LF	0.76	151	Routed in 3/4" Conduit	0.05	11	11	WIRE	69.06	732				900
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	50	LF	2.12	106	Routed in 1-1/2" Conduit	0.09	5	5	WIRE	69.06	311				400
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	100	LF	2.67	267	Routed in 1-1/2" Conduit	0.35	35	35	WIRE	69.06	2,417				2,700
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	0	LF	3.58	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Control Cables - Pumps	5/C #14, 600V	Est	175	LF	0.67	118	Routed in 3/4" Conduit	0.03	6	6	WIRE	69.06	387				500
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,125	LF	2.06	4,373		0.19	412	412	ECND	49.67	20,477				24,800
	1-1/2" Conduit		Est	150	LF	4.67	701		0.28	43	43	ECND	49.67	2,116				2,800
	2" Conduit		Est	0	LF	6.25	0		0.35	0	0	ECND	49.67	0				0
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND	49.67	8,009				11,300
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0
AP-5	DCS SYSTEM ADDITIONS																	

Louisville Gas & Electric																	Estimate No.:	22001B
Ghent Unit 1																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 4 - Sodium Bisulfite (SBS)																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Reviewer:	
Labor Productivity =																	Louisville, KY	
																	1	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE																	
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						693,130				2,558			143,552				836,900
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,675.00	3,675		1250.00	1,250	1,250	PNTR	55.58	69,475				73,200
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
	PUMP HOUSE 15' X 20'																	
	PREFAB BLDG.			1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
MISC-5	CFD MODEL STUDY		Est	1	LS	0.00	0		40.00	40	40	STST	86.46	3,458				3,500
MISC-6	TANK BERM		Est	1	LS	72,000.00	72,000		260.00	260	260	STST	86.46	22,480				94,500
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	36,000.00	36,000		60.00	60	60	STST	86.46	5,188				41,200
MISC-8	MISC. SUBTOTAL						160,963				2,215			136,691				297,700
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000
	SUBTOTAL						3,808,730			0	14,471			1,051,368				4,860,300
	Craft Support During Startup	At 3% of Total Manhours									434	MECH	66.86	29,026				29,000
	Allowance for Premium Time Labor																	Not Included

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22001B						
Cost Type: Est = Estimated, Bid = Vendor quote												Project No.: 10584-022						
												Date: 12/20/2005						
												Rev Date: 1/27/2006						
												Run Date: 1/27/2006						
												Preparer:						
												Reviewer:						
												Wage Rates Based on: Louisville, KY						
												Labor Productivity = 1						
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																243,000
	Erection Contractor's Profit	At 8% of Material and Labor Costs																388,800
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																19,000
	Freight To Site	At 4.5% of Equipment/Material Cost																171,400
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	14,905			1,080,394				5,711,500
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								571,200
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								1,266,500
	CLIENT INTERNAL COST	Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								7,699,200

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 5 - Trona Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.:	22002B						
Cost Type: Est = Estimated, Bid = Vendor quote												Project No.:	10584-022	Date:	12/20/2005	Rev Date:	1/27/2006	Run Date:	1/27/2006	Preparer:		Reviewer:	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost					
DUCTWORK MODIFICATIONS																							
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																						
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138					5,800				
	INSULATION & LAGGING	3 1/2" INSUL	Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203					4,900				
DW-2	DUCTWORK SUPPORT STRUCTURES																						
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917					16,400				
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392					24,000				
DW-4	DUCTWORK SUBTOTAL						26,355				329			24,650					51,100				
Injection System																							
EQUIPMENT/COMPONENTS																							
	Air Blowers	150 hp each	Est	6	EA	55,125.00	330,750		105.00	630	630	PUMP	65.83	41,473					372,200				
	VFD Rotary Feeder	3 hp - Stainless Steel	Est	3	EA	10,500.00	31,500		30.00	90	90	TANK	65.78	5,920					37,400				
	Long-Term Storage Silo - 1 Unit (10 Days)	2,687,900 lb full - 11,610 ft³ - D=20.7' - H=83.0' - CS Silo - SS Hopper	Est	1	EA	590,000.00	590,000		4200.00	4,200	4,200	TANK	65.78	276,276					866,300				
	Short-Term Storage Silo - (24 Hours)	268,800 lb full - 1,160 ft³ - D=8.7' - H=39.0' - CS Silo - SS Hopper	Est	1	EA	180,000.00	180,000		120.00	120	120	TANK	65.78	7,894					187,900				
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093					53,100				
	Injection Nozzles (50 Qty)	Stainless Steel	Est	1	LT	10,500.00	10,500		240.00	240	240	MECH	66.86	16,046					26,500				
	System Piping																						
	8" - CS	Includes fitting allowance	Est	350	LF	18.48	6,468		0.46	160	160	SPNG	70.4	11,236					17,700				
	Piping Insulation & Lagging		Est	0	LF	6.62	0		0.14	0	0	INSUL	53.39	0					0				
	Heat Tracing		Est	0	LF	0.00	0		0.00	0	0	WIRE	69.06	0					0				
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742					2,800				
	Supply Piping																						
	Water Supply	Allowance	Est	0	LS	840.00	0		100.00	0	0	SPNG	70.4	0					0				
	Air Supply	Allowance	Est	0	LS	525.00	0		80.00	0	0	SPNG	70.4	0					0				
	Piping Supports	Allowance	Est	1	LS	1,575.00	1,575		60.00	60	60	SPNG	70.4	4,224					5,800				
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834					35,800				
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	90	CY	157.50	14,175		7.00	630	630	CONP	52.91	33,333					47,500				
	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834					35,800				
IS-3	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735					116,700				
IS-4	IS SYSTEM SUBTOTAL						1,253,018				8,098			552,639					1,805,500				
MATERIAL UNLOADING SYSTEM																							
ASH-1	TRUCK UNLOADING SYSTEM	Included in silo	Est	0	Set	105,000.00	0		1254.00	0	0	SPNG	70.4	0					0				
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						0				0			0					0				

Sargent & Lundy LLC Chicago			Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 5 - Trona Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1			Estimate No.: 22002B	Project No.: 10584-022	Date: 12/20/2005	Rev Date: 1/27/2006	Run Date: 1/27/2006	Preparer:	Reviewer:
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip/ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost						
AUXILIARY POWER SUPPLY SYSTEM/I&C																								
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1MVA, 6.9-480V XFMR's																						
	480V SWITCHGEAR		Est	1	EA	580,000.00	580,000		500.00	500	500	EHEA	53.92	26,960				607,000						
	New Breaker at Existing 4160V Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400						
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600						
	Misc Electrical Equipment & Controls		Est	1	LS	60,900.00	60,900		300.00	300	300	EHEA	53.92	16,176				77,100						
AP-2	GROUNDING																							
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100						
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400						
AP-3	CABLE																							
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0						
	Power Cables for MCC's	3/C 500kcmil, 600kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600						
	Power Cables for 480V Switchgear	3/C 4/0kcmil, 5kV	Est	250	LF	8.40	2,100	Routed in 2" Conduit	0.35	88	88	WIRE	69.06	6,043				8,100						
								Routed in 1-1/2" Conduit																
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Conduit	0.52	0	0	WIRE	69.06	0				0						
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	150	LF	0.76	113	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				700						
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0						
								Routed in 1-1/2" Conduit																
	Power Cables from MCC to Loads - 50 HP	3/C #4, 600V	Est	150	LF	2.10	315	Conduit	0.09	14	14	WIRE	69.06	932				1,200						
								Routed in 1-1/2" Conduit																
	Power Cables from MCC to Loads - 100HP	3/C #4/0, 600V	Est	150	LF	9.45	1,418	Conduit	0.50	75	75	WIRE	69.06	5,180				6,600						
	Power Cables from MCC to Loads - 150HP	3/C #350, 600V	Est	900	LF	10.50	9,450	Routed in 2" Conduit	0.69	621	621	WIRE	69.06	42,886				52,300						
	Control Cables - Pumps	5/C #14, 600V	Est	150	LF	0.67	101	Routed in 3/4" Conduit	0.03	5	5	WIRE	69.06	332				400						
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0						
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800						
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400						
AP-4	RACEWAY																							
	3/4" Conduit		Est	2,300	LF	2.06	4,733		0.19	446	446	ECND	49.67	22,163				26,900						
	1-1/2" Conduit		Est	300	LF	4.67	1,402		0.28	85	85	ECND	49.67	4,232				5,600						
	2" Conduit		Est	1,150	LF	6.25	7,185		0.35	405	405	ECND	49.67	20,106				27,300						
	3" Conduit		Est	900	LF	13.13	11,813		0.65	581	581	ECND	49.67	28,833				40,600						
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0						
AP-5	DCS SYSTEM ADDITIONS																							
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700						
AP-8	DCS PROGRAMMING/INTERFACE																							
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800						
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300						
	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL	60.02	6,002				16,500						
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						890,012				4,163			237,359				1,127,400						

Sargent & Lundy LLC Chicago			Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 5 - Trona Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22002B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:					
Cost Type: Est = Estimated, Bid = Vendor quote													Wage Rates Based on: Labor Productivity =		Louisville, KY 1			
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,150.00	3,150		1170.00	1,170	1,170	PNTR	55.58	65,029				68,200
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
	BLOWER HOUSE																	
	PREFAB BLDG (15' x 20')			1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
MISC-5	CFD MODEL STUDY		Est	1	LS	30,000.00	30,000		40.00	40	40	STST	86.46	3,458				33,500
MISC-6	TANK BERM		Est	1	LS	0.00	0		260.00	260	260	STST	86.46	22,480				22,500
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	0.00	0		60.00	60	60	STST	86.46	5,188				5,200
MISC-5	MISC. SUBTOTAL						82,438				2,135			132,244				214,700
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000
	SUBTOTAL						2,251,823				14,725			1,046,893				3,298,700
	Craft Support During Startup	At 3% of Total Manhours									442	MECH	66.86	29,536				29,500
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																164,900
	Erection Contractor's Profit	At 8% of Material and Labor Costs																263,900
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs

Louisville Gas & Electric																	Estimate No.:	22002B
Ghent Unit 1																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 5 - Trona																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Louisville, KY	
Labor Productivity =																	1	
Reviewer:																		
Sargent & Lundy LLC																		
Chicago																		
Cost Type: Est = Estimated, Bid = Vendor quote																		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Special Tools	Included w\Equipment Costs																Included w\Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																11,300
	Freight To Site	At 4.5% of Equipment/Material Cost																101,300
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	15,167			1,076,429				3,869,600
	ENGINEERING / CONSTRUCTION MANAGEMENT PERMITTING, MODELING, ETC.	Furnished by Project Team								0								387,000
	STARTUP REAGENT TESTING (15 DAYS)									0								0
	CONTINGENCY	At 20% of Total								0								50,000
	CLIENT INTERNAL COST	To Be Furnished by Owner								0								861,300
	REPAIR PARTS									0								100,000
	OPERATION	Not Included								0								Not Included
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								5,267,900

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 6 - Vertical Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22003B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
DUCTWORK MODIFICATIONS																									
DW-1	MODIFY GAS DUCT FOR WESP AND TO ACCEPT INJECTION NOZZLES		Est	0	TN	2,500.00	0		35.00	0	0	FLDU	89.66	0				0							
	DUCTWORK MODS		Est	0	SF	8.00	0		0.27	0	0	DINS	59.32	0				0							
	INSULATION & LAGGING																								
DW-4	DUCTWORK SUPPORT STRUCTURES		Est	0	TN	1,800.00	0		16.00	0	0	STST	86.46	0				0							
	STRUCTURAL STEEL		Est	0	SF	30.00	0		0.40	0	0	GALL	71.2	0				0							
	ACCESS & GALLERIES																								
DW-5	FOUNDATIONS		Est	0	CY	150.00	0		7.00	0	0	COMP	52.91	0				0							
	FOUNDATIONS FOR DUCTWORK AND STRUCTURAL STEEL	INCLUDES EXCAVATION & BACKFILL																							
DW-6	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0							
	DUCTWORK SUBTOTAL						0				0			0				0							
WESP & ASSOCIATED EQUIP																									
WE-1	EQUIPMENT/COMPONENTS																								
WE-2	WESP (One ESP boxes, with three fields, 6 feet long, total 150 SCA. All internal 2205, with 2205 carbon steel clad alloy plate construction)	INCLUDES ALL ASSOCIATED DUCTWORK AND WASTE WATER EQUIPMENT.PIPING AND TANKS	Est	1	EA	19,450,000.00	19,450,000	BUDGETARY INPUT FROM VENDORS	196033	196,033	196,033	PREC	86.72	17,000,000				36,450,000							
WE-3	Chimney Liner Adjustment	RETURN TO EXISTING CHIMNEY	Est	0	LF	0.00	0		-55	0	0	PREC	86.72	0				0							
WE-4	Chimney Breaching Adjustment	NONE	Est	0	LS	0.00	0		0	0	0	PREC	86.72	0				0							
WE-5	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	210	CY	157.50	33,075		7.00	1,470	1,470	COMP	52.91	77,778				110,900							
WE-6	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700							
WE-7	FIBERGLASS DUCT			50	LF	7,200.00	360,000		50.00	2,500	2,500	DUCT	82.81	207,025				567,000							
WE-8	WE SYSTEM SUBTOTAL						19,865,075				201,147			17,379,537				37,244,600							
AUXILIARY POWER SUPPLY SYSTEM/I&C																									
AP-1	POWER SOURCE																								
	SWITCHGEAR	Double Ended Unit Substation with (2) 2MVA, 6.9 480V XFMR'S	Est	2	EA	575,000.00	1,150,000		500.00	1,000	1,000	EHEA	53.92	53,920				1,203,900							
	New Breaker at Existing 13.2kV Switchgear		Est	2	EA	63,000.00	126,000		100.00	200	200	EHEA	53.92	10,784				136,800							
	MCC		Est	2	EA	52,500.00	105,000		240.00	480	480	EHEA	53.92	25,882				130,900							

Louisville Gas & Electric																	Estimate No.:	22003B
Ghent Unit 1																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 6 - Vertical Flow WESP																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Reviewer:	
Labor Productivity =																	Louisville, KY	1
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Misc Electrical Equipment & Controls		Est	1	LS	86,100.00	86,100		504.00	504	504	EHEA	53.92	27,176				113,300
AP-2	GROUNDING																	0
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	100	LF	33.60	3,360	Routed in 5" Conduit	0.69	69	69	WIRE	69.06	4,765				8,100
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	0	LF	14.70	0	Routed in 3" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	1,000	LF	8.40	8,400	Routed in 2" Conduit	0.35	350	350	WIRE	69.06	24,171				32,600
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	3,600	LF	6.30	22,680	Routed in 1-1/2" Conduit	0.52	1,872	1,872	WIRE	69.06	129,280				152,000
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	0	LF	0.76	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	1,500	LF	1.58	2,363	Routed in 3/4" Conduit	0.05	80	80	WIRE	69.06	5,490				7,900
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	0	LF	2.12	0	Routed in 1-1/2" Conduit	0.09	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	0	LF	2.67	0	Routed in 1-1/2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	0	LF	3.58	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Control Cables - Pumps	5/C #14, 600V	Est	1,500	LF	0.67	1,008	Routed in 3/4" Conduit	0.03	48	48	WIRE	69.06	3,315				4,300
	Control Cables - TR Sets	7/C #14, 600V	Est	3,600	LF	0.81	2,911	Routed in 1-1/2" Conduit	0.04	144	144	WIRE	69.06	9,945				12,900
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	4,750	LF	2.06	9,776		0.19	922	922	ECND	49.67	45,771				55,500
	1-1/2" Conduit		Est	3,600	LF	4.67	16,821		0.28	1,022	1,022	ECND	49.67	50,783				67,600
	2" Conduit		Est	1,000	LF	6.25	6,248		0.35	352	352	ECND	49.67	17,484				23,700
	3" Conduit		Est	0	LF	13.13	0		0.65	0	0	ECND	49.67	0				0
	5" Conduit		Est	100	LF	38.33	3,833		1.13	113	113	ECND	49.67	5,598				9,400
AP-5	DCS SYSTEM ADDITIONS																	
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE																	
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						1,609,556				7,569			441,458				2,051,200
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	87150.00	87,150		3250.00	3,250	3,250	PNTR	55.58	180,635				267,800

Louisville Gas & Electric																	Estimate No.:	22003B
Ghent Unit 1																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 6 - Vertical Flow WESP																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
																	Reviewer:	
																	Wage Rates Based on:	Louisville, KY
																	Labor Productivity =	1
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
MISC-2	ROADWORK	20' WIDTH X 1000 LF GRAVEL	Est	1	LS	46000.00	46,000		380.00	380	380	PBIT	62.43	23,723				69,700
MISC-3	STORM DRAINAGE		Est	1	LS	7350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
MISC-5	MISC. SUBTOTAL						140,500				3,930			219,949				360,400
MISC-1	PAINTING	Touch-up and Field Finish	Est	0	LS		0		3250.00	0	0	PNTR	55.58	0				0
MISC-2	ROADWORK	20' WIDTH X 1000 LF GRAVEL	Est	0	LS		0		475.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	0	LS		0		538.43	0	0	YDRN	51.97	0				0
MISC-4	OTHER																	
MISC-5	CFD MODEL STUDY		Est	1	LS	0.00	0		40.00	40	40	STST	86.46	3,458				3,500
MISC-5	MISC. SUBTOTAL						0				40			3,458				3,500
GENERAL SUPPORT																		
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000
GS-2	CRANE RENTAL	700 Ton - 4 months	Est	1	LT		0	Includes freight in and out						480,000				480,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			580,000				580,000
SUBTOTAL							21,615,131			0	212,686			18,624,403				40,239,700
Craft Support During Startup		At 3% of Total Manhours									6,381	MECH	66.86	426,606				426,600
Allowance for Premium Time Labor																		Not Included
Productivity Loss Due To Overtime																		Not Included
Per Diem Expense																		Not Included
Project Wrap (Efficacy) Insurance																		Not Included
Erection Contractor's General & Administrative Costs		At 5% of Material and Labor Costs - WESP																1,039,500
Erection Contractor's Profit		At 8% of Material and Labor Costs - WESP																1,663,200
Mandatory Spare Parts (Start-up/Testing)		Included w/Equipment Costs																Included w/Equipment Costs
Special Tools		Included w/Equipment Costs																Included w/Equipment Costs
Consumables		At 0.5% of Equipment/Material Cost																108,100

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 6 - Vertical Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22003B						
Cost Type: Est = Estimated, Bid = Vendor quote												Project No.: 10584-022						
												Date: 12/20/2005						
												Rev Date: 1/27/2006						
												Run Date: 1/27/2006						
												Preparer:						
												Reviewer:						
												Wage Rates Based on: Louisville, KY						
												Labor Productivity = 1						
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Freight To Site	At 4.5% of Equipment/Material Cost																972,700
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	219,067			19,051,009				44,449,800
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								2,000,200
	PERMITTING, MODELING, ETC.									0								0
	STARTUP AND TESTING									0								100,000
	CONTINGENCY	At 20% of Total								0								9,310,000
	CLIENT INTERNAL COST	To Be Furnished by Owner								0								200,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								56,060,000

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 7 - Horizontal Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22004B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:						
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Labor Productivity =		Louisville, KY 1				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS		COSTS																
WESP & ASSOCIATED EQUIP																		
WE-1	WESP (Two ESP boxes, with 29 feet three fields, 9 feet long 1st field at 9.75" spacing with 76 gas passages, and 11 feet long 2nd and 3rd fields at 11.75" spacing with 64 passages, total 170 SCA. All internal 2205, with 2205 carbon steel clad alloy plate construction)	INCLUDES ALL ASSOCIATED DUCTWORK AND WASTE WATER EQUIPMENT, PIPING AND TANKS	Est	1	EA	30,610,000.00	30,610,000	BUDGETARY INPUT FROM VENDOR	142817	142,817	142,817	PREC	86.72	12,385,047				42,995,000
WE-2	Chimney Liner Adjustment (WITH MODIFIED BREECHING AT WESP OUTLET ELEVATION)	RETURN TO EXISTING BREECHING	Est	0	LF	5,302.50	0		55	0	0	PREC	86.72	0				0
WE-3	Chimney Breaching Adjustment		Est	0	LS	21,000.00	0		220	0	0	PREC	86.72	0				0
	Electrical Building	20'x40'	Est	1	EA	21,000.00	21,000		100.00	100	100	STST	86.46	8,646				29,600
WE-5	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	810	CY	157.50	127,575		7.00	5,670	5,670	CONP	52.91	300,000				427,600
WE-6	STRUCTURAL STEEL		Est	170	TN	2,200.00	374,000		16.00	2,720	2,720	STST	86.46	235,171				609,200
WE-7	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,000	LF	10.00	20,000		0.52	1,040	1,040	PILE	82.81	86,122				106,100
WE-7	FIBER GLASS DUCT 23' DIA		Est	450	LF	7,200.00	3,240,000		50.00	22,500	22,500	DUCT	59.32	1,334,700				4,574,700
WE-8	WE SYSTEM SUBTOTAL						34,392,575				174,847			14,349,686				48,742,200
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 2MVA, 6.9 480V XFMR's																
	SWITCHGEAR		Est	1	EA	575,000.00	575,000		500.00	500	500	EHEA	53.92	26,960				602,000
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	52,500.00	105,000		240.00	480	480	EHEA	53.92	25,882				130,900
	Misc Electrical Equipment & Controls		Est	1	LS	86,100.00	86,100		324.00	324	324	EHEA	53.92	17,470				103,600
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	100	LF	33.60	3,360	Routed in 5" Conduit	0.69	69	69	WIRE	69.06	4,765				8,100
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	0	LF	14.70	0	Routed in 3" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	1,000	LF	8.40	8,400	Routed in 2" Conduit	0.35	350	350	WIRE	69.06	24,171				32,600
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	2,400	LF	6.30	15,120	Routed in 1-1/2" Conduit	0.52	1,248	1,248	WIRE	69.06	86,187				101,300
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	0	LF	0.76	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	1,500	LF	1.58	2,363	Routed in 3/4" Conduit	0.05	80	80	WIRE	69.06	5,490				7,900
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	0	LF	2.12	0	Routed in 1-1/2" Conduit	0.09	0	0	WIRE	69.06	0				0

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 1 SO3 Mitigation System Option 7 - Horizontal Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22004B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	0	LF	2.67	0	Routed in 1-1/2" Conduit	0.35	0	0	WIRE	69.06	0				0							
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	0	LF	3.58	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0							
	Control Cables - Pumps	5/C #14, 600V	Est	1,500	LF	0.67	1,008	Routed in 3/4" Conduit	0.03	48	48	WIRE	69.06	3,315				4,300							
	Control Cables - TR Sets	7/C #14, 600V	Est	2,400	LF	0.81	1,940	Routed in 1-1/2" Conduit	0.04	96	96	WIRE	69.06	6,630				8,600							
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800							
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400							
AP-4	RACEWAY																								
	3/4" Conduit		Est	4,750	LF	2.06	9,776		0.19	922	922	ECND	49.67	45,771				55,500							
	1-1/2" Conduit		Est	2,400	LF	4.67	11,214		0.28	682	682	ECND	49.67	33,855				45,100							
	2" Conduit		Est	1,000	LF	6.25	6,248		0.35	352	352	ECND	49.67	17,484				23,700							
	3" Conduit		Est	0	LF	13.13	0		0.65	0	0	ECND	49.67	0				0							
	5" Conduit		Est	100	LF	38.33	3,833		1.13	113	113	ECND	49.67	5,598				9,400							
AP-5	DCS SYSTEM ADDITIONS																								
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700							
AP-6	DCS PROGRAMMING/INTERFACE																								
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800							
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300							
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800							
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						957,418				5,776			336,065				1,293,700							
	REINFORCING OF EXISTING EQUIPMENT	NONE																							
	DEMOLITION / RELOCATIONS	NONE																							
	MISCELLANEOUS	NONE																							
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	87,150.00	87,150		3250.00	3,250	3,250	PNTR	55.58	180,635				267,800							
MISC-2	ROADWORK	20' WIDTH X 1000 LF GRAVEL	Est	1	LS	45,937.50	45,938		380.00	380	380	PBIT	62.43	23,723				69,700							
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900							
MISC-4	OTHER																								
MISC-5	MISC. SUBTOTAL						140,438				3,930			219,949				360,400							
	GENERAL SUPPORT																								
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000							

Louisville Gas & Electric																	Estimate No.:	22004B
Ghent Unit 1																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 7 - Horizontal Flow WESP																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Louisville, KY	
Labor Productivity =																	1	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
GS-2	CRANE RENTAL	700 Ton - 2 months	Est	1	LT		0	Includes freight in and out						310,000				310,000
GS-2	GENERAL SUPPORT SUBTOTAL						0			0				410,000				410,000
	SUBTOTAL						35,490,431			0	184,553			15,315,700				50,806,300
	Craft Support During Startup	At 3% of Total Manhours								5,537	MECH	66.86		370,176				370,200
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs - WESP																1,009,800
	Erection Contractor's Profit	At 8% of Material and Labor Costs - WESP																1,615,700
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																177,500
	Freight To Site	At 4.5% of Equipment/Material Cost																1,597,100
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	190,089			15,685,876				55,576,600
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team																2,501,000
	PERMITTING, MODELING, ETC.																	0
	STARTUP AND TESTING																	100,000
	CONTINGENCY	At 20% of Total																11,635,500
	CLIENT INTERNAL COST	To Be Furnished by Owner																200,000
	SPARE PARTS																	Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								70,013,100

Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 1 - Hydrated Lime Order of Magnitude Cost Estimate -CONFIDENTIAL-															Estimate No.: 22005B			
Sargent & Lundy LLC Chicago															Project No.: 10584-022			
Cost Type: Est = Estimated, Bid = Vendor quote															Date: 12/20/2005			
															Rev Date: 1/27/2006			
															Run Date: 1/27/2006			
															Preparer:			
															Reviewer:			
															Wage Rates Based on: Louisville, KY			
															Labor Productivity = 1			
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	DUCTWORK MODS		Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
	INSULATION & LAGGING	3 1/2" INSUL																
DW-2	DUCTWORK SUPPORT STRUCTURES		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	STRUCTURAL STEEL		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
	ACCESS & GALLERIES																	
DW-4	DUCTWORK SUBTOTAL						26,355				329			24,650				51,100
Injection System																		
EQUIPMENT/COMPONENTS																		
	Air Blowers	150 hp each	Est	5	EA	55,125.00	275,625		105.00	525	525	PUMP	65.83	34,561				310,200
	VFD Rotary Feeder	3 hp - Stainless Steel	Est	3	EA	10,500.00	31,500		30.00	90	90	TANK	65.78	5,920				37,400
	Long-Term Storage Silo - Common for 2 Units (10 Days), Unit cost is split between Units 3 and 4	2,937,600 lb full - 19,615 ft ³ - D=20.5' - H=82.0' - CS Silo - SS Hopper	Est	1	EA	808,000.00	808,000		2545.52	2,546	2,546	TANK	65.78	167,444				975,400
	Short-Term Storage Silo - (24 Hours)	293,760 lb full - 1,920 ft ³ - D=8.5' - H=38.0' - CS Silo - SS Hopper	Est	1	EA	200,000.00	200,000		764.00	764	764	TANK	65.78	50,256				250,300
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100
	Injection Nozzles (50 Qty)	Stainless Steel	Est	1	LT	10,500.00	10,500		240.00	240	240	MECH	66.86	16,046				26,500
	System Piping	Includes fitting allowance	Est	350	LF	18.48	6,468		0.46	161	161	SPNG	70.4	11,334				17,800
	8" - CS		Est	0	LF	6.62	0		0.14	0	0	INSUL	53.39	0				0
	Piping Insulation & Lagging		Est	0	LF	0.00	0		0.00	0	0	WIRE	69.06	0				0
	Heat Tracing		Est	0	LF	0.00	0		0.00	0	0	WIRE	69.06	0				0
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800
	Supply Piping		Est	0	LS	840.00	0		100.00	0	0	SPNG	70.4	0				0
	Water Supply	Allowance	Est	0	LS	525.00	0		80.00	0	0	SPNG	70.4	0				0
	Air Supply	Allowance	Est	1	LS	1,575.00	1,575		60.00	60	60	SPNG	70.4	4,224				5,800
	Piping Supports	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	50	CY	157.50	7,875		7.00	350	350	COMP	52.91	18,519				26,400
IS-3	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-4	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700
IS-5	IS SYSTEM SUBTOTAL						1,429,593				6,704			464,542				1,894,000
MATERIAL UNLOADING SYSTEM																		
1	TRUCK DELIVERY	INCLUDED IN SILO	Est	0	Set	315,000.00	0		1753.67	0	0	SPNG	70.4	0				0
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE																	

Sargent & Lundy ^{LLC} Chicago										Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 1 - Hydrated Lime Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22005B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:			
Cost Type: Est = Estimated, Bid = Vendor quote										Wage Rates Based on: Louisville, KY													
										Labor Productivity = 1													

Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	480V SWITCHGEAR	Double Ended Unit Substation with (2) 2MVA, 6.9-480V XFMR's	Est	1	EA	575,000.00	575,000		500.00	500	500	EHEA	53.92	26,960				602,000
	New Breaker at Existing 6900V Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	60,900.00	60,900		300.00	300	300	EHEA	53.92	16,176				77,100
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600
	Power Cables for 480V Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit Routed in 1-1/2"	0.35	0	0	WIRE	69.06	0				0
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	150	LF	0.76	113	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				700
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	150	LF	1.58	236	Routed in 3/4" Conduit Routed in 1-1/2"	0.05	8	8	WIRE	69.06	549				800
	Power Cables from MCC to Loads - 50 HP	3/C #4, 600V	Est	150	LF	2.10	315	Conduit Routed in 1-1/2"	0.09	14	14	WIRE	69.06	932				1,200
	Power Cables from MCC to Loads - 100HP	3/C #4/0, 600V	Est	150	LF	9.45	1,418	Conduit	0.50	75	75	WIRE	69.06	5,180				6,600
	Power Cables from MCC to Loads - 150HP	3/C #350, 600V	Est	300	LF	10.50	3,150	Routed in 2" Conduit	0.69	207	207	WIRE	69.06	14,295				17,400
	Control Cables - Pumps	5/C #14, 600V	Est	150	LF	0.67	101	Routed in 3/4" Conduit Routed in 1-1/2"	0.03	5	5	WIRE	69.06	332				400
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Conduit	0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,300	LF	2.06	4,733		0.19	446	446	ECND	49.67	22,163				26,900
	1-1/2" Conduit		Est	300	LF	4.67	1,402		0.28	85	85	ECND	49.67	4,232				5,600
	2" Conduit		Est	300	LF	6.25	1,874		0.35	106	106	ECND	49.67	5,245				7,100
	3" Conduit		Est	900	LF	13.13	11,813		0.65	581	581	ECND	49.67	28,833				40,600
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0
AP-5	DCS SYSTEM ADDITIONS																	
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE																	
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL	60.02	6,002				16,500
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						871,538				3,370			188,413				1,060,000
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 1 - Hydrated Lime Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22005B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
MISCELLANEOUS		NONE																							
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,150.00	3,150		1170.00	1,170	1,170	PNTR	55.58	65,029				68,200							
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0							
MISC-3	STORM DRAINAGE		Est	0	LS	7,350.00	0		300.00	0	0	YDRN	51.97	0				0							
MISC-4	OTHER																								
	BLOWER HOUSE																								
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	COMP	52.91	9,259				13,200							
	PREFAB BLDG. 15'X20'		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200							
MISC-5	CFD MODEL STUDY		Est	1	LS	30,000.00	30,000		40.00	40	40	STST	86.46	3,458				33,500							
-6	TANK BERM		Est	1	LS	0.00	0		260.00	260	260	STST	86.46	22,480				22,500							
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	0.00	0		60.00	60	60	STST	86.46	5,188				5,200							
MISC-5	MISC. SUBTOTAL						75,088			1,835				116,653				191,800							
GENERAL SUPPORT																									
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							150,000				150,000							
GS-2	GENERAL SUPPORT SUBTOTAL						0			0				150,000				150,000							
SUBTOTAL							2,402,574			0	12,238			944,258				3,346,900							
	Craft Support During Startup	At 3% of Total Manhours									367	MECH	66.86	24,548				24,500							
	Allowance for Premium Time Labor																	Not Included							
	Productivity Loss Due To Overtime																	Not Included							
	Per Diem Expense																	Not Included							
	Project Wrap (Efficacy) Insurance																	Not Included							
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																167,300							
	Erection Contractor's Profit	At 8% of Material and Labor Costs																267,800							
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs							
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs							
	Consumables	At 0.5% of Equipment/Material Cost																12,000							
	Freight To Site	At 4.5% of Equipment/Material Cost																108,100							
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included							

Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 1 - Hydrated Lime Order of Magnitude Cost Estimate -CONFIDENTIAL-																	Estimate No.:	22005B
Sargent & Lundy LLC Chicago																	Project No.:	10584-022
Cost Type: Est = Estimated, Bid = Vendor quote																	Date:	12/20/2005
																	Rev Date:	1/27/2006
																	Run Date:	1/27/2006
																	Preparer:	
																	Reviewer:	
																	Wage Rates Based on:	Louisville, KY
																	Labor Productivity =	1
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	12,606			968,806				3,926,600
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								392,660
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								873,900
	CLIENT INTERNAL COST	Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								5,343,160

Louisville Gas & Electric
 Ghent Unit 3
 SO3 Mitigation System
 Option 2 - Magnesium Hydroxide
 Order of Magnitude Cost Estimate
 -CONFIDENTIAL-

Sargent & Lundy LLC
 Chicago

Cost Type: Est = Estimated, Bid = Vendor quote

Wage Rates Based on:
 Labor Productivity = Louisville, KY
 1

Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost	
DUCTWORK MODIFICATIONS																			
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800	
	DUCTWORK MODS		Est	200	SF	21.00	4,200		0.27	54	54	DINS	59.32	3,203				7,400	
	INSULATION & LAGGING	6" THICK INSULATION	Est																
DW-4	DUCTWORK SUPPORT STRUCTURES		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400	
	STRUCTURAL STEEL		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000	
	ACCESS & GALLERIES																		
DW-6	BOILER MODS		Est	2	TN	2,625.00	5,250		35.00	70	70	FLDU	89.66	6,276				11,500	
	WALL AND TUBE MODS																		
	DUCTWORK SUBTOTAL						34,125				399			30,926				65,100	
Injection System																			
IS-1	EQUIPMENT/COMPONENTS																		
	Air Blowers	Not required	Est	3	EA	21,000.00	63,000		40.00	120	120	MECH	66.86	8,023				71,000	
	VFD Rotary Feeder	Not required	Est	1	EA	10,500.00	10,500		30.00	30	30	MECH	66.86	2,006				12,500	
	Long-Term Storage Tank -	1,617,900 lb full - 17,060 ft3 -	Est	1	EA	239,000.00	239,000		580.00	580	580	TANK	65.78	38,152				277,200	
	Short-Term Storage Silo - (24 Hours)	D=26.3' - H=31.6' -	Est	0	EA	0.00	0		60.00	0	0	TANK	65.78	0				0	
	Air Compressors (2 Qty)	Not required	Est	2	EA	21,000.00	42,000		80.00	160	160	MECH	66.86	10,698				52,700	
	Mixing Tank - 1 Unit - (24 Hours)	50 hp - 2 X 100% 808,320 lb full - 8,520 ft3 - D=20.8' - H=25.0' - CS Silo - SS Hopper	Est	1	EA	115,000.00	115,000		880.00	880	880	TANK	65.78	57,886				172,900	
	Mixing Tank Agitator (1 Qty)	20 hp - CS Shaft	Est	1	EA	21,000.00	21,000		30.00	30	30	MECH	66.86	2,006				23,000	
	Water Storage Tank - 1 Unit (24 Hrs)	125,000 lb full - 2,000 ft3 - D=13.7' - H=13.7' - CS	Est	1	EA	48,000.00	48,000		880.00	880	880	TANK	65.78	57,886				105,900	
	Slurry/Water Pumps (6 Qty)	2 hp - CS	Est	6	EA	5,250.00	31,500		20.00	120	120	PUMP	65.83	7,900				39,400	
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100	
	Dual Fluid Injection Nozzles (20 Qty)	Stainless Steel	Est	1	LT	42,000.00	42,000		96.00	96	96	MECH	66.86	6,419				48,400	
	System Piping																		
	1" - CS	Includes fitting allowance	Est	300	LF	2.27	680		0.16	49	49	SPNG	70.4	3,464				4,100	
	4" - CS	Includes fitting allowance	Est	50	LF	9.28	464		0.33	17	17	SPNG	70.4	1,162				1,600	
	Piping Insulation & Lagging		Est	350	LF	2.99	1,047		0.08	26	26	INSUL	53.39	1,402				2,400	
	Heat Tracing		Est	350	LF	21.00	7,350		0.31	109	109	WIRE	69.06	7,493				14,800	
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800	
	Supply Piping																		
	Water Supply	Allowance	Est	200	LS	840.00	168,000		100.00	20,000	20,000	SPNG	70.4	1,408,000				1,576,000	
	Air Supply	Allowance	Est	200	LS	525.00	105,000		80.00	16,000	16,000	SPNG	70.4	1,126,400				1,231,400	
	Piping Supports	Allowance	Est	1	LS	2,100.00	2,100		40.00	40	40	SPNG	70.4	2,816				4,900	
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800	
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	110	CY	157.50	17,325		7.00	770	770	CONP	52.91	40,741				58,100	
IS-3	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800	

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22006B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
IS-4	AUGER CAST PILES (120 TON CAPACITY)	90 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0							
IS-5	IS SYSTEM SUBTOTAL						980,017				40,731			2,843,955				3,823,800							
MATERIAL UNLOADING SYSTEM																									
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300							
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000				1,254			88,282				193,300							
AUXILIARY POWER SUPPLY SYSTEM/I&C																									
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1 MVA, 6.9-480V XFMR's																							
	SWITCHGEAR		Est	1	EA	460,000.00	460,000		500.00	500	500	EHEA	53.92	26,960				487,000							
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA						63,000							
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600							
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600							
AP-2	GROUNDING																								
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100							
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400							
AP-3	CABLE																								
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0							
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE													
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE													
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0							
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	300	LF	0.76	227	Routed in 3/4" Conduit	0.05	16	16	WIRE	69.06	1,098				1,300							
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	150	LF	1.58	236	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				800							
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	0	LF	2.12	0	Routed in 1-1/2" Conduit	0.09	0	0	WIRE													
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	100	LF	2.67	267	Routed in 1-1/2" Conduit	0.35	35	35	WIRE													
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	50	LF	3.58	179	Routed in 2" Conduit	0.35	18	18	WIRE	69.06	1,209				1,400							
	Control Cables - Pumps	5/C #14, 600V	Est	300	LF	0.67	202	Routed in 3/4" Conduit	0.03	10	10	WIRE	69.06	663				900							
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0							
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800							
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE													
AP-4	RACEWAY																								
	3/4" Conduit		Est	2,500	LF	2.06	5,145		0.19	485	485	ECND													
	1-1/2" Conduit		Est	100	LF	4.67	467		0.28	28	28	ECND													
	2" Conduit		Est	50	LF	6.25	312		0.35	18	18	ECND													
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND													
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND													

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22006B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:						
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Labor Productivity =		Louisville, KY 1				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
AP-5	DCS SYSTEM ADDITIONS Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA						
AP-8	DCS PROGRAMMING/INTERFACE Interface Hardware Programming /Interface		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC						
			Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL						
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						689,199				2,615			80,761				709,200
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	5,250.00	5,250		1550.00	1,550	1,550	PNTR	55.58	86,149				91,400
MISC-2	ROADWORK	Not Required	Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
	PUMP HOUSE 15' X 20'																	
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
	PREFAB BLDG.		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
MISC-5	CFD MODEL STUDY		Est	1	LS	100,000.00	100,000		40.00	40	40	STST	86.46	3,458				103,500
MISC-6	TANK BERM		Est	1	LS	76,000.00	76,000		260.00	260	260	STST	86.46	22,480				98,500
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	35,000.00	35,000		60.00	60	60	STST	86.46	5,188				40,200
MISC-5	MISC. SUBTOTAL						54,538				2,155			122,239				176,700
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000
	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000
	SUBTOTAL						2,073,879				47,514			3,297,288				5,310,300
	Craft Support During Startup	At 3% of Total Manhours									1,425	MECH	66.86	95,303				95,300

Sargent & Lundy LLC Chicago										Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22006B	
Cost Type: Est = Estimated, Bid = Vendor quote										Wage Rates Based on: Louisville, KY										Project No.: 10584-022	
										Labor Productivity = 1										Date: 12/20/2005	
																				Rev Date: 1/27/2006	
																				Run Date: 1/27/2006	
																				Preparer:	
																				Reviewer:	

Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																265,500
	Erection Contractor's Profit	At 8% of Material and Labor Costs																424,800
	Mandatory Spare Parts (Start-up/Testing)	Included wEquipment Costs																Included wEquipment Costs
	Special Tools	Included wEquipment Costs																Included wEquipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																10,400
	Freight To Site	At 4.5% of Equipment/Material Cost																93,300
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	48,939			3,392,592				6,199,600
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team																620,000
	PERMITTING, MODELING, ETC.																	0
	STARTUP, TESTING AND REAGENT (15 DAYS)																	50,000
	CONTINGENCY	At 20% of Total																1,373,900
	CLIENT INTERNAL COST	To Be Furnished by Owner																100,000
	SPARE PARTS																	Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								8,343,500

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22007B						
Cost Type: Est = Estimated, Bid = Vendor quote												Project No.: 10584-022						
												Date: 12/20/2005						
												Rev Date: 1/27/2006						
												Run Date: 1/27/2006						
												Preparer:						
												Reviewer:						
												Wage Rates Based on:						
												Louisville, KY						
												Labor Productivity =						
												1						
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																	
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	INSULATION & LAGGING	3 1/2" INSUL	Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
DW-4	DUCTWORK SUPPORT STRUCTURES																	
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
DW-9	DUCTWORK SUBTOTAL						26,355			329				24,650				51,100
Injection System																		
EQUIPMENT/COMPONENTS																		
	Process Technology Package (PTP) by URS		Est	1	EA	1,800,000.00	1,800,000		20.00	20	20	PUMP	65.83	1,317				1,801,300
	Pumps (6 Qty)	4 - CS internals - 2.0 HP / 4 - SS internals - 1.0 HP	Est	6	EA	2,100.00	12,600		20.00	120	120	PUMP	65.83	7,900				20,500
	Long-Term Storage Silo - Common for 2 Units (10 Days), Unit cost is split between Units 3 and 4	420,250 lb full - 5,180 ft ³ - D=17.6' - H=21.2' - SS	Est	1	EA	363,000.00	363,000		535.21	535	535	TANK	65.78	35,206				398,200
	Soft H ₂ O Storage Tank - 1 Unit - (24 Hours)	309,312 lb full - 4,957 ft ³ - D=18.48' - H=18.48' - CS	Est	1	EA	83,000.00	83,000		489.52	490	490	TANK	65.78	32,201				115,200
	Agitator (1 Qty)	SS Shaft - 20 HP	Est	1	EA	21,000.00	21,000		30.00	30	30	MECH	66.86	2,006				23,000
	Air Compressors (2 Qty)	2 x 100% - 50 HP	Est	2	EA	21,000.00	42,000		80.00	160	160	MECH	66.86	10,698				52,700
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100
	Dual Fluid Injection Nozzles (100 Qty)	Stainless Steel	Est	1	LT	21,000.00	21,000		480.00	480	480	MECH	66.86	32,093				53,100
	System Piping	L=250' - D=4" - SS / L=50' - D=4" - CS / L=50' - D=2" - SS																
	6" - SS	Includes fitting allowance	Est	250	LF	30.61	7,652		0.42	105	105	SPNG	70.4	7,392				15,000
	6" - CS	Includes fitting allowance	Est	50	LF	11.89	594		0.42	21	21	SPNG	70.4	1,478				2,100
	4" - SS	Includes fitting allowance	Est	50	LF	24.89	1,244		0.33	17	17	SPNG	70.4	1,162				2,400
	Piping Insulation & Lagging		Est	350	LF	9.14	3,197		0.17	60	60	INSUL	53.39	3,177				6,400
	Heat Tracing		Est	350	LF	21.00	7,350		0.31	109	109	WIRE	69.06	7,493				14,800
	Valves	Allowance	Est	1	LS	2,520.00	2,520		48.00	48	48	SPNG	70.4	3,379				5,900
	Supply Piping																	
	Water Supply	Allowance	Est	1	LS	840.00	840		100.00	100	100	SPNG	70.4	7,040				7,900
	Air Supply	Allowance	Est	1	LS	525.00	525		80.00	80	80	SPNG	70.4	5,632				6,200
	Piping Supports	Allowance	Est	1	LS	2,940.00	2,940		112.00	112	112	SPNG	70.4	7,885				10,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	75	CY	157.50	11,813		7.00	525	525	CONP	52.91	27,778				39,600
	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-	AUGER CAST PILES (125 TON CAPACITY)	100 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0
IS-3	ROYALTY FEE		Est	0	LF									0				0

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22007B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
IS-4	IS SYSTEM SUBTOTAL						2,446,275				3,810			253,595					2,699,800						
	MATERIAL UNLOADING SYSTEM																								
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300							
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000				1,254			88,282				193,300							
	AUXILIARY POWER SUPPLY SYSTEM/I&C																								
AP-1	POWER SOURCE																								
	SWITCHGEAR		Est	1	EA	460,000.00	460,000		500.00	500	500	EHEA	53.92	26,960				487,000							
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400							
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600							
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600							
AP-2	GROUNDING																								
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100							
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400							
AP-3	CABLE																								
	Power Cables for MCC's		Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0							
	Power Cables for MCC's		Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600							
	Power Cables for Switchgear		Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0							
	Power Cables from Switchgear to TR Sets		Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0							
	Power Cables from MCC to Loads - 1 ~ 5HP		Est	200	LF	0.76	151	Routed in 3/4" Conduit	0.05	11	11	WIRE	69.06	732				900							
	Power Cables from MCC to Loads - 15HP		Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0							
	Power Cables from MCC to Loads - 20 ~ 30 HP		Est	50	LF	2.12	106	Routed in 1-1/2" Conduit	0.09	5	5	WIRE	69.06	311				400							
	Power Cables from MCC to Loads - 50HP		Est	100	LF	2.67	267	Routed in 1-1/2" Conduit	0.35	35	35	WIRE	69.06	2,417				2,700							
	Power Cables from MCC to Loads - 60HP		Est	0	LF	3.58	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0							
	Control Cables - Pumps		Est	175	LF	0.67	118	Routed in 3/4" Conduit	0.03	6	6	WIRE	69.06	387				500							
	Control Cables - TR Sets		Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0							
	Instrumentation Cables		Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800							
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400							
AP-4	RACEWAY																								
	3/4" Conduit		Est	2,125	LF	2.06	4,373		0.19	412	412	ECND	49.67	20,477				24,800							
	1-1/2" Conduit		Est	150	LF	4.67	701		0.28	43	43	ECND	49.67	2,116				2,800							
	2" Conduit		Est	0	LF	6.25	0		0.35	0	0	ECND	49.67	0				0							
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND	49.67	8,009				11,300							
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0							
AP-5	DCS SYSTEM ADDITIONS																								
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700							
AP-8	DCS PROGRAMMING/INTERFACE																								

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-											Estimate No.: 22007B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:					
Cost Type: Est = Estimated, Bid = Vendor quote													Wage Rates Based on: Labor Productivity =		Louisville, KY 1			
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						693,130				2,558			143,552				836,900
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,675.00	3,675		1250.00	1,250	1,250	PNTR	55.58	69,475				73,200
2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
	PUMP HOUSE 15' X 20'																	
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	COMP	52.91	9,259				13,200
	PREFAB BLDG.		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
MISC-5	CFD MODEL STUDY		Est	1	LS	0.00	0		40.00	40	40	STST	86.46	3,458				3,500
MISC-6	TANK BERM		Est	1	LS	61,000.00	61,000		260.00	260	260	STST	86.46	22,480				83,500
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	37,000.00	37,000		60.00	60	60	STST	86.46	5,188				42,200
MISC-5	MISC. SUBTOTAL						150,963				2,215			136,691				287,700
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000
	SUBTOTAL						3,421,723				0		10,167	746,770				4,168,800
	Craft Support During Startup	At 3% of Total Manhours									305	MECH	66.86	20,392				20,400
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22007B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:						
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Louisville, KY		Labor Productivity = 1				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																208,400
	Erection Contractor's Profit	At 8% of Material and Labor Costs																333,500
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																17,100
	Freight To Site	At 4.5% of Equipment/Material Cost																154,000
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	10,472			767,162				4,902,200
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								490,200
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								1,088,500
	CLIENT INTERNAL COST	Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								6,630,900

Louisville Gas & Electric																	Estimate No.:	22008B
Ghent Unit 3																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 4 - Sodium Bisulfite (SBS)																	Rev Date:	1/26/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
																	Reviewer:	
																	Wage Rates Based on:	Louisville, KY
																	Labor Productivity =	1
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																	
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	INSULATION & LAGGING	3 1/2" INSUL	Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
DW-4	DUCTWORK SUPPORT STRUCTURES																	
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
DW-9	DUCTWORK SUBTOTAL						26,355				329			24,650				51,100
Injection System																		
EQUIPMENT/COMPONENTS																		
	Process Technology Package (PTP). The cost shown here is for a single skid shared by Unit 3 and 4.	P&ID, Control Logic, Injection and metering pump skids, Proprietary injection lances 4 - CS internals - 2.0 HP / 4 - SS internals - 1.0 HP, included in PTP	Budget	1	EA	1,200,000.00	1,200,000		200.00	200	200	MISC	65.83	13,166				1,213,200
	Pumps (0 Qty)		Est	0	EA	0.00	0		20.00	0	0	PUMP	65.83	0				0
	SBS Solution Tank - 1 Unit (10 Days)	825,400 lb full - 12,100 ft ³ - D=23.4' - H=28.0' - SS	Est	1	EA	217,000.00	217,000		1064.00	1,064	1,064	TANK	65.78	69,990				287,000
	Soft H ₂ O Storage Tank - 1 Unit - (24 Hours)	309,312 lb full - 4,957 ft ³ - D=18.48' - H=18.48' - CS	Est	1	EA	45,000.00	45,000		820.92	821	821	TANK	65.78	54,000				99,000
	Agitator (1 Qty)	SS Shaft - 20 HP	Est	1	EA	10,000.00	10,000		30.00	30	30	MECH	66.86	2,006				12,000
	Air Compressors (2 operating, 1 standby for each Unit)	3 x 100% - 150 HP	Est	3	EA	225,000.00	675,000		120.00	360	360	MECH	66.86	24,070				699,100
	Injection Manifold (2 Qty)	Stainless Steel included in PTP	Est	2	EA	0.00	0		0.00	0	0	MECH	66.86	0				0
	System Piping	L=300' - D=6" - SS / L=200' - D=6" - CS / L=100' - D=4" - SS																
	6" - SS	Includes fitting allowance	Est	300	LF	30.61	9,182		0.42	126	126	SPNG	70.4	8,870				18,100
	6" - CS	Includes fitting allowance	Est	200	LF	11.89	2,377		0.42	84	84	SPNG	70.4	5,914				8,300
	4" - SS	Includes fitting allowance	Est	100	LF	24.89	2,489		0.33	33	33	SPNG	70.4	2,323				4,800
	Piping Insulation & Lagging		Est	500	LF	9.14	4,568		0.17	85	85	INSUL	53.39	4,538				9,100
	Heat Tracing		Est	500	LF	21.00	10,500		0.31	155	155	WIRE	69.06	10,704				21,200
	Valves	Allowance	Est	1	LS	2,520.00	2,520		48.00	48	48	SPNG	70.4	3,379				5,900
	Supply Piping																	
	Water Supply piping	Allowance	Est	1	LS	840.00	840		100.00	100	100	SPNG	70.4	7,040				7,900
	Air Supply piping	Allowance	Est	1	LS	525.00	525		80.00	80	80	SPNG	70.4	5,632				6,200
	Piping Supports	Allowance	Est	1	LS	2,940.00	2,940		112.00	112	112	SPNG	70.4	7,885				10,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-3	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	90	CY	157.50	14,175		7.00	630	630	CONP	52.91	33,333				47,500
IS-3	STRUCTURAL STEEL	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800

Louisville Gas & Electric																	Estimate No.:	22008B
Ghent Unit 3																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 4 - Sodium Bisulfite (SBS)																	Rev Date:	1/26/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Reviewer:	
Labor Productivity =																	1	
Louisville, KY																		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
IS-3	AUGER CAST PILES (125 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700
IS-4	ROYALTY FEE	Not Included, \$ per MW, to be negotiated with Vendor	Est	0	LF									0				0
IS-5	IS SYSTEM SUBTOTAL																	
	MATERIAL UNLOADING SYSTEM																	
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL																	
	AUXILIARY POWER SUPPLY SYSTEM/I&C																	
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1 MVA, 6.9-480V XFMR's																
	SWITCHGEAR		Est	1	EA	488,750.00	488,750		500.00	500	500	EHEA	53.92	26,960				515,700
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	100	LF	33.60	3,360	Routed in 5" Conduit	0.69	69	69	WIRE	69.06	4,765				8,100
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	200	LF	0.76	151	Routed in 3/4" Conduit	0.05	11	11	WIRE	69.06	732				900
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	50	LF	2.12	106	Routed in 1-1/2" Conduit	0.09	5	5	WIRE	69.06	311				400
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	100	LF	2.67	267	Routed in 1-1/2" Conduit	0.35	35	35	WIRE	69.06	2,417				2,700
	Power Cables from MCC to Loads - 150HP	3/C 250kcmil, 600V	Est	250	LF	3.58	895	Routed in 3" Conduit	0.35	88	88	WIRE	69.06	6,043				6,900
	Control Cables - Pumps	5/C #14, 600V	Est	175	LF	0.67	118	Routed in 3/4" Conduit	0.03	6	6	WIRE	69.06	387				500
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,125	LF	2.06	4,373		0.19	412	412	ECND	49.67	20,477				24,800
	1-1/2" Conduit		Est	150	LF	4.67	701		0.28	43	43	ECND	49.67	2,116				2,800
	2" Conduit		Est	250	LF	6.25	1,562		0.35	88	88	ECND	49.67	4,371				5,900
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND	49.67	8,009				11,300
	5" Conduit		Est	100	LF	38.33	3,833		1.13	113	113	ECND	49.67	5,598				9,400

Louisville Gas & Electric																	Estimate No.:	22008B
Ghent Unit 3																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 4 - Sodium Bisulfite (SBS)																	Rev Date:	1/26/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Reviewer:	
Labor Productivity =																	Louisville, KY	1
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip/ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
AP-5	DCS SYSTEM ADDITIONS Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL					731,530					2,916			164,329				895,900
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,675.00	3,675		1250.00	1,250	1,250	PNTR	55.58	69,475				73,200
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER PUMP HOUSE 15' X 20' PREFAB BLDG.			1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
MISC-5	CFD Model Study		Est	1	LS	0.00	0		40.00	40	40	STST	86.46	3,458				3,500
MISC-6	Berm around Tanks	60,000 gallon tank, 12" concrete wall, 6" slab, sump, for 110% containment (40' x 40' x 6' high)	Est	1	LS	74,000.00	74,000		260.00	260	260	STST	86.46	22,480				96,500
MISC-7	Soft Water Supply System	36" x 60" regeration 1,845 gallon	Est	1	LS	23,000.00	23,000		60.00	60	60	STST	86.46	5,188				28,200
MISC-8	MISC. SUBTOTAL					149,963					2,215			136,691				286,700
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000

Louisville Gas & Electric										Estimate No.: 22008B								
Ghent Unit 3										Project No.: 10584-022								
SO3 Mitigation System										Date: 12/20/2005								
Option 4 - Sodium Bisulfite (SBS)										Rev Date: 1/26/2006								
Order of Magnitude Cost Estimate										Run Date: 1/27/2006								
-CONFIDENTIAL-										Preparer:								
										Reviewer:								
Wage Rates Based on:										Louisville, KY								
Labor Productivity =										1								
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
SUBTOTAL							3,275,963			0	12,105			889,204				4,165,400
	Craft Support During Startup	At 3% of Total Manhours								363	MECH	66.86	24,281					24,300
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																208,300
	Erection Contractor's Profit	At 8% of Material and Labor Costs																333,200
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																16,400
	Freight To Site	At 4.5% of Equipment/Material Cost																147,400
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
SUBTOTAL INSTALLED COST										0	12,469			913,485				4,895,000
ENGINEERING / CONSTRUCTION MANAGEMENT		Furnished by Project Team								0								489,500
PERMITTING, MODELING, ETC.										0								0
STARTUP, TESTING AND REAGENT (15 DAYS)										0								50,000
CONTINGENCY		At 20% of Total								0								1,086,900
CLIENT INTERNAL COST		Furnished by Owner								0								100,000
SPARE PARTS										0								Not Included
ESCALATION		Not Included																0
INTEREST DURING CONSTRUCTION (AFUDC)		Not Included																0
PROJECT TOTAL :										0								6,621,400

Louisville Gas & Electric																	Estimate No.:	22009A	
Ghent Unit 3																	Project No.:	10584-022	
SO3 Mitigation System																	Date:	12/20/2005	
Option 5 - Trona																	Rev Date:		
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006	
-CONFIDENTIAL-																	Preparer:		
Wage Rates Based on:																	Louisville, KY	Reviewer:	
Labor Productivity =																	1		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost	
DUCTWORK MODIFICATIONS																			
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800	
	DUCTWORK MODS		Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900	
	INSULATION & LAGGING	3 1/2" INSUL																	
DW-2	DUCTWORK SUPPORT STRUCTURES		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400	
	STRUCTURAL STEEL		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000	
	ACCESS & GALLERIES																		
DW-4	DUCTWORK SUBTOTAL						26,355			329				24,650				51,100	
Injection System																			
EQUIPMENT/COMPONENTS																			
	Air Blowers	150 hp each	Est	6	EA	55,125.00	330,750		105.00	630	630	PUMP	65.83	41,473				372,200	
	VFD Rotary Feeder	3 hp - Stainless Steel	Est	3	EA	10,500.00	31,500		30.00	90	90	TANK	65.78	5,920				37,400	
	Long-Term Storage Silo - Common for 2 Units (10 Days), Unit cost is split between Units 3 and 4	2,687,900 lb full - 11,610 ft ³ - D=20.7' - H=83.0' - CS Silo - SS Hopper	Est	1	EA	590,000.00	590,000		1624.00	1,624	1,624	TANK	65.78	106,827				696,800	
	Short-Term Storage Silo - (24 Hours)	268,800 lb full - 1,160 ft ³ - D=8.7' - H=39.0' - CS Silo - SS Hopper	Est	1	EA	180,000.00	180,000		120.00	120	120	TANK	65.78	7,894				187,900	
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100	
	Injection Nozzles (50 Qty)	Stainless Steel	Est	1	LT	10,500.00	10,500		240.00	240	240	MECH	66.86	16,046				26,500	
	System Piping																		
	8" - CS	Includes fitting allowance	Est	350	LF	18.48	6,468		0.46	160	160	SPNG	70.4	11,236				17,700	
	Piping Insulation & Lagging		Est	0	LF	6.62	0		0.14	0	0	INSUL	53.39	0				0	
	Heat Tracing		Est	0	LF	0.00	0		0.00	0	0	WIRE	69.06	0				0	
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800	
	Supply Piping																		
	Water Supply	Allowance	Est	0	LS	840.00	0		100.00	0	0	SPNG	70.4	0				0	
	Air Supply	Allowance	Est	0	LS	525.00	0		80.00	0	0	SPNG	70.4	0				0	
	Piping Supports	Allowance	Est	1	LS	1,575.00	1,575		60.00	60	60	SPNG	70.4	4,224				5,800	
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800	
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	90	CY	157.50	14,175		7.00	630	630	CONP	52.91	33,333				47,500	
	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800	
IS-3	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700	
IS-4	IS SYSTEM SUBTOTAL						1,253,018			5,522				383,190				1,636,000	
MATERIAL UNLOADING SYSTEM																			
ASH-1	TRUCK UNLOADING SYSTEM	Included in silo	Est	0	Set	105,000.00	0		1254.00	0	0	SPNG	70.4	0				0	
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						0			0				0				0	

Louisville Gas & Electric																	Estimate No.:	22009A
Ghent Unit 3																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 5 - Trona																	Rev Date:	
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Reviewer:	
Labor Productivity =																	Louisville, KY	1
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1MVA, 6.9-480V XFMR's																
	480V SWITCHGEAR		Est	1	EA	580,000.00	580,000		500.00	500	500	EHEA	53.92	26,960				607,000
	New Breaker at Existing 4160V Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	60,900.00	60,900		300.00	300	300	EHEA	53.92	16,176				77,100
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 500kcmil, 600kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600
	Power Cables for 480V Switchgear	3/C 4/0kcmil, 5kV	Est	250	LF	8.40	2,100	Routed in 2" Conduit	0.35	88	88	WIRE	69.06	6,043				8,100
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	150	LF	0.76	113	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				700
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 50 HP	3/C #4, 600V	Est	150	LF	2.10	315	Routed in 1-1/2" Conduit	0.09	14	14	WIRE	69.06	932				1,200
	Power Cables from MCC to Loads - 100HP	3/C #4/0, 600V	Est	150	LF	9.45	1,418	Routed in 1-1/2" Conduit	0.50	75	75	WIRE	69.06	5,180				6,600
	Power Cables from MCC to Loads - 150HP	3/C #350, 600V	Est	300	LF	10.50	3,150	Routed in 2" Conduit	0.69	207	207	WIRE	69.06	14,295				17,400
	Control Cables - Pumps	5/C #14, 600V	Est	150	LF	0.67	101	Routed in 3/4" Conduit	0.03	5	5	WIRE	69.06	332				400
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,300	LF	2.06	4,733		0.19	446	446	ECND	49.67	22,163				26,900
	1-1/2" Conduit		Est	300	LF	4.67	1,402		0.28	85	85	ECND	49.67	4,232				5,600
	2" Conduit		Est	550	LF	6.25	3,436		0.35	194	194	ECND	49.67	9,616				13,100
	3" Conduit		Est	900	LF	13.13	11,813		0.65	581	581	ECND	49.67	28,833				40,600
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0
AP-5	DCS SYSTEM ADDITIONS																	
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE																	
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL	60.02	6,002				16,500
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						879,964				3,538			198,278				1,078,300

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 5 - Trona Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22009A		Project No.: 10584-022		Date: 12/20/2005		Rev Date:		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
	REINFORCING OF EXISTING EQUIPMENT	NONE																							
	DEMOLITION / RELOCATIONS	NONE																							
	MISCELLANEOUS	NONE																							
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,150.00	3,150		1170.00	1,170	1,170	PNTR	55.58	65,029				68,200							
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0							
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900							
MISC-4	OTHER																								
	BLOWER HOUSE																								
	PREFAB BLDG (15' x 20')			1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200							
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200							
MISC-5	CFD MODEL STUDY		Est	1	LS	30,000.00	30,000		40.00	40	40	STST	86.46	3,458				33,500							
MISC-6	TANK BERM		Est	1	LS	0.00	0		260.00	260	260	STST	86.46	22,480				22,500							
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	0.00	0		60.00	60	60	STST	86.46	5,188				5,200							
MISC-5	MISC. SUBTOTAL						82,438				2,135			132,244				214,700							
	GENERAL SUPPORT																								
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000							
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000							
	SUBTOTAL						2,241,774				11,524			838,362				3,080,100							
	Craft Support During Startup	At 3% of Total Manhours									346	MECH	66.86	23,115				23,100							
	Allowance for Premium Time Labor																	Not Included							
	Productivity Loss Due To Overtime																	Not Included							
	Per Diem Expense																	Not Included							
	Project Wrap (Efficacy) Insurance																	Not Included							
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																154,000							
	Erection Contractor's Profit	At 8% of Material and Labor Costs																246,400							
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs							

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 5 - Trona Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22009A		Project No.: 10584-022		Date: 12/20/2005		Rev Date:		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
	Special Tools	Included w/Equipment Costs																	Included w/Equipment Costs						
	Consumables	At 0.5% of Equipment/Material Cost																	11,200						
	Freight To Site	At 4.5% of Equipment/Material Cost																	100,900						
	Taxes - Sales/Use/VAT/Business/Etc.																		Not Included						
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																	By Owner						
	SUBTOTAL INSTALLED COST									0	11,870			861,477					3,615,700						
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0									361,600						
	PERMITTING, MODELING, ETC.									0									0						
	STARTUP REAGENT TESTING (15 DAYS)									0									50,000						
	CONTINGENCY	At 20% of Total								0									805,500						
	CLIENT INTERNAL COST	To Be Furnished by Owner								0									100,000						
	IE PARTS									0									Not Included						
	LOCALIZATION	Not Included								0									0						
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0									0						
	PROJECT TOTAL :									0									4,932,800						

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 6 - Vertical Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22010A		Project No.: 10584-022		Date: 12/20/2005		Rev Date:		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
DUCTWORK MODIFICATIONS																									
DW-1	MODIFY GAS DUCT FOR WESP AND TO ACCEPT INJECTION NOZZLES		Est	0	TN	2,500.00	0		35.00	0	0	FLDU	89.66	0				0							
	DUCTWORK MODS		Est	0	SF	8.00	0		0.27	0	0	DINS	59.32	0				0							
	INSULATION & LAGGING																								
DW-4	DUCTWORK SUPPORT STRUCTURES		Est	0	TN	1,800.00	0		16.00	0	0	STST	86.46	0				0							
	STRUCTURAL STEEL		Est	0	SF	30.00	0		0.40	0	0	GALL	71.2	0				0							
	ACCESS & GALLERIES																								
DW-5	FOUNDATIONS		Est	0	CY	150.00	0		7.00	0	0	CONP	52.91	0				0							
	FOUNDATIONS FOR DUCTWORK AND STRUCTURAL STEEL	INCLUDES EXCAVATION & BACKFILL																							
DW-6	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0							
	DUCTWORK SUBTOTAL						0			0				0				0							
WESP & ASSOCIATED EQUIP																									
WE-1	EQUIPMENT/COMPONENTS																								
WE-2	WESP (One ESP boxes, with three fields, 6 feet long, total 150 SCA. All internal 2205, with 2205 carbon steel clad alloy plate construction)	INCLUDES ALL ASSOCIATED DUCTWORK AND WASTE WATER EQUIPMENT.PIPING AND TANKS	Est	1	EA	28,945,000.00	28,945,000	BUDGETARY INPUT FROM VENDORS	76901	76,901	76,901	PREC	86.72	6,668,871				35,613,900							
WE-3	Chimney Liner Adjustment	RETURN TO EXISTING CHIMNEY	Est	0	LF	-5302.50	0		-55	0	0	PREC	86.72	0				0							
WE-4	Chimney Breaching Adjustment	NONE	Est	0	LS	0.00	0		0	0	0	PREC	86.72	0				0							
WE-5	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	210	CY	157.50	33,075		7.00	1,470	1,470	CONP	52.91	77,778				110,900							
WE-6	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0							
WE-7	FIBERGLASS DUCT			50	LF	7,200.00	360,000		50.00	2,500	2,500	DUCT	82.81	207,025				567,000							
WE-8	WE SYSTEM SUBTOTAL						29,338,075			80,871				6,953,674				36,291,800							
AUXILIARY POWER SUPPLY SYSTEM/I&C																									
AP-1	POWER SOURCE																								
	SWITCHGEAR	Double Ended Unit Substation with (2) 2MVA, 6.9 480V XFMR's	Est	2	EA	575,000.00	1,150,000		500.00	1,000	1,000	EHEA	53.92	53,920				1,203,900							
	New Breaker at Existing 13.2kV Switchgear		Est	2	EA	63,000.00	126,000		100.00	200	200	EHEA	53.92	10,784				136,800							
	MCC		Est	2	EA	52,500.00	105,000		240.00	480	480	EHEA	53.92	25,882				130,900							

Louisville Gas & Electric																	Estimate No.:	22010A	
Ghent Unit 3																	Project No.:	10584-022	
SO3 Mitigation System																	Date:	12/20/2005	
Option 6 - Vertical Flow WESP																	Rev Date:		
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006	
-CONFIDENTIAL-																	Preparer:		
Wage Rates Based on:																	Louisville, KY	Reviewer:	
Labor Productivity =																	1		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost	
	Misc Electrical Equipment & Controls		Est	1	LS	86,100.00	86,100		504.00	504	504	EHEA	53.92	27,176				113,300	
AP-2	GROUNDING																	0	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100	
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400	
AP-3	CABLE																		
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	100	LF	33.60	3,360	Routed in 5" Conduit	0.69	69	69	WIRE	69.06	4,765				8,100	
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	0	LF	14.70	0	Routed in 3" Conduit	0.69	0	0	WIRE	69.06	0				0	
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	1,000	LF	8.40	8,400	Routed in 2" Conduit	0.35	350	350	WIRE	69.06	24,171				32,600	
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	3,600	LF	6.30	22,680	Routed in 1-1/2" Conduit	0.52	1,872	1,872	WIRE	69.06	129,280				152,000	
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	0	LF	0.76	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0	
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	1,500	LF	1.58	2,363	Routed in 3/4" Conduit	0.05	80	80	WIRE	69.06	5,490				7,900	
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	0	LF	2.12	0	Routed in 1-1/2" Conduit	0.09	0	0	WIRE	69.06	0				0	
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	0	LF	2.67	0	Routed in 1-1/2" Conduit	0.35	0	0	WIRE	69.06	0				0	
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	0	LF	3.58	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0	
	Control Cables - Pumps	5/C #14, 600V	Est	1,500	LF	0.67	1,008	Routed in 3/4" Conduit	0.03	48	48	WIRE	69.06	3,315				4,300	
	Control Cables - TR Sets	7/C #14, 600V	Est	3,600	LF	0.81	2,911	Routed in 1-1/2" Conduit	0.04	144	144	WIRE	69.06	9,945				12,900	
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800	
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400	
AP-4	RACEWAY																		
	3/4" Conduit		Est	4,750	LF	2.06	9,776		0.19	922	922	ECND	49.67	45,771				55,500	
	1-1/2" Conduit		Est	3,600	LF	4.67	16,821		0.28	1,022	1,022	ECND	49.67	50,783				67,600	
	2" Conduit		Est	1,000	LF	6.25	6,248		0.35	352	352	ECND	49.67	17,484				23,700	
	3" Conduit		Est	0	LF	13.13	0		0.65	0	0	ECND	49.67	0				0	
	5" Conduit		Est	100	LF	38.33	3,833		1.13	113	113	ECND	49.67	5,598				9,400	
AP-5	DCS SYSTEM ADDITIONS																		
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700	
AP-8	DCS PROGRAMMING/INTERFACE																		
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800	
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300	
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800	
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						1,609,556			7,569				441,458				2,051,200	
	REINFORCING OF EXISTING EQUIPMENT	NONE																	
	DEMOLITION / RELOCATIONS	NONE																	
	MISCELLANEOUS	NONE																	
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	87150.00	87,150		3250.00	3,250	3,250	PNTR	55.58	180,635				267,800	

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 6 - Vertical Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22010A Project No.: 10584-022 Date: 12/20/2005 Rev Date Run Date: 1/27/2006 Preparer: Reviewer:						
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Labor Productivity =		Louisville, KY 1				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
MISC-2	ROADWORK	20' WIDTH X 1000 LF GRAVEL	Est	1	LS	46000.00	46,000		380.00	380	380	PBIT	62.43	23,723				69,700
MISC-3	STORM DRAINAGE		Est	1	LS	7350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
MISC-5	MISC. SUBTOTAL						140,500				3,930			219,949				360,400
MISC-1	PAINTING	Touch-up and Field Finish	Est	0	LS	0	0		3250.00	0	0	PNTR	55.58	0				0
MISC-2	ROADWORK	20' WIDTH X 1000 LF GRAVEL	Est	0	LS	0	0		475.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	0	LS	0	0		538.43	0	0	YDRN	51.97	0				0
MISC-4	OTHER																	
MISC-5	CFD MODEL STUDY		Est	1	LS	0.00	0		40.00	40	40	STST	86.46	3,458				3,500
MISC-5	MISC. SUBTOTAL						0				40			3,458				3,500
GENERAL SUPPORT																		
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT	0	0							100,000				100,000
GS-2	CRANE RENTAL	700 Ton - 4 months	Est	1	LT	0	0	includes freight in and out						480,000				480,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			580,000				580,000
SUBTOTAL							31,088,131				92,410			8,198,540				39,286,900
Craft Support During Startup		At 3% of Total Manhours									2,772	MECH	66.86	185,357				185,400
Allowance for Premium Time Labor																		Not Included
Productivity Loss Due To Overtime																		Not Included
Per Diem Expense																		Not Included
Project Wrap (Efficacy) Insurance																		Not Included
Erection Contractor's General & Administrative Costs		At 5% of Material and Labor Costs - WESP																517,100
Erection Contractor's Profit		At 8% of Material and Labor Costs - WESP																827,400
Mandatory Spare Parts (Start-up/Testing)		Included w/Equipment Costs																Included w/Equipment Costs
Special Tools		Included w/Equipment Costs																Included w/Equipment Costs
Consumables		At 0.5% of Equipment/Material Cost																155,400

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 3 SO3 Mitigation System Option 6 - Vertical Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22010A Project No.: 10584-022 Date: 12/20/2005 Rev Date: Run Date: 1/27/2006 Preparer: Reviewer:						
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Labor Productivity =		Louisville, KY 1				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Freight To Site	At 4.5% of Equipment/Material Cost																1,399,000
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	95,183			8,383,896				42,371,200
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								1,906,700
	PERMITTING, MODELING, ETC.									0								0
	STARTUP AND TESTING									0								100,000
	CONTINGENCY	At 20% of Total								0								8,875,600
	CLIENT INTERNAL COST	To Be Furnished by Owner								0								200,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included								0								0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0								0
	PROJECT TOTAL :									0								53,453,500

Louisville Gas & Electric																	Estimate No.:	22011A
Ghent Unit 4																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 7 - Horizontal Flow WESP																	Rev Date:	
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
																	Reviewer:	
																	Wage Rates Based on:	Louisville, KY
																	Labor Productivity =	1
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS		COSTS																
WESP & ASSOCIATED EQUIP																		
WE-1	WESP (Two ESP boxes, with 29 feet three fields, 9 feet long 1st field at 9.75" spacing with 76 gas passages, and 11 feet long 2nd and 3rd fields at 11.75" spacing with 64 passages, total 170 SCA. All internal 2205, with 2205 carbon steel clad alloy plate construction)	INCLUDES ALL ASSOCIATED DUCTWORK AND WASTE WATER EQUIPMENT, PIPING AND TANKS	Est	1	EA	30,490,000.00	30,490,000	BUDGETARY INPUT FROM VENDOR	142817	142,817	142,817	PREC	86.72	12,385,047				42,875,000
WE-2	Chimney Liner Adjustment (WITH MODIFIED BREECHING AT WESP OUTLET ELEVATION)	RETURN TO EXISTING BREECHING	Est	0	LF	5,302.50	0		55	0	0	PREC	86.72	0				0
	Chimney Breaching Adjustment		Est	0	LS	21,000.00	0		220	0	0	PREC	86.72	0				0
WE-4	Electrical Building	20'x40'	Est	1	EA	21,000.00	21,000		100.00	100	100	STST	86.46	8,646				29,600
WE-5	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	810	CY	157.50	127,575		7.00	5,670	5,670	COMP	52.91	300,000				427,600
WE-6	STRUCTURAL STEEL		Est	170	TN	2,200.00	374,000		16.00	2,720	2,720	STST	86.46	235,171				609,200
WE-7	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,000	LF	10.00	20,000		0.52	1,040	1,040	PILE	82.81	86,122				106,100
WE-7	FIBER GLASS DUCT 23' DIA		Est	450	LF	7,200.00	3,240,000		50.00	22,500	22,500	DUCT	59.32	1,334,700				4,574,700
WE-8	WE SYSTEM SUBTOTAL						34,272,575				174,847			14,349,686				48,622,200
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 2MVA, 6.9-480V XFMR's																
	SWITCHGEAR		Est	1	EA	575,000.00	575,000		500.00	500	500	EHEA	53.92	26,960				602,000
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	52,500.00	105,000		240.00	480	480	EHEA	53.92	25,882				130,900
	Misc Electrical Equipment & Controls		Est	1	LS	86,100.00	86,100		324.00	324	324	EHEA	53.92	17,470				103,600
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	100	LF	33.60	3,360	Routed in 5" Conduit	0.69	69	69	WIRE	69.06	4,765				8,100
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	0	LF	14.70	0	Routed in 3" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	1,000	LF	8.40	8,400	Routed in 2" Conduit	0.35	350	350	WIRE	69.06	24,171				32,600
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	2,400	LF	6.30	15,120	Routed in 1-1/2" Conduit	0.52	1,248	1,248	WIRE	69.06	86,187				101,300
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	0	LF	0.76	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	1,500	LF	1.58	2,363	Routed in 3/4" Conduit	0.05	80	80	WIRE	69.06	5,490				7,900
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	0	LF	2.12	0	Routed in 1-1/2" Conduit	0.09	0	0	WIRE	69.06	0				0

Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 7 - Horizontal Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-															Estimate No.: 22011A			
Sargent & Lundy LLC Chicago															Project No.: 10584-022			
															Date: 12/20/2005			
															Rev Date:			
															Run Date: 1/27/2006			
															Preparer:			
															Reviewer:			
Cost Type: Est = Estimated, Bid = Vendor quote															Wage Rates Based on: Louisville, KY			
															Labor Productivity = 1			
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	0	LF	2.67	0	Routed in 1-1/2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	0	LF	3.58	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Control Cables - Pumps	5/C #14, 600V	Est	1,500	LF	0.67	1,008	Routed in 3/4" Conduit	0.03	48	48	WIRE	69.06	3,315				4,300
	Control Cables - TR Sets	7/C #14, 600V	Est	2,400	LF	0.81	1,940	Routed in 1-1/2" Conduit	0.04	96	96	WIRE	69.06	6,630				8,600
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	4,750	LF	2.06	9,776		0.19	922	922	ECND	49.67	45,771				55,500
	1-1/2" Conduit		Est	2,400	LF	4.67	11,214		0.28	682	682	ECND	49.67	33,855				45,100
	2" Conduit		Est	1,000	LF	6.25	6,248		0.35	352	352	ECND	49.67	17,484				23,700
	3" Conduit		Est	0	LF	13.13	0		0.65	0	0	ECND	49.67	0				0
	5" Conduit		Est	100	LF	38.33	3,833		1.13	113	113	ECND	49.67	5,598				9,400
AP-5	DCS SYSTEM ADDITIONS																	
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE																	
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						957,418				5,776			336,065				1,293,700
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	87,150.00	87,150		3250.00	3,250	3,250	PNTR	55.58	180,635				267,800
MISC-2	ROADWORK	20' WIDTH X 1000 LF GRAVEL	Est	1	LS	45,937.50	45,938		380.00	380	380	PBIT	62.43	23,723				69,700
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
MISC-5	MISC. SUBTOTAL						140,438				3,930			219,949				360,400
-5	CFD MODEL STUDY		Est	1	LS	0.00	0		40.00	40	40	STST	86.46	3,458				3,500
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000

Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 7 - Horizontal Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 22011A Project No.: 10584-022 Date: 12/20/2005 Rev Date: Run Date: 1/27/2006 Preparer: Reviewer:				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
GS-2	CRANE RENTAL	700 Ton - 2 months	Est	1	LT		0	Includes freight in and out						310,000				310,000
GS-2	GENERAL SUPPORT SUBTOTAL						0			0				410,000				410,000
	SUBTOTAL						35,370,431			0	184,593			15,319,159				50,689,800
	Craft Support During Startup	At 3% of Total Manhours								5,538		MECH	66.86	370,256				370,300
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs - WESP																1,010,000
	Erection Contractor's Profit	At 8% of Material and Labor Costs - WESP																1,616,000
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																176,900
	Freight To Site	At 4.5% of Equipment/Material Cost																1,591,700
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	190,131			15,689,415				55,454,700
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								2,495,000
	PERMITTING, MODELING, ETC.									0								0
	STARTUP AND TESTING									0								100,000
	CONTINGENCY	At 20% of Total								0								11,609,900
	CLIENT INTERNAL COST	To Be Furnished by Owner								0								200,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included								0								0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0								0
	PROJECT TOTAL :									0								69,859,600

Sargent & Lundy LLC
Chicago

Louisville Gas & Electric
Ghent Unit 4
SO3 Mitigation System
Option 1 - Hydrated Lime
Order of Magnitude Cost Estimate
-CONFIDENTIAL-

Estimate No.: 22012B
Project No.: 10584-022
Date: 12/20/2005
Rev Date: 1/27/2006
Run Date: 1/27/2006
Preparer:
Reviewer:

Cost Type: Est = Estimated, Bid = Vendor quote

Wage Rates Based on: Louisville, KY
Labor Productivity = 1

Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																	
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	INSULATION & LAGGING	3 1/2" INSUL	Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
DW-2	DUCTWORK SUPPORT STRUCTURES																	
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
DW-4	DUCTWORK SUBTOTAL						26,355				329			24,650				51,100
Injection System																		
IS-1	EQUIPMENT/COMPONENTS																	
	Air Blowers	150 hp each	Est	5	EA	55,125.00	275,625		105.00	525	525	PUMP	65.83	34,561				310,200
	VFD Rotary Feeder	3 hp - Stainless Steel	Est	3	EA	10,500.00	31,500		30.00	90	90	TANK	65.78	5,920				37,400
	Long-Term Storage Silo - Common for 2 Units (10 Days), Unit cost is split between Units 3 and 4	2,937,600 lb full - 19,615 ft ³ - D=20.5' - H=82.0' - CS Silo - SS Hopper	Est	1	EA	808,000.00	808,000		2545.52	2,546	2,546	TANK	65.78	167,444				975,400
	Short-Term Storage Silo - (24 Hours)	293,760 lb full - 1,920 ft ³ - D=8.5' - H=38.0' - CS Silo - SS Hopper	Est	1	EA	200,000.00	200,000		764.00	764	764	TANK	65.78	50,256				250,300
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100
	Injection Nozzles (50 Qty)	Stainless Steel	Est	1	LT	10,500.00	10,500		240.00	240	240	MECH	66.86	16,046				26,500
	System Piping																	
	8" - CS	Includes fitting allowance	Est	350	LF	18.48	6,468		0.46	161	161	SPNG	70.4	11,334				17,800
	Piping Insulation & Lagging		Est	0	LF	6.62	0		0.14	0	0	INSUL	53.39	0				0
	Heat Tracing		Est	0	LF	0.00	0		0.00	0	0	WIRE	69.06	0				0
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800
	Supply Piping																	
	Water Supply	Allowance	Est	0	LS	840.00	0		100.00	0	0	SPNG	70.4	0				0
	Air Supply	Allowance	Est	0	LS	525.00	0		80.00	0	0	SPNG	70.4	0				0
	Piping Supports	Allowance	Est	1	LS	1,575.00	1,575		60.00	60	60	SPNG	70.4	4,224				5,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	50	CY	157.50	7,875		7.00	350	350	CONP	52.91	18,519				26,400
IS-3	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-4	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700
IS-5	IS SYSTEM SUBTOTAL						1,429,593				6,704			464,542				1,894,000
MATERIAL UNLOADING SYSTEM																		
ASH-1	TRUCK DELIVERY	INCLUDED IN SILO	Est	0	Set	315,000.00	0		1753.67	0	0	SPNG	70.4	0				0
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE																	

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 1 - Hydrated Lime Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22012B						
Cost Type: Est = Estimated, Bid = Vendor quote		Wage Rates Based on: Louisville, KY										Project No.: 10584-022						
		Labor Productivity = 1										Date: 12/20/2005						
												Rev Date: 1/27/2006						
												Run Date: 1/27/2006						
												Preparer:						
												Reviewer:						
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	480V SWITCHGEAR	Double Ended Unit Substation with (2) 2MVA, 6.9-480V XFMR's	Est	1	EA	575,000.00	575,000		500.00	500	500	EHEA	53.92	26,960				602,000
	New Breaker at Existing 6900V Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	60,900.00	60,900		300.00	300	300	EHEA	53.92	16,176				77,100
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600
	Power Cables for 480V Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	150	LF	0.76	113	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				700
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	150	LF	1.58	236	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				800
	Power Cables from MCC to Loads - 50 HP	3/C #4, 600V	Est	150	LF	2.10	315	Routed in 1-1/2" Conduit	0.09	14	14	WIRE	69.06	932				1,200
	Power Cables from MCC to Loads - 100HP	3/C #4/0, 600V	Est	150	LF	9.45	1,418	Routed in 1-1/2" Conduit	0.50	75	75	WIRE	69.06	5,180				6,600
	Power Cables from MCC to Loads - 150HP	3/C #350, 600V	Est	300	LF	10.50	3,150	Routed in 2" Conduit	0.69	207	207	WIRE	69.06	14,295				17,400
	Control Cables - Pumps	5/C #14, 600V	Est	150	LF	0.67	101	Routed in 3/4" Conduit	0.03	5	5	WIRE	69.06	332				400
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,300	LF	2.06	4,733		0.19	446	446	ECND	49.67	22,163				26,900
	1-1/2" Conduit		Est	300	LF	4.67	1,402		0.28	85	85	ECND	49.67	4,232				5,600
	2" Conduit		Est	300	LF	6.25	1,874		0.35	106	106	ECND	49.67	5,245				7,100
	3" Conduit		Est	900	LF	13.13	11,813		0.65	581	581	ECND	49.67	28,833				40,600
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0
AP-5	DCS SYSTEM ADDITIONS																	
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE																	
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL	60.02	6,002				16,500
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						871,538			3,370				188,413				1,060,000
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																

Louisville Gas & Electric																	Estimate No.:	22012B
Ghent Unit 4																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 1 - Hydrated Lime																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Reviewer:	
Labor Productivity =																	Louisville, KY	
																	1	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
MISCELLANEOUS		NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,150.00	3,150		1170.00	1,170	1,170	PNTR	55.58	65,029				68,200
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	0	LS	7,350.00	0		300.00	0	0	YDRN	51.97	0				0
MISC-4	OTHER																	
	BLOWER HOUSE																	
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	COMP	52.91	9,259				13,200
	PREFAB BLDG. 15'X20'		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
MISC-5	CFD MODEL STUDY		Est	1	LS	30,000.00	30,000		40.00	40	40	STST	86.46	3,458				33,500
6	TANK BERM		Est	1	LS	0.00	0		260.00	260	260	STST	86.46	22,480				22,500
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	0.00	0		60.00	60	60	STST	86.46	5,188				5,200
MISC-5	MISC. SUBTOTAL						75,088				1,835			116,653				191,800
GENERAL SUPPORT																		
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							150,000				150,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			150,000				150,000
SUBTOTAL							2,402,574			0	12,238			944,258				3,346,900
	Craft Support During Startup	At 3% of Total Manhours									367	MECH	66.86	24,548				24,500
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																167,300
	Erection Contractor's Profit	At 8% of Material and Labor Costs																267,800
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																12,000
	Freight To Site	At 4.5% of Equipment/Material Cost																108,100
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included

Sargent & Lundy ^{LLC} cago		Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 1 - Hydrated Lime Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.:	22012B	
Cost Type: Est = Estimated, Bid = Vendor quote																Project No.:	10584-022	
																Date:	12/20/2005	
																Rev Date:	1/27/2006	
																Run Date:	1/27/2006	
																Preparer:		
																Reviewer:		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	12,606			968,806				3,926,600
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								392,660
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								873,900
	CLIENT INTERNAL COST	Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								5,343,160

Sargent & Lundy LLC Chicago			Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-											Estimate No.: 22013B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:				
Cost Type: Est = Estimated, Bid = Vendor quote														Wage Rates Based on: Louisville, KY Labor Productivity = 1				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																	
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	INSULATION & LAGGING	6" THICK INSULATION	Est	200	SF	21.00	4,200		0.27	54	54	DINS	59.32	3,203				7,400
DW-4	DUCTWORK SUPPORT STRUCTURES																	
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
DW-6	BOILER MODS																	
	WALL AND TUBE MODS		Est	2	TN	2,625.00	5,250		35.00	70	70	FLDU	89.66	6,276				11,500
DW-7	DUCTWORK SUBTOTAL						34,125				399			30,926				65,100
Injection System																		
IS-1	EQUIPMENT/COMPONENTS																	
	Air Blowers	Not required	Est	3	EA	21,000.00	63,000		40.00	120	120	MECH	66.86	8,023				71,000
	VFD Rotary Feeder	Not required	Est	1	EA	10,500.00	10,500		30.00	30	30	MECH	66.86	2,006				12,500
	Long-Term Storage Silo - Common for 2 Units (10 Days), Unit cost is split between Units 3 and 4	1,617,900 lb full - 17,060 ft3 - D=26.3' - H=31.6' - CS Silo - SS Hopper	Est	1	EA	139,000.00	139,000		580.00	580	580	TANK	65.78	38,152				177,200
	Short-Term Storage Silo - (24 Hours)	Not required	Est	0	EA	0.00	0		60.00	0	0	TANK	65.78	0				0
	Air Compressors (2 Qty)	50 hp - 2 X 100%	Est	2	EA	21,000.00	42,000		80.00	160	160	MECH	66.86	10,698				52,700
	Mixing Tank - 1 Unit - (24 Hours)	808,320 lb full - 8,520 ft3 - D=20.8' - H=25.0' - CS Silo - SS Hopper	Est	1	EA	61,000.00	61,000		880.00	880	880	TANK	65.78	57,886				118,900
	Mixing Tank Agitator (1 Qty)	20 hp - CS Shaft	Est	1	EA	21,000.00	21,000		30.00	30	30	MECH	66.86	2,006				23,000
	Water Storage Tank - 1 Unit (24 Hrs)	125,000 lb full - 2,000 ft3 - D=13.7' - H=13.7' - CS	Est	1	EA	55,500.00	55,500		880.00	880	880	TANK	65.78	57,886				113,400
	Slurry/Water Pumps (6 Qty)	2 hp - CS	Est	6	EA	5,250.00	31,500		20.00	120	120	PUMP	65.83	7,900				39,400
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100
	Dual Fluid Injection Nozzles (20 Qty)	Stainless Steel	Est	1	LT	42,000.00	42,000		96.00	96	96	MECH	66.86	6,419				48,400
	System Piping																	
	1" - CS	Includes fitting allowance	Est	300	LF	2.27	680		0.16	49	49	SPNG	70.4	3,464				4,100
	4" - CS	Includes fitting allowance	Est	50	LF	9.28	464		0.33	17	17	SPNG	70.4	1,162				1,600
	Piping Insulation & Lagging		Est	350	LF	2.99	1,047		0.08	26	26	INSUL	53.39	1,402				2,400
	Heat Tracing		Est	350	LF	21.00	7,350		0.31	109	109	WIRE	69.06	7,493				14,800
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800
	Supply Piping																	
	Water Supply	Allowance	Est	200	LS	840.00	168,000		100.00	20,000	20,000	SPNG	70.4	1,408,000				1,576,000
	Air Supply	Allowance	Est	200	LS	525.00	105,000		80.00	16,000	16,000	SPNG	70.4	1,126,400				1,231,400
	Piping Supports	Allowance	Est	1	LS	2,100.00	2,100		40.00	40	40	SPNG	70.4	2,816				4,900
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	110	CY	157.50	17,325		7.00	770	770	CONP	52.91	40,741				58,100

Louisville Gas & Electric																	Estimate No.:	22013B
Ghent Unit 4																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 2 - Magnesium Hydroxide																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
																	Reviewer:	
Wage Rates Based on:																	Louisville, KY	
Labor Productivity =																	1	
Cost Type: Est = Estimated, Bid = Vendor quote																		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
IS-3	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-4	AUGER CAST PILES (120 TON CAPACITY)	90 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0
IS-5	IS SYSTEM SUBTOTAL						833,517				40,731			2,843,955				3,677,300
MATERIAL UNLOADING SYSTEM																		
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000				1,254			88,282				193,300
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
POWER SOURCE																		
		Double Ended Unit Substation with (2) 1 MVA, 6.9-480V XFMR's																
	SWITCHGEAR		Est	1	EA	460,000.00	460,000		500.00	500	500	EHEA	53.92	26,960				487,000
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA						63,000
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600
											0							0
AP-2	GROUNDING		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Cable - 500kcmil GND		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
	Grounding Rod																	
AP-3	CABLE		Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE						
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE						
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF		0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 3/4" Conduit	0.05	16	16	WIRE	69.06	1,098				1,300
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	300	LF	0.76	227	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				800
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	150	LF	1.58	236	Routed in 1-1/2" Conduit	0.09	0	0	WIRE						
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	0	LF	2.12	0	Routed in 1-1/2" Conduit	0.35	35	35	WIRE						
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	100	LF	2.67	267	Routed in 2" Conduit	0.35	18	18	WIRE	69.06	1,209				1,400
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	50	LF	3.58	179	Routed in 3/4" Conduit	0.03	10	10	WIRE	69.06	663				900
	Control Cables - Pumps	5/C #14, 600V	Est	300	LF	0.67	202	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	32	32	WIRE						
	Data Highway Cable		Est	1,000	LF	3.15	3,150											
RACEWAY																		
	3/4" Conduit		Est	2,500	LF	2.06	5,145		0.19	485	485	ECND						
	1-1/2" Conduit		Est	100	LF	4.67	467		0.28	28	28	ECND						
	2" Conduit		Est	50	LF	6.25	312		0.35	18	18	ECND						
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND						
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND						

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22013B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Labor Productivity =		Louisville, KY 1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
AP-5	DCS SYSTEM ADDITIONS Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA													
AP-8	DCS PROGRAMMING/INTERFACE Interface Hardware Programming /Interface		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC													
			Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300							
AP-9	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL													
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						689,199				2,615			80,761				709,200							
	REINFORCING OF EXISTING EQUIPMENT	NONE																							
	DEMOLITION / RELOCATIONS	NONE																							
	MISCELLANEOUS	NONE																							
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	5,250.00	5,250		1550.00	1,550	1,550	PNTR	55.58	86,149				91,400							
MISC-2	ROADWORK	Not Required	Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0							
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900							
MISC-4	OTHER																								
	PUMP HOUSE 15' X 20'																								
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	COMP	52.91	9,259				13,200							
	PREFAB BLDG.		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200							
MISC-5	CFD MODEL STUDY		Est	1	LS	100,000.00	100,000		40.00	40	40	STST	86.46	3,458				103,500							
MISC-6	TANK BERM		Est	1	LS	76,000.00	76,000		260.00	260	260	STST	86.46	22,480				98,500							
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	35,000.00	35,000		60.00	60	60	STST	86.46	5,188				40,200							
MISC-5	MISC. SUBTOTAL						54,538				2,155			122,239				176,700							
	GENERAL SUPPORT																								
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000							
C	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000							
	SUBTOTAL						1,927,379				47,514			3,297,288				5,163,800							

Louisville Gas & Electric																	Estimate No.:	22013B
Ghent Unit 4																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 2 - Magnesium Hydroxide																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
																	Reviewer:	
Sargent & Lundy LLC Chicago																	Wage Rates Based on: Louisville, KY	
Cost Type: Est = Estimated, Bid = Vendor quote																	Labor Productivity = 1	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Craft Support During Startup	At 3% of Total Manhours									1,425	MECH	66.86	95,303				95,303
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																258,200
	Erection Contractor's Profit	At 8% of Material and Labor Costs																413,100
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																9,600
	Freight To Site	At 4.5% of Equipment/Material Cost																86,700
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST										0			48,939				3,392,592
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team									0							602,700
	PERMITTING, MODELING, ETC.										0							0
	STARTUP, TESTING AND REAGENT (15 DAYS)										0							50,000
	CONTINGENCY	At 20% of Total									0							1,335,900
	CLIENT INTERNAL COST	To Be Furnished by Owner									0							100,000
	SPARE PARTS										0							Not Included
	ESCALATION	Not Included									0							0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included									0							0
	PROJECT TOTAL :										0							8,115,300

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Louisville, KY		Estimate No.: 22014B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Labor Productivity = 1															
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost									
DUCTWORK MODIFICATIONS																											
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800									
	DUCTWORK MODS		Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900									
	INSULATION & LAGGING	3 1/2" INSUL																									
DW-4	DUCTWORK SUPPORT STRUCTURES		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400									
	STRUCTURAL STEEL		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000									
	ACCESS & GALLERIES																										
DW-9	DUCTWORK SUBTOTAL						26,355			329			24,650					51,100									
Injection System																											
EQUIPMENT/COMPONENTS																											
	Process Technology Package (PTP) by URS		Est	1	EA	1,800,000.00	1,800,000		20.00	20	20	PUMP	65.83	1,317				1,801,300									
	Pumps (6 Qty)	4 - CS internals - 2.0 HP / 4 - SS internals - 1.0 HP	Est	6	EA	2,100.00	12,600		20.00	120	120	PUMP	65.83	7,900				20,500									
	Long-Term Storage Silo - Common for 2 Units (10 Days),	420,250 lb full - 5,180 ft ³ - D=17.6' - H=21.2' - SS	Est	1	EA	363,000.00	363,000		535.21	535	535	TANK	65.78	35,206				398,200									
	Soft H ₂ O Storage Tank - 1 Unit - (24 Hours)	309,312 lb full - 4,957 ft ³ - D=18.48' - H=18.48' - CS	Est	1	EA	83,000.00	83,000		489.52	490	490	TANK	65.78	32,201				115,200									
	Agitator (1 Qty)	SS Shaft - 20 HP	Est	1	EA	21,000.00	21,000		30.00	30	30	MECH	66.86	2,006				23,000									
	Air Compressors (2 Qty)	2 x 100% - 50 HP	Est	2	EA	21,000.00	42,000		80.00	160	160	MECH	66.86	10,698				52,700									
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100									
	Dual Fluid Injection Nozzles (100 Qty)	Stainless Steel	Est	1	LT	21,000.00	21,000		480.00	480	480	MECH	66.86	32,093				53,100									
	System Piping	L=250' - D=4" - SS / L=50' - D=4" - CS / L=50' - D=2" - SS																									
	6" - SS	Includes fitting allowance	Est	250	LF	30.61	7,652		0.42	105	105	SPNG	70.4	7,392				15,000									
	6" - CS	Includes fitting allowance	Est	50	LF	11.89	594		0.42	21	21	SPNG	70.4	1,478				2,100									
	4" - SS	Includes fitting allowance	Est	50	LF	24.89	1,244		0.33	17	17	SPNG	70.4	1,162				2,400									
	Piping Insulation & Lagging		Est	350	LF	9.14	3,197		0.17	60	60	INSUL	53.39	3,177				6,400									
	Heat Tracing		Est	350	LF	21.00	7,350		0.31	109	109	WIRE	69.06	7,493				14,800									
	Valves	Allowance	Est	1	LS	2,520.00	2,520		48.00	48	48	SPNG	70.4	3,379				5,900									
	Supply Piping																										
	Water Supply	Allowance	Est	1	LS	840.00	840		100.00	100	100	SPNG	70.4	7,040				7,900									
	Air Supply	Allowance	Est	1	LS	525.00	525		80.00	80	80	SPNG	70.4	5,632				6,200									
	Piping Supports	Allowance	Est	1	LS	2,940.00	2,940		112.00	112	112	SPNG	70.4	7,885				10,800									
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800									
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	75	CY	157.50	11,813		7.00	525	525	CONP	52.91	27,778				39,600									
	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800									
IS-3	AUGER CAST PILES (125 TON CAPACITY)	100 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0									
IS-3	ROYALTY FEE		Est	0	LF									0				0									

Louisville Gas & Electric																	Estimate No.:	22014B
Ghent Unit 4																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 3 - Soda Ash																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Reviewer:	
Labor Productivity =																	1	
Louisville, KY																		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
IS-4	IS SYSTEM SUBTOTAL						2,446,275				3,810			253,595				2,699,800
	MATERIAL UNLOADING SYSTEM																	
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000				1,254			88,282				193,300
	AUXILIARY POWER SUPPLY SYSTEM/I&C																	
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1MVA, 6.9-480V XFMR's																
	SWITCHGEAR		Est	1	EA	460,000.00	460,000		500.00	500	500	EHEA	53.92	26,960				487,000
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	200	LF	0.76	151	Routed in 3/4" Conduit	0.05	11	11	WIRE	69.06	732				900
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	900	LF	2.12	1,909	Routed in 1-1/2" Conduit	0.09	81	81	WIRE	69.06	5,594				7,500
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	250	LF	2.67	667	Routed in 1-1/2" Conduit	0.35	88	88	WIRE	69.06	6,043				6,700
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	0	LF	3.58	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Control Cables - Pumps	5/C #14, 600V	Est	900	LF	0.67	605	Routed in 3/4" Conduit	0.03	29	29	WIRE	69.06	1,989				2,600
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,850	LF	2.06	5,865		0.19	553	553	ECND	49.67	27,463				33,300
	1-1/2" Conduit		Est	1,150	LF	4.67	5,373		0.28	327	327	ECND	49.67	16,222				21,600
	2" Conduit		Est	0	LF	6.25	0		0.35	0	0	ECND	49.67	0				0
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND	49.67	8,009				11,300
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0
AP-5	DCS SYSTEM ADDITIONS																	
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE																	

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.:	22014B	
Cost Type: Est = Estimated, Bid = Vendor quote																Project No.:	10584-022	
																Date:	12/20/2005	
																Rev Date:	1/27/2006	
																Run Date:	1/27/2006	
																Preparer:		
																Reviewer:		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						701,985				3,135			175,156				877,400
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,675.00	3,675		1250.00	1,250	1,250	PNTR	55.58	69,475				73,200
2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
	PUMP HOUSE 15' X 20'																	
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
	PREFAB BLDG.		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
MISC-5	CFD MODEL STUDY		Est	1	LS	30,000.00	30,000		40.00	40	40	STST	86.46	3,458				33,500
MISC-6	TANK BERM		Est	1	LS	61,000.00	61,000		260.00	260	260	STST	86.46	22,480				83,500
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	22,000.00	22,000		60.00	60	60	STST	86.46	5,188				27,200
MISC-5	MISC. SUBTOTAL						165,963				2,215			136,691				302,700
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000
	SUBTOTAL						3,445,578				0		10,743	778,373				4,224,300
	Craft Support During Startup	At 3% of Total Manhours									322	MECH	66.86	21,549				21,500
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included

Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																211,200
	Erection Contractor's Profit	At 8% of Material and Labor Costs																337,900
	Mandatory Spare Parts (Start-up/Testing)	Included w\Equipment Costs																Included w\Equipment Costs
	Special Tools	Included w\Equipment Costs																Included w\Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																17,200
	Freight To Site	At 4.5% of Equipment/Material Cost																155,100
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	11,066			799,922				4,967,200
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								496,700
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								1,102,800
	CLIENT INTERNAL COST	Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								6,716,700

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-											Estimate No.: 22015B					
Cost Type: Est = Estimated, Bid = Vendor quote													Project No.: 10584-022					
													Date: 12/20/2005					
													Rev Date: 1/26/2006					
													Run Date: 1/27/2006					
													Preparer:					
													Reviewer:					
													Wage Rates Based on: Louisville, KY					
													Labor Productivity = 1					
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																	
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	INSULATION & LAGGING	3 1/2" INSUL	Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
DW-4	DUCTWORK SUPPORT STRUCTURES																	
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
DW-9	DUCTWORK SUBTOTAL					26,355				329				24,650				51,100
Injection System																		
EQUIPMENT/COMPONENTS																		
	Process Technology Package (PTP). The cost shown here is for a single skid shared by Unit 3 and 4.	P&ID, Control Logic, Injection and metering pump skids, Proprietary injection lances 4 - CS internals - 2.0 HP / 4 - SS internals - 1.0 HP, included in PTP	Budget	1	EA	1,200,000.00	1,200,000		200.00	200	200	MISC	65.83	13,166				1,213,200
	Pumps (0 Qty)		Est	0	EA	0.00	0		20.00	0	0	PUMP	65.83	0				0
	SBS Solution Tank - 1 Unit (10 Days)	825,400 lb full - 12,100 ft ³ - D=23.4' - H=28.0' - SS	Est	1	EA	221,000.00	221,000		1064.00	1,064	1,064	TANK	65.78	69,990				291,000
	Soft H ₂ O Storage Tank - 1 Unit - (24 Hours)	309,312 lb full - 4,957 ft ³ - D=18.48' - H=18.48' - CS	Est	1	EA	83,000.00	83,000		1514.14	1,514	1,514	TANK	65.78	99,600				182,600
	Agitator (1 Qty)	SS Shaft - 20 HP	Est	1	EA	10,000.00	10,000		30.00	30	30	MECH	66.86	2,006				12,000
	Air Compressors (2 operating, 1 standby for each Unit)	3 x 100% - 150 HP	Est	3	EA	225,000.00	675,000		120.00	360	360	MECH	66.86	24,070				699,100
	Injection Manifold (2 Qty)	Stainless Steel included in PTP	Est	2	EA	0.00	0		0.00	0	0	MECH	66.86	0				0
	System Piping	L=500' - D=6" - SS / L=400' - D=6" - CS / L=300' - D=4" - SS																
	6" - SS	Includes fitting allowance	Est	500	LF	30.61	15,304		0.42	210	210	SPNG	70.4	14,784				30,100
	6" - CS	Includes fitting allowance	Est	300	LF	11.89	3,566		0.42	126	126	SPNG	70.4	8,870				12,400
	4" - SS	Includes fitting allowance	Est	300	LF	24.89	7,466		0.33	99	99	SPNG	70.4	6,970				14,400
	Piping Insulation & Lagging		Est	500	LF	9.14	4,568		0.17	85	85	INSUL	53.39	4,538				9,100
	Heat Tracing		Est	500	LF	21.00	10,500		0.31	155	155	WIRE	69.06	10,704				21,200
	Valves	Allowance	Est	1	LS	2,520.00	2,520		48.00	48	48	SPNG	70.4	3,379				5,900
	Supply Piping																	
	Water Supply piping	Allowance	Est	1	LS	840.00	840		100.00	100	100	SPNG	70.4	7,040				7,900
	Air Supply piping	Allowance	Est	1	LS	525.00	525		80.00	80	80	SPNG	70.4	5,632				6,200
	Piping Supports	Allowance	Est	1	LS	2,940.00	2,940		112.00	112	112	SPNG	70.4	7,885				10,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	90	CY	157.50	14,175		7.00	630	630	CONP	52.91	33,333				47,500
IS-3	STRUCTURAL STEEL	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-											Estimate No.: 22015B						
Cost Type: Est = Estimated, Bid = Vendor quote													Project No.: 10584-022						
													Date: 12/20/2005						
													Rev Date: 1/26/2006						
													Run Date: 1/27/2006						
													Preparer:						
													Reviewer:						
													Wage Rates Based on: Louisville, KY						
													Labor Productivity = 1						
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost	
IS-3	AUGER CAST PILES (125 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700	
IS-4	ROYALTY FEE	Not Included, \$ per MW, to be negotiated with Vendor	Est	0	LF									0				0	
IS-5	IS SYSTEM SUBTOTAL									6,077				421,203				2,751,700	
MATERIAL UNLOADING SYSTEM																			
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300	
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000			1,254				88,282				193,300	
AUXILIARY POWER SUPPLY SYSTEM/I&C																			
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1 MVA, 6.9-480V XFMR's																	
	SWITCHGEAR		Est	1	EA	488,750.00	488,750		500.00	500	500	EHEA	53.92	26,960				515,700	
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400	
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600	
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600	
AP-2	GROUNDING																		
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100	
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400	
AP-3	CABLE																		
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	100	LF	33.60	3,360	Routed in 5" Conduit	0.69	69	69	WIRE	69.06	4,765				8,100	
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600	
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0	
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0	
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	200	LF	0.76	151	Routed in 3/4" Conduit	0.05	11	11	WIRE	69.06	732				900	
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0	
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	50	LF	2.12	106	Routed in 1-1/2" Conduit	0.09	5	5	WIRE	69.06	311				400	
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	100	LF	2.67	267	Routed in 1-1/2" Conduit	0.35	35	35	WIRE	69.06	2,417				2,700	
	Power Cables from MCC to Loads - 150HP	3/C #2, 600V	Est	250	LF	3.58	895	Routed in 2" Conduit	0.35	88	88	WIRE	69.06	6,043				6,900	
	Control Cables - Pumps	5/C #14, 600V	Est	175	LF	0.67	118	Routed in 3/4" Conduit	0.03	6	6	WIRE	69.06	387				500	
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0	
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800	
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400	
AP-4	RACEWAY																		
	3/4" Conduit		Est	2,125	LF	2.06	4,373		0.19	412	412	ECND	49.67	20,477				24,800	
	1-1/2" Conduit		Est	150	LF	4.67	701		0.28	43	43	ECND	49.67	2,116				2,800	
	2" Conduit		Est	250	LF	6.25	1,562		0.35	88	88	ECND	49.67	4,371				5,900	
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND	49.67	8,009				11,300	
	5" Conduit		Est	100	LF	38.33	3,833		1.13	113	113	ECND	49.67	5,598				9,400	

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22015B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/26/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
AP-5	DCS SYSTEM ADDITIONS Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700							
AP-8	DCS PROGRAMMING/INTERFACE Interface Hardware Programming /Interface		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800							
			Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300							
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800							
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						731,530				2,916			164,329				895,900							
	REINFORCING OF EXISTING EQUIPMENT	NONE																							
	DEMOLITION / RELOCATIONS	NONE																							
	MISCELLANEOUS	NONE																							
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,675.00	3,675		1250.00	1,250	1,250	PNTR	55.58	69,475				73,200							
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0							
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900							
MISC-4	OTHER PUMP HOUSE 15' X 20' PREFAB BLDG.			1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200							
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200							
MISC-5	CFD MODEL STUDY		Est	1	LS	0.00	0		40.00	40	40	STST	86.46	3,458				3,500							
MISC-6	TANK BERM		Est	1	LS	61,000.00	61,000		260.00	260	260	STST	86.46	22,480				83,500							
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	37,000.00	37,000		60.00	60	60	STST	86.46	5,188				42,200							
MISC-8	MISC. SUBTOTAL						150,963				2,215			136,691				287,700							
	GENERAL SUPPORT																								
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000							
	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000							
	SUBTOTAL						3,331,250				0			12,991				948,321							
	Craft Support During Startup	At 3% of Total Manhours									390	MECH	66.86	26,057				26,100							

Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 22015B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/26/2006 Run Date: 1/27/2006 Preparer: Reviewer:				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																214,000
	Erection Contractor's Profit	At 8% of Material and Labor Costs																342,400
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																16,700
	Freight To Site	At 4.5% of Equipment/Material Cost																149,900
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	13,380			974,377				5,028,800
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								502,900
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								1,116,300
	CLIENT INTERNAL COST	Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								6,798,000

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 5 - Trona Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22016B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:						
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Labor Productivity =		Louisville, KY 1				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	DUCTWORK MODS		Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
	INSULATION & LAGGING	3 1/2" INSUL																
DW-2	DUCTWORK SUPPORT STRUCTURES		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	STRUCTURAL STEEL		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
	ACCESS & GALLERIES																	
DW-4	DUCTWORK SUBTOTAL						26,355				329			24,650				51,100
Injection System																		
EQUIPMENT/COMPONENTS																		
	Air Blowers	150 hp each	Est	6	EA	55,125.00	330,750		105.00	630	630	PUMP	65.83	41,473				372,200
	VFD Rotary Feeder	3 hp - Stainless Steel	Est	3	EA	10,500.00	31,500		30.00	90	90	TANK	65.78	5,920				37,400
	Long-Term Storage Silo - Common for 2 Units (10 Days), Unit cost is split between Units 3 and 4	2,687,900 lb full - 11,610 ft³ - D=20.7' - H=83.0' - CS Silo - SS Hopper	Est	1	EA	590,000.00	590,000		1624.00	1,624	1,624	TANK	65.78	106,827				696,800
	Short-Term Storage Silo - (24 Hours)	268,800 lb full - 1,160 ft³ - D=8.7' - H=39.0' - CS Silo - SS Hopper	Est	1	EA	180,000.00	180,000		120.00	120	120	TANK	65.78	7,894				187,900
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		530.00	1,060	1,060	MECH	66.86	70,872				91,900
	Injection Nozzles (50 Qty)	Stainless Steel	Est	1	LT	21,000.00	21,000		540.00	540	540	MECH	66.86	36,104				57,100
	System Piping																	
	8" - CS	Includes fitting allowance	Est	350	LF	18.48	6,468		0.46	160	160	SPNG	70.4	11,236				17,700
	Piping Insulation & Lagging		Est	0	LF	6.62	0		0.14	0	0	INSUL	53.39	0				0
	Heat Tracing		Est	0	LF	0.00	0		0.00	0	0	WIRE	69.06	0				0
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800
	Supply Piping																	
	Water Supply	Allowance	Est	0	LS	840.00	0		100.00	0	0	SPNG	70.4	0				0
	Air Supply	Allowance	Est	0	LS	525.00	0		80.00	0	0	SPNG	70.4	0				0
	Piping Supports	Allowance	Est	1	LS	1,575.00	1,575		60.00	60	60	SPNG	70.4	4,224				5,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	90	CY	157.50	14,175		7.00	630	630	COMP	52.91	33,333				47,500
	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-3	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700
IS-4	IS SYSTEM SUBTOTAL						1,263,518				6,402			442,027				1,705,400
MATERIAL UNLOADING SYSTEM																		
ASH-1	TRUCK UNLOADING SYSTEM	Included in silo	Est	0	Set	105,000.00	0		1254.00	0	0	SPNG	70.4	0				0
ASH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						0				0			0				0

Sargent & Lundy LLC Chicago																Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 5 - Trona Order of Magnitude Cost Estimate -CONFIDENTIAL-																Estimate No.:	22016B																
Cost Type: Est = Estimated, Bid = Vendor quote																Wage Rates Based on: Labor Productivity =																Louisville, KY 1																Project No.:	10584-022
																																																Date:	12/20/2005
																																																Rev Date:	1/27/2006
																																																Run Date:	1/27/2006
																																																Preparer:	
																																																Reviewer:	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost																															
AUXILIARY POWER SUPPLY SYSTEM/I&C																																																	
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1MVA, 6.9-480V XFMR's																																															
	480V SWITCHGEAR		Est	1	EA	580,000.00	580,000		500.00	500	500	EHEA	53.92	26,960				607,000																															
	New Breaker at Existing 4160V Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400																															
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600																															
	Misc Electrical Equipment & Controls		Est	1	LS	60,900.00	60,900		300.00	300	300	EHEA	53.92	16,176				77,100																															
AP-2	GROUNDING																																																
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100																															
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400																															
AP-3	CABLE																																																
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0																															
	Power Cables for MCC's	3/C 500kcmil, 600kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600																															
	Power Cables for 480V Switchgear	3/C 4/0kcmil, 5kV	Est	250	LF	8.40	2,100	Routed in 2" Conduit	0.35	88	88	WIRE	69.06	6,043				8,100																															
								Routed in 1-1/2"																																									
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Conduit	0.52	0	0	WIRE	69.06	0				0																															
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	150	LF	0.76	113	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				700																															
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0																															
								Routed in 1-1/2"																																									
	Power Cables from MCC to Loads - 50 HP	3/C #4, 600V	Est	900	LF	2.10	1,890	Conduit	0.09	81	81	WIRE	69.06	5,594				7,500																															
								Routed in 1-1/2"																																									
	Power Cables from MCC to Loads - 100HP	3/C #4/0, 600V	Est	950	LF	9.45	8,978	Conduit	0.50	475	475	WIRE	69.06	32,804				41,800																															
	Power Cables from MCC to Loads - 150HP	3/C #350, 600V	Est	300	LF	10.50	3,150	Routed in 2" Conduit	0.69	207	207	WIRE	69.06	14,295				17,400																															
	Control Cables - Pumps	5/C #14, 600V	Est	150	LF	0.67	101	Routed in 3/4" Conduit	0.03	5	5	WIRE	69.06	332				400																															
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2"	0.04	0	0	WIRE	69.06	0				0																															
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800																															
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400																															
AP-4	RACEWAY																																																
	3/4" Conduit		Est	2,300	LF	2.06	4,733		0.19	446	446	ECND	49.67	22,163				26,900																															
	1-1/2" Conduit		Est	1,850	LF	4.67	8,644		0.28	525	525	ECND	49.67	26,097				34,700																															
	2" Conduit		Est	550	LF	6.25	3,436		0.35	194	194	ECND	49.67	9,616				13,100																															
	3" Conduit		Est	900	LF	13.13	11,813		0.65	581	581	ECND	49.67	28,833				40,600																															
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0																															
AP-5	DCS SYSTEM ADDITIONS																																																
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700																															
AP-8	DCS PROGRAMMING/INTERFACE																																																
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800																															
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300																															
AP-10	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL	60.02	6,002				16,500																															
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						896,341							4,445				1,148,900																															

Sargent & Lundy LLC Chicago	Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 5 - Trona Order of Magnitude Cost Estimate -CONFIDENTIAL-												Estimate No.: 22016B					
Cost Type: Est = Estimated, Bid = Vendor quote													Project No.: 10584-022					
													Date: 12/20/2005					
													Rev Date: 1/27/2006					
													Run Date: 1/27/2006					
													Preparer:					
													Reviewer:					
										Wage Rates Based on:		Louisville, KY						
										Labor Productivity =		1						
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,150.00	3,150		1170.00	1,170	1,170	PNTR	55.58	65,029				68,200
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
	BLOWER HOUSE																	
	PREFAB BLDG (15' x 20')			1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
MISC-5	CFD MODEL STUDY		Est	1	LS	60,000.00	60,000		40.00	40	40	STST	86.46	3,458				63,500
MISC-6	TANK BERM		Est	1	LS	0.00	0		260.00	260	260	STST	86.46	22,480				22,500
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	0.00	0		60.00	60	60	STST	86.46	5,188				5,200
MISC-5	MISC. SUBTOTAL						112,438				2,135			132,244				244,700
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000
GS-2	GENERAL SUPPORT SUBTOTAL						0			0				100,000				100,000
	SUBTOTAL						2,298,651			0	13,312			951,349				3,250,100
	Craft Support During Startup	At 3% of Total Manhours									399	MECH	66.86	26,701				26,700
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																162,500
	Erection Contractor's Profit	At 8% of Material and Labor Costs																260,000
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs

Louisville Gas & Electric										Estimate No.: 22016B								
Ghent Unit 4										Project No.: 10584-022								
SO3 Mitigation System										Date: 12/20/2005								
Option 5 - Trona										Rev Date: 1/27/2006								
Order of Magnitude Cost Estimate										Run Date: 1/27/2006								
-CONFIDENTIAL-										Preparer:								
										Reviewer:								
Wage Rates Based on:										Louisville, KY								
Labor Productivity =										1								
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Special Tools	Included wEquipment Costs																Included wEquipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																11,500
	Freight To Site	At 4.5% of Equipment/Material Cost																103,400
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	13,711			978,050				3,814,200
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								381,400
	PERMITTING, MODELING, ETC.									0								0
	STARTUP REAGENT TESTING (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								849,100
	NET INTERNAL COST	To Be Furnished by Owner								0								100,000
	EXCESSIVE PARTS									0								Not Included
	ESCALATION	Not Included								0								0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0								0
	PROJECT TOTAL :									0								5,194,700

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 6 - Vertical Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22017B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:						
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Labor Productivity =		Louisville, KY 1				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT FOR WESP AND TO ACCEPT INJECTION NOZZLES																	
	DUCTWORK MODS		Est	0	TN	2,500.00	0		35.00	0	0	FLDU	89.66	0				0
	INSULATION & LAGGING		Est	0	SF	8.00	0		0.27	0	0	DINS	59.32	0				0
DW-4	DUCTWORK SUPPORT STRUCTURES																	
	STRUCTURAL STEEL		Est	0	TN	1,800.00	0		16.00	0	0	STST	86.46	0				0
	ACCESS & GALLERIES		Est	0	SF	30.00	0		0.40	0	0	GALL	71.2	0				0
DW-5	FOUNDATIONS																	
	FOUNDATIONS FOR DUCTWORK AND STRUCTURAL STEEL	INCLUDES EXCAVATION & BACKFILL	Est	0	CY	150.00	0		7.00	0	0	COMP	52.91	0				0
DW-6	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0
DW-8	DUCTWORK SUBTOTAL						0				0			0				0
WESP & ASSOCIATED EQUIP																		
WE-1	EQUIPMENT/COMPONENTS																	
WE-2	WESP (One ESP boxes, with three fields, 6 feet long, total 150 SCA. All internal 2205, with 2205 carbon steel clad alloy plate construction)	INCLUDES ALL ASSOCIATED DUCTWORK AND WASTE WATER EQUIPMENT.PIPING AND TANKS	Est	1	EA	28,945,000.00	28,945,000	BUDGETARY INPUT FROM VENDORS	76901	76,901	76,901	PREC	86.72	6,668,871				35,613,900
WE-3	Chimney Liner Adjustment	RETURN TO EXISTING CHIMNEY	Est	0	LF	-5302.50	0		-55	0	0	PREC	86.72	0				0
WE-4	Chimney Breaching Adjustment	NONE	Est	0	LS	0.00	0		0	0	0	PREC	86.72	0				0
WE-5	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	210	CY	157.50	33,075		7.00	1,470	1,470	COMP	52.91	77,778				110,900
WE-6	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0
WE-7	FIBERGLASS DUCT			50	LF	7,200.00	360,000		50.00	2,500	2,500	DUCT	82.81	207,025				567,000
WE-8	WE SYSTEM SUBTOTAL						29,338,075				80,871			6,953,674				36,291,800
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE																	
	SWITCHGEAR	Double Ended Unit Substation with (2) 2MVA, 6.9-480V XFMR's	Est	2	EA	575,000.00	1,150,000		500.00	1,000	1,000	EHEA	53.92	53,920				1,203,900
	New Breaker at Existing 13.2kV Switchgear		Est	2	EA	63,000.00	126,000		100.00	200	200	EHEA	53.92	10,784				136,800
	MCC		Est	2	EA	52,500.00	105,000		240.00	480	480	EHEA	53.92	25,882				130,900

Sargent & Lundy LLC Chicago			Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 6 - Vertical Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22017B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:							
Cost Type: Est = Estimated, Bid = Vendor quote													Wage Rates Based on: Labor Productivity =				Louisville, KY 1			
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost		
	Misc Electrical Equipment & Controls		Est	1	LS	86,100.00	86,100		504.00	504	504	EHEA	53.92	27,176				113,300		
AP-2	GROUNDING																	0		
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100		
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400		
AP-3	CABLE																	0		
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	100	LF	33.60	3,360	Routed in 5" Conduit	0.69	69	69	WIRE	69.06	4,765				8,100		
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	0	LF	14.70	0	Routed in 3" Conduit	0.69	0	0	WIRE	69.06	0				0		
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	1,000	LF	8.40	8,400	Routed in 2" Conduit	0.35	350	350	WIRE	69.06	24,171				32,600		
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	3,600	LF	6.30	22,680	Routed in 1-1/2" Conduit	0.52	1,872	1,872	WIRE	69.06	129,280				152,000		
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	0	LF	0.76	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0		
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	1,500	LF	1.58	2,363	Routed in 3/4" Conduit	0.05	80	80	WIRE	69.06	5,490				7,900		
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	0	LF	2.12	0	Routed in 1-1/2" Conduit	0.09	0	0	WIRE	69.06	0				0		
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	0	LF	2.67	0	Routed in 1-1/2" Conduit	0.35	0	0	WIRE	69.06	0				0		
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	0	LF	3.58	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0		
	Control Cables - Pumps	5/C #14, 600V	Est	1,500	LF	0.67	1,008	Routed in 3/4" Conduit	0.03	48	48	WIRE	69.06	3,315				4,300		
	Control Cables - TR Sets	7/C #14, 600V	Est	3,600	LF	0.81	2,911	Routed in 1-1/2" Conduit	0.04	144	144	WIRE	69.06	9,945				12,900		
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800		
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400		
AP-4	RACEWAY																	0		
	3/4" Conduit		Est	4,750	LF	2.06	9,776		0.19	922	922	ECND	49.67	45,771				55,500		
	1-1/2" Conduit		Est	3,600	LF	4.67	16,821		0.28	1,022	1,022	ECND	49.67	50,783				67,600		
	2" Conduit		Est	1,000	LF	6.25	6,248		0.35	352	352	ECND	49.67	17,484				23,700		
	3" Conduit		Est	0	LF	13.13	0		0.65	0	0	ECND	49.67	0				0		
	5" Conduit		Est	100	LF	38.33	3,833		1.13	113	113	ECND	49.67	5,598				9,400		
AP-5	DCS SYSTEM ADDITIONS																	0		
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700		
AP-8	DCS PROGRAMMING/INTERFACE																	0		
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800		
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300		
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800		
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						1,609,556			7,569				441,458				2,051,200		
	REINFORCING OF EXISTING EQUIPMENT	NONE																		
	DEMOLITION / RELOCATIONS	NONE																		
	MISCELLANEOUS	NONE																		
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	87150.00	87,150		3250.00	3,250	3,250	PNTR	55.58	180,635				267,800		

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 6 - Vertical Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22017B						
Cost Type: Est = Estimated, Bid = Vendor quote												Project No.: 10584-022						
												Date: 12/20/2005						
												Rev Date: 1/27/2006						
												Run Date: 1/27/2006						
												Preparer:						
												Reviewer:						
												Wage Rates Based on: Louisville, KY						
												Labor Productivity = 1						
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
MISC-2	ROADWORK	20' WIDTH X 1000 LF GRAVEL	Est	1	LS	46000.00	46,000		380.00	380	380	PBIT	62.43	23,723				69,700
MISC-3	STORM DRAINAGE		Est	1	LS	7350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
MISC-5	MISC. SUBTOTAL						140,500			3,930				219,949				360,400
MISC-1	PAINTING	Touch-up and Field Finish	Est	0	LS	0	0		3250.00	0	0	PNTR	55.58	0				0
MISC-2	ROADWORK	20' WIDTH X 1000 LF GRAVEL	Est	0	LS	0	0		475.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	0	LS	0	0		538.43	0	0	YDRN	51.97	0				0
MISC-4	OTHER																	
MISC-5	CFD MODEL STUDY		Est	1	LS	0.00	0		40.00	40	40	STST	86.46	3,458				3,500
MISC-5	MISC. SUBTOTAL						0			40				3,458				3,500
GENERAL SUPPORT																		
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT	0	0							100,000				100,000
GS-2	CRANE RENTAL	700 Ton - 4 months	Est	1	LT	0	0	Includes freight in and out						480,000				480,000
GS-2	GENERAL SUPPORT SUBTOTAL						0			0				580,000				580,000
SUBTOTAL							31,088,131			0	92,410			8,198,540				39,286,900
Craft Support During Startup		At 3% of Total Manhours									2,772	MECH	66.86	185,357				185,400
Allowance for Premium Time Labor																		Not Included
Productivity Loss Due To Overtime																		Not Included
Per Diem Expense																		Not Included
Project Wrap (Efficacy) Insurance																		Not Included
Erection Contractor's General & Administrative Costs		At 5% of Material and Labor Costs - WESP																517,100
Erection Contractor's Profit		At 8% of Material and Labor Costs - WESP																827,400
Mandatory Spare Parts (Start-up/Testing)		Included w/Equipment Costs																Included w/Equipment Costs
Special Tools		Included w/Equipment Costs																Included w/Equipment Costs
Consumables		At 0.5% of Equipment/Material Cost																155,400

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 6 - Vertical Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22017B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
	Freight To Site	At 4.5% of Equipment/Material Cost																1,399,000							
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included							
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner							
	SUBTOTAL INSTALLED COST									0	95,183			8,383,896				42,371,200							
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								1,906,700							
	PERMITTING, MODELING, ETC.									0								0							
	STARTUP AND TESTING									0								100,000							
	CONTINGENCY	At 20% of Total								0								8,875,600							
	CLIENT INTERNAL COST	To Be Furnished by Owner								0								200,000							
	SPARE PARTS									0								Not Included							
	ESCALATION	Not Included																0							
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0							
	PROJECT TOTAL :									0								53,453,500							

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 7 - Horizontal Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22018B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:						
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Labor Productivity =		Louisville, KY 1				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	DUCTWORK MODIFICATIONS	COSTS																
	WESP & ASSOCIATED EQUIP																	
WE-1	WESP (Two ESP boxes, with 29 feet three fields, 9 feet long 1st field at 9.75" spacing with 76 gas passages, and 11 feet long 2nd and 3rd fields at 11.75" spacing with 64 passages, total 170 SCA. All internal 2205, with 2205 carbon steel clad alloy plate construction)	INCLUDES ALL ASSOCIATED DUCTWORK AND WASTE WATER EQUIPMENT, PIPING AND TANKS	Est	1	EA	31,570,000.00	31,570,000	BUDGETARY INPUT FROM VENDOR	142817	142,817	142,817	PREC	86.72	12,385,047				43,955,000
WE-2	Chimney Liner Adjustment (WITH MODIFIED BREECHING AT WESP OUTLET ELEVATION)	RETURN TO EXISTING BREECHING	Est	0	LF	5,302.50	0		55	0	0	PREC	86.72	0				0
WE-3	Chimney Breaching Adjustment		Est	0	LS	21,000.00	0		220	0	0	PREC	86.72	0				0
4	Electrical Building	20'x40'	Est	1	EA	21,000.00	21,000		100.00	100	100	STST	86.46	8,646				29,600
WE-5	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	810	CY	157.50	127,575		7.00	5,670	5,670	COMP	52.91	300,000				427,600
WE-6	STRUCTURAL STEEL		Est	170	TN	2,200.00	374,000		16.00	2,720	2,720	STST	86.46	235,171				609,200
WE-7	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,000	LF	10.00	20,000		0.52	1,040	1,040	PILE	82.81	86,122				106,100
WE-7	FIBER GLASS DUCT 23' DIA		Est	450	LF	7,200.00	3,240,000		50.00	22,500	22,500	DUCT	59.32	1,334,700				4,574,700
WE-8	WE SYSTEM SUBTOTAL						35,352,575				174,847			14,349,686				49,702,200
	AUXILIARY POWER SUPPLY SYSTEM/I&C																	
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 2MVA, 6.9/480V XFMR's																
	SWITCHGEAR		Est	1	EA	575,000.00	575,000		500.00	500	500	EHEA	53.92	26,960				602,000
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	52,500.00	105,000		240.00	480	480	EHEA	53.92	25,882				130,900
	Misc Electrical Equipment & Controls		Est	1	LS	86,100.00	86,100		324.00	324	324	EHEA	53.92	17,470				103,600
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	100	LF	33.60	3,360	Routed in 5" Conduit	0.69	69	69	WIRE	69.06	4,765				8,100
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	0	LF	14.70	0	Routed in 3" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	1,000	LF	8.40	8,400	Routed in 2" Conduit	0.35	350	350	WIRE	69.06	24,171				32,600
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	2,400	LF	6.30	15,120	Routed in 1-1/2" Conduit	0.52	1,248	1,248	WIRE	69.06	86,187				101,300
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	0	LF	0.76	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	1,500	LF	1.58	2,363	Routed in 3/4" Conduit	0.05	80	80	WIRE	69.06	5,490				7,900
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	0	LF	2.12	0	Routed in 1-1/2" Conduit	0.09	0	0	WIRE	69.06	0				0

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 7 - Horizontal Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 22018B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	0	LF	2.67	0	Routed in 1-1/2" Conduit	0.35	0	0	WIRE	69.06	0				0							
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	0	LF	3.58	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0							
	Control Cables - Pumps	5/C #14, 600V	Est	1,500	LF	0.67	1,008	Routed in 3/4" Conduit	0.03	48	48	WIRE	69.06	3,315				4,300							
	Control Cables - TR Sets	7/C #14, 600V	Est	2,400	LF	0.81	1,940	Routed in 1-1/2" Conduit	0.04	96	96	WIRE	69.06	6,630				8,600							
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800							
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400							
AP-4	RACEWAY																								
	3/4" Conduit		Est	4,750	LF	2.06	9,776		0.19	922	922	ECND	49.67	45,771				55,500							
	1-1/2" Conduit		Est	2,400	LF	4.67	11,214		0.28	682	682	ECND	49.67	33,855				45,100							
	2" Conduit		Est	1,000	LF	6.25	6,248		0.35	352	352	ECND	49.67	17,484				23,700							
	3" Conduit		Est	0	LF	13.13	0		0.65	0	0	ECND	49.67	0				0							
	5" Conduit		Est	100	LF	38.33	3,833		1.13	113	113	ECND	49.67	5,598				9,400							
AP-5	DCS SYSTEM ADDITIONS																								
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700							
AP-6	DCS PROGRAMMING/INTERFACE																								
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800							
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300							
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800							
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						957,418				5,776			336,065				1,293,700							
	REINFORCING OF EXISTING EQUIPMENT	NONE																							
	DEMOLITION / RELOCATIONS	NONE																							
	MISCELLANEOUS	NONE																							
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	87,150.00	87,150		3250.00	3,250	3,250	PNTR	55.58	180,635				267,800							
MISC-2	ROADWORK	20' WIDTH X 1000 LF GRAVEL	Est	1	LS	45,937.50	45,938		380.00	380	380	PBIT	62.43	23,723				69,700							
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900							
MISC-4	OTHER																								
MISC-5	CFD MODEL STUDY		Est	1	LS	0.00	0		40.00	40	40	STST	86.46	3,458				3,500							
MISC-5	MISC. SUBTOTAL						140,438				3,970			223,408				363,900							
	GENERAL SUPPORT																								
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000							

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Ghent Unit 4 SO3 Mitigation System Option 7 - Horizontal Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 22018B	Project No.: 10584-022	Date: 12/20/2005	Rev Date: 1/27/2006	Run Date: 1/27/2006	Preparer:	Reviewer:
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost				
GS-2	CRANE RENTAL	700 Ton - 2 months	Est	1	LT		0	Includes freight in and out						310,000				310,000				
GS-2	GENERAL SUPPORT SUBTOTAL						0			0				410,000				410,000				
	SUBTOTAL						36,450,431			0	184,593			15,319,159				51,769,800				
	Craft Support During Startup	At 3% of Total Manhours									5,538	MECH	66.86	370,256				370,300				
	Allowance for Premium Time Labor																	Not Included				
	Productivity Loss Due To Overtime																	Not Included				
	Per Diem Expense																	Not Included				
	Project Wrap (Efficacy) Insurance																	Not Included				
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs - WESP																1,010,000				
	Erection Contractor's Profit	At 8% of Material and Labor Costs - WESP																1,616,000				
	Mandatory Spare Parts (Start-up/Testing)	Included w\Equipment Costs																Included w\Equipment Costs				
	Special Tools	Included w\Equipment Costs																Included w\Equipment Costs				
	Consumables	At 0.5% of Equipment/Material Cost																182,300				
	Freight To Site	At 4.5% of Equipment/Material Cost																1,640,300				
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included				
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner				
	SUBTOTAL INSTALLED COST									0	190,131			15,689,415				56,588,700				
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								2,546,000				
	PERMITTING, MODELING, ETC.									0								0				
	STARTUP AND TESTING									0								100,000				
	CONTINGENCY	At 20% of Total								0								11,846,900				
	CLIENT INTERNAL COST	To Be Furnished by Owner								0								200,000				
	SPARE PARTS									0								Not Included				
	ESCALATION	Not Included																0				
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0				
	PROJECT TOTAL :									0								71,281,600				

Louisville Gas & Electric Mill Creek Unit 3 SO3 Mitigation System Option 1 - Hydrated Lime Order of Magnitude Cost Estimate -CONFIDENTIAL-															Estimate No.: 21984B			
Saraent & Lundy LLC Chicago															Project No.: 10584-022			
Cost Type: Est = Estimated, Bid = Vendor quote															Date: 12/20/2005			
															Rev Date: 1/27/2006			
															Run Date: 1/27/2006			
															Preparer:			
															Reviewer:			
															Wage Rates Based on: Louisville, KY			
															Labor Productivity = 1			
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																	
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	INSULATION & LAGGING	3 1/2" INSUL	Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
DW-2	DUCTWORK SUPPORT STRUCTURES																	
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
DW-4	DUCTWORK SUBTOTAL						26,355			329				24,650				51,100
Injection System																		
EQUIPMENT/COMPONENTS																		
	Air Blowers	150 hp each	Est	5	EA	55,125.00	275,625		105.00	525	525	PUMP	65.83	34,561				310,200
	VFD Rotary Feeder	3 hp - Stainless Steel	Est	3	EA	10,500.00	31,500		30.00	90	90	TANK	65.78	5,920				37,400
	Long-Term Storage Silo - Common for 2 Units (10 Days), Unit cost is split between Units 3 and 4	2,020,600 lb full - 13,492 ft ³ - D=16.3' - H=65.2' - CS Silo - SS Hopper	Est	1	EA	645,000.00	645,000		2545.52	2,546	2,546	TANK	65.78	167,444				812,400
	Short-Term Storage Silo Common for Units 3 and 4- (24 Hours)	202,100 lb full - 1,350 ft ³ - D=7.5' - H=30.0' - CS Silo - SS Hopper	Est	1	EA	162,000.00	162,000		764.00	764	764	TANK	65.78	50,256				212,300
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100
	Injection Nozzles (50 Qty)	Stainless Steel	Est	1	LT	10,500.00	10,500		240.00	240	240	MECH	66.86	16,046				26,500
	System Piping																	
	8" - CS	Includes fitting allowance	Est	350	LF	18.48	6,468		0.46	161	161	SPNG	70.4	11,334				17,800
	Piping Insulation & Lagging		Est	0	LF	6.62	0		0.14	0	0	INSUL	53.39	0				0
	Heat Tracing		Est	0	LF	0.00	0		0.00	0	0	WIRE	69.06	0				0
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800
	Supply Piping																	
	Water Supply	Allowance	Est	0	LS	840.00	0		100.00	0	0	SPNG	70.4	0				0
	Air Supply	Allowance	Est	0	LS	525.00	0		80.00	0	0	SPNG	70.4	0				0
	Piping Supports	Allowance	Est	1	LS	1,575.00	1,575		60.00	60	60	SPNG	70.4	4,224				5,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	50	CY	157.50	7,875		7.00	350	350	COMP	52.91	18,519				26,400
IS-3	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-4	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700
IS-5	IS SYSTEM SUBTOTAL						1,228,593			6,704				464,542				1,693,000
MATERIAL UNLOADING SYSTEM																		
	TRUCK DELIVERY	INCLUDED IN SILO	Est	0	Set	315,000.00	0		1753.67	0	0	SPNG	70.4	0				0
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE																	

Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
MISCELLANEOUS		NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,150.00	3,150		1170.00	1,170	1,170	PNTR	55.58	65,029				68,200
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	0	LS	7,350.00	0		300.00	0	0	YDRN	51.97	0				0
MISC-4	OTHER																	
	BLOWER HOUSE																	
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
	PREFAB BLDG. 15'X20'		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
MISC-5	CFD MODEL STUDY		Est	1	LS	30,000.00	30,000		40.00	40	40	STST	86.46	3,458				33,500
MISC-6	TANK BERM		Est	1	LS	0.00	0		260.00	260	260	STST	86.46	22,480				22,500
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	0.00	0		60.00	60	60	STST	86.46	5,188				5,200
MISC-5	MISC. SUBTOTAL						75,088				1,835			116,653				191,800
GENERAL SUPPORT																		
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							150,000				150,000
GS-2	GENERAL SUPPORT SUBTOTAL						0			0				150,000				150,000
SUBTOTAL							2,201,574			0	12,238			944,258				3,145,900
	Craft Support During Startup	At 3% of Total Manhours									367	MECH	66.86	24,548				24,500
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																157,300
	Erection Contractor's Profit	At 8% of Material and Labor Costs																251,700
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																11,000
	Freight To Site	At 4.5% of Equipment/Material Cost																99,100

Louisville Gas & Electric																	Estimate No.:	21984B
Mill Creek Unit 3																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 1 - Hydrated Lime																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Wage Rates Based on:	Louisville, KY
																	Labor Productivity =	1
																	Preparer:	
																	Reviewer:	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip/ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	12,606			968,806				3,689,500
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								368,950
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								821,700
	CLIENT INTERNAL COST	Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								5,030,150

Louisville Gas & Electric Mill Creek Unit 3 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 21985B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Sargent & Lundy LLC Chicago										Cost Type: Est = Estimated, Bid = Vendor quote																	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost									
DUCTWORK MODIFICATIONS																											
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																										
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800									
	INSULATION & LAGGING	6" THICK INSULATION	Est	200	SF	21.00	4,200		0.27	54	54	DINS	59.32	3,203				7,400									
DW-4	DUCTWORK SUPPORT STRUCTURES																										
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400									
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000									
DW-6	BOILER MODS																										
	WALL AND TUBE MODS		Est	2	TN	2,625.00	5,250		35.00	70	70	FLDU	89.66	6,276				11,500									
DUCTWORK SUBTOTAL							34,125				399			30,926				65,100									
Injection System																											
IS-1	EQUIPMENT/COMPONENTS																										
	Air Blowers	15 hp each	Est	3	EA	21,000.00	63,000		40.00	120	120	MECH	66.86	8,023				71,000									
	VFD Rotary Feeder	3 hp -Stainless steel	Est	1	EA	10,500.00	10,500		30.00	30	30	MECH	66.86	2,006				12,500									
	Long-Term Storage Tank - Common for 2 Units (10 Days), Unit cost is split between Units 3 and 4	1,617,900 lb full - 17,060 ft3 - D=26.3' - H=31.6' - CS	Est	1	EA	151,000.00	151,000		580.00	580	580	TANK	65.78	38,152				189,200									
	Short-Term Storage Silo - (24 Hours)	Not required	Est	0	EA	10,500.00	0		60.00	0	0	TANK	65.78	0				0									
	Air Compressors (2 Qty)	50 hp - 2 X 100%	Est	2	EA	21,000.00	42,000		80.00	160	160	MECH	66.86	10,698				52,700									
	Mixing Tank - 1 Unit - (24 Hours)	808,320 lb full - 8,520 ft3 - D=20.8' - H=25.0'	Est	1	EA	63,000.00	63,000		880.00	880	880	TANK	65.78	57,886				120,900									
	Mixing Tank Agitator (1 Qty)	20 hp - CS Shaft	Est	2	EA	21,000.00	42,000		30.00	60	60	MECH	66.86	4,012				46,000									
	Water Storage Tank - 1 Unit (24 Hrs)	125,000 lb full - 2,000 ft3 - D=13.7' - H=13.7' - CS	Est	1	EA	46,000.00	46,000		880.00	880	880	TANK	65.78	57,886				103,900									
	Slurry/Water Pumps (6 Qty)	2 hp - CS	Est	6	EA	5,250.00	31,500		20.00	120	120	PUMP	65.83	7,900				39,400									
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100									
	Dual Fluid Injection Nozzles (20 Qty)	Stainless Steel	Est	1	LT	42,000.00	42,000		96.00	96	96	MECH	66.86	6,419				48,400									
	System Piping																										
	1" - CS	Includes fitting allowance	Est	300	LF	2.27	680		0.16	49	49	SPNG	70.4	3,464				4,100									
	4" - CS	Includes fitting allowance	Est	50	LF	9.28	464		0.33	17	17	SPNG	70.4	1,162				1,600									
	Piping Insulation & Lagging		Est	350	LF	2.99	1,047		0.08	26	26	INSUL	53.39	1,402				2,400									
	Heat Tracing		Est	350	LF	21.00	7,350		0.31	109	109	WIRE	69.06	7,493				14,800									
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800									
	Supply Piping																										
	Water Supply	Allowance	Est	200	LS	840.00	168,000		100.00	20,000	20,000	SPNG	70.4	1,408,000				1,576,000									
	Air Supply	Allowance	Est	200	LS	525.00	105,000		80.00	16,000	16,000	SPNG	70.4	1,126,400				1,231,400									
	Piping Supports	Allowance	Est	1	LS	2,100.00	2,100		40.00	40	40	SPNG	70.4	2,816				4,900									
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800									
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	110	CY	157.50	17,325		7.00	770	770	CONP	52.91	40,741				58,100									
IS-3	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800									

Sargent & Lundy LLC Chicago			Louisville Gas & Electric Mill Creek Unit 3 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21985B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:					
Cost Type: Est = Estimated, Bid = Vendor quote													Wage Rates Based on: Labor Productivity =		Louisville, KY 1			
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
IS-4	AUGER CAST PILES (120 TON CAPACITY)	90 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0
IS-5	IS SYSTEM SUBTOTAL						859,017				40,761			2,845,961				3,704,800
MATERIAL UNLOADING SYSTEM																		
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000				1,254			88,282				193,300
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1 MVA, 6.9-480V XFMR's																
	SWITCHGEAR		Est	1	EA	460,000.00	460,000		500.00	500	500	EHEA	53.92	26,960				487,000
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA						63,000
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600
														0				0
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE						
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE						
								Routed in 1-1/2" Conduit										
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0		0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	300	LF	0.76	227	Routed in 3/4" Conduit	0.05	16	16	WIRE	69.06	1,098				1,300
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	150	LF	1.58	236	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				800
								Routed in 1-1/2" Conduit										
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	0	LF	2.12	0		0.09	0	0	WIRE						
								Routed in 1-1/2" Conduit										
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	100	LF	2.67	267		0.35	35	35	WIRE						
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	50	LF	3.58	179	Routed in 2" Conduit	0.35	18	18	WIRE	69.06	1,209				1,400
	Control Cables - Pumps	5/C #14, 600V	Est	300	LF	0.67	202	Routed in 3/4" Conduit	0.03	10	10	WIRE	69.06	663				900
								Routed in 1-1/2" Conduit										
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0		0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE						
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,500	LF	2.06	5,145		0.19	485	485	ECND						
	1-1/2" Conduit		Est	100	LF	4.67	467		0.28	28	28	ECND						
	2" Conduit		Est	50	LF	6.25	312		0.35	18	18	ECND						
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND						
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND						
AP-5	DCS SYSTEM ADDITIONS																	

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Mill Creek Unit 3 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 21985B	Project No.: 10584-022	Date: 12/20/2005	Rev Date: 1/27/2006	Run Date: 1/27/2006	Preparer:	Reviewer:
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost				
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA										
AP-8	DCS PROGRAMMING/INTERFACE		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC										
	Interface Hardware		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300				
	Programming /Interface																					
AP-9	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL										
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						689,199				2,615			80,761				709,200				
	REINFORCING OF EXISTING EQUIPMENT	NONE																				
	DEMOLITION / RELOCATIONS	NONE																				
	MISCELLANEOUS	NONE																				
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	5,250.00	5,250		1550.00	1,550	1,550	PNTR	55.58	86,149				91,400				
MISC-2	ROADWORK	Not Required	Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0				
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900				
MISC-4	OTHER																					
	PUMP HOUSE 15' X 20'																					
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200				
	PREFAB BLDG.		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200				
MISC-5	CFD MODEL STUDY		Est	1	LS	100,000.00	100,000		40.00	40	40	STST	86.46	3,458				103,500				
MISC-6	TANK BERM		Est	1	LS	65,000.00	65,000		260.00	260	260	STST	86.46	22,480				87,500				
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	25,000.00	25,000		60.00	60	60	STST	86.46	5,188				30,200				
MISC-5	MISC. SUBTOTAL						54,538				2,155			122,239				176,700				
	GENERAL SUPPORT																					
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000				
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000				
	SUBTOTAL						1,931,879			0	47,544			3,299,294				5,170,300				
	Craft Support During Startup Allowance for Premium Time Labor	At 3% of Total Manhours									1,426	MECH	66.86	95,364				95,400				
																		Not Included				

Louisville Gas & Electric Mill Creek Unit 3 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 21985B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																258,500
	Erection Contractor's Profit	At 8% of Material and Labor Costs																413,600
	Mandatory Spare Parts (Start-up/Testing)	Included w\Equipment Costs																Included w\Equipment Costs
	Special Tools	Included w\Equipment Costs																Included w\Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																9,700
	Freight To Site	At 4.5% of Equipment/Material Cost																86,900
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	48,970			3,394,658				6,034,400
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								603,400
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								1,337,600
	CLIENT INTERNAL COST	To Be Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included								0								0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0								0
	PROJECT TOTAL :									0								8,125,400

Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																	
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	INSULATION & LAGGING	3 1/2" INSUL	Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
DW-4	DUCTWORK SUPPORT STRUCTURES																	
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
DW-9	DUCTWORK SUBTOTAL						26,355				329			24,650				51,100
Injection System																		
EQUIPMENT/COMPONENTS																		
	Process Technology Package (PTP) by URS		Est	1	EA	1,800,000.00	1,800,000		300.00	300	300	PUMP	65.83	19,749				1,819,700
	Pumps (6 Qty)	4 - CS internals - 2.0 HP / 4 - SS internals - 1.0 HP	Est	6	EA	2,100.00	12,600		20.00	120	120	PUMP	65.83	7,900				20,500
	Long-Term Storage Silo - Common for 2 Units (10 Days), Unit cost is split between Units 3 and 4	420,250 lb full - 5,180 ft ³ - D=17.6' - H=21.2' - SS	Est	1	EA	151,000.00	151,000		535.21	535	535	TANK	65.78	35,206				186,200
	Soft H ₂ O Storage Tank - 1 Unit - (24 Hours)	309,312 lb full - 4,957 ft ³ - D=18.48' - H=18.48' - CS	Est	1	EA	39,375.00	39,375		489.52	490	490	TANK	65.78	32,201				71,600
	Agitator (1 Qty)	SS Shaft - 20 HP	Est	1	EA	21,000.00	21,000		30.00	30	30	MECH	66.86	2,006				23,000
	Air Compressors (2 Qty)	2 x 100% - 50 HP	Est	2	EA	21,000.00	42,000		80.00	160	160	MECH	66.86	10,698				52,700
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100
	Dual Fluid Injection Nozzles (100 Qty)	Stainless Steel	Est	1	LT	21,000.00	21,000		480.00	480	480	MECH	66.86	32,093				53,100
	System Piping	L=250' - D=4" - SS / L=50' - D=4" - CS / L=50' - D=2" - SS																
	6" - SS	Includes fitting allowance	Est	250	LF	30.61	7,652		0.42	105	105	SPNG	70.4	7,392				15,000
	6" - CS	Includes fitting allowance	Est	50	LF	11.89	594		0.42	21	21	SPNG	70.4	1,478				2,100
	4" - SS	Includes fitting allowance	Est	50	LF	24.89	1,244		0.33	17	17	SPNG	70.4	1,162				2,400
	Piping Insulation & Lagging		Est	350	LF	9.14	3,197		0.17	60	60	INSUL	53.39	3,177				6,400
	Heat Tracing		Est	350	LF	21.00	7,350		0.31	109	109	WIRE	69.06	7,493				14,800
	Valves	Allowance	Est	1	LS	2,520.00	2,520		48.00	48	48	SPNG	70.4	3,379				5,900
	Supply Piping																	
	Water Supply	Allowance	Est	1	LS	840.00	840		100.00	100	100	SPNG	70.4	7,040				7,900
	Air Supply	Allowance	Est	1	LS	525.00	525		80.00	80	80	SPNG	70.4	5,632				6,200
	Piping Supports	Allowance	Est	1	LS	2,940.00	2,940		112.00	112	112	SPNG	70.4	7,885				10,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	75	CY	157.50	11,813		7.00	525	525	CONP	52.91	27,778				39,600
	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-1	AUGER CAST PILES (125 TON CAPACITY)	100 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0
IS-3	ROYALTY FEE		0 Est	0	LF									0				0

Louisville Gas & Electric Mill Creek Unit 3 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 21986B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
IS-4	IS SYSTEM SUBTOTAL						2,190,650				4,090			272,027				2,462,600
	MATERIAL UNLOADING SYSTEM																	
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000				1,254			88,282				193,300
	AUXILIARY POWER SUPPLY SYSTEM/I&C																	
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1MVA, 6.9-480V XFMR's																
	SWITCHGEAR		Est	1	EA	460,000.00	460,000		500.00	500	500	EHEA	53.92	26,960				487,000
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	200	LF	0.76	151	Routed in 3/4" Conduit	0.05	11	11	WIRE	69.06	732				900
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	50	LF	2.12	106	Routed in 1-1/2" Conduit	0.09	5	5	WIRE	69.06	311				400
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	100	LF	2.67	267	Routed in 1-1/2" Conduit	0.35	35	35	WIRE	69.06	2,417				2,700
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	0	LF	3.58	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Control Cables - Pumps	5/C #14, 600V	Est	175	LF	0.67	118	Routed in 3/4" Conduit	0.03	6	6	WIRE	69.06	387				500
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,125	LF	2.06	4,373		0.19	412	412	ECND	49.67	20,477				24,800
	1-1/2" Conduit		Est	150	LF	4.67	701		0.28	43	43	ECND	49.67	2,116				2,800
	2" Conduit		Est	0	LF	6.25	0		0.35	0	0	ECND	49.67	0				0
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND	49.67	8,009				11,300
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0
AP-7	DCS SYSTEM ADDITIONS																	
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE																	

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Mill Creek Unit 3 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21986B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:						
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Louisville, KY Labor Productivity = 1						
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						693,130				2,558			143,552				836,900
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,675.00	3,675		1250.00	1,250	1,250	PNTR	55.58	69,475				73,200
2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
	PUMP HOUSE 15' X 20'																	
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
	PREFAB BLDG.		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
MISC-5	MISC. SUBTOTAL						52,963				1,855			105,565				158,500
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000
	SUBTOTAL						3,068,098				10,087			734,076				3,802,400
	Craft Support During Startup	At 3% of Total Manhours									303	MECH	66.86	20,232				20,200
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																190,100
	Erection Contractor's Profit	At 8% of Material and Labor Costs																304,200
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs

Louisville Gas & Electric Mill Creek Unit 3 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21986B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Sargent & Lundy LLC Chicago										Wage Rates Based on: Louisville, KY		Labor Productivity = 1											
Cost Type: Est = Estimated, Bid = Vendor quote																							
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost					
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs					
	Consumables	At 0.5% of Equipment/Material Cost																15,300					
	Freight To Site	At 4.5% of Equipment/Material Cost																138,100					
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included					
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner					
	SUBTOTAL INSTALLED COST									0	10,389			754,308				4,470,300					
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								447,000					
	PERMITTING, MODELING, ETC.									0								0					
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000					
	CONTINGENCY	At 20% of Total								0								993,500					
	OWNER INTERNAL COST	Furnished by Owner								0								100,000					
	EXCESS PARTS									0								Not Included					
	ESCALATION	Not Included								0								0					
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0								0					
	PROJECT TOTAL :									0								6,060,800					

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Mill Creek Unit 3 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21987B						
Cost Type: Est = Estimated, Bid = Vendor quote												Project No.: 10584-022						
												Date: 12/20/2005						
												Rev Date: 1/27/2006						
												Run Date: 1/27/2006						
												Preparer:						
												Reviewer:						
												Wage Rates Based on: Louisville, KY						
												Labor Productivity = 1						
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																	
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	INSULATION & LAGGING	3 1/2" INSUL	Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
DW-4	DUCTWORK SUPPORT STRUCTURES																	
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
DW-9	DUCTWORK SUBTOTAL						26,355			329				24,650				51,100
Injection System																		
EQUIPMENT/COMPONENTS																		
	Process Technology Package (PTP). The cost shown here is for a single skid shared by Unit 3 and 4.	P&ID, Control Logic, Injection and metering pump skids, Proprietary injection lances	Budget	1	EA	1,800,000.00	1,800,000		200.00	200	200	PUMP	65.83	13,166				1,213,200
	Pumps (6 Qty)	4 - CS internals - 2.0 HP / 4 - SS internals - 1.0 HP	Est	6	EA	2,100.00	12,600		20.00	120	120	PUMP	65.83	7,900				20,500
	Long-Term Storage Silo - Common for 2 Units (10 Days), Unit cost is split between Units 3 and 4	825,400 lb full - 12,100 ft ³ - D=16.2' - H=20.0' - SS	Est	1	EA	605,000.00	605,000		1064.00	1,064	1,064	TANK	65.78	69,990				675,000
	Soft H ₂ O Storage Tank - 1 Unit - (24 Hours)	Included in Soft water Supply System	Est	0	EA	0.00	0		0.00	0	0	TANK	65.78	0				0
	Agitator (1 Qty)	SS Shaft - 20 HP	Est	0	EA	21,000.00	0		0.00	0	0	MECH	66.86	0				0
	Air Compressors (2 Qty)	2 x 100% - 150 HP	Est	3	EA	275,000.00	825,000		80.00	240	240	MECH	66.86	16,046				841,000
	Injection Manifold (2 Qty)	Stainless Steel	Est	0	EA	10,500.00	0		0.00	0	0	MECH	66.86	0				0
	Dual Fluid Injection Nozzles (100 Qty)	Stainless Steel	Est	0	LT	21,000.00	0		0.00	0	0	MECH	66.86	0				0
	System Piping	L=250' - D=4" - SS / L=50' - D=4" - CS / L=50' - D=2" - SS																
	6" - SS	Includes fitting allowance	Est	250	LF	30.61	7,652		0.42	105	105	SPNG	70.4	7,392				15,000
	6" - CS	Includes fitting allowance	Est	50	LF	11.89	594		0.42	21	21	SPNG	70.4	1,478				2,100
	4" - SS	Includes fitting allowance	Est	50	LF	24.89	1,244		0.33	17	17	SPNG	70.4	1,162				2,400
	Piping Insulation & Lagging		Est	350	LF	9.14	3,197		0.17	60	60	INSUL	53.39	3,177				6,400
	Heat Tracing		Est	350	LF	21.00	7,350		0.31	109	109	WIRE	69.06	7,493				14,800
	Valves	Allowance	Est	1	LS	2,520.00	2,520		48.00	48	48	SPNG	70.4	3,379				5,900
	Supply Piping																	
	Water Supply	Allowance	Est	1	LS	840.00	840		100.00	100	100	SPNG	70.4	7,040				7,900
	Air Supply	Allowance	Est	1	LS	525.00	525		80.00	80	80	SPNG	70.4	5,632				6,200
	Piping Supports	Allowance	Est	1	LS	2,940.00	2,940		112.00	112	112	SPNG	70.4	7,885				10,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-1	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	90	CY	157.50	14,175		7.00	630	630	CONP	52.91	33,333				47,500
IS-2	STRUCTURAL STEEL	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-3	AUGER CAST PILES (125 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Mill Creek Unit 3 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.:	21987B	
Cost Type: Est = Estimated, Bid = Vendor quote																Project No.:	10584-022	
																Date:	12/20/2005	
																Rev Date:	1/27/2006	
																Run Date:	1/27/2006	
																Preparer:		
																Reviewer:		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
IS-4	ROYALTY FEE	Not Included, \$ per MW, to be negotiated with Vendor	Est	0	LF									0				0
IS-5	IS SYSTEM SUBTOTAL						3,349,638			4,369				307,475				3,057,000
MATERIAL UNLOADING SYSTEM																		
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000			1,254				88,282				193,300
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1 MVA, 6.9-480V XFMR's																
	SWITCHGEAR		Est	1	EA	460,000.00	460,000		500.00	500	500	EHEA	53.92	26,960				487,000
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	200	LF	0.76	151	Routed in 3/4" Conduit	0.05	11	11	WIRE	69.06	732				900
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	50	LF	2.12	106	Routed in 1-1/2" Conduit	0.09	5	5	WIRE	69.06	311				400
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	100	LF	2.67	267	Routed in 1-1/2" Conduit	0.35	35	35	WIRE	69.06	2,417				2,700
	Power Cables from MCC to Loads - 150HP	3/C #250kcmil, 600V	Est	100	LF	1,980.00	198,000	Routed in 2" Conduit	0.35	35	35	WIRE	69.06	2,417				200,400
	Control Cables - Pumps	5/C #14, 600V	Est	175	LF	0.67	118	Routed in 3/4" Conduit	0.03	6	6	WIRE	69.06	387				500
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,125	LF	2.06	4,373		0.19	412	412	ECND	49.67	20,477				24,800
	1-1/2" Conduit		Est	150	LF	4.67	701		0.28	43	43	ECND	49.67	2,116				2,800
	2" Conduit		Est	100	LF	6.25	625		0.35	35	35	ECND	49.67	1,748				2,400
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND	49.67	8,009				11,300
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0
AP-5	DCS SYSTEM ADDITIONS																	

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Mill Creek Unit 3 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21987B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700							
AP-8	DCS PROGRAMMING/INTERFACE																								
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800							
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300							
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800							
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						891,755							2,629				147,718	1,039,700						
	REINFORCING OF EXISTING EQUIPMENT	NONE																							
	DEMOLITION / RELOCATIONS	NONE																							
	MISCELLANEOUS	NONE																							
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,675.00	3,675		1250.00	1,250	1,250	PNTR	55.58	69,475				73,200							
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0							
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900							
MISC-4	OTHER																								
	PUMP HOUSE 15' X 20'																								
	PREFAB BLDG.			1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200							
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200							
MISC-5	CFD MODEL STUDY		Est	1	LS	0.00	0		40.00	40	40	STST	86.46	3,458				3,500							
MISC-6	TANK BERM		Est	1	LS	87,000.00	87,000		260.00	260	260	STST	86.46	22,480				109,500							
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	27,000.00	27,000		60.00	60	60	STST	86.46	5,188				32,200							
MISC-8	MISC. SUBTOTAL						166,963							2,215				136,691	303,700						
	GENERAL SUPPORT																								
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0											100,000	100,000						
GS-2	GENERAL SUPPORT SUBTOTAL						0							0				100,000	100,000						
	SUBTOTAL						4,539,710							0				10,795	804,815	4,744,800					
	Craft Support During Startup	At 3% of Total Manhours												324	MECH	66.86		21,653	21,700						
	Allowance for Premium Time Labor																		Not Included						
	Productivity Loss Due To Overtime																		Not Included						

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Mill Creek Unit 3 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21987B	
Cost Type: Est = Estimated, Bid = Vendor quote												Project No.: 10584-022	
												Date: 12/20/2005	
												Rev Date: 1/27/2006	
												Run Date: 1/27/2006	
												Preparer:	
												Reviewer:	
												Wage Rates Based on: Louisville, KY	
												Labor Productivity = 1	

Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																237,200
	Erection Contractor's Profit	At 8% of Material and Labor Costs																379,600
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																22,700
	Freight To Site	At 4.5% of Equipment/Material Cost																204,300
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	11,119			826,468				5,610,300
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								561,000
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								1,244,300
	CLIENT INTERNAL COST	Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included								0								0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0								0
	PROJECT TOTAL :									0								7,565,600

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Mill Creek Unit 3 SO3 Mitigation System Option 5 - Trona Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY		Estimate No.: 21988B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost											
DUCTWORK MODIFICATIONS																													
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800											
	DUCTWORK MODS		Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900											
	INSULATION & LAGGING	3 1/2" INSUL																											
DW-2	DUCTWORK SUPPORT STRUCTURES		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400											
	STRUCTURAL STEEL		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000											
	ACCESS & GALLERIES																												
DW-4	DUCTWORK SUBTOTAL						26,355				329			24,650				51,100											
Injection System																													
EQUIPMENT/COMPONENTS																													
	Air Blowers	150 hp each	Est	6	EA	55,125.00	330,750		105.00	630	630	PUMP	65.83	41,473				372,200											
	VFD Rotary Feeder	3 hp - Stainless Steel	Est	3	EA	10,500.00	31,500		30.00	90	90	TANK	65.78	5,920				37,400											
	Long-Term Storage Silo - Common for 2 Units (10 Days), Unit cost is split between Units 3 and 4	2,687,900 lb full - 11,610 ft ³ - D=20.7' - H=83.0' - CS Silo - SS Hopper	Est	1	EA	590,000.00	590,000		1624.00	1,624	1,624	TANK	65.78	106,827				696,800											
	Short-Term Storage Silo - (24 Hours)	268,800 lb full - 1,160 ft ³ - D=8.7' - H=39.0' - CS Silo - SS Hopper	Est	1	EA	180,000.00	180,000		120.00	120	120	TANK	65.78	7,894				187,900											
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100											
	Injection Nozzles (50 Qty)	Stainless Steel	Est	1	LT	10,500.00	10,500		240.00	240	240	MECH	66.86	16,046				26,500											
	System Piping																												
	8" - CS	Includes fitting allowance	Est	350	LF	18.48	6,468		0.46	160	160	SPNG	70.4	11,236				17,700											
	Piping Insulation & Lagging		Est	0	LF	6.62	0		0.14	0	0	INSUL	53.39	0				0											
	Heat Tracing		Est	0	LF	0.00	0		0.00	0	0	WIRE	69.06	0				0											
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800											
	Supply Piping																												
	Water Supply	Allowance	Est	0	LS	840.00	0		100.00	0	0	SPNG	70.4	0				0											
	Air Supply	Allowance	Est	0	LS	525.00	0		80.00	0	0	SPNG	70.4	0				0											
	Piping Supports	Allowance	Est	1	LS	1,575.00	1,575		60.00	60	60	SPNG	70.4	4,224				5,800											
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800											
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	90	CY	157.50	14,175		7.00	630	630	COMP	52.91	33,333				47,500											
	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800											
IS-3	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700											
IS-4	IS SYSTEM SUBTOTAL						1,253,018				5,522			383,190				1,636,000											
MATERIAL UNLOADING SYSTEM																													
ASH-1	TRUCK UNLOADING SYSTEM	Included in silo	Est	0	Set	105,000.00	0		1254.00	0	0	SPNG	70.4	0				0											
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						0				0			0				0											

Louisville Gas & Electric																	Estimate No.:	21988B
Mill Creek Unit 3																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 5 - Trona																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Reviewer:	
Labor Productivity =																	1	
Louisville, KY																		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1MVA, 6.9-480V XFMR's																
	480V SWITCHGEAR		Est	1	EA	570,000.00	570,000		4228.49	4,228	4,228	EHEA	53.92	228,000				798,000
	New Breaker at Existing 4160V Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	60,900.00	60,900		1418.55	1,419	1,419	EHEA	53.92	76,488				137,400
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 500kcmil, 600kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600
	Power Cables for 480V Switchgear	3/C 4/0kcmil, 5kV	Est	250	LF	8.40	2,100	Routed in 2" Conduit	0.35	88	88	WIRE	69.06	6,043				8,100
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 - 5HP	3/C #10, 600V	Est	150	LF	0.76	113	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				700
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 50 HP	3/C #4, 600V	Est	950	LF	2.10	1,995	Routed in 1-1/2" Conduit	0.09	86	86	WIRE	69.06	5,905				7,900
	Power Cables from MCC to Loads - 100HP	3/C #4/0, 600V	Est	150	LF	9.45	1,418	Routed in 1-1/2" Conduit	0.50	75	75	WIRE	69.06	5,180				6,600
	Power Cables from MCC to Loads - 150HP	3/C #350, 600V	Est	300	LF	10.50	3,150	Routed in 2" Conduit	0.69	207	207	WIRE	69.06	14,295				17,400
	Control Cables - Pumps	5/C #14, 600V	Est	150	LF	0.67	101	Routed in 3/4" Conduit	0.03	5	5	WIRE	69.06	332				400
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,300	LF	2.06	4,733		0.19	446	446	ECND	49.67	22,163				26,900
	1-1/2" Conduit		Est	1,100	LF	4.67	5,140		0.28	312	312	ECND	49.67	15,517				20,700
	2" Conduit		Est	550	LF	6.25	3,436		0.35	194	194	ECND	49.67	9,616				13,100
	3" Conduit		Est	900	LF	13.13	11,813		0.65	581	581	ECND	49.67	28,833				40,600
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0
AP-5	DCS SYSTEM ADDITIONS																	
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE																	
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL	60.02	6,002				16,500
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						875,382				8,684			475,887				1,351,400

Sargent & Lundy LLC Chicago			Louisville Gas & Electric Mill Creek Unit 3 SO3 Mitigation System Option 5 - Trona Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21988B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:					
Cost Type: Est = Estimated, Bid = Vendor quote													Wage Rates Based on: Labor Productivity =		Louisville, KY 1			
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,150.00	3,150		1170.00	1,170	1,170	PNTR	55.58	65,029				68,200
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
	BLOWER HOUSE																	
	PREFAB BLDG (15' x 20')			1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
MISC-5	CFD MODEL STUDY		Est	1	LS	30,000.00	30,000		40.00	40	40	STST	86.46	3,458				33,500
MISC-6	TANK BERM		Est	1	LS	0.00	0		260.00	260	260	STST	86.46	22,480				22,500
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	0.00	0		60.00	60	60	STST	86.46	5,188				5,200
MISC-5	MISC. SUBTOTAL						82,438				2,135			132,244				214,700
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000
	SUBTOTAL						2,237,192				16,670			1,115,972				3,353,200
	Craft Support During Startup	At 3% of Total Manhours									500	MECH	66.86	33,437				33,400
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																167,700
	Erection Contractor's Profit	At 8% of Material and Labor Costs																268,300
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Mill Creek Unit 3 SO3 Mitigation System Option 5 - Trona Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21988B						
Cost Type: Est = Estimated, Bid = Vendor quote												Project No.: 10584-022						
												Date: 12/20/2005						
												Rev Date: 1/27/2006						
												Run Date: 1/27/2006						
												Preparer:						
												Reviewer:						
												Wage Rates Based on: Louisville, KY						
												Labor Productivity = 1						
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Special Tools	Included wEquipment Costs																Included wEquipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																11,200
	Freight To Site	At 4.5% of Equipment/Material Cost																100,700
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	17,170			1,149,409				3,934,500
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								393,500
	PERMITTING, MODELING, ETC.									0								0
	STARTUP REAGENT TESTING (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								875,600
	CLIENT INTERNAL COST	To Be Furnished by Owner								0								100,000
	E PARTS									0								Not Included
	ALATION	Not Included								0								0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0								0
	PROJECT TOTAL :									0								5,353,600

Louisville Gas & Electric																	Estimate No.:	21990B
Mill Creek Unit 3																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 7 - Horizontal Flow WESP																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Reviewer:	
Labor Productivity =																	Louisville, KY	1
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	DUCTWORK MODIFICATIONS	COSTS																
	WESP & ASSOCIATED EQUIP																	
WE-1	WESP (Two ESP boxes, with 29 feet three fields, 9 feet long 1st field at 9.75" spacing with 76 gas passages, and 11 feet long 2nd and 3rd fields at 11.75" spacing with 64 passages, total 170 SCA. All internal 2205, with 2205 carbon steel clad alloy plate construction)	INCLUDES ALL ASSOCIATED DUCTWORK AND WASTE WATER EQUIPMENT, PIPING AND TANKS	Est	1	EA	31,570,000.00	31,570,000	BUDGETARY INPUT FROM VENDOR	142817	142,817	142,817	PREC	86.72	12,385,047				43,955,000
WE-2	Chimney Liner Adjustment (WITH MODIFIED BREECHING AT WESP OUTLET ELEVATION)	RETURN TO EXISTING BREECHING	Est	0	LF	5,302.50	0		55	0	0	PREC	86.72	0				0
WF-3	Chimney Breaching Adjustment		Est	0	LS	21,000.00	0		220	0	0	PREC	86.72	0				0
	Electrical Building	20'x40'	Est	1	EA	21,000.00	21,000		100.00	100	100	STST	86.46	8,646				29,600
WE-5	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	810	CY	157.50	127,575		7.00	5,670	5,670	CONP	52.91	300,000				427,600
WE-6	STRUCTURAL STEEL		Est	170	TN	2,200.00	374,000		16.00	2,720	2,720	STST	86.46	235,171				609,200
WE-7	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,000	LF	10.00	20,000		0.52	1,040	1,040	PILE	82.81	86,122				106,100
WE-7	FIBER GLASS DUCT 23' DIA		Est	450	LF	7,200.00	3,240,000		50.00	22,500	22,500	DUCT	59.32	1,334,700				4,574,700
WE-8	WE SYSTEM SUBTOTAL						35,352,575				174,847			14,349,686				49,702,200
	AUXILIARY POWER SUPPLY SYSTEM/I&C																	
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 2MVA, 6.9 480V XFMR's																
	SWITCHGEAR		Est	1	EA	575,000.00	575,000		500.00	500	500	EHEA	53.92	26,960				602,000
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	52,500.00	105,000		240.00	480	480	EHEA	53.92	25,882				130,900
	Misc Electrical Equipment & Controls		Est	1	LS	86,100.00	86,100		324.00	324	324	EHEA	53.92	17,470				103,600
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	100	LF	33.60	3,360	Routed in 5" Conduit	0.69	69	69	WIRE	69.06	4,765				8,100
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	0	LF	14.70	0	Routed in 3" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	1,000	LF	8.40	8,400	Routed in 2" Conduit	0.35	350	350	WIRE	69.06	24,171				32,600
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	2,400	LF	6.30	15,120	Routed in 1-1/2" Conduit	0.52	1,248	1,248	WIRE	69.06	86,187				101,300
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	0	LF	0.76	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	1,500	LF	1.58	2,363	Routed in 3/4" Conduit	0.05	80	80	WIRE	69.06	5,490				7,900
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	0	LF	2.12	0	Routed in 1-1/2" Conduit	0.09	0	0	WIRE	69.06	0				0

Louisville Gas & Electric																	Estimate No.:	21990B
Mill Creek Unit 3																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 7 - Horizontal Flow WESP																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Wage Rates Based on:	Louisville, KY
																	Labor Productivity =	1
Sargent & Lundy LLC																	Preparer:	
Chicago																	Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote																		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	0	LF	2.67	0	Routed in 1-1/2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	0	LF	3.58	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Control Cables - Pumps	5/C #14, 600V	Est	1,500	LF	0.67	1,008	Routed in 3/4" Conduit	0.03	48	48	WIRE	69.06	3,315				4,300
	Control Cables - TR Sets	7/C #14, 600V	Est	2,400	LF	0.81	1,940	Routed in 1-1/2" Conduit	0.04	96	96	WIRE	69.06	6,630				8,600
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	4,750	LF	2.06	9,776		0.19	922	922	ECND	49.67	45,771				55,500
	1-1/2" Conduit		Est	2,400	LF	4.67	11,214		0.28	682	682	ECND	49.67	33,855				45,100
	2" Conduit		Est	1,000	LF	6.25	6,248		0.35	352	352	ECND	49.67	17,484				23,700
	3" Conduit		Est	0	LF	13.13	0		0.65	0	0	ECND	49.67	0				0
	5" Conduit		Est	100	LF	38.33	3,833		1.13	113	113	ECND	49.67	5,598				9,400
AP-5	DCS SYSTEM ADDITIONS																	
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE																	
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						957,418				5,776			336,065				1,293,700
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	87,150.00	87,150		3250.00	3,250	3,250	PNTR	55.58	180,635				267,800
MISC-2	ROADWORK	20' WIDTH X 1000 LF GRAVEL	Est	1	LS	45,937.50	45,938		380.00	380	380	PBIT	62.43	23,723				69,700
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
MISC-5	PHYSICAL MODEL STUDY		Est	1	LS	120,000.00	120,000		40.00	40	40	STST	86.46	3,458				123,500
MISC-5	MISC. SUBTOTAL						260,438				3,970			223,408				483,900
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000

Louisville Gas & Electric										Estimate No.: 21990B								
Mill Creek Unit 3										Project No.: 10584-022								
SO3 Mitigation System										Date: 12/20/2005								
Option 7 - Horizontal Flow WESP										Rev Date: 1/27/2006								
Order of Magnitude Cost Estimate										Run Date: 1/27/2006								
-CONFIDENTIAL-										Preparer:								
										Reviewer:								
Wage Rates Based on:										Louisville, KY								
Labor Productivity =										1								
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
GS-2	CRANE RENTAL	700 Ton - 2 months	Est	1	LT		0	Includes freight in and out						310,000				310,000
GS-2	GENERAL SUPPORT SUBTOTAL						0			0				410,000				410,000
	SUBTOTAL						36,570,431			0	184,593			15,319,159				51,889,800
	Craft Support During Startup	At 3% of Total Manhours								5,538	MECH	66.86		370,256				370,300
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs - WESP																1,016,000
	Erection Contractor's Profit	At 8% of Material and Labor Costs - WESP																1,625,600
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																182,900
	Freight To Site	At 4.5% of Equipment/Material Cost																1,645,700
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	190,131			15,689,415				56,730,300
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								2,553,000
	PERMITTING, MODELING, ETC.									0								0
	STARTUP AND TESTING									0								100,000
	CONTINGENCY	At 20% of Total								0								11,876,700
	CLIENT INTERNAL COST	To Be Furnished by Owner								0								200,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included								0								0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0								0
	PROJECT TOTAL :									0								71,460,000

Louisville Gas & Electric
Mill Creek Unit 4
SO3 Mitigation System
Option 1 - Hydrated Lime
Order of Magnitude Cost Estimate
-CONFIDENTIAL-

Estimate No.: 21991B
Project No.: 10584-022
Date: 12/20/2005
Rev Date: 1/27/2006
Run Date: 1/27/2006
Preparer:
Reviewer:

Cost Type: Est = Estimated, Bid = Vendor quote

Wage Rates Based on: Louisville, KY
Labor Productivity = 1

Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																	
	DUCTWORK MODS																	
	INSULATION & LAGGING	3 1/2" INSUL	Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
			Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
DW-2	DUCTWORK SUPPORT STRUCTURES																	
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
DW-4	DUCTWORK SUBTOTAL						26,355				329			24,650				51,100
Injection System																		
IS-1	EQUIPMENT/COMPONENTS																	
	Air Blowers	150 hp each	Est	5	EA	55,125.00	275,625		105.00	525	525	PUMP	65.83	34,561				310,200
	VFD Rotary Feeder	3 hp - Stainless Steel	Est	3	EA	10,500.00	31,500		30.00	90	90	TANK	65.78	5,920				37,400
	Long-Term Storage Silo - Common for 2 Units (10 Days), Unit cost is split between Units 3 and 4	2,937,600 lb full - 19,615 ft³ - D=20.5' - H=82.0' - CS Silo - SS Hopper	Est	1	EA	808,000.00	808,000		2545.52	2,546	2,546	TANK	65.78	167,444				975,400
	Short-Term Storage Silo - (24 Hours)	293,760 lb full - 1,920 ft³ - D=8.5' - H=38.0' - CS Silo - SS Hopper	Est	1	EA	200,000.00	200,000		764.00	764	764	TANK	65.78	50,256				250,300
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100
	Injection Nozzles (50 Qty)	Stainless Steel	Est	1	LT	10,500.00	10,500		240.00	240	240	MECH	66.86	16,046				26,500
	System Piping	8" - CS																
	Piping Insulation & Lagging	Includes fitting allowance	Est	350	LF	18.48	6,468		0.46	161	161	SPNG	70.4	11,334				17,800
	Heat Tracing		Est	0	LF	6.62	0		0.14	0	0	INSUL	53.39	0				0
	Valves	Allowance	Est	0	LF	0.00	0		0.00	0	0	WIRE	69.06	0				0
	Supply Piping		Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800
	Water Supply	Allowance	Est	0	LS	840.00	0		100.00	0	0	SPNG	70.4	0				0
	Air Supply	Allowance	Est	0	LS	525.00	0		80.00	0	0	SPNG	70.4	0				0
	Piping Supports	Allowance	Est	1	LS	1,575.00	1,575		60.00	60	60	SPNG	70.4	4,224				5,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	50	CY	157.50	7,875		7.00	350	350	CONP	52.91	18,519				26,400
IS-3	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-4	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700
IS-5	IS SYSTEM SUBTOTAL						1,429,593				6,704			464,542				1,894,000
MATERIAL UNLOADING SYSTEM																		
ASH-1	TRUCK DELIVERY	INCLUDED IN SILO	Est	0	Set	315,000.00	0		1753.67	0	0	SPNG	70.4	0				0
	AUXILIARY POWER SUPPLY SYSTEM/I&C																	
AP-1	POWER SOURCE																	

Louisville Gas & Electric Mill Creek Unit 4 SO3 Mitigation System Option 1 - Hydrated Lime Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.:	21991B			
Sargent & Lundy LLC Chicago										Project No.:		10584-022		Date:	12/20/2005			
Cost Type: Est = Estimated, Bid = Vendor quote										Rev Date:		1/27/2006		Run Date:	1/27/2006			
										Preparer:				Reviewer:				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	480V SWITCHGEAR	Double Ended Unit Substation with (2) 2MVA, 6.9-480V XFMR's	Est	1	EA	575,000.00	575,000		500.00	500	500	EHEA	53.92	26,960				602,000
	New Breaker at Existing 6900V Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	60,900.00	60,900		300.00	300	300	EHEA	53.92	16,176				77,100
AP-2	GROUNDING		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Cable - 500kcmil GND		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
	Grounding Rod																	
AP-3	CABLE		Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Power Cables for 480V Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	150	LF	0.76	113	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				700
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	150	LF	1.58	236	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				800
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	150	LF	2.10	315	Routed in 1-1/2" Conduit	0.09	14	14	WIRE	69.06	932				1,200
	Power Cables from MCC to Loads - 50 HP	3/C #4, 600V	Est	150	LF	9.45	1,418	Routed in 1-1/2" Conduit	0.50	75	75	WIRE	69.06	5,180				6,600
	Power Cables from MCC to Loads - 100HP	3/C #4/0, 600V	Est	300	LF	10.50	3,150	Routed in 2" Conduit	0.69	207	207	WIRE	69.06	14,295				17,400
	Power Cables from MCC to Loads - 150HP	3/C #350, 600V	Est	150	LF	0.67	101	Routed in 3/4" Conduit	0.03	5	5	WIRE	69.06	332				400
	Control Cables - Pumps	5/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Control Cables - TR Sets	7/C #14, 600V	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Instrumentation Cables	2 PR #16 SHLD	Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
	Data Highway Cable																	
AP-4	RACEWAY		Est	2,300	LF	2.06	4,733		0.19	446	446	ECND	49.67	22,163				26,900
	3/4" Conduit		Est	300	LF	4.67	1,402		0.28	85	85	ECND	49.67	4,232				5,600
	1-1/2" Conduit		Est	300	LF	6.25	1,874		0.35	106	106	ECND	49.67	5,245				7,100
	2" Conduit		Est	900	LF	13.13	11,813		0.65	581	581	ECND	49.67	28,833				40,600
	3" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0
	5" Conduit																	
AP-5	DCS SYSTEM ADDITIONS		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
	Cabinets																	
AP-8	DCS PROGRAMMING/INTERFACE		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Interface Hardware		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
	Programming /Interface																	
AP-9	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL	60.02	6,002				16,500
							871,538							3,370				1,060,000
10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL																	
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																

Louisville Gas & Electric																	Estimate No.:	21991B	
Mill Creek Unit 4																	Project No.:	10584-022	
SO3 Mitigation System																	Date:	12/20/2005	
Option 1 - Hydrated Lime																	Rev Date:	1/27/2006	
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006	
-CONFIDENTIAL-																	Preparer:		
Wage Rates Based on:																	Louisville, KY	Reviewer:	
Labor Productivity =																	1		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost	
MISCELLANEOUS		NONE																	
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,150.00	3,150		1170.00	1,170	1,170	PNTR	55.58	65,029				68,200	
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0	
MISC-3	STORM DRAINAGE		Est	0	LS	7,350.00	0		300.00	0	0	YDRN	51.97	0				0	
MISC-4	OTHER																		
	BLOWER HOUSE																		
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	COMP	52.91	9,259				13,200	
	PREFAB BLDG. 15'X20'		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200	
MISC-5	CFD MODEL STUDY		Est	1	LS	30,000.00	30,000		40.00	40	40	STST	86.46	3,458				33,500	
MISC-6	TANK BERM		Est	1	LS	0.00	0		260.00	260	260	STST	86.46	22,480				22,500	
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	0.00	0		60.00	60	60	STST	86.46	5,188				5,200	
MISC-5	MISC. SUBTOTAL						75,088				1,835			116,653				191,800	
GENERAL SUPPORT																			
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							150,000				150,000	
GS-2	GENERAL SUPPORT SUBTOTAL						0			0				150,000				150,000	
SUBTOTAL							2,402,574			0	12,238			944,258				3,346,900	
	Craft Support During Startup	At 3% of Total Manhours									367	MECH	66.86	24,548				24,500	
	Allowance for Premium Time Labor																	Not Included	
	Productivity Loss Due To Overtime																	Not Included	
	Per Diem Expense																	Not Included	
	Project Wrap (Efficacy) Insurance																	Not Included	
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																167,300	
	Erection Contractor's Profit	At 8% of Material and Labor Costs																267,800	
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs	
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs	
	Consumables	At 0.5% of Equipment/Material Cost																12,000	
	Freight To Site	At 4.5% of Equipment/Material Cost																108,100	
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included	

Louisville Gas & Electric Mill Creek Unit 4 SO3 Mitigation System Option 1 - Hydrated Lime Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 21991B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	12,606			968,806				3,926,600
	ENGINEERING / CONSTRUCTION MANAGEMENT PERMITTING, MODELING, ETC.	Furnished by Project Team								0								392,660
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								0
	CONTINGENCY	At 20% of Total								0								50,000
	CLIENT INTERNAL COST	Furnished by Owner								0								873,900
	SPARE PARTS									0								100,000
	ESCALATION	Not Included																Not Included
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								5,343,160

Sargent & Lundy LLC Chicago	Louisville Gas & Electric Mill Creek Unit 4 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-													Estimate No.: 21992B				
Cost Type: Est = Estimated, Bid = Vendor quote														Project No.: 10584-022				
														Date: 12/20/2005				
														Rev Date: 1/27/2006				
														Run Date: 1/27/2006				
														Preparer:				
														Reviewer:				
														Wage Rates Based on:				
														Labor Productivity =				
														Louisville, KY				
														1				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																	
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	INSULATION & LAGGING	6" THICK INSULATION	Est	200	SF	21.00	4,200		0.27	54	54	DINS	59.32	3,203				7,400
DW-4	DUCTWORK SUPPORT STRUCTURES																	
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
DW-6	BOILER MODS																	
	WALL AND TUBE MODS		Est	2	TN	2,625.00	5,250		35.00	70	70	FLDU	89.66	6,276				11,500
DW-7	DUCTWORK SUBTOTAL						34,125				399			30,926				65,100
Injection System																		
IS-1	EQUIPMENT/COMPONENTS																	
	Air Blowers	15 hp each	Est	3	EA	21,000.00	63,000		40.00	120	120	MECH	66.86	8,023				71,000
	VFD Rotary Feeder	3 hp - Stainless steel	Est	1	EA	10,500.00	10,500		30.00	30	30	MECH	66.86	2,006				12,500
	Long-Term Storage Tank - Common for 2 Units (10 Days), Unit cost is split between Units 3 and 4	1,617,900 lb full - 17,060 ft3 - D=26.3' - H=31.6' -	Est	1	EA	151,000.00	151,000		580.00	580	580	TANK	65.78	38,152				189,200
	Short-Term Storage Silo - (24 Hours)	Not required	Est	0	EA	0.00	0		60.00	0	0	TANK	65.78	0				0
	Air Compressors (2 Qty)	50 hp - 2 X 100%	Est	2	EA	21,000.00	42,000		80.00	160	160	MECH	66.86	10,698				52,700
	Mixing Tank - 1 Unit - (24 Hours)	808,320 lb full - 8,520 ft3 - D=20.8' - H=25.0' - CS Silo - SS Hopper	Est	1	EA	122,000.00	122,000		880.00	880	880	TANK	65.78	57,886				179,900
	Mixing Tank Agitator (1 Qty)	20 hp - CS Shaft	Est	1	EA	21,000.00	21,000		30.00	30	30	MECH	66.86	2,006				23,000
	Water Storage Tank - 1 Unit (24 Hrs)	125,000 lb full - 2,000 ft3 - D=13.7' - H=13.7' - CS	Est	1	EA	115,500.00	115,500		880.00	880	880	TANK	65.78	57,886				173,400
	Slurry/Water Pumps (6 Qty)	2 hp - CS	Est	6	EA	5,250.00	31,500		20.00	120	120	PUMP	65.83	7,900				39,400
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100
	Dual Fluid Injection Nozzles (20 Qty)	Stainless Steel	Est	1	LT	42,000.00	42,000		96.00	96	96	MECH	66.86	6,419				48,400
	System Piping																	
	1" - CS	Includes fitting allowance	Est	300	LF	2.27	680		0.16	49	49	SPNG	70.4	3,464				4,100
	4" - CS	Includes fitting allowance	Est	50	LF	9.28	464		0.33	17	17	SPNG	70.4	1,162				1,600
	Piping Insulation & Lagging		Est	350	LF	2.99	1,047		0.08	26	26	INSUL	53.39	1,402				2,400
	Heat Tracing		Est	350	LF	21.00	7,350		0.31	109	109	WIRE	69.06	7,493				14,800
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800
	Supply Piping																	
	Water Supply	Allowance	Est	200	LS	840.00	168,000		100.00	20,000	20,000	SPNG	70.4	1,408,000				1,576,000
	Air Supply	Allowance	Est	200	LS	525.00	105,000		80.00	16,000	16,000	SPNG	70.4	1,126,400				1,231,400
	Piping Supports	Allowance	Est	1	LS	2,100.00	2,100		40.00	40	40	SPNG	70.4	2,816				4,900
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	110	CY	157.50	17,325		7.00	770	770	CONP	52.91	40,741				58,100
IS-3	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800

Louisville Gas & Electric																	Estimate No.:	21992B
Mill Creek Unit 4																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 2 - Magnesium Hydroxide																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
																	Reviewer:	
Wage Rates Based on:																	Louisville, KY	
Labor Productivity =																	1	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
IS-4	AUGER CAST PILES (120 TON CAPACITY)	90 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0
IS-5	IS SYSTEM SUBTOTAL						966,517				40,731			2,843,955				3,810,300
MATERIAL UNLOADING SYSTEM																		
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000				1,254			88,282				193,300
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1 MVA, 6.9-480V XFMR's	Est	1	EA	460,000.00	460,000		500.00	500	500	EHEA	53.92	26,960				487,000
	SWITCHGEAR		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA						63,000
	New Breaker at Existing 13.2kV Switchgear		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	MCC		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600
	Misc Electrical Equipment & Controls										0			0				
AP-2	GROUNDING		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Cable - 500kcmil GND		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE		Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE						
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE						
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF		0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	300	LF	0.76	227	Routed in 3/4" Conduit	0.05	16	16	WIRE	69.06	1,098				1,300
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	150	LF	1.58	236	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				800
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF		0	Routed in 1-1/2" Conduit	0.09	0	0	WIRE						
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	0	LF	2.12	0	Routed in 1-1/2" Conduit	0.35	35	35	WIRE						
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	100	LF	2.67	267	Routed in 2" Conduit	0.35	18	18	WIRE	69.06	1,209				1,400
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	50	LF	3.58	179	Routed in 3/4" Conduit	0.03	10	10	WIRE	69.06	663				900
	Control Cables - Pumps	5/C #14, 600V	Est	300	LF	0.67	202	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189											
	Data Highway Cable		Est	1,000	LF	3.15	3,150											
AP-4	RACEWAY		Est	2,500	LF	2.06	5,145		0.19	485	485	ECND						
	3/4" Conduit		Est	100	LF	4.67	467		0.28	28	28	ECND						
	1-1/2" Conduit		Est	50	LF	6.25	312		0.35	18	18	ECND						
	2" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND						
	3" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND						
	5" Conduit		Est	0	LF		0				0							

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Mill Creek Unit 4 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 21992B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
AP-5	DCS SYSTEM ADDITIONS Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA						
AP-8	DCS PROGRAMMING/INTERFACE Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC						
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL						
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						689,199				2,615			80,761				709,200
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	5,250.00	5,250		1550.00	1,550	1,550	PNTR	55.58	86,149				91,400
MISC-2	ROADWORK	Not Required	Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
	PUMP HOUSE 15' X 20'																	
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
	PREFAB BLDG.		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
MISC-5	CFD MODEL STUDY		Est	1	LS	100,000.00	100,000		40.00	40	40	STST	86.46	3,458				103,500
MISC-6	TANK BERM		Est	1	LS	76,000.00	76,000		260.00	260	260	STST	86.46	22,480				98,500
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	26,000.00	26,000		60.00	60	60	STST	86.46	5,188				31,200
MISC-5	MISC. SUBTOTAL						54,538				2,155			122,239				176,700
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000
GS	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000
	SUBTOTAL						2,051,379				47,514			3,297,288				5,287,800
	Craft Support During Startup	At 3% of Total Manhours									1,425	MECH	66.86	95,303				95,300

Louisville Gas & Electric Mill Creek Unit 4 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21992B								
Sargent & Lundy LLC Chicago										Project No.: 10584-022								
Cost Type: Est = Estimated, Bid = Vendor quote										Date: 12/20/2005								
										Rev Date: 1/27/2006								
										Run Date: 1/27/2006								
										Preparer:								
										Reviewer:								
										Wage Rates Based on: Louisville, KY								
										Labor Productivity = 1								
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																264,400
	Erection Contractor's Profit	At 8% of Material and Labor Costs																423,000
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																10,300
	Freight To Site	At 4.5% of Equipment/Material Cost																92,300
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	48,939			3,392,592				6,173,100
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								617,300
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								1,368,100
	CLIENT INTERNAL COST	To Be Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								8,308,500

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Mill Creek Unit 4 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21993B						
Cost Type: Est = Estimated, Bid = Vendor quote												Project No.: 10584-022						
												Date: 12/20/2005						
												Rev Date: 1/27/2006						
												Run Date: 1/27/2006						
												Preparer:						
												Reviewer:						
												Wage Rates Based on: Labor Productivity = 1 Louisville, KY						
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																	
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	INSULATION & LAGGING	3 1/2" INSUL	Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
DW-4	DUCTWORK SUPPORT STRUCTURES																	
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
DW-9	DUCTWORK SUBTOTAL						26,355				329			24,650				51,100
Injection System																		
EQUIPMENT/COMPONENTS																		
IS-1	Process Technology Package (PTP) by URS		Est	1	EA	1,800,000.00	1,800,000		100.00	100	100	PUMP	65.83	6,583				1,806,600
	Pumps (6 Qty)	4 - CS internals - 2.0 HP / 4 - SS internals - 1.0 HP	Est	6	EA	2,100.00	12,600		20.00	120	120	PUMP	65.83	7,900				20,500
	Long-Term Storage Silo - Common for 2 Units (10 Days), Unit cost is split between Units 3 and 4	420,250 lb full - 5,180 ft³ - D=17.6' - H=21.2' - SS	Est	1	EA	133,000.00	133,000		535.21	535	535	TANK	65.78	35,206				168,200
	Soft H₂O Storage Tank - 1 Unit - (24 Hours)	309,312 lb full - 4,957 ft³ - D=18.48' - H=18.48' - CS	Est	1	EA	83,000.00	83,000		489.52	490	490	TANK	65.78	32,201				115,200
	Agitator (1 Qty)	SS Shaft - 20 HP	Est	1	EA	21,000.00	21,000		30.00	30	30	MECH	66.86	2,006				23,000
	Air Compressors (2 Qty)	2 x 100% - 50 HP	Est	2	EA	21,000.00	42,000		80.00	160	160	MECH	66.86	10,698				52,700
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100
	Dual Fluid Injection Nozzles (100 Qty)	Stainless Steel	Est	1	LT	21,000.00	21,000		480.00	480	480	MECH	66.86	32,093				53,100
	System Piping	L=250' - D=4" - SS / L=50' - D=4" - CS / L=50' - D=2" - SS																
	6" - SS	Includes fitting allowance	Est	250	LF	30.61	7,652		0.42	105	105	SPNG	70.4	7,392				15,000
	6" - CS	Includes fitting allowance	Est	50	LF	11.89	594		0.42	21	21	SPNG	70.4	1,478				2,100
	4" - SS	Includes fitting allowance	Est	50	LF	24.89	1,244		0.33	17	17	SPNG	70.4	1,162				2,400
	Piping Insulation & Lagging		Est	350	LF	9.14	3,197		0.17	60	60	INSUL	53.39	3,177				6,400
	Heat Tracing		Est	350	LF	21.00	7,350		0.31	109	109	WIRE	69.06	7,493				14,800
	Valves	Allowance	Est	1	LS	2,520.00	2,520		48.00	48	48	SPNG	70.4	3,379				5,900
	Supply Piping																	
	Water Supply	Allowance	Est	1	LS	840.00	840		100.00	100	100	SPNG	70.4	7,040				7,900
	Air Supply	Allowance	Est	1	LS	525.00	525		80.00	80	80	SPNG	70.4	5,632				6,200
	Piping Supports	Allowance	Est	1	LS	2,940.00	2,940		112.00	112	112	SPNG	70.4	7,885				10,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	75	CY	157.50	11,813		7.00	525	525	CONP	52.91	27,778				39,600
	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS	AUGER CAST PILES (125 TON CAPACITY)	100 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0
IS-3	ROYALTY FEE		0 Est	0	LF									0				0

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Mill Creek Unit 4 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21993B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
IS-4	IS SYSTEM SUBTOTAL						2,216,275				3,890			258,861				2,475,100							
	MATERIAL UNLOADING SYSTEM																								
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300							
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000				1,254			88,282				193,300							
	AUXILIARY POWER SUPPLY SYSTEM/I&C																								
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1MVA, 6.9-480V XFMR's																							
	SWITCHGEAR		Est	1	EA	460,000.00	460,000		500.00	500	500	EHEA	53.92	26,960				487,000							
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400							
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600							
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600							
	GROUNDING																								
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100							
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400							
AP-3	CABLE																								
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0							
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600							
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0							
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0							
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	200	LF	0.76	151	Routed in 3/4" Conduit	0.05	11	11	WIRE	69.06	732				900							
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0							
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	50	LF	2.12	106	Routed in 1-1/2" Conduit	0.09	5	5	WIRE	69.06	311				400							
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	100	LF	2.67	267	Routed in 1-1/2" Conduit	0.35	35	35	WIRE	69.06	2,417				2,700							
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	0	LF	3.58	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0							
	Control Cables - Pumps	5/C #14, 600V	Est	175	LF	0.67	118	Routed in 3/4" Conduit	0.03	6	6	WIRE	69.06	387				500							
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0							
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800							
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400							
AP-4	RACEWAY																								
	3/4" Conduit		Est	2,125	LF	2.06	4,373		0.19	412	412	ECND	49.67	20,477				24,800							
	1-1/2" Conduit		Est	150	LF	4.67	701		0.28	43	43	ECND	49.67	2,116				2,800							
	2" Conduit		Est	0	LF	6.25	0		0.35	0	0	ECND	49.67	0				0							
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND	49.67	8,009				11,300							
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0							
	DCS SYSTEM ADDITIONS																								
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700							
AP-8	DCS PROGRAMMING/INTERFACE																								

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Mill Creek Unit 4 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21993B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800							
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300							
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800							
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						693,130				2,558			143,552				836,900							
	REINFORCING OF EXISTING EQUIPMENT	NONE																							
	DEMOLITION / RELOCATIONS	NONE																							
	MISCELLANEOUS	NONE																							
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,675.00	3,675		1250.00	1,250	1,250	PNTR	55.58	69,475				73,200							
2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0							
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900							
MISC-4	OTHER																								
	PUMP HOUSE 15' X 20'																								
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200							
	PREFAB BLDG.		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200							
MISC-5	CFD MODEL STUDY		Est	1	LS	0.00	0		40.00	40	40	STST	86.46	3,458				3,500							
MISC-6	TANK BERM		Est	1	LS	62,000.00	62,000		260.00	260	260	STST	86.46	22,480				84,500							
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	16,000.00	16,000		60.00	60	60	STST	86.46	5,188				21,200							
MISC-5	MISC. SUBTOTAL						130,963				2,215			136,691				267,700							
	GENERAL SUPPORT																								
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000							
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000							
	SUBTOTAL						3,171,723				0			10,247				752,036							
	Craft Support During Startup	At 3% of Total Manhours									307	MECH	66.86	20,553				0							
	Allowance for Premium Time Labor																	20,600							
	Productivity Loss Due To Overtime																	Not Included							
	Per Diem Expense																	Not Included							
	Project Wrap (Efficacy) Insurance																	Not Included							

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Mill Creek Unit 4 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21993B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:						
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Labor Productivity =		Louisville, KY 1				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																196,200
	Erection Contractor's Profit	At 8% of Material and Labor Costs																313,900
	Mandatory Spare Parts (Start-up/Testing)	Included wEquipment Costs																Included wEquipment Costs
	Special Tools	Included wEquipment Costs																Included wEquipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																15,900
	Freight To Site	At 4.5% of Equipment/Material Cost																142,700
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	10,554			772,588				4,613,400
	ENGINEERING / CONSTRUCTION MANAGEMENT PERMITTING, MODELING, ETC.	Furnished by Project Team								0								461,300
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								0
	CONTINGENCY	At 20% of Total								0								50,000
	CLIENT INTERNAL COST	Furnished by Owner								0								1,024,900
	SPARE PARTS									0								100,000
	ESCALATION	Not Included								0								Not Included
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0								0
	PROJECT TOTAL :									0								6,249,600

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Mill Creek Unit 4 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21994B		Project No.: 10584-022				
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Date: 12/20/2005		
														Rev Date: 1/27/2006				
														Run Date: 1/27/2006				
														Preparer:				
														Reviewer:				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES																	
	DUCTWORK MODS		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	INSULATION & LAGGING	3 1/2" INSUL	Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
DW-4	DUCTWORK SUPPORT STRUCTURES																	
	STRUCTURAL STEEL		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	ACCESS & GALLERIES		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
DW-9	DUCTWORK SUBTOTAL						26,355			329				24,650				51,100
Injection System																		
25.9																		
EQUIPMENT/COMPONENTS																		
	Process Technology Package (PTP). The cost shown here is for a single skid shared by Unit 3 and 4.	P&ID, Control Logic, Injection and metering pump skids, Proprietary injection lances	Budget	1	EA	1,800,000.00	1,800,000		200.00	200	200	MISC	65.83	13,166				1,813,200
	Pumps (0 Qty), included in PTP	4 - CS internals - 2.0 HP / 4 - SS internals - 1.0 HP	Est	0	EA	2,100.00	0		20.00	0	0	PUMP	65.83	0				0
	Long-Term Storage Silo -	60,000 gallon - D=16.5' - H=23.1' - SS	Est	1	EA	173,000.00	173,000		535.21	535	535	TANK	65.78	35,206				208,200
	Soft H ₂ O Storage Tank - 1 Unit - (24 Hours)	included in Soft Water supply system	Est	0	EA	0.00	0		489.52	0	0	TANK	65.78	0				0
	Agitator (1 Qty), included in PTP	SS Shaft - 20 HP	Est	0	EA	0.00	0		30.00	0	0	MECH	66.86	0				0
	Air Compressors (2operating+ 1 spare Qty)	3 x 100% - 150 HP	Est	3	EA	275,000.00	825,000		80.00	240	240	MECH	66.86	16,046				841,000
	Injection Manifold (2 Qty), PTP	Stainless Steel	Est	0	EA	0.00	0		240.00	0	0	MECH	66.86	0				0
	Dual Fluid Injection Nozzles (0 Qty), PTP	Stainless Steel	Est	0	LT	0.00	0		480.00	0	0	MECH	66.86	0				0
	System Piping	L=250' - D=4" - SS / L=50' - D=4" - CS / L=50' - D=2" - SS																
	6" - SS	Includes fitting allowance	Est	250	LF	30.61	7,652		0.42	105	105	SPNG	70.4	7,392				15,000
	6" - CS	Includes fitting allowance	Est	50	LF	11.89	594		0.42	21	21	SPNG	70.4	1,478				2,100
	4" - SS	Includes fitting allowance	Est	50	LF	24.89	1,244		0.33	17	17	SPNG	70.4	1,162				2,400
	Piping Insulation & Lagging		Est	350	LF	9.14	3,197		0.17	60	60	INSUL	53.39	3,177				6,400
	Heat Tracing		Est	350	LF	21.00	7,350		0.31	109	109	WIRE	69.06	7,493				14,800
	Valves	Allowance	Est	1	LS	2,520.00	2,520		48.00	48	48	SPNG	70.4	3,379				5,900
	Supply Piping																	
	Water Supply	Allowance	Est	1	LS	840.00	840		100.00	100	100	SPNG	70.4	7,040				7,900
	Air Supply	Allowance	Est	1	LS	525.00	525		80.00	80	80	SPNG	70.4	5,632				6,200
	Piping Supports	Allowance	Est	1	LS	2,940.00	2,940		112.00	112	112	SPNG	70.4	7,885				10,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	90	CY	157.50	14,175		7.00	630	630	CONP	52.91	33,333				47,500
IS-2	STRUCTURAL STEEL	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-3	AUGER CAST PILES (125 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Mill Creek Unit 4 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.:	21994B	
Cost Type: Est = Estimated, Bid = Vendor quote																Project No.:	10584-022	
																Date:	12/20/2005	
																Rev Date:	1/27/2006	
																Run Date:	1/27/2006	
																Preparer:		
																Reviewer:		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
IS-4	ROYALTY FEE	Not Included, \$ per MW, to be negotiated with Vendor	Est	0	LF									0				0
IS-5	IS SYSTEM SUBTOTAL						2,905,038			3,720				264,791				3,169,700
MATERIAL UNLOADING SYSTEM																		
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000			1,254				88,282				193,300
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1 MVA, 6.9-480V XFMR's																
	SWITCHGEAR		Est	1	EA	460,000.00	460,000		500.00	500	500	EHEA	53.92	26,960				487,000
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	200	LF	0.76	151	Routed in 3/4" Conduit	0.05	11	11	WIRE	69.06	732				900
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	50	LF	2.12	106	Routed in 1-1/2" Conduit	0.09	5	5	WIRE	69.06	311				400
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	100	LF	2.67	267	Routed in 1-1/2" Conduit	0.35	35	35	WIRE	69.06	2,417				2,700
	Power Cables from MCC to Loads - 150HP	3/C 250kcmil, 600V	Est	100	LF	1,980.00	198,000	Routed in 3" Conduit	0.35	35	35	WIRE	69.06	2,417				200,400
	Control Cables - Pumps	5/C #14, 600V	Est	175	LF	0.67	118	Routed in 3/4" Conduit	0.03	6	6	WIRE	69.06	387				500
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	900	LF	3.15	2,835	Routed in 3/4" Conduit	0.03	29	29	WIRE	69.06	1,989				4,800
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,025	LF	2.06	4,168		0.19	393	393	ECND	49.67	19,513				23,700
	1-1/2" Conduit		Est	150	LF	4.67	701		0.28	43	43	ECND	49.67	2,116				2,800
	2" Conduit		Est	100	LF	6.25	625		0.35	35	35	ECND	49.67	1,748				2,400
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND	49.67	8,009				11,300
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0
AP-5	DCS SYSTEM ADDITIONS																	

Louisville Gas & Electric																	Estimate No.:	21994B
Mill Creek Unit 4																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 4 - Sodium Bisulfite (SBS)																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Reviewer:	
Labor Productivity =																	1	
Louisville, KY																		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Interface Hardware		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
	Programming /Interface																	
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						891,234				2,606			146,533				1,038,000
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,675.00	3,675		1250.00	1,250	1,250	PNTR	55.58	69,475				73,200
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
	PUMP HOUSE 15' X 20'																	
	PREFAB BLDG.			1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
MISC-5	CFD Model Study	included in PTP	Est	1	LS	0.00	0		40.00	40	40	STST	86.46	3,458				3,500
MISC-6	Berm around Tanks	60,000 gallon tank, 12" concrete wall, 6" slab, sump, for 110% containment (40' x 40' x 6' high)	Est	1	LS	74,000.00	74,000		260.00	260	260	STST	86.46	22,480				96,500
MISC-7	Soft Water Supply System	50 gpm capacity	Est	1	LS	50,000.00	50,000		60.00	60	60	STST	86.46	5,188				55,200
MISC-5	CFD MODEL STUDY		Est	1	LS	0.00	0		40.00	40	40	STST	86.46	3,458				3,500
MISC-6	TANK BERM		Est	1	LS	74,000.00	74,000		260.00	260	260	STST	86.46	22,480				96,500
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	28,000.00	28,000		60.00	60	60	STST	86.46	5,188				33,200
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000

<div style="display: flex; justify-content: space-between;"> Sargent & Lundy LLC Chicago <div style="text-align: center;"> Louisville Gas & Electric Mill Creek Unit 4 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL- </div> Estimate No.: 21994B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer: </div>																		
<div style="display: flex; justify-content: space-between;"> Cost Type: Est = Estimated, Bid = Vendor quote Wage Rates Based on: Louisville, KY </div>																		
<div style="display: flex; justify-content: space-between;"> Labor Productivity = 1 </div>																		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000
	SUBTOTAL						4,206,589			0	10,484			792,073				4,999,000
	Craft Support During Startup	At 3% of Total Manhours									315	MECH	66.86	21,028				21,000
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																250,000
	Erection Contractor's Profit	At 8% of Material and Labor Costs																399,900
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																21,000
	Freight To Site	At 4.5% of Equipment/Material Cost																189,300
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	10,798			813,101				5,880,200
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								588,000
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								1,303,600
	CLIENT INTERNAL COST	Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included								0								0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0								0
	PROJECT TOTAL :									0								7,921,800

Louisville Gas & Electric Mill Creek Unit 4 SO3 Mitigation System Option 5 - Trona Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 21995B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Sargent & Lundy LLC Chicago		Cost Type: Est = Estimated, Bid = Vendor quote																									
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost									
DUCTWORK MODIFICATIONS																											
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800									
	DUCTWORK MODS		Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900									
	INSULATION & LAGGING	3 1/2" INSUL																									
DW-2	DUCTWORK SUPPORT STRUCTURES		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400									
	STRUCTURAL STEEL		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000									
	ACCESS & GALLERIES																										
DW-4	DUCTWORK SUBTOTAL						26,355				329			24,650				51,100									
Injection System																											
EQUIPMENT/COMPONENTS																											
	Air Blowers	150 hp each	Est	6	EA	55,125.00	330,750		105.00	630	630	PUMP	65.83	41,473				372,200									
	VFD Rotary Feeder	3 hp - Stainless Steel	Est	3	EA	10,500.00	31,500		30.00	90	90	TANK	65.78	5,920				37,400									
	Long-Term Storage Silo - Common for 2 Units (10 Days), Unit cost is split between Units 3 and 4	2,687,900 lb full - 11,610 ft ³ - D=20.7' - H=83.0' - CS Silo - SS Hopper	Est	1	EA	590,000.00	590,000		1624.00	1,624	1,624	TANK	65.78	106,827				696,800									
	Short-Term Storage Silo - (24 Hours)	268,800 lb full - 1,160 ft ³ - D=8.7' - H=39.0' - CS Silo - SS Hopper	Est	1	EA	180,000.00	180,000		120.00	120	120	TANK	65.78	7,894				187,900									
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100									
	Injection Nozzles (50 Qty)	Stainless Steel	Est	1	LT	10,500.00	10,500		240.00	240	240	MECH	66.86	16,046				26,500									
	System Piping																										
	8" - CS	Includes fitting allowance	Est	350	LF	18.48	6,468		0.46	160	160	SPNG	70.4	11,236				17,700									
	Piping Insulation & Lagging		Est	0	LF	6.62	0		0.14	0	0	INSUL	53.39	0				0									
	Heat Tracing		Est	0	LF	0.00	0		0.00	0	0	WIRE	69.06	0				0									
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800									
	Supply Piping																										
	Water Supply	Allowance	Est	0	LS	840.00	0		100.00	0	0	SPNG	70.4	0				0									
	Air Supply	Allowance	Est	0	LS	525.00	0		80.00	0	0	SPNG	70.4	0				0									
	Piping Supports	Allowance	Est	1	LS	1,575.00	1,575		60.00	60	60	SPNG	70.4	4,224				5,800									
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800									
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	90	CY	157.50	14,175		7.00	630	630	CONP	52.91	33,333				47,500									
	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800									
IS-3	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700									
IS-4	IS SYSTEM SUBTOTAL						1,253,018				5,522			383,190				1,636,000									
MATERIAL UNLOADING SYSTEM																											
ASH-1	TRUCK UNLOADING SYSTEM	Included in silo	Est	0	Set	105,000.00	0		1254.00	0	0	SPNG	70.4	0				0									
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						0				0			0				0									

Louisville Gas & Electric																	Estimate No.:	21995B
Mill Creek Unit 4																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 5 - Trona																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Wage Rates Based on:	Louisville, KY
																	Labor Productivity =	1
																	Preparer:	
																	Reviewer:	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1MVA, 6.9-480V XFMR's																
	480V SWITCHGEAR		Est	1	EA	460,000.00	460,000		500.00	500	500	EHEA	53.92	26,960				487,000
	New Breaker at Existing 4160V Switchgear MCC		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	Misc Electrical Equipment & Controls		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
			Est	1	LS	60,900.00	60,900		300.00	300	300	EHEA	53.92	16,176				77,100
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 500kcmil, 600kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600
	Power Cables for 480V Switchgear	3/C 4/0kcmil, 5kV	Est	250	LF	8.40	2,100	Routed in 2" Conduit	0.35	88	88	WIRE	69.06	6,043				8,100
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	150	LF	0.76	113	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				700
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 50 HP	3/C #4, 600V	Est	150	LF	2.10	315	Routed in 1-1/2" Conduit	0.09	14	14	WIRE	69.06	932				1,200
	Power Cables from MCC to Loads - 100HP	3/C #4/0, 600V	Est	150	LF	9.45	1,418	Routed in 1-1/2" Conduit	0.50	75	75	WIRE	69.06	5,180				6,600
	Power Cables from MCC to Loads - 150HP	3/C #350, 600V	Est	300	LF	10.50	3,150	Routed in 2" Conduit	0.69	207	207	WIRE	69.06	14,295				17,400
	Control Cables - Pumps	5/C #14, 600V	Est	150	LF	0.67	101	Routed in 3/4" Conduit	0.03	5	5	WIRE	69.06	332				400
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,300	LF	2.06	4,733		0.19	446	446	ECND	49.67	22,163				26,900
	1-1/2" Conduit		Est	300	LF	4.67	1,402		0.28	85	85	ECND	49.67	4,232				5,600
	2" Conduit		Est	550	LF	6.25	3,436		0.35	194	194	ECND	49.67	9,616				13,100
	3" Conduit		Est	900	LF	13.13	11,813		0.65	581	581	ECND	49.67	28,833				40,600
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0
AP-5	DCS SYSTEM ADDITIONS																	
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE																	
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL	60.02	6,002				16,500
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						759,964				3,538			198,278				958,300

Louisville Gas & Electric																	Estimate No.:	21995B
Mill Creek Unit 4																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 5 - Trona																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Reviewer:	
Labor Productivity =																	1	
Louisville, KY																		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,150.00	3,150		1170.00	1,170	1,170	PNTR	55.58	65,029				68,200
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
	BLOWER HOUSE																	
	PREFAB BLDG (15' x 20')			1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
MISC-5	CFD MODEL STUDY		Est	1	LS	30,000.00	30,000		40.00	40	40	STST	86.46	3,458				33,500
MISC-6	TANK BERM		Est	1	LS	0.00	0		260.00	260	260	STST	86.46	22,480				22,500
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	0.00	0		60.00	60	60	STST	86.46	5,188				5,200
MISC-5	MISC. SUBTOTAL						82,438				2,135			132,244				214,700
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000
	SUBTOTAL						2,121,774				11,524			838,362				2,960,100
	Craft Support During Startup	At 3% of Total Manhours									346	MECH	66.86	23,115				23,100
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																148,000
	Erection Contractor's Profit	At 8% of Material and Labor Costs																236,800
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs

Louisville Gas & Electric																	Estimate No.:	21995B
Mill Creek Unit 4																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 5 - Trona																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Louisville, KY	
Labor Productivity =																	1	
Reviewer:																		
Sargent & Lundy LLC																		
Chicago																		
Cost Type: Est = Estimated, Bid = Vendor quote																		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																10,600
	Freight To Site	At 4.5% of Equipment/Material Cost																95,500
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	11,870			861,477				3,474,100
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								347,400
	PERMITTING, MODELING, ETC.									0								0
	STARTUP REAGENT TESTING (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								774,300
	IT INTERNAL COST	To Be Furnished by Owner								0								100,000
	IE PARTS									0								Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								4,745,800

Louisville Gas & Electric Mill Creek Unit 4 SO3 Mitigation System Option 7 - Horizontal Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-															Estimate No.: 21997B			
Sargent & Lundy LLC Chicago															Project No.: 10584-022			
Cost Type: Est = Estimated, Bid = Vendor quote															Date: 12/20/2005			
															Rev Date: 1/27/2006			
															Run Date: 1/27/2006			
															Preparer:			
															Reviewer:			
															Wage Rates Based on: Louisville, KY			
															Labor Productivity = 1			
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS		COSTS																
WESP & ASSOCIATED EQUIP																		
WE-1	WESP (Two ESP boxes, with 29 feet three fields, 9 feet long 1st field at 9.75" spacing with 76 gas passages, and 11 feet long 2nd and 3rd fields at 11.75" spacing with 64 passages, total 170 SCA. All internal 2205, with 2205 carbon steel clad alloy plate construction)	INCLUDES ALL ASSOCIATED DUCTWORK AND WASTE WATER EQUIPMENT, PIPING AND TANKS	Est	1	EA	31,570,000.00	31,570,000	BUDGETARY INPUT FROM VENDOR	142817	142,817	142,817	PREC	86.72	12,385,047				43,955,000
WE-2	Chimney Liner Adjustment (WITH MODIFIED BREECHING AT WESP OUTLET ELEVATION)	RETURN TO EXISTING BREECHING	Est	0	LF	5,302.50	0		55	0	0	PREC	86.72	0				0
	Chimney Breaching Adjustment		Est	0	LS	21,000.00	0		220	0	0	PREC	86.72	0				0
WE-4	Electrical Building	20'x40'	Est	1	EA	21,000.00	21,000		100.00	100	100	STST	86.46	8,646				29,600
WE-5	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	810	CY	157.50	127,575		7.00	5,670	5,670	COMP	52.91	300,000				427,600
WE-6	STRUCTURAL STEEL		Est	170	TN	2,200.00	374,000		16.00	2,720	2,720	STST	86.46	235,171				609,200
WE-7	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,000	LF	10.00	20,000		0.52	1,040	1,040	PILE	82.81	86,122				106,100
WE-7	FIBER GLASS DUCT 23' DIA		Est	450	LF	7,200.00	3,240,000		50.00	22,500	22,500	DUCT	59.32	1,334,700				4,574,700
WE-8	WE SYSTEM SUBTOTAL						35,352,575				174,847			14,349,686				49,702,200
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 2MVA, 6.9/480V XFMR's																
	SWITCHGEAR		Est	1	EA	575,000.00	575,000		500.00	500	500	EHEA	53.92	26,960				602,000
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	52,500.00	105,000		240.00	480	480	EHEA	53.92	25,882				130,900
	Misc Electrical Equipment & Controls		Est	1	LS	86,100.00	86,100		324.00	324	324	EHEA	53.92	17,470				103,600
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	100	LF	33.60	3,360	Routed in 5" Conduit	0.69	69	69	WIRE	69.06	4,765				8,100
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	0	LF	14.70	0	Routed in 3" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	1,000	LF	8.40	8,400	Routed in 2" Conduit	0.35	350	350	WIRE	69.06	24,171				32,600
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	2,400	LF	6.30	15,120	Routed in 1-1/2" Conduit	0.52	1,248	1,248	WIRE	69.06	86,187				101,300
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	0	LF	0.76	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	1,500	LF	1.58	2,363	Routed in 3/4" Conduit	0.05	80	80	WIRE	69.06	5,490				7,900
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	0	LF	2.12	0	Routed in 1-1/2" Conduit	0.09	0	0	WIRE	69.06	0				0

Louisville Gas & Electric Mill Creek Unit 4 SO3 Mitigation System Option 7 - Horizontal Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-															Estimate No.: 21997B			
Sargent & Lundy LLC Chicago															Project No.: 10584-022			
Cost Type: Est = Estimated, Bid = Vendor quote															Date: 12/20/2006			
															Rev Date: 1/27/2006			
															Run Date: 1/27/2006			
															Preparer:			
															Reviewer:			
															Wage Rates Based on: Louisville, KY			
															Labor Productivity = 1			
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	0	LF	2.67	0	Routed in 1-1/2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	0	LF	3.58	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Control Cables - Pumps	5/C #14, 600V	Est	1,500	LF	0.67	1,008	Routed in 3/4" Conduit	0.03	48	48	WIRE	69.06	3,315				4,300
	Control Cables - TR Sets	7/C #14, 600V	Est	2,400	LF	0.81	1,940	Routed in 1-1/2" Conduit	0.04	96	96	WIRE	69.06	6,630				8,600
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	4,750	LF	2.06	9,776		0.19	922	922	ECND	49.67	45,771				55,500
	1-1/2" Conduit		Est	2,400	LF	4.67	11,214		0.28	682	682	ECND	49.67	33,855				45,100
	2" Conduit		Est	1,000	LF	6.25	6,248		0.35	352	352	ECND	49.67	17,484				23,700
	3" Conduit		Est	0	LF	13.13	0		0.65	0	0	ECND	49.67	0				0
	5" Conduit		Est	100	LF	38.33	3,833		1.13	113	113	ECND	49.67	5,598				9,400
AP-5	DCS SYSTEM ADDITIONS																	
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE																	
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						957,418				5,776			336,065				1,293,700
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	87,150.00	87,150		3250.00	3,250	3,250	PNTR	55.58	180,635				267,800
MISC-2	ROADWORK	20' WIDTH X 1000 LF GRAVEL	Est	1	LS	45,937.50	45,938		380.00	380	380	PBIT	62.43	23,723				69,700
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
MISC-5	CFD MODEL STUDY		Est	1	LS	0.00	0		40.00	40	40	STST	86.46	3,458				3,500
MISC-5	MISC. SUBTOTAL						140,438				3,970			223,408				363,900
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000

Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
GS-2	CRANE RENTAL	700 Ton - 2 months	Est	1	LT		0	Includes freight in and out						310,000				310,000
GS-2	GENERAL SUPPORT SUBTOTAL						0			0				410,000				410,000
	SUBTOTAL						36,450,431			0	184,593			15,319,159				51,769,800
	Craft Support During Startup	At 3% of Total Manhours									5,538	MECH	66.86	370,256				370,300
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs - WESP																1,010,000
	Erection Contractor's Profit	At 8% of Material and Labor Costs - WESP																1,616,000
	Mandatory Spare Parts (Start-up/Testing)	Included w\Equipment Costs																Included w\Equipment Costs
	Special Tools	Included w\Equipment Costs																Included w\Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																182,300
	Freight To Site	At 4.5% of Equipment/Material Cost																1,640,300
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	190,131			15,689,415				56,588,700
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								2,546,000
	PERMITTING, MODELING, ETC.									0								0
	STARTUP AND TESTING									0								100,000
	CONTINGENCY	At 20% of Total								0								11,846,900
	CLIENT INTERNAL COST	To Be Furnished by Owner								0								200,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included								0								0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0								0
	PROJECT TOTAL :									0								71,281,600

**Louisville Gas & Electric
Trimble County Unit 1
SO3 Mitigation System
Option 1 - Hydrated Lime
Order of Magnitude Cost Estimate
-CONFIDENTIAL-**

Wage Rates Based on: Louisville, KY
Labor Productivity = 1

Cost Type: Est = Estimated, Bid = Vendor quote

Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	DUCTWORK MODS		Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
	INSULATION & LAGGING	3 1/2" INSUL	Est															
DW-2	DUCTWORK SUPPORT STRUCTURES		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	STRUCTURAL STEEL		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
	ACCESS & GALLERIES																	
DW-4	DUCTWORK SUBTOTAL						26,355				329			24,650				51,100
Injection System																		
IS-1	EQUIPMENT/COMPONENTS																	
	Air Blowers	150 hp each	Est	5	EA	55,125.00	275,625		105.00	525	525	PUMP	65.83	34,561				310,200
	VFD Rotary Feeder	3 hp - Stainless Steel	Est	3	EA	10,500.00	31,500		30.00	90	90	TANK	65.78	5,920				37,400
	Long-Term Storage Silo - 1 Unit (10 Days)	2,937,600 lb full - 19,615 ft ³ - D=20.5' - H=82.0' - CS Silo - SS Hopper	Est	1	EA	609,000.00	609,000		2545.52	2,546	2,546	TANK	65.78	167,444				776,400
	Short-Term Storage Silo - (24 Hours)	293,760 lb full - 1,920 ft ³ - D=8.5' - H=38.0' - CS Silo - SS Hopper	Est	1	EA	201,600.00	201,600		764.00	764	764	TANK	65.78	50,256				251,900
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100
	Injection Nozzles (50 Qty)	Stainless Steel	Est	1	LT	10,500.00	10,500		240.00	240	240	MECH	66.86	16,046				26,500
	System Piping																	
	8" - CS	Includes fitting allowance	Est	350	LF	18.48	6,468		0.46	161	161	SPNG	70.4	11,334				17,800
	Piping Insulation & Lagging		Est	0	LF	6.62	0		0.14	0	0	INSUL	53.39	0				0
	Heat Tracing		Est	0	LF	0.00	0		0.00	0	0	WIRE	69.06	0				0
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800
	Supply Piping																	
	Water Supply	Allowance	Est	0	LS	840.00	0		100.00	0	0	SPNG	70.4	0				0
	Air Supply	Allowance	Est	0	LS	525.00	0		80.00	0	0	SPNG	70.4	0				0
	Piping Supports	Allowance	Est	1	LS	1,575.00	1,575		60.00	60	60	SPNG	70.4	4,224				5,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	50	CY	157.50	7,875		7.00	350	350	CONP	52.91	18,519				26,400
IS-3	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-4	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700
IS-5	IS SYSTEM SUBTOTAL						1,232,193				6,704			464,542				1,696,600
MATERIAL UNLOADING SYSTEM																		
AM-1	TRUCK DELIVERY	INCLUDED IN SILO	Est	0	Set	315,000.00	0		1753.67	0	0	SPNG	70.4	0				0
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE																	

Louisville Gas & Electric Trimble County Unit 1 SO3 Mitigation System Option 1 - Hydrated Lime Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 21975B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost									
	480V SWITCHGEAR	Double Ended Unit Substation with (2) 2MVA, 6.9-480V XFMR's	Est	1	EA	575,000.00	575,000		500.00	500	500	EHEA	53.92	26,960				602,000									
	New Breaker at Existing 6900V Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400									
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600									
	Misc Electrical Equipment & Controls		Est	1	LS	60,900.00	60,900		300.00	300	300	EHEA	53.92	16,176				77,100									
AP-2	GROUNDING		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100									
	Cable - 500kcmil GND		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400									
	Grounding Rod																										
AP-3	CABLE		Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0									
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600									
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0									
	Power Cables for 480V Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0									
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	150	LF	0.76	113	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				700									
	Power Cables from MCC to Loads - 1 - 5HP	3/C #10, 600V	Est	150	LF	1.58	236	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				800									
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	150	LF	2.10	315	Routed in 1-1/2" Conduit	0.09	14	14	WIRE	69.06	932				1,200									
	Power Cables from MCC to Loads - 50 HP	3/C #4, 600V	Est	150	LF	9.45	1,418	Routed in 1-1/2" Conduit	0.50	75	75	WIRE	69.06	5,180				6,600									
	Power Cables from MCC to Loads - 100HP	3/C #4/0, 600V	Est	300	LF	10.50	3,150	Routed in 2" Conduit	0.69	207	207	WIRE	69.06	14,295				17,400									
	Power Cables from MCC to Loads - 150HP	3/C #350, 600V	Est	150	LF	0.67	101	Routed in 3/4" Conduit	0.03	5	5	WIRE	69.06	332				400									
	Control Cables - Pumps	5/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0									
	Control Cables - TR Sets	7/C #14, 600V	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800									
	Instrumentation Cables	2 PR #16 SHLD	Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400									
	Data Highway Cable																										
AP-4	RACEWAY		Est	2,300	LF	2.06	4,733		0.19	446	446	ECND	49.67	22,163				26,900									
	3/4" Conduit		Est	300	LF	4.67	1,402		0.28	85	85	ECND	49.67	4,232				5,600									
	1-1/2" Conduit		Est	300	LF	6.25	1,874		0.35	106	106	ECND	49.67	5,245				7,100									
	2" Conduit		Est	900	LF	13.13	11,813		0.65	581	581	ECND	49.67	28,833				40,600									
	3" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0									
	5" Conduit																										
AP-5	DCS SYSTEM ADDITIONS		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700									
	Cabinets																										
AP-8	DCS PROGRAMMING/INTERFACE		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800									
	Interface Hardware		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300									
	Programming /Interface																										
AP-9	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL	60.02	6,002				16,500									
	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						871,538				3,370			188,413				1,060,000									
	REINFORCING OF EXISTING EQUIPMENT	NONE																									
	DEMOLITION / RELOCATIONS	NONE																									

Louisville Gas & Electric Trimble County Unit 1 SO3 Mitigation System Option 1 - Hydrated Lime Order of Magnitude Cost Estimate -CONFIDENTIAL-																	Estimate No.:	21975B
Sar & Lundy LLC ago																	Project No.:	10584-022
Cost Type: Est = Estimated, Bid = Vendor quote																	Date:	12/20/2005
																	Rev Date:	1/27/2006
																	Run Date:	1/27/2006
																	Preparer:	
																	Reviewer:	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,150.00	3,150		1170.00	1,170	1,170	PNTR	55.58	65,029				68,200
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	0	LS	7,350.00	0		300.00	0	0	YDRN	51.97	0				0
MISC-4	OTHER																	
	BLOWER HOUSE	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
	FOUNDATIONS		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
	PREFAB BLDG. 15'X20'																	
Misc-5	MISC. SUBTOTAL						45,088				1,475			85,528				130,600
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							150,000				150,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			150,000				150,000
	SUBTOTAL						2,175,174				0			11,878				913,133
	Craft Support During Startup	At 3% of Total Manhours												356	MECH	66.86		23,826
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	154,400
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																247,100
	Erection Contractor's Profit	At 8% of Material and Labor Costs																Included w\Equipment Costs
	Mandatory Spare Parts (Start-up/Testing)	Included w\Equipment Costs																Included w\Equipment Costs
	Special Tools	Included w\Equipment Costs																10,900
	Consumables	At 0.5% of Equipment/Material Cost																97,900
	Freight To Site	At 4.5% of Equipment/Material Cost																Not Included
	Taxes - Sales/Use/VAT/Business/Etc.																	By Owner
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																
	SUBTOTAL INSTALLED COST										0			12,235				936,958
																		3,622,400

Louisville Gas & Electric Trimble County Unit 1 SO3 Mitigation System Option 1 - Hydrated Lime Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21975B								
Sargent & Lundy LLC Chicago										Project No.: 10584-022								
Cost Type: Est = Estimated, Bid = Vendor quote										Date: 12/20/2005								
										Rev Date: 1/27/2006								
										Run Date: 1/27/2006								
										Preparer:								
										Reviewer:								
										Wage Rates Based on: Louisville, KY								
										Labor Productivity = 1								
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								362,240
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								806,900
	CLIENT INTERNAL COST	Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								4,941,540

Louisville Gas & Electric Trimble County Unit 1 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-															Estimate No.: 21969B			
Sargent & Lundy LLC Chicago															Project No.: 10584-022			
Cost Type: Est = Estimated, Bid = Vendor quote															Date: 12/20/2005			
															Rev Date: 1/27/2006			
															Run Date: 1/27/2006			
															Preparer:			
															Reviewer:			
															Wage Rates Based on: Louisville, KY			
															Labor Productivity = 1			
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	DUCTWORK MODS		Est	200	SF	21.00	4,200		0.27	54	54	DINS	59.32	3,203				7,400
	INSULATION & LAGGING	6" THICK INSULATION	Est															
DW-4	DUCTWORK SUPPORT STRUCTURES		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	STRUCTURAL STEEL		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
	ACCESS & GALLERIES		Est															
DW-6	BOILER MODS		Est	2	TN	2,625.00	5,250		35.00	70	70	FLDU	89.66	6,276				11,500
	WALL AND TUBE MODS		Est															
							34,125				399			30,926				65,100
	DUCTWORK SUBTOTAL																	
Injection System																		
IS-1	EQUIPMENT/COMPONENTS		Est	3	EA	21,000.00	63,000		40.00	120	120	MECH	66.86	8,023				71,000
	Air Blowers	Not required	Est	1	EA	10,500.00	10,500		30.00	30	30	MECH	66.86	2,006				12,500
	VFD Rotary Feeder	Not required	Est															
	Long-Term Storage Tank - 1 Unit (10 Days)	1,617,900 lb full - 17,060 ft3 - D=26.3' - H=31.6' -	Est	1	EA	105,000.00	105,000		580.00	580	580	TANK	65.78	38,152				143,200
	Short-Term Storage Silo - (24 Hours)	Not required	Est	0	EA	10,500.00	0		60.00	0	0	TANK	65.78	0				0
	Air Compressors (2 Qty)	50 hp - 2 X 100% 808,320 lb full - 8,520 ft3 - D=20.8' - H=25.0' - CS Silo - SS Hopper	Est	2	EA	21,000.00	42,000		80.00	160	160	MECH	66.86	10,698				52,700
	Mixing Tank - 1 Unit - (24 Hours)	20 hp - CS Shaft	Est	1	EA	115,500.00	115,500		880.00	880	880	TANK	65.78	57,886				173,400
	Mixing Tank Agitator (1 Qty)	125,000 lb full - 2,000 ft3 - D=13.7' - H=13.7' - CS	Est	1	EA	21,000.00	21,000		30.00	30	30	MECH	66.86	2,006				23,000
	Water Storage Tank - 1 Unit (24 Hrs)	2 hp - CS	Est	6	EA	5,250.00	31,500		20.00	120	120	PUMP	65.83	7,900				39,400
	Slurry/Water Pumps (6 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100
	Injection Manifold (2 Qty)	Stainless Steel	Est	1	LT	42,000.00	42,000		96.00	96	96	MECH	66.86	6,419				48,400
	Dual Fluid Injection Nozzles (20 Qty)		Est															
	System Piping		Est															
	1" - CS	Includes fitting allowance	Est	300	LF	2.27	680		0.16	49	49	SPNG	70.4	3,464				4,100
	4" - CS	Includes fitting allowance	Est	50	LF	9.28	464		0.33	17	17	SPNG	70.4	1,162				1,600
	Piping Insulation & Lagging		Est	350	LF	2.99	1,047		0.08	26	26	INSUL	53.39	1,402				2,400
	Heat Tracing		Est	350	LF	21.00	7,350		0.31	109	109	WIRE	69.06	7,493				14,800
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800
	Supply Piping		Est															
	Water Supply	Allowance	Est	200	LS	840.00	168,000		100.00	20,000	20,000	SPNG	70.4	1,408,000				1,576,000
	Air Supply	Allowance	Est	200	LS	525.00	105,000		80.00	16,000	16,000	SPNG	70.4	1,126,400				1,231,400
	Piping Supports	Allowance	Est	1	LS	2,100.00	2,100		40.00	40	40	SPNG	70.4	2,816				4,900
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	110	CY	157.50	17,325		7.00	770	770	CONP	52.91	40,741				58,100
IS-3	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800

Louisville Gas & Electric															Estimate No.: 21969B			
Trimble County Unit 1															Project No.: 10584-022			
SO3 Mitigation System															Date: 12/20/2005			
Option 2 - Magnesium Hydroxide															Rev Date: 1/27/2006			
Order of Magnitude Cost Estimate															Run Date: 1/27/2006			
-CONFIDENTIAL-															Preparer:			
Wage Rates Based on:															Louisville, KY			
Labor Productivity =															1			
Cost Type: Est = Estimated, Bid = Vendor quote															Reviewer:			
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
IS-4	AUGER CAST PILES (120 TON CAPACITY)	90 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0
IS-5	IS SYSTEM SUBTOTAL						914,017				40,731			2,843,955				3,757,800
MATERIAL UNLOADING SYSTEM																		
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000				1,254			88,282				193,300
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1 MVA, 6.9-480V XFMR's	Est	1	EA	570,000.00	570,000		4228.49	4,228	4,228	EHEA	53.92	228,000				798,000
	SWITCHGEAR		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA						63,000
	New Breaker at Existing 13.2kV Switchgear MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		1418.55	1,419	1,419	EHEA	53.92	76,488				84,900
AP-2	GROUNDING		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Cable - 500kcmil GND		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE		Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE						
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE						
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF		0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	300	LF	0.76	227	Routed in 3/4" Conduit	0.05	16	16	WIRE	69.06	1,098				1,300
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	150	LF	1.58	236	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				800
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF		0	Routed in 1-1/2" Conduit	0.09	0	0	WIRE						
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	100	LF	2.67	267	Routed in 1-1/2" Conduit	0.35	35	35	WIRE						
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	50	LF	3.58	179	Routed in 2" Conduit	0.35	18	18	WIRE	69.06	1,209				1,400
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	300	LF	0.67	202	Routed in 3/4" Conduit	0.03	10	10	WIRE	69.06	663				900
	Control Cables - Pumps	5/C #14, 600V	Est	0	LF		0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Control Cables - TR Sets	7/C #14, 600V	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Instrumentation Cables	2 PR #16 SHLD	Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE						
	Data Highway Cable		Est	0	LF		0											
	RACEWAY		Est	2,500	LF	2.06	5,145		0.19	485	485	ECND						
	3/4" Conduit		Est	100	LF	4.67	467		0.28	28	28	ECND						
	1-1/2" Conduit		Est	50	LF	6.25	312		0.35	18	18	ECND						
	2" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND						
	3" Conduit		Est	0	LF		0		1.13	0	0	ECND						
	5" Conduit		Est	0	LF		0											

Louisville Gas & Electric Trimble County Unit 1 SO3 Mitigation System Option 2 - Magnesium Hydroxide Order of Magnitude Cost Estimate -CONFIDENTIAL-																	Estimate No.:	21969B
Sargent & Lundy LLC Chicago																	Project No.:	10584-022
Cost Type: Est = Estimated, Bid = Vendor quote																	Date:	12/20/2005
																	Rev Date:	1/27/2006
																	Run Date:	1/27/2006
																	Preparer:	
																	Reviewer:	
																	Wage Rates Based on:	Louisville, KY
																	Labor Productivity =	1
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
AP-5	DCS SYSTEM ADDITIONS Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA						
AP-8	DCS PROGRAMMING/INTERFACE Interface Hardware Programming /Interface		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC						
			Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL						
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						799,199				7,462			342,113				1,080,500
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	5,250.00	5,250		1550.00	1,550	1,550	PNTR	55.58	86,149				91,400
MISC-2	ROADWORK	Not Required	Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
	PUMP HOUSE 15' X 20'																	
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
	PREFAB BLDG.		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
MISC-5	MISC. SUBTOTAL						54,538				2,155			122,239				176,700
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000
	SUBTOTAL						1,906,879				52,001			3,527,515				5,373,400
	Craft Support During Startup	At 3% of Total Manhours									1,560	MECH	66.86	104,304				104,300
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																268,700

Louisville Gas & Electric																	Estimate No.:	21969B
Trimble County Unit 1																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 2 - Magnesium Hydroxide																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Louisville, KY	
Labor Productivity =																	1	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Erection Contractor's Profit	At 8% of Material and Labor Costs																429,900
	Mandatory Spare Parts (Start-up/Testing)	Included wEquipment Costs																Included wEquipment Costs
	Special Tools	Included wEquipment Costs																Included wEquipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																9,500
	Freight To Site	At 4.5% of Equipment/Material Cost																85,800
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	53,561			3,631,818				6,271,600
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								627,200
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								1,389,800
	CLIENT INTERNAL COST	To Be Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0								0
	PROJECT TOTAL :									0								8,438,600

Louisville Gas & Electric Trimble County Unit 1 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-																	Estimate No.:	21983B
Sargent & Lundy LLC Chicago																	Project No.:	10584-022
Cost Type: Est = Estimated, Bid = Vendor quote																	Date:	12/20/2005
																	Rev Date:	1/27/2006
																	Run Date:	1/27/2006
																	Preparer:	
																	Reviewer:	
																	Wage Rates Based on:	Louisville, KY
																	Labor Productivity =	1
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	DUCTWORK MODS		Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
	INSULATION & LAGGING	3 1/2" INSUL																
DW-4	DUCTWORK SUPPORT STRUCTURES		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	STRUCTURAL STEEL		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
	ACCESS & GALLERIES																	
DW-9	DUCTWORK SUBTOTAL						26,355				329			24,650				51,100
Injection System																		
	EQUIPMENT/COMPONENTS		Est	1	EA	1,800,000.00	1,800,000		200.00	200	200	PUMP	65.83	13,166				1,813,200
	Process Technology Package (PTP) by URS																	
	Pumps (6 Qty)	4 - CS internals - 2.0 HP / 4 - SS internals - 1.0 HP	Est	6	EA	2,100.00	12,600		20.00	120	120	PUMP	65.83	7,900				20,500
	Soda Ash Solution Tank - 1 Unit (10 Days)	420,250 lb full - 5,180 ft ³ - D=17.6' - H=21.2' - SS	Est	1	EA	43,050.00	43,050		535.21	535	535	TANK	65.78	35,206				78,300
	Soft H ₂ O Storage Tank - 1 Unit - (24 Hours)	309,312 lb full - 4,957 ft ³ - D=18.48' - H=18.48' - CS	Est	1	EA	39,375.00	39,375		489.52	490	490	TANK	65.78	32,201				71,600
	Agitator (1 Qty)	SS Shaft - 20 HP	Est	1	EA	21,000.00	21,000		30.00	30	30	MECH	66.86	2,006				23,000
	Air Compressors (2 Qty)	2 x 100% - 50 HP	Est	2	EA	21,000.00	42,000		80.00	160	160	MECH	66.86	10,698				52,700
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100
	Dual Fluid Injection Nozzles (100 Qty)	Stainless Steel	Est	1	LT	21,000.00	21,000		480.00	480	480	MECH	66.86	32,093				53,100
	System Piping	L=250' - D=4" - SS / L=50' - D=4" - CS / L=50' - D=2" - SS																
	6" - SS	Includes fitting allowance	Est	250	LF	30.61	7,652		0.42	105	105	SPNG	70.4	7,392				15,000
	6" - CS	Includes fitting allowance	Est	50	LF	11.89	594		0.42	21	21	SPNG	70.4	1,478				2,100
	4" - SS	Includes fitting allowance	Est	50	LF	24.89	1,244		0.33	17	17	SPNG	70.4	1,162				2,400
	Piping Insulation & Lagging		Est	350	LF	9.14	3,197		0.17	60	60	INSUL	53.39	3,177				6,400
	Heat Tracing		Est	350	LF	21.00	7,350		0.31	109	109	WIRE	69.06	7,493				14,800
	Valves	Allowance	Est	1	LS	2,520.00	2,520		48.00	48	48	SPNG	70.4	3,379				5,900
	Supply Piping																	
	Water Supply	Allowance	Est	1	LS	840.00	840		100.00	100	100	SPNG	70.4	7,040				7,900
	Air Supply	Allowance	Est	1	LS	525.00	525		80.00	80	80	SPNG	70.4	5,632				6,200
	Piping Supports	Allowance	Est	1	LS	2,940.00	2,940		112.00	112	112	SPNG	70.4	7,885				10,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	75	CY	157.50	11,813		7.00	525	525	CONP	52.91	27,778				39,600
	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-3	AUGER CAST PILES (125 TON CAPACITY)	100 ft LONG	Est	0	LF	10.00	0		0.52	0	0	PILE	82.81	0				0
IS-3	ROYALTY FEE		Est	0	LF									0				0

Louisville Gas & Electric																Estimate No.:	21983B	
Trimble County Unit 1																Project No.:	10584-022	
SO3 Mitigation System																Date:	12/20/2005	
Option 3 - Soda Ash																Rev Date:	1/27/2006	
Order of Magnitude Cost Estimate																Run Date:	1/27/2006	
-CONFIDENTIAL-																Preparer:		
Wage Rates Based on: Louisville, KY																Reviewer:		
Labor Productivity = 1																		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip/ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
IS-4	IS SYSTEM SUBTOTAL						2,082,700			3,990				265,444				2,348,200
	MATERIAL UNLOADING SYSTEM																	
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000			1,254				88,282				193,300
	AUXILIARY POWER SUPPLY SYSTEM/I&C																	
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1MVA, 6.9-480V XFMR's																
	SWITCHGEAR		Est	1	EA	460,000.00	460,000		500.00	500	500	EHEA	53.92	26,960				487,000
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		300.00	300	300	EHEA	53.92	16,176				24,600
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	200	LF	0.76	151	Routed in 3/4" Conduit	0.05	11	11	WIRE	69.06	732				900
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	50	LF	2.12	106	Routed in 1-1/2" Conduit	0.09	5	5	WIRE	69.06	311				400
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	100	LF	2.67	267	Routed in 1-1/2" Conduit	0.35	35	35	WIRE	69.06	2,417				2,700
	Power Cables from MCC to Loads -150HP	3/C #2, 600V	Est	200	LF	9.90	1,980	Routed in 2" Conduit	1.55	310	310	WIRE	69.06	21,409				23,400
	Control Cables - Pumps	5/C #14, 600V	Est	175	LF	0.67	118	Routed in 3/4" Conduit	0.03	6	6	WIRE	69.06	387				500
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,125	LF	2.06	4,373		0.19	412	412	ECND	49.67	20,477				24,800
	1-1/2" Conduit		Est	150	LF	4.67	701		0.28	43	43	ECND	49.67	2,116				2,800
	2" Conduit		Est	200	LF	6.25	1,250		0.35	70	70	ECND	49.67	3,497				4,700
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND	49.67	8,009				11,300
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0
AP-5	DCS SYSTEM ADDITIONS																	
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE																	

Louisville Gas & Electric																	Estimate No.:	21983B
Trimble County Unit 1																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 3 - Soda Ash																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Wage Rates Based on:	Louisville, KY
																	Labor Productivity =	1
																	Preparer:	
																	Reviewer:	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						696,360				2,939			168,458				865,000
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,675.00	3,675		1250.00	1,250	1,250	PNTR	55.58	69,475				73,200
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
	PUMP HOUSE 15' X 20'																	
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
	PREFAB BLDG.		Est	1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
MISC-5	MISC. SUBTOTAL						52,963				1,855			105,565				158,500
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000
	SUBTOTAL						2,963,377				10,367			752,399				3,716,100
	Craft Support During Startup	At 3% of Total Manhours									311	MECH	66.86	20,794				20,800
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																185,800
	Erection Contractor's Profit	At 8% of Material and Labor Costs																297,300
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs

Louisville Gas & Electric Trimble County Unit 1 SO3 Mitigation System Option 3 - Soda Ash Order of Magnitude Cost Estimate -CONFIDENTIAL-																			
Estimate No.: 21983B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:																			
Cost Type: Est = Estimated, Bid = Vendor quote Wage Rates Based on: Louisville, KY Labor Productivity = 1																			
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost	
	Special Tools	Included wEquipment Costs																Included wEquipment Costs	
	Consumables	At 0.5% of Equipment/Material Cost																	14,800
	Freight To Site	At 4.5% of Equipment/Material Cost																	133,400
	Taxes - Sales/Use/VAT/Business/Etc.																		Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																	By Owner
	SUBTOTAL INSTALLED COST									0	10,678			773,193					4,368,200
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0									436,800
	PERMITTING, MODELING, ETC.									0									0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0									50,000
	AGENCY	At 20% of Total								0									971,000
	CLIENT INTERNAL COST	Furnished by Owner								0									100,000
	SPARE PARTS	Not Included																	Not Included
	ESCALATION	Not Included																	0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0									0
	PROJECT TOTAL :																		5,926,000

Louisville Gas & Electric Trimble County Unit 1 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-													Estimate No.: 21970B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:					
Sargent & Lundy LLC Chicago													Wage Rates Based on: Labor Productivity = 1 Louisville, KY					
Cost Type: Est = Estimated, Bid = Vendor quote																		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	DUCTWORK MODS		Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
	INSULATION & LAGGING	3 1/2" INSUL																
DW-4	DUCTWORK SUPPORT STRUCTURES		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	STRUCTURAL STEEL		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
	ACCESS & GALLERIES																	
DW-9	DUCTWORK SUBTOTAL						26,355			329				24,650				51,100
Injection System																		
EQUIPMENT/COMPONENTS																		
	Process Technology Package (URS). The cost shown here is on a single unit basis, multi-contract or economies of scale is not included.	P&ID, Control Logic, Injection and metering pump skids, Proprietary injection lances	Budget	1	EA	1,800,000.00	1,800,000		300.00	300	300	MISC	65.83	19,749				1,819,700
	Pumps (6 Qty)	4 - CS internals - 2.0 HP / 4 - SS internals - 1.0 HP	Est	6	EA	2,100.00	12,600		20.00	120	120	PUMP	65.83	7,900				20,500
	SBS Solution Tank - 1 Unit (10 Days)	62,000 gallon - D=23.4' - H=28.0' SS	Est	1	EA	205,000.00	205,000		535.21	535	535	TANK	65.78	35,206				240,200
	Soft H ₂ O Storage Tank - 1 Unit - (24 Hours)	Included in SoftWater supply system	Est	0	EA	0.00	0		489.52	0	0	TANK	65.78	0				0
	Agitator (1 Qty)	SS Shaft - 20 HP	Est	1	EA	21,000.00	21,000		30.00	30	30	MECH	66.86	2,006				23,000
	Air Compressors (2 Qty)	2 x 100% - 50 HP	Est	3	EA	225,000.00	675,000		80.00	240	240	MECH	66.86	16,046				691,000
	Injection Manifold (2 Qty)	Stainless Steel	Est	0	EA	10,500.00	0		240.00	0	0	MECH	66.86	0				0
	Dual Fluid Injection Nozzles (100 Qty)	Stainless Steel	Est	0	LT	21,000.00	0		480.00	0	0	MECH	66.86	0				0
	System Piping	L=250' - D=4" - SS / L=50' - D=4" - CS / L=50' - D=2" - SS																
	6" - SS	Includes fitting allowance	Est	250	LF	30.61	7,652		0.42	105	105	SPNG	70.4	7,392				15,000
	6" - CS	Includes fitting allowance	Est	50	LF	11.89	594		0.42	21	21	SPNG	70.4	1,478				2,100
	4" - SS	Includes fitting allowance	Est	50	LF	24.89	1,244		0.33	17	17	SPNG	70.4	1,162				2,400
	Piping Insulation & Lagging		Est	350	LF	9.14	3,197		0.17	60	60	INSUL	53.39	3,177				6,400
	Heat Tracing		Est	350	LF	21.00	7,350		0.31	109	109	WIRE	69.06	7,493				14,800
	Valves	Allowance	Est	1	LS	2,520.00	2,520		48.00	48	48	SPNG	70.4	3,379				5,900
	Supply Piping																	
	Water Supply	Allowance	Est	1	LS	840.00	840		100.00	100	100	SPNG	70.4	7,040				7,900
	Air Supply	Allowance	Est	1	LS	525.00	525		80.00	80	80	SPNG	70.4	5,632				6,200
	Piping Supports	Allowance	Est	1	LS	2,940.00	2,940		112.00	112	112	SPNG	70.4	7,885				10,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	90	CY	157.50	14,175		7.00	630	630	CONP	52.91	33,333				47,500
IS-3	STRUCTURAL STEEL	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-3	AUGER CAST PILES (125 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700

Louisville Gas & Electric																	Estimate No.:	21970B
Trimble County Unit 1																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 4 - Sodium Bisulfite (SBS)																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
Wage Rates Based on:																	Reviewer:	
Labor Productivity =																	Louisville, KY	
																	1	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
IS-4	ROYALTY FEE	Not Included, \$ per MW, to be negotiated with Vendor	Est	0	LF									0				0
IS-5	IS SYSTEM SUBTOTAL						1,020,638			3,670				261,531				1,282,000
MATERIAL UNLOADING SYSTEM																		
ASH-1	TRUCK UNLOADING SYSTEM		Est	1	Set	105,000.00	105,000		1254.00	1,254	1,254	SPNG	70.4	88,282				193,300
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						105,000			1,254				88,282				193,300
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1 MVA, 6.9-480V XFMR's																
	SWITCHGEAR		Est	1	EA	570,000.00	570,000		4228.49	4,228	4,228	EHEA	53.92	228,000				798,000
	New Breaker at Existing 13.2kV Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	8,400.00	8,400		1418.55	1,419	1,419	EHEA	53.92	76,488				84,900
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV	Est	0	LF	8.40	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	200	LF	0.76	151	Routed in 3/4" Conduit	0.05	11	11	WIRE	69.06	732				900
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	50	LF	2.12	106	Routed in 1-1/2" Conduit	0.09	5	5	WIRE	69.06	311				400
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	100	LF	2.67	267	Routed in 1-1/2" Conduit	0.35	35	35	WIRE	69.06	2,417				2,700
	Power Cables from MCC to Loads - 150HP	3/C 250kcmil, 600V	Est	100	LF	3.58	358	Routed in 2" Conduit	0.35	35	35	WIRE	69.06	2,417				2,800
	Control Cables - Pumps	5/C #14, 600V	Est	175	LF	0.67	118	Routed in 3/4" Conduit	0.03	6	6	WIRE	69.06	387				500
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,125	LF	2.06	4,373		0.19	412	412	ECND	49.67	20,477				24,800
	1-1/2" Conduit		Est	150	LF	4.67	701		0.28	43	43	ECND	49.67	2,116				2,800
	2" Conduit		Est	100	LF	6.25	625		0.35	35	35	ECND	49.67	1,748				2,400
	3" Conduit		Est	250	LF	13.13	3,281		0.65	161	161	ECND	49.67	8,009				11,300
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0
AP-5	DCS SYSTEM ADDITIONS																	

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Trimble County Unit 1 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21970B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on:		Louisville, KY											
												Labor Productivity =		1											
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost							
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700							
AP-8	DCS PROGRAMMING/INTERFACE																								
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800							
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300							
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800							
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						804,113				7,476			409,070				1,213,400							
	REINFORCING OF EXISTING EQUIPMENT	NONE																							
	DEMOLITION / RELOCATIONS	NONE																							
	MISCELLANEOUS	NONE																							
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,675.00	3,675		1250.00	1,250	1,250	PNTR	55.58	69,475				73,200							
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0							
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900							
MISC-4	OTHER																								
	PUMP HOUSE 15' X 20'																								
	PREFAB BLDG.			1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200							
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200							
MISC-5	CFD MODEL STUDY		Est	1	LS	0.00	0		40.00	40	40	STST	86.46	3,458				3,500							
MISC-6	TANK BERM		Est	1	LS	75,000.00	75,000		260.00	260	260	STST	86.46	22,480				97,500							
MISC-7	SOFT WATER SUPPLY SYSTEM		Est	1	LS	27,000.00	27,000		60.00	60	60	STST	86.46	5,188				32,200							
MISC-8	MISC. SUBTOTAL						154,963				2,215			136,691				291,700							
	GENERAL SUPPORT																								
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000							
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000							
	SUBTOTAL						3,911,068				15,243			1,039,972				4,951,200							
	Craft Support During Startup	At 3% of Total Manhours									457	MECH	66.86	30,575				30,600							
	Allowance for Premium Time Labor																	Not Included							
	Productivity Loss Due To Overtime																	Not Included							

Louisville Gas & Electric Trimble County Unit 1 SO3 Mitigation System Option 4 - Sodium Bisulfite (SBS) Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 21970B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																247,600
	Erection Contractor's Profit	At 8% of Material and Labor Costs																396,100
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																19,600
	Freight To Site	At 4.5% of Equipment/Material Cost																176,000
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	15,701			1,070,547				5,821,100
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								582,100
	PERMITTING, MODELING, ETC.									0								0
	STARTUP, TESTING AND REAGENT (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								1,290,600
	CLIENT INTERNAL COST	Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included																0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included																0
	PROJECT TOTAL :									0								7,843,800

Louisville Gas & Electric Trimble County Unit 1 SO3 Mitigation System Option 5 - Trona Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.:	21972B			
Sargent & Lundy LLC Chicago										Project No.:		10584-022		Date:	12/20/2005			
Cost Type: Est = Estimated, Bid = Vendor quote										Rev Date:		1/27/2006		Run Date:	1/27/2006			
										Preparer:				Reviewer:				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
DUCTWORK MODIFICATIONS																		
DW-1	MODIFY GAS DUCT TO ACCEPT INJECTION NOZZLES		Est	1	TN	2,625.00	2,625		35.00	35	35	FLDU	89.66	3,138				5,800
	DUCTWORK MODS		Est	200	SF	8.40	1,680		0.27	54	54	DINS	59.32	3,203				4,900
	INSULATION & LAGGING	3 1/2" INSUL																
DW-2	DUCTWORK SUPPORT STRUCTURES		Est	5	TN	1,890.00	9,450		16.00	80	80	STST	86.46	6,917				16,400
	STRUCTURAL STEEL		Est	400	SF	31.50	12,600		0.40	160	160	GALL	71.2	11,392				24,000
	ACCESS & GALLERIES																	
DW-4	DUCTWORK SUBTOTAL						26,355				329			24,650				51,100
Injection System																		
EQUIPMENT/COMPONENTS																		
	Air Blowers	150 hp each	Est	6	EA	55,125.00	330,750		105.00	630	630	PUMP	65.83	41,473				372,200
	VFD Rotary Feeder	3 hp - Stainless Steel	Est	3	EA	10,500.00	31,500		30.00	90	90	TANK	65.78	5,920				37,400
	Long-Term Storage Silo - 1 Unit (10 Days)	2,687,900 lb full - 11,610 ft³ - D=20.7' - H=83.0' - CS Silo - SS Hopper	Est	1	EA	304,500.00	304,500		1624.00	1,624	1,624	TANK	65.78	106,827				411,300
	Short-Term Storage Silo - (24 Hours)	268,800 lb full - 1,160 ft³ - D=8.7' - H=39.0' - CS Silo - SS Hopper	Est	1	EA	23,100.00	23,100		120.00	120	120	TANK	65.78	7,894				31,000
	Injection Manifold (2 Qty)	Stainless Steel	Est	2	EA	10,500.00	21,000		240.00	480	480	MECH	66.86	32,093				53,100
	Injection Nozzles (50 Qty)	Stainless Steel	Est	1	LT	10,500.00	10,500		240.00	240	240	MECH	66.86	16,046				26,500
	System Piping																	
	8" - CS	Includes fitting allowance	Est	350	LF	18.48	6,468		0.46	160	160	SPNG	70.4	11,236				17,700
	Piping Insulation & Lagging		Est	0	LF	6.62	0		0.14	0	0	INSUL	53.39	0				0
	Heat Tracing		Est	0	LF	0.00	0		0.00	0	0	WIRE	69.06	0				0
	Valves	Allowance	Est	1	LS	1,050.00	1,050		24.75	25	25	SPNG	70.4	1,742				2,800
	Supply Piping																	
	Water Supply	Allowance	Est	0	LS	840.00	0		100.00	0	0	SPNG	70.4	0				0
	Air Supply	Allowance	Est	0	LS	525.00	0		80.00	0	0	SPNG	70.4	0				0
	Piping Supports	Allowance	Est	1	LS	1,575.00	1,575		60.00	60	60	SPNG	70.4	4,224				5,800
	Piping Rack	Allowance	Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-2	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	90	CY	157.50	14,175		7.00	630	630	CONP	52.91	33,333				47,500
	STRUCTURAL STEEL		Est	10	TN	2,200.00	22,000		16.00	160	160	STST	86.46	13,834				35,800
IS-3	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,200	LF	10.00	22,000		0.52	1,144	1,144	PILE	82.81	94,735				116,700
IS-4	IS SYSTEM SUBTOTAL						810,618				5,522			383,190				1,193,600
MATERIAL UNLOADING SYSTEM																		
ASH-1	TRUCK UNLOADING SYSTEM	Included in silo	Est	0	Set	105,000.00	0		1254.00	0	0	SPNG	70.4	0				0
AH-6	MATERIAL UNLOADING SYSTEM SUBTOTAL						0				0			0				0

Louisville Gas & Electric Trimble County Unit 1 SO3 Mitigation System Option 5 - Trona Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.:	21972B			
Sargent & Lundy LLC Chicago										Project No.:		10584-022		Date:	12/20/2005			
Cost Type: Est = Estimated, Bid = Vendor quote										Rev Date:		1/27/2006		Run Date:	1/27/2006			
										Preparer:				Reviewer:				
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
AUXILIARY POWER SUPPLY SYSTEM/I&C																		
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 1MVA, 6.9-480V XFMR's																
	480V SWITCHGEAR		Est	1	EA	570,000.00	570,000		4280.00	4,280	4,280	EHEA	53.92	230,778				800,800
	New Breaker at Existing 4160V Switchgear		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400
	MCC		Est	2	EA	42,000.00	84,000		200.00	400	400	EHEA	53.92	21,568				105,600
	Misc Electrical Equipment & Controls		Est	1	LS	60,900.00	60,900		1434.00	1,434	1,434	EHEA	53.92	77,321				138,200
AP-2	GROUNDING																	
	Cable - 500kcmil GND		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100
	Grounding Rod		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400
AP-3	CABLE																	
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	33.60	0	Routed in 5" Conduit	0.69	0	0	WIRE	69.06	0				0
	Power Cables for MCC's	3/C 500kcmil, 600kV	Est	250	LF	14.70	3,675	Routed in 3" Conduit	0.69	173	173	WIRE	69.06	11,913				15,600
	Power Cables for 480V Switchgear	3/C 4/0kcmil, 5kV	Est	250	LF	8.40	2,100	Routed in 2" Conduit	0.35	88	88	WIRE	69.06	6,043				8,100
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	0	LF	6.30	0	Routed in 1-1/2" Conduit	0.52	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	150	LF	0.76	113	Routed in 3/4" Conduit	0.05	8	8	WIRE	69.06	549				700
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V	Est	0	LF	1.58	0	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 50 HP	3/C #4, 600V	Est	150	LF	2.10	315	Routed in 1-1/2" Conduit	0.09	14	14	WIRE	69.06	932				1,200
	Power Cables from MCC to Loads - 100HP	3/C #4/0, 600V	Est	150	LF	9.45	1,418	Routed in 1-1/2" Conduit	0.50	75	75	WIRE	69.06	5,180				6,600
	Power Cables from MCC to Loads - 150HP	3/C #350, 600V	Est	900	LF	10.50	9,450	Routed in 2" Conduit	0.69	621	621	WIRE	69.06	42,886				52,300
	Control Cables - Pumps	5/C #14, 600V	Est	150	LF	0.67	101	Routed in 3/4" Conduit	0.03	5	5	WIRE	69.06	332				400
	Control Cables - TR Sets	7/C #14, 600V	Est	0	LF	0.81	0	Routed in 1-1/2" Conduit	0.04	0	0	WIRE	69.06	0				0
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	2,300	LF	2.06	4,733		0.19	446	446	ECND	49.67	22,163				26,900
	1-1/2" Conduit		Est	300	LF	4.67	1,402		0.28	85	85	ECND	49.67	4,232				5,600
	2" Conduit		Est	1,150	LF	6.25	7,185		0.35	405	405	ECND	49.67	20,106				27,300
	3" Conduit		Est	900	LF	13.13	11,813		0.65	581	581	ECND	49.67	28,833				40,600
	5" Conduit		Est	0	LF	38.33	0		1.13	0	0	ECND	49.67	0				0
AP-5	DCS SYSTEM ADDITIONS																	
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE																	
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
	LIGHTING ALLOWANCE		Est	1	LT	10,500.00	10,500		100.00	100	100	INEL	60.02	6,002				16,500
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						880,012				9,077			502,322				1,382,300

Louisville Gas & Electric																	Estimate No.:	21972B
Trimble County Unit 1																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 5 - Trona																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Wage Rates Based on:	Louisville, KY
																	Labor Productivity =	1
																	Preparer:	
																	Reviewer:	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	3,150.00	3,150		1170.00	1,170	1,170	PNTR	55.58	65,029				68,200
MISC-2	ROADWORK		Est	0	LS	36,750.00	0		380.00	0	0	PBIT	62.43	0				0
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
	BLOWER HOUSE																	
	PREFAB BLDG (15' x 20')			1	LS	38,000.00	38,000		130.00	130	130	STST	86.46	11,240				49,200
	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	25	CY	157.50	3,938		7.00	175	175	CONP	52.91	9,259				13,200
MISC-5	MISC. SUBTOTAL						52,438				1,775			101,119				153,500
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000
GS-2	GENERAL SUPPORT SUBTOTAL						0				0			100,000				100,000
	SUBTOTAL						1,769,423				16,703			1,111,281				2,880,500
	Craft Support During Startup	At 3% of Total Manhours									501	MECH	66.86	33,504				33,500
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs																144,000
	Erection Contractor's Profit	At 8% of Material and Labor Costs																230,400
	Mandatory Spare Parts (Start-up/Testing)	Included wEquipment Costs																Included wEquipment Costs
	Special Tools	Included wEquipment Costs																Included wEquipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																8,800

Sargent & Lundy LLC Chicago		Louisville Gas & Electric Trimble County Unit 1 SO3 Mitigation System Option 5 - Trona Order of Magnitude Cost Estimate -CONFIDENTIAL-										Estimate No.: 21972B Project No.: 10584-022 Date: 12/20/2005 Rev Date: 1/27/2006 Run Date: 1/27/2006 Preparer: Reviewer:						
Cost Type: Est = Estimated, Bid = Vendor quote												Wage Rates Based on: Louisville, KY						
												Labor Productivity = 1						
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Freight To Site	At 4.5% of Equipment/Material Cost																79,600
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	17,204			1,144,784				3,376,800
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								337,700
	PERMITTING, MODELING, ETC.									0								0
	STARTUP REAGENT TESTING (15 DAYS)									0								50,000
	CONTINGENCY	At 20% of Total								0								752,900
	CLIENT INTERNAL COST	To Be Furnished by Owner								0								100,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included								0								0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0								0
	PROJECT TOTAL :									0								4,617,400

Louisville Gas & Electric Trimble County Unit 1 SO3 Mitigation System Option 7 - Horizontal Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.: 21973B		Project No.: 10584-022		Date: 12/20/2005		Rev Date: 1/27/2006		Run Date: 1/27/2006		Preparer:		Reviewer:	
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost									
Sargent & Lundy LLC Chicago																			Cost Type: Est = Estimated, Bid = Vendor quote								
DUCTWORK MODIFICATIONS																			COSTS								
WESP & ASSOCIATED EQUIP																											
WE-1	WESP (Two ESP boxes, with 29 feet three fields, 9 feet long 1st field at 9.75" spacing with 76 gas passages, and 11 feet long 2nd and 3rd fields at 11.75" spacing with 64 passages, total 170 SCA. All internal 2205, with 2205 carbon steel clad alloy plate construction)	INCLUDES ALL ASSOCIATED DUCTWORK, MODAL STUDY, WASTE WATER EQUIPMENT, PIPING AND TANKS	Est	1	EA	30,490,000.00	30,490,000	BUDGETARY INPUT FROM VENDOR	142817	142,817	142,817	PREC	86.72	12,385,047				42,875,000									
WE-2	Chimney Liner Adjustment (WITH MODIFIED BREECHING AT WESP OUTLET ELEVATION)	RETURN TO EXISTING BREECHING	Est	0	LF	5,302.50	0		55	0	0	PREC	86.72	0				0									
3	Chimney Breaching Adjustment		Est	0	LS	21,000.00	0		220	0	0	PREC	86.72	0				0									
WE-4	Electrical Building	20'x40'	Est	1	EA	21,000.00	21,000		100.00	100	100	STST	86.46	8,646				29,600									
WE-5	FOUNDATIONS	INCLUDES EXCAVATION & BACKFILL	Est	810	CY	157.50	127,575		7.00	5,670	5,670	CONP	52.91	300,000				427,600									
WE-6	STRUCTURAL STEEL		Est	170	TN	2,200.00	374,000		16.00	2,720	2,720	STST	86.46	235,171				609,200									
WE-7	AUGER CAST PILES (120 TON CAPACITY)	100 ft LONG	Est	2,000	LF	10.00	20,000		0.52	1,040	1,040	PILE	82.81	86,122				106,100									
WE-7	FIBER GLASS DUCT 23' DIA		Est	450	LF	7,200.00	3,240,000		50.00	22,500	22,500	DUCT	59.32	1,334,700				4,574,700									
WE-8	WE SYSTEM SUBTOTAL						34,272,575				174,847			14,349,686				48,622,200									
AUXILIARY POWER SUPPLY SYSTEM/I&C																											
AP-1	POWER SOURCE	Double Ended Unit Substation with (2) 2MVA, 6.9-480V XFMR's	Est	1	EA	575,000.00	575,000		500.00	500	500	EHEA	53.92	26,960				602,000									
	SWITCHGEAR		Est	1	EA	63,000.00	63,000		100.00	100	100	EHEA	53.92	5,392				68,400									
	New Breaker at Existing 13.2kV Switchgear		Est	2	EA	52,500.00	105,000		240.00	480	480	EHEA	53.92	25,882				130,900									
	MCC		Est	1	LS	86,100.00	86,100		324.00	324	324	EHEA	53.92	17,470				103,600									
	Misc Electrical Equipment & Controls																										
AP-2	GROUNDING		Est	2,000	LF	2.10	4,200		0.05	100	100	WIRE	69.06	6,906				11,100									
	Cable - 500kcmil GND		Est	12	EA	199.50	2,394		4.00	48	48	PILE	82.81	3,975				6,400									
	Grounding Rod																										
AP-3	CABLE		Est	100	LF	33.60	3,360	Routed in 5" Conduit	0.69	69	69	WIRE	69.06	4,765				8,100									
	Power Cables for MCC's	3/C 750kcmil, 5kV	Est	0	LF	14.70	0	Routed in 3" Conduit	0.69	0	0	WIRE	69.06	0				0									
	Power Cables for MCC's	3/C 500kcmil, 5kV	Est	1,000	LF	8.40	8,400	Routed in 2" Conduit	0.35	350	350	WIRE	69.06	24,171				32,600									
	Power Cables for Switchgear	3/C 4/0kcmil, 5kV						Routed in 1-1/2" Conduit	0.52	1,248	1,248	WIRE	69.06	86,187				101,300									
	Power Cables from Switchgear to TR Sets	3/C #2/0, 600V	Est	2,400	LF	0.76	1,824	Routed in 3/4" Conduit	0.05	0	0	WIRE	69.06	0				0									
	Power Cables from MCC to Loads - 1 ~ 5HP	3/C #10, 600V	Est	1,500	LF	1.58	2,363	Routed in 3/4" Conduit	0.05	80	80	WIRE	69.06	5,490				7,900									
	Power Cables from MCC to Loads - 15HP	3/C #8, 600V						Routed in 1-1/2" Conduit	0.09	0	0	WIRE	69.06	0				0									
	Power Cables from MCC to Loads - 20 ~ 30 HP	3/C #6, 600V	Est	0	LF	2.12	0											0									

Sargent & Lundy LLC tago		Louisville Gas & Electric Trimble County Unit 1 SO3 Mitigation System Option 7 - Horizontal Flow WESP Order of Magnitude Cost Estimate -CONFIDENTIAL-										Wage Rates Based on: Labor Productivity =		Louisville, KY 1		Estimate No.:	21973B	
Cost Type: Est = Estimated, Bid = Vendor quote																Project No.:	10584-022	
																Date:	12/20/2005	
																Rev Date:	1/27/2006	
																Run Date:	1/27/2006	
																Preparer:		
																Reviewer:		
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip/ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
	Power Cables from MCC to Loads - 50HP	3/C #4, 600V	Est	0	LF	2.67	0	Routed in 1-1/2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Power Cables from MCC to Loads - 60HP	3/C #2, 600V	Est	0	LF	3.58	0	Routed in 2" Conduit	0.35	0	0	WIRE	69.06	0				0
	Control Cables - Pumps	5/C #14, 600V	Est	1,500	LF	0.67	1,008	Routed in 3/4" Conduit	0.03	48	48	WIRE	69.06	3,315				4,300
	Control Cables - TR Sets	7/C #14, 600V	Est	2,400	LF	0.81	1,940	Routed in 1-1/2" Conduit	0.04	96	96	WIRE	69.06	6,630				8,600
	Instrumentation Cables	2 PR #16 SHLD	Est	750	LF	0.25	189	Routed in 3/4" Conduit	0.03	24	24	WIRE	69.06	1,657				1,800
	Data Highway Cable		Est	1,000	LF	3.15	3,150	Routed in 3/4" Conduit	0.03	32	32	WIRE	69.06	2,210				5,400
AP-4	RACEWAY																	
	3/4" Conduit		Est	4,750	LF	2.06	9,776		0.19	922	922	ECND	49.67	45,771				55,500
	1-1/2" Conduit		Est	2,400	LF	4.67	11,214		0.28	682	682	ECND	49.67	33,855				45,100
	2" Conduit		Est	1,000	LF	6.25	6,248		0.35	352	352	ECND	49.67	17,484				23,700
	3" Conduit		Est	0	LF	13.13	0		0.65	0	0	ECND	49.67	0				0
	5" Conduit		Est	100	LF	38.33	3,833		1.13	113	113	ECND	49.67	5,598				9,400
AP-5	DCS SYSTEM ADDITIONS																	
	Cabinets		Est	1	EA	31,500.00	31,500		40.00	40	40	EHEA	53.92	2,157				33,700
AP-8	DCS PROGRAMMING/INTERFACE																	
	Interface Hardware		Est	1	EA	2,625.00	2,625		20.00	20	20	EHEC	59.36	1,187				3,800
	Programming /Interface		Est	1	LT	5,250.00	5,250		0.00	0	0	WIRE	69.06	0				5,300
AP-9	LIGHTING ALLOWANCE		Est	1	LT	15,750.00	15,750		150.00	150	150	INEL	60.02	9,003				24,800
AP-10	AUXILIARY POWER SYSTEM / I&C SUBTOTAL						957,418			5,776				336,065				1,293,700
	REINFORCING OF EXISTING EQUIPMENT	NONE																
	DEMOLITION / RELOCATIONS	NONE																
	MISCELLANEOUS	NONE																
MISC-1	PAINTING	Touch-up and Field Finish	Est	1	LS	87,150.00	87,150		3250.00	3,250	3,250	PNTR	55.58	180,635				267,800
MISC-2	ROADWORK	20' WIDTH X 1000 LF GRAVEL	Est	1	LS	45,937.50	45,938		380.00	380	380	PBIT	62.43	23,723				69,700
MISC-3	STORM DRAINAGE		Est	1	LS	7,350.00	7,350		300.00	300	300	YDRN	51.97	15,591				22,900
MISC-4	OTHER																	
MISC-5	MISC. SUBTOTAL						140,438			3,930				219,949				360,400
	GENERAL SUPPORT																	
GS-1	MOBILIZATION / DEMOBILIZATION		Est	1	LT		0							100,000				100,000

Louisville Gas & Electric																	Estimate No.:	21973B
Trimble County Unit 1																	Project No.:	10584-022
SO3 Mitigation System																	Date:	12/20/2005
Option 7 - Horizontal Flow WESP																	Rev Date:	1/27/2006
Order of Magnitude Cost Estimate																	Run Date:	1/27/2006
-CONFIDENTIAL-																	Preparer:	
																	Reviewer:	
																	Wage Rates Based on:	Louisville, KY
																	Labor Productivity =	1
Item No.	Description	Scope Definition	Cost Type	Quantity	Unit of Measure	Unit Equip./ Mat. Cost	Total Equipment or Material Cost	Cost Development	Unit Man-hours (Base)	Total Man-hours (Base)	Total Man-hours, Prod = 1	Crew Code	Crew Wage Rate	Total Construction & Erection Cost	Sub-Contracts	DOR (Furnish)	DOR (Install)	Total Projected Cost
GS-2	CRANE RENTAL	700 Ton - 2 months	Est	1	LT		0	Includes freight in and out						310,000				310,000
GS-2	GENERAL SUPPORT SUBTOTAL						0			0				410,000				410,000
	SUBTOTAL						35,370,431			0	184,553			15,315,700				50,686,300
	Craft Support During Startup	At 3% of Total Manhours								5,537	MECH	66.86		370,176				370,200
	Allowance for Premium Time Labor																	Not Included
	Productivity Loss Due To Overtime																	Not Included
	Per Diem Expense																	Not Included
	Project Wrap (Efficacy) Insurance																	Not Included
	Erection Contractor's General & Administrative Costs	At 5% of Material and Labor Costs - WESP																1,009,800
	Erection Contractor's Profit	At 8% of Material and Labor Costs - WESP																1,615,700
	Mandatory Spare Parts (Start-up/Testing)	Included w/Equipment Costs																Included w/Equipment Costs
	Special Tools	Included w/Equipment Costs																Included w/Equipment Costs
	Consumables	At 0.5% of Equipment/Material Cost																176,900
	Freight To Site	At 4.5% of Equipment/Material Cost																1,591,700
	Taxes - Sales/Use/VAT/Business/Etc.																	Not Included
	Construction Utilities (Elect, Water, etc.) During Construction	Furnished by Owner																By Owner
	SUBTOTAL INSTALLED COST									0	190,089			15,685,876				55,450,600
	ENGINEERING / CONSTRUCTION MANAGEMENT	Furnished by Project Team								0								2,495,000
	PERMITTING, MODELING, ETC.									0								0
	STARTUP AND TESTING									0								100,000
	CONTINGENCY	At 20% of Total								0								11,609,100
	CLIENT INTERNAL COST	To Be Furnished by Owner								0								200,000
	SPARE PARTS									0								Not Included
	ESCALATION	Not Included								0								0
	INTEREST DURING CONSTRUCTION (AFUDC)	Not Included								0								0
	PROJECT TOTAL :									0								69,854,700



8.2: First Year O&M Costs

Economic Evaluation

PLANT INFORMATION

Cost Analysis Parameter	Units	Ammonia	Hydrated Lime	Humidification Water	Magnesium Hydroxide	Magnesium Oxide	Micronized Limestone	Sodium Bisulfite	Trona	Soda Ash	Wet ESP
Unit Net Capacity	MW	511	511	511	511	511	511	511	511	511	511
Capacity Factor	%	80	80	80	80	80	80	80	80	80	80
SO ₂ Before Treatment	lb/hr	846.0	846.0	846.0	846.0	846.0	846.0	846.0	846.0	846.0	634.0
Required Removal	wt%	90	90	---	90	90	90	90	90	90	90
SO ₃ Removed by Treatment	lb/hr	762.4	762.4	---	762.4	762.4	762.4	762.4	762.4	762.4	571.4

O&M COST INFORMATION

Cost Analysis Parameter	Units	Ammonia	Hydrated Lime	Humidification Water	Magnesium Hydroxide	Magnesium Oxide	Micronized Limestone	Sodium Bisulfite	Trona	Soda Ash	Wet ESP
Chemical Molar Stoichiometric Ratio	---	1.25	10.00	---	7.00	7.00	7.00	2.00	3.00	1.00	1.00
Chemical Use	lb/hr	202.5	7,062.1	0.0	3,869.4	2,668.6	6,671.4	2,401.7	6,461.7	1,010.2	416.4
Unit Chemical Cost	\$/dry ton	\$300	\$109	\$0	\$210	\$450	\$30	\$200	\$205	\$220	\$210
Yearly Chemical Cost	\$	\$212,894	\$2,697,286	\$0	\$2,847,263	\$4,207,778	\$701,296	\$1,785,311	\$4,641,580	\$880,973	\$306,400
Softened Water Consumption	gpm	0.0	0.0	75.0	36.7	0.0	75.0	43.2	0.0	0.0	0.0
Unit Softened Water Cost	\$/kgal	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06
Yearly Softened Water Cost	\$	\$0	\$0	\$1,766	\$910	\$1,766	\$1,766	\$1,017	\$0	\$428	\$0
Auxiliary Power Need (Total Installed Equipment)	KW	40	85	110	280	70	310	130	340	130	3,500
Unit Auxiliary Power Cost	\$/MMW-h	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87
Additional Outage Cost	\$/MMW-h	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59
Yearly Auxiliary Power Cost	\$	\$7,137	\$15,166	\$19,627	\$49,959	\$12,490	\$55,311	\$23,195	\$60,664	\$23,195	\$624,483
O&M Labor	man-hours	333	666	333	666	666	666	666	666	666	333
O&M Labor Cost	\$/man-hour	\$40	\$40	\$40	\$40	\$40	\$40	\$40	\$40	\$40	\$40
Yearly O&M Cost	\$	\$13,312.00	\$26,624.00	\$13,312.00	\$26,624.00	\$26,624.00	\$26,624.00	\$26,624.00	\$26,624.00	\$26,624.00	\$13,312.00
Subtotal	\$	\$233,342	\$2,739,076	\$34,705	\$2,924,756	\$4,246,892	\$784,998	\$1,896,147	\$4,728,868	\$931,220	\$944,195

Single unit.
 Licensing fee of \$200/MMW-yr applied to SBS and Soda Ash systems.
 Reagent use in WESP option is for wash water neutralization.
 Humidification water only saturates flue gas and won't remove the stated SO₂.

Economic Evaluation

PLANT INFORMATION

Cost Analysis Parameter	Units	Ammonia	Hydrated Lime	Humidification Water	Magnesium Hydroxide	Magnesium Oxide	Micronized Limestone	Sodium Bisulfite	Trona	Soda Ash	Wet ESP
Unit Net Capacity	MW	511	511	511	511	511	511	511	511	511	511
Capacity Factor	%	80	80	80	80	80	80	80	80	80	80
SO ₂ Before Treatment	lb/hr	846.0	846.0	846.0	846.0	846.0	846.0	846.0	846.0	846.0	634.0
Required Removal	wt%	90	90	---	---	---	---	---	---	---	---
SO ₃ Removed by Treatment	lb/hr	762.4	762.4	---	---	---	---	---	---	---	---
O&M COST INFORMATION											

O&M COST INFORMATION

Cost Analysis Parameter	Units	Ammonia	Hydrated Lime	Humidification Water	Magnesium Hydroxide	Magnesium Oxide	Micronized Limestone	Sodium Bisulfite	Trona	Soda Ash	Wet ESP
Chemical Molar Stoichiometric Ratio	---	1.25	10.00	---	7.00	7.00	7.00	2.00	3.00	1.00	1.00
Chemical Use	lb/hr	202.5	7,062.1	0.0	3,869.4	2,668.6	6,671.4	2,401.7	6,461.7	1,010.2	416.4
Unit Chemical Cost	\$/dry ton	\$300	\$109	\$0	\$210	\$450	\$30	\$200	\$205	\$220	\$210
Yearly Chemical Cost	\$	\$212,894	\$2,697,286	\$0	\$2,847,263	\$4,207,778	\$701,296	\$1,785,311	\$4,641,580	\$880,973	\$306,400
Softened Water Consumption	gpm	0.0	0.0	75.0	98.7	0.0	75.0	43.2	0.0	18.2	0.0
Unit Softened Water Cost	\$/kgal	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06
Yearly Softened Water Cost	\$	\$0	\$0	\$1,766	\$910	\$0	\$1,766	\$1,017	\$0	\$428	\$0
Auxiliary Power Need (Total Installed Equipment)	kw	40	85	110	280	70	310	130	340	130	3,500
Unit Auxiliary Power Cost	\$/MW-h	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87
Additional Outage Cost	\$/MW-h	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59
Yearly Auxiliary Power Cost	\$	\$7,137	\$15,166	\$19,627	\$49,959	\$12,490	\$55,311	\$23,195	\$60,864	\$23,195	\$624,483
O&M Labor	man-hours	333	666	333	666	666	666	666	666	666	333
O&M Labor Cost	\$/man-hour	\$40	\$40	\$40	\$40	\$40	\$40	\$40	\$40	\$40	\$40
Yearly O&M Cost	\$	\$13,312.00	\$26,624.00	\$13,312.00	\$26,624.00	\$26,624.00	\$26,624.00	\$26,624.00	\$26,624.00	\$26,624.00	\$13,312.00
Subtotal	\$	\$233,342	\$2,739,076	\$34,705	\$2,924,756	\$4,246,892	\$784,998	\$1,836,147	\$4,728,868	\$931,220	\$944,195

Single unit
 Licensing fee of \$200,000/yr applied to SBS and Soda Ash systems.
 Reagent use in WESP options is for wash water neutralization.
 Humidification water only saturates the gas and won't remove the stated SO₂.

Economic Evaluation

PLANT INFORMATION

Cost Analysis Parameter	Units	Ammonia	Hydrated Lime	Humidification Water	Magnesium Hydroxide	Magnesium Oxide	Micronized Limestone	Sodium Bisulfite	Trona	Soda Ash	Wet ESP
Unit Net Capacity	MW	386	386	386	386	386	386	386	386	386	386
Capacity Factor	%	80	80	80	80	80	80	80	80	80	80
SO ₂ Before Treatment	lb/hr	511.0	511.0	511.0	511.0	511.0	511.0	511.0	511.0	511.0	345.0
Required Removal	w%	87	87	---	87	87	87	87	87	87	87
SO ₃ Removed by Treatment	lb/hr	443.1	443.1	---	443.1	443.1	443.1	443.1	443.1	443.1	299.1

O&M COST INFORMATION

Cost Analysis Parameter	Units	Ammonia	Hydrated Lime	Humidification Water	Magnesium Hydroxide	Magnesium Oxide	Micronized Limestone	Sodium Bisulfite	Trona	Soda Ash	Wet ESP
Chemical Molar Stoichiometric Ratio	---	1.25	10.00	---	7.00	7.00	7.00	2.00	3.00	1.00	1.00
Chemical Use	lb/hr	117.7	4,103.8	0.0	2,248.5	1,550.7	3,876.7	1,395.6	3,754.9	587.0	218.0
Unit Chemical Cost	\$/dry ton	\$300	\$109	\$0	\$210	\$450	\$30	\$200	\$205	\$220	\$210
Yearly Chemical Cost	\$	\$123,711	\$1,567,371	\$0	\$1,654,521	\$2,445,105	\$407,518	\$1,055,242	\$2,697,184	\$529,739	\$160,403
Softened Water Consumption	gpm	0.0	0.0	75.0	22.5	0.0	75.0	25.1	0.0	10.6	0.0
Unit Softened Water Cost	\$/gal	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06
Yearly Softened Water Cost	\$	\$0	\$0	\$1,766	\$529	\$0	\$1,766	\$591	\$0	\$249	\$0
Auxiliary Power Need (Total Installed Equipment)	KW	40	85	110	280	70	310	130	340	130	3,500
Unit Auxiliary Power Cost	\$/MMW-h	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87
Additional Outage Cost	\$/MMW-h	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59
Yearly Auxiliary Power Cost	\$	\$7,137	\$15,166	\$19,627	\$49,959	\$12,480	\$55,311	\$23,195	\$60,664	\$23,195	\$624,483
O&M Labor	man-hours	333	666	333	666	666	666	666	666	666	333
O&M Labor Cost	\$/man-hour	\$40	\$40	\$40	\$40	\$40	\$40	\$40	\$40	\$40	\$40
Yearly O&M Cost	\$	\$13,312.00	\$26,624.00	\$13,312.00	\$26,624.00	\$26,624.00	\$26,624.00	\$26,624.00	\$26,624.00	\$26,624.00	\$13,312.00
Subtotal	\$	\$144,160	\$1,609,161	\$34,705	\$1,731,633	\$2,484,219	\$491,219	\$1,105,652	\$2,784,472	\$579,806	\$798,198

Single unit.
Licensing fee of \$200/MMW applied to SBS and Soda Ash systems.
Reagent use in WESP options is for wash water neutralization.
Humidification water only saturates flue gas and won't remove the stated SO₂.

Economic Evaluation

PLANT INFORMATION

Cost Analysis Parameter	Units	Ammonia	Hydrated Lime	Humidification Water	Magnesium Hydroxide	Magnesium Oxide	Micronized Limestone	Sodium Bisulfite	Trona	Soda Ash	Wet ESP
Unit Net Capacity	MW	490	490	490	490	490	490	490	490	490	490
Capacity Factor	%	80	80	80	80	80	80	80	80	80	80
SO ₂ Before Treatment	lb/hr	545.0	545.0	545.0	545.0	545.0	545.0	545.0	545.0	545.0	364.0
Required Removal	wt%	85	85	---	85	85	85	85	85	85	85
SO ₃ Removed by Treatment	lb/hr	465.9	465.9	---	465.9	465.9	465.9	465.9	465.9	465.9	311.2

O&M COST INFORMATION

Cost Analysis Parameter	Units	Ammonia	Hydrated Lime	Humidification Water	Magnesium Hydroxide	Magnesium Oxide	Micronized Limestone	Sodium Bisulfite	Trona	Soda Ash	Wet ESP
Chemical Molar Stoichiometric Ratio	---	1.25	10.00	---	7.00	7.00	7.00	2.00	3.00	1.00	1.00
Chemical Use	lb/hr	123.8	4,315.8	0.0	2,364.6	1,630.8	4,077.0	1,467.7	3,948.8	617.4	226.8
Unit Chemical Cost	\$/dry ton	\$300	\$109	\$0	\$210	\$450	\$30	\$200	\$205	\$220	\$210
Yearly Chemical Cost	\$	\$130,102	\$1,648,350	\$0	\$1,740,004	\$2,571,434	\$428,572	\$1,126,574	\$2,836,537	\$573,919	\$166,877
Softened Water Consumption	gpm	0.0	0.0	75.0	23.6	0.0	75.0	28.4	0.0	11.1	0.0
Unit Softened Water Cost	\$/gal	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06
Yearly Softened Water Cost	\$	\$0	\$1,766	\$556	\$0	\$1,766	\$0	\$621	\$0	\$261	\$0
Auxiliary Power Need (Total Installed Equipment)	kw	40	85	110	280	70	310	130	340	130	3,500
Unit Auxiliary Power Cost	\$/MW-h	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87
Yearly Auxiliary Power Cost	\$/MW-h	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59
Additional Outage Cost	\$	\$7,137	\$15,166	\$19,627	\$49,959	\$12,490	\$55,311	\$23,195	\$60,564	\$23,195	\$624,483
Yearly Auxiliary Power Cost	\$	333	666	333	666	666	666	666	666	666	333
O&M Labor Cost	\$/man-hour	\$40	\$40	\$40	\$40	\$40	\$40	\$40	\$40	\$40	\$40
Yearly O&M Cost	\$	\$13,312.00	\$26,624.00	\$13,312.00	\$26,624.00	\$26,624.00	\$26,624.00	\$26,624.00	\$26,624.00	\$26,624.00	\$13,312.00
Subtotal	\$	\$150,551	\$1,690,140	\$34,705	\$1,817,143	\$2,610,548	\$512,274	\$1,177,014	\$2,923,825	\$624,000	\$604,672

Single unit
Licensing fee of \$200/MW/yr applied to SRS and Soda Ash systems.
Reagent use in WESP columns is for wash water neutralization.
Humidification water only saturates flue gas and won't remove the stated SO₂.

Economic Evaluation

PLANT INFORMATION

Cost Analysis Parameter	Units	Ammonia	Hydrated Lime	Humidification Water	Magnesium Hydroxide	Magnesium Oxide	Micronized Limestone	Sodium Bisulfite	Trona	Soda Ash	Wet ESP
Unit Net Capacity	MW	495	495	495	495	495	495	495	495	495	495
Capacity Factor	%	80	80	80	80	80	80	80	80	80	80
SO ₂ Before Treatment	lb/hr	877.0	877.0	877.0	877.0	877.0	877.0	877.0	877.0	877.0	610.0
Required Removal	wt%	90	90	90	90	90	90	90	90	90	90
SO ₃ Removed by Treatment	lb/hr	792.8	792.8	792.8	792.8	792.8	792.8	792.8	792.8	792.8	551.4

O&M COST INFORMATION


Cost Analysis Parameter	Units	Ammonia	Hydrated Lime	Humidification Water	Magnesium Hydroxide	Magnesium Oxide	Micronized Limestone	Sodium Bisulfite	Trona	Soda Ash	Wet ESP
Chemical Molar Stoichiometric Ratio	---	1.25	10.00	---	7.00	7.00	7.00	2.00	3.00	1.00	1.00
Chemical Use	lb/hr	210.6	7,343.1	0.0	4,023.4	2,774.7	6,936.8	2,497.3	6,718.8	1,050.4	401.8
Unit Chemical Cost	\$/dry ton	\$300	\$109	\$0	\$210	\$450	\$30	\$200	\$205	\$220	\$210
Yearly Chemical Cost	\$	\$221,364	\$2,804,599	\$0	\$2,960,543	\$4,375,187	\$729,198	\$1,849,075	\$4,826,248	\$908,757	\$295,695
Softened Water Consumption	gpm	0.0	0.0	75.0	40.2	0.0	75.0	44.9	0.0	18.9	0.0
Unit Softened Water Cost	\$/kgal	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06	\$0.06
Yearly Softened Water Cost	\$	\$0	\$0	\$1,766	\$946	\$0	\$1,766	\$1,057	\$0	\$445	\$0
Auxiliary Power Need (Total Installed Equipment)	kW	40	85	110	280	70	310	130	340	130	3,500
Unit Auxiliary Power Cost	\$/MW-h	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87	\$16.87
Additional Outage Cost	\$/MW-h	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59	\$8.59
Yearly Auxiliary Power Cost	\$	\$7,137	\$15,166	\$19,627	\$49,959	\$12,490	\$55,311	\$23,195	\$60,664	\$23,195	\$624,463
O&M Labor	man-hours	333	666	333	666	666	666	666	666	666	333
Yearly O&M Labor Cost	\$/man-hour	\$40	\$40	\$40	\$40	\$40	\$40	\$40	\$40	\$40	\$40
Yearly O&M Cost	\$	\$13,312.00	\$26,624.00	\$13,312.00	\$26,624.00	\$26,624.00	\$26,624.00	\$26,624.00	\$26,624.00	\$26,624.00	\$13,312.00
Subtotal	\$	\$241,813	\$2,846,389	\$34,705	\$3,038,072	\$4,414,301	\$912,899	\$1,899,951	\$4,913,536	\$959,021	\$933,490

Single unit
Licensing fee of \$200/MW/yr applied to SRS and Soda Ash systems.
Reagent use in WESP options is for wash water neutralization.
Humidification water only saturates flue gas and won't remove the stated SO₂.



9: Drawings

Ghent 1



PLAN

SCALE: 1" = 100'-0"


Sargent & Lundy

This drawing has been drawn by, or reproduced from, a drawing prepared by an organization other than Sargent & Lundy. Sargent & Lundy is not responsible for work by other organizations.

DRAWING RELEASE RECORD			
REV	DATE RELEASED	PURPOSE	PREPARED REVIEWED APPROVED
08	01-27-06		N. PATEL G. SWITAK

<p>GENERAL ARRANGEMENT SITE PLAN SO3 MITIGATION STRATEGY STUDY EQUIPMENT ARRANGEMENT CHENT UNIT 1</p>	<p style="font-size: small;">Sargent & Lundy</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="width: 80%;">DRAWING NO.</th> <th style="width: 20%;">REV.</th> </tr> <tr> <td style="text-align: center;">GHTS03GA01</td> <td style="text-align: center;">08</td> </tr> <tr> <td style="font-size: x-small;">SHEET</td> <td style="font-size: x-small;">OF</td> </tr> </table>	DRAWING NO.	REV.	GHTS03GA01	08	SHEET	OF
DRAWING NO.	REV.						
GHTS03GA01	08						
SHEET	OF						

TYPICAL FOR UNIT 1, 3 AND UNIT 4




Equipment	QTY	HP	Power Source
First Field Recirc Water Pumps	3		480 MCC
Second Field Recirc Water Pumps	3		480 MCC
Third Field Recirc Water Pumps	3		480 MCC
Misting Recirc Water Pumps	3		480 MCC
Make-up Water Pumps	3		480 MCC
T/R Set	12	120KVA	480 Switchgear

New 4.16kV Swgr supplied as part of the new FGD modification. New aux power system is expected to be designed to support these requirements. All power and control cable to support the use of the FGD 4kV Switchgear in the responsibility of this estimate. 4kV breaker is supplied, but assume all relaying and current transformers required are not included.

Low voltage loads will be evenly across both 480V SWGR and MCC buses.

DRAWING RELEASE RECORD						SCALE	PRELIMINARY LAYOUT	Sargent & Lundy	
REV	DATE	PREPARED	REVIEWED	APPROVED	PURPOSE				
0	12-09-05	BTC			RELEASED FOR PRELIMINARY LAYOUT	NONE	GHENT UNIT 3	DWG CLASS:	REV.
						PROJECT NUMBER		SK-G1-WE-22	0
						10584-022	WET ESP SYSTEM	SHEET 1 OF 1	

TYPICAL FOR UNIT 1, 3 AND UNIT 4



Description	HP	units	QTY
Convey Air Blower Motor	250	hp	2
Blower Enclosure Fan Motor	10	hp	2
Hydraulic Duty Pump Motor	25	hp	1
Hydraulic Standby Motor	25	hp	1
Hydraulic Recirculation Pump Motor	10	hp	1
Dust Collector Fan Motor	10	hp	2
Dust Collector Rotary Feeder Motor	10	hp	1
Hydraulic Cooling Fan Motor	10	hp	1
Silo Screw Feeder Motor	25	hp	1
Weigh Bin Rotary Feeder Motor	10	hp	2
Airlock Rotary Feeder Motor	10	hp	2
Glycol Duty Pump Motor	25	hp	1
Glycol Standby Pump Motor	25	hp	1
Chiller Motor	10	hp	7
Desiccant Wheel Reg Fan Motor	1	hp	2
Desiccant Wheel Drive Motor	2	hp	2
Desiccant Wheel React Heater	24	kw	2
Main Elevator Motor	50	hp	1
Transformer 480:208V Lighting/HVAC 3 phase	28	kva	1
Transformer 480:120/240V Control 1 phase	50	kva	1
HVAC Exhaust Fan Motor	7.5	hp	2
HVAC Supply Fan Motor	7.5	hp	2
HVAC Blower Heater	5	kw	4
HVAC Blower Heater	10	kw	4

DRAWER RELEASE RECORD					
REV	DATE	PREPARED	REVIEWED	APPROVED	PURPOSE
0	12-09-05	BTC			RELEASED FOR PRELIMINARY LAYOUT

SCALE
NONE
PROJECT NUMBER
10584-022

PRELIMINARY LAYOUT
GHENT UNIT 3
SORBENT INJECTION SYSTEM

Sargent & Lundy

DWG CLASS: SK-G3-SI-22

SHEET 1 OF 1



REV. 1



9: Drawings

Ghent 3

10000-W-0HD



PLAN
SCALE: 1" = 100'-0"

DRAWING RELEASE RECORD				DRAWING RELEASE RECORD			
REV.	DATE	PREPARED BY	APPROVED BY	REV.	DATE	PREPARED BY	APPROVED BY

FLUOR
100 Flow Dredge Drive
Raleigh, NC 27601
919-281-4400

SCALE
PROJECT NUMBER

CHERT POWER STATION
MASTER PLANNING ARRANGEMENT
WEST SIDE PLAN

KU Kentucky Utilities Company
GHO-M-00001

Sargent & Lundy

This drawing has been drawn by, or reproduced from, a drawing prepared by an organization other than Sargent & Lundy. Sargent & Lundy is not responsible for work by other organizations.


DRAWING RELEASE RECORD			
REV.	DATE RELEASED	PURPOSE	PREPARED / REVIEWED / APPROVED
08	1-27-06		N. PATEL / G. SWITAK

Sargent & Lundy

**GENERAL ARRANGEMENT
SITE PLAN
SO3 MITIGATION STRATEGY STUDY
EQUIPMENT ARRANGEMENT
CHERT UNIT 3 & 4**

DRAWING NO.	REV.
GHTS03GA02	08

GHENT UNIT 3
OPTION 1



ELEVATION

SO3 MITIGATION STUDY
EQUIPMENT ARRANGEMENT
GHENT PLANT UNIT 3


<i>Bergant & Lundy</i>	
DRAWING NO.	REV.
GHENTGA03	0
SHEET	OF



9: Drawings

Ghent 4

GHENT UNIT 4
OPTION 1





ELEVATION

S03 MITIGATION STUDY
EQUIPMENT ARRANGEMENT
GHENT PLANT UNIT 4



DRAWING NO.	REV.
GHENTGA01	0
SHEET	OF

GHENT UNIT 4
OPTION 2



S03 MITIGATION STUDY
EQUIPMENT ARRANGEMENT
GHENT PLANT UNIT 4

Sargent & Lundy

DRAWING NO.	REV.
GHENTGA02	0
SHEET	OF




9: Drawings

Mill Creek 3

Mg(OH)₂
(SEE DWG.
C801 U4)

SORBENT
(SEE DWG.
C801 U4)



PRECIPITATORS

I.D. FANS

CHIMNEY

I.D. FANS

FLY ASH
BLOWER
BDDG. 3

OAS
TANK

MH#18

MH#19

UNIT #3
REACTION TANK
PUMP HOUSE

SERVICE
BLDG.

SDRS CONTROL
BDDG.

CON
T

CLARIFIER

ABS
REA
T.

SS



Sargent & Lundy


This drawing has been drawn by, or reproduced from, a drawing prepared by an organization other than Sargent & Lundy. Sargent & Lundy is not responsible for work by other organizations.

DRAWING RELEASE RECORD			
REV	DATE RELEASED	PURPOSE	PREPARED REVIEWED APPROVED
08	01-27-06		N. PATEL G. SWITAK

GENERAL ARRANGEMENT SITE PLAN SO3 MITIGATION STRATEGY STUDY EQUIPMENT ARRANGEMENT MILL CREEK UNIT 3		<i>Sargent & Lundy</i>	
DRAWING NO.	REV.		
C801 U3	08		
SHEET	OF		


PLAN

REVISIONS	
1	Issue for construction
2	Change in dimensions of reaction tanks
3	Change in dimensions of precipitators
4	Change in dimensions of S.R.S.
5	Change in dimensions of S.R.S.
6	Change in dimensions of S.R.S.
7	Change in dimensions of S.R.S.
8	Change in dimensions of S.R.S.
9	Change in dimensions of S.R.S.
10	Change in dimensions of S.R.S.
11	Change in dimensions of S.R.S.
12	Change in dimensions of S.R.S.
13	Change in dimensions of S.R.S.
14	Change in dimensions of S.R.S.
15	Change in dimensions of S.R.S.
16	Change in dimensions of S.R.S.
17	Change in dimensions of S.R.S.
18	Change in dimensions of S.R.S.
19	Change in dimensions of S.R.S.
20	Change in dimensions of S.R.S.




PLAN
SCALE: 1/8" = 1'-0"

317273 - M201 C 317273 - E241	IGE General Engineering & Electric Company 10000 W. 10th Avenue Denver, Colorado 80202 Telephone: 333-1111 Telex: 317273	Project Name Project No. Client Name Client Address Client Phone Client Telex
General Arrangement Cross Section "D-B" Looking North Precipitators & S.R.S.		
Pioneer Service	317273	M201 US D



PLAN




ELEVATION
"A-A"

NOTE:
1. SUPPORTS FOR NEW DUCT NOT SHOWN.

S03 MITIGATION STUDY EQUIPMENT ARRANGEMENT MILL CREEK PLANT UNIT 3		Sargent & Lundy ^{INC}	
		DRAWING NO. MILLGA03	REV. 0
SHEET		OF	

TYPICAL FOR BOTH UNIT 3 AND UNIT 4




Description	HP	units	QTY
Convey Air Blower Motor	250	hp	2
Blower Enclosure Fan Motor	10	hp	2
Hydraulic Duty Pump Motor	25	hp	1
Hydraulic Standby Motor	25	hp	1
Hydraulic Recirculation Pump Motor	10	hp	1
Dust Collector Fan Motor	10	hp	2
Dust Collector Rotary Feeder Motor	10	hp	1
Hydraulic Cooling Fan Motor	10	hp	1
Silo Screw Feeder Motor	25	hp	1
Weigh Bin Rotary Feeder Motor	10	hp	2
Airlock Rotary Feeder Motor	10	hp	2
Glycol Duty Pump Motor	25	hp	1
Glycol Standby Pump Motor	25	hp	1
Chiller Motor	10	hp	7
Desicant Wheel Reg Fan Motor	1	hp	2
Desicant Wheel Drive Motor	2	hp	2
Desicant Wheel React Heater	24	kw	2
Main Elevator Motor	50	hp	1
Transformer 480:208V Lighting/HVAC 3 phase	28	kva	1
Transformer 480:120/240V Control 1 phase	50	kva	1
HVAC Exhaust Fan Motor	7.5	hp	2
HVAC Supply Fan Motor	7.5	hp	2
HVAC Blower Heater	5	kw	4
HVAC Blower Heater	10	kw	4

DRAWING RELEASE RECORD						SCALE	PROJECT NUMBER	PRELIMINARY LAYOUT	Sargent & Lundy ^{llc}	
REV	DATE	PREPARED	REVIEWED	APPROVED	PURPOSE					
0	12-09-05	BTC			RELEASED FOR PRELIMINARY LAYOUT	NONE	10584-022	MILL CREEK UNIT 3	DWG CLASS:	REV.
									SK-MC3-SI-22	0
								SORBENT INJECTION SYSTEM	SHEET 1 OF 1	



9: Drawings

Mill Creek 4



PLAN



Sargent & Lundy

This drawing has been drawn by, or reproduced from, a drawing prepared by an organization other than Sargent & Lundy. Sargent & Lundy is not responsible for work by other organizations.

DRAWING RELEASE RECORD			
REV	DATE RELEASED	PURPOSE	PREPARED REVIEWED APPROVED
08	01-27-06		N. PATEL G. SWITAK


**GENERAL ARRANGEMENT
SITE PLAN
SO3 MITIGATION STRATEGY STUDY
EQUIPMENT ARRANGEMENT
MILL CREEK UNIT 4**

Sargent & Lundy

DRAWING NO.	REV.
C801 U4	08
SHEET	OF


REVISIONS

1	PLANS 1027W
2	REVISIONS
3	REVISIONS
4	REVISIONS
5	REVISIONS
6	REVISIONS
7	REVISIONS
8	REVISIONS
9	REVISIONS
10	REVISIONS
11	REVISIONS
12	REVISIONS
13	REVISIONS
14	REVISIONS
15	REVISIONS
16	REVISIONS
17	REVISIONS
18	REVISIONS
19	REVISIONS
20	REVISIONS
21	REVISIONS
22	REVISIONS
23	REVISIONS
24	REVISIONS
25	REVISIONS
26	REVISIONS
27	REVISIONS
28	REVISIONS
29	REVISIONS
30	REVISIONS
31	REVISIONS
32	REVISIONS
33	REVISIONS
34	REVISIONS
35	REVISIONS
36	REVISIONS
37	REVISIONS
38	REVISIONS
39	REVISIONS
40	REVISIONS
41	REVISIONS
42	REVISIONS
43	REVISIONS
44	REVISIONS
45	REVISIONS
46	REVISIONS
47	REVISIONS
48	REVISIONS
49	REVISIONS
50	REVISIONS




PLAN
SCALE: 1/8" = 1'-0"

<p>31725 - 1000 C</p>	<p>General Arrangement Cross Section "A-B" Looking North Precipitators & S.B.R.s.</p>	<p>31725</p>	<p>M201 U4 D</p>
-----------------------	---	--------------	------------------



PLAN




ELEVATION
"A-A"


NOTE: 1. SUPPORTS FOR NEW DUCT NOT SHOWN.

S03 MITIGATION STUDY EQUIPMENT ARRANGEMENT MILL CREEK PLANT UNIT 4			
		DRAWING NO. MILLGA04	REV. 0
SHEET OF			

MILL CREEK OPTION 1



PLAN



ELEVATION

SO3 MITIGATION STUDY
 EQUIPMENT ARRANGEMENT
 MILL CREEK PLANT UNIT 4




DRAWING NO.	REV.
MILLGA01	0
SHEET	OF



9: Drawings

Trimble County 1



NOTES:
 WORK THIS DRAWING WITH DRAWING TC-M10016
 FOR REFERENCE DRAWINGS SEE DRAWING
 TC-M10016

PLAN
 SCALE: 1/8" = 1'-0"

Sargent & Lundy


This drawing has been drawn by, or reproduced from, a drawing prepared by an organization other than Sargent & Lundy. Sargent & Lundy is not responsible for work by other organizations.

DRAWING RELEASE RECORD			
REV	DATE RELEASED	PURPOSE	PREPARED REVIEWED APPROVED
0A	12-14-05		N. PATEL G. SWITAK

Sargent & Lundy

GENERAL ARRANGEMENT SITE PLAN SO3 MITIGATION STRATEGY STUDY EQUIPMENT ARRANGEMENT TRIMBLE COUNTY UNIT 1		DRAWING NO. TRIS03GA01	REV. 0A
SHEET		OF	0A

27'-6" (J) 27'-2 1/2" (H) 13'-7 1/2" (G) 13'-7 1/2" (F) 13'-7 1/2" (E) 13'-7 1/2" (D) 13'-7 1/2" (C) 17'-5" (B) 30'-0" (A) 38'-0" (L) FOR CONTINUATION SEE TC-M10001




ELEVATION-LOOKING NORTH
 (DWG. TC-M10017)
 SCALE: 1/8" = 1'-0"

DRAWING RELEASE RECORD

REV	DATE RELEASED	PURPOSE	PREPARED	REVIEWED
0A	12-14-05		N. PATEL	G. SWITAK

**GENERAL ARRANGEMENT
 SITE PLAN
 S03 MITIGATION STRATEGY STUDY
 EQUIPMENT ARRANGEMENT
 TRIMBLE COUNTY UNIT 1**

TRI S03GA02
 SHEET 01 OF 01



ELEVATION
LOOKING WEST


FOR PLAN SEE DWG. TRIMBLEGA01

S03 MITIGATION STUDY
EQUIPMENT ARRANGEMENT
TRIMBLE COUNTY UNIT 1

Sargent & Lundy

DRAWING NO.	REV.
TRIMBLEGA02	0
SHEET	OF

TRIMBLE COUNTY UNIT 1




PLAN

FOR SECTION SEE DWG. TRIMBLEGA02



SO₂ MITIGATION STUDY
EQUIPMENT ARRANGEMENT
TRIMBLE COUNTY UNIT 1

Sargent & Lundy	
DRAWING NO.	REV.
TRIMBLEGA01	0
SHEET	OF




Equipment	QTY	HP	Power Source
First Field Recirc Water Pumps	3		480 MCC
Second Field Recirc Water Pumps	3		480 MCC
Third Field Recirc Water Pumps	3		480 MCC
Misting Recirc Water Pumps	3		480 MCC
Make-up Water Pumps	3		480 MCC
T/R Set	12	120KVA	480 Switchgear

Existing 6.9kV Swgr vertical sections, breakers relaying, current transformers, etc will need to be supplied as part of this estimate. All power and control cable to support the use of the 6.9kV Switchgear in the responsibility of this estimate. The 6.9kV switchgear is rated 500MVA and the additional breakers and vertical sections will need to meet these requirements.

Low voltage loads will be evenly across both 480V SWGR and MCC buses.

DRAWING RELEASE RECORD						SCALE	PROJECT NUMBER	PRELIMINARY LAYOUT TRIMBLE COUNTY UNIT 1 WET ESP SYSTEM	Sargent & Lundy ^{inc}	
REV	DATE	PREPARED	REVIEWED	APPROVED	PURPOSE				DWG CLASS:	REV.
0	12-09-05	BTC			RELEASED FOR PRELIMINARY LAYOUT	NONE	10584-022	SK-TC-WE-22	0	
								SHEET 1 OF 1		



Description	HP	units	QTY
Convey Air Blower Motor	250	hp	2
Blower Enclosure Fan Motor	10	hp	2
Hydraulic Duty Pump Motor	25	hp	1
Hydraulic Standby Motor	25	hp	1
Hydraulic Recirculation Pump Motor	10	hp	1
Dust Collector Fan Motor	10	hp	2
Dust Collector Rotary Feeder Motor	10	hp	1
Hydraulic Cooling Fan Motor	10	hp	1
Silo Screw Feeder Motor	25	hp	1
Weigh Bin Rotary Feeder Motor	10	hp	2
Airlock Rotary Feeder Motor	10	hp	2
Glycol Duty Pump Motor	25	hp	1
Glycol Standby Pump Motor	25	hp	1
Chiller Motor	10	hp	7
Desicant Wheel Reg Fan Motor	1	hp	2
Desicant Wheel Drive Motor	2	hp	2
Desicant Wheel React Heater	24	kw	2
Main Elevator Motor	50	hp	1
Transformer 480:208V Lighting/HVAC 3 phase	28	kva	1
Transformer 480:120/240V Control 1 phase	50	kva	1
HVAC Exhaust Fan Motor	7.5	hp	2
HVAC Supply Fan Motor	7.5	hp	2
HVAC Blower Heater	5	kw	4
HVAC Blower Heater	10	kw	4

DRAWING RELEASE RECORD						SCALE	PROJECT NUMBER	PRELIMINARY LAYOUT TRIMBLE COUNTY UNIT 1 SORBENT INJECTION SYSTEM	Sargent & Lundy ^{inc}	
REV	DATE	PREPARED	REVIEWED	APPROVED	PURPOSE				DWG CLASS:	REV.
0	12-09-05	BTC			RELEASED FOR PRELIMINARY LAYOUT	NONE	10584-022	SK-TC-SI-22	0	
								SHEET 1 OF 1		