

COMMONWEALTH OF KENTUCKY
BEFORE THE PUBLIC SERVICE COMMISSION

RECEIVED

JUL 23 2007

PUBLIC SERVICE
COMMISSION

In the matter of:

THE APPLICATION OF EAST KENTUCKY NETWORK)
LIMITED LIABILITY COMPANY FOR THE ISSUANCE)
OF A CERTIFICATE OF PUBLIC CONVENIENCE AND) CASE No 2007-00307
NECESSITY TO CONSTRUCT A TOWER IN ESTILL)
COUNTY, KENTUCKY).

In case number 91-002 East Kentucky Network, LLC, formerly Mountaineer Cellular Limited Liability Company was granted a Certificate of Public Convenience and Necessity by the Kentucky Public Service Commission to construct and operate a cellular radio telecommunications system for KY RSA 10.

In an effort to improve service in Estill County, East Kentucky Network, LLC Pursuant to KRS 278.020 Subsection 1 and 807 KAR 5:001 Section 9 is seeking the Commission's approval to construct a tower near on a ridge east of Drowning Creek which is a tributary of the Kentucky River, approximately four miles west of Irvine in Estill county, Kentucky. The proposed tower will be a 190' foot self-supporting tower located near the Estill / Madison county line. (37°42'13.3"N 84°04'19.5"W). A map and detailed directions to the site can be found in Exhibit 8.

East Kentucky Network LLC merger documents were filed with the Commission on February 2, 2001 in Case # 2001-022.

FAA and Kentucky Airport Zoning Commission approvals have been applied and these applications are enclosed as Exhibit 4 and 6.

No Federal Communications Commission approval is required prior to construction of this facility. Once service is established from this tower we must immediately notify the Federal Communications Commission of its operation. Prior approval is needed only if the proposed

facility increases the size of the cellular geographic service area. This cell site will not expand the cellular geographic service area.

A geologist was employed to determine soil and rock types and to ascertain the distance to solid bedrock. The geotechnical report is enclosed as Exhibit 3

A copy of the tower design information is enclosed as Exhibit 5. The proposed tower has been designed by engineers at Allstate Tower Inc of Henderson, Kentucky and will be constructed under their supervision. Their qualifications are evidenced in Exhibit 5 by the seal and signature of the registered professional engineer responsible for this project.

The tower will be erected by A & D Communication of Cattlesburg, Kentucky. A & D has vast experience in the erection of communications towers.

Enclosed, and should be filed with Exhibit 10 is a survey of the proposed tower site signed by a Kentucky registered professional engineer. There is no structure within 500 feet of the proposed tower as indicated in this enclosure. Exhibit 2 is a list of all Property owners or residents according to the property valuation administrator's record who reside or own property within 500 feet of the proposed tower in accordance with the Public Valuation Administrator'. No other properties are contiguous with East Kentucky's property.

Exhibit 12, back of folder, contains a vertical sketch of the tower supplied by Coleman Engineering.

Pursuant to 807 KAR5:063 Sections 1 (1)(L) and Section 1(1)(n)(1) all affected property owners according to the property valuation administrator's record who reside or own property within 500 feet of the proposed Tower were notified by certified mail return receipt requested of East Kentucky Network, LLC's proposed construction and informed of their right to intervene. They were given the docket number under which this application is filed. Enclosed in Exhibit 2 is a copy of that notification.

Estill County has no formal local planning unit. In absence of this unit the Estill County Judge Executive's office was notified by certified mail, return receipt requested of East Kentucky Network Limited Liability Company's proposal and informed of their right to intervene. They were given the docket number under which this application is filed. Enclosed in Exhibit 1 is a copy of that notification.

East Kentucky Network, LLC will finance the subject Construction with earned surplus in its General Fund.

Estimated Cost of Construction	140,000.00
Annual Operation Expense of Tower	12,500.00

Two notice signs meeting the requirements prescribed by 807 KAR 5:063, Section 1(2), measuring at least two (2) feet in height and four (4) feet in width and containing all required language in letters of required height, have been posted, one at a visible location on the proposed site and one on the nearest public road. The two signs were posted on July 20, 2007 and will remain posted for at least two weeks after filing of this application as specified.

Enclosed in Exhibit 9 is a copy of East Kentucky Network LLC's deeds to the site.

Notice of the location of the proposed construction was published on the last week of July and the first week of August in the Citizen Voice and Times. Enclosed is a copy of that notice in Exhibit 1. The Citizen Voice and Times is the newspaper with the largest circulation in Estill County.

The proposed construction site is on a very rugged mountaintop some feet from the nearest structure. Prior to construction the site was wooded.

Due to the steep hillside surrounding the proposed site, the property in close proximity is unsuitable for any type of development. East Kentucky Network LLC's operation will not affect the use of nearby land nor its value. No more suitable site exists in the area. A copy of the search area map is enclosed in Exhibit 8. No other tower capable of supporting East Kentucky Network LLC's load exists in the general area; therefore, there is no opportunity for co-location of our facilities with anyone else.

WHEREFORE, Applicant respectfully requests that the PSC accept the foregoing Application for filing, and having met the requirements of KRS [278.020(1), 278.650, and 278.665] and all applicable rules and regulations of the PSC, grant a Certificate of Public Convenience and Necessity to construct and operate the proposed tower.

The foregoing document was prepared by Janice Robinson, Technical Site Coordinator for East Kentucky Network d/b/a Appalachian Wireless. All related questions or correspondence concerning this filing should be mailed to East Kentucky Network, LLC d/b/a Appalachian Wireless, 101 Technology Trail, Ivel, KY 41642.

SUBMITTED BY: _____

Janice Robinson
Janice Robinson, Cell Site Coordinator

DATE: 07-20-07

APPROVED BY: _____

DATE: _____

Gerald Robinette, General Manager

Contacts:

Gerald Robinette, General Manager

Phone: (606) 791-2375, Ext. 111

Email: grobinette@ekn.com

Janice Robinson, Technical Site Coordinator

Phone: (606) 791-2375, Ext. 166

Email: jrobinson@ekn.com

Mailing Address:

**East Kentucky Network, LLC.
d/b/a Appalachian Wireless
101 Technology Trail
Ivel, KY 41642**

1	Notification/Response From County
2	Copies of Cell Site Notices.
3	Universal Letter of Soil Bearing Analysis
4	Kentucky Airport Zoning Commission Application.
5	Tower Design
6	FAA Approval/Notice of Proposed Construction.
7	Audited Financial Statements.
8	Driving directions and Map to Suitable Scale.
9	Deed/Lease Agreement for Proposed Site.
10	Survey of Site Signed/Sealed by Professional Engineer Registered in St. of Kentucky.
11	Site Survey Map with Property Owners identified in Accordance with PVA of County.
12	Vertical Profile Sketch of Proposed Tower.

EAST KENTUCKY NETWORK
101 TECHNOLOGY TRAIL
IVEL, KY 41642
PHONE: (606) 874-7550
FAX: (606) 874-7551
EMAIL: INFO@EKN.COM
WEBSITE: WWW.EKN.COM

EAST KENTUCKY
NETWORK



VIA: U.S. CERTIFIED MAIL

July 17, 2007

Wallace C. Taylor, Judge Executive
Estill County Court House
130 Main St., Room 102
Irvine, KY 40336

RE: Public Notice-Public Service Commission of Kentucky (Case No. 2007-00307)

East Kentucky Network, LLC d/b/a Appalachian Wireless has applied to the Public Service Commission of Kentucky for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide cellular telecommunications service. The facility will include a 190 foot self supporting tower with attached antennas extending upwards, and an equipment shelter located approximately four miles west of Irvine in Estill County, Kentucky (37°42'13.3"N 84°04'19.5"W). A map showing the location of the proposed new facility is enclosed. This notice is being sent to you because you are the present County Judge Executive of Estill County.



The Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. The Commission must receive your initial communication within 20 days of the date of this letter as shown above.

Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, P.O. Box 615, Frankfort, KY 40602. Please refer to Case No. 2007-00307 in your correspondence.

Sincerely,


Janice Robinson
Technical Site Coordinator
enclosure

Location Map



d/b/a Appalachian Wireless
101 TECHNOLOGY TRAIL
IVEL, KY 41642
Phone: 606/874-7550
Fax: 606/791-2225

EAST KENTUCKY
NETWORK



Fax

To: Citizens Voice & Times
P. O. box 660
Irvine, KY 40336

From: JANICE ROBINSON, Accounting
East Kentucky Network,
d/b/a Appalachian Wireless

Fax: 606-723-5161 **Phone:** 606-874-7550, Ext. 166

Phone: **Pages:** 1 Page (INCLUDING COVER)

Re: PUBLIC NOTICE ADVERTISEMENT **CC:**

Nancy,

We would like to have the following public notice printed in The Citizen Voice and Times for the next two weeks. The notice should state the following:

PUBLIC NOTICE:

RE: Public Service Commission of Kentucky (CASE NO. 2007-00187)

Notice is hereby given that East Kentucky Network, LLC, dba Appalachian Wireless has applied to the Kentucky Public Service Commission to construct a tower located on a ridge east of Drowning Creek which is a tributary of the Kentucky River, approximately four miles west of Irvine in Estill County, Kentucky (37°42'13.3" 84°04'19.5"). The proposed tower will be a 190-foot self-supporting tower. If you would like to respond to this notice, please contact the Executive Director, Public Service Commission, 211 Sower Boulevard, PO Box 615, Frankfort, Kentucky 40602. Please refer to Case No. 2007-00307.

If you have questions about the placement of the above mentioned notice, please call me at 606-874-7550, ext. 166.

Thank you, **Janice Robinson, Technical Site Coordinator**

Accounting Department If you have any problems with this fax, please call 606/886-6007. The message above and the information contained in the documents transmitted are confidential and intended only for the person(s) named above. Dissemination, distribution or copying of this communication by anyone other than the person(s) named above is prohibited. If you have received this communication in error, please notify us immediately by telephone and return the original message to us at the address listed above via regular mail. Thank you.

EXHIBIT II : LIST OF PROPERTY OWNERS:

WINSTON SITE, ESTILL COUNTY, KENTUCKY

Statement Pursuant to Section 1 (1) (I) 807 KAR 5:063

Section 1 (1)(I) 1. The following is a list of every property owner who according to property valuation administrator's records, owns property within 500 feet of the proposed tower and each have been: notified by certified mail, return receipt requested, of the proposed construction.,

Section 1 (1) I 2. : Every person listed below who, according to the property valuation administrator's records, owns property within 500 feet of the proposed tower has been: Given the Commission docket number under which the application will be processed: and

Section 1 (1) I 3. Every person listed below who, according to property valuation administrator's records, owns property within 500 feet of the proposed tower has been: Informed of his right to request intervention.

LIST OF PROPERTY OWNERS

Donald & Debbie Jordon
195 Strong Lane
Winston, KY 40495

Estill County Water District
76 Cedar Grove Road
Irvine, KY 40336

James & Mary Burgess
205 Burgess Lane
Winston, KY 40495

Timothy Harold Gould
95 Strong Lane
Winston, KY 40495

Bruce & Mia Newman
6025 Richmond Road
Irvine, KY 40336

Irvine Community Television
P O Box 186
Irvine, KY 40336

Wesley Rose
270 Winston Road
Irvine, KY 40336

EAST KENTUCKY NETWORK
101 TECHNOLOGY TRAIL
IRVINE, KY 41642
PHONE: (606) 874-7550
FAX: (606) 874-7551
EMAIL: INFO@EKN.COM
WEBSITE: WWW.EKN.COM

EAST KENTUCKY
NETWORK



VIA: U.S. CERTIFIED MAIL

(CASE NO. 2007-00307)

PUBLIC NOTICE

July 17, 2007

Wesley Rose
270 Winston Road
Irvine, KY 40336

RE: Public Notice-Public Service Commission of Kentucky (Case No. 2007-00307)

East Kentucky Network, LLC d/b/a Appalachian Wireless has applied to the Public Service Commission of Kentucky for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide cellular telecommunications service. The facility will include a 190 foot self-supporting tower with attached antennas extending upwards, and an equipment shelter located approximately four miles west of Irvine in Estill County, Kentucky (37°42'13.3"N 84°04'19.5"W). A map showing the location of the proposed new facility is enclosed. This notice is being sent to you because you own property or reside within a 500' radius of the proposed tower.

The Commission invites your comments regarding the proposed construction. You also have the right to *intervene in this matter*. The Commission must receive your initial communication within 20 days of the date of this letter as shown above.

Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, P.O. Box 615, Frankfort, KY 40602. Please refer to Case No. 2007-00307 in your correspondence.

Sincerely,

Janice Robinson
Technical Site Coordinator
Enclosure 1

EAST KENTUCKY NETWORK
101 TECHNOLOGY TRAIL
IRVINE, KY 41642
PHONE: (606) 874-7550
FAX: (606) 874-7551
EMAIL: INFO@EKN.COM
WEBSITE: WWW.EKN.COM

EAST KENTUCKY
NETWORK



VIA: U.S. CERTIFIED MAIL

(CASE NO. 2007-00307)

PUBLIC NOTICE

July 17, 2007

Irvine Community Television
P O Box 186
Irvine, KY 40336

RE: Public Notice-Public Service Commission of Kentucky (Case No. 2007-00307)

East Kentucky Network, LLC d/b/a Appalachian Wireless has applied to the Public Service Commission of Kentucky for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide cellular telecommunications service. The facility will include a 190 foot self supporting tower with attached antennas extending upwards, and an equipment shelter located approximately four miles west of Irvine in Estill County, Kentucky (37°42'13.3"N 84°04'19.5"W). A map showing the location of the proposed new facility is enclosed. This notice is being sent to you because you own property or reside within a 500' radius of the proposed tower.

The Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. The Commission must receive your initial communication within 20 days of the date of this letter as shown above.

Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, P.O. Box 615, Frankfort, KY 40602. Please refer to Case No. 2007-00307 in your correspondence.

Sincerely,

Janice Robinson
Technical Site Coordinator
Enclosure 1

EAST KENTUCKY NETWORK
101 TECHNOLOGY TRAIL
IVEL, KY 41642
PHONE: (606) 874-7550
FAX: (606) 874-7551
EMAIL: INFO@EKN.COM
WEBSITE: WWW.EKN.COM

EAST KENTUCKY
NETWORK



VIA: U.S. CERTIFIED MAIL

(CASE NO. 2007-00307)

PUBLIC NOTICE

July 17, 2007

Bruce & Mia Newman
6025 Richmond Road
Irvine, KY 40336

RE: Public Notice-Public Service Commission of Kentucky (Case No. 2007-00307)

East Kentucky Network, LLC d/b/a Appalachian Wireless has applied to the Public Service Commission of Kentucky for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide cellular telecommunications service. The facility will include a 190 foot self-supporting tower with attached antennas extending upwards, and an equipment shelter located approximately four miles west of Irvine in Estill County, Kentucky (37°42'13.3"N 84°04'19.5"W). A map showing the location of the proposed new facility is enclosed. This notice is being sent to you because you own property or reside within a 500' radius of the proposed tower.

The Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. The Commission must receive your initial communication within 20 days of the date of this letter as shown above.

Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, P.O. Box 615, Frankfort, KY 40602. Please refer to Case No. 2007-00307 in your correspondence.

Sincerely,

Janice Robinson
Technical Site Coordinator
Enclosure 1

EAST KENTUCKY NETWORK
101 TECHNOLOGY TRAIL
IRVINE, KY 41642
PHONE: (606) 874-7550
FAX: (606) 874-7551
EMAIL: INFO@EKN.COM
WEBSITE: WWW.EKN.COM

EAST KENTUCKY
NETWORK



VIA: U.S. CERTIFIED MAIL

(CASE NO. 2007-00307)

PUBLIC NOTICE

July 17, 2007

Timothy Harold Gould
95 Strong Lane
Winston, KY 40495

RE: Public Notice-Public Service Commission of Kentucky (Case No. 2007-00307)

East Kentucky Network, LLC d/b/a Appalachian Wireless has applied to the Public Service Commission of Kentucky for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide cellular telecommunications service. The facility will include a 190 foot self supporting tower with attached antennas extending upwards, and an equipment shelter located approximately four miles west of Irvine in Estill County, Kentucky (37°42'13.3"N 84°04'19.5"W). A map showing the location of the proposed new facility is enclosed. This notice is being sent to you because you own property or reside within a 500' radius of the proposed tower.

The Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. The Commission must receive your initial communication within 20 days of the date of this letter as shown above.

Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, P.O. Box 615, Frankfort, KY 40602. Please refer to Case No. 2007-00307 in your correspondence.

Sincerely,

Janice Robinson
Technical Site Coordinator
Enclosure 1

EAST KENTUCKY NETWORK
101 TECHNOLOGY TRAIL
IRVINE, KY 41642
PHONE: (606) 874-7550
FAX: (606) 874-7551
E: INFO@EKN.COM
WEBSITE: WWW.EKN.COM



VIA: U.S. CERTIFIED MAIL

(CASE NO. 2007-00307)

PUBLIC NOTICE

July 17, 2007

James & Mary Burgess
205 Burgess Lane
Irvine, KY 40495

RE: Public Notice-Public Service Commission of Kentucky (Case No. 2007-00307)

East Kentucky Network, LLC d/b/a Appalachian Wireless has applied to the Public Service Commission of Kentucky for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide cellular telecommunications service. The facility will include a 190 foot self supporting tower with attached antennas extending upwards, and an equipment shelter located approximately four miles west of Irvine in Estill County, Kentucky (37°42'13.3"N 84°04'19.5"W). A map showing the location of the proposed new facility is enclosed. This notice is being sent to you because you own property or reside within a 500' radius of the proposed tower.

The Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. The Commission must receive your initial communication within 20 days of the date of this letter as shown above.

Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, P.O. Box 615, Frankfort, KY 40602. Please refer to Case No. 2007-00307 in your correspondence.

Sincerely,

A handwritten signature in cursive script that reads "Janice Robinson".

Janice Robinson
Technical Site Coordinator
Enclosure 1

EAST KENTUCKY NETWORK
101 TECHNOLOGY TRAIL
IRVINE, KY 41642
PHONE: (606) 874-7550
FAX: (606) 874-7551
EMAIL: INFO@EKN.COM
WEBSITE: WWW.EKN.COM

EAST KENTUCKY
NETWORK



VIA: U.S. CERTIFIED MAIL

(CASE NO. 2007-00307)

PUBLIC NOTICE

July 17, 2007

Estill County Water District
76 Cedar Grove Road
Irvine, KY 40336


RE: Public Notice-Public Service Commission of Kentucky (Case No. 2007-00307)

East Kentucky Network, LLC d/b/a Appalachian Wireless has applied to the Public Service Commission of Kentucky for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide cellular telecommunications service. The facility will include a 190 foot self supporting tower with attached antennas extending upwards, and an equipment shelter located approximately four miles west of Irvine in Estill County, Kentucky (37°42'13.3"N 84°04'19.5"W). A map showing the location of the proposed new facility is enclosed. This notice is being sent to you because you own property or reside within a 500' radius of the proposed tower.

The Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. The Commission must receive your initial communication within 20 days of the date of this letter as shown above.

Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, P.O. Box 615, Frankfort, KY 40602. Please refer to Case No. 2007-00307 in your correspondence.

Sincerely,



Janice Robinson
Technical Site Coordinator
Enclosure 1

EAST KENTUCKY NETWORK
101 TECHNOLOGY TRAIL
IVEL, KY 41642
PHONE: (606) 874-7550
FAX: (606) 874-7551
EMAIL: INFO@EKN.COM
WEBSITE: WWW.EKN.COM

EAST KENTUCKY
NETWORK



VIA: U.S. CERTIFIED MAIL

(CASE NO. 2007-00307)

PUBLIC NOTICE

July 17, 2007

Donald & Debbie Jordon
195 Strong Lane
Winston, KY 40495

RE: Public Notice-Public Service Commission of Kentucky (Case No. 2007-00307)

East Kentucky Network, LLC d/b/a Appalachian Wireless has applied to the Public Service Commission of Kentucky for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide cellular telecommunications service. The facility will include a 190 foot self supporting tower with attached antennas extending upwards, and an equipment shelter located approximately four miles west of Irvine in Estill County, Kentucky (37°42'13.3"N 84°04'19.5"W). A map showing the location of the proposed new facility is enclosed. This notice is being sent to you because you own property or reside within a 500' radius of the proposed tower.

The Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. The Commission must receive your initial communication within 20 days of the date of this letter as shown above.

Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, P.O. Box 615, Frankfort, KY 40602. Please refer to Case No. 2007-00307 in your correspondence.

Sincerely,

Janice Robinson
Technical Site Coordinator
Enclosure 1

WENDELL R. HOLMES, P.G.
120 Church Street
Whitesburg, KY 41858
(606) 633-1511

June 28, 2007

Winston Tower Site

Purpose:

A site assessment was conducted for Appalachian Wireless on a tract of land located in Estill County near Winston, Kentucky. The site of the proposed tower is now forestland. The purpose of this investigation was to determine the depth to bedrock and of what type of rock the bedrock consists.

Site Investigation:

The trenching method was used to determine the type of bedrock material at the proposed tower site. A Case bobcat was used to expose the bedrock material. It is approximately 3.00 feet to the shale bedrock. (See attached page for descriptions of materials encountered.)

The terrain in Estill County is slightly to moderately steep. The tower site is located on a ridge east of Drowning Creek which is a tributary of the Kentucky River, approximately four miles west of Irvine in Estill County, near the Estill / Madison County line. The shale formation below the tower site is approximately 20.00 feet thick based on the information obtained from the site investigation and geological maps of the area.

Conclusions:

The proposed tower site is located on a ridge in the area. The shale bedrock on the proposed tower site is part of the New Albany Shale Formation, and is upper to middle Devonian in age. Tests were not conducted to determine the load-bearing strength of the bedrock. However, it is apparent that the tower will be constructed on the shale bedrock formation.

The field work for this site was performed by Wendell R. Holmes, using generally accepted methods in the practice of geological science.

Wendell R. Holmes, P.G.
Registered Professional Geologist
Kentucky Board of Registration for Professional Geologists



WENDELL R. HOLMES, P.G.

**120 Church Street
Apartment 3
Whitesburg, Ky. 41858**

Geologist Log

Location: Winston Tower Site

Unit Thickness	Total depth	Strata	Description
3.00'	3.00'	Soil	Brown and Black, Shale Fragments
20.00'	23.00'	Shale	Brown and Dark Gray

Kentucky Transportation Cabinet, Kentucky Airport Zoning Commission. 200 Mero Street, Frankfort, KY 40622

Kentucky Aeronautical Study Number

APPLICATION FOR PERMIT TO CONSTRUCT OR ALTER A STRUCTURE
INSTRUCTIONS INCLUDED

1 APPLICANT -- Name, Address, Telephone, Fax, etc
East Kentucky Network, LLC
c/o Lukas, Nace, Gutierrez & Sachs, Chtd
1650 Tysons Blvd, Suite 1500
McLean, VA 22102
T: 703-584-8667 F: 703-584-8692

2 Representative of Applicant -- Name, Address, Telephone, Fax
Ali Kuzehkanani
Lukas, Nace, Gutierrez & Sachs, Chtd
1650 Tysons Blvd, Suite 1500
McLean, VA 22102
T: 703-584-8667 F: 703-584-8692

3 Application for: New Construction Alteration Existing
4 Duration: Permanent Temporary (Months _____ Days _____)
5 Work Schedule: Start 7/30/2007 End 8/5/2007
6 Type: Antenna Tower Crane Building Power Line
 Landfill Water Tank Other _____
7 Marking/Painting and/or Lighting Preferred:
Red Lights and Paint Dual - Red & Medium Intensity White
 White - Medium Intensity Dual - Red & High Intensity White
 White - High Intensity Other NONE
8. FAA Aeronautical Study Number _____

9 Latitude: 37 ° 42 ' 13 " 3 "
10 Longitude: 84 ° 04 ' 19 " 5 "
11 Datum: NAD83 NAD27 Other _____
12 Nearest Kentucky City: Winston County Estill
13 Nearest Kentucky public use or Military airport:
Madison Airport
14 Distance from #13 to Structure: 24.3 kilometers
15 Direction from #13 to Structure: ENE
16 Site Elevation (AMSL): 985.00 Feet
17 Total Structure Height (AGL): 190.00 Feet
18 Overall Height (#16 + #17) (AMSL): 1,175.00 Feet
19 Previous FAA and/or Kentucky Aeronautical Study Number(s):

20 Description of Location: (Attach USGS 7.5 minute Quadrangle Map or an Airport layout Drawing with the precise site marked and any certified survey)
Site is located approx 0.6 mi (1.0 km) east of Winston (Estill), KY

21. Description of Proposal:
The structure will include a 180' tower with top-mounted cellular antennas (overall height of 190' AGL). The ERP will be 500 watts.



22 Has a "NOTICE OF CONSTRUCTION OR ALTERATION" (FAA Form 7460-1) been filed with the Federal Aviation Administration?
 No Yes, When July 05, 2007

CERTIFICATION: I hereby certify that all the above statements made by me are true, complete and correct to the best of my knowledge and belief
Ali Kuzehkanani/Dir of Eng Ali Kuzehkanani 7/8/2007
Printed Name and Title Signature Date

PENALTIES: Persons failing to comply with Kentucky Revised Statutes (KRS 183.861 through 183.990) and Kentucky Administrative Regulations (602 KAR 050:Series) are liable for fines and/or imprisonment as set forth in KRS 183.990(3). Non-compliance with Federal Aviation Administration Regulations may result in further penalties.


Commission Action: Chairman, KAZC Administrator, KAZC
 Approved _____ Date _____
 Disapproved _____

LEG DIA.	Ø3.25"	Ø3.25"	Ø2.75"	Ø2.75"	Ø2.5"	Ø2.5"	Ø2.25"	Ø2.25"	Ø1.75"
DIAGONALS	L2.5" x .1875"	L2" x .1875"							
GIRTS			N/A						A
BRACE BOLTS	Ø.75"	Ø.625"						Ø.5"	
FLANGE BOLTS	Ø1"							Ø.75"	
# OF BAYS	3 BAY : X-BRACED	4 BAY : X-BRACED							




PLAN VIEW REF.:
 1) (6) FEEDLINES
 2) STEP BOLTS

SYMBOL LIST: A) L1.75" x .125"	
BASE REACTIONS:	
TOTAL SHEAR =	17 KIPS
AXIAL LOAD =	28 KIPS
UPLIFT / LEG =	137 KIPS
COMP. / LEG =	155 KIPS
O.T. MOMENT =	1881 FT-K



DESIGN NOTES:
 1) ALL LEGS ARE SOLID ROUND ASTM A-572 GRADE : $F_y \geq 50$ KSI.
 2) ALL BRACE MATERIAL IS ASTM A-36 : $F_y \geq 36$ KSI.
 3) ALL BRACE AND FLANGE BOLTS ARE A325-X.
 4) (6) Ø1.125" x 6'-0" LONG A-36 ANCHOR BOLTS PER LEG.
 5) TOWER IS DESIGNED FOR A 70 MPH BASIC WIND SPEED IN ACCORDANCE WITH THE TIA/EIA-222-F STANDARD INCLUDING A 0.5" OF RADIAL ICE.

ELEV.	ANTENNA	FEEDLINE
180'	(12) 4' x 1' CELLULAR PANELS	(12) 1.625"
170'	(12) 4' x 1' CELLULAR PANELS	(12) 1.625"
160'	(12) 4' x 1' CELLULAR PANELS	(12) 1.625"
--- STEP BOLTS UTILIZED FOR CLIMBING WITH SAFETY CLIMB DEVICE. --- SEE PLAN VIEW FOR FEEDLINE DISTRIBUTION.		




P.O. BOX 25
 HENDERSON, KY 42419
 PHONE: (270) 533-6000
 FAX: (270) 533-6888

SCALE: N.T.S.	PROPRIETARY STATEMENT: THIS DRAWING IS THE PROPERTY OF ALLSTATE TOWER CO. IT IS NOT TO BE REPRODUCED OR COPIED IN ANYWAY WITHOUT PRIOR WRITTEN CONSENT OF ALLSTATE TOWER CO.
TOLERANCE BANDS: ALL DIMENSIONS ARE ±1/16" ALL ANGULAR DIM ARE ±1/2° UNLESS OTHERWISE NOTED	CUSTOMER: APPALACHIAN WIRELESS
APPROX. WEIGHT 15.88 KIPS	DESCRIPTION: 180' SELF SUPPORT TOWER
	LOCATION: ESTILL COUNTY, KY.
	SITE: WINSTON
	PROPOSAL #: AB1444-REV 1 - SELF SUPPORT
	DRAWN BY: J.B.
	DATE: 06/05/2007
	REV: REV. NO.
	REV. DATE: REV. DATE
	JOB NO. SHEET
	AF40782 A


REINFORCEMENT BAR MAT

CENTER OF TOWER AND FOUNDATION




PLAN VIEW

TOTAL VOLUME OF CONCRETE = 32-3/4 YD³



SECTION A-A



DETAIL "A"

(6) $\phi 1-1/8"$ X 6'-0" OVERALL LENGTH ANCHOR BOLTS W/ $3/4"$ THK BEARING PLATE AT THE BOTTOM OF THE ANCHOR BOLT CLUSTER (5' MIN. ANCHOR BOLT EMBEDMENT).

USE EPOXY BONDING AGENT WHEN POURED SEPARATELY

(8) #7 VERTICAL BARS W/ #4 TIES AT 12" ON CENTER

(26) #7 HORIZONTAL BARS X 22'-6" LONG EQUALLY SPACED EACH WAY AT TOP AND BOTTOM OF MAT. (TOTAL = 104)


REINFORCEMENT BAR SPlicing:

- ALL LAP SPICES SHALL CONFORM TO ACI 318 REQUIREMENTS.
- REFER TO CHART BELOW WHEN REINFORCEMENT BAR SPlicing IS NECESSARY.

REINFORCING BAR SIZE	LAP SPlice LENGTH
3	15"
4	17"
5	21"
6	26"
7	30"
8	36"
9	46"
10	58"
11	71"

FOUNDATION INSTALLATION/DESIGN NOTES:

- THIS FOUNDATION IS DESIGNED TO MEET ALL STANDARDS SET FORTH BY ACI 318: AMERICAN CONCRETE INSTITUTE, BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE, ANSI/TIA/EIA 222-F: STRUCTURAL STANDARDS FOR STEEL ANTENNA TOWERS AND ANTENNA SUPPORTING STRUCTURES. THIS FOUNDATION IS DESIGNED UTILIZING THE GEOTECHNICAL REPORT PERFORMED BY WENDELL R. HOLMES, P.G.; DATED 6-28-07. THE FOUNDATION CONTRACTOR SHALL INSTALL THE FOUNDATIONS IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE GEOTECHNICAL REPORT.
- ALL WORK PERFORMED FROM THESE DRAWINGS SHOULD BE BY QUALIFIED CONTRACTORS EXPERIENCED IN TOWER FOUNDATION CONSTRUCTION.
- ALL FOOTING EXCAVATIONS SHALL BE MANUALLY CLEANED PRIOR TO PLACING CONCRETE. COMPACT THE EXPOSED SOIL SURFACE AND ANY GRANULAR FILL UNDER THE FOUNDATION TO 95% OF THE MODIFIED PROCTOR DENSITY. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI AFTER 28 DAYS. COPIES OF THE CONCRETE CYLINDER TEST REPORTS SHALL BE SENT TO THE RESIDENT ENGINEER / INSPECTOR.
- MINIMUM CONCRETE COVER FOR REINFORCING BARS SHALL BE 3". FIELD BENDING OR WELDING OF REINFORCEMENT BARS IS NOT PERMITTED. PROVIDE CHAMFERS AT ALL EXPOSED CORNERS OF CONCRETE.
- BACKFILL NEAR AND AROUND THE FOUNDATIONS SHALL BE A WELL GRADED FILL MATERIAL PLACED IN 8" THICK LAYERS THAT HAS BEEN COMPACTED TO 95% OF THE MODIFIED PROCTOR DENSITY PER ASTM D1557.
- SOME DETAIL HAS BEEN PURPOSELY OMITTED TO CLARIFY ILLUSTRATION.



P.O. BOX 25
HENDERSON, KY 42419
PHONE: (270) 830-8512
FAX: (270) 830-8475

SCALE:

N.T.S.

TOLERANCE BANDS
ALL DIMENSIONS
ARE $\pm 1/16"$
ALL ANGULAR DIM
ARE $\pm 1/2"$ UNLESS
OTHERWISE NOTED

APPROX. WEIGHT
N/A

PROPRIETARY STATEMENT: THIS DRAWING IS THE PROPERTY OF ALLSTATE TOWER CO. IT IS NOT TO BE REPRODUCED OR COPIED IN ANYWAY WITHOUT PRIOR WRITTEN CONSENT OF ALLSTATE TOWER CO.

CUSTOMER: APPALACHIAN WIRELESS

DESCRIPTION: PAD/PIER FOUNDATION DESIGN

LOCATION: ESTILL COUNTY, KY.

SITE: WINSTON

PROPOSAL #
AB1444-REV 1 - SELF SUPPORT

DRAWN BY: J.B.

DATE: 07/05/2007

REV. NO.

REV. DATE:

JOB NO.

AF40782

SHEET

B

LUKAS, NACE, GUTIERREZ & SACHS

ARTERED

1050 TYSONS BOULEVARD, SUITE 1500
MCLEAN, VIRGINIA 22102
703 584 8678 • 703 584 8696 FAX

WWW.FCCLAW.COM

RUSSELL D. LUKAS
DAVID L. NACE
THOMAS GUTIERREZ*
ELIZABETH R. SACHS*
GEORGE L. LYON, JR.
PAMELA L. GIST
DAVID A. LAFURIA
B. LYNN F. RATNAVALE*
TODD SLAMOWITZ*
STEVEN M. CHERNOFF*

CONSULTING ENGINEERS
ALI KUZEHKANANI
LEILA REZANAVAZ
OF COUNSEL
JOHN J. MCAVOY*
J. K. HAGE III*
LEONARD S. KOLSKY*
HON. GERALD S. MCGOWAN*
TAMARA DAVIS-BROWN*

*NOT ADMITTED IN VA

Writers Direct Dial
(703) 584-8667
akuzehkanani@fcclaw.com

July 5, 2007

Via U.S. Mail

EXPRESS PROCESSING CENTER
Federal Aviation Administration
Southwest Regional Office
Air Traffic Airspace Branch, ASW-520
2601 Meacham Blvd.
Fort Worth, TX 76137-4298

Dear FAA Evaluator:


Enclosed is an FAA Form 7460-1 (Notice of Proposed Construction or Alteration) for a new 190' communications tower structure (180' tower plus 10' antenna/lightning rod) near Winston (Estill), Kentucky. The site ("Winston") is approximately 0.6 mi (1.0 kilometer) east of the town Winston.

The proponent, East Kentucky Network, LLC, is the licensee for Cellular Block B service in Kentucky 10 - Powell Rural Service Area (KY10B RSA), Market No. 452B. Transmit technology to be employed at this station is CDMA in the Cellular Band B frequency band (880 - 890 MHz and 891 - 894 MHz); the maximum ERP is 500 Watts.

The transmitting systems at this site will be installed and maintained such that transmitter spurious radiation in the frequency range of 118 MHz to 137 MHz is attenuated at least 71 dB below the unmodulated carrier level.

Should you have any questions or require additional information, please do not hesitate to call the undersigned at the above identified telephone number.

Sincerely,



Ali Kuzehkanani
Director of Engineering

Enclosure

cc: East Kentucky Network, LLC
Attention: Marty Thacker and Gerald Robinett

Notice of Proposed Construction or Alteration (7460-1)

Project Name: EAST -000071170-07

Sponsor: East Kentucky Network, LLC

Details for Case : Winston

Show Project Summary

Case Status

ASN: 2007-ASO-3464-OE

Status: Accepted

Date Accepted: 07/05/2007

Date Determined:

Letters: None

Construction / Alteration Information

Notice Of: Construction

Duration: Permanent

if Temporary: Months: Days:

Work Schedule - Start: 07/30/2007

Work Schedule - End: 08/05/2007

State Filing: Filed with State

Structure Summary

Structure Type: Antenna Tower

Structure Name: Winston

FCC Number:

Prior ASN:

Structure Details

Latitude: 37° 42' 13.3" N

Longitude: 84° 4' 19.5" W

Horizontal Datum: NAD83

Site Elevation (SE): 985 (nearest foot)

Structure Height (AGL): 190 (nearest foot)

Marking/Lighting: None

Other :

Nearest City: Winston

Nearest State: Kentucky

Traverseway: No Traverseway



Description of Location: Site is located approx. 0.6 mi (1.0 km) east of Winston (Estill), KY

Description of Proposal: A new 180-foot tower with top-mounted antennas for an overall height of 190 feet (ERP of 500w).

Common Frequency Bands

Low Freq	High Freq	Freq Unit	ERP	ERP Unit
806	824	MHz	500	W
824	849	MHz	500	W
851	866	MHz	500	W
869	894	MHz	500	W
896	901	MHz	500	W

Specific Frequencies



37° 42' 13"N, 84° 04' 20"W (NAD83/WGS84)

USGS Panola (KY) Quadrangle

Projection is UTM Zone 16 NAD83 Datum

Magnetic
and
geographic
declination
from UTM
grid for
this topo
map.

**EAST KENTUCKY NETWORK, LLC
DBA APPALACHIAN WIRELESS**

FINANCIAL REPORT

December 31, 2006

CONTENTS

	Page
INDEPENDENT AUDITOR'S REPORT ON THE FINANCIAL STATEMENTS	1
FINANCIAL STATEMENTS	
Balance sheets	2
Statements of income	3
Statements of members' equity	4
Statements of cash flows	5-6
Notes to financial statements	7-13
INDEPENDENT AUDITOR'S REPORT ON THE SUPPLEMENTARY INFORMATION	14
SUPPLEMENTARY INFORMATION	
Statement of income detail	15 and 16

INDEPENDENT AUDITOR'S REPORT

To the Members
East Kentucky Network, LLC
dba Appalachian Wireless
Ivel, Kentucky 41642

We have audited the accompanying balance sheets of East Kentucky Network, LLC, dba Appalachian Wireless as of December 31, 2006 and 2005 and the related statements of income, members' equity and cash flows for the years then ended. These financial statements are the responsibility of the Company's management. Our responsibility is to express an opinion on these financial statements based on our audits.

We conducted our audits in accordance with auditing standards generally accepted in the United States of America. Those standards require that we plan and perform the audit to obtain reasonable assurance about whether the financial statements are free of material misstatement. An audit includes examining, on a test basis, evidence supporting the amounts and disclosures in the financial statements. An audit also includes assessing the accounting principles used and significant estimates made by management, as well as evaluating the overall financial statement presentation. We believe that our audits provide a reasonable basis for our opinion.

In our opinion, the financial statements referred to above present fairly, in all material respects, the financial position of East Kentucky Network, LLC, dba Appalachian Wireless as of December 31, 2006 and 2005 and the results of its operations and its cash flows for the years then ended in conformity with accounting principles generally accepted in the United States of America.

Jones, Nale & Mattingly, P.C.

Louisville, Kentucky
March 15, 2007

**EAST KENTUCKY NETWORK, LLC
DBA APPALACHIAN WIRELESS**

**BALANCE SHEETS
December 31, 2006 and 2005**

ASSETS	<u>2006</u>	<u>2005</u>
CURRENT ASSETS		
Cash and cash equivalents	\$ 2,818,346	\$ 1,046,669
Short-term investments	46,271	43,803
Accounts receivable, less allowance for doubtful accounts of \$567,790 in 2006 and \$375,856 in 2005	2,802,673	1,560,267
Accounts receivable, members (Notes 5 and 6)	37,612	3,149
USF receivable (Note 7)	--	589,913
Inventory	1,584,039	1,056,766
Prepaid expenses	<u>173,657</u>	<u>143,547</u>
Total current assets	<u>\$ 7,462,598</u>	<u>\$ 4,444,114</u>
 PROPERTY, PLANT AND EQUIPMENT (Note 3)		
Plant in service:		
General support	\$ 18,914,927	\$ 10,633,736
MTSO equipment	13,354,875	11,934,434
Cell equipment	39,339,797	34,785,982
Paging equipment	3,321,068	3,320,416
Fiber ring	6,471,128	6,245,412
Unfinished plant	<u>657,524</u>	<u>3,992,696</u>
	\$ 82,059,319	\$ 70,912,676
Less accumulated depreciation	<u>33,358,066</u>	<u>27,810,940</u>
	<u>\$ 48,701,253</u>	<u>\$ 43,101,736</u>
 OTHER ASSETS		
Investment in affiliated company, RTFC (Note 3)	\$ 862,394	\$ 875,133
Intangible assets, net of accumulated amortization of \$2,646,913 in 2006 and \$2,179,654 in 2005 (Note 2)	4,497,032	4,623,855
Other	<u>27,550</u>	<u>28,669</u>
	<u>\$ 5,386,976</u>	<u>\$ 5,527,657</u>
	<u>\$ 61,550,827</u>	<u>\$ 53,073,507</u>

The Notes to Financial Statements are an integral part of these statements.

LIABILITIES AND MEMBERS' EQUITY	<u>2006</u>	<u>2005</u>
CURRENT LIABILITIES		
Current maturities of long-term debt (Note 3)	\$ 1,200,000	\$ 48,033
Accounts payable	1,166,909	851,643
Accounts payable, member (Notes 5 and 6)	2,899	2,936
Accrued expenses	2,113,530	1,457,463
Accrued state corporation taxes	232,157	85,989
Customer deposits	317,603	291,380
Total current liabilities	<u>\$ 5,033,098</u>	<u>\$ 2,737,444</u>
 LONG-TERM DEBT, less current maturities (Note 3)	 13,000,000	 13,297,220
MEMBERS' EQUITY	43,517,729	37,038,843
	 <u><u>\$ 61,550,827</u></u>	 <u><u>\$ 53,073,507</u></u>

**EAST KENTUCKY NETWORK, LLC
DBA APPALACHIAN WIRELESS**

**STATEMENTS OF INCOME
Years Ended December 31, 2006 and 2005**

	2006	2005
REVENUE		
Retail	\$ 24,156,320	\$ 20,908,570
Roamer	6,964,309	6,868,904
Long distance	155,046	177,350
Paging	852,011	1,039,429
Equipment sales, cellular	2,922,817	2,152,962
Equipment sales, paging	27,894	57,632
Other	3,065,078	2,359,809
Total revenue	\$ 38,143,475	\$ 33,564,656
EXPENSES		
Cost of cellular service	\$ 7,888,446	\$ 7,924,553
Cost of paging service	411,177	510,665
Cost of equipment sales, cellular	6,813,457	4,912,998
Cost of equipment sales, paging	58,755	78,428
Customer service	1,330,573	1,208,726
Billing	1,097,834	1,200,135
Selling	2,703,570	2,131,009
Maintenance	1,267,034	1,042,844
Utilities	454,008	354,870
Bad debts	800,268	672,263
Recovery of bad debts	(90,925)	(120,673)
Cell site rental	158,500	135,012
Taxes	565,271	257,247
Advertising	1,574,298	1,139,697
General and administrative	2,238,348	2,249,226
Occupancy	334,981	359,928
Depreciation	5,541,628	4,635,200
Amortization	508,526	495,241
Total expenses	\$ 33,655,749	\$ 29,187,369
Income from operations	\$ 4,487,726	\$ 4,377,287
OTHER INCOME (EXPENSE)		
Interest income	\$ 49,052	\$ 23,915
Interest expense	(821,277)	(795,898)
Universal Service Fund income (Note 7)	3,716,602	589,913
Impairment of goodwill (Note 8)	--	(331,286)
	\$ 2,944,377	\$ (513,356)
Income before taxes	\$ 7,432,103	\$ 3,863,931
Kentucky corporation tax expense	399,157	170,197
Net income	\$ 7,032,946	\$ 3,693,734

The Notes to Financial Statements are an integral part of these statements.

**EAST KENTUCKY NETWORK, LLC
DBA APPALACHIAN WIRELESS**

**STATEMENTS OF MEMBERS' EQUITY
Years Ended December 31, 2006 and 2005**

	Cellular Services, Inc.	Gearhart Communi- cations Company, Inc.	Mountain Tele- communi- cations, Inc.	Thacker- Grigsby Telephone Co., Inc.	Peoples Rural Telephone Coop- erative Corp- oration, Inc.	Total
Balance, January 1, 2005	\$ 6,781,309	\$ 6,781,309	\$ 6,781,309	\$ 6,781,309	\$ 6,781,308	\$33,906,544
Net income	738,747	738,747	738,747	738,746	738,747	3,693,734
Capital distributions	<u>(112,287)</u>	<u>(112,287)</u>	<u>(112,287)</u>	<u>(112,287)</u>	<u>(112,287)</u>	<u>(561,435)</u>
Balance, December 31, 2005	\$ 7,407,769	\$ 7,407,769	\$ 7,407,769	\$ 7,407,768	\$ 7,407,768	\$37,038,843
Net income	1,406,589	1,406,589	1,406,589	1,406,590	1,406,589	7,032,946
Capital distributions	<u>(110,812)</u>	<u>(110,812)</u>	<u>(110,812)</u>	<u>(110,812)</u>	<u>(110,812)</u>	<u>(554,060)</u>
Balance, December 31, 2006	<u>\$ 8,703,546</u>	<u>\$ 8,703,546</u>	<u>\$ 8,703,546</u>	<u>\$ 8,703,546</u>	<u>\$ 8,703,545</u>	<u>\$43,517,729</u>

The Notes to Financial Statements are an integral part of these statements.

**EAST KENTUCKY NETWORK, LLC
DBA APPALACHIAN WIRELESS**

**STATEMENTS OF CASH FLOWS
Years Ended December 31, 2006 and 2005**

	2006	2005
CASH FLOWS FROM OPERATING ACTIVITIES		
Net income	\$ 7,032,946	\$ 3,693,734
Adjustments to reconcile net income to net cash provided by operating activities:		
Depreciation	5,541,628	4,635,200
Amortization	508,526	495,241
Impairment of goodwill	--	331,286
Changes in assets and liabilities, net of the effects of investing and financing activities:		
(Increase) in accounts receivable	(1,242,406)	(78,367)
Decrease in accounts receivable, members	(34,463)	51,248
(Increase) decrease in USF receivable	589,913	(589,913)
(Increase) in inventory	(527,273)	(230,130)
(Increase) decrease in prepaid expenses	(30,110)	5,012
(Increase) decrease in other assets	13,858	(646)
Increase (decrease) in accounts payable	315,266	(291,123)
Increase (decrease) in accounts payable, member	(37)	2,332
Increase in accrued expenses	656,067	339,038
Increase in accrued state corporation taxes	146,168	85,989
Increase in customer deposits	26,223	139,030
Net cash provided by operating activities	\$ 12,996,306	\$ 8,587,931
CASH FLOWS FROM INVESTING ACTIVITIES		
Purchase of property, plant and equipment	\$ (11,182,411)	\$ (11,469,668)
Purchase of intangible assets	(340,437)	(299,159)
Proceeds from sale of short-term investments	(2,468)	56,197
Net cash (used in) investing activities	\$ (11,525,316)	\$ (11,712,630)
CASH FLOWS FROM FINANCING ACTIVITIES		
Capital distributions	\$ (554,060)	\$ (561,435)
Proceeds from long-term borrowings	14,200,000	3,450,000
Payments on long-term borrowings	(13,345,253)	(832,731)
Net cash provided by financing activities	\$ 300,687	\$ 2,055,834
Net increase (decrease) in cash and cash equivalents	\$ 1,771,677	\$ (1,068,865)
Cash and cash equivalents:		
Beginning	1,046,669	2,115,534
Ending	\$ 2,818,346	\$ 1,046,669

The Notes to Financial Statements are an integral part of these statements.

EAST KENTUCKY NETWORK, LLC
DBA APPALACHIAN WIRELESS

STATEMENTS OF CASH FLOWS (Continued)
Years Ended December 31, 2006 and 2005

	<u>2006</u>	<u>2005</u>
SUPPLEMENTAL DISCLOSURE OF CASH FLOW INFORMATION		
Cash payments for interest	<u>\$ 866,941</u>	<u>\$ 788,610</u>
Cash payments for state corporation taxes	<u>\$ 167,000</u>	<u>\$ 84,207</u>
SUPPLEMENTAL SCHEDULE OF NONCASH INVESTING AND FINANCING ACTIVITIES		
Settlement of note payable from impairment of goodwill	<u>\$ --</u>	<u>\$ 400,000</u>
Settlement of accrued interest from impairment of goodwill	<u>\$ --</u>	<u>\$ 56,000</u>

The Notes to Financial Statements are an integral part of these statements.

EAST KENTUCKY NETWORK, LLC
DBA APPALACHIAN WIRELESS

NOTES TO FINANCIAL STATEMENTS

Note 1. Summary of Significant Accounting Policies

Nature of operations

East Kentucky Network, LLC, dba Appalachian Wireless, is a Kentucky limited liability company formed by the merger of Appalachian Cellular, LLC, Mountaineer Cellular, LLC and East Kentucky Network, LLC on January 1, 2000. The Company is engaged in cellular telephone communications and paging services to residential and commercial customers located in eastern Kentucky. The Company's five members consist of Cellular Services, Inc.; Gearheart Communications Company, Inc.; Mountain Telecommunications, Inc.; Peoples Rural Telephone Cooperative Corporation, Inc.; and Thacker-Grigsby Telephone Co., Inc.

Cash

The Company maintains its cash balances, which exceed the \$100,000 federally insured limit, with several financial institutions. These financial institutions have strong credit ratings and management believes that credit risk related to the accounts is minimal.

Cash equivalents

For purposes of the statement of cash flows, the Company considers temporary investments having a maturity of three months or less to be cash equivalents.

Short-term investments

Certificates of deposit having original maturities between three and nine months are classified as short-term investments, are carried at cost, which approximates fair value, and are held to maturity.

Inventory

Inventory is composed of cellular telephone equipment, paging equipment, and accessories purchased for resale during the ordinary course of business. The inventory is valued at the lower of cost or market, cost being determined by the first-in, first-out (FIFO) method.

Property, plant and equipment

Property, plant and equipment are recorded at cost. Depreciation is provided using the straight-line method over the estimated useful lives of the assets.

Investment

The investment in affiliated company is composed of equity certificates in Rural Telephone Finance Cooperative and is reported at cost, which approximates fair value.

NOTES TO FINANCIAL STATEMENTS

Note 1. Summary of Significant Accounting Policies (Continued)

Intangible assets

The customer lists, non-compete agreements, FCC licenses, and use of name are recorded at cost and are being amortized over 15 years by the straight-line method. The excess cost over the fair value of the net assets acquired (goodwill) related to paging acquisitions is measured for impairment on an annual basis, and written down, if necessary, to its estimated value at that time. During the prior year, the Company expensed the remaining balance of goodwill as an impairment (see Note 8).

Recognition of revenue

Cellular service and paging revenues are recognized when earned. Monthly access and feature charges are billed one month in advance and recognized as revenue the following month. Revenue from telephone and accessories sold are recognized as revenue upon delivery to the customer.

Advertising

Advertising costs are expensed as incurred. At December 31, 2006 and 2005, these costs were \$1,574,298 and \$1,139,697, respectively.

Income taxes

Under existing provisions of the Internal Revenue Code, the income or loss of a limited liability company is recognized by the members for income tax purposes. Accordingly, no provision for federal income taxes has been provided for in the accompanying financial statements. Effective for years beginning on or after January 1, 2005, the State of Kentucky enacted legislation which now provides for the taxation of limited liability companies' at the entity level. The accompanying financial statements include the related state tax liability under the new regulations.

Use of estimates

Management uses estimates and assumptions in preparing financial statements. Those estimates and assumptions affect the reported amounts of assets and liabilities, the disclosure of contingent assets and liabilities, and the reported revenues and expenses.

NOTES TO FINANCIAL STATEMENTS

Note 2. Intangible Assets

Intangible assets consist of the following at December 31, 2006:

	Gross Amount	Accumulated Amortization
Customer lists	\$ 5,363,530	\$ (2,152,951)
Non-compete agreements	220,348	(121,577)
FCC licenses	1,141,593	(330,542)
Use of name	10,000	(4,334)
Other	408,474	(37,509)
	\$ 7,143,945	\$ (2,646,913)

Intangible assets consist of the following at December 31, 2005:

	Gross Amount	Accumulated Amortization
Customer lists	\$ 5,363,530	\$ (1,795,634)
Non-compete agreements	220,348	(106,898)
FCC licenses	1,141,593	(264,446)
Use of name	10,000	(3,668)
Other	68,038	(9,008)
	\$ 6,803,509	\$ (2,179,654)

Aggregate amortization expense related to these intangible assets for the years ended December 31, 2006 and 2005 totaled \$467,259 and \$437,982, respectively. The following represents the total estimated amortization of intangible assets for each of the succeeding five years:

Year ending December 31:

2006	\$ 450,000
2007	450,000
2008	450,000
2009	450,000
2010	450,000

NOTES TO FINANCIAL STATEMENTS

Note 3. Long-Term Debt

Long-term debt consists of the following at December 31:

	2006	2005
Note payable, Fifth Third Bank (a)		
Dated 02/28/06, variable rate		
(5.41% at 12/31/06)	\$ 14,200,000	\$ --
Notes payable, RTFC (b)		
Dated 11/13/97, variable rate		
Paid in full 03/01/06	--	194,957
Dated 11/13/97, variable rate		
Paid in full 03/01/06	--	899,406
Dated 11/13/97, fixed rate		
Paid in full 03/01/06	--	727,521
Dated 12/31/98, fixed rate		
Paid in full 03/01/06	--	618,521
Dated 02/13/01, variable rate		
Paid in full 03/01/06	--	786,457
Dated 02/13/01, variable rate		
Paid in full 03/01/06	--	932,200
Dated 07/27/01, variable rate		
Paid in full 03/01/06	--	2,845,311
Lines of Credit, RTFC		
Line of credit, variable rate (c)		
Paid in full 03/01/06	--	5,000,000
Line of credit, variable rate (d)		
Paid in full 03/01/06	--	1,750,000
Line of Credit, Fifth Third Bank (e)		
Due 03/28/08, variable rate	--	--
(5.41% at 12/31/06)		
	\$ --	\$ 13,754,373

(a) On February 28, 2006, the Company borrowed \$14,200,000 to restructure its debt. The note is payable in 10 annual installments of \$1,200,000 for 2007, \$1,400,000 for 2008 through 2012, and \$1,500,000 for 2013 through 2016, with a variable interest rate. The note is collateralized by the assets of the Company.

(b) The notes payable to Rural Telephone Finance Cooperative (RTFC) were secured by mortgage and security agreements that include substantially all of the assets of the Company. In addition, the Company was required to purchase equity certificates in RTFC equal to 5% of the total amounts borrowed. The notes were payable in quarterly installments over 15 years with interest at variable or fixed rates set by RTFC. The notes were paid in full on March 1, 2006.

NOTES TO FINANCIAL STATEMENTS

Note 3. Long-Term Debt (Continued)

- (c) The line of credit agreement with RTFC provided for borrowings up to \$5,000,000. The agreement carried an interest rate at prime, plus one and one-half percent, was unsecured and was renewed June 28, 2004 for 24 months. The line of credit was paid in full on March 1, 2006.
- (d) The line of credit agreement with RTFC provided for borrowings up to \$2,000,000. The agreement carried an interest rate at prime, plus one and one-half percent, was unsecured and due May 16, 2006. The line of credit was paid in full on March 1, 2006.
- (e) The line of credit agreement with Fifth Third Bank provides for borrowing up to \$3,000,000. The agreement carries a variable interest rate, is secured by certain assets of the company, and is due March 28, 2008.

Approximate maturities or payments required on principal under note payable agreements for each of the succeeding five years are as follows:

Year ending December 31:

2006	\$ 1,200,000
2007	1,400,000
2008	1,400,000
2009	1,400,000
2010	1,400,000

Note 4. Retirement Plans

The Company has a 401(k) plan for qualifying employees who have reached twenty-one years of age. Eligible employees are allowed to invest up to 15% of their compensation and the Company has agreed to match 100% of the first 3% of the employees' contribution and 50% of the employees' contribution between 3% and 5%. The Company contributed \$73,607 and \$67,460 matching funds for its 401(k) plan during the years ended December 31, 2006 and 2005, respectively.

The Company also offers an employer sponsored retirement savings plan for qualified employees who have reached twenty-one years of age. The Company has agreed to contribute 9% of the eligible employee's compensation, plus an additional 5% of the original contribution.

The Company contributed \$259,859 and \$221,669 to its retirement savings plan during the years ended December 31, 2006 and 2005, respectively.

NOTES TO FINANCIAL STATEMENTS

Note 5. Related Party Transactions

The Company shares personnel with one of its members. The Company paid \$114,996 and \$132,681 for shared personnel during the years ended December 31, 2006 and 2005 respectively. The Company also leased offices and warehouse space from two members. The leases are for an unspecified length of time. The monthly lease payments total approximately \$7,000. In addition, the Company incurred interconnection and telephone charges from its members aggregating \$752,095 and \$786,283 for the years ended December 31, 2006 and 2005, respectively.

The Company leases two cellular tower sites from the officers and majority shareholders of a member for \$100 per month for each site. The leases are for an unspecified length of time. In addition, the Company leases two other sites from a company owned by this member for \$600 each on a month to month basis.

The Company leases cellular tower sites from the parent company of one of its other members for \$1,039 per month. The leases are for five years with options to renew.

The Company pays commissions to two of its members for phone sales to customers. The amount of commissions paid to related parties was \$45,484 and \$43,873 for 2006 and 2005 respectively.

Note 6. Operating Leases

The Company has entered into operating leases with its members and other customers to provide fiber optic transmission capacity and ancillary services. The terms of these leases are for 15 years.

Total rental income earned from these operating lease commitments included in the statements of income were \$1,130,809 and \$1,254,902 for the years ended December 31, 2006 and 2005, respectively. Rental income earned from the Company's members from these leases was \$631,789 and \$713,599 for the years ended December 31, 2006 and 2005, respectively.

Investments in operating leases are as follows at December 31:

	2006	2005
Fiber ring	\$ 6,471,128	\$ 6,245,412
Accumulated depreciation	(982,379)	(773,028)
	\$ 5,488,749	\$ 5,472,384

The future minimum rental payments expected to be received under these lease agreements for each of the succeeding five years are approximately \$700,000 each year based upon new contracts negotiated during 2005.

NOTES TO FINANCIAL STATEMENTS

Note 6. Operating Leases (Continued)

The Company has also entered into lease agreements with its members to obtain fiber optic transmission and digital microwave transmission services. The terms of these leases are for 15 years.

Rental expenses incurred under these operating lease commitments included in the statements of income were \$194,083 and \$33,329 for the years ended December 31, 2006 and 2005, respectively. The future minimum lease payments required under these lease agreements for each of the succeeding five years are \$115,734 each year.

Note 7. Eligible Telecommunication Carrier

During the prior year, the Company was granted Eligible Telecommunication Carrier (ETC) status by the Kentucky Public Service Commission. As an ETC, the Company receives funding from the federal Universal Service Fund (USF) to support the high cost of providing local telephone service in rural areas. USF payments amounted to \$3,716,602 and \$589,913 for 2006 and 2005 respectively.

Note 8. Impairment of Goodwill

During 2005, the Company completed its annual valuation of the acquired goodwill related to paging acquisitions. Pursuant to the valuation, the Company expensed the remaining balance of goodwill. In management's judgment, the underlying assets associated with the goodwill were determined to be of substantially less value than the amount originally paid. The Company disputed the amount based upon the estimated current market value of the purchased customer lists, which approximates the current amortized book value. Accordingly, the entire balance of the remaining note payable issued as part of the acquisitions, along with the related accrued interest, has been written off due to the impairment of goodwill.

The following is a summary of the impairment of goodwill expense included in the financial statements for the year ended December 31, 2005:

Goodwill	\$ 787,286
Note payable	(400,000)
Accrued interest	(56,000)
	<u>\$ 331,286</u>



Directions To Winston Site

Starting from the courthouse in Estill County Ky. Take Hwy 52 West 5.4 miles to Hwy 3325 (Winston Road). Turn Left onto Winston road and go 1.6 miles to Strong Lane. Turn Right onto Strong lane and go .13 miles to site located on your left as you drive by on Strong Lane.

Directions were written by:

Marty Thacker
Appalachian Wireless
606-634-9505 Cell Phone
606-785-2203 Office
m.thacker@tgtel.com email

Search Area Map



DEED OF CONVEYANCE

THIS DEED OF CONVEYANCE, entered into this 31st day of May, 2007, between **Harold Timothy Gould and Rhonda Gould, his wife**, of 95 Strong Lane, General Delivery, Winston, Kentucky 40495, **Grantors**, and **East Kentucky Network, LLC, d/b/a Appalachian Wireless**, 101 Technology Trail, Ivel, Kentucky 41642, Grantee.

WITNESSETH:

That said Grantor for and in consideration of the sum of Twenty-Five Thousand Dollars (\$25,000.00), cash in hand paid, the receipt and sufficiency of which is hereby acknowledged, does hereby grant, sell and convey to the Grantee, its successors and assigns, the following described property, to-wit:

BEING a part of the same property conveyed to Grantors by deed dated September 30, 1994, recorded in Deed Book 209, Page 699, Estill County Records Clerk's Office.

BEING the same property described by metes and bounds in the description attached hereto and made a part hereof as Exhibit "A", and as shown on the plat dated 4th day of April, 2007, prepared by Steven E. Haywood, Licensed Land Surveyor, and attached hereto and made a part hereof as Exhibit "B."

Grantors grant and convey unto Grantee, its successors or assigns, a permanent easement and right of way (non-exclusive) for a roadway of sufficient width for ingress and egress with men, vehicles, equipment and machinery over and across Grantors' retained surface property to the tract or parcel of land granted and conveyed herein to Grantee, its successors and assigns together with the right to reconstruct or use any existing roadways over Grantors' retained surface for such purposes. Grantee shall repair any damage to said roadway caused by Grantee.

Grantors grant and convey unto Grantee, its successors or assigns, an easement and

right of way from the corner of the property of Grantee four hundred-twelve feet (412') more or less to property of Grantor to construct and maintain any and all power lines, telephone lines, co-axial lines or any other utilities, such lines to be run underground or related facilities needed and/or necessary for use by Grantee, its successors or assigns, over and across Grantors' retained surface property to the tract or parcel of land granted and conveyed herein to Grantee, its successor and assigns, and being that portion of the tract of property as set forth and marked "utility easement" on the plat at Exhibit "B" hereof..

Grantors further grant and convey unto Grantee, its successors and assigns, the right to remove any trees, tree limbs, undergrowth or obstructions upon Grantors' retained surface property that might interfere with or damage any towers or structures that Grantee, its successors or assigns, may place upon the above described tract of land, or with the easements and rights of way granted herein; provided Grantee must first counsel with Grantors and obtain their consent (which may be reasonably withheld) as to any trees to be removed, if such trees are marketable, Grantors shall receive the benefits from any sale of such trees.

TO HAVE AND TO HOLD the same with all appurtenances thereunto belonging unto the Grantee, its successors and assigns forever, with covenant of General Warranty.

We, the undersigned, do hereby certify and swear pursuant to KRS Chapter 382, that the full and complete consideration paid for the transfer of the hereinabove described property was Twenty-Five Thousand Dollars (\$25,000.00).

IN TESTIMONY WHEREOF, the parties have hereunto subscribed their names, this day and year aforesaid.

GRANTORS:

Harold Timothy Gould
Harold Timothy Gould

Rhonda Gould
Rhonda Gould

GRANTEE:

EAST KENTUCKY NETWORK, LLC
d/b/a APPALACHIAN WIRELESS


BY: Gerald F. Robinette

ITS: General Manager

STATE OF KENTUCKY

COUNTY OF Johnson

I, Candi Price, a Notary Public in and for the County and State aforesaid, do hereby certify that the foregoing Deed of Conveyance and Consideration Certificate was this day produced, acknowledged, subscribed and sworn before me in the said County and State and signed by **Harold Timothy Gould and Rhonda Gould, married, Grantors**, this 31st day of May, 2007.




Candi Price
NOTARY PUBLIC

Commission Expires: 1-28-09

STATE OF KENTUCKY

COUNTY OF Floyd


I, Teresa M. Apel, a Notary Public in and for the county and state aforesaid, do hereby certify that the foregoing Deed of Conveyance and Consideration Certificate was this day produced, acknowledged, subscribe and sworn to before me in said County and State and signed by **East Kentucky Network, LLC, d/b/a Appalachian Wireless**, by Gerald F. Robinette, its General Manager/CEO, this 30 day of May, 2007.



Teresa M. Apel
NOTARY PUBLIC

Commission Expires: June 22, 2009

This is to certify that this instrument was prepared by:



WILLIAM S. KENDRICK, ATTORNEY
FRANCIS, KENDRICK & FRANCIS
P.O. Box 268
Prestonsburg, Kentucky 41653
606/886-2812

STATE OF KENTUCKY

COUNTY OF ESTILL

Clerk's Certificate of
Lodgment and Record

I, _____, Clerk of the County for the County and State aforesaid, certify that the foregoing Deed was on the ____ day of _____, 2007 lodged for record, whereupon the same, with the foregoing and this certificate have been duly recorded in my office.

WITNESS my hand, this ____ day of _____, 2007.

_____ Clerk

By _____ D.C.



Bearings shown hereon are based on an observation between monuments shown on map titled Property Survey for Mrs. Fae Strong, Map 15 of For Mr. Fae Strong, Map 15 of record in Plat Cabinet 1, Slide 256 of the records of the Estill County Court Clerk.

Harold Timothy Gould
D.B. 209 P. 699
Tract #7

Boundary line between Tract #3 and Tract #7
Donald Jordan
D.B. 210 P. 181
D.B. 233 P. 646
Tract #3
N 52°04'40" W
397.05'

Boundary line between Tract #3 and Tract #7
100.00'

N10,017.276
E:19,815.291

Harold Timothy Gould
D.B. 209 P. 699
10040.5 SQ. FT.
0.23 ACRES

Harold Timothy Gould
D.B. 209 P. 699
Tract #7

N:9,955.558
E:19,894.386

Owner Information:
Harold Timothy Gould
94 Strong Lane
General Delivery
Winston, Ky 40495
606-723-6017

LEGEND

- Boundary line out conveyance
- Existing Boundary Line
- Underground Utilities
- UGU
- T/Bar set with metal cap, stamped Summit Engineering, L.S. #2661, unless noted otherwise
- Monument found and noted

Donald Jordan
D.B. 210 P. 181
D.B. 233 P. 646
Tract #4
Boundary line between Tract #3 and Tract #4

Gravel Road
for access to Jordan, Tract.


Access along existing Road
34.75'

S 37°56'55" W
100.00'

Harold Timothy Gould
D.B. 209 P. 699
Tract #7

N 52°04'40" W
55.95'

Re-Bar with cap
stamped Alton #2582
Found



Map of Reference:
Plat Map, Property Survey for Mrs. Fae Strong, Dated August 1994 and prepared by Alton Flynn Professional Land Surveyor, #2582.
Map is filed in Plat Cabinet #1 Slide #256 of the records of the Estill County Court Clerk's office.

Survey Date: 4/2/07
Revision: Property Lines, 5/10/07
Revision: Underground Utilities, 5/24/07

I HEREBY CERTIFY THAT THE SURVEY DEPICTED BY THIS PLAT WAS DONE BY PERSONS UNDER MY DIRECT SUPERVISION BY THE METHOD OF RANDOM TRAVERSE WITH SIDESHOTS, THE UNADJUSTED PRECISION RATIO OF THE TRAVERSE WAS 1/50,817 AND WAS NOT ADJUSTED. THE SURVEY AS SHOWN HEREON IS A CLASS "B" SURVEY AND THE ACCURACY AND PRECISION OF SAID SURVEY MEETS ALL THE SPECIFICATIONS OF THIS CLASS.

STEVEN E. HAYWOOD
PLS #2661
DATE 5-27-07

PROFESSIONAL
LICENSED
LAND SURVEYOR
STEVE
HAYWOOD
2007

DATE: 4/3/07	FILENAME: EC4207
SCALE: 1"=30'	DISK NO.
DRAWN BY: seh	

East Kentucky Network, LLC
204 Technology Trail
Ivel, Kentucky 41642

Map of
Portion of the Harold Timothy Gould
Tract of land located at Winston, KY

SUMMIT ENGINEERING
131 SUMMIT DRIVE
PIKEVILLE, KY 41501
(606) 432-1447

LEXINGTON, KY BRANDYVA, LOS...
CHARLESTON, WV HAZARD,

A certain tract of land located on Strong Lane, in the Community of Winton, Estill County, Kentucky and more particularly described as follows.


Unless stated otherwise any monument referred to herein as a T/T-Bar is a steel T-Bar having three radial arms of one half inch and is 18" inches in length, with a metal cap stamped Summit Engineering, L.S. #2661. All bearings stated herein are based on an observation between found monuments as shown on map titled Property Survey for Mrs. Fae Strong. Map is of record in Plat Cabinet 1, Slide #256 of the records of the Estill County Court Clerk's office.

Beginning at a set T/T-Bar on the boundary line between Donald Jordan (D.B. 210 P. 181 and D.B. 233 P. 646) and Harold Timothy Gould (D.B. 209 P. 699) and being N 52°02'40" W 55.95' from a found Re-Bar with cap stamped ALTON #2582; Thence, leaving said boundary line and running the line of Harold Timothy Gould, remaining, S 37°56'55" W a distance of 112.12' to a set T/T-Bar; Thence, N 52°35'12" W a distance of 100.31' to a set T/T-bar; Thence, N 37°51'25" E a distance of 113.08' to a set T/T-Bar next to a 1/2" metal pipe on the boundary line of Donald Jordan; Thence, with the line of Donald Jordan S 52°02'07" E a distance of 100.49' feet which is the point of beginning, having an area of 11304.73 square feet, 0.260 acres according to a survey performed by personal under the direct supervision of Steven E. Haywood, PLS #2661, with Summit Engineering, Inc. on April 2, 2005 and being a part of the tract of land conveyed to Harold Timothy Gould and Rhonda Gould by Fae Strong, by deed dated September 30, 1994 which is of record in Deed Book 209 Page 699 of the records of the Estill County Court Clerk's office.



Steven E. Haywood, PLS #2661

Date: 4/3/07



A certain tract of land located on Strong Lane, in the Community of Winton, Estill County, Kentucky and more particularly described as follows.


Unless stated otherwise any monument referred to herein as a T/T-Bar is a steel T-Bar having three radial arms of one half inch and is 18" inches in length, with a metal cap stamped Summit Engineering, L.S. #2661. All bearings stated herein are based on an observation between found monuments as shown on map titled Property Survey for Mrs. Fae Strong. Map is of record in Plat Cabinet 1, Slide #256 of the records of the Estill County Court Clerk's office.

Beginning at a set T/T-Bar on the boundary line between Donald Jordan (D.B. 210 P. 181 and D.B. 233 P. 646) and Harold Timothy Gould (D.B. 209 P. 699) and being N 52°02'40" W 55.95' from a found Re-Bar with cap stamped ALTON #2582; Thence, leaving said boundary line and running the line of Harold Timothy Gould, remaining, S 37°56'55" W a distance of 112.12' to a set T/T-Bar; Thence, N 52°35'12" W a distance of 100.31' to a set T/T-bar; Thence, N 37°51'25" E a distance of 113.08' to a set T/T-Bar next to a ½" metal pipe on the boundary line of Donald Jordan; Thence, with the line of Donald Jordan S 52°02'07" E a distance of 100.49' feet which is the point of beginning, having an area of 11304.73 square feet, 0.260 acres according to a survey performed by personal under the direct supervision of Steven E. Haywood, PLS #2661, with Summit Engineering, Inc. on April 2, 2005 and being a part of the tract of land conveyed to Harold Timothy Gould and Rhonda Gould by Fae Strong, by deed dated September 30, 1994 which is of record in Deed Book 209 Page 699 of the records of the Estill County Court Clerk's office.



Steven E. Haywood, PLS #2661

Date: 4/3/07



DOCUMENT NO: 287425
RECORDED ON: MAY 31, 2007 01:45:18PM
TOTAL FEES: \$25.00
TRANSFER TAX: \$25.00
COUNTY CLERK: SHERRY L FOX
COUNTY: ESTILL COUNTY
DEPUTY CLERK: HARPER, JANICE M
BOOK 0 269 PAGES 234 - 239

