



Steven L. Beshear
Governor

Leonard K. Peters
Secretary
Energy and Environment Cabinet

Commonwealth of Kentucky
Public Service Commission
211 Sower Blvd.
P.O. Box 615
Frankfort, Kentucky 40602-0615
Telephone: (502) 564-3940
Fax: (502) 564-3460
psc.ky.gov

David L. Armstrong
Chairman

James W. Gardner
Vice Chairman

Charles R. Borders
Commissioner

June 10, 2011

Mr. Gerald Sheperson
Ms. Mischell Lee
North Mercer Water District
Post Office Box 79
Salvisa, Kentucky 40372

W. Randall Jones, Esq.
Rubin & Hays
Kentucky Home Trust Building
450 South Third Street
Louisville, Kentucky 40202

Thomas M. Jones, Esq.
138 South Main Street
Lawrenceburg, Kentucky 40342

Mr. Ron Gastineau
Gastineau & Associates
3465 Rabbits Foot Trail
Lexington, Kentucky 40503

Re: Cases No. 2011-000170 and No. 2011-00171
North Mercer Water District

Ms. Lee and Gentlemen:

The enclosed electronic mail message and its attachments have been filed in the record of the above-reference cases.

Mr. Gastineau advised Commission Staff by telephone on June 9, 2011 that the attached bid sheets reflect the final specifications for the proposed construction projects and contain modifications to the specifications set forth in the preliminary engineering reports.

Sincerely,

A handwritten signature in black ink, appearing to read "Jeff Derouen".

Jeff Derouen
Executive Director

Cc: Case File

Wuetcher, Jerry (PSC)

From: regksg@windstream.net
Sent: Thursday, June 09, 2011 15:27
To: Wuetcher, Jerry (PSC)
Subject: North Mercer Water District

Attachments: BID SCHEDULE PHASE 1-1.xls; BID SCHEDULE PHASE 1-2.xls; BID SCHEDULE NMWD 2-1REVISED 4-7-11.xls; BID SCHEDULE NMWD 2-2 REVISED 4-7-11.xls; BID SCHEDULE NMWD 2-3.xls; BID SCHEDULE NMWD 2-4.xls



BID SCHEDULE PHASE 1-1.xls (27..PHASE 1-2.xls (29..MWD 2-1REVISED 4MWD 2-2 REVISED NMWD 2-3.xls (20 ..NMWD 2-4.xls (17 ..

Mr. Wuetcher,

Attached are the bid sheets for all 6 contracts. Two contracts are for Phase 1 and are designated as 1-1 and 1-2. The others are Phase 2 designated as 2-1, 2-2, 2-3, and 2-4.

Ron G.

BID SCHEDULE
 NORTH MERCER WATER DISTRICT
 CONTRACT NMWD MPI 1-1
 US127 AND MUNDY'S LANDING

ITEM NO.	ITEM	UNIT	QUANTITY	UNIT PRICE	COST OF ITEM
1	8" CL-200 PVC Pipe	LF	15643		
2	6" CL200 PVC PIPE	LF	9080		
3	8" Tapping sleeve and valve	EA	1		
4	8" Gate Valve	EA	4		
5	6" Gate Valve	EA	3		
6	8" Check Valve assembly	EA	1		
7	6" Check Valve assembly	EA	2		
8	4" Check Valve assembly	EA	1		
9	3" Check Valve assembly	EA	1		
10	3/4" PE service tubing, jacked	LF	284		
11	3/4" PE service tubing, trenched	LF	514		
12	1" PE Service tubing, jacked	LF	30		
13	1" PE Service tubing, trenched	LF	52		
14	12" Steel casing, bore and jack	LF	86		
15	16" Steel casing, bore and jack	LF	320		
16	3/4" Air release valve	EA	4		
17	1" Air release valve	EA	2		
18	Crushed stone driveway repair, DGA	TON	34		
19	Crushed stone bedding	TON	386		
20	#12 Copper insulated tracer wire	LF	24723		
21	Tie in detail-Providence Road	LS	1		
22	Tie in detail No. 1 Mundy's Landing	LS	1		
23	Tie in detail No. 2 Mundy's Landing	LS	1		
24	Connect hydrant to new line	EA	1		
25	8" Creek crossing, type II	LF	30		
26	Reconnect existing 5/8"X3/4" customer meter to new service line	EA	22		
27	Reconnect existing 1" customer meter to new service line	EA	1		
28	Asphalt replacement	Ton	2		
29	8" DIMJ 90° Bend	EA	10		
30	8" DIMJ 45° Bend	EA	1		
31	8" DIMJ 22-1/2° Bend	EA	2		
32	6" DIMJ 90° Bend	EA	3		
33	6" DIMJ Tee	EA	2		

TOTAL BID

BID SCHEDULE
NORTH MERCER WATER DISTRICT
CONTRACT: NMWD MPI 1-2
UNITY, CUMMINS FERRY, GASH, AND SAWD

ITEM NO.	ITEM	UNIT	QUANTITY	UNIT PRICE	COST OF ITEM
1	8" CL 200 PVC Pipe	LF	4375		
2	6" CL 200 PVC PIPE	LF	8642		
3	4" CL 200 PVC Pipe	LF	5578		
4	8" Tapping sleeve and valve	EA	1		
5	6" Tapping sleeve and valve	EA	2		
6	4" Tapping sleeve and valve	EA	1		
7	3" Tapping sleeve and valve	EA	3		
8	2" Tapping saddle	EA	1		
9	6" Blowoff assembly	EA	1		
10	Flush Hydrant assembly	EA	2		
11	6" Gate Valve	EA	1		
12	2" Gate Valve	EA	1		
13	3/4" PE service tubing, jacked	LF	150		
14	3/4" PE service tubing, trenched	LF	145		
15	8" Steel casing, bore and jack	LF	78		
16	16" Steel casing, bore and jack	LF	292		
17	4" Blowoff assembly	EA	2		
18	3/4" Air release valve	EA	1		
19	Crushed stone driveway repair, DGA	TON	54		
20	Crushed stone bedding	TON	556		
21	#12 Copper insulated tracer wire	LF	18595		
22	4" Creek crossing, type II	LF	20		
23	6" Creek crossing, type II	LF	40		
24	Reconnect existing 5/8"X3/4" customer meter to new service line	EA	9		
25	Install 1-1/2" By Pass meter (less gate valve) on existing 6" line-See plan sheet 2 for location	EA	4		
26	Install 1-1/2" By Pass meter (less gate valve) on existing 4" line-See plan sheet 2 for location	EA	2		
27	Install 8" lever and weight check valve in existing 8" line. Use 30" diameter meter box with lid	EA	1		
28	Install 6" lever and weight check valve in existing 6" line. Use 30" diameter meter box with lid	EA	2		
29	Install 4" lever and weight check valve in existing 4" line. Use 30" diameter meter box with lid	EA	3		
30	Install 3" lever and weight check valve in existing 3" line. Use 30" diameter meter box with lid	EA	1		
31	Move hydrant to new line	EA	1		
32	8" DIMJ 90° Bend	EA	4		
33	8" DIMJ 45° Bend	EA	2		
34	6" DIMJ 90° Bend	EA	2		
35	6" DIMJ Tee	EA	1		
36	4" DIMJ 90° Bend	EA	3		
37	4" DIMJ 45° Bend	EA	2		
38	4"X3" DIMJ Reducer	EA	1		
39	Wheat School road pump station	LS	1		

TOTAL BID

--	--

BID SCHEDULE
 NORTH MERCER WATER DISTRICT
 CONTRACT: NMWD MPI 2-1
 MARTIN LANE, NEW DIXVILLE ROAD, THREE LICK ROAD, BATTLE ROAD
 REVISED APRIL 7,2011

ITEM No.	ITEM	UNIT	QUANTITY	UNIT PRICE	COST OF ITEM
1	6" CL 200 PVC PIPE	LF	20470		
2	4" CL200 PVC PIPE	LF	370		
3	6" PE SDR 9, OPEN CUT	LF	100		
4	10" STEEL CASING PIPE, B & J	LF	28		
5	10" STEEL CASING PIPE, OPEN CUT	LF	98		
6	6" RESILIENT WEDGE GATE VALVE	EA	4		
7	8"X6" TAPPING SLEEVE & 6" TAPPING VALVE	EA	1		
8	4" TAPPING SLEEVE AND VALVE	EA	1		
9	3" TAPPING SLEEVE AND VALVE	EA	1		
10	TIE IN DETAIL No. 1 NEW DIXVILLE ROAD	LS	1		
11	TIE IN DETAIL No. 2 NEW DIXVILLE ROAD	LS	1		
12	TIE IN DETAIL BATTLE ROAD	LS	1		
13	TIE IN DETAIL CORNISHVILLE	LS	1		
14	5/8"X3/4" METER AND BOX	EA	3		
15	3/4" PE SERVICE LINE, OPEN CUT	LF	75		
16	3/4" PE SERVICE LINE, BORE	LF	35		
17	1-1/2" BY PASS METER WITHOUT GATE VALVE	EA	11		
18	6" BLOW OFF	EA	1		
19	4" BLOW OFF	EA	1		
20	3/4" AIR RELEASE VALVE	EA	6		
21	6" CREEK CROSSING, TYPE II	LF	136		
22	6" DIMJ 90° BEND	EA	8		
23	6" DIMJ 45° BEND	EA	4		
24	TIE TO EXISTING 6" VALVE	EA	1		
25	CRUSHED STONE BACKFILL	TON	1200		
26	CRUSHED STONE (DGA)	TON	220		
27	#12 COPPER TRACING WIRE	LF	20840		

TOTAL

--

BID SCHEDULE
 NORTH MERCER WATER DISTRICT
 CONTRACT: NMWD MPI 2-2
 US 127
 REVISED APRIL 7, 2011

ITEM No.	ITEM	UNIT	QUANTITY	UNIT PRICE	COST OF ITEM
1	12" CL 200 PVC	LF	1370		
2	10" CL 200 PVC PIPE	LF	4760		
3	8" CL 200 PVC PIPE	LF	8440		
4	20" STEEL CASING PIPE, B & J	LF	186		
5	16" STEEL CASING PIPE, B & J	LF	790		
6	10" RESILIENT WEDGE GATE VALVE	LF	2		
7	8" RESILIENT WEDGE GATE VALVE	LF	2		
8	8" CREEK CROSSING, TYPE II	LF	20		
9	TIE IN DETAIL No. 2 US 127	LS	1		
10	TIE IN DETAIL No. 3 US 127	LS	1		
11	3/4" AIR RELEASE VALVE	EA	3		
12	12" DIMJ 90° BEND	EA	2		
13	12" DIMJ 22 1/2° BEND	EA	1		
14	12"X10" DIMJ REDUCER	EA	1		
15	10" DIMJ 90° BEND	EA	3		
16	10"X8" DIMJ REDUCER	EA	1		
17	CRUSHED STONE BACKFILL	TON	1070		
18	CRUSHED STONE (DGA)	TON	110		
19	#12 COPPER TRACING WIRE	LF	14570		
20	US 127 MASTER METER VAULT	LS	1		

TOTAL CONTRACT: NMWD MPI 2-2

BID SCHEDULE
 NORTH MERCER WATER DISTRICT
 CONTRACT: NMWD MPI 2-3
 WARWICK ROAD

ITEM No.	ITEM	UNIT	QUANTITY	UNIT PRICE	COST OF ITEM
1	8" CL 200 PVC PIPE	LF	14196		
2	16" STEEL CASING PIPE, B & J	LF	715		
3	8" RESILIENT WEDGE GATE VALVE	LF	3		
4	RECONNECT EXISTING 5/8"X3/4" METER TO NEW LINE	EA	57		
5	DISCONNECT EXISTING METER AND CLOSE CORPORATION STOP AT OLD LINE	EA	57		
6	RECONNECTING EXISTING 2" SERVICE LINE TO NEW LINE	EA	1		
7	TIE IN DETAIL @ PUMP STATION WARWICK	LS	1		
8	OTT ELLIOT TIE IN DETAIL	LS	1		
9	K-LEIGH TIE IN	LS	1		
10	WARWICK ROAD END OF LINE TIE IN	LS	1		
11	3/4" PE SERVICE LINE, OPEN CUT	LF	1080		
12	3/4" PE SERVICE LINE, BORE	LF	820		
13	3/4" AIR RELEASE VALVE	EA	7		
14	8" DIMJ 90° BEND	EA	12		
15	8" DIMJ 45° BEND	EA	4		
16	CRUSHED STONE BACKFILL	TON	222		
17	CRUSHED STONE (DGA)	TON	78		
18	#12 COPPER TRACING WIRE	LF	14196		

TOTAL

--

BID SCHEDULE
 NORTH MERCER WATER DISTRICT
 CONTRACT: NMWD MPI 2-4
 PUMPING STATIONS AND McCROSKEY TANK VALVE PIT

ITEM No.	ITEM	UNIT	QUANTITY	UNIT PRICE	COST OF ITEM
1	MARTIN LANE PUMP STATION	LS	1		
2	CORNISHVILLE PUMP STATION	LS	1		
3	CITY PARK PUMP STATION	LS	1		
4	McCROSKEY TANK VALVE VAULT	LS	1		

TOTAL

--