

RECEIVED

AUG 31 2018

PUBLIC SERVICE  
COMMISSION

COMMONWEALTH OF KENTUCKY  
BEFORE THE PUBLIC SERVICE COMMISSION

In the matter of:

THE APPLICATION OF EAST KENTUCKY NETWORK, )  
LLC FOR THE ISSUANCE OF A CERTIFICATE OF )  
PUBLIC CONVENIENCE AND NECESSITY TO ) CASE NO. 2018-00283  
CONSTRUCT A TOWER IN BELL COUNTY, KENTUCKY )

East Kentucky Network, LLC d/b/a Appalachian Wireless, was granted authorization to provide cellular service in the KY-11 Cellular Market Area (CMA453) by the Federal Communications Commission (FCC). The FCC license is included as Exhibit 1. East Kentucky Network, LLC merger documents were filed with the Commission on February 2, 2001 in Case No. 2001-022. East Kentucky Network, LLC is a Kentucky limited liability company that was organized on June 16, 1998. East Kentucky Network, LLC is in good standing with the state of Kentucky.

In an effort to improve service in Bell County, pursuant to KRS 278.020 Subsection 1 and 807 KAR 5:001, East Kentucky Network, LLC is seeking the Commission's approval to construct a 300-foot self-supporting tower on a tract of land located at 565 Halls Hollow Road, Pineville, Bell County, Kentucky (36°47'24.94"N 83°31'59.74"W). A map and detailed directions to the site can be found in Exhibit 7.

Exhibit 2 is a list of all Property owners or residents according to the Property Valuation Administrator's record who own property within 500 feet of the proposed Tower and all property owners that own property contiguous to the property upon which construction is proposed in accordance with the Property Valuation Administrator's record.

Pursuant to 807 KAR 5:063 Section 1(1)(l), Section 1(m) and Section 2, all affected property owners according to the Property Valuation Administrator's records who own property



within 500 feet of the proposed Tower or who own property contiguous to the property upon which construction is proposed were notified by certified mail return receipt requested of East Kentucky Network, LLC's proposed construction and informed of their right to intervene. They were given the docket number under which this application is filed. Enclosed in Exhibit 2 is a copy of that notification.

Bell County has no formal local planning unit. In absence of this unit, the Bell County Judge Executive's office was notified by certified mail, return receipt requested of East Kentucky Network, LLC's proposal and informed of their right to intervene. The Bell County Judge Executive's Office was also given the docket number under which this application is filed. Enclosed in Exhibit 3 is a copy of that notification.

Notice of the location of the proposed construction was published in The Pineville Sun, August 30, 2018 edition. Enclosed is a copy of that notice in Exhibit 3. The Pineville Sun is the newspaper with the largest circulation in Bell County.

A geologist was employed to determine soil and rock types and to ascertain the distance to solid bedrock. The geotechnical report is enclosed as Exhibit 4.

A copy of the tower design information is enclosed as Exhibit 5. The proposed tower has been designed by engineers at Allstate Tower, Inc. and will be constructed under their supervision. Their qualifications are evidenced in Exhibit 5 by the seal and signature of the registered professional engineer responsible for this project.

The tower will be erected by S & S Tower Services of St. Albans, West Virginia. S & S Tower Services has vast experience in the erection of communications towers.

FAA and Kentucky Airport Zoning Commission approvals are included as Exhibit 6.

No Federal Communications Commission approval is required prior to construction of this facility. Once service is established from this tower we must immediately notify the Federal

Communications Commission of its operation. Prior approval is needed only if the proposed facility increases the size of the cellular geographic service area. This cell site will not expand the cellular geographic service area.

East Kentucky Network, LLC will finance the subject Construction with earned surplus in its General Fund.

Estimated Cost of Construction	\$ 350,000.00
Annual Operation Expense of Tower	\$ 12,500.00

Two notice signs meeting the requirements prescribed by 807 KAR 5:063, Section 1(2), measuring at least two (2) feet in height and four (4) feet in width and containing all required language in letters of required height, have been posted, one at a visible location on the proposed site and one on the nearest public road. The two signs were posted on August 28, 2018, and will remain posted for at least two weeks after filing of this application as specified.

Enclosed in Exhibit 8 is a copy of East Kentucky Network, LLC's Deed for the site location along with a lot description.

The proposed construction site is on a mountaintop some feet from the nearest structure. Prior to construction, the site was wooded.

East Kentucky Network, LLC's operation will not affect the use of nearby land nor its value. No more suitable site exists in the area. A copy of the search area map is enclosed in Exhibit 7. No other tower capable of supporting East Kentucky Network, LLC's load exists in the general area; therefore, there is no opportunity for co-location of our facilities with anyone else.

Enclosed, and filed as Exhibit 9 is a survey of the proposed tower site signed by a Kentucky registered professional engineer.

Exhibit 10 is a map in one (1) inch equals 200 feet scale identifying every structure and every owner of real estate within 500 feet of the proposed tower and all property owners who own contiguous property to the property upon which construction is proposed

Exhibit 11 contains a vertical sketch of the tower supplied by James W. Caudill, Kentucky registered professional engineer.

Enclosed as Exhibit 12 is a list of utilities, corporations, or persons with whom the tower is likely to compete.

**[THE REMAINDER OF THIS PAGE INTENTIONALLY LEFT BLANK.]**

**WHEREFORE**, Applicant, having met the requirements of KRS 278.020(1), 278.650, 278.665, and all applicable rules and regulations of the PSC, respectfully requests that the PSC accept the foregoing Application for filing and grant a Certificate of Public Convenience and Necessity to construct and operate the proposed tower.

The foregoing document was prepared by Krystal Branham, Regulatory Compliance Attorney for East Kentucky Network, LLC d/b/a Appalachian Wireless. All related questions or correspondence concerning this filing should be mailed to East Kentucky Network, LLC d/b/a/ Appalachian Wireless, Attn: Regulatory Compliance Department, 101 Technology Trail, Ivel, KY 41642.

SUBMITTED BY: Lynn Haney DATE: 8/29/18  
Lynn Haney, Regulatory Compliance Director

APPROVED BY: W.A. Gillum DATE: 8/29/18  
W.A. Gillum, General Manager

ATTORNEY: Krystal Branham DATE: 8/29/18  
Hon. Krystal Branham, Attorney

**CONTACT INFORMATION:**

**W.A. Gillum, General Manager**  
**Phone: (606) 477-2355, Ext. 111**  
**Email: wagillum@ekn.com**

**Lynn Haney, Regulatory Compliance Director**  
**Phone: (606) 477-2355, Ext. 1007**  
**Email: lhaney@ekn.com**

**Krystal Branham, Attorney**  
**Phone: (606) 477-2355, Ext. 1009**  
**Email: kbranham@ekn.com**

**Mailing Address:**

**East Kentucky Network, LLC  
d/b/a Appalachian Wireless  
Attn: Regulatory Compliance Department  
101 Technology Trail  
Ivel, KY 41642**

ULS License

## 700 MHz Lower Band (Blocks C, D) License - WPWV284 - East Kentucky Network, LLC d/b/a Appalachian Wireless

Call Sign	WPWV284	Radio Service	WZ - 700 MHz Lower Band (Blocks C, D)
Status	Active	Auth Type	Regular

### Rural Service Provider Bidding Credit

Is the Applicant seeking a Rural Service Provider (RSP) bidding credit?

### Reserved Spectrum

Reserved Spectrum

### Market

Market	CMA453 - Kentucky 11 - Clay	Channel Block	C
Submarket	0	Associated Frequencies (MHz)	000710.00000000-000716.00000000 000740.00000000-000746.00000000

### Dates

Grant	01/24/2003	Expiration	06/13/2019
Effective	11/02/2013	Cancellation	

### Buildout Deadlines

1st	06/13/2019	2nd	
-----	------------	-----	--

### Notification Dates

1st		2nd	
-----	--	-----	--

### Licensee

FRN	0001786607	Type	Limited Liability Company
-----	------------	------	---------------------------

### Licensee

East Kentucky Network, LLC d/b/a Appalachian Wireless 101 Technology Trail Ivel, KY 41642 ATTN W.A. Gillum, General Manager/CEO	P:(606)477-2355
--	-----------------

### Contact

Lukas, Nace, Gutierrez & Sachs, LLP Pamela L Gist Esq 8300 Greensboro Drive McLean, VA 22102	P:(703)584-8665 F:(703)584-8695 E:pgist@fcclaw.com
---	--

### Ownership and Qualifications

Radio Service Type	Fixed, Mobile, Radio Location		
Regulatory Status	Common Carrier, Non-Common Carrier	Interconnected	Yes

### Alien Ownership

The Applicant answered "No" to each of the Alien Ownership questions.

### Basic Qualifications

The Applicant answered "No" to each of the Basic Qualification questions.

### Tribal Land Bidding Credits

This license did not have tribal land bidding credits.

### Demographics

Race	
Ethnicity	Gender

## **EXHIBIT 2 – LIST OF PROPERTY OWNERS**

### **Statement Pursuant to Section 1 (1) (I) 807 KAR 5:063**

**Section 1 (1)(I) 1.** The following is a list of every property owner who according to property valuation administrator's records, owns property within 500 feet of the proposed tower and each have been: notified by certified mail, return receipt requested, of the proposed construction,

**Section 1 (1)(I) 2.** Every person listed below who, according to the property valuation administrator's records, owns property within 500 feet of the proposed tower has been: Given the Commission docket number under which the application will be processed: and

**Section 1 (1)(I) 3.** Every person listed below who, according to property valuation administrator's records owns property within 500 feet of the proposed tower has been: Informed of his right to request intervention.

**Section 2.** If the construction is proposed for an area outside the incorporated boundaries of a city, the application shall state that public notices required by Section 1(1)(L) have been sent to every person who, according to the property valuation administrator, owns property contiguous to the property upon which the construction is proposed

#### **LIST OF PROPERTY OWNERS**

Richard Calloway  
562 Halls Hollow Road  
Hulen, KY 40845

Richard Dale and Sharon Calloway  
P.O. Box 203  
Calvin, KY 40845

Donald and Doris Wilson Trustees  
Wilson Family Revocable Trust  
1344 Pennsylvania Ave.  
Des Plains, IL 60018

Kentucky Natural Lands Trust, Inc.  
433 Chestnut Street  
Berea, KY 40402

Margrie Hall  
246 Eaton Road  
London, KY 40741



Muriel J. Calloway Harbin  
42 Mink Lane  
Pineville, KY 40977

VIA: U.S. CERTIFIED MAIL

PUBLIC NOTICE

August 30, 2018

Richard Calloway  
562 Halls Hollow Road  
Hulen, KY 40845

RE: Public Notice-Public Service Commission of Kentucky (Case No. 2018-00283)

East Kentucky Network, LLC d/b/a Appalachian Wireless has applied to the Public Service Commission of Kentucky for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide cellular telecommunications service in Bell County. The facility will include a 300-foot self-supporting tower with attached antennas extending upwards, and an equipment shelter located on a tract of land near 565 Halls Hollow Road, Pineville, Bell County. A map showing the location of the proposed new facility is enclosed. This notice is being sent to you because you may own property within a 500' radius of the proposed tower or own property contiguous to the property upon which construction is proposed.

The Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. The Commission must receive your initial communication within 20 days of the date of this letter as shown above.

Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, P.O. Box 615, Frankfort, KY 40602. Please refer to Case No. 2018-00283 in your correspondence.

If you have any questions for East Kentucky Network, LLC, please direct them to my attention at the following address: East Kentucky Network, LLC, 101 Technology Trail, Ivel, KY 41642 or call me at 606-477-2355, Ext. 1007.

Sincerely,



Lynn Haney, CPA  
Regulatory Compliance Director  
Enclosure 1

VIA: U.S. CERTIFIED MAIL

PUBLIC NOTICE

August 30, 2018

Richard Dale and Sharon Calloway  
P.O. Box 203  
Calvin, KY 40845

RE: Public Notice-Public Service Commission of Kentucky (Case No. 2018-00283)


East Kentucky Network, LLC d/b/a Appalachian Wireless has applied to the Public Service Commission of Kentucky for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide cellular telecommunications service in Bell County. The facility will include a 300-foot self-supporting tower with attached antennas extending upwards, and an equipment shelter located on a tract of land near 565 Halls Hollow Road, Pineville, Bell County. A map showing the location of the proposed new facility is enclosed. This notice is being sent to you because you may own property within a 500' radius of the proposed tower or own property contiguous to the property upon which construction is proposed.

The Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. The Commission must receive your initial communication within 20 days of the date of this letter as shown above.

Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, P.O. Box 615, Frankfort, KY 40602. Please refer to Case No. 2018-00283 in your correspondence.

If you have any questions for East Kentucky Network, LLC, please direct them to my attention at the following address: East Kentucky Network, LLC, 101 Technology Trail, Ivel, KY 41642 or call me at 606-477-2355, Ext. 1007.

Sincerely,



Lynn Haney, CPA  
Regulatory Compliance Director  
Enclosure 1



VIA: U.S. CERTIFIED MAIL

PUBLIC NOTICE

August 30, 2018

Donald and Doris Wilson Trustees  
Wilson Family Revocable Trust  
1344 Pennsylvania Ave.  
Des Plains, IL 60018

RE: Public Notice-Public Service Commission of Kentucky (Case No. 2018-00283)


East Kentucky Network, LLC d/b/a Appalachian Wireless has applied to the Public Service Commission of Kentucky for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide cellular telecommunications service in Bell County. The facility will include a 300-foot self-supporting tower with attached antennas extending upwards, and an equipment shelter located on a tract of land near 565 Halls Hollow Road, Pineville, Bell County. A map showing the location of the proposed new facility is enclosed. This notice is being sent to you because you may own property within a 500' radius of the proposed tower or own property contiguous to the property upon which construction is proposed.

The Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. The Commission must receive your initial communication within 20 days of the date of this letter as shown above.

Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, P.O. Box 615, Frankfort, KY 40602. Please refer to Case No. 2018-00283 in your correspondence.

If you have any questions for East Kentucky Network, LLC, please direct them to my attention at the following address: East Kentucky Network, LLC, 101 Technology Trail, Ivel, KY 41642 or call me at 606-477-2355, Ext. 1007.

Sincerely,



Lynn Haney, CPA  
Regulatory Compliance Director  
Enclosure 1

VIA: U.S. CERTIFIED MAIL

PUBLIC NOTICE

August 30, 2018

Kentucky Natural Lands Trust, Inc.  
433 Chestnut Street  
Berea, KY 40402

RE: Public Notice-Public Service Commission of Kentucky (Case No. 2018-00283)

East Kentucky Network, LLC d/b/a Appalachian Wireless has applied to the Public Service Commission of Kentucky for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide cellular telecommunications service in Bell County. The facility will include a 300-foot self-supporting tower with attached antennas extending upwards, and an equipment shelter located on a tract of land near 565 Halls Hollow Road, Pineville, Bell County. A map showing the location of the proposed new facility is enclosed. This notice is being sent to you because you may own property within a 500' radius of the proposed tower or own property contiguous to the property upon which construction is proposed.

The Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. The Commission must receive your initial communication within 20 days of the date of this letter as shown above.

Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, P.O. Box 615, Frankfort, KY 40602. Please refer to Case No. 2018-00283 in your correspondence.

If you have any questions for East Kentucky Network, LLC, please direct them to my attention at the following address: East Kentucky Network, LLC, 101 Technology Trail, Ivel, KY 41642 or call me at 606-477-2355, Ext. 1007.

Sincerely,



Lynn Haney, CPA  
Regulatory Compliance Director  
Enclosure 1





VIA: U.S. CERTIFIED MAIL

PUBLIC NOTICE

August 30, 2018

Margrie Hall  
246 Eaton Road  
London, KY 40741

RE: Public Notice-Public Service Commission of Kentucky (Case No. 2018-00283)

East Kentucky Network, LLC d/b/a Appalachian Wireless has applied to the Public Service Commission of Kentucky for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide cellular telecommunications service in Bell County. The facility will include a 300-foot self-supporting tower with attached antennas extending upwards, and an equipment shelter located on a tract of land near 565 Halls Hollow Road, Pineville, Bell County. A map showing the location of the proposed new facility is enclosed. This notice is being sent to you because you may own property within a 500' radius of the proposed tower or own property contiguous to the property upon which construction is proposed.

The Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. The Commission must receive your initial communication within 20 days of the date of this letter as shown above.

Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, P.O. Box 615, Frankfort, KY 40602. Please refer to Case No. 2018-00283 in your correspondence.

If you have any questions for East Kentucky Network, LLC, please direct them to my attention at the following address: East Kentucky Network, LLC, 101 Technology Trail, Ivel, KY 41642 or call me at 606-477-2355, Ext. 1007.

Sincerely,

Lynn Haney, CPA  
Regulatory Compliance Director  
Enclosure 1

VIA: U.S. CERTIFIED MAIL

PUBLIC NOTICE

August 30, 2018

Muriel J. Calloway Harbin  
42 Mink Lane  
Pineville, KY 40977

RE: Public Notice-Public Service Commission of Kentucky (Case No. 2018-00283)

East Kentucky Network, LLC d/b/a Appalachian Wireless has applied to the Public Service Commission of Kentucky for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide cellular telecommunications service in Bell County. The facility will include a 300-foot self-supporting tower with attached antennas extending upwards, and an equipment shelter located on a tract of land near 565 Halls Hollow Road, Pineville, Bell County. A map showing the location of the proposed new facility is enclosed. This notice is being sent to you because you may own property within a 500' radius of the proposed tower or own property contiguous to the property upon which construction is proposed.

The Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. The Commission must receive your initial communication within 20 days of the date of this letter as shown above.

Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, P.O. Box 615, Frankfort, KY 40602. Please refer to Case No. 2018-00283 in your correspondence.

If you have any questions for East Kentucky Network, LLC, please direct them to my attention at the following address: East Kentucky Network, LLC, 101 Technology Trail, Ivel, KY 41642 or call me at 606-477-2355, Ext. 1007.

Sincerely,



Lynn Haney, CPA  
Regulatory Compliance Director  
Enclosure 1




# Hulen

Location:

565 Halls Hollow Road  
Pineville, KY 40977

Coordinates:

36°47'24.94"N  
83°31'59.74"W





VIA: U.S. CERTIFIED MAIL

August 30, 2018

Albey Brock, Judge Executive  
P.O. Box 339  
Pineville, KY 40977

RE: Public Notice-Public Service Commission of Kentucky (Case No. 2018-00283)

East Kentucky Network, LLC d/b/a Appalachian Wireless has applied to the Public Service Commission of Kentucky for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide cellular telecommunications service in Bell County. The facility will include a 300-foot self-supporting tower with attached antennas extending upwards, and an equipment shelter located on a tract of land at 565 Halls Hollow Road, Pineville, Bell County, Kentucky. A map showing the location of the proposed new facility is enclosed. This notice is being sent to you because you are the County Judge Executive of Bell County.

The Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. The Commission must receive your initial communication within 20 days of the date of this letter as shown above.

Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, P.O. Box 615, Frankfort, KY 40602. Please refer to Case No. 2018-00283 in your correspondence.

If you have any questions for East Kentucky Network, LLC, please direct them to my attention at the following address: East Kentucky Network, LLC, 101 Technology Trail, Ivel, KY 41642 or call me at 606-477-2355, Ext. 1007.

Sincerely,



Lynn Haney  
Regulatory Compliance Director  
Enclosure

dba Appalachian Wireless  
101 Technology Trail  
Ivel, KY 41642  
Phone: 606-477-2355  
Fax: 606-791-2225

## EAST KENTUCKY NETWORK



**To:** The Pineville Sun  
Attn: Classifieds

**From:** Raina Helton  
Regulatory Compliance Assistant

**Email:** [advertising@thepinevillesun.com](mailto:advertising@thepinevillesun.com)

**Date:** August 22, 2018

**Re:** PUBLIC NOTICE ADVERTISEMENT

**Pages:** 1

**Please place the following Public Notice Advertisement in The Pineville Sun to be ran on August 30, 2018.**

**PUBLIC NOTICE:**

RE: Public Service Commission of Kentucky (CASE NO. 2018-00283)

Public Notice is hereby given that East Kentucky Network, LLC, dba Appalachian Wireless has applied to the Kentucky Public Service Commission to construct a cellular telecommunications tower on a tract of land located at 565 Halls Hollow Road, Pineville, Bell County, Kentucky. The proposed tower will be a 300 foot self-supporting tower with attached antennas. If you would like to respond to this notice, please contact the Executive Director, Public Service Commission, 211 Sower Boulevard, PO Box 615, Frankfort, Kentucky 40602. Please refer to Case No. 2018-00283.

If you have any questions about the placement of the above mentioned notice, please call me at 606-477-2375, ext. 1005.

Thank you,

Raina Helton  
Regulatory Compliance Assistant

The message above and the information contained in the documents transmitted are confidential and intended only for the person(s) named above. Dissemination, distribution or copying of this communication by anyone other than the person(s) named above is prohibited. If you have received this communication in error, please notify us immediately by telephone and return the original message to us at the address listed above via regular mail. Thank you.




# Hulen

Location:

565 Halls Hollow Road  
Pineville, KY 40977

Coordinates:

36°47'24.94"N  
83°31'59.74"W







230 Swartz Drive • Hazard • Kentucky • 41701  
Phone (606) 551-1050

---

**EAST KENTUCKY ENGINEERING, LLC.**

**APPALACHIAN WIRELESS  
Geotechnical Investigation on the  
Hulen Tower Site  
Bell County, Kentucky  
EKYENG Project No. 165-000-0064**

PREPARED FOR:  
Appalachian Wireless.  
101 Technology Trail  
Ivel, Kentucky 41642

PREPARED BY:  
Richard Dirk Smith PE, PLS  
President  
**East Kentucky Engineering**  
230 Swartz Drive  
Hazard, Kentucky 41701



, 20215, June 10<sup>th</sup>, 2018



# **EAST KENTUCKY ENGINEERING, LLC.**

---

## **EXECUTIVE SUMMARY**

### **1.0 INTRODUCTION**

### **2.0 PROJECT DESCRIPTION**

### **3.0 SITE DESCRIPTION & HISTORICAL MINING**

#### **3.1 GENERAL INFORMATION**

#### **3.2 SURFACE MINING**

#### **3.3 UNDERGROUND MINING**

### **4.0 FIELD EXPLORATION**

#### **4.1 SITE INFORMATION**

#### **4.2 TEST PITS**

#### **4.3 GROUNDWATER**

#### **4.4 SEISMIC SITE CLASSIFICATION**

### **5.0 DISCUSSION AND RECOMMENDATIONS**

#### **5.1 GENERAL**

#### **5.2 SHALLOW MAT FOUNDATIONS RECOMMENDATIONS**

#### **5.3 BURIED UTILITIES**

### **6.0 WARRANTY**

#### **6.1 SUBSURFACE EXPLORATION**

#### **6.2 LABORATORY AND FIELD TEST**

#### **6.3 ANALYSIS AND RECOMMENDATIONS**

#### **6.4 CONSTRUCTION MONITORING**

#### **6.5 GENERAL**

## **SPECIFICATIONS**

### **I – GENERAL**

### **II – ENGINEERED FILL BENEATH STRUCTURES CLEARING AND GRADING**

### **SPECIFICATIONS**

### **III – GUIDELINES FOR EXCAVATIONS AND TRENCHING**

### **IV – GENERAL CONCRETE SPECIFICATIONS**

### **V – DRILLED PIER INSTALLATION**

## **APPENDIX A – PHOTOGRAPHS**

## **APPENDIX B – SEISMIC DATA**

## **APPENDIX C – MAPS**



## EAST KENTUCKY ENGINEERING, LLC.

### EXECUTIVE SUMMARY

A geotechnical investigation has been performed on the Hulen Tower Site, located in Bell County, Kentucky. This site is not readily accessible. A location map is shown in Figure 1 of this report. Field inspections were completed by digging open pits by hand. Access to this site with equipment is limited. The following geotechnical considerations were identified:

- Pit excavations and sounding that were utilized for this study encountered mine spoils and underground mine coal waste.
- The maximum estimated base elevation of tower mat foundation is 1299 ft.
- This site is an old mine waste site with thick vegetation.
- **The allowable bearing capacities is estimated at 1200 psf once the recommended remediation has been completed.**
- The 2015 International Building Code seismic site classification for this site is "C."
- If during the foundation design it becomes necessary to lower or raise the footer, alternate design recommendations can be provided by EKYENG.
- Once equipment access is available, we recommend that this tower location is re-evaluated to better validate the depth and consistency of the underlying soils.
- Close monitoring of the construction operations discussed herein will be critical in achieving the design subgrade support. We, therefore, recommend that EKYENG is retained to monitor this portion of the work.

This executive summary is included to provide a general overview of the project and should not be relied upon except for the purpose it was prepared. Please rely on the complete report for the information on the findings, recommendations, and all other concerns.





Drawn: RDS	Date: 05/07/18
Job: 165-064	Scale: 1"=1000'

Appalachian Wireless  
 USGS Quadrangle  
 Location Map  
 Hulen Tower Site  
 Figure No. 1

East Kentucky Engineering, LLC.  
 230 Swartz Drive  
 Hazard, KY 41701  
 (606) 551-1050





## **EAST KENTUCKY ENGINEERING, LLC.**

### **3.0 SITE DESCRIPTION & HISTORICAL MINING**

#### **3.1 GENERAL INFORMATION**

The site location is on rolling terrain on a reclaimed surface mine, in Bell County, Kentucky. The current surface elevation is approximately 1306 ft. Research on the historical mining was conducted by obtaining previous mine license maps from the "Kentucky Mine Mapping Information System" (KMMIS).

#### **3.2 SURFACE MINING**

This site appears to be an old mine waste pile that was placed on an old Mason Coal Seam strip mine bench. During our research no mine mapping was found to validate this but based upon our field investigations, geologic map interpretation and calculations we have estimated the depth to rock up to approximately 140 ft.

#### **3.3 UNDERGROUND MINING**


No underground mines were found within the vicinity of this site. Therefore, no subsidence issues are anticipated.

### **4.0 FIELD EXPLORATION**

#### **4.1 SITE INFORMATION**

The proposed site is located on a reclaimed mine site in Bell County, Kentucky. The site lies within the Balkan Quadrangle. The site is not readily accessible by conventional exploratory equipment. An estimated pad location was determined based on the information provided. Foundation dimensions were estimated to be a 43.5 ft. X 43.5 ft. footer for this report.





Drawn: RDS	Date: 05/07/18
Job: 165-064	Scale: 1"=1000'

Appalachian Wireless  
USGS Quadrangle  
Location Map  
Hulen Tower Site  
Figure No. 1

East Kentucky Engineering, LLC.  
230 Swartz Drive  
Hazard, KY 41701  
(606) 551-1050





## EAST KENTUCKY ENGINEERING, LLC.

### 4.2 TEST PITS

This investigation was conducted by excavating two (2) pits by hand. Test holes are shown on the attached maps in Appendix C. The combinations of pits, and visual inspections were conducted to evaluate the site lithology and type of materials immediately below the proposed tower site. The following soils and rock properties were found.

TABLE 2  
PIT EXCAVATION / SOUNDING

Test Pit	DEPTH INCREMENT, (FT.)	SOILS TYPE
TH1	3.0 / 4.0	Mine Waste
TH2	3.0 / 4.0	Mine Waste

*Note: A cross-section of this information is in Appendix C of this report*

### 4.3 GROUNDWATER

Groundwater in Eastern Kentucky is characterized by water flowing through a system of internal fractures that lead to an alluvial aquifer near the bottom of valley floors. Large, defined aquifers other than the alluvium is not common, especially in higher elevations such as where this tower site is proposed. Therefore, groundwater should not be a concern in this area. During boring activities, no groundwater resources were observed.

### 4.4 SEISMIC SITE CLASSIFICATION

Based on the encountered soil conditions at the project site, the site classification was determined to be "Site Class C" per the 2015 Kentucky Building Code. In addition, an  $S_{DS}$  coefficient of 0.230 g was calculated, and an  $S_{D1}$  coefficient of



## EAST KENTUCKY ENGINEERING, LLC.

0.118 g was also calculated for design based on the aforementioned building code.

### 5.0 DISCUSSION AND RECOMMENDATIONS

#### 5.1 GENERAL

The structure will be a self-supporting free-standing tri-pole tower. Due to wind loading, lattice tower foundations can experience both vertical loads and horizontal loads. The vertical loads act in both an upward and downward direction as the tower attempts to overturn and can act in any directions. Due to the estimated depth to rock of up to 140 ft, it is probably non-economical to use deep foundations.

#### 5.2 SHALLOW MAT FOUNDATIONS RECOMMENDATIONS

Typically, we do not recommend shallow foundations on sites consisting of spoil. Settlement can and is likely to occur once the final structure's loading is in place. No settlement calculations have been evaluated for this report. If shallow foundations are used, it should be noted that the material type and bearing capacity can vary significantly due to the inconsistency of the underlying material. Based on the laboratory and field testing, visual inspection of the materials and practical experience we have estimated that the **allowable bearing capacity at this site will be 1200 psf once the following remediation is completed.**

If shallow foundations are used, we recommend that the site is over excavated to a minimum of eight (8) ft. below the footing subgrade and ten (10) ft. outside the footing area. Any large rock and unsuitable material be removed and backfilled with a select backfill or dense grade aggregate. The material is to be placed in 8-inch horizontal lifts, compacted to not less than 95% of the maximum density as determined by the standard Proctor dry unit weight (ASTM D-968) and within +2% and -2% of the optimum moisture content. This remediation should assist in preventing differential settlement.



## EAST KENTUCKY ENGINEERING, LLC.

---

It is furthermore recommended that the slabs-on-grade be supported on a 4 to 6-inch layer of relatively clean granular material such as sand and gravel or crushed stone. This is to help distribute concentrated loads and equalize moisture conditions beneath the slab. Proper drainage must be incorporated into this granular layer to preclude future wet areas in the finished slab-on-grade. However, all topsoil and/or other deleterious materials encountered during site preparation must be removed and replaced with 4000 psi. concrete below the foundation base. Provided that a minimum of 4 inches of granular material is placed below the new slab-on-grade, a modulus of subgrade reaction ( $k_{30}$ ) of 100 lbs./cu. in. can be used for the design of the slabs.

Support structure for this tower can be placed as needed. It is recommended that test pits are examined to ensure that any of these structures are on the competent materials. If pockets of soft, loose or otherwise unsuitable material are encountered in the footing excavations, and it is inconvenient to lower the footings, the proposed footing elevations may be re-established by backfilling after the undesirable material has been removed. The undercut excavation beneath each footing should extend to suitable bearing soils, and the dimensions of the excavation base should be determined by imaginary planes extending outward and down on a 1 (vertical) to 1 (horizontal) slope from the base perimeter of the footing. The entire excavation should then be refilled with a well-compacted engineered fill, or lean concrete (Please note that the width of the lean concrete zone should be equal or wider than the width of the overlying footing element). Special care should be exercised to remove any sloughed, loose or soft materials near the base of the excavation slopes. In addition, special care should be taken to "tie-in" the compacted fill with the excavation slopes, with benches as necessary, to ensure that no pockets of loose or soft materials will be left in place along the excavation slopes below the foundation bearing level. All Federal, State, and Local regulations should be strictly adhered to relative to excavation side-slope geometry.



## **EAST KENTUCKY ENGINEERING, LLC.**

---

### **5.3 BURIED UTILITIES**

Excavations for buried utility pipelines should follow the guidelines set forth in this report. Depending on the pipeline material, a minimum thickness of at least 0.5 feet of select fine-grained granular bedding material should be used beneath all below-grade pipes, with a minimum cover thickness of at least 3 feet to afford an "arching" effect and reduce stresses on the pipe. The cover thickness may be reduced if the external loading condition on the pipe is relatively light or if the pipe is designed to withstand the external loading condition. It is not recommended that "pea-gravel" or other "open-work" aggregates be used for trench backfill since these materials are nearly impossible to compact and tend to pond water within their interstices.

## **6.0 WARRANTY**

Our professional services have been performed, our findings obtained, and our recommendations prepared in accordance with generally accepted geotechnical engineering principles and practices. No other warranty, express or implied, is made.

While the services of EKYENG are a valuable and integral part of the design and construction teams, we do not warrant, guarantee, or ensure the quality or completeness of services provided by other members of those teams, the quality, completeness, or satisfactory performance of construction plans and specifications which we have not prepared, nor the ultimate performance of building site materials.

### **6.1 SUBSURFACE EXPLORATION**

Subsurface exploration is normally accomplished by test borings, although test pits are sometimes employed. The method of determining the boring location and the surface elevation at the boring is noted in the report and is presented on the Boring Location Plan or on the boring log. The location and elevation of the



## **EAST KENTUCKY ENGINEERING, LLC.**

---

boring should be considered accurate only to the degree inherent with the method used.

The boring log includes sampling information, description of the materials recovered, approximate depth of boundaries between soil and rock strata and groundwater data. The boring log represents conditions specifically at the location and time the boring was made. The boundaries between different soil strata are indicated at specific depths; however, these depths are in fact approximate and are somewhat dependent upon the frequency of sampling (The transition between soil strata is often gradual). Free groundwater level readings are made at the times and under conditions stated on the boring logs (Groundwater levels change with time and season). The borehole does not always remain open sufficiently long enough for the measured water level to coincide with the groundwater table.

### **6.2 LABORATORY AND FIELD TESTS**

Laboratory and field tests are performed by specific ASTM standards unless otherwise indicated. All determinations included in each ASTM standard are not always required and performed. Each test report indicates the measurements and determinations made.

### **6.3 ANALYSIS AND RECOMMENDATIONS**

The geotechnical report is prepared primarily to aid in the engineering design of site work and structural foundations. Although the information in the report is expected to be sufficient for these purposes, it is not intended to determine the cost of construction or to stand alone as a construction specification.

Our engineering report recommendations are based primarily on data from test borings made at the locations shown in a boring location drawing included. Soil variations may exist between borings, and these variations may not become evident until construction. If significant variations are then noted, the geotechnical



## **EAST KENTUCKY ENGINEERING, LLC.**

---

engineer should be contacted so that field conditions can be examined and recommendations revised if necessary.

The geotechnical engineering report states our understanding as to the location, dimensions and structural features proposed for the site. Any significant changes in the nature, design, or location of the site improvements **MUST** be communicated to the geotechnical engineer such that the geotechnical analysis, conclusions, and recommendations can be appropriately adjusted. The geotechnical engineer should be given the opportunity to review all drawings that have been prepared based on their recommendations.

### **6.4 CONSTRUCTION MONITORING**

Construction monitoring is a vital element of complete geotechnical services. The field engineer/inspector is the owner's "representative" observing the work of the contractor, performing tests as required in the specifications, and reporting data developed from such tests and observations. The field engineer or inspector does not direct the contractor's construction means, methods, operations or personnel. The field inspector/engineer does not interfere with the relationship between the owner and the contractor and, except as an observer, does not become a substitute owner on site. The field inspector/engineer is responsible for his own safety but has no responsibility for the safety of other personnel at the site. The field inspector/engineer is an important member of a team whose responsibility is to watch and test the work being done and report to the owner whether that work is being carried out in general conformance with the plans and specifications.

### **6.5 GENERAL**

The scope of our services did not include an environmental assessment for the presence or absence of hazardous or toxic materials in the soil, surface water, groundwater or air, on, within or beyond the site studied. Any statements in the report or on the boring logs regarding odors, staining of soils or other unusual items or conditions observed are strictly for the information of our client.



## **EAST KENTUCKY ENGINEERING, LLC.**

---

To evaluate the site for possible environmental liabilities, we recommend an environmental assessment, consisting of a detailed site reconnaissance, a record review, and report of findings. Additional subsurface drilling and samplings, including groundwater sampling, may be required.

This report has been prepared for the exclusive use of Appalachian Wireless, for specific application to the proposed cellular tower located on the Hulen Property located in Bell County, Kentucky. Specific design and construction recommendations have been provided in the various sections of the report. The report shall, therefore, be used in its entirety. This report is not a bidding document and shall not be used for that purpose. Anyone reviewing this report must interpret and draw their conclusions regarding the specific construction techniques and methods that were chosen. EKYENG is not responsible for the independent conclusions, opinions or recommendations made by others based on the field exploratory and laboratory test data presented in this report.





## EAST KENTUCKY ENGINEERING, LLC.

### SPECIFICATIONS

#### I – GENERAL

##### 1.0 STANDARDS AND DEFINITIONS

##### 1.1 STANDARDS - All standards refer to latest edition unless otherwise noted.

1.1.1 ASTM D-698-70 (Method C) "Standard Test Methods for Moisture, Density Relations of Soils and Soil Aggregate Mixtures Using 5.5-lb (2.5 kg.) Rammer and 12-inch (305-mm) Drop".

1.1.2 ASTM D-2922 "Standard Test Method for Density of Soil and Soil Aggregate in Place by Nuclear methods (Shallow Depth)".

1.1.3 ASTM D-1556 "Standard Test Method for Density of Soil in place by the Sand-Cone Method".

##### 1.2 DEFINITIONS

1.2.1 Owner - In these specifications the word "Owner" shall mean Appalachian Wireless.

1.2.2 Engineer - In these specifications the word "Engineer" shall mean the Owner designated engineer.

1.2.3 Design Engineer - In these specifications the words "Design Engineer" shall mean the Owner designated design engineer.

1.2.4 Contractor - In these specifications the word "Contractor" shall mean the firm or corporation undertaking the execution of any work under the terms of these specifications.

1.2.5 Approved - In these specifications the word "approved" shall refer to the approval of the Engineer or his designated representative.

1.2.6 As Directed - In these specifications the words "as directed" shall refer to the directions to the Contractor from the Owner or his designated representative.



## EAST KENTUCKY ENGINEERING, LLC.

---

### **2.0 GENERAL CONDITIONS**

- 2.1** The Contractor shall furnish all labor, material and equipment and perform all work and services except those set out and furnished by the Owner, necessary to complete in a satisfactory manner the site preparation, excavation, filling, compaction, grading as shown on the plans and as described therein.

This work shall consist of all mobilization clearing and grading, grubbing, stripping, removal of existing material unless otherwise stated, preparation of the land to be filled, filling of the land, spreading and compaction of the fill, and all subsidiary work necessary to complete the grading of the cut and fill areas to conform with the lines, grades, slopes, and specifications.

This work is to be accomplished under the observation of the Owner or his designated representative.

- 2.2** Prior to bidding the work, the Contractor shall examine, investigate and inspect the construction site as to the nature and location of the work, and the general and local conditions at the construction site, including, without limitation, the character of surface or subsurface conditions and obstacles to be encountered on and around the construction site; and shall make such additional investigation as he may deem necessary for the planning and proper execution of the work.

If conditions other than those indicated are discovered by the Contractor, the Owner should be notified immediately. The material which the Contractor believes to be a changed condition should not be disturbed so that the owner can investigate the condition.

- 2.3** The construction shall be performed under the direction of an experienced engineer who is familiar with the design plan.





## **EAST KENTUCKY ENGINEERING, LLC.**

### **II - ENGINEERED FILL BENEATH STRUCTURES CLEARING AND GRADING SPECIFICATIONS**

#### **1.0 GENERAL CONDITIONS**

The Contractor shall furnish all labor, materials, and equipment, and perform all work and services necessary to complete in a satisfactory manner the site preparation, excavation, filling, compaction and grading as shown on the plans and as described therein.

This work shall consist of all clearing and grading, removal of existing structures unless otherwise stated, preparation of the land to be filled, filling of the land, spreading and compaction of the fill, and all subsidiary work necessary to complete the grading of the cut and fill areas to conform with the lines, grades, slopes, and specifications.

This work is to be accomplished under the constant and continuous supervision of the Owner or his designated representative.

In these specifications, the terms "approved" and "as directed" shall refer to directions to the Contractor from the Owner or his designated representative.

#### **2.0 SUBSURFACE CONDITIONS**

Prior to bidding the work, the Contractor shall examine, investigate and inspect the construction site as to the nature and location of the work, and the general and local conditions at the construction site, including without limitation, the character of surface or subsurface conditions and obstacles to be encountered on and around the construction site; and shall make such additional investigation as he may deem necessary for the planning and proper execution of the work. Borings and/or soil investigations shall have been made. Results of these borings and studies will be made available by the Owner to the Contractor upon his request, but the Owner is not responsible for any interpretations or conclusions with respect thereto made by the Contractor based on such information, and the Owner further has no responsibility for the accuracy of the borings and the soil investigations.

If conditions other than those indicated are discovered by the Contractor, the Owner should be notified immediately. The material which the Contractor believes to be a changed condition should not be disturbed so that the Owner can investigate the condition.

#### **3.0 SITE PREPARATION**

Within the specified areas, all trees, brush, stumps, logs, tree roots, and structures scheduled for demolition shall be removed and disposed of.

All cut, and fill areas shall be properly stripped. Topsoil will be removed to its full depth and stockpiled for use in finish grading. Any rubbish, organic and other objectionable soils, and other deleterious material shall be disposed of off the site, or as directed by the Owner or his designated representative if on site disposal is provided. In no case shall such objectionable material be allowed in or under the fill unless specifically authorized in writing.



## EAST KENTUCKY ENGINEERING, LLC.

---

Prior to the addition of fill, the original ground shall be compacted to job specifications as outlined below. Special notice shall be given to the proposed fill area now. If wet spots, spongy conditions, or groundwater seepage is found, corrective measures must be taken before the placement of fill.

### **4.0 FORMATION OF FILL AREAS**

Fills shall be formed of satisfactory materials placed in successive horizontal layers of not more than eight (8) inches in loose depth for the full width of the cross-section. The depth of lift may be increased if the Contractor can demonstrate the ability to compact a larger lift. If compaction is accomplished using hand-tamping equipment, lifts will be limited to 4-inch loose lifts. Engineered fill placed below the structure bearing elevation shall be compacted to at least 95% of the maximum dry unit weight with a moisture content within 2% of the optimum moisture content as determined by the modified Proctor test. The top size of the material placed shall not exceed 4 inches.

All material entering the fill shall be free of organic matter such as leaves, grass, roots, and other objectionable material.

The operations on earth work shall be suspended at any time when satisfactory results cannot be obtained because of rain, freezing weather, or other unsatisfactory conditions. The Contractor shall keep the work areas graded to provide the drainage always.

The fill material shall be of the proper moisture content before compaction efforts are started. Wetting or drying of the material and manipulation to secure a uniform moisture content throughout the layer shall be required. Should the material be too wet to permit proper compaction or rolling, all work thus affected shall be delayed until the material has dried to the required moisture content. The moisture content of the fill material should be no more than two (2) percentage points higher or lower than optimum unless otherwise authorized. Sprinkling shall be done with equipment that will satisfactorily distribute the water over the disced area. Any areas inaccessible to a roller shall be consolidated and compacted by mechanical tampers. The equipment shall be operated in such a manner that hardpan, cemented gravel, clay or other chunky soil material will be broken up into small particles and become incorporated with the other material in the layer.

In the construction of filled areas, starting layers shall be placed in the deepest portion of the fill, and as placement progresses, additional layers shall be constructed in horizontal planes. Original slopes shall be continuously, vertically benched to provide horizontal fill planes. The size of the benches shall be formed so that the base of the bench is horizontal, and the back of the bench is vertical. As many benches as are necessary to bring the site to final grade shall be constructed. Filling operations shall begin on the lowest bench, with the fill being placed in horizontal eight (8) inch thick loose lifts unless otherwise authorized. The filling shall progress in this manner until the entire first bench has been filled, before any fill is placed on the succeeding benches. Proper drainage shall be maintained always during benching and filling of the benches, to ensure that all water is drained away from the fill area.



## **EAST KENTUCKY ENGINEERING, LLC.**

---

Frozen material shall not be placed in the fill nor shall the fill be placed upon frozen material.

The Contractor shall be responsible for the stability of all fills made under the contract, and shall replace any portion, which in the opinion of the Owner or his designated representative, has become displaced due to carelessness or negligence on the part of the Contractor. Fill damaged by inclement weather shall be repaired at the Contractor's expense.

### **5.0 SLOPE RATIO AND STORM WATER RUN-OFF**

Slopes shall not be greater than 2 (horizontal) to 1 (vertical) in both cut and fill, or as illustrated on the construction drawings. Excavations shall be constructed in accordance with all Federal, State and local codes relative to slope geometry.

### **6.0 GRADING**

The Contractor shall furnish, operate, and maintain such equipment as is necessary to construct uniform layers, and control smoothness of grade for maximum compaction and drainage.

### **7.0 COMPACTING**

The compaction equipment shall be approved equipment of such design, weight, and quantity to obtain the required density in accordance with these specifications.

### **8.0 TESTING AND INSPECTION SERVICES**

Testing and inspection services will be provided by the Owner.



## EAST KENTUCKY ENGINEERING, LLC.

---

### lien GUIDELINES FOR EXCAVATIONS AND TRENCHES

The following represents some general guidelines relative to the design and construction of excavations and trenches. It must be emphasized that these guidelines are not intended to represent a "safety plan," but rather are presented herein to provide general guidance regarding the design characteristics and safety measures for excavations and trenches.

1. Check with the following utilities prior to breaking ground:
  - Sewer
  - Telephone
  - Fuel
  - Electric
  - Water
  - Gas
  - Cable

When utility companies or owners do not respond to your request within 48 hours, the contractor may only then proceed provided the contractor does so with caution by using detection equipment or other acceptable means to locate utility installations.

Once the excavation is open, the contractor should protect and support the exposed underground utilities or remove installations to safeguard workers and prevent damage to exposed utilities.

2. Access and egress ramps must be designed by a "competent person" and structural ramps used for equipment must be designed by a "competent person" with qualified knowledge in structural design. In addition:
  - Ramps must be secured to prevent displacement;
  - Ramps used in lieu of steps must have cleats to prevent slipping; and
  - Trenching excavations four feet or greater in depth must have a stairway, ladder, ramps or other safe means to egress with lateral travel no more than 25 feet.
3. Workers must be provided with reflector garments, such as warning orange or red vests, when exposed to vehicular traffic.
4. Contractors must not allow workers to work under or near equipment when there is danger of falling debris, spillage or equipment-related injuries.





## EAST KENTUCKY ENGINEERING, LLC.

---

5. Mobile equipment, operating adjacent to an open excavation or approaching the edge of an excavation, must have one of the following when the operator's view is obstructed:
  - Warning System
  - Mechanical Signals
  - Barricades
  - Stop Logs
  - Hand Signals
6. The contractor must check the atmosphere for hazardous gases and oxygen deficiencies when excavating four feet or greater around landfills, or when hazardous substances are stored nearby, and when the contractor expects there could be any exposure to the workers.
7. When hazardous atmospheric conditions exist, or when conditions could change, the contractor must make emergency rescue equipment readily available including breathing apparatus, safety harnesses with life lines and a basket stretcher.
8. When workers enter bell-bottom pier holes or other deep and confined excavations, the worker must wear (always while performing work in the confined space) a separate life line attached to a harness. The line must be attended by someone above while work is being performed. The worker must check for hazardous atmospheric conditions prior to entry.
9. The contractor must ensure that water does not accumulate in open excavations and must inspect the excavation prior to allowing workers to re-enter after heavy rains.
10. Adjacent structures (buildings, walls, etc.) must be supported or secured to prevent worker exposure to unsafe conditions and damage to existing structures.
11. A registered professional engineer must approve operations when a contractor underpins existing structures to ensure worker safety and prevent damage to existing structures.
12. Workers must not be exposed to loose soil and rock or materials in and around excavations. Materials, such as removed soil and rock, must not be stored closer than two feet from the edge of the excavation.
13. Daily inspections of the excavation, the adjacent areas and protective systems must be made by a "competent person" for evidence of possible cave-ins, indications of failure of protective systems, hazardous





## **EAST KENTUCKY ENGINEERING, LLC.**

---

atmospheres or other hazardous conditions. The "competent person" must stop work immediately and remove workers from the excavation when conditions change and pose a threat to their safety.

- 14.** Workers must not be exposed to fall hazards associated with excavations. Protective walkways or bridges with standard guard rails must be provided.
- 15.** All wells, pits, shafts etc. must be barricaded or covered. After completion of work, all wells, pits, shafts etc. must be backfilled.



## EAST KENTUCKY ENGINEERING, LLC.

---

### IV - GENERAL CONCRETE SPECIFICATIONS

#### 1.0 GENERAL

It is the intent of this specification to secure, for every part of the work, concrete of homogenous structure which, when hardened, will have the required strength and resistance to weathering. To this end, the limiting values of concrete and the requirements hereinafter specified must be met. Standard tests of the cement, aggregates, concrete and reinforcement will be made by the Owner as it sees fit. The Contractor shall furnish the material for all required samples plus such labor as required to obtain samples. The Contractor shall provide to authorized representatives of the Owner, convenient access to all parts of the work of all concreting operations for sampling and inspection.

#### 2.0 SCOPE

Contractor shall furnish all materials, labor, services, transportation, tools, equipment, and related items required to complete work indicated on the drawings and/or specified.

Unless otherwise noted or as modified by more stringent requirements specified herein, all plain and reinforced concrete work shall be performed in full compliance with applicable requirements of the Building Code Requirements for Reinforced Concrete ACI 318.

Contractor shall obtain Owner's approval of all subgrades, footing bottoms, forms, and reinforcement just prior to placing concrete.

Contractor shall coordinate the work specified in this section with that specified in other sections so that all anchors, pipes and other embedded items are properly installed before concrete is placed.

Contractor shall clean all exposed concrete surfaces and obtain approval of Owner for method of cleaning.

#### 3.0 MATERIALS

All materials shall be of the respective quality specified herein, delivered, stored, and handled as to prevent inclusion of foreign matter and damage by dampness or breakage. Packaged material shall be stored in original container until ready for use. Materials showing evidence of dampness or other damage may be rejected.

A. Fine and Coarse Aggregates: Coarse and fine aggregates shall conform to ASTM Specification C33. The maximum size of aggregate shall not be larger than one-fifth (1/5) of the narrowest dimensions between forms, or larger than three fourths (3/4) of the minimum clear spacing between reinforcement.

1. Fine Aggregate: Sand shall be composed essentially of clean, hard, strong, durable grains free of structurally weak grains, organic matter, loam, clay, silt, salt, mica or other fine materials that may affect bonding of the cement paste.



## EAST KENTUCKY ENGINEERING, LLC.

2. Coarse Aggregate: Cement concrete shall consist of crushed rock or screened gravel and shall be composed essentially of clean, hard, strong and impermeable particles, resistant to wear and frost and free from deleterious amounts of organic matter, loam, clay, salts, mica, and soft, thin, elongated, laminated or disintegrated stone, and shall be inert to water and cement.
- B. Portland Cement: Portland cement shall conform to ASTM Specification C150. Type I or Type II Portland Cement shall be used if they are not intermixed during any one batch. Type II Portland Cement shall not be used unless indicated on the plans.
- C. Water: Water for mixing and curing shall be clean, fresh, and free from deleterious materials.
- D. Metal Reinforcement: Rebar shall be Grade 60 and with deformations conforming to ASTM Specification A305. Welded wire mesh shall conform to W4 x W4 size and be of Grade 60 steel.
- E. Admixtures: Except as herein noted, admixtures shall not be used.
  1. Under adverse weather conditions only retarding or accelerating agents containing no chloride may be used.
  2. Air-Entraining Agent shall be used for all concrete will give an entrained air range of not less than 4 percent but no greater than 8 percent in the finished product. Under no circumstances shall the air-entraining be interground with cement.
  3. Approval in writing shall be required from Owner prior to the use of any admixture.

### 4.0 FORM

Forms shall be constructed with proper shoring and cross-bracing, safeguarding the total structure and specifically lateral stability and sufficiently strong to stand vibrations of concrete and to carry, without appreciable deflection or displacement, all dead and live loads to which they may be subjected.

### 5.0 INSERTS, ETC.

Anchors, bolts, dowels, conduit, water stops, vent pipes and other similar built-in or concreted-in items shall be properly located, accurately positioned and secured. The Contractor shall cooperate in placing of such items with other contractors who require a fastening device for their work and he shall maintain them in proper location during the progress of his work.

### 6.0 REINFORCEMENT



## EAST KENTUCKY ENGINEERING, LLC.

Reinforcement at the time concrete is placed shall be free from rust, scale or other coatings that will destroy or reduce the bond.

Reinforcement shall be accurately placed and securely tied at intersections and shall be securely held in position during the placing of concrete by pacers, chairs, or other approved supports.

The reinforcement of foundations, footings and other principal structural members in which the concrete is deposited against the ground shall not have less than three (3) inches of concrete between it and the ground contact surface. If concrete surfaces after removal of the forms are to be exposed to the weather or to be in contact with the ground or rock, reinforcement shall be protected with not less than two (2) inches of concrete,

### 7.0 CONCRETE

Concrete for the various parts of the work shall be of 4000 pounds per square inch compressive strength with a minimum 28-day cure. Contractor is responsible to provide a mix of not less than 6 bags of cement per yard of concrete and not more than 7 gallons of water per bag of cement, producing a minimum slump of 2-1/2 inches and a maximum slump of 4-1/2 inches. Concrete that exceeds the above range of maximum or minimum slump requirements may be rejected by the Owner. All concrete shall be air-entrained. Contractors are required to furnish the name or names of the company(s) that will be providing the mix. The Owner reserves the right to disapprove any concrete supplier that has been known to supply an undesirable material to the Owner on previous occasions.

### 8.0 DEPOSITING CONCRETE

4.1. Preparation for Placing Concrete: Before depositing concrete, the Contractor shall:

1. Remove from space to be occupied by concrete all debris, including snow, ice, and water unless otherwise permitted by Owner.
2. Provide diversion, satisfactory to Owner, of any flow of water to an excavation to avoid washing the freshly deposited concrete.
3. Coat the forms prior to placing of reinforcing steel as required in form work.
4. Secure firmly in correct position, all reinforcement and other items to be encased and remove therefrom all coating including ice and frost.

B. Transportation of Concrete from Batch Plant: The concrete shall be delivered to the site of the work and discharge shall be completed within 90 minutes after addition of the cement and water to the aggregates. Each batch of concrete delivered at the job site shall be accompanied by a time slip issued at the batching plant, bearing the time of charging of the mixer drum with the cement and aggregates.





## EAST KENTUCKY ENGINEERING, LLC.

---

- C. Transporting of Concrete from Mixer to Place of Final Deposit: Transportation shall be done as rapidly as practical by means which shall prevent the separation or loss of the ingredients. If chutes are used, they shall be at a slope not flatter than one vertical to two horizontal. Buggies or carts shall be equipped with pneumatic rubber tires or surfaces of runways shall be sufficiently smooth or both so as not to cause separation or segregation of concrete ingredients. Concrete shall not be allowed to drop freely more than 4 feet. Where greater drops are required, canvas "elephant trunks" or galvanized iron chutes equipped with suitable hopper heads shall be employed and a sufficient number placed to ensure that the concrete may be effectively compacted into horizontal layers not exceeding 12 inches in thickness with minimum lateral movements.
- D. Depositing of Concrete: Depositing of concrete shall:
1. Proceed continuously after once starting until reaching the end of a section of construction joint location shown on the drawings, or as approved by the Owner. The operations shall be conducted so that no concrete is deposited on concrete sufficiently hardened to cause formation of seams, and planes of weakness.
  2. Be as near as practical to its final position in the forms.
  3. Proceed to maintain constantly a top surface which is approximately level.
  4. Be placed before initial set has occurred, and in no event after it has contained its water content for more than 90 minutes.
  5. Be thoroughly worked and compacted by means of suitable tools to provide impermeability, durability and strength and shall be thoroughly worked around reinforcements and embedded items and into corners of forms and to be free from voids, pockets or honeycombing. Care shall be taken to provide impermeability.
- E. Vibration Equipment: Vibration equipment shall be of the appropriate type and shall, always, be adequate in number of units and power of each unit to properly consolidate all concrete.
- F. Monolithic Pours: Proper delivery of concrete shall be the Contractor's responsibility to make a mono-lithic pour without delays and changes of cold joints.



## **EAST KENTUCKY ENGINEERING, LLC.**

---

### **9.0 CURING**

All concrete work shall be protected from injurious action by the sun, rain, flowing water, frost and other injury and shall be covered with plastic after application of curing compound for three (3) days on pours located above ground.

Contractor shall not remove any formwork for a minimum period of 24 hours after a concrete pour without written approval of the Owner.

### **10.0 CONCRETE FINISHES**

Finishes of all exposed concrete shall be free of defects which impair its durability or adversely affect its appearance. All such surfaces when stripped, shall be uniform in appearance and any surfaces displaying any deviations from adjacent uniform surfaces shall be rejected and subject to removal.

Finished work shall be level and plumb, true to lines, and dimensions. Finished plane surfaces shall be smooth, and as nearly perfect as practical; however, deviations from a true plane shall not exceed 1/8 inch when measured from a 6-foot straight edge placed against the surface to any point on the surface and under the straight edge.

All exposed surfaces shall have defects corrected, protrusions removed, and holes filled.



## EAST KENTUCKY ENGINEERING, LLC.

---

### APPENDIX A PHOTOGRAPHS



TEST PIT TCH1



TEST PIT TCH2



**EAST KENTUCKY ENGINEERING, LLC.**

---



**TOWER LOCATION**





**EAST KENTUCKY ENGINEERING, LLC.**

---

<b>APPENDIX B   SEISMIC</b>
-----------------------------

# **Design Maps Summary Report**

## User-Specified Input


**Report Title** Hulen Site  
Wed June 13, 2018 11:57:04 UTC

**Building Code Reference Document** 2012/2015 International Building Code  
(which utilizes USGS hazard data available in 2008)

**Site Coordinates** 36.79034°N, 83.53337°W

**Site Soil Classification** Site Class C - "Very Dense Soil and Soft Rock"



**Risk Category** IV (e.g. essential facilities)



## USGS-Provided Output

$S_s = 0.288 \text{ g}$	$S_{MS} = 0.345 \text{ g}$	$S_{DS} = 0.230 \text{ g}$
$S_1 = 0.104 \text{ g}$	$S_{M1} = 0.177 \text{ g}$	$S_{D1} = 0.118 \text{ g}$

For information on how the  $S_s$  and  $S_1$  values above have been calculated from probabilistic (risk-targeted) and deterministic ground motions in the direction of maximum horizontal response, please return to the application and select the "2009 NEHRP" building code reference document.



Although this information is a product of the U.S. Geological Survey, we provide no warranty, expressed or implied, as to the accuracy of the data contained therein. This tool is not a substitute for technical subject-matter knowledge.




**EAST KENTUCKY ENGINEERING, LLC.**

---

<b>APPENDIX C    MAPS</b>
---------------------------





**East Kentucky Engineering, LLC**

Hazard Location  
230 Swartz  
Hazard, KY 41701  
(606) 551-1050  
Email: rdsekyeng@outlook.com



0' 20' 40'



Drawn by: RDS

Date: 6/8/2018

Job #: 165-0064

Scale: NOTED

File Location:

**APPALACHIAN  
WIRELESS  
HULEN TOWER SITE  
BELL COUNTY KENTUCKY**

## MEMBER INFORMATION

SECTION	ELEVATION	FACE SIZE	LEG DIA.	DIAGONALS	HORIZONTALS	RED. HORZ/DIAGS.	INNER BRACING	GIRTS	# OF BAYS
1	0' - 20'	24'-0"	Ø5"	2L 3" x 3/16"	2L 2 1/2" x 3/16"	2L 2" x 3/16"	2L 2" x 3/16"	N/A	4 - MOD X
2	20' - 40'	22'-6"	Ø5"	2L 3" x 3/16"	2L 2 1/2" x 3/16"	2L 2" x 3/16"	2L 2" x 3/16"	N/A	4 - MOD X
3	40' - 60'	21'-0"	Ø5"	L 4" x 1/4"	N/A	N/A	N/A	N/A	3 - X
4	60' - 80'	19'-6"	Ø4 3/4"	L 4" x 1/4"	N/A	N/A	N/A	N/A	3 - X
5	80' - 100'	18'-0"	Ø4 3/4"	L 3 1/2" x 1/4"	N/A	N/A	N/A	N/A	3 - X
6	100' - 120'	16'-6"	Ø4 1/2"	L 3 1/2" x 1/4"	N/A	N/A	N/A	N/A	3 - X
7	120' - 140'	15'-0"	Ø4 1/2"	L 3" x 1/4"	N/A	N/A	N/A	N/A	3 - X
8	140' - 160'	13'-6"	Ø4 1/4"	L 3" x 3/16"	N/A	N/A	N/A	N/A	3 - X
9	160' - 180'	12'-0"	Ø4"	L 3" x 3/16"	N/A	N/A	N/A	N/A	3 - X
10	180' - 200'	10'-6"	Ø3 3/4"	L 2 1/2" x 3/16"	N/A	N/A	N/A	N/A	3 - X
11	200' - 220'	9'-0"	Ø3 1/4"	L 2" x 3/16"	N/A	N/A	N/A	N/A	4 - X
12	220' - 240'	7'-6"	Ø3"	L 2" x 3/16"	N/A	N/A	N/A	N/A	4 - X
13	240' - 260'	6'-0"	Ø2 3/4"	L 2" x 1/8"	N/A	N/A	N/A	N/A	4 - X
14	260' - 280'	4'-6"	Ø2 1/2"	L 2" x 1/8"	N/A	N/A	N/A	N/A	4 - X
15	280' - 300'	4'-6"	Ø1 3/4"	L 1 1/2" x 1/8"	N/A	N/A	N/A	L 1 1/2" x 1/8"	4 - X

## ANTENNA INFORMATION

ELEVATION	ANTENNA	LINE
295'	(12) NN-65A-M	(6) 1-5/8" HELIAX + (4) 7/8" HYBRID
295'	(12) ERICSSON-2212 (BEHIND ANTENNA)	N/A
285'	(12) NN-65A-M	(6) 1-5/8" HELIAX + (4) 7/8" HYBRID
285'	(12) ERICSSON-2212 (BEHIND ANTENNA)	N/A
275'	(12) NN-65A-M	(4) 7/8" HYBRID
275'	(12) ERICSSON-2212 (BEHIND ANTENNA)	N/A
265'	(12) NN-65A-M	(4) 1-5/8" HELIAX + (4) 7/8" HYBRID
265'	(12) ERICSSON-2212 (BEHIND ANTENNA)	N/A
240'	(2) 6' HP DISH	(2) EW63
200'	(12) NN-65A-M	(4) 7/8" HYBRID
200'	(12) ERICSSON-2212 (BEHIND ANTENNA)	N/A
190'	(12) NN-65A-M	(4) 7/8" HYBRID
190'	(12) ERICSSON-2212 (BEHIND ANTENNA)	N/A
180'	(2) 8' HP DISH	(2) EW63

## DESIGN NOTES:

- 1) TOWER LEGS ARE CONSTRUCTED OF SOLID ROUND BAR MATERIAL.
- 2) SOLID ROUND 0.75" AND LARGER ASTM A-572 GRADE : 50 KSI MIN.
- 3) SOLID ROUND 0.625" AND SMALLER IS ASTM A-36 GRADE : 36 KSI MIN.
- 4) ALL ANGLE MATERIAL IS ASTM A-529 : 50 KSI MIN.
- 5) ALL BRACE AND FLANGE BOLTS ARE A325-X
- 6) THIS TOWER IS DESIGNED FOR STEP BOLTS UP ONE LEG FOR CLIMBING WITH SAFETY CLIMB DEVICE.
- 7) (6) Ø1 3/4" x 4'-6" LONG (F1554-GR.105) ANCHOR BOLTS PER LEG.
- 8) THIS TOWER IS DESIGNED FOR A 90 M.P.H. WIND SPEED WITH NO ICE AND A 30 M.P.H. WIND SPEED WITH 0.75" ICE IN ACCORDANCE WITH THE TIA/EIA-222-G STANDARD. ICE IS CONSIDERED TO INCREASE IN THICKNESS WITH HEIGHT. DEFLECTIONS BASED ON A 60 M.P.H. WIND.
- 9) TOWER DESIGNED TO EXPOSURE C; STRUCTURE CLASS II; TOPO. CAT 1.
- 10)

APPROX. WEIGHT  
68.6 KIPS

PROPRIETARY STATEMENT: THIS DRAWING IS THE PROPERTY OF ALLSTATE TOWER INC. IT IS NOT TO BE REPRODUCED OR COPIED IN ANYWAY WITHOUT WRITTEN CONSENT OF ALLSTATE TOWER INC.

REV #	DESCRIPTION	DATE	BY	RC	UNLESS OTHERWISE NOTED DIMENSIONS ARE IN INCHES	DESCRIPTION
1	UPDATED ANCHOR BOLT LENGTH	8/20/18			TOLERANCE BANDS: X ±3/32" & ANGLES ±.2° XX ±3/32" XXX ±1/16" HOLES ±0.1/16"	TOWER OVERVIEW APPALACHIAN WIRELESS "HULEN" BELL CO., KY 300' SELF SUPPORT TOWER
SCALE: NTS					DRAWN BY: RC	FILE NAME: FT071262-A - SD
					DATE: 4/30/2018	DESIGN: FT071262
						SHEET A

BASE REACTIONS:(FACTORED)  
TOTAL SHEAR = 84 KIPS  
AXIAL LOAD = 247 KIPS  
UPLIFT / LEG = 625 KIPS  
COMP. / LEG = 718 KIPS  
O.T. MOMENT = 14175 FT-K

PLAN VIEW

PLAN VIEW REF:  
1) 1 5/8" HELIAX  
2) 7/8" HYBRID  
3) EW63  
4) STEP BOLTS




Keith M. Eaton  
8-21-2018

**ALLSTATE TOWER**

ALLSTATE TOWER INC.  
P.O. BOX 25  
HENDERSON KY 42419  
PHONE: (270) 630-8512  
FAX: (270) 630-8475  
WWW.PTTG.COM






TOTAL VOLUME OF CONCRETE = 153.5 YD<sup>3</sup>

#### FOUNDATION INSTALLATION/DESIGN NOTES:

1. THIS FOUNDATION IS DESIGNED TO MEET ALL STANDARDS SET FORTH BY ACI 318: AMERICAN CONCRETE INSTITUTE, BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE, ANSI/TIA/EIA 222-G: STRUCTURAL STANDARDS FOR STEEL ANTENNA TOWERS AND ANTENNA SUPPORTING STRUCTURES.
2. THIS FOUNDATION IS DESIGNED UTILIZING THE GEOTECHNICAL REPORT PERFORMED BY EAST KENTUCKY ENGINEERING, LLC; DATED 6-10-2018; EKYENG PROJECT NO. 165-000-0064. THE FOUNDATION CONTRACTOR SHALL INSTALL THE FOUNDATIONS IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE GEOTECHNICAL REPORT.
3. THIS SITE IS LOCATED ON A RECLAIMED MINE. SOIL REMEDIATION SHALL BE PERFORMED AS OUTLINED IN THE GEOTECHNICAL REPORT, TO PREVENT DIFFERENTIAL SETTLEMENT. FOUNDATION SHOULD BE OVER-EXCAVATED 8" BELOW FOUNDATION SUBGRADE AND 10' OUTSIDE FOUNDATION AREA. LARGE ROCKS AND UNSUITABLE SHALL BE REMOVED, AND BACKFILLED WITH SELECT BACKFILL OR DENSE GRADE AGGREGATE. THE BACKFILL MATERIAL SHALL BE PLACED IN 8" LIFTS, COMPACTED TO NOT LESS THAN 95% OF THE MAXIMUM DENSITY AS DETERMINED BY THE STANDARD PROCTOR DRY UNIT WEIGHT (ASTM D-968) AND WITHIN 2% OF THE OPTIMUM MOISTURE CONTENT.
4. ALL WORK PERFORMED FROM THESE DRAWINGS SHOULD BE BY QUALIFIED CONTRACTORS EXPERIENCED IN TOWER FOUNDATION CONSTRUCTION.
5. ALL FOOTING EXCAVATIONS SHALL BE MANUALLY CLEANED PRIOR TO PLACING CONCRETE. COMPACT THE EXPOSED SOIL SURFACE AND ANY GRANULAR FILL UNDER THE FOUNDATION TO 90% OF THE MODIFIED PROCTOR DENSITY.
6. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI AFTER 28 DAYS. COPIES OF THE CONCRETE CYLINDER TEST REPORTS SHALL BE SENT TO THE RESIDENT ENGINEER / INSPECTOR.
7. MINIMUM CONCRETE COVER FOR REINFORCING BARS SHALL BE 3". ALL REINFORCING BARS SHALL BE GRADE 60 REBAR (MIN YIELD = 60KSI).
8. FIELD BENDING OR WELDING OF REINFORCEMENT BARS IS NOT PERMITTED.
9. PROVIDE CHAMFERS AT ALL EXPOSED CORNERS OF CONCRETE.
10. SOME DETAIL HAS BEEN PURPOSELY OMITTED TO CLARIFY ILLUSTRATION.




(6) #1 3/4" X 4'-6" OVERALL LENGTH ANCHOR BOLTS (F1554-GR105) W/ 1" THK BEARING PLATE AT THE BOTTOM OF THE ANCHOR BOLT CLUSTER (3'-6" MIN. ANCHOR BOLT EMBEDMENT).

USE EPOXY BONDING AGENT WHEN POURED SEPARATELY

(28) #9 VERTICAL BARS w/ 6" HOOK WITH (3) #4 TIES EQUALLY SPACED

(44) #6 HORIZONTAL BARS x 44'-6" LONG SPACED 12" O.C. EACH WAY AT TOP OF MAT. (TOTAL=88)

(66) #9 HORIZONTAL BARS x 44'-6" LONG SPACED 8" O.C. EACH WAY AT BOTTOM OF MAT. (TOTAL=132)



#### REINFORCEMENT BAR SPlicing:

1. ALL LAP SPICES SHALL CONFORM TO ACI 318 REQUIREMENTS.
2. REFER TO CHART BELOW WHEN REINFORCEMENT BAR SPlicing IS NECESSARY.

REINFORCING BAR SIZE	LAP SPICE LENGTH
3	15"
4	17"
5	21"
6	26"
7	30"
8	36"
9	46"
10	56"
11	71"



Keith M. Eaton  
8-21-2018

**ALLSTATE TOWER**

ALLSTATE TOWER INC.  
P.O. BOX 25  
HENDERSON, KY 42420  
PHONE: (270) 830-8512  
FAX: (270) 830-8476  
WWW.FT13.COM

PROPRIETARY STATEMENT: THIS DRAWING IS THE PROPERTY OF ALLSTATE TOWER INC. IT IS NOT TO BE REPRODUCED OR COPIED IN ANYWAY WITHOUT PRIOR WRITTEN CONSENT OF ALLSTATE TOWER INC.

REV#	DESCRIPTION	DATE	BY	UNLESS OTHERWISE NOTED DIMENSIONS ARE IN	DESCRIPTION
A	UPDATED DESIGN & NOTES	8/20/18	RC	INCHES	PAD & PIER FOUNDATION DESIGN
				TOLERANCE BANDS:	APPALACHIAN WIRELESS
				X +3/32" / -0 ANCHORS +/- 2"	"HULEN" BELL CO., KY
				XX +3/32" / -0	
				XXX +1/16" / -0 HOLES +/- 8/16" / -0	
				DRAWN BY: RC	FILE NAME: FT-071262-A - B
				DATE: 4/30/2018	DESIGN: FT-071262
				SCALE: NTS	SHEET B





Mail Processing Center  
Federal Aviation Administration  
Southwest Regional Office  
Obstruction Evaluation Group  
10101 Hillwood Parkway  
Fort Worth, TX 76177

Aeronautical Study No.  
2018-ASO-6892-OE

Issued Date: 05/23/2018

Ali Kuzehkanani  
East Kentucky Network, LLC  
8300 Greensboro Drive, Suite 1200  
Tysons, VA 22102

**\*\* DETERMINATION OF NO HAZARD TO AIR NAVIGATION \*\***

The Federal Aviation Administration has conducted an aeronautical study under the provisions of 49 U.S.C., Section 44718 and if applicable Title 14 of the Code of Federal Regulations, part 77, concerning:

Structure:	Tower Hulen
Location:	Hulen, KY
Latitude:	36-47-25.24N NAD 83
Longitude:	83-32-00.12W
Heights:	1306 feet site elevation (SE)
	310 feet above ground level (AGL)
	1616 feet above mean sea level (AMSL)

This aeronautical study revealed that the structure does not exceed obstruction standards and would not be a hazard to air navigation provided the following condition(s), if any, is(are) met:

As a condition to this Determination, the structure is to be marked/lighted in accordance with FAA Advisory circular 70/7460-1 L Change 1, Obstruction Marking and Lighting, 24-hr med-strobes - Chapters 4,6(MIWOL),&12.

Any failure or malfunction that lasts more than thirty (30) minutes and affects a top light or flashing obstruction light, regardless of its position, should be reported immediately to (877) 487-6867 so a Notice to Airmen (NOTAM) can be issued. As soon as the normal operation is restored, notify the same number.

It is required that FAA Form 7460-2, Notice of Actual Construction or Alteration, be e-filed any time the project is abandoned or:

- ☐ At least 10 days prior to start of construction (7460-2, Part 1)  
☒ Within 5 days after the construction reaches its greatest height (7460-2, Part 2)

This determination expires on 11/23/2019 unless:

- (a) the construction is started (not necessarily completed) and FAA Form 7460-2, Notice of Actual Construction or Alteration, is received by this office.
- (b) extended, revised, or terminated by the issuing office.

- (c) the construction is subject to the licensing authority of the Federal Communications Commission (FCC) and an application for a construction permit has been filed, as required by the FCC, within 6 months of the date of this determination. In such case, the determination expires on the date prescribed by the FCC for completion of construction, or the date the FCC denies the application.

NOTE: REQUEST FOR EXTENSION OF THE EFFECTIVE PERIOD OF THIS DETERMINATION MUST BE E-FILED AT LEAST 15 DAYS PRIOR TO THE EXPIRATION DATE. AFTER RE-EVALUATION OF CURRENT OPERATIONS IN THE AREA OF THE STRUCTURE TO DETERMINE THAT NO SIGNIFICANT AERONAUTICAL CHANGES HAVE OCCURRED, YOUR DETERMINATION MAY BE ELIGIBLE FOR ONE EXTENSION OF THE EFFECTIVE PERIOD.

This determination does not constitute authority to transmit on the frequency(ies) identified in this study. The proponent is required to obtain a formal frequency transmit license from the Federal Communications Commission (FCC) or National Telecommunications and Information Administration (NTIA), prior to on-air operations of these frequency(ies).

This determination of No Hazard is granted provided the following conditional statement is included in the proponent's construction permit or license to radiate:

Upon receipt of notification from the Federal Communications Commission that harmful interference is being caused by the licensee's (permittee's) transmitter, the licensee (permittee) shall either immediately reduce the power to the point of no interference, cease operation, or take such immediate corrective action as is necessary to eliminate the harmful interference. This condition expires after 1 year of interference-free operation.

This determination is based, in part, on the foregoing description which includes specific coordinates, heights, frequency(ies) and power. Any changes in coordinates, heights, and frequencies or use of greater power, except those frequencies specified in the Colo Void Clause Coalition; Antenna System Co-Location; Voluntary Best Practices, effective 21 Nov 2007, will void this determination. Any future construction or alteration, including increase to heights, power, or the addition of other transmitters, requires separate notice to the FAA. This determination includes all previously filed frequencies and power for this structure.

If construction or alteration is dismantled or destroyed, you must submit notice to the FAA within 5 days after the construction or alteration is dismantled or destroyed.

This determination does include temporary construction equipment such as cranes, derricks, etc., which may be used during actual construction of the structure. However, this equipment shall not exceed the overall heights as indicated above. Equipment which has a height greater than the studied structure requires separate notice to the FAA.

This determination concerns the effect of this structure on the safe and efficient use of navigable airspace by aircraft and does not relieve the sponsor of compliance responsibilities relating to any law, ordinance, or regulation of any Federal, State, or local government body.

A copy of this determination will be forwarded to the Federal Communications Commission (FCC) because the structure is subject to their licensing authority.

If we can be of further assistance, please contact our office at (202) 267-5281, or [lynnette.farrell@faa.gov](mailto:lynnette.farrell@faa.gov). On any future correspondence concerning this matter, please refer to Aeronautical Study Number 2018-ASO-6892-OE.

**Signature Control No: 361557904-366025020**

( DNE )

Lynnette Farrell  
Technician

Attachment(s)  
Frequency Data  
Map(s)

cc: FCC

# Frequency Data for ASN 2018-ASO-6892-OE

LOW FREQUENCY	HIGH FREQUENCY	FREQUENCY UNIT	ERP	ERP UNIT
6	7	GHz	55	dBW
6	7	GHz	42	dBW
10	11.7	GHz	55	dBW
10	11.7	GHz	42	dBW
17.7	19.7	GHz	55	dBW
17.7	19.7	GHz	42	dBW
21.2	23.6	GHz	55	dBW
21.2	23.6	GHz	42	dBW
614	698	MHz	1000	W
614	698	MHz	2000	W
698	806	MHz	1000	W
806	901	MHz	500	W
806	824	MHz	500	W
824	849	MHz	500	W
851	866	MHz	500	W
869	894	MHz	500	W
896	901	MHz	500	W
901	902	MHz	7	W
929	932	MHz	3500	W
930	931	MHz	3500	W
931	932	MHz	3500	W
932	932.5	MHz	17	dBW
935	940	MHz	1000	W
940	941	MHz	3500	W
1670	1675	MHz	500	W
1710	1755	MHz	500	W
1850	1910	MHz	1640	W
1850	1990	MHz	1640	W
1930	1990	MHz	1640	W
1990	2025	MHz	500	W
2110	2200	MHz	500	W
2305	2360	MHz	2000	W
2305	2310	MHz	2000	W
2345	2360	MHz	2000	W
2496	2690	MHz	500	W



TOPO Map for ASN 2018-ASO-6892-OE





## KENTUCKY AIRPORT ZONING COMMISSION

MATTHEW BEVIN  
Governor

421 Buttermilk Pike  
Covington, KY 41017  
[www.transportation.ky.gov](http://www.transportation.ky.gov)  
859-341-2700

June 22, 2018

### APPROVAL OF APPLICATION

**APPLICANT:**

East Kentucky Network, LLC.  
East Kentucky Network, LLC.  
8300 Greensboro Drive/Suite 1200  
McLean, VA 22102

**SUBJECT:** AS-007-I35-2018-047

**STRUCTURE:** Antenna Tower  
**LOCATION:** Hulen, KY  
**COORDINATES:** 36° 47' 25.24" N / 83° 32' 00.12" W  
**HEIGHT:** 310' AGL/1616' AMSL

The Kentucky Airport Zoning Commission has approved your application for a permit to construct 310' AGL/ 1616' AMSL Antenna Tower near Hulen, KY 36° 47' 25.24" N / 83° 32' 00.12" W.

This permit is valid for a period of 18 Month(s) from its date of issuance. If construction is not completed within said 18-Month period, this permit shall lapse and be void, and no work shall be performed without the issuance of a new permit.

A copy of the approved application is enclosed for your files.

Medium Intensity White Obstruction Lighting is required in accordance with 602 KAR 50:100.



John Houlihan  
Administrator



An Equal Opportunity Employer M/F/D





# KENTUCKY AIRPORT ZONING COMMISSION

MATTHEW BEVIN  
Governor

421 Buttermilk Pike  
Covington, KY 41017  
www.transportation.ky.gov  
859-341-2700

## CONSTRUCTION/ALTERATION STATUS REPORT

June 22, 2018

AERONAUTICAL STUDY NUMBER: AS-007-135-2018-047

East Kentucky Network, LLC.  
East Kentucky Network, LLC.  
8300 Greensboro Drive; Suite 1200  
McLean, VA 22102

This concerns the permit which was issued to you by the Kentucky Airport Zoning Commission on June 22, 2018. This permit is valid for a period of 18 Month(s) from its date of issuance. If construction is not completed within the said 18-Month period, this permit shall lapse and be void, and no work shall be performed without the issuance of a new permit. When appropriate, please indicate the status of the project in the place below and return this letter to John Houlihan, Administrator, Kentucky Airport Zoning Commission, 421 Buttermilk Pike, Covington, KY, 41017. 859-341-2700.

STRUCTURE: Antenna Tower  
LOCATION: Hulen, KY  
COORDINATES: 36° 47' 25.24" N / 83° 32' 00.12" W  
HEIGHT: 310' AGL / 1616' AMSL

### CONSTRUCTION/ALTERATION STATUS

1. The project ( ) is abandoned. ( ) is not abandoned.

2. Construction status is as follows:

Structure reached its greatest height of \_\_\_\_\_ ft. AGL  
\_\_\_\_\_ ft. AMSL on \_\_\_\_\_ (date).

Date construction was completed. \_\_\_\_\_

Type of obstruction marking/painting. \_\_\_\_\_

Type of obstruction lighting. \_\_\_\_\_

As built coordinates. \_\_\_\_\_

Miscellaneous Information. \_\_\_\_\_

DATE \_\_\_\_\_

SIGNATURE/TITLE \_\_\_\_\_



An Equal Opportunity Employer M/F/D



KENTUCKY TRANSPORTATION CABINET

KENTUCKY AIRPORT ZONING COMMISSION

TC 56-50

Rev. 07/2010

Page 2 of 2

## APPLICATION FOR PERMIT TO CONSTRUCT OR ALTER A STRUCTURE

<b>APPLICANT (name)</b> East Kentucky Network, LLC c/o LLGS		<b>PHONE</b> 703-584-8667	<b>FAX</b> 703-584-8692	<b>KY AERONAUTICAL STUDY #</b> 45-007-135-2018-047	
<b>ADDRESS (street)</b> 8300 Greensboro Dr, #1200		<b>CITY</b> Tysons		<b>STATE</b> VA	<b>ZIP</b> 22102
<b>APPLICANT'S REPRESENTATIVE (name)</b> Ali Kuzehkanani		<b>PHONE</b> 703-584-8667	<b>FAX</b> 703-584-8692		
<b>ADDRESS (street)</b> 8300 Greensboro Dr, #1200		<b>CITY</b> Tysons		<b>STATE</b> VA	<b>ZIP</b> 22102
<b>APPLICATION FOR</b> <input checked="" type="checkbox"/> New Construction <input type="checkbox"/> Alteration <input type="checkbox"/> Existing <b>DURATION</b> <input type="checkbox"/> Permanent <input type="checkbox"/> Temporary (months days )				<b>WORK SCHEDULE</b> Start 05/15/18 End 05/20/18	
<b>TYPE</b> <input type="checkbox"/> Crane <input type="checkbox"/> Building <input checked="" type="checkbox"/> Antenna Tower <input type="checkbox"/> Power Line <input type="checkbox"/> Water Tank <input type="checkbox"/> Landfill <input type="checkbox"/> Other		<b>MARKING/PAINTING/LIGHTING PREFERRED</b> <input type="checkbox"/> Red Lights & Paint <input checked="" type="checkbox"/> White- medium intensity <input type="checkbox"/> White- high intensity <input type="checkbox"/> Dual- red & medium intensity white <input type="checkbox"/> Dual- red & high intensity white <input type="checkbox"/> Other			
<b>LATITUDE</b> 36°47'25.24"		<b>LONGITUDE</b> 83°32'00.12"		<b>DATUM</b> <input checked="" type="checkbox"/> NAD83 <input type="checkbox"/> NAD27 <input type="checkbox"/> Other	
<b>NEAREST KENTUCKY</b> City Hulen County Bell		<b>NEAREST KENTUCKY PUBLIC USE OR MILITARY AIRPORT</b> Tucker-Guthrie Memorial Airport			
<b>SITE ELEVATION (AMSL, feet)</b> 1306		<b>TOTAL STRUCTURE HEIGHT (AGL, feet)</b> 310		<b>CURRENT (FAA aeronautical study #)</b>	
<b>OVERALL HEIGHT (site elevation plus total structure height, feet)</b> 1616				<b>PREVIOUS (FAA aeronautical study #)</b>	
<b>DISTANCE (from nearest Kentucky public use or Military airport to structure)</b> 10.8 mi				<b>PREVIOUS (KY aeronautical study #)</b>	
<b>DIRECTION (from nearest Kentucky public use or Military airport to structure)</b> ENE					
<b>DESCRIPTION OF LOCATION</b> (Attach USGS 7.5 minute quadrangle map or an airport layout drawing with the precise site marked and any certified survey.) Approximately 1.1 miles N of Hulen (Bell), KY					
<b>DESCRIPTION OF PROPOSAL</b> A new 300' tower with top-mounted antennas (overall height of 310' AGL)					
<b>FAA Form 7460-1</b> (Has the "Notice of Construction or Alteration" been filed with the Federal Aviation Administration?) <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes, when? 04/04/18					
<b>CERTIFICATION</b> (I hereby certify that all the above entries, made by me, are true, complete, and correct to the best of my knowledge and belief.) <b>PENALTIES</b> (Persons failing to comply with KRS 183.861 to 183.990 and 602 KAR 050 are liable for fines and/or imprisonment as set forth in KRS 183.990(3). Noncompliance with FAA regulations may result in further penalties.)					
<b>NAME</b> Ali Kuzehkanani	<b>TITLE</b> Dir of Engineering	<b>SIGNATURE</b> 		<b>DATE</b> 04/04/18	
<b>COMMISSION ACTION</b> <input checked="" type="checkbox"/> Approved <input type="checkbox"/> Disapproved <b>SIGNATURE</b> <input type="checkbox"/> Chairperson, KAZC <input checked="" type="checkbox"/> Administrator, KAZC <b>DATE</b> 6-22-18					



### Driving Directions for Hulen

Beginning in front of the Courthouse in Pineville, Bell County, Kentucky on the corner of Kentucky Ave. and Pine Street go .1 miles and turn right onto 25E. Go 1 mile to the intersection of 25E and 119 and turn left. Go 12.8 miles to the intersection of 119 and Halls Hollow Road. Turn right onto Halls Hollow Road and drive .5 miles. Site road will begin to your left (signs will be posted). From here its foot traffic only. Walk .5 mile (sign will be posted).

Prepared By:  
Daryl Bartley  
Appalachian Wireless  
(606) 791-0310

# Hulen


## Location:


565 Halls Hollow Road  
Pineville, KY 40977

## Coordinates:

36°47'25.24"N  
83°32'00.13"W

## Legend

 1/2 Mile Search Area

 Proposed Hulen Site

Wilder Ln

72

Cherry

Long St

Oak St

Levi Taylor Rd

Halls Hwy

N

2000 ft



**DEED**

THIS DEED OF CONVEYANCE is made and entered into this 8<sup>th</sup> day of May, 2018, by and between **RICHARD D. CALLOWAY** and **SHARON CALLOWAY**, husband and wife, whose address is 562 Halls Hollow Road, Hulen, Kentucky 40845 (hereinafter referred to as "**Grantor**"), and **EAST KENTUCKY NETWORK, LLC D/B/A APPALACHIAN WIRELESS**, a Kentucky limited liability company (hereinafter referred to as "**Grantee**"), whose address is 101 Technology Trail, Ivel, Kentucky 41642, which is also the "in care of" address to which the property tax bill for 2018 should be sent.

W I T N E S S E T H

That for and in consideration of the sum of Forty-Five Thousand and 00/100 Dollars (\$45,000.00), cash in hand paid, the receipt and sufficiency of which are hereby acknowledged, Grantor does hereby GRANT, SELL, and CONVEY to the Grantee, its successors and assigns, that certain real property near Hulen, Bell County, Kentucky, which is more particularly described in the Description **attached** hereto and made a part herein as **Exhibit A** and depicted on the plat **attached** hereto and made a part herein as **Exhibit B**, prepared by James W. Caudill, Licensed Professional Land Surveyor (hereinafter referred to as the "Property").

Being the same property conveyed to Richard Calloway by William Calloway and his wife, Dilcie Calloway by Deed dated June 23, 2016, and recorded June 23, 2016, in the Bell County Clerk's Office in Deed Book 370, Page 339.

TO HAVE AND TO HOLD the same with all appurtenances and privileges thereunto belonging unto the Grantee, its successors and assigns forever, with covenant of GENERAL WARRANTY.

CONSIDERATION CERTIFICATE

The parties to this deed certify that the consideration reflected in this deed is the full consideration paid for the property and understand that falsification of the stated consideration is a class D felony, subject to one to five years imprisonment and fines up to \$10,000.00.

IN TESTIMONY WHEREOF, the parties have hereunto subscribed their names as of the date set forth herein.

GRANTORS:

Richard D Calloway  
RICHARD D. CALLOWAY

Sharon Calloway  
SHARON CALLOWAY

COMMONWEALTH OF KENTUCKY  
COUNTY OF Bell:

I, Raina Helton, a Notary Public in and for the County and State aforesaid, do hereby certify that the foregoing Deed and Consideration Certificate was this day produced, acknowledged, subscribed, and sworn to before me in the County and State aforesaid and signed by RICHARD D. CALLOWAY and SHARON CALLOWAY, Grantors, this 8th day of May, 2018.

Raina L. Helton  
Notary Public

My Commission Expires: Feb 6, 2020





GRANTEE:  
EAST KENTUCKY NETWORK, LLC D/B/A  
APPALACHIAN WIRELESS

W A Gillum

By: W.A. Gillum  
Its: CEO/General Manager

COMMONWEALTH OF KENTUCKY  
COUNTY OF Floyd:

I, Raina Helton, a Notary Public in and for the County and State aforesaid, do hereby certify that the foregoing Consideration Certificate was this day produced, acknowledged, subscribed, and sworn to before me in the County and State aforesaid and signed by W.A. Gillum, in his capacity as the CEO/General Manager of East Kentucky Network, LLC d/b/a Appalachian Wireless, Grantee, this 9th day of May, 2018.

Raina L. Helton  
Notary Public

My Commission Expires: Feb 6, 2020

This is to certify that this  
instrument was prepared by:

Krystal Branham  
Krystal Branham, Attorney  
101 Technology Trail  
Ivel, Kentucky 41642  
(606) 477-2355



# LOT DESCRIPTION

Property of  
Richard Calloway  
562 Halls Hollow Road  
Hulen, KY 40845  
Off State Highway 119 Near Hulén  
in Bell County, KY  
February 28, 2018


A certain tract or parcel of land lying and being in Bell County, Kentucky, and being a portion of the property conveyed to Richard Calloway, by Deed of Conveyance dated June 23, 2016, from William Calloway, and his wife, Dilcie Calloway, of record in Deed Book 370 Page 339, in the office of the Bell County Clerk, Pineville, Kentucky and being more particularly described as follows:

## Being lots 1,2, & 3 of tract 2 block B

Beginning on an iron pin (found, no cap) near Halls Hollow Road and being a corner to Muriel J. Calloway Harbin (Will Book 8, page 785); thence a straight line with Harbin, North 53 deg 34 min 22 sec East, a distance of 606.47 feet to an iron pin (found, no cap) on top of the ridge by a T-Post and being a common corner to Kentucky Natural Lands Trust (Deed Book 371, page 22) and Muriel J. Calloway Harbin; thence leaving the line of Harbin and with the line of Kentucky Natural Lands Trust along the top of the ridge South 78 deg 57 min 06 sec East, a distance of 135.48 feet to an iron pin (found, no cap) by a T-Post on top of ridge; thence continuing with the line of Kentucky Natural Lands Trust and with the top of the ridge South 49 deg 29 min 54 sec East, a distance of 89.60 feet to a set iron pin with cap marked LS#2259 on top of the ridge and being a common corner to Wilma Calloway Lay (Deed Book 256, page 625) and Kentucky Natural Lands Trust; thence leaving the line of Kentucky Natural Lands Trust and with the line of Wilma Calloway Lay down the hill South 44 deg 23 min 40 sec West, a distance of 704.37 feet to an iron pin (found, no cap) at the edge of Halls Hollow Road; thence leaving the line of Wilma C. Lay and continuing with the edge of said road North 39 deg 41 sec 50 min West, a distance of 102.89 feet to an iron pin (found, no cap) at the edge of the road; thence continuing with edge of said road North 46 deg 42 min 32 sec West, a distance of 97.29 feet to an iron pin (found, no cap) at the edge of the road; thence continuing with the edge of said road North 36 deg 16 min 15 sec West, a distance of 101.02 feet to the point of beginning. Containing a calculated area of 165727 sq ft or 3.80 Acres.

Unless stated otherwise, any monument referred to herein as "set iron pin with cap" is a set  $\frac{1}{2}$ " diameter rebar, at least eighteen (18") in length, with a plastic cap stamped "LS-2259". All bearings stated herein are referred to NAD83, KY single zone of the Kentucky state plane system.

This survey was performed on February 28, 2018 by James W. Caudill, a Kentucky Licensed Professional Land Surveyor No. 2259.



*James W. Caudill*  
James W. Caudill, PLS #2259  
2-28-18

APPALACHIAN WIRELESS  
101 TECHNOLOGY TRAIL  
IVEL, KY. 41642  
PROPOSED TOWER SITE  
OFF HWY 25E NEAR HULEN  
IN BELL COUNTY, KY.

MAP 162-10 PARCEL 70  
MURIEL J CALLOWAY HARBIN  
42 MINK LANE  
PINEVILLE, KY 40977  
WILL BOOK 8 PAGE 785

MAP 152 PARCEL 23  
KENTUCKY NATURAL LANDS TRUST INC.  
433 CHESTNUT STREET  
BEREA, KY 40402  
DB 371 PG 22

MAP 162-10 PARCEL 27  
MARGIE HALL  
246 EATON ROAD  
LONDON, KY 40741  
DB 204 PG 117

## PLAT OF SURVEY

DRAWN JWC	DATE 2/28/18	SUBDIVISION OF THE PROPERTY OF RICHARD CALLOWAY 562 HALLS HOLLOW ROAD HULEN, KY 40845 OFF HIGHWAY 119 DEED BOOK 370 PAGE 339
APPROVED	DATE 2/28/18	
SCALE 1" = 100'	SHEET 1 OF 1	SURVEYED BY JAMES W. CAUDILL LS2259 2999 PERKINS/MADDEN ROAD AMBURGEE, KY 41773 PHONE 606-642-3217

TOTAL AREA  
165727 Sq. Feet  
3.80 Acres


STATE of KENTUCKY  
JAMES W. CAUDILL  
LS 2259  
LICENSED  
PROFESSIONAL  
LAND SURVEYOR

URBAN CLASS SURVEY  
I HEREBY CERTIFY THAT THIS PLAT DEPICTS A SURVEY, MADE  
BY ME, BY THE METHOD OF RANDOM TRAVERSE. THE  
BEARINGS SHOWN HEREON HAVE NOT BEEN ADJUSTED FOR  
CLOSURE. THIS SURVEY AND PLAT MEETS OR EXCEEDS  
THE MINIMUM STANDARDS OF GOVERNING AUTHORITIES.  
THE UNADJUSTED ERROR OF CLOSURE WAS 1 IN 18300

James W. Caudill  
NAME  
2259  
PLS#  
2-28-18  
DATE

0' 100' 200' 300'  
SURVEY STA  
IRON PIN WITH CAP (18" X .5" REBAR PLASTIC CAP MARKED LS2259)  
BOUNDARY LINE  
ACCESS ROAD  
PARENT TR LINE

NAD83 KY SINGLE ZONE





## DEED

THIS DEED OF CONVEYANCE is made and entered into this 5<sup>th</sup> day of April, 2018, by and between **WILMA CALLOWAY LAY**, widow, whose address is 1550 Meadow Run Drive, Morristown, Tennessee 37814 (hereinafter referred to as "**Grantor**"), and **EAST KENTUCKY NETWORK, LLC D/B/A APPALACHIAN WIRELESS**, a Kentucky limited liability company (hereinafter referred to as "**Grantee**"), whose address is 101 Technology Trail, Ivel, Kentucky 41642, which is also the "in care of" address to which the property tax bill for 2018 should be sent.

## W I T N E S S E T H

That for and in consideration of the sum of Twelve Thousand and 00/100 Dollars (\$12,000.00), cash in hand paid, the receipt and sufficiency of which are hereby acknowledged, Grantor does hereby GRANT, SELL, and CONVEY to the Grantee, its successors and assigns, that certain real property near Hulen, Bell County, Kentucky, which is more particularly described as follows:

### TRACT 2 BEING BLOCK B LOT NO. 4

BEGINNING on a Iron Pin set at the edge of the County Road, also being a corner of Lot No. 3, thence up the hill with said Lot No. 3 Northeast 700 feet to a Iron Pin on top of the hill, thence around the hill South 46-33 East 71 feet to a Iron Pin, corner of Lot No. 5, thence down the hill with Lot No. 5 Southwest 710 feet to a Iron Pin at edge of the County Road, also a corner of Lot No. 5, thence with said County Road North 36-28 West 100 feet to the point of beginning containing 1.3 Acres more or less as shown on Survey and Plat by Andrew Buell, Jr., Professional Engineer and Licensed Land Surveyor No. 2378 on August 20, 1988.

Being the same property conveyed to Wilma Calloway Lay by deed recorded December 21, 1988 in Deed Book 256, Page 625 of the Bell County Clerk's Office as "Tract 2 Being Block B Lot No. 4."

This conveyance is subject to the mineral reservation in the  
aforementioned deed.

TO HAVE AND TO HOLD the same with all appurtenances and privileges  
thereunto belonging unto the Grantee, its successors and assigns forever, with covenant of  
GENERAL WARRANTY.

CONSIDERATION CERTIFICATE

The parties to this deed certify that the consideration reflected in this deed is the full  
consideration paid for the property and understand that falsification of the stated consideration is  
a class D felony, subject to one to five years imprisonment and fines up to \$10,000.00.

IN TESTIMONY WHEREOF, the parties have hereunto subscribed their names as of the  
date set forth herein.

GRANTOR:

*Wilma Calloway Lay*  
WILMA CALLOWAY LAY

by CLAUDE RICHARD LAY,  
Power of Attorney

*Clyde Richard Lay*  
P.O.A.

COMMONWEALTH OF KENTUCKY  
COUNTY OF Bell:

I, Raina Helton, a Notary Public in and for the County and State aforesaid, do  
hereby certify that the foregoing Deed and Consideration Certificate was this day produced,  
acknowledged, subscribed, and sworn to before me in the County and State aforesaid and signed  
by WILMA CALLOWAY LAY, by CLAUDE RICHARD LAY, Power of Attorney, Grantor, this  
5<sup>th</sup> day of April, 2018.

*Raina Helton*  
Notary Public

My Commission Expires: Feb 6, 2020



GRANTEE:  
EAST KENTUCKY NETWORK, LLC D/B/A  
APPALACHIAN WIRELESS

W.A. Gillum  
By: W.A. Gillum  
Its: CEO/General Manager

COMMONWEALTH OF KENTUCKY  
COUNTY OF Floyd:

I, Raina Helton, a Notary Public in and for the County and State aforesaid, do hereby certify that the foregoing Consideration Certificate was this day produced, acknowledged, subscribed, and sworn to before me in the County and State aforesaid and signed by W.A. Gillum, in his capacity as the CEO/General Manager of East Kentucky Network, LLC d/b/a Appalachian Wireless, Grantee, this 10<sup>th</sup> day of April, 2018.

Raina L. Helton  
Notary Public

My Commission Expires Feb 6, 2020



This is to certify that this  
instrument was prepared by:

Krystal Branham  
Krystal Branham, Attorney  
101 Technology Trail  
Ivel, Kentucky 41642  
(606) 477-2355



APPALACHIAN WIRELESS  
101 TECHNOLOGY TRAIL  
IVEL, KY. 41642  
PROPOSED TOWER SITE  
OFF HWY 119 NEAR HULEN  
IN BELL COUNTY, KY.

MAP:162-10  
PARCEL:70


MAP:162-10 PARCEL:10.01  
EAST KENTUCKY NETWORK, LLC  
RICHARD CALLOWAY TRACT  
DB:370 PG:339  
TRACT 2 LOT 1

MAP:162-10 PARCEL:11  
EAST KENTUCKY NETWORK, LLC  
RICHARD CALLOWAY TRACT  
DB:370 PG:339  
TRACT 2 LOT 2

MAP:162-10 PARCEL:67  
EAST KENTUCKY NETWORK, LLC  
RICHARD CALLOWAY TRACT  
DB:370 PG:339  
TRACT 2 LOT 3

MAP:162-10 PARCEL:44  
EAST KENTUCKY NETWORK, LLC  
WILMA CALLOWAY LAY TRACT  
1550 MEADOW REIN DRIVE  
MORRISTOWN, TN 37814  
DB:256 PG:625

PROPOSED TOWER SITE  
LAT:36°47'25.2419"  
LON:83°32'00.1289"  
N:3454955.77  
E:5570343.92  
EL:1305'



**SURVEY STA** **SET** **FOUND**  
IRON PIN WITH CAP (1/8" X .5" REBAR PLASTIC CAP MARKED LS2259)  
**BOUNDARY LINE**  
**ACCESS ROAD**  
**LOT BOUNDARY**


LINE	BEARING	DISTANCE
L1	S 03°52'29" W	139.93'
L2	S 00°19'58" E	113.51'
L3	S 01°23'17" E	129.52'
L4	S 04°56'42" E	101.30'
L5	S 07°39'55" E	136.54'
L6	S 08°59'05" E	111.48'
L7	S 15°57'25" E	91.28'
L8	S 18°52'16" E	103.94'
L9	S 60°11'39" W	124.32'
L10	S 56°30'36" W	158.65'
L11	S 53°55'16" W	122.93'
L12	S 51°26'03" W	166.05'
L13	S 49°46'10" W	126.82'
L14	S 46°22'50" W	158.52'

"I CERTIFY THAT THE LATITUDE N 36° 47' 25.2419" AND LONGITUDE W 83° 32' 00.1289" ARE WITHIN +/- 50 FEET HORIZONTALLY; AND THE SITE ELEVATION 1305.0 FT. MSL, IS WITHIN +/- 20 FEET VERTICALLY. WITH A STRUCTURE HEIGHT OF 300 FT AGL, THE OVERALL HEIGHT IS 1605 FT, AMSL. THE HORIZONTAL DATUM (COORDINATES) IS IN TERMS OF THE NORTH AMERICAN DATUM OF 1983 (NAD 83). THE VERTICAL DATUM HEIGHTS ARE IN TERMS OF THE NORTH AMERICAN VERTICAL DATUM OF 1983, AND ARE DETERMINED TO THE NEAREST FOOT."

SIGNED: *James W. Caudill* 3-23-18

PRINTED: JAMES W. CAUDILL PE #12305 & LS #2259

- THE PROPOSED TOWER HAS BEEN LOCATED USING DUAL FREQUENCY GPS UNIT PROCESSED BY "OPUS"
- STATE PLANE COORDINATES NAD 83 KY SINGLE ZONE N:3454955.77, E:5570343.92, EL 1305' TOP OF FOUNDATION TOP OF PROPOSED TOWER ELEV. 1605'
- THIS SURVEY MEETS OBSTACLE ACCURACY CODE 2C.
- PROPERTY LINE INFORMATION TAKEN FROM DEEDS



SEE FOUNDATION DRAWINGS FOR DETAILS.

PROPOSED SITE PLAN AND STRUCTURE LOCATION HULEN TOWER APPALACHIAN WIRELESS		
DRAWN JWC	DATE 02/23/18	RICHARD CALLOWAY TR. HALLS HOLLOW ROAD OFF HIGHWAY 119 NEAR HULEN IN BELL COUNTY, KY.
APPROVED	DATE	
SCALE 1" = 20'	SHEET 2 OF 3	PROJECT NO. HULEN/HU202C



APPALACHIAN WIRELESS  
101 TECHNOLOGY TRAIL  
IVEL, KY. 41642  
HULEN PROPOSED TOWER SITE  
OFF HIGHWAY 119 NEAR HULEN  
IN BELL COUNTY, KY.

MAP:162-10 PARCEL:9  
J.S. AND CARRIE CALLOWAY ESTATE  
C/O CHARLES BENNETT  
304 HALLS HOLLOW ROAD  
HULEN, KY 40845  
DB:243 PG:660

MAP:162-10 PARCEL:12  
WILLIAM CLAY  
1550 MEADOW RAIN DRIVE  
MORRISTOWN, TN 37814  
DB:256 PG:625

MAP:162-10 PARCEL:71  
WILLIAM R. AND DILCIE G. CALLOWAY  
452 HALLS HOLLOW ROAD, HULEN, KY 40845  
DB:351 PG:481

MAP:162-10 PARCEL:72  
WILLIAM R. AND DILCIE G. CALLOWAY  
452 HALLS HOLLOW ROAD, HULEN, KY 40845  
DB:350 PG:470

MAP:162-10 PARCEL:13  
WILLIAM R. AND DILCIE G. CALLOWAY  
452 HALLS HOLLOW ROAD, HULEN, KY 40845  
DB:354 PG:179

MAP:162-10 PARCEL:73  
WILLIAM R. AND DILCIE G. CALLOWAY  
452 HALLS HOLLOW ROAD, HULEN, KY 40845  
DB:354 PG:179

MAP:162-10 PARCEL:76  
RICHARD DALE AND SHARON CALLOWAY  
PO BOX 25 CALVIN, KY 40813  
DB:370 PG:359

MAP:162-10 PARCEL:10  
RICHARD CALLOWAY, 562 HALLS HOLLOW ROAD, HULEN, KY 40845  
DB:370 PG:359

MAP:162-10 PARCEL:74  
R.T. CALLOWAY  
C/O MURIEL HARBIN  
42 MINK LANE  
PINEVILLE, KY 40977

MAP:162-10 PARCEL:34  
BILLY E. AND MURIEL J. HARBIN  
42 MINK LANE  
PINEVILLE, KY 40977  
DB:201 PG:713

MAP:162-10 PARCEL:70  
MURIEL J. CALLOWAY HARBIN  
42 MINK LANE  
PINEVILLE, KY 40977  
WILL BOOK 8 PAGE 785

MAP:162-10 PARCEL:16  
RICHARD DALE AND SHARON CALLOWAY  
562 HALLS HOLLOW ROAD  
HULEN, KY 40845  
DB:291 PG:4

MAP:162-10 PARCEL:18  
CLARENCE, JR. AND LINDA B. HALL  
724 HALLS HOLLOW ROAD  
HULEN, KY 40845  
DB:311 PG:718

MAP:162-10 PARCEL:19  
CLARENCE AND OLLIE JEAN HALL  
1069 HALLS HOLLOW ROAD  
HULEN, KY 40845  
DB:344 PG:240

MAP:162-10 PARCEL:23  
SARAH HALL LIFE ESTATE  
1095 HALLS HOLLOW ROAD  
HULEN, KY 40845  
DB:345 PG:352

MAP:162-10 PARCEL:66  
JEFFREY I. AND MICHELLE CRAIG  
203 BLACKMONT ROAD  
HULEN, KY 40845  
DB:275 PG:321

MAP:162-10 PARCEL:42  
JEFFREY I. AND CYNTHIA CRAIG  
203 BLACKMONT SCHOOL ROAD  
HULEN, KY 40845  
DB:263 PG:124

MAP:162-10 PARCEL:43  
EWELL DANIELS  
PO BOX 12  
CALVIN, KY 40813  
DB:344 PG:253

MAP:162-10 PARCEL:45  
SHERMAN JR. AND CHRISTINE CRAIG  
231 BLACKMONT ROAD  
HULEN, KY 40845  
DB:273 PG:536



MAP:162 PARCEL:23  
KENTUCKY NATURAL LANDS TRUST INC.  
433 CHESTNUT STREET  
BEREA, KY 40402  
DB:371 PG:22

PROPOSED TOWER SITE  
LAT:36°47'25.2419"  
LON:83°32'00.1289"  
N:3454955.77  
E:5570343.92  
EL:1305'

MAP:162-10 PARCEL:27  
MARGRIE HALL  
246 EATON ROAD  
LONDON, KY 40741  
DB:204 PG:117

MAP:162-10 PARCEL:28  
HALL CEMETERY  
HULEN, KY 40845

MAP:162 PARCEL:3  
KENTUCKY NATURAL LANDS TRUST INC.  
433 CHESTNUT STREET  
BEREA, KY 40403  
DB:371 PG:22




LEGEND  
BOUNDARY LINE PVA  
ACCESS ROAD  
CONTOUR LINES  
POWER LINES

J W CAUDILL ENGINEERING  
9283 HWY 15 STE. C ISOM, KY 41824  
ENGINEER'S CERTIFICATE: I HEREBY CERTIFY THAT INFORMATION SHOWN  
REFLECTS THE INFORMATION OBTAINED AND PROVIDED BY THE BELL COUNTY PROPERTY  
VALUATION ADMINISTRATION OFFICE IN PINEVILLE, KY.  
James W. Caudill 12305 2-23-18  
JAMES W. CAUDILL P.E.# DATE

PROPOSED SITE PLAN AND STRUCTURE LOCATION HULEN TOWER APPALACHIAN WIRELESS		
DRAWN JWC	DATE 02/23/2018	STRUCTURES AND PROPERTY OWNERS WITHIN 500' RICHARD CALLOWAY TRACT OFF OF HIGHWAY 119 NEAR HULEN IN BELL COUNTY
APPROVED	DATE	
SCALE 1" = 200'	SHEET 1 OF 3	PROJECT NO. HULEN/HULEN200PVA




APPALACHIAN WIRELESS  
101 TECHNOLOGY TRAIL  
IVEL, KY. 41642  
PROPOSED TOWER SITE  
OFF HWY 119 NEAR HULEN  
IN BELL COUNTY, KY.



# PROFILE WITH TOWER


THIS IS A VERTICAL PROFILE SKETCH OF THE TOWER INDICATING THE PROPOSED ANTENNA AND DISH ELEVATIONS. NO DESIGN CRITERIA WAS CONSIDERED IN THE PREPARATION OF THIS DRAWING.



*James W. Caudill* 12305 2-23-18  
JAMES W. CAUDILL PE #. DATE

NOTE: SEE FOUNDATION DRAWINGS FOR DETAILS

02/23/18  
SCALE 1" = 20'



PROPOSED SITE PLAN AND STRUCTURE LOCATION HULEN TOWER APPALACHIAN WIRELESS		
DRAWN JWC	DATE 02/23/18	RICHARD CALLOWAY TR. HALLS HOLLOW ROAD OFF HIGHWAY 119 NEAR HULEN IN BELL COUNTY, KY.
APPROVED	DATE	
SCALE 1" = 20'	SHEET 3 OF 3	PROJECT NO. HULEN/HUPRO20



Utility ID	Utility Name	Utility Type	Class	City	State
4107900	365 Wireless, LLC	Cellular	D	Atlanta	GA
4109300	Access Point, Inc.	Cellular	D	Cary	NC
4108300	Air Voice Wireless, LLC	Cellular	A	Bloomfield Hill	MI
4110650	Alliant Technologies of KY, L.L.C.	Cellular	C	Morristown	NJ
44451184	Alltel Communications, LLC	Cellular	A	Basking Ridge	NJ
4110850	AltaWorx, LLC	Cellular	C	Fairhope	AL
4107800	American Broadband and Telecommunications Company	Cellular	C	Toledo	OH
4108650	AmeriMex Communications Corp.	Cellular	D	Dunedin	FL
4105100	AmeriVision Communications, Inc. d/b/a Affinity 4	Cellular	D	Virginia Beach	VA
4110700	Andrew David Balholm dba Norcell	Cellular	C	Clayton	WA
4108600	BCN Telecom, Inc.	Cellular	D	Morristown	NJ
4110550	Blue Casa Mobile, LLC	Cellular	D	Santa Barbara	CA
4108750	Blue Jay Wireless, LLC	Cellular	C	Carrollton	TX
4111050	BlueBird Communications, LLC	Cellular	C	New York	NY
4202300	Bluegrass Wireless, LLC	Cellular	A	Elizabethtown	KY
4107600	Boomerang Wireless, LLC	Cellular	B	Hiawatha	IA
4105500	BullsEye Telecom, Inc.	Cellular	D	Southfield	MI
4110050	CampusSims, Inc.	Cellular	D	Boston	MA
4100700	Cellco Partnership dba Verizon Wireless	Cellular	A	Basking Ridge	NJ
4106600	Cintex Wireless, LLC	Cellular	D	Rockville	MD
4111000	ComApp Technologies LLC	Cellular	C	Melrose	MA
4101900	Consumer Cellular, Incorporated	Cellular	A	Portland	OR
4106400	Credo Mobile, Inc.	Cellular	A	San Francisco	CA
4108850	Cricket Wireless, LLC	Cellular	A	San Antonio	TX
4001900	CTC Communications Corp. d/b/a EarthLink Business I	Cellular	D	Grand Rapids	MI
10640	Cumberland Cellular Partnership	Cellular	A	Elizabethtown	KY
4101000	East Kentucky Network, LLC dba Appalachian Wireless	Cellular	A	Ivel	KY
4002300	Easy Telephone Service Company dba Easy Wireless	Cellular	D	Ocala	FL
4109500	Enhanced Communications Group, LLC	Cellular	D	Bartlesville	OK
4110450	Excellus Communications, LLC	Cellular	D	Chattanooga	TN
4105900	Flash Wireless, LLC	Cellular	C	Concord	NC
4104800	France Telecom Corporate Solutions L.L.C.	Cellular	D	Oak Hill	VA
4109350	Global Connection Inc. of America	Cellular	D	Norcross	GA
4102200	Globalstar USA, LLC	Cellular	B	Covington	LA
4109600	Google North America Inc.	Cellular	A	Mountain View	CA
33350363	Granite Telecommunications, LLC	Cellular	D	Quincy	MA
4106000	GreatCall, Inc. d/b/a Jitterbug	Cellular	A	San Diego	CA
10630	GTE Wireless of the Midwest dba Verizon Wireless	Cellular	A	Basking Ridge	NJ
4110600	Horizon River Technologies, LLC	Cellular	C	Atlanta	GA
4103100	i-Wireless, LLC	Cellular	A	Newport	KY
4109800	IM Telecom, LLC d/b/a Infiniti Mobile	Cellular	D	Tulsa	OK
22215360	KDDI America, Inc.	Cellular	D	New York	NY
10872	Kentucky RSA #1 Partnership	Cellular	A	Basking Ridge	NJ
10680	Kentucky RSA #3 Cellular General	Cellular	A	Elizabethtown	KY
10681	Kentucky RSA #4 Cellular General	Cellular	A	Elizabethtown	KY
4109750	Konatel, Inc. dba telecom.mobi	Cellular	D	Johnstown	PA
4110900	Lunar Labs, Inc.	Cellular	C	Detroit	MI
4107300	Lycamobile USA, Inc.	Cellular	D	Newark	NJ
4108800	MetroPCS Michigan, LLC	Cellular	A	Bellevue	WA
4109650	Mitel Cloud Services, Inc.	Cellular	D	Mesa	AZ
4202400	New Cingular Wireless PCS, LLC dba AT&T Mobility, PCS	Cellular	A	San Antonio	TX
10900	New Par dba Verizon Wireless	Cellular	A	Basking Ridge	NJ
4000800	Nextel West Corporation	Cellular	D	Overland Park	KS
4001300	NPCR, Inc. dba Nextel Partners	Cellular	D	Overland Park	KS

4001800	OnStar, LLC	Cellular	A	Detroit	MI
4110750	Onvoy Spectrum, LLC	Cellular	C	Plymouth	MN
4109050	Patriot Mobile LLC	Cellular	D	Southlake	TX
4110250	Plintron Technologies USA LLC	Cellular	D	Bellevue	WA
33351182	PNG Telecommunications, Inc. dba PowerNet Global Communications	Cellular	D	Cincinnati	OH
4202100	Powertel/Memphis, Inc. dba T-Mobile	Cellular	A	Bellevue	WA
4107700	Puretalk Holdings, LLC	Cellular	A	Covington	GA
4106700	Q Link Wireless, LLC	Cellular	A	Dania	FL
4108700	Ready Wireless, LLC	Cellular	B	Hiawatha	IA
4110500	Republic Wireless, Inc.	Cellular	D	Raleigh	NC
4111100	ROK Mobile, Inc.	Cellular	C	Culver City	CA
4106200	Rural Cellular Corporation	Cellular	A	Basking Ridge	NJ
4108550	Sage Telecom Communications, LLC dba TruConnect	Cellular	D	Los Angeles	CA
4109150	SelecTel, Inc. d/b/a SelecTel Wireless	Cellular	D	Freemont	NE
4106300	SI Wireless, LLC	Cellular	A	Carbondale	IL
4110150	Spectrotel, Inc. d/b/a Touch Base Communications	Cellular	D	Neptune	NJ
4200100	Sprint Spectrum, L.P.	Cellular	A	Atlanta	GA
4200500	SprintCom, Inc.	Cellular	A	Atlanta	GA
4109550	Stream Communications, LLC	Cellular	D	Dallas	TX
4110200	T C Telephone LLC d/b/a Horizon Cellular	Cellular	D	Red Bluff	CA
4202200	T-Mobile Central, LLC dba T-Mobile	Cellular	A	Bellevue	WA
4002500	TAG Mobile, LLC	Cellular	D	Carrollton	TX
4109700	Telecom Management, Inc. dba Pioneer Telephone	Cellular	D	South Portland	ME
4107200	Telefonica USA, Inc.	Cellular	D	Miami	FL
4108900	Telrite Corporation dba Life Wireless	Cellular	D	Covington	GA
4108450	Tempo Telecom, LLC	Cellular	D	Kansas City	MO
4109950	The People's Operator USA, LLC	Cellular	D	New York	NY
4109000	Ting, Inc.	Cellular	A	Toronto	ON
4110400	Torch Wireless Corp.	Cellular	D	Jacksonville	FL
4103300	Touchtone Communications, Inc.	Cellular	D	Whippany	NJ
4104200	TracFone Wireless, Inc.	Cellular	D	Miami	FL
4002000	Truphone, Inc.	Cellular	D	Durham	NC
4110300	UVNV, Inc.	Cellular	D	Costa Mesa	CA
4105700	Virgin Mobile USA, L.P.	Cellular	A	Atlanta	GA
4110800	Visible Service LLC	Cellular	C	Lone Tree	CO
4106500	WiMacTel, Inc.	Cellular	D	Palo Alto	CA
4110950	Wing Tel Inc.	Cellular	C	New York	NY
4109900	Wireless Telecom Cooperative, Inc. dba theWirelessFreeway	Cellular	D	Louisville	KY