

COMMONWEALTH OF KENTUCKY
BEFORE THE PUBLIC SERVICE COMMISSION

In the Matter of:

**THE APPLICATION OF LOUISVILLE GAS AND)
ELECTRIC COMPANY TO MODIFY ITS)
CERTIFICATE OF PUBLIC CONVENIENCE) CASE NO. 2012-00469
AND NECESSITY AS TO THE MILL CREEK)
UNIT 3 FLUE-GAS DESULFURIZATION UNIT)**

APPLICATION

Louisville Gas and Electric Company (“LG&E”), pursuant to KRS 278.020(1), KRS 278.183, and 807 KAR 5:001, Sections 8 and 9, hereby petitions the Kentucky Public Service Commission (“Commission”) by application to issue an order modifying the Certificate of Public Convenience and Necessity granted by the Commission in Case No. 2011-00162 to permit LG&E to construct a new wet flue gas desulfurization system (“WFGD”) to serve Unit 3 at the Mill Creek Generating Station instead of rehabilitating the existing WFGD at Unit 4.

LG&E consulted with all of the interveners in Case No. 2011-00162 concerning this proposal. The Attorney General, the Kentucky Industrial Utility Customers, Inc., The Kroger Company, Department of Defense and Other Federal Executive Agencies, and the Metropolitan Housing Coalition have authorized LG&E to state that they do not object to the proposal in this Application.

In support of this Application, LG&E states as follows:

1. Address: The applicant’s full name and post office address is: Louisville Gas and Electric Company, 220 West Main Street, Post Office Box 32010, Louisville, Kentucky 40202.
2. Articles of Incorporation: A certified copy of LG&E’s Articles of Incorporation are on file with the Commission in Case No. 2010-00204, *In the Matter of: Joint Application of*

PPL Corporation, E.ON AG, E.ON U.S. Investments Corp., E.ON U.S. LLC, Louisville Gas and Electric Company, and Kentucky Utilities Company for Approval of an Acquisition of Ownership and Control of Utilities, filed on May 28, 2010, and is incorporated by reference herein pursuant to 807 KAR 5:001, Section 8(3).

3. LG&E is a public utility, as defined in KRS 278.010(3)(a), engaged in the electric and gas business. LG&E generates and purchases electricity, and distributes and sells electricity at retail in Jefferson County and portions of Bullitt, Hardin, Henry, Meade, Oldham, Shelby, Spencer, and Trimble Counties. LG&E also purchases, stores, and transports natural gas and distributes and sells natural gas at retail in Jefferson County and portions of Barren, Bullitt, Green, Hardin, Hart, Henry, Larue, Marion, Meade, Metcalfe, Nelson, Oldham, Shelby, Spencer, Trimble, and Washington Counties.

Background of the Certificates of Public Convenience and Necessity Awarded in Case No. 2011-00162 for the Mill Creek Units

4. In Case No. 2011-00162, *In the Matter of: Application of Louisville Gas and Electric Company for Certificates of Public Convenience and Necessity and Approval of Its 2011 Compliance Plan for Recovery by Environmental Surcharge*, LG&E sought the Commission's approval of certain Certificates of Public Convenience and Necessity ("Certificates"), which included Certificates for projects related to its Mill Creek generating station.

5. In its Final Order in Case No. 2011-00162, the Commission granted Certificates for LG&E to: build two WFGD units (one to serve both Mill Creek Units 1 and 2, another to serve Mill Creek Unit 4); to tie Mill Creek 3 into the existing (but rehabilitated) Mill Creek Unit 4 WFGD, and then to remove the existing WFGDs on Mill Creek Units 1, 2, and 3. These new and rehabilitated facilities continue to be needed to comply with the one-hour SO₂ National

Ambient Air Quality Standard (“NAAQS”) and the Mercury and Toxic Air Standards (“MATS”) Rule (formerly known as the Hazardous Air Pollutants (“HAPs”) Rule).¹

Request to Modify the Existing Certificate of Public Convenience and Necessity for the Existing Unit 4 WFGD

6. The 2010 Black & Veatch Study, which LG&E utilized to develop its 2011 Environmental Compliance Plan, recommended new WFGDs for all units at Mill Creek, including Unit 3. At the time LG&E filed its application in Case No. 2011-00162, based on preliminary information it believed a viable compliance option and a more cost effective solution would be to rehabilitate the existing WFGD at Unit 4, and therefore did not include a new Unit 3 WFGD as part of its Plan. Instead, LG&E sought and obtained approval to rehabilitate the existing WFGD at Unit 4, then tie Unit 3 into the rehabilitated facility.

7. Statement of Need (807 KAR 5:001 § 9(2)(a)): The reasons supporting LG&E’s need to provide rehabilitated or new WFGD facilities for Mill Creek Unit 3 remain unchanged from LG&E’s application in Case No. 2011-00162, as LG&E must comply with all applicable environmental rules and regulations. In particular, LG&E requires rehabilitated or new WFGD facilities for Mill Creek Unit 3 to comply with the impacts of the tightened National Ambient Air Quality Standards (“NAAQS”) 1-hour SO₂ requirement that will establish a lower stack emission rate from all Mill Creek units by 2017 as a part of the State Implementation Plan (“SIP”) for the non-attainment status of Jefferson County, Kentucky. This requirement is independent of the Cross-State Air Pollution Rule (“CSAPR”), which the U.S. Court of Appeals for the D.C. Circuit vacated on August 21, 2012.² In this application, LG&E seeks only an

¹ With the issuance of the final standards on December 16, 2011, the US EPA began using the phrase Mercury and Toxic Air Standards (“MATS”) Rule instead of HAPs. See 77 FR 9304, Feb. 16, 2012 (available at <http://www.epa.gov/mats/actions.html>).

² Order available at <http://www.scribd.com/doc/103461023/EME-Homer-City-Generation-v-EPA-No-11-1302-Striking-Down-EPA-Transport-Rule>. The predecessor rule to CSAPR, the Clean Air Interstate Rule (“CAIR”),

amendment to its Certificate authority in order to utilize a more cost effective manner of compliance.

There are no utilities, corporations, or persons with whom the proposed new construction is likely to compete.

8. Permits or Franchises (807 KAR 5:001 § 9(2)(b)): LG&E submitted to the Louisville Metro Air Pollution Control District (“LMAPCD”) requests to construct the proposed Mill Creek WFGD in June 2011. The LMAPCD issued a draft construction permit in May 2012, and issued a final air permit on June 18, 2012, with an effective date of June 15, 2012, allowing construction to commence. LG&E will also seek any additional applicable construction permits and an updated Title V operating permit.

9. Description of Proposed Construction (807 KAR 5:001 § 9(2)(c)): Since the Commission issued the Certificates in Case No. 2011-00162, LG&E, in accordance with prudent practices and competitive bid policies, has proceeded with further engineering assessment beyond the conceptual stages, updated, monitored, and re-evaluated the costs associated with the WFGDs. As part of this ongoing evaluation, LG&E has determined that the total current estimated costs associated with rehabilitating the existing WFGD at Mill Creek Unit 4 for an additional twenty-plus-year life, which, through a tie-in, would serve Mill Creek Unit 3, exceed the costs of constructing a new WFGD to serve Mill Creek Unit 3. To complete the environmental compliance projects in the most cost effective manner, LG&E is requesting the Commission modify its Certificate with regard to rehabilitating the existing WFGD at Mill Creek Unit 4 and instead permit LG&E to construct a new WFGD to serve Unit 3. LG&E is also proposing to demolish the existing WFGD at Unit 4 to provide space for the new WFGD.

remains in effect. *Id.* at 60 (“EPA must continue administering CAIR pending the promulgation of a valid replacement.”).

10. When LG&E proposed rehabilitating the existing WFGD at Unit 4, it had preliminary information from Babcock Power Environmental Inc. (“Babcock”) regarding the costs to increase the WFGD SO₂-removal efficiency via rehabilitation and replacement of equipment and components of the existing WFGD based upon an engineering study completed in February 2011. Those costs were combined with structural steel estimates provided by Black and Veatch in their Phase II report and thought to be the most cost-effective approach at the time. While Case No. 2011-00162 was proceeding, LG&E began receiving bids for the projects it had proposed. As part of that process, on December 2, 2011, Babcock presented to LG&E the Mill Creek Unit 4 WFGD Upgrade Study developed after a detailed internal component inspection during an outage of Unit 4 and its WFGD, a copy of which is attached to the testimony of John N. Voyles as Exhibit JNV-1. That report identified more significant levels of repair were necessary beyond the components of the WFGD that affected sulfur dioxide removal performance that the initial conceptual study contemplated. After this later report, a comprehensive inspection and estimate were developed to identify all existing components of the existing Unit 4 WFGD that would need refurbished or replaced to provide a twenty-plus year life as that of a new WFGD. The rehabilitation cost estimates were revised to reflect these process improvement and infrastructure modification determinations. Based upon further engineering assessments and revised rehabilitation costs, which are approximately \$161 million, LG&E began evaluating the cost of building a new WFGD instead of rehabilitating the existing Unit 4 WFGD. LG&E contacted Zachry Holdings, Inc. (“Zachry”) in July 2012 to obtain an estimate of the total expected construction costs to construct a new WFGD for Unit 3 similar to what was contracted to them to construct for Units 4 and the combined WFGD for Units 1 and 2, as well as the cost to demolish the existing WFGD at Unit 4. Zachry is performing the majority of the

other environmental compliance projects at Mill Creek. As set forth in Exhibit JNV-2, on September 11, 2012, Zachry provided its estimated cost to complete these projects, which is approximately \$132 million, roughly \$29 million less than the updated cost from Babcock to rehabilitate the existing WFGD at Mill Creek Unit 4. This estimate is consistent with the cost for the other two WFGDs which Zachry is contracted for at Mill Creek, both of which are significantly lower than the estimated cost in the 2011 filing. The refurbished and new WFGD option values represent the installed cost with a Level I engineering accuracy.

11. Area Maps (807 KAR 5:001 § 9(2)(d)): The required area maps showing the location of the proposed construction for the new WFGD is attached as Application Exhibit 1.

12. Financing Plans (807 KAR 5:001 § 9(2)(e)): LG&E proposes to finance the proposed new WFGD for Mill Creek Unit 3 in the manner described in the testimony of Lonnie E. Bellar. LG&E does not propose any changes to the method of financing the construction from that presented in Case No. 2011-00162.

13. Estimated Cost of Operation (807 KAR 5:001 § 9(2)(f)): LG&E closely examined, by line item, the estimates Babcock and Zachry provided, in order to assess its overall confidence in the expected accuracy of the costs. An updated analysis of the retire/retrofit decision made in the 2011 Environmental Compliance Plan utilizing these costs was performed and a copy of the document LG&E prepared that illustrates this analysis is included in Exhibit JNV-3. After completing this review, LG&E determined that constructing a new WFGD for Unit 3 and demolishing the existing WFGD at Unit 4 was a more cost-effective method of compliance if an amendment to its Certificate could be obtained expeditiously from the Commission. The estimated annual cost of operating the new WFGD is also set forth in Exhibit JNV-3.

14. Although the total estimated capital cost for all of the compliance projects on Mill Creek Unit 3 has increased from the 2011 Environmental Compliance Plan estimate by approximately \$21 million, the anticipated fixed and variable operating expenses have decreased largely because of the lower-than-expected cost of operating the baghouse, including the lower cost of sorbent injection for mercury and sulfuric acid. When the 2011 Environmental Compliance Plan was developed, LG&E based its projected baghouse operating costs on the Black & Veatch studies for high-sulfur coal applications and its limited experience with operating a similar facility at Trimble County Unit 2. As its experience has developed, LG&E has further revised the projected costs, resulting in a reduction in operating expenses. As such, the decision to construct a new WFGD, even at a higher capital cost than contained in the 2011 Environmental Compliance Plan, does not affect the fiscal prudence of LG&E's decision to retrofit, instead of retire, Mill Creek Unit 3.

15. In fact, the Net Present Value of Revenue Requirements ("NPVRR") savings associated with retrofitting Mill Creek Unit 3, which were initially projected to be \$756 million, can be maximized even if LG&E rehabilitates the existing WFGD at Mill Creek Unit 4. To maximize the NPVRR savings to customers, however, approval to modify the Certificate to permit LG&E to construct a new WFGD must be obtained by January 18, 2013. This should allow LG&E to complete the new WFGD by April 2016, which is the date it must be in compliance with the MATS Rule (with a one year extension being granted). Under this scenario, the NPVRR savings to retrofit Mill Creek Unit 3 are \$820 million, which is a \$64 million increase (eight percent) over the projected savings in the 2011 Environmental Compliance Plan. Under this scenario, Commission approval as requested should ensure construction can be commenced and be completed in a timely manner. If Commission approval to modify LG&E's

Certificate is not obtained as requested, constructing a new WFGD will not meet the compliance deadline and will no longer maximize NPVRR savings; instead based on this analysis, rehabilitating the existing WFGD at Unit 4 as planned would be more cost effective to customers, as the NPVRR savings for rehabilitating the WFGD results in \$794 million in savings.

16. If LG&E constructs a new WFGD, but is unable to complete construction prior to the April 2016 compliance date or obtain a second year extension of the MATS Rule compliance date, the savings steadily decline because LG&E will no longer be able to operate Mill Creek Unit 3 and thus will have to purchase power from a third party to replace its capacity.³ For example, if the new WFGD is not completed until October 2016, a six-month delay, the NPVRR savings decline to \$782 million, based on estimated costs to purchase power from a third party. These analyses demonstrate there is a short window of opportunity for LG&E to maximize NPVRR savings under the new construction option.

17. LG&E supports its request for a Certificate modification with the verified testimony and exhibits of the following persons:

- Lonnie E. Bellar, Vice President – State Regulation and Rates
- John N. Voyles, Vice President – Transmission and Generation Services

18. Prior to filing this Application, LG&E discussed its plan to seek a modification of the Certificate in the manner herein described with the intervenors to Case No. 2011-00162. The Office of the Attorney General, Utility Rate Intervention Division; Kentucky Industrial Utility Customers, Inc.; The Kroger Co.; Metropolitan Housing Coalition; and the United States Department of Defense and Other Federal Executive Agencies have authorized counsel for

³ It is not clear that LG&E will be able to obtain a second year extension.

LG&E to represent in this Application that they have no objection to LG&E's Application or the relief requested herein.

WHEREFORE, Louisville Gas and Electric Company respectfully asks the Commission to enter an order by January 18, 2013 modifying the Certificate awarded in Case No. 2011-00162 to permit it to construct a new WFGD to serve Mill Creek Unit 3.

Dated: October 25, 2012

Respectfully submitted,




Kendrick R. Riggs
W. Duncan Crosby III
Monica H. Braun
Stoll Keenon Ogden PLLC
2000 PNC Plaza
500 West Jefferson Street
Louisville, Kentucky 40202
Telephone: (502) 333-6000

Allyson K. Sturgeon
Senior Corporate Attorney
LG&E and KU Services Company
220 West Main Street
Louisville, Kentucky 40202
Telephone: (502) 627-2088

Counsel for Louisville Gas and Electric Company

CERTIFICATE OF COMPLIANCE

In accordance with Ordering Paragraph No. 10 of the Commission's October 25, 2012 Order, this is to certify that Louisville Gas and Electric Company's October 25, 2012 electronic filing is a true and accurate copy of the documents being filed in paper medium; that the electronic filing has been transmitted to the Commission on October 25, 2012; that there are currently no parties that the Commission has excused from participation by electronic means in this proceeding; and that an original and one copy of the filing will be hand-delivered to the Commission on October 26, 2012. There are currently no other parties to this proceeding.

A handwritten signature in blue ink, reading "Gerald R. Riggs". The signature is written in a cursive style with a horizontal line at the end.



Counsel for Louisville Gas and Electric Company

Application Exhibit 1


Mill Creek Maps



PPL companies



Parallel scale at 38°N 0°E




Mill Creek Generating Station



PPL companies

1000 2000 3000 4000 5000 6000 7000 FEET
0 1 2 3 4 5 6 7 8 9 10 KILOMETER

CONTOUR INTERVAL 10 FEET
DOTTED LINES REPRESENT 5-FOOT CONTOURS
NATIONAL GEODETIC VERTICAL DATUM OF 1929



COMMONWEALTH OF KENTUCKY
BEFORE THE PUBLIC SERVICE COMMISSION

In the Matter of:

**THE APPLICATION OF LOUISVILLE GAS)
AND ELECTRIC COMPANY TO MODIFY ITS)
CERTIFICATE OF PUBLIC CONVENIENCE)
AND NECESSITY AS TO THE MILL CREEK)
UNIT 3 FLUE-GAS DESULFURIZATION UNIT)**

CASE NO. 2012-00469

**TESTIMONY OF
LONNIE E. BELLAR
VICE PRESIDENT, STATE REGULATION AND RATES
LOUISVILLE GAS AND ELECTRIC COMPANY**

Filed: October 25, 2012

1 **Q. Please state your name, position and business address.**

2 A. My name is Lonnie E. Bellar. I am the Vice President, State Regulation and Rates for
3 Kentucky Utilities Company (“KU”) and Louisville Gas and Electric Company
4 (“LG&E”). I am employed by LG&E and KU Services Company, which provides
5 services to KU and LG&E (collectively “the Companies”). My business address is
6 220 West Main Street, Louisville, Kentucky 40202. A complete statement of my
7 education and work experience is attached to this testimony as Appendix A.

8 **Q. Have you previously testified before the Kentucky Public Service Commission?**

9 A. Yes. I have testified before the Commission numerous times, including the
10 Companies’ most recent base rate cases.¹ Also, I testified in the Companies’ 2011
11 Environmental Compliance Plan cases.²

12 **Q. What is the purpose of your testimony?**

13 A. The purpose of my testimony is to describe the savings customers will experience if
14 the Commission modifies the Certificate of Public Convenience and Necessity
15 (“Certificate”) the Commission issued in LG&E’s 2011 Environmental Compliance
16 Plan case. Specifically, LG&E asks the Commission to modify the Certificate related
17 to Mill Creek Unit 3 to permit LG&E to build a new wet flue-gas-desulfurization
18 system (“WFGD”) for Mill Creek Unit 3 rather than rehabilitating the existing Mill
19 Creek Unit 4 WFGD to serve Mill Creek Unit 3.

¹*In the Matter of: Application of Kentucky Utilities Company for an Adjustment of Its Base Rates*, Case No. 2012-00221; *In the Matter of: Application of Louisville Gas and Electric Company for an Adjustment of Its Electric and Gas Base Rates, a Certificate of Public Convenience and Necessity, Approval of Ownership of Gas Service Lines and Risers, and a Gas Line Surcharge*, Case No. 2012-00222.

²Case Nos. 2011-00161 (KU 2011 Environmental Compliance Plan), 2011-00162 (LG&E 2011 Environmental Compliance Plan).

1 I will also describe the views of those interveners from LG&E's 2011
2 Environmental Compliance Plan case who have authorized LG&E to report their
3 position to the Commission.

4 **Q. How will building a new WFGD for Mill Creek Unit 3 be more economical than**
5 **refurbishing the existing Mill Creek Unit 4 WFGD to serve Mill Creek Unit 3?**

6 A. As John N. Voyles explains in greater detail in his testimony, since the Commission
7 issued its final order in LG&E's 2011 Environmental Compliance Plan case, LG&E
8 has obtained further engineering studies and cost estimates showing that rehabilitating
9 the existing Mill Creek Unit 4 WFGD to serve Mill Creek Unit 3 will be significantly
10 more expensive than initially estimated: \$161 million in estimated capital cost rather
11 than \$74 million. Building a new WFGD for Mill Creek Unit 3 will have an
12 estimated capital cost of \$132 million.

13 **Q. If the WFGD-related estimated capital costs for Mill Creek Unit 3 are higher**
14 **than LG&E expected, is it still true that building environmental-compliance**
15 **equipment for the unit is more economical than retiring and replacing it?**

16 A. Yes. As Mr. Voyles explains more fully in his testimony, other reduced estimated
17 capital costs and lower anticipated operating costs have more than offset the effect of
18 the higher estimated WFGD capital cost. In fact, the Net Present Value of Revenue
19 Requirement ("NPVRR") savings associated with retrofitting Mill Creek Unit 3 rather
20 than retiring it, which were initially projected to be \$756 million, can be maximized
21 even if LG&E rehabilitates the existing WFGD at Mill Creek Unit 4. But to
22 maximize the NPVRR savings to customers as shown in the table below, LG&E must
23 receive approval to modify the Mill Creek Unit 3 Certificate by January 18, 2013:

24 **Table 1: NPVRR Savings of WFGD Options for Mill Creek Unit 3**

	2011 ECR Plan	Updated Rehab	New FGD	New FGD with Delay
<i>Retrofit Savings (NPVRR, 2011 \$M)</i>	<i>756</i>	<i>794</i>	<i>820</i>	<i>782</i>

1

2

3

4

5

6

7

8

9

10

Q. How does LG&E plan to finance construction of the new Mill Creek Unit 3 WFGD?

11

12

A. LG&E expects to finance the costs of the new facility with a combination of new debt and equity. The mix of debt and equity used to finance the project will be determined so as to allow LG&E to maintain its strong investment-grade credit rating. To the extent that tax-exempt financing may be available for these projects, the Companies anticipate using such opportunities to the extent that they are reasonably cost-effective. This is the same financing approach LG&E proposed to finance rehabilitating the Mill Creek Unit 4 WFGD to serve Mill Creek Unit 3 in LG&E’s 2011 Environmental Compliance Plan case.

13

14

15

16

17

18

19

20

Q. Has LG&E communicated with the interveners in LG&E’s 2011 Environmental Compliance Plan case concerning this proposal?

21

1 A. Yes. LG&E reached out to all of the interveners in LG&E's 2011 Environmental
2 Compliance Plan case concerning this proposal, inviting them to attend an informal
3 conference at the Commission's offices on October 10, 2012. LG&E subsequently
4 followed up with the interveners to ask about their position on LG&E's proposal to
5 build a new WFGD for Mill Creek Unit 3. The Attorney General, the Kentucky
6 Industrial Utility Customers, Inc., The Kroger Company, the Department of Defense
7 and Other Federal Agencies, and the Metropolitan Housing Coalition informed
8 LG&E that they do not object to the proposal and authorized LG&E to make the
9 Commission aware of the same.

10 **Q. What is your recommendation to the Commission?**

11 A. I recommend that the Commission issue an order by January 18, 2013 modifying the
12 Certificate the Commission issued in LG&E's 2011 Environmental Compliance Plan
13 case related to Mill Creek Unit 3 to permit LG&E to build a new WFGD to serve the
14 unit and to demolish rather than rehabilitate the existing Mill Creek Unit 4 WFGD.
15 This will result in lower costs for customers, less SO₂ emissions (as Mr. Voyles
16 describes in his testimony), and is not opposed by most of the interveners to LG&E's
17 2011 Environmental Compliance Plan case.

18 **Q. Does this conclude your testimony?**

19 A. Yes, it does.

APPENDIX A

Lonnie E. Bellar

LG&E and KU Energy LLC
220 West Main Street
Louisville, Kentucky 40202

Education

Bachelors in Electrical Engineering;
University of Kentucky, May 1987
Bachelors in Engineering Arts;
Georgetown College, May 1987
E.ON Academy, Intercultural Effectiveness Program: 2002-2003
E.ON Finance, Harvard Business School: 2003
E.ON Executive Pool: 2003-2007
E.ON Executive Program, Harvard Business School: 2006
E.ON Academy, Personal Awareness and Impact: 2006

Professional Experience

E.ON U.S. LLC

Vice President, State Regulation and Rates	Aug. 2007 – Present
Director, Transmission	Sept. 2006 – Aug. 2007
Director, Financial Planning and Controlling	April 2005 – Sept. 2006
General Manager, Cane Run, Ohio Falls and Combustion Turbines	Feb. 2003 – April 2005
Director, Generation Services	Feb. 2000 – Feb. 2003
Manager, Generation Systems Planning	Sept. 1998 – Feb. 2000
Group Leader, Generation Planning and Sales Support	May 1998 – Sept. 1998

Kentucky Utilities Company

Manager, Generation Planning	Sept. 1995 – May 1998
Supervisor, Generation Planning	Jan. 1993 – Sept. 1995
Technical Engineer I, II and Senior, Generation System Planning	May 1987 – Jan. 1993

Professional Memberships

IEEE

Civic Activities

E.ON U.S. Power of One Co-Chair – 2007
Louisville Science Center – Board of Directors – 2008 – Present
Chairman of Louisville Science Center Board beginning June 2012
Metro United Way Campaign – 2008
UK College of Engineering Advisory Board – 2009 – Present

COMMONWEALTH OF KENTUCKY
BEFORE THE PUBLIC SERVICE COMMISSION

In the Matter of:

THE APPLICATION OF LOUISVILLE GAS)	
AND ELECTRIC COMPANY TO MODIFY ITS)	
CERTIFICATE OF PUBLIC CONVENIENCE)	CASE NO. 2012-00469
AND NECESSITY AS TO THE MILL CREEK)	
UNIT 3 FLUE-GAS DESULFURIZATION UNIT)	

TESTIMONY OF
JOHN N. VOYLES, JR.
VICE PRESIDENT, TRANSMISSION AND GENERATION SERVICES
LOUISVILLE GAS AND ELECTRIC COMPANY

Filed: October 25, 2012

1 **Q. Please state your name, position and business address.**

2 A. My name is John N. Voyles, Jr. I am the Vice President of Transmission and
3 Generation Services for Kentucky Utilities Company (“KU”) and Louisville Gas and
4 Electric Company (“LG&E”), and I am an employee of LG&E and KU Services
5 Company, which provides services to LG&E and KU (collectively “the Companies”).
6 My business address is 220 West Main Street, Louisville, Kentucky 40202. A
7 complete statement of my education and work experience is attached to this testimony
8 as Appendix A.

9 **Q. Have you previously testified before this Commission?**

10 A. Yes. I testified in the Companies’ 2011 and 2009 environmental compliance plan
11 cases,¹ and I testified in a number of earlier proceedings, including LG&E’s original
12 application for recovery of its 1995 Environmental Compliance Plan.²

13 **Q. Are you sponsoring any exhibits?**

14 A. Yes. I am sponsoring the following exhibits:

15 Exhibit JNV-1: Babcock Power Environmental Inc. Mill Creek Unit 4 Upgrade
16 Study

17 Exhibit JNV-2: Zachry New WFGD Estimate for Mill Creek Unit 3

18 Exhibit JNV-3: Update to Mill Creek 3 Retire/Retrofit Decision, October 2012

19 **Q. What is the purpose of your testimony?**

20 A. The purpose of my testimony is to describe the analysis LG&E recently undertook
21 concerning its Commission-approved plan to rehabilitate the existing wet flue-gas-

¹ Case Nos. 2011-00161 (KU 2011 Environmental Compliance Plan), 2011-00162 (LG&E 2011 Environmental Compliance Plan), 2009-00197 (KU 2009 Environmental Compliance Plan), and 2009-00198 (LG&E 2009 Environmental Compliance Plan).

² *In the Matter of: The Application of Louisville Gas and Electric Company for Approval of Compliance Plan and to Assess a Surcharge Pursuant to KRS 278.183 to Recover Costs of Compliance With Environmental Requirements For Coal Combustion Wastes and By-Products*, Case No. 93-332.

1 desulfurization system (“WFGD”) for Mill Creek Unit 4 for Mill Creek Unit 3’s
2 future use. The analysis shows (1) retrofitting Mill Creek Unit 3 with environmental
3 controls remains a lower-cost alternative than retiring the unit, (2) building a new
4 WFGD to serve Mill Creek Unit 3 will be lower-cost than rehabilitating the existing
5 Mill Creek Unit 4 WFGD, and (3) delaying the construction of a new WFGD for Mill
6 Creek Unit 3 by even six months could cause that option to become higher-cost than
7 rehabilitating the existing Mill Creek Unit 4 WFGD. In other words, the cost-saving
8 opportunity of building a new WFGD for Mill Creek Unit 3 is the reason LG&E
9 requests expedited action by the Commission to approve the modification to the
10 existing Certificate of Public Convenience and Necessity (“Certificate”) the
11 Commission issued in LG&E’s 2011 Environmental Compliance Plan case. LG&E
12 therefore asks the Commission to issue an order by January 18, 2013, granting a
13 Certificate modification authorizing LG&E to build a new WFGD for Mill Creek
14 Unit 3.

15 **Q. Why did LG&E seek a CPCN for an upgraded WFGD for Mill Creek Unit 3 in**
16 **its 2011 Environmental Compliance Plan case?**

17 A. As I explained in my testimony in that proceeding:
18 LG&E proposes to build two new FGDs (one to serve both Mill Creek Units 1
19 and 2, another to serve Mill Creek Unit 4), to tie Mill Creek Unit 3 into the
20 existing (but upgraded) Mill Creek Unit 4 FGD, and then to remove the
21 current FGDs on Mill Creek Units 1, 2, and 3. These new and upgraded
22 facilities are necessary to comply with the 1-hour SO₂ NAAQS [National
23 Ambient Air Quality Standards], under which Jefferson County is expected to
24 be declared a non-attainment area and would require SO₂ emission reductions

1 at Mill Creek. These projects also support compliance with the proposed
2 reductions on the emission of SO₂ from the [Cross-State Air Pollution Rule
3 (“CSAPR”)].³

4 LG&E witness Gary H. Revlett further explained in his testimony the SO₂ NAAQS
5 and its impact on Mill Creek:

6 [T]he EPA finalized a new 1-hour SO₂ NAAQS in June 2010, which required
7 state and local air pollution control agencies to develop implementation plans
8 for any non-attainment area. Jefferson County has already begun recording
9 SO₂ levels in excess of the new 1-hour NAAQS. According to the CAAA for
10 NAAQS, the LMAPCD [Louisville Metro Air Pollution Control District] must
11 declare the county to be in “non-attainment” of the standard, which the EPA
12 must confirm within 1 year. After that, the LMAPCD must file, and the EPA
13 must approve, a plan to bring the county back into attainment. Emission
14 sources must then take actions to reduce SO₂ emissions consistent with the
15 approved plan. As the largest SO₂ emitter in Jefferson County, the Mill Creek
16 Station will need to reduce its SO₂ emissions, which has been true of all the
17 previous SO₂ non-attainment plans developed by the LMAPCD.⁴

18 **Q. Please briefly explain the role and purpose of LMAPCD.**

19 A. For over sixty years, LMAPCD or its predecessors have studied and worked to
20 improve the air quality in Jefferson County, Kentucky. In 1952, the Kentucky
21 legislature passed KRS Chapter 77 authorizing the formation of county air pollution

³ *In the Matter of: Application of Louisville Gas and Electric Company for Certificates of Public Convenience and Necessity and Approval of Its 2011 Compliance Plan for Recovery by Environmental Surcharge*, Case No. 2011-00162, Testimony of John N. Voyles at 6-7 (June 1, 2011).

⁴ *In the Matter of: Application of Louisville Gas and Electric Company for Certificates of Public Convenience and Necessity and Approval of Its 2011 Compliance Plan for Recovery by Environmental Surcharge*, Case No. 2011-00162, Testimony of Gary H. Revlett at 3-4 (June 1, 2011).

1 control districts. The same year, the Air Pollution Control District of Jefferson
2 County was created and staffed with air quality professionals to study and improve air
3 quality in Louisville. LMAPCD is governed by the Air Pollution Control Board,
4 which includes seven members appointed by the Mayor of Louisville and approved
5 by the Louisville Metro Council.

6 Among other things, LMAPCD, as the only local air pollution control agency
7 in Kentucky, is responsible for developing the Jefferson County portion of the State
8 Implementation Plan (“SIP”). In addition, LMAPCD monitors and measures
9 throughout Jefferson County the concentration of pollutants under the NAAQS,
10 including ozone (O₃), carbon monoxide (CO), sulfur dioxide (SO₂), nitrogen dioxide
11 (NO₂) and nitric oxide (NO), inhalable particulates (PM₁₀), fine particulates (PM_{2.5})
12 and lead (Pb). Most of LMAPCD’s monitoring is currently conducted at seven air
13 monitoring sites. To insure national consistency in air monitoring data, EPA requires
14 that all sites meet certain criteria and that monitors are operated using approved
15 procedures. LMAPCD develops and submits its network plans to EPA for review and
16 approval.

17 **Q. Have portions of Jefferson County been designated by LMAPCD as non-**
18 **attainment areas under the 1-hour SO₂ NAAQS?**

19 A. Yes. In a letter dated June 2, 2011, Kentucky recommended to U.S. EPA Region 4
20 that all counties, except Jefferson County, be classified as attainment and Jefferson
21 County be designated as nonattainment. Following further discussions with staff at
22 U.S. EPA Region 4, LMAPCD performed further analysis to more precisely define
23 the area of Jefferson County to be designated nonattainment. On December 20, 2011,
24 Kentucky provided the results of U.S. EPA Region 4 analysis to EPA Region 4,

1 expressed its concurrence LMAPCD's review, and requested a specific boundary for
2 SO₂ nonattainment be established which includes the Mill Creek Generation Station.

3 **Q. What is the status of CSAPR?**

4 A. The U.S. Court of Appeals for the D.C. Circuit vacated CSAPR on August 21, 2012.⁵
5 The predecessor rule to CSAPR, the Clean Air Interstate Rule ("CAIR"), remains in
6 effect.⁶

7 **Q. Does a rehabilitated or new WFGD for Mill Creek Unit 3 continue to be
8 necessary even though CSAPR has been vacated?**

9 A. Yes. LG&E requires rehabilitated or new WFGD facilities for Mill Creek Unit 3 to
10 comply with the impacts of the tightened NAAQS 1-hour SO₂ requirement that will
11 establish a lower stack emission rate from all Mill Creek units by 2017 as a part of the
12 State Implementation Plan ("SIP") for the non-attainment status of Jefferson County,
13 Kentucky. This requirement is independent of CSAPR.

14 **Q. Why is LG&E asking the Commission to modify the Certificate it granted
15 LG&E concerning the WFGD to serve Mill Creek Unit 3?**

16 A. In LG&E's most recent Environmental Compliance Plan case, LG&E sought, and the
17 Commission granted, Certificates related to a number of 2011 Environmental
18 Compliance Plan projects.⁷ Among the Certificates the Commission granted was one
19 authorizing LG&E to rehabilitate the existing Mill Creek Unit 4 WFGD and to tie
20 Mill Creek Unit 3 into it. Upgraded scrubbing ability is necessary for Mill Creek Unit
21 3 to comply with the impacts of the 1-hour SO₂ National Ambient Air Quality

⁵ Order available at <http://www.scribd.com/doc/103461023/EME-Homer-City-Generation-v-EPA-No-11-1302-Striking-Down-EPA-Transport-Rule>.

⁶ *Id.* at 60 ("EPA must continue administering CAIR pending the promulgation of a valid replacement.").

⁷ *In the Matter of: Application of Louisville Gas and Electric Company for Certificates of Public Convenience and Necessity and Approval of Its 2011 Compliance Plan for Recovery by Environmental Surcharge*, Case No. 2011-00162, Order (Dec. 15, 2011).

1 Standard (“NAAQS”). At the time of LG&E’s application and the Commission’s
2 approval, LG&E’s conceptual engineering information indicated that an option of
3 rehabilitating the existing Mill Creek Unit 4 WFGD for Mill Creek Unit 3’s use
4 would be the lowest-reasonable-cost means to achieve additional SO₂ reductions from
5 Mill Creek Unit 3’s flue gas.⁸

6 Since the Commission issued the Certificate related to Mill Creek Unit 3 in
7 Case No. 2011-00162, LG&E, in accordance with prudent practices and competitive
8 bid policies, has proceeded with further engineering assessment beyond the
9 conceptual stages, updated, monitored, and re-evaluated the costs associated with the
10 WFGDs. As part of this ongoing evaluation, LG&E has determined that the total
11 current estimated costs associated with rehabilitating the existing WFGD at Mill
12 Creek Unit 4 for an additional twenty-plus-year life, which, through a tie-in, would
13 serve Mill Creek Unit 3, exceed the costs of constructing a new WFGD to serve Mill
14 Creek Unit 3. To complete the environmental compliance projects in the most cost-
15 effective manner, LG&E asks the Commission to modify its Certificate with regard to
16 rehabilitating the existing WFGD at Mill Creek Unit 4 and instead permit LG&E to
17 construct a new WFGD to serve Unit 3. LG&E is also proposing to demolish the
18 existing WFGD at Unit 4 to provide space for the new WFGD.

19 **Q. Please describe in greater detail how LG&E has reached the conclusion that**
20 **building a new WFGD for Mill Creek Unit 3 will be more economical than**
21 **rehabilitating the existing Mill Creek Unit 4 WFGD to serve Mill Creek Unit 3.**

22 A. When LG&E proposed rehabilitating the existing WFGD at Unit 4, it had preliminary
23 information from Babcock Power Environmental Inc. (“Babcock”) regarding the

⁸ This compared favorably to the 2010 Black & Veatch report for constructing a new WFGD for Mill Creek Unit 3. See Case No. 2011-00162, Testimony of John N. Voyles Exh. JNV-2 Appx. A (June 1, 2011).

1 costs to increase the WFGD SO₂-removal efficiency via rehabilitation and
2 replacement of equipment and components of the existing WFGD based upon an
3 engineering study completed in February 2011. Those costs were combined with
4 structural steel estimates provided by Black and Veatch in their Phase II report and
5 thought to be the most cost-effective approach at the time. While Case No. 2011-
6 00162 was proceeding, LG&E began receiving bids for the projects it had proposed.
7 As part of that process, on December 2, 2011, Babcock presented to LG&E the Mill
8 Creek Unit 4 WFGD Upgrade Study developed after performing detailed internal
9 component inspection during an outage of Unit 4 and its WFGD after the filing in
10 June 2011, a copy of which is attached as Exhibit JNV-1. That report identified more
11 significant levels of repair were necessary beyond the components of the WFGD that
12 affected sulfur dioxide removal performance than the initial conceptual study
13 contemplated. After this later report, a comprehensive inspection and estimate were
14 developed to identify all existing components of the existing Unit 4 WFGD that
15 would need refurbished or replaced to provide a twenty-plus year life as that of a new
16 WFGD. The rehabilitation cost estimates were revised to reflect these process
17 improvement and infrastructure modification determinations. Based upon further
18 engineering assessments and revised rehabilitation costs, which are approximately
19 \$161 million, LG&E began evaluating the cost of building a new WFGD instead of
20 rehabilitating the existing Unit 4 WFGD. LG&E contacted Zachry Holdings, Inc.
21 (“Zachry”) in July 2012 to obtain an estimate of the total expected construction costs
22 to construct a new WFGD for Unit 3 similar to what was contracted to them to
23 construct for Units 4 and the combined WFGD for Units 1 and 2, as well as the cost
24 to demolish the existing WFGD at Unit 4. Zachry is performing the majority of the

1 other environmental compliance projects at Mill Creek. As set forth in Exhibit JNV-
2 2, on September 11, 2012, Zachry provided its estimated cost to complete these
3 projects, which is approximately \$132 million, roughly \$29 million less than the
4 updated cost from Babcock to rehabilitate the existing WFGD at Mill Creek Unit 4.
5 This estimate is consistent with the cost for the other two WFGDs which Zachry is
6 contracted for at Mill Creek, both of which are significantly lower than the estimated
7 cost in the 2011 filing. The refurbished and new WFGD option values represent the
8 installed cost with a Level I engineering accuracy.

9 LG&E closely examined, by line item, the estimates Babcock and Zachry
10 provided, to assess its overall confidence in the expected accuracy of the costs. An
11 updated analysis of the retire/retrofit decision made in the 2011 Environmental
12 Compliance Plan utilizing these costs was performed and a copy of the document
13 LG&E prepared that illustrates this analysis is attached as Exhibit JNV-3. After
14 completing this review, LG&E determined that constructing a new WFGD for Unit 3
15 and demolishing the existing WFGD at Unit 4 was a more cost-effective method of
16 compliance if an amendment to its Certificate could be obtained expeditiously from
17 the Commission. The estimated annual cost of operating the new WFGD is also set
18 forth in the attached Exhibit JNV-3.

19 **Q. If the WFGD-related capital costs for Mill Creek Unit 3 are higher than LG&E**
20 **expected, is it still true that building environmental-compliance equipment for**
21 **the unit is more economical than retiring and replacing it?**

22 A. Yes. Although the total estimated capital cost for all of the compliance projects for
23 Mill Creek Unit 3 has increased from the 2011 Environmental Compliance Plan
24 estimate by approximately \$21 million, the anticipated fixed and variable operating

1 expenses have decreased largely because of the lower-than-expected cost of operating
 2 the baghouse, including the lower cost of sorbent injection for mercury and sulfuric
 3 acid. When the 2011 Environmental Compliance Plan was developed, LG&E based
 4 its projected baghouse operating costs on the Black & Veatch studies for high sulfur
 5 coal applications and its limited experience with operating a similar facility at
 6 Trimble County Unit 2. As its experience has developed, LG&E has further revised
 7 the projected costs, resulting in a reduction in operating expenses. As such, the
 8 decision to construct a new WFGD, even at a higher capital cost than contained in the
 9 2011 Environmental Compliance Plan, does not affect the prudence of LG&E's
 10 decision to retrofit, instead of retire, Mill Creek Unit 3.

11 In fact, the Net Present Value of Revenue Requirement (“NPVRR”) savings
 12 associated with retrofitting Mill Creek Unit 3 rather than retiring it, which were
 13 initially projected to be \$756 million, can be maximized even if LG&E rehabilitates
 14 the existing WFGD at Mill Creek Unit 4. But to maximize the NPVRR savings to
 15 customers as shown in the table below, LG&E must receive approval to modify the
 16 Mill Creek Unit 3 Certificate by January 18, 2013:

17 **Table 1: NPVRR Savings of WFGD Options for Mill Creek Unit 3**

	2011 ECR Plan	Updated Rehab	New FGD	New FGD with Delay
<i>Retrofit Savings (NPVRR, 2011 \$M)</i>	756	794	820	782

18
 19 Timely approval should allow LG&E to complete the new WFGD by April
 20 2016, which is the date it must be in compliance with the Mercury and Air Toxics
 21 Rule (“MATS Rule”) (with a one year extension being granted). Under this scenario,

1 the NPVRR savings to retrofit Mill Creek Unit 3 are \$820 million, which is a \$64
2 million increase (eight percent) over the projected savings in the 2011 Environmental
3 Compliance Plan. Under this scenario, Commission approval as requested should
4 ensure construction can be commenced and be completed in a timely manner. If
5 Commission approval to modify LG&E's Certificate is not obtained as requested,
6 constructing a new WFGD will not meet the compliance deadline and will no longer
7 maximize NPVRR savings; instead, based on this analysis rehabilitating the existing
8 WFGD at Unit 4 as planned would be more cost effective to customers, as the
9 NPVRR savings for rehabilitating the WFGD results in \$794 million in savings.

10 **Q. Why is it important for the Commission to approve expeditiously LG&E's**
11 **proposal?**

12 A. If LG&E constructs a new WFGD but is unable to complete construction prior to the
13 April 2016 compliance date or obtain a second year extension of the MATS Rule
14 compliance date, the savings steadily decline because LG&E will no longer be able to
15 operate Mill Creek Unit 3 and thus will have to purchase power from a third party to
16 replace its capacity.⁹ For example, if the new WFGD is not completed until October
17 2016, a six-month delay, the NPVRR savings decline to \$782 million, based on
18 estimated costs to purchase power from a third party. These analyses demonstrate
19 there is a short window of opportunity for LG&E to maximize NPVRR savings under
20 the new construction option.

21 **Q. For the sake of clarity, please state what would be the cost of delaying an**
22 **approval of LG&E's proposal and how LG&E will proceed if it does not receive**
23 **a timely approval.**

⁹ It is not clear that LG&E will be able to obtain a second year extension.

1 A. The cost to LG&E’s customers of not receiving an order by January 18, 2013,
 2 approving the requested Certificate modification would be \$26 million in NPVRR
 3 terms. Table 1 above shows that the value to customers of pursuing a new WFGD for
 4 Mill Creek Unit 3 rather than rehabilitating Mill Creek Unit 4’s WFGD disappears
 5 after that time due to the need to purchase replacement capacity (most likely in the
 6 form of a power-purchase agreement). Therefore, this analysis suggests LG&E
 7 should proceed within its current Certificate authority to rehabilitate the Mill Creek
 8 Unit 4 WFGD if the Commission does not approve the requested Certificate
 9 modification as requested.

10 **Q. Do the NPVRR savings of building a new Mill Creek Unit 3 WFGD remain**
 11 **under different fuel-price projections less favorable to retrofitting existing coal**
 12 **units?**

13 A. Yes, these savings hold true even under fuel-cost projections generally less favorable
 14 to coal units, such as those from the Cambridge Energy Research Associates
 15 (“CERA”) the Companies included in their analyses from the 2011 Environmental
 16 Compliance Plan cases, as shown in Table 2 below:

17 **Table 2: NPVRR Savings of WFGD Options for Mill Creek Unit 3**


	2011 ECR Plan	Updated Rehab	New FGD	New FGD with Delay
<i>Retrofit Savings (NPVRR, 2011 \$M)</i>	<i>338</i>	<i>376</i>	<i>402</i>	<i>370</i>

18
 19 Current base fuel-price projections remain within the ranges the Companies studied in
 20 their 2011 Environmental Compliance Plan cases, so these results remain valid and
 21 continue to support retrofitting Mill Creek Unit 3 generally, as well as specifically
 22 supporting building a new WFGD for the unit.

1 **Q. In addition to the savings associated with LG&E’s proposal, what would be the**
2 **environmental benefits of building a new WFGD for Mill Creek Unit 3 rather**
3 **than rehabilitating the existing Mill Creek Unit 4 WFGD to serve Mill Creek**
4 **Unit 3?**

5 A. Both WFGD solutions will significantly improve the control of Mill Creek Unit 3’s
6 SO₂ emissions, but one of the significant benefits of building a new WFGD for Mill
7 Creek Unit 3 is that it would remove at least 25% more of the likely SO₂ emissions
8 from a rehabilitated Mill Creek Unit 4 WFGD. The Babcock study indicated the
9 rehabilitated WFGD could remove up to 98% of the SO₂, increasing from the current
10 levels of up to 90% removal. A new WFGD would have a guaranteed removal rate of
11 98.5% with expected removal rates of 99% or higher, which would remove over three
12 hundred more tons of SO₂ emissions at Mill Creek Unit 3’s forecasted 60% capacity
13 factor than would a rehabilitated WFGD, as shown in Figure 1 below:

Figure 1: Mill Creek 3 SO₂ Emissions at Forecasted 60% Capacity Factor



1

2

3

4

5

6

7

The company's experience with the same WFGD technology recently installed and operating at the KU Ghent and E.W. Brown stations have shown performance can exceed the guaranteed value of 98.5%. Thus, a new WFGD would deliver greater environmental benefits while reducing customers' energy costs. To deliver this win-win solution LG&E requests the Commission to approve the Certificate modification on an expedited basis.

8

Q. Is there a contracting advantage to committing soon to put in place a new WFGD?

9

10

A. Yes. LG&E is currently contracting for the other WFGD work at Mill Creek, making

11

it important to act soon to increase the possibility of obtaining pricing similar to the

1 excellent pricing that has been obtained for the Unit 4 and combined Unit 1 and 2
2 WFGDs, as well as making it possible to lock in the pricing discussed herein.


3 **Q. Does this conclude your testimony?**

4 **A. Yes, it does.**

VERIFICATION


COMMONWEALTH OF KENTUCKY)
) SS:
COUNTY OF JEFFERSON)

The undersigned, **John N. Voyles, Jr.**, being duly sworn, deposes and says that he is Vice President, Transmission and Generation Services for Louisville Gas and Electric Company and an employee of LG&E and KU Services Company, and that he has personal knowledge of the matters set forth in the foregoing testimony, and that the answers contained therein are true and correct to the best of his information, knowledge and belief.



John N. Voyles, Jr.

Subscribed and sworn to before me, a Notary Public in and before said County and State, this 24th day of October 2012.



Notary Public (SEAL)

My Commission Expires:
SHERI L. GARDNER
Notary Public, State at Large, KY
My commission expires Dec. 24, 2013

APPENDIX A

John N. Voyles, Jr.

Vice President, Transmission and Generation Services
Louisville Gas and Electric Company and Kentucky Utilities Company
220 West Main Street
Louisville, Kentucky 40202
(502) 627-4762

Education

Rose-Hulman Institute of Technology, B.S. in Mechanical Engineering - 1976

Previous Positions

E.ON U.S. LLC

June 2008 - Present - Vice President, Transmission and Generation Services

2003 - 2008 - Vice President, Regulated Generation

LG&E Energy Corp.

February - May 2003 -- Director, Generation Services

Louisville Gas and Electric Company

1998 - 2003 -- General Manager, Cane Run, Ohio Falls and
Combustion Turbines

1996 - 1998 -- General Manager, Jefferson County Operations

1991 - 1995 -- Director, Environmental Excellence

1989 - 1991 -- Division Manager, Power Production, Mill Creek

1984 - 1989 -- Assistant Plant Manager, Mill Creek

1982 - 1984 -- Technical and Administrative Manager, Mill Creek

1976 - 1982 -- Mechanical Engineer

Professional Development

Emory Business School -- Management Development Program

Center for Creative Leadership (La Jolla, CA)

University of Louisville - The Effective Executive

Harvard Business School - Finance for the Non-Financial Manager

MIT - Leading Innovation & Growth: Managing the International Energy Co.

Board/Committee Memberships

Fund for the Arts - Board Member

Ohio Valley Electric Co. (OVEC) - Board member and Executive Committee member

Electric Energy, Inc. - Board member

Edison Electric Institute (EEI) - Committee member Energy Supply Executive Advisory
Committee and the Environment Executive Advisory Committee


Electric Power Research Institute (EPRI) - Chairman, Research Advisory Committee

Exhibit JNV-1

Babcock Power Environmental Inc.
Mill Creek Unit 4 Upgrade Study



**LG&E and KU Services Company
Mill Creek Station
WFGD Performance Upgrade Study**



**Feasibility Assessment
Mill Creek Unit 3 Gas Being Diverted to Unit 4
WFGD System Upgrades**

December 2, 2011



BabcockPower
ENVIRONMENTAL



BabcockPower
ENVIRONMENTAL

LG&E and KU Services Company

Mill Creek Station Unit 4 Upgrade Analysis
WFGD System Upgrade

December 2, 2011



December 2, 2011

Mr. Larry Van Gansbeke
LG&E and KU Services Company
Project Engineering
820 West Broadway
Louisville, KY 40202

RE: Mill Creek Station FGD System Upgrade Analysis
Mill Creek Station, 14660 Dixie Highway, Louisville, KY 40272

Dear Mr. Van Gansbeke:

Babcock Power Environmental Inc. (BPEI) has conducted an in-depth condition survey and evaluation of the existing Unit 4 Wet Flue Gas Desulfurization (WFGD) System at Louisville Gas and Electric and KU Services Company's (LG&E and KU's) Mill Creek Generating Station. The purpose of the evaluation was to perform an Upgrade Analysis of Unit 4 WFGD System to service boiler Unit 3 while maintaining high (+98%) SO₂ removal at both 12,500 ppm¹ and 50,000 ppm chlorides.

BPEI's current evaluation of the existing Unit 4 WFGD is built on the Feasibility Assessment completed on March 16, 2011. By working with LG&E Engineering and the Mill Creek plant, BPEI has conducted a comprehensive assessment of existing conditions and has defined the upgrades required to meet the Basis of Design specification and Project goals. The Basis of Design and goals are as follows:

- o Fuel: 6.3lb SO₂/mmBtu
- o Operating Chloride limit: 12,500 ppm & 50,000 ppm
- o SO₂ Removal Efficiency: +98.0%

BPEI and LG&E/KU have a long and very successful history of contracting and delivering multiple AQC Systems for your generating stations. We are confident this Upgrade Analysis will prove to further enhance our relationship as well as save LG&E/KU substantial capital compared to the cost of completely replacing the existing Mill Creek 4 Scrubber. Should you have any questions regarding our report please do not hesitate to contact me at (508) 854-3964, or via email: doleary@babcockpower.com

Very truly yours,

Daniel O'Leary
Project Manager

¹ Chloride content of 12,500 ppm and 15,000 ppm has been used interchangeably in this report. They represent the same upgrade solution.

Cc: Eileen Saunders, LG&E and KU – Project Engineering
Harry Culberson – BPEI
Mike Kelly - BPEI



LG&E and KU Services Company
Contract No. 843037

Mill Creek Unit 4 WFGD System Upgrade Analysis to Service Boiler Unit #3

Table of Contents

- A. Letter of Transmittal

- 1. EXECUTIVE SUMMARY
- 2. INSPECTION AND EVALUATION OF EXISTING WFGD SYSTEM
 - 2.1 Absorbers
 - 2.2 Inlet Duct
 - 2.3 Recycle Spray Header
 - 2.4 Recycle Spray Pumps
 - 2.5 Mist Eliminator
 - 2.6 Oxidation Air System
 - 2.7 Limestone Slurry Feed
 - 2.8 Absorber Bleed System
 - 2.9 Primary Dewatering and Chloride Purge
- 3. MATERIAL BALANCE – CHLORIDE PURGE EVALUATION
 - 3.1 Design Basis
 - 3.2 Original Design Basis with Filtrate Return
 - 3.2.1 Maintaining 8,000 ppm Chloride in Unit 3 WFGD System
 - 3.2.2 Maintaining 15,000 ppm or 50,000 ppm Chloride in Unit 3 WFGD system
 - 3.3 Revised Design Basis without Filtrate Return
 - 3.3.1 Maintaining 8,000 ppm Chloride in Unit 3 WFGD System
 - 3.3.2 Maintaining 15,000 ppm or 50,000 ppm Chloride in Unit 3 WFGD system
 - 3.4 Existing Dewatering System
- 4. PROCESS UPGRADES FOR EXISTING UNIT 4 WFGD SYSTEM
 - 4.1 Existing Absorber Modules
 - 4.2 Absorber Inlet and Awning above Absorber Inlet
 - 4.3 Recycle Spray Headers
 - 4.4 Spray Nozzles
 - 4.5 Wall Rings
 - 4.6 Recycle Pumps
 - 4.7 Agitators and Oxidation Air Lances
 - 4.8 Mist Eliminators and Mist Eliminator Wash
 - 4.9 Process Chemistry and Controls
 - 4.10 Absorber Vent and Overflow
 - 4.11 Bleed Pumps
 - 4.12 Hydrocyclones and Underflow Tank and Pumps
 - 4.13 Physical Flow Modeling
- 5. PROJECT PLAN



- 5.1 Basis of Design
- 5.2 Project Schedule
- 5.3 Outage Schedule
- 5.4 Work Scope and Construction Materials
 - 5.4.1 General Work 2012 to 2014
 - 5.4.2 Unit 4 - 4 week Outage 4/16/2012 to 5/7/2012
 - 5.4.3 Unit 4 - 1 week Outage 5/13/2013 and 1 week Outage 11/11/2013
 - 5.4.4 Unit 4 - 8 weeks Outage 9/29/2014 to 11/17/2014
- 6. Estimated Pricing

Attachments

General Arrangement Drawings

Material Balances

- Second Design Basis – no filtrate return
- First Design Basis – filtrate return via Clearwell Pond

Design Basis

Water Flow Schematic

Budget Engineering and Procurement Estimate

Work Scope

Schedule (high level)

1. EXECUTIVE SUMMARY

Babcock Power Environmental Inc. (BPEI) conducted an in-depth condition survey and evaluation of the existing Unit 4 Wet Flue Gas Desulfurization (WFGD) System at Louisville Gas and Electric and KU Services Company's (LG&E and KU's) Mill Creek Generating Station. The purpose of the evaluation was to perform an Upgrade Analysis of Unit 4 WFGD System to service boiler Unit 3, while maintaining high (+98%) SO₂ removal and high system reliability at both 12,500 ppm¹ and 50,000 ppm chlorides while burning a 6.3 lb SO₂/MMBtu coal.

Inspection

An inspection of Unit 4 WFGD absorbers was conducted by BPEI on September 27-28, 2011 during a short unit outage. The purpose of the inspection was to better understand the conditions and capability of the existing Unit 4 absorbers in order to develop a comprehensive scope of work to retrofit this unit to treat Unit 3 flue gas and reliably achieve high SO₂ removals.

The inspection revealed a number of issues that need to be corrected to achieve the high SO₂ removal efficiency specified while processing Unit 3 flue gas at design coal conditions. These findings include:

- Significant evidence of corrosion on the unit and support steel.
- Absorber flue gas inlet is shorter, and has a larger surface area, than typical new absorber designs.
- Quench water is run daily to prevent solids build up at the inlet. The use of quench water in this manner is not typical of a well configured system.
- In a high efficiency scrubber, the distance between spray levels and the distance between the tray and spray levels are ≥ 5 ft. In Unit 4 this spacing is only 3 ft.
- First spray header is only 3.25 ft above the top of the absorber inlet, as compared to a minimum of 6.5 ft in a new scrubber.
- Current spray nozzles provide little spray coverage along the absorber wall and between the absorber nozzles.
- Spray zone in Unit 4 is 11'7" as compared to high efficiency open spray towers which would typically have a spray zone of 20'.
- Use of reclaim water for ME washing often leads to scaling on the ME elements rather than washing off the solids. Scaling was evident on the chevron style Mist Eliminator (ME) in Unit 4. A clean water source should be used for this service
- Bleed pump performance is not optimal in terms of either pump wear and tear or power consumption without an orifice on the bleed return to the reaction tank.
- The hydrocyclone assembly is of an older design.

¹ Chloride content of 12,500 ppm and 15,000 ppm has been used interchangeably in this report. The materials required to maintain a 12,500 ppm chlorides level is also suitable to allow the system to operate at 15,000 ppm chlorides.

Design Basis

The design basis coal has a sulfur content of 6.3 lb SO₂/MMBtu. Material balances were created for Unit 4 allowing the scrubber slurry to cycle up to 8,000 ppm chlorides (current operation) and to levels of 15,000 ppm and 50,000 ppm chlorides assuming material upgrades in the absorbers.

Process Upgrades

A number of process upgrades are recommended for the existing Unit 4 WFGD system to be able to treat Unit 3 flue gas maintaining high (+98%) SO₂ removal and chloride concentrations of 15,000 ppm and 50,000 ppm:

- Replace existing WFGD Absorber modules with new high grade alloy materials and upgraded design.
- Replace and extend the absorber inlet and replace the absorber inlet awning
- Replace recycle spray headers and space 5' apart above the tray.
- Stagger spray nozzles layout and increase spray nozzle density
- Replace nozzles with dual-flow nozzles and add wall rings to spray levels 2 and 3.
- Replace recycle pumps with pumps suitable for high chloride service.
- Install five (5) new agitators and oxidation air lances on each reactor tank
- Install new DV210 Mist Eliminators.
- Provide a source of clean water for the ME wash system.
- Optimize process operating ranges and control logic.
- Redirect reaction tank vent into the absorber and add a seal pot to the overflow.
- Replace bleed pumps and primary dewatering hydrocyclones.
- Complete physical model to evaluate new ductwork layout and inlet duct design.

Project Plan

Babcock Power Environmental, Inc. has developed a preliminary Project Plan that capitalizes on its engineering, product fabrication, installation, and startup expertise to provide LG&E-KU Services Company with an efficient retrofit design that provides a low project cost and a short outage schedules.

The fully upgraded Unit 4 absorbers will be finished and available for service on November 17, 2014 at the completion of an 8-week outage on Unit 4. Flue gas from Unit 3 can be processed in the upgraded Unit 4 absorber once the blank off plate is removed during a one-week outage on Unit 3 scheduled in the Fall of 2014.

There are six outages, of various lengths, scheduled on Units 3 and 4 starting with a four (4) week outage on Unit 4 beginning April 16, 2012. Babcock Power needs to receive full notice to proceed by 1/1/2012 in order to place orders with vendors, perform detailed engineering and materials fabrication for this outage. BPEI plans to replace the absorber reaction tank tile lining as required, replace the reaction tank roof, replace the floor and install agitator mounting boxes and nozzles during this first outage. Scope of work assigned to the other outages was scheduled based on the lead time to engineer, procure and deliver vendor supplied equipment.

General work that can take place while the unit is operating has been scheduled throughout the period of 2012 to 2014. The general work includes replacement of the recycle pumps and oxidation air piping.

Part of the general work includes structural steel improvements and an interconnecting duct between Unit 3 and 4. These activities are critical for the upgrade of Unit 4, but are in LG&E-KU's scope of work. BPEI has included them in the project schedule to ensure the project can be completed in the available time.

Materials of construction were identified for two chloride levels: 12,500 ppm and 50,000 ppm. These two cases require the selection of different materials to address the condition in the absorber. The schedule for installing this equipment is not however affected by the required material.

Estimated Pricing

The estimated Engineering and Procurement cost of the retrofit improvements for the Mill Creek Unit 4 WFGD upgrade are shown below. This cost is based on current 2011 dollars without escalation. The accuracy is +25% to -10%. The pricing is for engineering and procurement only. No allowances have been made for BOP work, construction or maintenance upgrades to the WFGD structure. Additional details of this estimate are available in the attachments.

Budget Engineering and Procurement Estimate

<u>Description</u>	<u>Engineering Labor</u>	<u>Materials</u>	<u>Total</u>
Case 1: Alloy 27-7MO Unit 4 (12,500 ppm chlorides)	\$7,800,000	\$24,700,000	\$32,500,000
Case 2: Alloy C-276 Unit 4 (50,000 ppm chlorides)	\$7,800,000	\$27,400,000	\$35,200,000

Conclusion

Flue gas from Unit 3 can be processed in an upgraded Unit 4 while maintaining high (+98%) SO₂ removal and high reliability at both 12,500 ppm and 50,000 ppm chlorides. These removal efficiencies can be achieved with quality, well proven, reliable and cost effective technology that has been successfully applied at multiple installations throughout the United States.

The Unit 4 upgrade can be completed and the Unit 3 flue gas stream tied-in by November, 2014 through the effective use of six outages, of various lengths, scheduled for Units 3 and 4.

EPC cost to upgrade Unit 4 WFGD System is extremely cost competitive to the cost of new construction. To fully evaluate cost, the cost of existing infrastructure and BOP upgrades should be added to the estimated cost provided in this report.

2. INSPECTION AND EVALUATION OF EXISTING WFGD SYSTEM

A walk down and inspection of Unit 4 absorbers was completed in September on the 27th and 28th during a short unit outage. The reaction tanks were not drained during this outage and, therefore, were not available for inspection. The purpose of the inspection was to better understand the capability of the Unit 4 absorbers in order to develop a comprehensive scope of work to retrofit this unit to treat Unit 3 flue gas and achieve high SO₂ removals. A previous evaluation of the Mill Creek system was completed earlier this year and the results were summarized in a report issued to LG&E-KU in March of 2011.

2.1 Absorbers

Unit 4 Boiler System is currently configured with two 50% ID Fans. Flue gas from ID Fan A is directed to two absorber towers where recycle slurry is supplied from a common reaction tank. Flue gas from ID Fan B is directed to two additional absorber towers where recycle slurry is supplied from a common reaction tank servicing these two absorber towers. Both reaction tanks are Stebbins tile lined. These reaction tanks are relatively small for a forced oxidation WFGD system. The reaction tanks and absorber overflows vent to atmosphere. Figure 1 shows photos of the existing reaction tank vent and overflow line.

Figure 1. Absorber Reaction Tank Vent and Overflow



Each absorber tower has a single tray level and four recycle spray levels. Each reaction tank has four recycle pumps each providing slurry to two recycle spray levels, one on the 'A' and one on the 'B' towers, for a total of 8 recycle pumps feeding 16 recycle spray levels. Oxidation air is introduced thru a sparger type system. The sparger is arranged as a single header located above the floor introducing air evenly throughout the absorber.

Flue gas flows vertically through the four spray levels, interacting with the slurry sprayed from the recycle spray headers. Above the first spray header, LG&E has installed a perforated plate or



tray for the purpose of providing even flue gas distribution. Flue gas exits the absorbers through the mist eliminators to the stack. Figures 2 and 3 show the general arrangements of the existing Unit 4 absorbers.

Figure 2. General Arrangement – South Elevation





Figure 3. General Arrangement – East Elevation



All scrubber internals are some degree of stainless steel. Hastelloy or 317LMN wallpaper has been applied at various locations in the scrubber and outlet duct. Reheaters, originally installed in the outlet duct of the scrubber towers, have been removed. There was significant evidence of corrosion on the unit and support steel. Main contributors to the corrosion are believed to be flue gas leakage from the ductwork and pinhole leaks in the absorber shell. Figure 4 shows a few of the areas of corrosion.

Figure 4. Areas of Corrosion on Unit 4



2.2 Inlet Duct

The absorber flue gas inlet is shorter and has a larger surface area than is typical for new absorber designs. The length, shape, and angle of a typical absorber inlet are designed to minimize splash back of absorber slurry into the carbon steel ductwork. Flue gas velocity in the absorber is controlled with the size of the absorber inlet to evenly distribute flue gas prior to the first spray level, to eliminate any reverse flow in the duct, and to maintain the wet/dry interface in the absorber area. Otherwise, a large, shallow absorber inlet may result in corrosion of the ductwork upstream of the absorber. Flow modeling can determine if the installed tray offsets the

negative impact of the current absorber inlet design or if modifications are required to the absorber inlet and/or the size of the awning (rain hood) installed to prevent slurry from entering the absorber inlet duct.


There is an emergency quench water system installed at the absorber inlet that is operated daily to reduce the solids buildup at the absorber inlet. The use of quench water in this manner is not typical of a well configured system and is an indication of issues with the existing inlet design and spray header layout.

2.3 Recycle Spray Header

The spray levels and tray are closely spaced together (approximately 3 ft apart) compared to high efficiency scrubber designs (≥ 5 ft apart). When the tray was added to the absorbers between spray levels 1 and 2, the spray nozzles installed on spray level 2 were directed to spray up to prevent erosion issues on the tray.

Dual-spray nozzles are designed to produce a finer mist without sacrificing pressure drop. However, dual-spray nozzles on the first spray level would have to remain downward-only spray because of the tray installed directly above the spray header. Likewise, the dual-spray nozzles on the second spray level would have to remain upward-only spray. As a result, if there are no modifications completed to the existing spray header arrangement, dual-spray, bi-directional spray nozzles could only be installed on the third spray header. The total spray zone is also very small, only 11'7". High efficiency open spray towers of this size would normally have a spray zone that is closer to 20' in length, almost twice the height of the existing spray header arrangement. Figure 5 shows the existing spray zone on the Unit 4 absorber compared to a high-efficiency designed absorber.

Figure 5. Absorber Spray Zone Height




Internal inspection determined that only the second and third recycle spray level piping is 316L stainless steel where it was previously thought all 4 spray-levels were stainless steel. The piping in the first and fourth recycle spray levels is FRP and is showing signs of stress and fatigue. The location of the first spray level is much closer to the absorber inlet than recommended in new scrubber designs. The spray header is only 3.25' above the top of the absorber inlet. There might be additional issues of splash back into the carbon steel section of the ductwork upstream of the absorber inlet as a result. New scrubber designs utilize at least 6.5' between the top of the absorber inlet and the first spray header. Figure 6 shows photos of the existing spray headers.

Figure 6. Existing Absorber Spray Headers



The high-flow, hollow-cone spray nozzles currently installed in the Mill Creek absorber are designed to produce small droplets with a spray pressure of 10 psig at a spray angle of 120°. Figure 7 shows the spray coverage with this spray header and nozzle configuration and clearly shows there is very little spray coverage along the absorber wall and between the absorber nozzles. The four spray headers are identical in layout such that some channeling of the flue gas through the absorber likely occurs. Installing wall rings at spray levels 2 and 3 could help prevent flue gas sneakeage in the corners and along the walls of the absorber.

Figure 7. Typical Spray Coverage at Mill Creek



LG&E-KU requested that BPEI estimate the SO₂ removal efficiency from the currently configured absorber with upgrades similar to the Trimble County and also asked what fuel sulfur level would be needed to achieve 98% removal with these same modifications. The scrubbing efficiency of the currently configured absorber could be improved with the addition of wall rings and dual flow spray nozzles², similar to Trimble County. However, an upgrade limited to these modifications is not recommended as these upgrades will not address all of Mill Creek's concerns, namely: meeting high SO₂ removal efficiencies, eliminating corrosion issues, increasing reliability, and allowing operation at 12,500 or 50,000 ppm chlorides. A very short spray zone and the inability to install dual-orifice, bi-directional spray nozzles on all lower spray headers are the prime factors that limit SO₂ removal from the current Unit 4. The performance capability of the currently configured Unit 4 absorber with the addition of wall rings and dual-flow spray nozzles is limited as follows:

- An SO₂ removal efficiency of 95% and as high as potentially 96% can be maintained at the design coal conditions
- An SO₂ removal efficiency of 98% if the sulfur content of the coal is reduced by 50%, or to approximately 3.2 lb SO₂/MMBtu

² As mentioned previously, only spray level 3 would have up/down dual flow nozzles installed. The other three spray levels would have single direction dual flow nozzles installed in the absorber as currently configured.

2.4 Recycle Spray Pumps

Unit 4 recycle pumps were replaced in the mid 1990s and appear to be adequately sized to provide a high L/G ratio of 162 gal/macf when treating Unit 3 flue gas. However, SO₂ removal will be limited because of the poor spray coverage and the limited spray zone height.

2.5 Mist Eliminator

The lower mist eliminator (ME) wash water header piping is FRP while the middle wash water header piping is alloy. The mist eliminator section contains baffles that are used to direct the air flow. It is not clear why the baffles are necessary or the exact geometry of the ME section.

The chevron style MEs showed scaling/buildup in some areas as well as some plugged wash nozzles. The plant reported that the Clearwell Pond is the source of wash water for the ME wash system and that this pond receives filtrate return from dewatering. Reclaim water is not recommended for ME wash. The high calcium, magnesium, and sulfate concentrations and any fines in the water result in hard water scaling in piping, wash nozzle pluggage, and erosion of wash valves. These components can also introduce a source of alkalinity at the ME section in the absorber. This alkalinity will remove a fraction of the remaining SO₂ exiting in the flue gas resulting in precipitation of solids in the ME section. Reclaim water often ends up causing scaling on the ME elements instead of washing solids off the ME elements. Figure 8 are photos showing scaling evident during the inspection.

Figure 8. Photos of Existing Unit 4 Mist Eliminator Elements



2.6 Oxidation Air System

There are no agitators installed on the reaction tanks. Mixing and absorber chemistry is maintained with oxidation air. Oxidation air is injected by a sparge system in a ring installed several feet off the absorber reaction tank floor. A fraction of the oxidation air is also used to maintain agitation in the area sump. There is a quench system on the oxidation header at each reaction tank. There are two quench nozzles installed at each location spraying approximately 100 gpm of quench water. Adequate quench can be maintained with less than 10 gpm at each location. The air sparger ring is also a source of high unreliability in the absorber system causing


forced unit outages whenever the oxidation air system is out of service longer than 30 minutes due to sparger ring pluggage.

Oxidation is supplied by 2 of 3 air compressors. The control logic is such that there is a lead blower that is base loaded and the second blower in service follows to maintain oxidation air supply pressure set point. The standby compressor will automatically start if one of the compressors in service trips.

2.7 Limestone Slurry Feed

Limestone slurry feed is based on maintaining absorber slurry pH between 4.7 and 5.8. The pH set point is adjusted by the control room operator based on unit load and SO₂ removal. Gypsum purity is maintained above 90% in the absorber and is measured by the on site lab. Figure 9 is a photo of the limestone slurry control valve on top of the reaction tank.

Figure 9. Limestone Slurry Control Valve and Bypass



2.8 Absorber Bleed System

Absorber density is maintained between 10-12% solids. A pair of bleed pumps (1 operating + 1 spare) on each reaction tank maintains absorber density. Bleed from each pair of pumps is directed to a dedicated hydrocyclone assembly. There are no orifices installed on the bleed return to the reaction to balance the pressure losses between bleeding to the hydrocyclone assembly and bleeding back to the reaction tank. The existing bleed pumps are not variable speed. Without orifices, the pumps must operate on different parts of the pump curve when bleeding to dewatering at high solids versus returning bleed to the reaction tank at low solids. This is not optimal for pump performance in terms of either pump wear and tear or power consumption. There is no flush on the bleed piping, slurry gravity drains back to reaction tank.

2.9 Primary Dewatering and Chloride Purge

At the high absorber slurry density set point, bleed is directed to primary dewatering hydrocyclones. Underflow from the hydrocyclones gravity drains to an underflow storage tank and is pumped to gypsum slurry storage at a common dewatering area. Overflow from the hydrocyclones is gravity fed back to the absorber. A fraction of the overflow can be directed to an area sump and purged from the absorber system to maintain chloride concentration and remove fines from the process to maintain gypsum quality and dewatering operation.

The hydrocyclone assembly is an older design with several cyclones (28 total cyclones for Unit 4 as compared to 10, plus 2 spare, cyclones proposed for the new Unit 4 WFGD system). There is no supply pressure indication to monitor hydrocyclone performance online. Monitoring hydrocyclone supply pressure can help determine if there are pluggage issues that need to be addressed. The lab monitors overflow and underflow solids concentration to ensure the hydrocyclone assembly does not have any buildup, pluggage, or wear issues. Photos of the existing hydrocyclone assemblies at Mill Creek and Brown are in Figure 10.

Figure 10. Photos of Hydrocyclone Assemblies at Mill Creek and Brown





3. MATERIAL BALANCE – CHLORIDE PURGE EVALUATION

3.1 Design Basis

The original design basis submitted for the new absorbers systems on Units 1/2 and 4 was used to re-model the material balance for Unit 3 operation through Unit 4 absorbers. This design utilizes coal with a sulfur content of 6.0 lb SO₂/MMBtu and a reclaim stream from the Clearwell Pond that contains filtrate from dewatering. Table 1 is a summary of the coal used to develop the flue gas properties for this evaluation. The previous evaluation, in the March 2011 report, was completed using slightly higher coal sulfur content, 6.3 vs. 6.0 lb SO₂/MMBtu.

Table 1. Design Coal Conditions

Coal Analysis	Design
Carbon	61.20%
Hydrogen	4.28%
Sulfur	3.36%
Nitrogen	1.27%
Chlorine	0.16%
Oxygen	6.89%
Ash	12.00%
Moisture	11.00%
Higher Heating Value	11,200 Btu/lb
Filtrate Return	Yes

A new design basis was submitted (4-Nov-11) for the new absorber systems on Units 1/2 and 4. This new design basis utilizes a coal with the higher sulfur content of 6.3 lbSO₂/MMBtu and a higher chlorine content of 0.35%. Also LG&E-KU reported that no filtrate will be returned through the Clearwell Pond. Table 2 is a summary of the revised coal. Material balances were completed for all cases as it is unclear which case is the appropriate design basis for Mill Creek current and future operation. The conflicting design conditions impact calculated purge rates, but do not impact the proposed absorber upgrades identified in this report.


Table 2. Revised Design Coal Conditions

Coal Analysis	Design
Carbon	60.00%
Hydrogen	4.00%
Sulfur	3.45%
Nitrogen	1.30%
Chlorine	0.35%
Oxygen	5.90%
Ash	14.00%
Moisture	11.00%
Higher Heating Value	10,900 Btu/lb
Filtrate Return	No

3.2 Original Design Basis with Filtrate Return

Chloride concentration is maintained by purging a fraction of the hydrocyclone overflow from the WFGD process. This purge rate was evaluated, for the original design basis (Table 1), assuming that the Unit 3³ WFGD system was designed for 8,000 ppm, 15,000 ppm and 50,000 ppm chlorides. These evaluations assumed that the filtrate containing chloride is returned to the WFGD systems via Clearwell Pond. Figure 11 is a schematic of the water streams leaving and returning to Unit 3 WFGD system. Section 3.3 describes a scenario when this filtrate is not returned to the system.

Figure 11. Schematic of Water Flow – Filtrate Returns to WFGD System



3.2.1 Maintaining 8,000 ppm Chloride in Unit 3 WFGD System

The system currently consists of materials of construction that allow the scrubber slurry to cycle up to 8,000 ppm chloride concentration. Chloride concentration is maintained by purging a fraction of the hydrocyclone overflow from the WFGD process. Based on the design coal and

³ Please note: reference to Unit 3 in this section refers to the flue gas from Unit 3 treated in the existing (or upgraded) Unit 4.

full load conditions, the average purge rate required to maintain a chloride concentration of 8,000 ppm when directing Unit 3 flue gas to the existing Unit 4 WFGD system is 136 gpm.

New WFGD systems are being proposed for Units 1/2 and 4. Units 1 and 2 flue gas streams will be combined to one absorber island and Unit 4 will have a dedicated absorber island. The materials of construction proposed for these new WFGD systems are designed to operate at chloride concentrations up to 50,000 ppm. The slurry from all the absorber systems is directed to a common dewatering system. It was reported by the plant that filtrate from dewatering eventually ends up in the Clearwell Pond and reclaimed as makeup to all the absorber systems. This reclaim will contain higher chlorides once the new WFGD systems start up. As a result, higher purge rates will be required to maintain Unit 3 operation at 8,000 ppm. Multiple material balances were completed to determine the purge rate required to maintain the existing materials of construction on the old Unit 4 absorbers when treating Unit 3 flue gas. These results are summarized in Table 3.

Table 3. Preliminary Purge Rates for Existing Materials of Construction

Water Balance		Preliminary Purge Rates, gpm			
U1/U2 & U4	U3	U1/U2	U4	U3	Total
8,000 ppm	8,000 ppm	211	168	136	515
15,000 ppm	8,000 ppm	99	79	227	405
50,000 ppm	8,000 ppm	12	10	680*	702
Direct Unit 3 Purge to Units 1/2 & 4					
15,000 ppm	8,000 ppm	166	133	**	299
50,000 ppm	8,000 ppm	73	58	**	131

* Require additional 14 gpm additional fresh water makeup

** Purge redirected to Units 1, 2, and 4

The new WFGD design calls for two specific design conditions, 15,000 ppm⁴ Cl and 50,000 ppm Cl. If Units 1/2 and Unit 4 WFGD systems operate at 15,000 ppm chloride, the purge rate for Unit 3 increases from 136 gpm to 227 gpm. If Mill Creek decides to operate the new WFGD systems at the design chloride concentration of 50,000 ppm to minimize purge from those WFGD processes, the purge from Unit 3 increases substantially, up to 680 gpm. To maintain this high of a purge rate, 100% of the overflow from the primary dewatering hydrocyclones will be directed to purge. Plus, reclaim makeup would have to be restricted by a small volume and additional (14 gpm) low-chloride service water makeup would be required to maintain 8,000 ppm chloride in the Unit 3 absorbers. At 50,000 ppm chlorides, the overall purge rate increases from the current design of 515 gpm at 8,000 ppm to 702 gpm because of the high purge rates required for Unit 3 operation.

Additional cases were completed to consider directing purge from Unit 3 to Units 1/2 and Unit 4 WFGD systems to decrease the overall purge from the WFGD system by cycling up the

⁴ The material balances were prepared at chloride levels of 15,000 ppm and 50,000 ppm which are equivalent to the design values for the new Units 1/2 and 4. The material required to maintain 12,500 ppm chlorides is also suitable to allow the system to operate at 15,000 ppm.

chlorides leaving with the purge from Unit 3 in Unit 1/2 and 4 absorbers. Under this scenario, the chloride purge is directed toward Unit 1/2 and 4 rather than going to the Ash Pond. If 15,000 ppm is maintained on Units 1/2 and Unit 4, the overall purge rate can be reduced from 405 gpm to 299 gpm by directing Unit 3 purge to the other two absorber systems. If 50,000 ppm is maintained on Units 1/2 and 4, the overall purge rate can be reduced from 702 gpm to 131 gpm by directing Unit 3 purge to the other two absorber systems.

3.2.2 Maintaining 15,000 ppm or 50,000 ppm Chloride in Unit 3 WFGD system

Additional material balances were completed to determine Unit 3 purge rates if the materials of construction were upgraded to higher grades of alloy. These cases are summarized in Table 4. If the materials of construction are upgraded to handle 15,000 ppm Cl⁵, Unit 3 purge rate can be reduced from 136 gpm to 64 gpm. However, if the new WFGD systems operation at a chloride concentration of 50,000 ppm, the purge from Unit 3 increases up to 335 gpm. If 50,000 ppm is maintained on Units 1/2 and 4, the overall purge rate can be reduced from 357 gpm to 76 gpm by directing Unit 3 purge to the other two absorber systems. If the materials of construction on Unit 3 are upgraded to handle 50,000 ppm Cl, Unit 3 purge rate can be reduced to 8 gpm.

Table 4. Preliminary Purge Rates for Upgrade Materials of Construction

Water Balance		Preliminary Purge Rates, gpm			
U1-U2 & U4	U3	U1&2	U4	U3	Total
8,000 ppm	8,000 ppm	211	168	136	515
15,000 ppm	15,000 ppm	99	79	64	242
50,000 ppm	15,000 ppm	12	10	335	357
50,000 ppm	50,000 ppm	12	10	8	30
Direct Unit 3 Purge to Units 1, 2, & 4					
50,000 ppm	15,000 ppm	42	34	**	76


** Purge redirected to Units 1, 2, and 4

3.3 Revised Design Basis without Filtrate Return

The purge rates were evaluated with the revised design basis (Table 2) assuming that Unit 3 WFGD system had a chloride concentration of 8,000 ppm, 15,000 ppm, and 50,000 ppm. These evaluations assume that the filtrate containing chloride is not returned to the WFGD system as shown in the schematic in Figure 12. When filtrate containing chloride is not returned to the WFGD systems, the purge rates from the absorber systems decrease under constant fuel conditions. However it should be noted, the overall purge from the plant also includes filtrate if it is not reclaimed through the absorbers.

⁵ Identical materials required to maintain 12,500 ppm Cl

Figure 12. Schematic of Water Flow – Filtrate Does Not Return to WFGD System



3.3.1 Maintaining 8,000 ppm Chloride in Unit 3 WFGD System

Based on the revised design coal with a higher chlorine content and full load conditions, the average purge rate required to maintain a chloride concentration of 8,000 ppm is 185 gpm when directing Unit 3 flue gas to the existing Unit 4 WFGD system.

Since no filtrate is returned from the common dewatering system, Unit 3 water balance is not impacted by water balances maintained on Units 1/2 and 4. The overall absorber purge rate decreases when higher chlorides are maintained in the new WFGD absorber systems. These results are summarized in Table 5. This table provides the total water purged from the system which is a combination of the chloride purge entering the Ash Pond and common filtrate entering "E" Pond.

Table 5. Preliminary Purge Rates for Existing Materials of Construction

Water Balance		Preliminary Purge Rates, gpm				Filtrate Loss, gpm	Total Water Purge, gpm
U1-U2 & U4	U3	U1&2	U4	U3	Total		
8,000 ppm	8,000 ppm	293	229	185	707	1,074	1,781
15,000 ppm	8,000 ppm	40	30	185	255	1,104	1,359
50,000 ppm	8,000 ppm	0	0	185	185	1,109	1,294
Direct Unit 3 Purge to Units 1, 2, & 4							
15,000 ppm	8,000 ppm	95	74	**	169	1,104	1,273
50,000 ppm	8,000 ppm	0	0	**		1,109	1,109

** Purge redirected to Units 1, 2, and 4

While no purge is required for chlorides at the 50,000 ppm operating condition for Units 1/2 and 4, some purge may be required to remove fines from the process to maintain dewatering operation.

Additional cases were completed to consider directing purge from Unit 3 to Units 1-2 and Unit 4 WFGD systems to decrease the overall purge from the WFGD system. If 15,000 ppm is maintained on Units 1/2 and Unit 4, the overall purge rate can be reduced from 255 gpm to 169 gpm by directing Unit 3 purge to the other two absorber systems. If 50,000 ppm is maintained on Units 1-2 and 4, the overall purge rate can be reduced from 185 gpm to 0 gpm by directing Unit 3 purge to the other two absorber systems. Again, there may be purge requirements to remove fines for dewatering operation.

3.3.2 Maintaining 15,000 ppm or 50,000 ppm Chloride in Unit 3 WFGD system

Additional material balances were completed to determine Unit 3 purge rates if the materials of construction were upgraded to higher grades of alloy. These cases are summarized in Table 6. If the materials of construction are upgraded to handle 15,000 ppm Cl, Unit 3 purge rate can be reduced from 185 gpm to 25 gpm. If 50,000 ppm is maintained on Units 1-2 and 4, the overall purge rate can be reduced from 25 gpm to 0 gpm by directing Unit 3 purge to the other two absorber systems. If the materials of construction on Unit 3 are upgraded to handle 50,000 ppm Cl, Unit 3 purge rate can be reduced to 0 gpm.

Table 6. Preliminary Purge Rates for Upgrade Materials of Construction

Water Balance		Preliminary Purge Rates, gpm				Filtrate Loss, gpm	Total Water Purge, gpm
U1-U2 & U4	U3	U1&2	U4	U3	Total		
8,000 ppm	8,000 ppm	293	229	185	707	1,074	1,781
15,000 ppm	15,000 ppm	40	30	25	95	1,115	1,210
50,000 ppm	15,000 ppm	0	0	25	25	1,119	1,144
50,000 ppm	50,000 ppm	0	0	0	0	1,122	1,122
Direct Unit 3 Purge to Units 1, 2, & 4							
50,000 ppm	15,000 ppm	0	0	**	0	1,119	1,119

** Purge redirected to Units 1, 2, and 4

3.4 Existing Dewatering System

BPEI recommends an evaluation of the balance of plant regarding operation at higher chloride concentrations. Specifically the dewatering and reclaim water system materials of construction, valves, and instrumentation should be reviewed

4. PROCESS UPGRADES FOR EXISTING UNIT 4 WFGD SYSTEM

The following upgrades are recommended for the existing Unit 4 WFGD system to be able to treat Unit 3 flue gas maintaining high (+98%) SO₂ removal and higher chloride concentrations.

- Replace existing WFGD Absorber modules with new upgraded design
- Replace absorber inlet
- Replace awning over absorber inlet
- Replace recycle spray headers and space 5' apart above the tray
- Stagger spray header layout
- Increase spray density by increasing the number of nozzles per spray level from 36 to 52
- Change spray level 1,2 & 3 nozzles to dual-flow, up-down nozzles
- Change spray level 4 nozzles to dual-flow, double-down nozzles
- Add wall rings to spray levels 2 and 3
- Replace recycle pumps with equipment suitable for high chloride service
- Install five (5) new agitators and five (5) new oxidation air lances on each reactor tank (total of 10 lances) and add external distribution ring above normal liquid level to supply air to the individual lances.
- Install new DV210 Mist Eliminators
- Provide a source of clean water for the ME wash system
- Optimize process operating ranges and control logic
- Redirect reaction tank vent to the absorber
- Add a seal pot to the reaction tank overflow
- Replace bleed pumps
- Replace primary dewatering hydrocyclones
- Complete physical model to evaluate new ductwork layout and inlet duct design

BPEI's recommended equipment vendors and justification for these vendor selections are included in the sections below.

4.1 Existing Absorber Modules

Replace existing 317LMN alloy absorber modules with higher grade alloy materials to handle higher chloride concentrations. For the same reason, all valves and instrumentation will have to be replaced on slurry and reclaim water lines to handle the higher chloride concentrations.

4.2 Absorber Inlet and Awning above Absorber Inlet

Since the inlet ductwork is going to be modified to accept flue gas from Unit 3 and the absorber modules replaced to handle higher chlorides, it is recommended to replace the absorber inlet. The new absorber inlet will be longer with a surface area designed to maintain flue gas velocity between 50 and 60 ft/sec. The awning design above absorber inlet will be evaluated and re-designed to minimize the potential for carryover into the inlet ductwork. Figure 13 are typical absorber inlet duct and awning drawings.

4.3 Recycle Spray Headers

The stainless steel headers will require new materials of construction to handle the higher chlorides, also the existing FRP headers show excessive signs of stress and deterioration and need to be replaced. BPEI proposes new FRP spray headers redesigned to produce a denser spray pattern and a staggered layout pattern. Spray nozzle location and spacing on the spray headers is an important design consideration, which must take into account relative locations of adjacent nozzles on alternate levels to take full advantage of the interaction between nozzle spray cones. Staggering nozzle layout between spray headers minimizes the potential of gas channeling or ‘laning’ through paths of low liquid flow. Increasing the spray density also has the potential additional benefits of increasing the removal of particulate and acid gas (SO₃) in the absorber. Increasing spray density will have some impact on pressure drop across the absorber.

The current arrangement of the tray and spray headers is less than optimal for maximum SO₂ removal. The spray headers are spaced closely together and the tray is installed between spray levels 1 and 2. The present nozzle arrangement is identical on all spray levels which results in flue gas channeling (“laning”) through the absorber, reducing SO₂ removal potential.

Historically, trays were installed in open spray towers with a spray header installed below the tray to quench the flue gas and minimize scaling on the tray. This issue primarily affected natural oxidation systems. Research has since been completed which demonstrates that a quench spray header is not necessary for limestone, forced-oxidation systems. BPEI proposes leaving the installed tray at its existing elevation and spacing the spray headers in the newly designed absorber module so that they are all located above the tray.

The spray headers will be relocated 5 ft apart to match current design practices for high efficiency absorbers. To create the extra space required in the spray zone section, BPEI is utilizing the abandoned re-heater section and relocating the mist eliminator section in this unused area. This concept for spray header spacing allows the use of bi-directional nozzles on all but the top-level spray header. Further, this combination of spray header spacing and nozzle selection provides uniform distribution of slurry to the entire spray zone and enhanced droplet collision and retention which increases SO₂ removal efficiency by promoting more intimate contact between SO₂ molecules and slurry droplets. Figure 14 shows the staggered pattern for the spray headers to provide better spray coverage and Figure 15 shows the spray pattern with the modified spray header layout.

Figure 14: Modified Spray Header Layout with 5' Spacing





Figure 15. Modified Nozzle Arrangement



4.4 Spray Nozzles

BPEI proposes installing dual-orifice nozzles on all four spray levels. Spray level 4 will use dual-orifice ‘double-down’ style nozzles while spray levels 1, 2, and 3 will use dual-orifice ‘up-down’ style nozzles. Installing dual-orifice nozzles on all four spray levels maximizes surface area available for liquid to gas contact. Dual-orifice spray nozzles increase the number of droplets and the number of droplet collisions (when measured against single-orifice nozzles) by increasing the amount of spray area from the same total nozzle flow. Increasing the number of droplet

collisions results in smaller droplets and a significant improvement in SO₂ removal efficiency due to increased intimate contact between flue gas and slurry droplet.

Up-down nozzles have the additional benefit of increasing the residence time of droplets in the absorber by doubling the slurry spray height. Spray level 4 utilizes double-downward nozzles to minimize carryover into the mist eliminator section. Figure 16 is an example of a bi-directional spray nozzle being tested.


Figure 16. Bi-directional Spray Nozzle Testing



4.5 Wall Rings


There is a physical limit to the degree of spray coverage along the wall of the absorbers especially in the corners of square reactor modules. Increased flue gas flow is expected along the wall because of the decreased resistance from this reduced coverage. BPEI will add wall rings to deflect flue gas from the absorber wall into the interior of the absorber where there is a greater chance of interaction with recycle spray droplets. This also promotes more thorough mixing of the flue gas, ensuring no areas of high SO₂ concentration along the walls are allowed to bypass the effective spray zones. Figure 17 shows a typical wall ring installation in a circular, tile-lined vessel.

Figure 17: Typical Wall Ring Arrangement (Ghent Plant)



Wall rings will be added at spray levels 2 and 3 to maximize the benefit of contacting flue gas with the slurry spray while minimizing the impact on pressure drop across the absorber. Preliminarily, the pressure drop increase is expected to be minimal. Figure 18 is a graphic representation of the wall rings proposed for Mill Creek absorbers.

Figure 18: Proposed Wall Ring, Typical Arrangement



4.6 Recycle Pumps

Two options were considered for the recycle pumps. The first is to replace the current equipment with pumps appropriate for operation up to 50,000 ppm chlorides. This alternative will require new foundations for the pumps plus new electrical and (spray header) piping. A

second option is to rebuild the pumps. This second option would allow the foundations, electrical and riser pipes to be reused. However, the allowable chloride level of the rebuilt pumps will be 5,000 ppm as discussed below.

4.6.1 New Recycle Pumps

As discussed earlier, the L/G ratio on Unit 4 absorber treating Unit 3 flue gas is more than adequate for high removal efficiency, once modifications are completed to increase the spray zone and spray coverage. Increasing the spray header elevation raises the recycle system resistance increasing in the total dynamic head (TDH) required. The new recycle pumps will be similar to the existing direct drive recycle pumps except they will be designed to handle higher chloride concentrations and increased TDH requirements. Figure 19 contains photos of recycle pumps designed for high chloride operation on smaller units.

Figure 19. Recycle Pumps



The recycle pumps are important to this project because they are utilized to pump a mixture of ground limestone slurry and gypsum crystals from the reservoir of the flue gas absorbers to a series of manifolds, from which the slurry is sprayed in the top of the absorber so as to combine with flue gas for the purpose of reducing the sulfur content of the gas. The flow rate and head of the slurry, plus resistance to abrasion and corrosion by the slurry, are the primary performance characteristics of interest in the recycle pumps.


The critical performance parameters for the Mill Creek pumps are head and flow, with consideration for required Net Positive Suction Head (NPSH). Babcock Power is planning to supply Dughting recycle pumps for the LG&E-KU Mill Creek Project.

The Dughting pump has an iron shell with a cast-in-place liner and impeller made of a composite of silicon carbide grains with an epoxy binder. The Dughting cast composite liner has been reported to provide excellent service at KU Brown Station, Alcoa Warrick Station and in a number of European installations. BPEI has had 26 Dughting pumps in service for the past 3 years with very good performance. The Dughting ceramic/epoxy has the highest protection against erosion but would tend to be less resistant to corrosion and erosion should pH level drop or chloride level increase beyond the warrantee limits.

Dughting Pumpen has been building and selling gypsum slurry service pumps since 1992. They have well over a thousand pumps in service throughout Europe and Asia. There are about 135 gypsum slurry service pumps of the same size (or larger) than those required for the Mill Creek project in service around the world. The pump-wetted parts are a cast silicon carbide material in an epoxy matrix binder. Wear characteristics are claimed to be several times that of abrasion resistant metals. The Dughting pumps would be serviced in this country by Dughting Pumps North America out of Middleton, MA.

The existing recycle piping is 36" in diameter. The slurry velocity of 8.7 ft/sec is within the limits of 5 to 10 ft/sec recommended by BPEI. When the recycle piping splits between the two absorbers the slurry velocity increases to 9.8 ft/sec. The slurry piping can be replaced in kind. Effort will be made to minimize the number of bends. Figure 20 is a photo of the existing Unit 4 spray header.

Figure 20. Spray Header



4.6.2 Rebuilt Recycle Pumps

LG&E-KU requested that BPEI evaluate the existing recycle pump for use with an upgraded absorber. Unfortunately, based on discussions with the recycle pump supplier, the pump materials of construction are designed to handle 5,000 ppm chlorides and would therefore be unworkable for high chloride operation. A summary of the pump materials, as received from the supplier, is outlined on Table 7. There is no data available to indicate that these materials of construction have been changed since the original pump installation. From a capacity standpoint, BPEI's preliminary review indicated that new gear boxes and a pump rpm increase of less than 10% would provide the necessary flow rate at the higher TDH required with the upgraded absorber.



Table 7. T2 Commercial Specification

I. SCOPE:									
ASTM A532-IIIA Abrasion resistant cast iron for use where corrosion as well as abrasion resistance is important. Use at Svedala-Thomas includes but is not limited to Pumps, Impellers, and Side Liners, A thermal treatment is used to obtain optimum wear resistant properties.									
II. CHEMICAL COMPOSITION:									
		C	Mn	Si	Cr	Mo	Ni	S	P
ASTM A532-IIIA	Min:	2.0	0	0	23	0	0	0	0
	Max:	3.3	2.0	1.5	30	3.0	2.5	0.06	0.10
III. PROPERTIES:									
<p>A. Metallurgical: A chemistry is chosen within the above limits that is mid-range in carbon and Chromium with enough hardenability (i.e. Mn, Ni, and Mo) to produce a microstructure of approximately 30% M7C3 carbides held in place by a matrix of Martensite and Retained Austenite.</p>									
<p>B. Mechanical:</p> <ol style="list-style-type: none"> 1. Hardness: >650 BHN (i.e. > 58.6Rc or 712 VPH) 2. Tensile strength 90⁶: - 110 KSI (i.e. 600-750 MPa) 3. Fracture Toughness⁶: 23 - 30 KSI-IN^{1/2} (i.e. 25 - 33 MN/m^{2/3}) 									

4.7 Agitators and Oxidation Air Lances

Poor mixing of injected oxidation air and absorber slurry can reduce the performance of the absorber. The oxidation air sparger ring currently installed requires higher oxygen to SO₂ (O:SO₂) ratios to provide enough excess air to complete the reaction of SO₂ removed by the absorber to gypsum. BPEI recommends adding agitator and air lance assemblies which will reduce the O:SO₂ requirements, increase agitation in the absorber allowing the absorber to be maintained at design solids concentration, improve reactivity by decreasing excess limestone in the absorber, and most importantly, improve reliability of the WFGD system. Oxidation air lances will be between 8” and 10” in diameter, which will eliminate issues with pluggage even if the oxidation air blower is out of service for several hours. Figure 21 show a photo of agitators and oxidation air lances on a Stebbins tile-line reaction tank. Figure 22 is a graphical representation of the agitator air-lance assembly. Agitators will be appropriately spaced from the recycle pumps to avoid entraining air in the recycle pump suction and causing cavitation. The


⁶ The most useful properties of abrasion resistant cast iron are its hardness and carbide content. Carbide content is established by Carbon and Chromium values. Hardness is usually the only property that is determined in practice. The determination of tensile strength and toughness is very difficult, and has little bearing on the intended use of the castings other than obvious ones (i.e. absence of fracture). These facts are generally recognized in standards of abrasion resistant cast iron. Tensile strength and Toughness are not part of this specification and are given for information only.

number and size of agitators and air lances required is a function of the reaction tank diameter, absorber slurry level in the reaction tank, and volume of oxidation air required to maintain full oxidation.

Figure 21: Oxidation Air Lances and Agitator Impellers in Tile-Line Tank



Figure 22. Agitator Air Lance Assembly



The oxidation air piping is designed that if the oxidation air blowers do trip out of service, slurry will not back up into the air sparger system because the oxidation air distribution ring is physically located above the reaction tank slurry level. Figure 23 is a photo of the oxidation air distribution ring at Brown Station.

Figure 23: Oxidation Air Distribution Ring and Agitators



Oxidation air rate required for the high sulfur, high SO₂ removal is 14,000 scfm with a supply pressure of 7.2 psig. The existing air compressors are capable of maintaining adequate airflow. The piping system will include an adjustment valve on each air lance to evenly distribute airflow. Quench requirements are much reduced compared to the quench rates currently maintained (10 gpm vs. 100 gpm). A quench system will be installed at each ring header with 1 operating and 2 spare quench nozzles.

Physical modeling is recommended to verify mixing and ensure the oxidation air can be dispersed in the reaction tanks to complete oxidation. The upgraded Unit 4 may require a higher O₂:SO₂ ratio than is typical for WFGDs because of the small reaction tanks, but preliminarily, the blower appears to have the capacity to accommodate higher air flows if necessary.

Agitator design is as much an art as it is a science. While agitators appear as relatively simple science, their operational parameters are complex and difficult to theoretically model. Further, agitators are one of the most critical components in the oxidizing WFGD absorber. If the agitators' operation is even marginal, serious operational problems will develop in areas including: gypsum quality, absorber efficiency, scaling and slurry settling. In the case of the Mill Creek WFGD program with reliability requirements being extremely important, design conservatism is requisite. Ekato is the clear leader in successful agitator experience for WFGD service that disperses oxidation air (mass transfer) to the slurry.

The WFGD oxidizing absorber agitator characteristics: mixing, erosion and corrosion resistance, mass transfer capability, resistance to flooding, torque and horsepower are the primary performance characteristics of interest. These key technical parameters were evaluated for Mill

Creek Unit 4. On all of these key performance parameters, Ekato emerges as the clear leader because:

- **Mixing:** Torque is key to adequate mixing. Ekato has the highest torque values as compared to the other vendors and is capable of provide the highest comparable level of mixing.
- **Erosion Resistance:** Erosion resistance is a function of impeller blade tip speed and impeller design. Ekato has low blade tip speeds as well as their proprietary “Wingjet” blade tip designed to minimize erosion.
- **Mass Transfer Capability:** A larger impeller is greatly preferred over high RPM for mass transfer. Ekato has the largest impellers as compared to the other manufacturers.
- **Resistance to Flooding:** Larger and lower RPM impellers have the best flooding resistance. Ekato has the largest impellers with comparative low RPM operation.
- **Torque and Horsepower:** These factors are related to mass transfer and mixing, the larger these figures are the better. Ekato has the highest operational torque and horsepower values.

In addition to the primary performance parameters, Ekato offers the following features that are a factor in critical operational parameters and experience issues:

- Ekato has more experience in oxidizing scrubber absorber agitator technology than any other manufacturer.
- Ekato has the most experience with mechanical seals in FGD operation.
- Ekato has a robust agitator shaft assembly
- The Ekato Impeller is a one piece monolithic cast design
- Ekato mounts their agitator about 2-2.5 impeller diameters off of the floor of the absorber, reducing risk of being locked in slurry during start-up.
- Ekato’s proprietary “WingJet” impeller is designed to provide more efficient mixing and mass transfer (oxidation air dispersion) with less erosion.

4.8 Mist Eliminators and Mist Eliminator Wash

Munter’s DV210 Mist Eliminators are an alternative to traditional flat mist eliminator arrangements and is the only known ME that will provide the de-misting and particulate removal performance BPEI demands. Figure 24 is a photo of a DV210 installation. The installation of a single layer benefits installation time and requires only one layer of support beams instead of two. Figure 25 is a graphic of the ME design typical in open spray tower systems.

Figure 24: DV210 Mist Eliminators








Figure 25. Mist Eliminator Layout



The purpose of the Mist Eliminators (ME) in a WFGD system is to remove the slurry mist entrained in the flue gas. If not removed, the mist can lead to the buildup of solids and liquid in the downstream ductwork and stack; corrosion of downstream equipment, ducts, and stack liner; and stack “rain” (emission of liquid, solids or slurry) to the area surrounding the plant. The physical and chemical environments in which the MEs operate require that the ME system (including the wash system) be carefully designed to ensure the reliability of the FGD system.

The critical performance parameters for the design and selection of the mist eliminators are: the ability to successfully remove mist from the flue gas stream (to the required droplet size), the spray wash system effectiveness, pressure drop across the ME, liquid drainage capability and re-entrainment, corrosion resistance, design (flat versus peaked) and expected life.

Munters has significant empirical data for the DV210 including third party engineering and testing analysis. Fisia, Licensor of BPEI WFGD Technology, has amassed significant data on the combined scrubber and DV210 performance for the collection of fly ash particulate.

The Munters DV210 peaked design adds an additional margin of performance not possible with traditional flat “pancake” type mist eliminator designs. Their angled design and multi-pass configuration traps wash water on their surface longer as it migrates to the lower inverted peak of the first pass stage. This makes the wash water more effective on a volumetric quantity basis and allows a longer coalescing path for the mist. The slower migration of the water down the profile of the blades is more effective at limiting re-entrainment of the water into the gas stream than other mist eliminator types. Further, these blades remain wetted longer (between wash cycles); provide an effective capture surface using the adhesive properties of water to more effectively capture particulate matter as compared to other designs. This, coupled with historical operational data, is the primary reason for specifying the Munters DV210.

The support structure for the Munters DV210 Mist Eliminator is a single level support. The “diamond” design of the DV210 extends with the lower ME section below the support structure and the upper section placed on top of the support structure. This is in contrast to the standard flat ME design where each stage requires a dedicated level of support. The DV210 (2-stage) can provide full ME capabilities in a 6’ vertical section of the absorber whereas the flat 2-stage design requires 9’ and is less efficient at coalescing the mist. The DV210 design provides savings over the flat ME design in two ways: first, a lesser quantity of exotic metal is used to support the ME and secondly, the vessel height can be reduced by the amount of ME depth difference between the two design types. This is an approximate 3’ savings in absorber structure as well as foundation and structural steel costs.

Maintenance requirements for the Munters DV210 mist eliminator are minimal and consist of periodic inspections as long as it is operated within the specified design constraints and is spray washed in accordance with the manufacturer’s recommendations. The Munters DV210, when operated in accordance with the manufacturer’s guidelines, should provide an operational life of about 15 years. This expected life is in contrast to typical flat designs with life expectancies anywhere from 5 to 15 years.

As explained earlier in section 2.5, BPEI highly recommends evaluating the source of water used for ME wash. There are several papers to support the conclusion that utilizing water that has even a fraction process liquor or filtrate causes scaling issues in the ME wash piping and on ME elements. Scaling of ME elements increases pressure drop and the potential of carryover into the outlet ductwork. ME elements can also scale to the degree that they fall through supports in the reaction tank causing pluggage in recycle slurry piping and spray nozzles. Clean, filtered water should be used. BPEI recommends an automatic, self-cleaning filter to handle the relatively high solids normally associated with Ohio River water.

The ME wash logic should be reviewed to ensure adequate ME wash is maintained while minimizing fresh water makeup to the WFGD system. The control logic will adjust wash frequency based on minimum requirements from the manufacturer and unit load. Clearwell Pond water can still be used to control absorber level by directly adding water to the absorber reaction tanks. It is also recommended to use clean service water for oxidation air quenching and for the emergency quench system.

4.9 Process Chemistry and Controls

The control logic will be revised as necessary to maintain appropriate ME wash frequency, maintain absorber level, maintain absorber density, and maintain SO₂ removal. ME wash frequency will be reviewed to maintain appropriate wash cycles but minimize excessive service water usage. Absorber level and density will be optimized to maximize liquid and solids residence times to maximize limestone utilization and gypsum quality. The logic for SO₂ removal will include feed forward logic with feedback trims to optimize SO₂ removal control and limestone slurry feed.

4.10 Absorber Vent and Overflow

The absorber reaction tanks will be modified to accommodate side-mounted agitators coupled with oxidation air lances. The reaction tank top will be replaced to eliminate any flue gas discharge from the reaction tank. The vent from the reaction tank will be re-routed to the absorber instead of venting to atmosphere. It is recommended to vent the reaction tank to the absorber to make sure there is no liquid carryover into the outlet duct. The absorber overflow will be redesigned so that the overflow is directed to a seal pot to prevent flue gas venting out of this line.

4.11 Bleed Pumps

BPEI recommends improving the reliability of the absorber bleed system so that absorber slurry density can be maintained within higher controlled limits to maintain 15-18% slurry density in the absorber reaction tank. Improving the reliability of the bleed system to operate at higher solids concentration will improve limestone utilization as a result of increasing the solids residence time in the reaction tank. Besides replacing the bleed pumps and control valves to handle the higher chlorides, BPEI recommends installing orifice(s) on the bleed return line to the reaction tank. The purpose of the orifice(s) is to keep the pump running on the same part of the pump curve by evening the pressure drop between bleeding to the hydrocyclones and bleeding

back to the reaction tank. When the bleed pump is designed to run on the same part of the pump curve, power consumption and pump performance is optimized. Figure 26 is a photo of bleed pumps installed at Brown Station.

Figure 26. Bleed Pumps at Brown Station



The Duchting pump was evaluated over other pumps and determined to be the technologically superior choice. Some of the more significant issues supporting the selection of the Duchting pump include:

- Lowest operating noise levels
- Exceptional chemical and corrosion resistance
- Erosion resistant SiCast construction
- Low operating speeds
- Best power efficiency
- Motor direct coupled to pump
- Same pump supplier as recycle pumps

The Duchting pump is a SiCast (Silicon Carbide cast in an epoxy matrix) construct that is well proven in other components for absorber slurry service. Both the pump casing and impeller are constructed of this SiCast material. This material is similar to the material used in absorber spray nozzles which experience little to no detectable wear. The proprietary SiCast product used by Duchting differs from the standard nozzle type silicon carbide type materials in that the ratio of silicon carbide to epoxy for the Duchting SiCast is considerably greater at an 80% to 20% average ratio. Typical spray nozzles have only a 50% to 60% silicon carbide concentration. This higher SiCast content product is more resistant to erosion than products with a lesser silicon

carbide percentage. Even though the velocities in the Duchting pump are the lowest, it probably matters little in that the SiCast material is far more resistant to abrasion and erosion than either of the other manufacturers' materials. From this, it is reasonable to conclude that the life of the Duchting pumps in these applications may significantly exceed the life of other types of pumps.

Strainers should be added in the suction line to the bleed pumps to screen any solid scale that may be present in the absorber reaction tank. The strainers will increase the life of the bleed pump impellers and reduce the potential for pluggage in the hydrocyclone assembly.

4.12 Hydrocyclones and Underflow Tank and Pumps

BPEI recommends replacing the hydrocyclone assembly with an assembly that has bigger vortexes and apexes. This will reduce the amount of pluggage without a negative impact on performance or increased bleed pump TDH. The assembly will have the proper instrumentation to monitor performance remotely from the DCS and be designed to handle the higher chloride concentrations. Figure 27 is a photo of hydrocyclone assemblies for a smaller WFGD system (< 500 MW).

Figure 27. Hydrocyclone Assemblies



The hydrocyclone absorber overflow will still be directed to an overflow tank where a purge stream can be maintained to control chloride concentration. The remaining fraction will be directed back to the reaction tank. At the reaction tank the return line will include a section of

pipng that drops below the normal slurry level to prevent any off-gassing through the overflow return when they hydrocyclone assembly is not in service.

A state of the art design hydrocyclone similar to the Krebs unit installed at the KU Brown WFGD system is recommended for this absorber upgrade.

No issues were brought up regarding the underflow tank and pumps. However, they probably require replacement to accommodate the higher chloride design.


4.13 Physical Flow Modeling

BPEI recommends physical modeling of planned modifications. Changes to ductwork (Unit 3 into Unit 4 Scrubber) can result in unforeseen gas dynamics that could be detrimental to the process if the appropriate internal flow control devices are not installed. BPEI makes extensive use of modeling technology for retrofit modifications such as those proposed for Mill Creek Generating Station. Some of the applications of this modeling are as follows:

- Prediction of gas distribution at the absorber inlet and into the first spray level
- Prediction of gas distribution and slurry spray distribution within the absorber spray zone
- Prediction of absorber sump recirculation for agitator performance as it relates to both suspension of solids and distribution of oxidation air for maximum effectiveness

Typical physical models are scaled for geometry and operate at full gas velocity, with the mist eliminators modeled in full scale. For this type of model, BPEI is able to analyze gas flow behavior at the gas inlet, entering, within the absorber, leaving the spray zone, and entering and leaving the mist eliminators. The results of these model tests are incorporated into the actual absorber design (ductwork layout, spray header layout, nozzle spacing, etc.) to ensure controlled gas behavior, uniform gas flow, high liquid-gas contact for maximum efficiency with installed components, and uniform gas flow to the mist eliminators for consistent mist elimination from the flue gas. Figure 28 shows examples of physical models constructed to test flue gas distribution, absorber inlet design, and mist eliminator performance.

Figure 28. Examples Physical Models Tested on other BPEI Projects



5. PROJECT PLAN

Babcock Power Environmental, Inc. has developed a preliminary Project Plan that capitalizes on its engineering, product fabrication, installation, and startup expertise to provide LG&E-KU Services Company with an efficient retrofit design that provides a low project price and a short outage schedule.

The fully upgraded Unit 4 absorbers will be finished and available for service on November 17, 2014 at the completion of an 8-week outage on Unit 4. Flue gas from Unit 3 can be processed in the upgraded Unit 4 absorber once the blank off plate is removed during a one-week outage on Unit 3 scheduled in the Fall of 2014.

5.1 Basis of Design

The Basis of Design for this Project Plan is to remove of 98% SO₂ at either 12,500 ppm or 50,000 ppm chlorides. It is this design basis that dictates the materials of selection for Babcock Power to offer LG&E-KU Services. Babcock Power's Project Plan has been set up to match the materials of construction, the vendor lead times, and the LG&E-KU outage schedule.

5.2 Project Schedule

The major milestones for the proposed schedule are shown on Table 8 including engineering, procurement, fabrication & delivery, construction and unit outages. A more detailed description of the activities can be found in the high level schedule in the attachments. Commissioning of the upgraded Unit 4 WFGD system should be completed by 13-Feb-15, but additional general work is scheduled to complete by mid-June. The ongoing general work does not require a unit outage.

Table 8. Project Schedule – Major Milestones

Activity Name	Duration (days)	Start	Finish
Engineering	175	2-Jan-12	31-Aug-12
Procurement	214	20-Jan-12	14-Nov-12
Fabrication & Delivery	640	23-Jan-12	04-Jul-14
Unit 4 2012 Outage (4 week)	16	16-Apr-12	07-May-12
Unit 4 2013 Outage (1 week - May)	6	13-May-13	20-May-13
Unit 4 2013 Outage (1 week - Nov)	5	11-Nov-13	15-Nov-13
Unit 3 2013 Outage (6 week - approximate)	5	01-Nov-13	07-Nov-13
Unit 4 2014 Outage (8 week)	30	29-Sep-14	07-Nov-14
Unit 3 2014 Outage (1 week - approximate)	11	03-Nov-14	17-Nov-14
Construction (general work between outages)	901	2-Jan-12	15-Jun-15
Start Up & Commissioning	75	03-Nov-14	13-Feb-15
Mill Creek Unit 4 WFGD Upgrade	901	2-Jan-12	15-Jun-15

Babcock Power has developed its project plan to match KU's outage schedule. Table 9 shows how the proposed work scope has been matched to the outage schedules. The first outage date occurs in April 2012 and will require that Babcock Power be released by 1/1/2012 in order to place orders with vendors and do engineering and fabrication.

Table 9. Work Scope vs. Outage Schedule

Outage Schedule	Work Scope
General Work – 2012 to 2014 (ongoing)	Engineer, supply and install recycle pumps Engineer, supply and install oxidation air piping
Unit 4 – 4 weeks 4/16/2012 to 5/7/2012	Evaluate absorber reaction tank walls Install agitator wall boxes Install prefabricated roof panels Install raised floor Install oxidation pipes and supports in the sump
Unit 4 – 1 week outage 5/13/2013 and 1 week outage 11/11/2013	Install all valves and instruments Install bleed pumps Install hydrocyclone Install FRP piping for Bleed/hydrocyclone Install agitators
Unit 3 – 6 weeks 2013 outage date fall (no info available)	Install Unit 3 outlet duct blank-off plate
Unit 4 – 8 weeks 9/29/2014 to 11/17/2014	Replace absorber vessel and internals: <ul style="list-style-type: none"> ○ Spray headers ○ Spray nozzles ○ Wall rings ○ Mist Eliminator Install recycle pipes Install outlet ducts Install inlet duct Install inlet & outlet expansion joints Install analyzers Sox Install knife gate valves suction and discharge Install emergency quench system
Unit 3 – 1 week 2014 outage date fall (no info available)	Remove Unit 3 blank off plate in the ductwork

5.4 Work Scope and Construction Materials

This section provides further details about the Work Scope outlined above and the materials of construction required for both a 12,500 ppm and 50,000 ppm chlorides case.

5.4.1 General Work 2012 to 2015

General Work is the work that can be done while the Unit 4 is operating. The general work involves replacing accessible equipment that has spares and also work to prepare components for an upcoming outage. The components of the planned general work are described below. There are approximately four months of general work that is scheduled after the upgraded Unit 4 is commissioned.

5.4.1.1 Recycle Pumps

Babcock Power is planning to remove one recycle pump from service and replace new, one recycle pump at a time with the unit in operation. With the recycle pump out of service, the pump will be disassembled and its foundation removed. BPEI will have a new foundation and wiring system designed and ready to be installed. The first pump will come off line on March 1, 2013 to be retrofitted. The reason the first pump does not start until 2013 is because the pump, foundation and wiring systems will need to be designed and the vendor released to fabricate as shown on Table 10.

Table 10. Lead Time for General Work Material

LEAD TIMES are from date BPEI issues Purchase Order to its Suppliers	Basis: Q1 CY2011		
	Material Lead Time	Fabrication Lead Time	Total Lead Time
Commodity Description			
Recycle Pump (SiCast Lined)	Included	42 Wks	42 Wks

The SiCast-lined recycle pump has a current lead-time, from the date of order placement to shipment, of 42 weeks. This lead-time is based on BPEI's experience with quoting and requisitioning this equipment. BPEI will be ready to begin changing the recycle pumps out March 1, 2013 after engineering has been completed and the pumps can be delivered. BPEI plans to remove and replace one pump per month starting in March of 2013 and ending in November 2013. This schedule leaves one (1) month of float to replace eight recycle pumps

As BPEI replaces the recycle pump foundations we will also set up and pour a new foundation for the bleed pumps. The bleed pumps will be discussed later in section 5.4.3.

5.4.1.2 Oxidation Air Piping

The oxidation air piping will also be installed during general work. BPEI is planning to reuse the existing Mill Creek oxidation air blowers. BPEI will modify the existing oxidation air piping external to the sump to accommodate a ring header for distribution of oxidation air to all lances. The oxidation air piping will be 20" carbon steel piping for the ring header and 8" drops from the header down to the oxidation air lances external to the sump. BPEI estimates it will use 120 hangers attached to the existing tank. This work is scheduled to take place from June 2012 to June of 2013. This work does not need to be completed until the November 2013 outage.

5.4.1.3 Structural Steel

BPEI has not included structural steel in this Mill Creek Unit 4 study. However, we have included the scheduling of the steel repair and or replacement. This work will take place from May 2012 to December 2014. This work is considered general work, which will take place between outages. The anticipated scope of structural steel work will include cover plating, replacement, sand blasting and painting of structural, handrail and grating.

5.4.1.4 Duct Between Unit 3 and Unit 4

This study does not include the ductwork between Unit 3 and Unit 4 that will transfer the flue gas. However, the study does set up a time frame for the owner to install this ductwork. It is anticipated that the ductwork will be installed from May 2013 to August 2013. This time frame will allow the owner or BPEI to engineer, fabricate and ship to the site modules for installation. By installing the support steel and ductwork in May to August of 2013, this will support BPEI in its planning for the eight week 2014 major outage.

5.4.1.5 Piping

The removal and replacement of random sections of piping and tubing is also part of general work and will support new valves and instruments that will be replaced in the two one-week outages in 2013. This random replacement of pipe and tubing will take place while the scrubber is on line and is scheduled from May 2013 to August 2013. Wherever possible, BPEI will replace valves and instruments while the unit is on line.

5.4.1.6 Grating

The final general work activity identified by BPEI is the replacement of the grating around the reactors through which the recycle piping passes. This grating cannot be replaced until the new recycle-piping configuration is developed. The schedule for this work is from April 2014 to August 2014.

5.4.2 Unit 4 – 4 weeks 4/16/2012 to 5/7/2012

Given that this 4 week outage is so close to the Notice to Proceed date of 1/1/2012, BPEI will be unable to engineer, procure and deliver vendor equipment. BPEI is planning to use this four-week outage to work the absorber reaction tanks. A purchase order will be issued to Stebbins to evaluate the tile lining, replace the floor and install agitator mounting boxes and nozzles. The mounting boxes and nozzles will be constructed of C-276 material for either the 12,500 or 50,000-ppm chloride option. The C-276 will be purchased from Corrosion Metals due to the short lead-time.

While Stebbins is repairing the wall tiles and possibly installing a new raised floor, BPEI will be designing and procuring precast concrete ceiling tiles for the new absorber reaction tank roof. The current reaction tank roof has many leaks, which allow the slurry gas to escape and corrode the steel supports.

During this outage, BPEI is planning to install new oxidation air lances and air lance supports. BPEI will install one air lance per agitator (5 per sump for a total of 10). These air lances will be

constructed of C-276 material 8” in diameter. The air lance supports will also be constructed of C-276 high alloy material.

BPEI will purchase the C-276 alloy steel plate direct from the manufacturer and/or distributor and free issue the plate material to a fabricator to make agitator mounting boxes and air lances. The purchase order will include plate thicknesses, lengths and widths as specified by BPEI’s engineering calculations and drawings.

BPEI plans to use C-276 for the Mill Creek Unit 4 absorber reaction tank internals in either the 12,500 or 50,000-ppm cases. C-276, a nickel-molybdenum-chromium-tungsten alloy, was selected due to its excellent general corrosion resistance and ease of fabrication. This alloy is appropriate for use in environments where resistance to hot contaminated mineral acids, organic and inorganic chloride-contaminated media, chlorine, formic and acetic acids, acetic, acetic anhydride, sea water and brine solutions is desired. The elemental comparison of C-276 is given on Table 11.

Table 11. C-276 Elemental Composition DATA

Element	Min	Max
Molybdenum	15.0	17.0
Chromium	14.5	16.5
Iron	4.00	7.00
Tungsten	3.00	4.50
Cobalt	--	2.50
Carbon	--	0.01
Silicon	--	0.08
Manganese	--	1.00
Vanadium	--	0.35
Phosphorus	--	0.04
Sulfur	--	0.03
Nickel	Remainder	

C-276 has resisted the formation of grain boundary precipitates in the weld heat-affected zone, making it a candidate for most chemical and petrochemical processing applications in the as-welded condition. The alloy has resisted both general and localized corrosion, including pitting, crevice corrosion, and stress corrosion cracking. C-276 is readily fabricated by welding, using methods similar to those utilized for nickel-based alloys.

5.4.3 Unit 4 – 1 week outage 5/13/2013 and 1 week outage 11/11/2013

There are two one-week outages on Unit 4 during 2013: one in May and the other in November. During the May 2013 outage BPEI is planning the following work:

- Remove and Replace Valves and Instruments
- Install a new Bleed Pump
- Install new Agitators in the Absorber Reaction Tank

During the November outage BPEI is planning to do the following work:

- Remove and Replace Instruments not replaced during May
- Remove and Replace the Hydrocyclone
- Remove and Replace FRP piping for the Bleed Pump and the Hydrocyclone

The work listed above is planned for 2013 due to engineering, procurement and fabrication lead times. The commodity lead-time chart, on Table 12, clarifies why this work must be planned for 2013.

Table 12. Lead Times for 2013 One-Week Outages

LEAD TIMES are from date BPI issues Purchase Order to its Suppliers	Basis: Q1 CY2011		
	Material Lead Time	Fabrication Lead Time	Total Lead Time
Commodity Description			
Absorber Agitators	Included	38 Wks	38 Wks
Piping (FRP)	Included	16-23 Wks	16-23 Wks
Bleed Pumps	Included	30 Wks	30 Wks
Misc. Valves & Instruments	8-10 Wks	10 Wks	18-20 Wks

5.4.3.1 *Instruments and Valves*

The replacement of valves and instruments will be planned during the 2012 engineering phase. At this time, each valve and instrument will be identified based on the current P&IDs and BPEI's new design. Once the valves and instruments have been identified both BPEI and LG&E-KU will jointly review and select the vendors. BPEI will place a purchase order in 2012 so that work can begin during the general work phase between the outages. BPEI would like to replace as many valves and instruments as possible with the unit in operation. Any valves and instruments that can't be replaced with the unit in operation will be replaced in the May 2013 one-week outage. Any valves and instrument replacement not completed during the May 2013 outage will be completed during the November 2013 outage.



5.4.3.2 Bleed Pumps

BPEI is planning to replace the bleed pumps that pump directly to the hydrocyclones. It is BPEI's plan to have four pumps, two per reaction tank. One pump will be operating the second will be a spare. Orifice plate(s) will be installed on the bleed return line to the reactor tank to improve pump performance. The bleed pumps will be sent from the vendor to a skid fabricator for assembly then shipment to the Mill Creek site for installation on the foundation installed before the outage. BPEI has chosen Duchting pumps because they meet both the 12,500 and 50,000-ppm chlorides cases.

5.4.3.3 Agitators

BPEI plans to install (5) side mounted absorber agitators per sump for a total of (10). The new sump penetrations will be installed during the first outage in 2013 as discussed in section 5.4.2. The plan is to install the agitators during the May 2012 one-week outage. BPEI is planning to design and purchase Ekato agitators for the 12,500-ppm chloride option. The agitator blades for the 50,000 ppm chloride case will be a high alloy material with a coating.

5.4.3.4 Hydrocyclones

The last task in this outage is the removal and replacement of the hydrocyclone system with a new state of the art design similar to the Krebs unit installed at the KU Brown WFGD system.

5.4.3.5 FRP Piping

The plan calls for installation of new FRP piping for the Hydrocyclone and Bleed systems during the November 2013 outage. Further information about FRP is included in section 5.4.4.2 below.

5.4.4 Unit 4 – 8 weeks 9/29/2014 to 11/17/2014 Outage

Up to this point in the discussion of outage work, BPEI has been using the same equipment for either 12,500 ppm or 50,000 ppm of chloride due to the selection of Duchting pumps, which are good for either 12,500 or 50,000 ppm chlorides. BPEI is planning to rework the following items the 8-week outage between September 29, 2014 and November 7, 2014:

- Replace absorber vessel and internals:
 - Spray headers
 - Spray nozzles
 - Wall rings
 - Mist Eliminator
- External Recycle Pipes
- Outlet Ducts (by owner)
- Inlet Duct
- Inlet & Outlet Expansion Joints
- Analyzers SO_x
- Knife Gate Valves Suction and Discharge
- Emergency Quench System

The lead times for the materials required for this outage are shown on Table 13.



Table 13. Lead Times for 2014 8-week Outage

LEAD TIMES are from date BPI issues Purchase Order to its Suppliers	Basis: Q1 CY2011		
	Material Lead Time	Fabrication Lead Time	Total Lead Time
Commodity Description			
Large Recycle Isolation Valves - Knife Gate	Included	46 Wks	46 Wks
Alloy Absorber/Ductwork (Alloy)	8-10 Wks	24 Wks	32-34 Wks
External Recycle Piping (FRP)	Included	16-23 Wks	16-23 Wks
Recycle Internal Spray Headers - FRP	Included	26 Wks	26 Wks
Recycle Internal Spray Header Supports-Alloy	8-10 Wks	10 Wks	18-20 Wks
Mist Eliminator	Included	26 Wks	26 Wks
Spray Nozzles	Included	26-30 Wks	26-30 Wks
Mist Eliminator Support Steel-Alloy	8-10 Wks	14 Wks	18-20 Wks

5.4.4.1 Absorber Vessel

The plan is to replace the absorber vessels and internals during the 8-week outage. In order for BPEI to guarantee 98% SO₂ removal with either 12,500 ppm or 50,000-ppm chloride, the absorber vessel needs a material upgrade. In the 12,500-ppm chloride level Babcock Power recommends using Incoloy alloy 27-7MO. The chemical composition of this material is given in Table 14.

Table 14. Alloy 27-7MO Elemental Composition DATA

Element	Min	Max
Molybdenum	6.5	8.0
Chromium	20.5	23.0
Iron	Balance	
Copper	0.5	1.5
Nitrogen	0.3	0.4
Carbon	--	0.020
Silicon	--	0.50
Manganese	--	3.00
Phosphorus	--	0.03
Sulfur	--	0.01
Nickel	26.0	28.0

Babcock Power recommends INCOLOY nickel-chromium-molybdenum alloy 7MO (UNSS31277) due to its high strength, ease of fabrication, and outstanding corrosion resistance at an economic price.

The second material choice for the absorber is C-276, which is good for 50,000-ppm chlorides. The composition of C-276 was shown previously on Table 11.

The INCONEL alloy C-276 (UNS N10276/W.Nr 2.4819) is known for its corrosion resistance in a wide range of aggressive media. The high molybdenum content imparts resistance to localized corrosion such as pitting. The low carbon minimizes carbide precipitation during welding to maintain resistance to intergranular attack in heat-affected zones of welded joints. It is used in chemical processing, pollution control, pulp and paper production; industrial and municipal waste treatment and the recovery of “sour” natural gas. Applications in air pollution control include stack liners, ducts, dampers, scrubbers, stack-gas re-heaters, fans and fan housings.

The BPEI plan, with either the Alloy 7MO or C-276 option is to fabricate the four absorbers and ship them to the site in two pieces each. Once at the site, the contractor will set up the two-absorber pieces on the ground and install the new spray headers, nozzles and DV210 mist eliminator. The tray and wall rings will come installed in the modules being sent from the shop. The tray and wall rings will be fabricated out of the same material as the absorber modules.

5.4.4.2 Absorber Vessel Internals

The FGD spray headers and recycle pipe for Unit 4 at the Mill Creek Plant will be constructed of fiberglass reinforced plastic (FRP). This material is being selected based on its compatibility with the application.

FRP is widely used in the chemical and utility industries primarily due to its excellent chemical and erosion resistance. In an Ashland application paper, it was reported that FRP made with epoxy vinyl ester resin has equal-to, or better than, corrosion resistance than alloy C-276 with another paper showing it suitable for use on 70% sulfuric acid up to 108 deg F or saturated chlorine in water up to 210 deg F. As for erosion resistance, one FRP vendor reports the erosion resistance of the FRP liner is actually better than Alloy 2205.

There are no appreciable differences between the FRP offered by the major vendors. All use epoxy vinyl ester resin with either a C-glass (glass fiber) or Nexus (synthetic) veil. There are minor differences between the additives used for the erosion liners with some vendors having proprietary additives and the others using Silicon Carbide (SiC).

Slurry nozzles must be designed to provide not only the desired slurry flow rate, spray angle, and droplet size but they must also survive the abrasive and corrosive environment within the absorber. The nozzles are subjected to erosive slurry on both their internal and external surfaces and may be exposed to high chloride concentrations. Several materials have been used to make slurry nozzles, but by far the material of choice is silicon carbide (SiC). With a Mohs hardness of 9-10, SiC has excellent thermal and abrasion resistance properties and is offered by all the major slurry nozzle vendors.

The Emergency Quench Water System is used to protect the Absorber spray nozzle piping, mist eliminators and mist eliminator wash piping when the Absorber inlet or outlet flue gas

temperature is high, or when the number and placement of operating recycle spray levels is not adequate. The quench water system is located in the Absorber inlet and water is supplied via the plant fire protection system. The environment in this location consists of unscrubbed flue gas at 300-350 degrees Fahrenheit.

During a temperature excursion, where the flue gas exceeds 400 degrees Fahrenheit, the Absorber outlet temp may exceed 350 degrees F. When this occurs, the quench water system is activated to protect the equipment referenced above. The fire protection system supplies water to the quench system and quickly cools and flushes the piping. During normal operating conditions the piping is empty and flue gas can migrate through the spray nozzles, up the individual pipes. This operating condition necessitates the use of corrosion resistant materials in the construction of the quench water system. Alloy C-276 has been selected as the appropriate material for the internal ductwork piping.

The recycle pump isolation valves are used to isolate flow to the pump from entering through the suction pipe. The suction valves are located between the absorber sump and the recycle pump. There is not currently a scheduled outage long enough to remove the knife gate valves and send them to the manufacturer for refurbishment, so it is BPEI's recommendation to install new valves into the system. The plan is to make use Tyco in-line gate valves.

6. ESTIMATED PRICING

The rough order of magnitude (ROM) price of the retrofit improvements for the Mill Creek Unit 4 WFGD upgrade is summarized on Table 15. This is based on current 2011 dollars without escalation and has an accuracy of +25% to -10%.


Table 15. Budget Engineering and Procurement Estimate



<u>Description</u>	<u>Engineering Labor</u>	<u>Materials</u>	<u>Total</u>
Case 1: Alloy 27-7MO Unit 4 (12,500 ppm chlorides)	\$7,800,000	\$24,700,000	\$32,500,000
Case 2: Alloy C-276 Unit 4 (50,000 ppm chlorides)	\$7,800,000	\$27,400,000	\$35,200,000


The scope of pricing is limited to the Engineering and Procurement of the retrofit improvements. There are no allowances for BOP work, construction or maintenance upgrades to the WFGD structure. Additional details of this estimate are available in the attachments.

ATTACHMENTS

GENERAL ARRANGEMENT DRAWINGS









MATERIAL BALANCES

DOCUMENT NUMBER:



BabcockPower
ENVIRONMENTAL

**MATERIAL BALANCE
WET FLUE GAS DESULFURIZATION**

PROJECT NUMBER	100585
CUSTOMER NAME	Louisville Gas & Electric (LG&E)
PROJECT NAME	Mill Creek Unit 3
LOCATION - CITY, STATE	Louisville, KY
DESCRIPTION	CASE: Design, 8,000 ppm Cl, no filtrate return
	LOAD: 100% MCR
	FUEL: High Sulfur Bituminous Coal
	SO ₂ Removal Efficiency: 98.5%
	REAGENT: Limestone
	WATER: Clearwell Pond Water

PREPARED	NAME	_____
	DATE	_____
CHECKED	NAME	_____
	DATE	_____
APPROVED	NAME	_____
	DATE	_____

REVISION HISTORY		PREPARED BY	APPROVED BY
1	_____	_____	_____
2	_____	_____	_____
3	_____	_____	_____
4	_____	_____	_____
5	_____	_____	_____
6	_____	_____	_____
7	_____	_____	_____
8	_____	_____	_____
9	_____	_____	_____
10	_____	_____	_____

DISTRIBUTION LIST	
1	6
2	7
3	8
4	9
5	10

This document and the information, design and material contained and/or illustrated therein (hereinafter "proprietary material"), is the property of BABCOCK POWER Inc., P.O. Box 15040, Worcester, MA 01615-0040, and is submitted, lent and furnished to recipient in strict confidence with the express understanding that the recipient shall not reproduce, copy, loan, dispose of, or disclose to anyone outside recipient's organization, directly or indirectly, or use said proprietary material for any purpose other than that for which it is furnished and submitted. Recipient by receiving said proprietary material agrees not to use the same in any way injurious to the interest or BABCOCK POWER Inc., and agrees to return same upon request. Copyright © BABCOCK POWER Inc., 2011.

DOCUMENT NUMBER:

0
0

BABCOCK POWER ENVIRONMENTAL INC.

Mill Creek Unit 3

MATERIAL BALANCE
GAS PATH STREAMS

Stream Number		11	13	15	16			
Notes								
Description		FLUE GAS BEFORE ABSORBER	FLUE GAS AFTER ABSORBER	OXIDATION AIR AFTER BLOWER	OXIDATION AIR AFTER HUMIDIFICATION			
Mass Flow	lb/hr, wet	4,959,500	5,321,479	110,824	115,803			
	lb/hr, dry	4,726,452	4,774,738	107,080	107,080			
Volume Flow	acfm, wet	1,656,934	1,362,302	44,249	17,558			
	scfm, wet	1,082,405	1,206,906	25,305	12,786			
	scfm, dry	999,348	1,012,098	23,358	23,358			
Molecular Weight	lb/lb-mole, wet	29.37	28.27	27.95	27.31			
	lb/lb-mole, dry	30.31	30.24	28.50	28.50			
Density	lb/ft ³	0.050	0.065	0.042	0.110			
Temperature	°F	357	131	327	158			
Pressure	iwg	TBD	TBD	--	--			
	psig	--	--	TBD	TBD			
N ₂	lb/hr	3,529,510	3,578,132	92,378	92,378			
O ₂	lb/hr	342,417	350,433	14,673	14,673			
CO ₂	lb/hr	826,212	845,358	29	29			
SO ₂	lb/hr	26,222	393	0	0			
SO ₃	lb/hr	553	277	0	0			
HCl	lb/hr	1,332	13	0	0			
HF	lb/hr	77	1	0	0			
H ₂ O	lb/hr	233,048	546,605	3,744	7,574			
Entrained Moisture	lb/hr	0	136	0	1,149			
Fly Ash	lb/hr	128	130	0	0			
SO ₂ Concentration	ppmv, dry @ actual O ₂	2,630	39	0	0			
SO ₃ Concentration	ppmv, dry @ actual O ₂	44	22	0	0			
HCl Concentration	ppmv, dry @ actual O ₂	235	2	0	0			
HF Concentration	ppmv, dry @ actual O ₂	25	0	0	0			
Dust Loading	gr/dscf @ actual O ₂	0.015	0.015	0.000	0.000			

Stream Number								
Notes								
Description								
Mass Flow	lb/hr, wet							
	lb/hr, dry							
Volume Flow	acfm, wet							
	scfm, wet							
	scfm, dry							
Molecular Weight	lb/lb-mole, wet							
	lb/lb-mole, dry							
Density	lb/ft ³							
Temperature	°F							
Pressure	iwg							
	psig							
N ₂	lb/hr							
O ₂	lb/hr							
CO ₂	lb/hr							
SO ₂	lb/hr							
SO ₃	lb/hr							
HCl	lb/hr							
HF	lb/hr							
H ₂ O	lb/hr							
Entrained Moisture	lb/hr							
Fly Ash	lb/hr							
SO ₂ Concentration	ppmv, dry @ actual O ₂							
SO ₃ Concentration	ppmv, dry @ actual O ₂							
HCl Concentration	ppmv, dry @ actual O ₂							
HF Concentration	ppmv, dry @ actual O ₂							
Dust Loading	gr/dscf @ actual O ₂							

DOCUMENT NUMBER:

0
0

BABCOCK POWER ENVIRONMENTAL INC.

Mill Creek Unit 3

MATERIAL BALANCE
LIQUID AND SOLID STREAMS

Stream Number		20	23	30	31	32		
Notes								
Description		TOTAL RECYCLE FLOW	LIMESTONE SLURRY TO ABSORBER	BLEED FROM ABSORBER	PRIMARY HC OVERFLOW	PRIMARY HC UNDERFLOW		
Mass Flow	lb/hr	120,899,868	276,858	562,764	419,051	143,713		
Volume Flow	gpm	220,000	494	1,024	820	204		
Specific Gravity	--	1.098	1.120	1.098	1.021	1.405		
Density	lb/ft3	68.51	69.94	68.51	63.73	87.70		
Temperature	°F	131	94	131	131	131		
Mass Flow Liquid	lb/hr	102,765,198	228,732	478,351	406,494	71,857		
Cl ⁻	lb/hr	822,122	12.6	3,827	3,252	575		
SO ₄ ⁻	lb/hr	435,763	21.4	2,028	1,724	306		
SO ₃ ⁻	lb/hr	26,725	0.0	124	106	19		
Ca ⁺⁺	lb/hr	178,439	32.5	831	706	125		
Mg ⁺⁺	lb/hr	283,229	14.8	1,318	1,120	199		
Na ⁺	lb/hr	17,393	13.1	81	69	12		
H ₂ O	lb/hr	101,001,528	228,638	470,141	399,518	70,621		
Mass Flow Solids	lb/hr	18,134,670	48,127	84,413	12,556	71,850		
CaSO ₄ ·2H ₂ O	lb/hr	15,953,069	0.0	74,258	7,426	66,827		
CaCO ₃	lb/hr	999,220	43,911	4,651	1,861	2,788		
Inert	lb/hr	761,656	1,328	3,545	2,838	711		
CaSO ₃ ·1/2H ₂ O	lb/hr	108,808	0.0	506	403	101		
MgCO ₃	lb/hr	311,916	2,887.6	1,451.9	28.9	1,422.8		
Ca(OH) ₂	lb/hr	0	0.0	0.0	0.0	0.0		
Mg(OH) ₂	lb/hr	0	0.0	0.0	0.0	0.0		
CaO	lb/hr	0	0.0	0.0	0.0	0.0		
MgO	lb/hr	0	0.0	0.0	0.0	0.0		
Total Suspended Solids	wt.%, wet	15.0	17.4	15.0	3.0	50.0		
Cl ⁻ Concentration	ppm	8,000	55	8,000	8,000	8,000		
pH	--	5 to 7	> 7	5 to 7	5 to 7	5 to 7		

Stream Number		35	38	44	45	47		
Notes								
Description		CHLORIDE PURGE	HC OVERFLOW TO ABSORBER	CLEARWELL POND WATER TO ME WASH	CLEARWELL POND WATER TO OXIDATION	CLEARWELL POND WATER TO ABSORBER		
Mass Flow	lb/hr	94,518	324,532	77,814	4,980	173,348		
Volume Flow	gpm	185	635	156	10.0	346		
Specific Gravity	--	1.021	1.021	0.995	0.995	0.998		
Density	lb/ft3	63.73	63.73	62.08	62.08	62.30		
Temperature	°F	131	131	95	95	95		
Mass Flow Liquid	lb/hr	91,686.2	314,808.3	78,098	4,980	173,061		
Cl ⁻	lb/hr	733.5	2,518.5	4.3	0.3	10		
SO ₄ ⁻	lb/hr	388.8	1,334.9	7.3	0.5	16		
SO ₃ ⁻	lb/hr	23.8	81.9	0.0	0.0	0		
Ca ⁺⁺	lb/hr	159.2	546.6	11.1	0.7	24		
Mg ⁺⁺	lb/hr	252.7	867.6	5.0	0.3	11		
Na ⁺	lb/hr	15.5	53.3	4.5	0.3	10		
H ₂ O	lb/hr	90,112.6	309,405.5	78,066	4,978	172,990		
Mass Flow Solids	lb/hr	2,832.1	3,973.3	1.1	0.1	2.4		
CaSO ₄ ·2H ₂ O	lb/hr	1,674.9	0.0	0.0	0.0	0.0		
CaCO ₃	lb/hr	419.7	1,441.1	0.0	0.0	0.0		
Inert	lb/hr	640.0	2,197.7	1.1	0.1	2.4		
CaSO ₃ ·1/2H ₂ O	lb/hr	90.9	312.1	0.0	0.0	0.0		
MgCO ₃	lb/hr	6.5	22.4	0.0	0.0	0.0		
Ca(OH) ₂	lb/hr	0.0	0.0	0.0	0.0	0.0		
Mg(OH) ₂	lb/hr	0.0	0.0	0.0	0.0	0.0		
CaO	lb/hr	0.0	0.0	0.0	0.0	0.0		
MgO	lb/hr	0.0	0.0	0.0	0.0	0.0		
Total Suspended Solids	wt.%, wet	3.0	1.2	0.0	0.0	0.0		
Cl ⁻ Concentration	ppm	8,000	8,000	55	55	55		
pH	--	5 to 7	5 to 7	6 to 8	6 to 8	6 to 8		

DOCUMENT NUMBER: 0
0

BABCOCK POWER ENVIRONMENTAL INC.
Mill Creek Unit 3

MATERIAL BALANCE
FUEL DATA, BOILER DATA, AND NOTES

Unit Rating	MWg	425
Boiler Heat Input	MBtu/hr	4,208
Fuel Feed Rate	lb/hr	386,068
SO ₂ Inlet Loading	lb SO ₂ /MBtu	6.32
SO ₂ Removal Efficiency	%	98.5
Excess Air	%	20.0
Air Heater Leakage	%	10.0
Oxygen at FGD Inlet	vol.%, dry	6.95
Site Elevation	ft above MSL	460
Ambient Pressure	in H ₂ O	14.45
Ambient Temperature	°F	-23.1 - 105.4

Coal Analysis		
Coal	--	Performance Fuel
Carbon	wt.%, wet	60.00
Hydrogen	wt.%, wet	4.00
Nitrogen	wt.%, wet	1.30
Oxygen	wt.%, wet	5.90
Sulfur	wt.%, wet	3.45
Chlorine	wt.%, wet	0.35
Fluorine	wt.%, wet	0.02
Ash	wt.%, wet	14.00
Moisture	wt.%, wet	11.00
Higher Heating Value (HHV)	BTU/lb	10,900

Limestone Analysis		
Total CaCO ₃	wt.%, dry	Note 4 94.6
Reactive CaCO ₃	%	91.3
Total MgCO ₃	wt.%, dry	2.4
Reactive MgCO ₃	%	
Inerts	wt.%, dry	3.0

Gypsum Quality (at HC Underflow)		
Free Moisture	wt.%	--
CaSO ₄ -2H ₂ O	wt.%, dry	93
CaSO ₃ -1/2H ₂ O	wt.%, dry	0.14
CaCO ₃	wt.%, dry	3.88
Inerts	wt.%, dry	0.99
MgCO ₃	wt.%, dry	2.0
Fly Ash	wt.%, dry	
Maximum Chloride Content	ppmvd	8,000
Total Suspended Solids (TSS)	wt.%	
Total Dissolved Solids (TDS)	mg/L	
Average Particle Diameter	microns	

- Notes:
1. For stream references see Process Flow Diagram, document number 502718-103000100.
 2. Values provided represent time-averaged values and do not necessarily represent equipment capacity or actual continuous operation.
 3. Emergency Quench flow normally 0 gpm.
 4. Assumes 96.5% CaCO₃ availability on total CaCO₃.

DOCUMENT NUMBER:



BabcockPower
ENVIRONMENTAL

MATERIAL BALANCE WET FLUE GAS DESULFURIZATION

PROJECT NUMBER	100585
CUSTOMER NAME	Louisville Gas & Electric (LG&E)
PROJECT NAME	Mill Creek Unit 3
LOCATION - CITY, STATE	Louisville, KY
DESCRIPTION	CASE: Design - 15,000 ppm Cl, no filtrate return
	LOAD: 100% MCR
	FUEL: High Sulfur Bituminous Coal
	SO ₂ Removal Efficiency: 98.5%
	REAGENT: Limestone
	WATER: Clearwell Pond Water

PREPARED	NAME	_____
	DATE	_____
CHECKED	NAME	_____
	DATE	_____
APPROVED	NAME	_____
	DATE	_____

REVISION HISTORY		PREPARED BY	APPROVED BY
1	_____	_____	_____
2	_____	_____	_____
3	_____	_____	_____
4	_____	_____	_____
5	_____	_____	_____
6	_____	_____	_____
7	_____	_____	_____
8	_____	_____	_____
9	_____	_____	_____
10	_____	_____	_____

DISTRIBUTION LIST	
1	6
2	7
3	8
4	9
5	10

This document and the information, design and material contained and/or illustrated therein (hereinafter "proprietary material"), is the property of BABCOCK POWER Inc., P.O. Box 15040, Worcester, MA 01615-0040, and is submitted, lent and furnished to recipient in strict confidence with the express understanding that the recipient shall not reproduce, copy, loan, dispose of, or disclose to anyone outside recipient's organization, directly or indirectly, or use said proprietary material for any purpose other than that for which it is furnished and submitted. Recipient by receiving said proprietary material agrees not to use the same in any way injurious to the interest or BABCOCK POWER Inc., and agrees to return same upon request. Copyright © BABCOCK POWER Inc., 2011.

DOCUMENT NUMBER:

0
0

BABCOCK POWER ENVIRONMENTAL INC.

Mill Creek Unit 3

MATERIAL BALANCE
GAS PATH STREAMS

Stream Number		11	13	15	16			
Notes								
Description		FLUE GAS BEFORE ABSORBER	FLUE GAS AFTER ABSORBER	OXIDATION AIR AFTER BLOWER	OXIDATION AIR AFTER HUMIDIFICATION			
Mass Flow	lb/hr, wet	4,959,500	5,321,518	110,824	115,803			
	lb/hr, dry	4,726,452	4,774,738	107,080	107,080			
Volume Flow	acfm, wet	1,656,934	1,362,319	44,249	17,558			
	scfm, wet	1,082,405	1,206,921	25,305	12,786			
	scfm, dry	999,348	1,012,098	23,358	23,358			
Molecular Weight	lb/lb-mole, wet	29.37	28.27	27.95	27.31			
	lb/lb-mole, dry	30.31	30.24	28.50	28.50			
Density	lb/ft ³	0.050	0.065	0.042	0.110			
Temperature	°F	357	131	327	158			
Pressure	iwg	TBD	TBD	--	--			
	psig	--	--	TBD	TBD			
N ₂	lb/hr	3,529,510	3,578,114	92,378	92,378			
O ₂	lb/hr	342,417	350,438	14,673	14,673			
CO ₂	lb/hr	826,212	845,372	29	29			
SO ₂	lb/hr	26,222	393	0	0			
SO ₃	lb/hr	553	277	0	0			
HCl	lb/hr	1,332	13	0	0			
HF	lb/hr	77	1	0	0			
H ₂ O	lb/hr	233,048	546,645	3,744	7,574			
Entrained Moisture	lb/hr	0	136	0	1,149			
Fly Ash	lb/hr	128	130	0	0			
SO ₂ Concentration	ppmv, dry @ actual O ₂	2,630	39	0	0			
SO ₃ Concentration	ppmv, dry @ actual O ₂	44	22	0	0			
HCl Concentration	ppmv, dry @ actual O ₂	235	2	0	0			
HF Concentration	ppmv, dry @ actual O ₂	25	0	0	0			
Dust Loading	gr/dscf @ actual O ₂	0.015	0.015	0.000	0.000			

Stream Number								
Notes								
Description								
Mass Flow	lb/hr, wet							
	lb/hr, dry							
Volume Flow	acfm, wet							
	scfm, wet							
	scfm, dry							
Molecular Weight	lb/lb-mole, wet							
	lb/lb-mole, dry							
Density	lb/ft ³							
Temperature	°F							
Pressure	iwg							
	psig							
N ₂	lb/hr							
O ₂	lb/hr							
CO ₂	lb/hr							
SO ₂	lb/hr							
SO ₃	lb/hr							
HCl	lb/hr							
HF	lb/hr							
H ₂ O	lb/hr							
Entrained Moisture	lb/hr							
Fly Ash	lb/hr							
SO ₂ Concentration	ppmv, dry @ actual O ₂							
SO ₃ Concentration	ppmv, dry @ actual O ₂							
HCl Concentration	ppmv, dry @ actual O ₂							
HF Concentration	ppmv, dry @ actual O ₂							
Dust Loading	gr/dscf @ actual O ₂							

DOCUMENT NUMBER:

0
0

BABCOCK POWER ENVIRONMENTAL INC.

Mill Creek Unit 3

MATERIAL BALANCE LIQUID AND SOLID STREAMS

Stream Number		20	23	30	31	32		
Notes								
Description		TOTAL RECYCLE FLOW	LIMESTONE SLURRY TO ABSORBER	BLEED FROM ABSORBER	PRIMARY HC OVERFLOW	PRIMARY HC UNDERFLOW		
Mass Flow	lb/hr	122,210,764	240,920	600,348	451,121	149,252		
Volume Flow	gpm	220,000	421	1,081	870	210		
Specific Gravity	--	1.109	1.142	1.109	1.035	1.417		
Density	lb/ft3	69.26	71.29	69.25	64.61	88.42		
Temperature	°F	131	94	131	131	131		
Mass Flow Liquid	lb/hr	103,872,211	192,793	510,271	435,670	74,626		
Cl ⁻	lb/hr	1,558,083	10.6	7,654	6,535	1,119		
SO ₄ ⁻	lb/hr	575,635	18.0	2,828	2,414	420		
SO ₃ ⁻	lb/hr	32,728	0.0	161	137	24		
Ca ⁺⁺	lb/hr	234,012	27.4	1,150	982	171		
Mg ⁺⁺	lb/hr	533,624	12.4	2,621	2,238	389		
Na ⁺	lb/hr	27,878	11.0	137	117	20		
H ₂ O	lb/hr	100,910,251	192,714	495,720	423,247	72,483		
Mass Flow Solids	lb/hr	18,338,553	48,126	90,086	15,451	74,626		
CaSO ₄ ·2H ₂ O	lb/hr	15,529,368	0.0	76,286	7,628	68,656		
CaCO ₃	lb/hr	1,056,195	43,910	5,188	2,075	3,112		
Inert	lb/hr	1,257,899	1,328	6,179	4,941	1,239		
CaSO ₃ ·1/2H ₂ O	lb/hr	198,037	0.0	973	777	194		
MgCO ₃	lb/hr	297,055	2,887.6	1,459.3	29.4	1,425.4		
Ca(OH) ₂	lb/hr	0	0.0	0.0	0.0	0.0		
Mg(OH) ₂	lb/hr	0	0.0	0.0	0.0	0.0		
CaO	lb/hr	0	0.0	0.0	0.0	0.0		
MgO	lb/hr	0	0.0	0.0	0.0	0.0		
Total Suspended Solids	wt.%, wet	15.0	20.0	15.0	3.4	50.0		
Cl ⁻ Concentration	ppm	15,000	55	15,000	15,000	15,000		
pH	--	5 to 7	> 7	5 to 7	5 to 7	5 to 7		

Stream Number		35	38	44	45	47		
Notes								
Description		CHLORIDE PURGE	HC OVERFLOW TO ABSORBER	CLEARWELL POND WATER TO ME WASH	CLEARWELL POND WATER TO OXIDATION	CLEARWELL POND WATER TO ABSORBER		
Mass Flow	lb/hr	12,781	438,340	77,814	4,980	133,103		
Volume Flow	gpm	25	846	156	10.0	266		
Specific Gravity	--	1.035	1.035	0.995	0.995	0.998		
Density	lb/ft3	64.61	64.61	62.08	62.08	62.30		
Temperature	°F	131	131	95	95	95		
Mass Flow Liquid	lb/hr	12,343.2	423,326.9	78,107	4,980	132,807		
Cl ⁻	lb/hr	185.1	6,349.9	4.3	0.3	7		
SO ₄ ⁻	lb/hr	68.4	2,346.0	7.3	0.5	12		
SO ₃ ⁻	lb/hr	3.9	133.4	0.0	0.0	0		
Ca ⁺⁺	lb/hr	27.8	953.7	11.1	0.7	19		
Mg ⁺⁺	lb/hr	63.4	2,174.8	5.0	0.3	8		
Na ⁺	lb/hr	3.3	113.6	4.5	0.3	8		
H ₂ O	lb/hr	11,991.3	411,255.6	78,075	4,978	132,753		
Mass Flow Solids	lb/hr	437.8	7,601.3	1.1	0.1	1.9		
CaSO ₄ ·2H ₂ O	lb/hr	216.2	0.0	0.0	0.0	0.0		
CaCO ₃	lb/hr	58.8	2,016.3	0.0	0.0	0.0		
Inert	lb/hr	140.0	4,801.3	1.1	0.1	1.9		
CaSO ₃ ·1/2H ₂ O	lb/hr	22.0	755.2	0.0	0.0	0.0		
MgCO ₃	lb/hr	0.8	28.5	0.0	0.0	0.0		
Ca(OH) ₂	lb/hr	0.0	0.0	0.0	0.0	0.0		
Mg(OH) ₂	lb/hr	0.0	0.0	0.0	0.0	0.0		
CaO	lb/hr	0.0	0.0	0.0	0.0	0.0		
MgO	lb/hr	0.0	0.0	0.0	0.0	0.0		
Total Suspended Solids	wt.%, wet	3.4	1.7	0.0	0.0	0.0		
Cl ⁻ Concentration	ppm	15,000	15,000	55	55	55		
pH	--	5 to 7	5 to 7	6 to 8	6 to 8	6 to 8		

DOCUMENT NUMBER: 0
0

BABCOCK POWER ENVIRONMENTAL INC.
Mill Creek Unit 3

MATERIAL BALANCE FUEL DATA, BOILER DATA, AND NOTES

Unit Rating	MWg	425
Boiler Heat Input	MBtu/hr	4,208
Fuel Feed Rate	lb/hr	386,068
SO ₂ Inlet Loading	lb SO ₂ /MBtu	6.32
SO ₂ Removal Efficiency	%	98.5
Excess Air	%	20.0
Air Heater Leakage	%	10.0
Oxygen at FGD Inlet	vol.%, dry	6.95
Site Elevation	ft above MSL	460
Ambient Pressure	in H ₂ O	14.45
Ambient Temperature	°F	-23.1 - 105.4
Coal Analysis		
Coal	--	Performance Fuel
Carbon	wt.%, wet	60.00
Hydrogen	wt.%, wet	4.00
Nitrogen	wt.%, wet	1.30
Oxygen	wt.%, wet	5.90
Sulfur	wt.%, wet	3.45
Chlorine	wt.%, wet	0.35
Fluorine	wt.%, wet	0.02
Ash	wt.%, wet	14.00
Moisture	wt.%, wet	11.00
Higher Heating Value (HHV)	BTU/lb	10,900
Limestone Analysis		
Total CaCO ₃	wt.%, dry	Note 4 94.6
Reactive CaCO ₃	%	91.3
Total MgCO ₃	wt.%, dry	2.4
Reactive MgCO ₃	%	
Inerts	wt.%, dry	3.0
Gypsum Quality (at HC Underflow)		
Free Moisture	wt.%	--
CaSO ₄ -2H ₂ O	wt.%, dry	92
CaSO ₃ -1/2H ₂ O	wt.%, dry	0.26
CaCO ₃	wt.%, dry	4.17
Inerts	wt.%, dry	1.66
MgCO ₃	wt.%, dry	1.9
Fly Ash	wt.%, dry	
Maximum Chloride Content	ppmvd	15,000
Total Suspended Solids (TSS)	wt.%	
Total Dissolved Solids (TDS)	mg/L	
Average Particle Diameter	microns	

Notes:

1. For stream references see Process Flow Diagram, document number 502718-103000100.
2. Values provided represent time-averaged values and do not necessarily represent equipment capacity or actual continuous operation.
3. Emergency Quench flow normally 0 gpm.
4. Assumes 96.5% CaCO₃ availability on total CaCO₃.

DOCUMENT NUMBER:



BabcockPower
ENVIRONMENTAL

**MATERIAL BALANCE
WET FLUE GAS DESULFURIZATION**

PROJECT NUMBER	100585
CUSTOMER NAME	Louisville Gas & Electric (LG&E)
PROJECT NAME	Mill Creek Unit 3
LOCATION - CITY, STATE	Louisville, KY
DESCRIPTION	CASE: Design - 50,000 ppm Cl - no filtrate return
	LOAD: 100% MCR
	FUEL: High Sulfur Bituminous Coal
	SO ₂ Removal Efficiency: 98.5%
	REAGENT: Limestone
	WATER: Clearwell Pond Water

PREPARED	NAME	_____
	DATE	_____
CHECKED	NAME	_____
	DATE	_____
APPROVED	NAME	_____
	DATE	_____

REVISION HISTORY		PREPARED BY	APPROVED BY
1	_____	_____	_____
2	_____	_____	_____
3	_____	_____	_____
4	_____	_____	_____
5	_____	_____	_____
6	_____	_____	_____
7	_____	_____	_____
8	_____	_____	_____
9	_____	_____	_____
10	_____	_____	_____

DISTRIBUTION LIST	
1	6
2	7
3	8
4	9
5	10

This document and the information, design and material contained and/or illustrated therein (hereinafter "proprietary material"), is the property of BABCOCK POWER Inc., P.O. Box 15040, Worcester, MA 01615-0040, and is submitted, lent and furnished to recipient in strict confidence with the express understanding that the recipient shall not reproduce, copy, loan, dispose of, or disclose to anyone outside recipient's organization, directly or indirectly, or use said proprietary material for any purpose other than that for which it is furnished and submitted. Recipient by receiving said proprietary material agrees not to use the same in any way injurious to the interest or BABCOCK POWER Inc., and agrees to return same upon request. Copyright © BABCOCK POWER Inc., 2011.

DOCUMENT NUMBER:

0
0

BABCOCK POWER ENVIRONMENTAL INC.

Mill Creek Unit 3

MATERIAL BALANCE
GAS PATH STREAMS

Stream Number		11	13	15	16			
Notes								
Description		FLUE GAS BEFORE ABSORBER	FLUE GAS AFTER ABSORBER	OXIDATION AIR AFTER BLOWER	OXIDATION AIR AFTER HUMIDIFICATION			
Mass Flow	lb/hr, wet	4,959,500	5,321,532	110,824	115,803			
	lb/hr, dry	4,726,452	4,774,738	107,080	107,080			
Volume Flow	acfm, wet	1,656,934	1,362,324	44,249	17,558			
	scfm, wet	1,082,405	1,206,925	25,305	12,786			
	scfm, dry	999,348	1,012,098	23,358	23,358			
Molecular Weight	lb/lb-mole, wet	29.37	28.27	27.95	27.31			
	lb/lb-mole, dry	30.31	30.24	28.50	28.50			
Density	lb/ft ³	0.050	0.065	0.042	0.110			
Temperature	°F	357	131	327	158			
Pressure	iwg	TBD	TBD	--	--			
	psig	--	--	TBD	TBD			
N ₂	lb/hr	3,529,510	3,578,108	92,378	92,378			
O ₂	lb/hr	342,417	350,440	14,673	14,673			
CO ₂	lb/hr	826,212	845,376	29	29			
SO ₂	lb/hr	26,222	393	0	0			
SO ₃	lb/hr	553	277	0	0			
HCl	lb/hr	1,332	13	0	0			
HF	lb/hr	77	1	0	0			
H ₂ O	lb/hr	233,048	546,658	3,744	7,574			
Entrained Moisture	lb/hr	0	136	0	1,149			
Fly Ash	lb/hr	128	130	0	0			
SO ₂ Concentration	ppmv, dry @ actual O ₂	2,630	39	0	0			
SO ₃ Concentration	ppmv, dry @ actual O ₂	44	22	0	0			
HCl Concentration	ppmv, dry @ actual O ₂	235	2	0	0			
HF Concentration	ppmv, dry @ actual O ₂	25	0	0	0			
Dust Loading	gr/dscf @ actual O ₂	0.015	0.015	0.000	0.000			

Stream Number								
Notes								
Description								
Mass Flow	lb/hr, wet							
	lb/hr, dry							
Volume Flow	acfm, wet							
	scfm, wet							
	scfm, dry							
Molecular Weight	lb/lb-mole, wet							
	lb/lb-mole, dry							
Density	lb/ft ³							
Temperature	°F							
Pressure	iwg							
	psig							
N ₂	lb/hr							
O ₂	lb/hr							
CO ₂	lb/hr							
SO ₂	lb/hr							
SO ₃	lb/hr							
HCl	lb/hr							
HF	lb/hr							
H ₂ O	lb/hr							
Entrained Moisture	lb/hr							
Fly Ash	lb/hr							
SO ₂ Concentration	ppmv, dry @ actual O ₂							
SO ₃ Concentration	ppmv, dry @ actual O ₂							
HCl Concentration	ppmv, dry @ actual O ₂							
HF Concentration	ppmv, dry @ actual O ₂							
Dust Loading	gr/dscf @ actual O ₂							

DOCUMENT NUMBER:

0

BABCOCK POWER ENVIRONMENTAL INC.

0

Mill Creek Unit 3

MATERIAL BALANCE

LIQUID AND SOLID STREAMS

Stream Number		20	23	30	31	32		
Notes								
Description		TOTAL RECYCLE FLOW	LIMESTONE SLURRY TO ABSORBER	BLEED FROM ABSORBER	PRIMARY HC OVERFLOW	PRIMARY HC UNDERFLOW		
Mass Flow	lb/hr	122,629,370	235,586	607,403	458,198	150,145		
Volume Flow	gpm	220,000	411	1,090	881	211		
Specific Gravity	--	1.113	1.145	1.113	1.039	1.421		
Density	lb/ft3	69.49	71.50	69.49	64.87	88.76		
Temperature	°F	131	94	131	131	131		
Mass Flow Liquid	lb/hr	104,219,432	187,459	516,224	442,092	75,072		
Cl ⁻	lb/hr	1,797,806	10.3	8,905	7,626	1,295		
SO ₄ ⁻	lb/hr	617,178	17.5	3,057	2,618	453		
SO ₃ ⁻	lb/hr	34,701	0.0	172	147	25		
Ca ⁺⁺	lb/hr	250,497	26.6	1,241	1,063	184		
Mg ⁺⁺	lb/hr	615,163	12.1	3,047	2,609	451		
Na ⁺	lb/hr	31,294	10.7	155	133	23		
H ₂ O	lb/hr	100,872,793	187,382	499,648	427,896	72,641		
Mass Flow Solids	lb/hr	18,409,937	48,131	91,187	16,107	75,072		
CaSO ₄ ·2H ₂ O	lb/hr	15,457,279	0.0	76,562	7,657	68,909		
CaCO ₃	lb/hr	1,063,988	43,915	5,270	2,107	3,161		
Inert	lb/hr	1,375,085	1,328	6,811	5,447	1,359		
CaSO ₃ ·1/2H ₂ O	lb/hr	219,056	0.0	1,085	868	218		
MgCO ₃	lb/hr	294,530	2,887.6	1,458.9	29.0	1,426.4		
Ca(OH) ₂	lb/hr	0	0.0	0.0	0.0	0.0		
Mg(OH) ₂	lb/hr	0	0.0	0.0	0.0	0.0		
CaO	lb/hr	0	0.0	0.0	0.0	0.0		
MgO	lb/hr	0	0.0	0.0	0.0	0.0		
Total Suspended Solids	wt.%, wet	15.0	20.4	15.0	3.5	50.0		
Cl ⁻ Concentration	ppm	17,250	55	17,250	17,250	17,250		
pH	--	5 to 7	> 7	5 to 7	5 to 7	5 to 7		

Stream Number		35	38	44	45	47		
Notes								
Description		CHLORIDE PURGE	HC OVERFLOW TO ABSORBER	CLEARWELL POND WATER TO ME WASH	CLEARWELL POND WATER TO OXIDATION	CLEARWELL POND WATER TO ABSORBER		
Mass Flow	lb/hr	1,483	456,715	77,814	4,980	127,130		
Volume Flow	gpm	3	877	156	10.0	254		
Specific Gravity	--	1.039	1.039	0.995	0.995	0.998		
Density	lb/ft3	64.88	64.88	62.08	62.08	62.30		
Temperature	°F	131	131	95	95	95		
Mass Flow Liquid	lb/hr	1,430.4	440,661.2	78,096	4,980	126,846		
Cl ⁻	lb/hr	24.7	7,601.4	4.3	0.3	7		
SO ₄ ⁻	lb/hr	8.5	2,609.5	7.3	0.5	12		
SO ₃ ⁻	lb/hr	0.5	146.7	0.0	0.0	0		
Ca ⁺⁺	lb/hr	3.4	1,059.1	11.1	0.7	18		
Mg ⁺⁺	lb/hr	8.4	2,601.0	5.0	0.3	8		
Na ⁺	lb/hr	0.4	132.3	4.5	0.3	7		
H ₂ O	lb/hr	1,384.4	426,511.2	78,064	4,978	126,794		
Mass Flow Solids	lb/hr	52.0	8,423.4	1.1	0.1	1.7		
CaSO ₄ ·2H ₂ O	lb/hr	24.7	0.0	0.0	0.0	0.0		
CaCO ₃	lb/hr	6.8	2,099.8	0.0	0.0	0.0		
Inert	lb/hr	17.6	5,429.4	1.1	0.1	1.7		
CaSO ₃ ·1/2H ₂ O	lb/hr	2.8	865.3	0.0	0.0	0.0		
MgCO ₃	lb/hr	0.1	28.9	0.0	0.0	0.0		
Ca(OH) ₂	lb/hr	0.0	0.0	0.0	0.0	0.0		
Mg(OH) ₂	lb/hr	0.0	0.0	0.0	0.0	0.0		
CaO	lb/hr	0.0	0.0	0.0	0.0	0.0		
MgO	lb/hr	0.0	0.0	0.0	0.0	0.0		
Total Suspended Solids	wt.%, wet	3.5	1.8	0.0	0.0	0.0		
Cl ⁻ Concentration	ppm	17,250	17,250	55	55	55		
pH	--	5 to 7	5 to 7	6 to 8	6 to 8	6 to 8		

DOCUMENT NUMBER: 0
0

BABCOCK POWER ENVIRONMENTAL INC.
Mill Creek Unit 3

MATERIAL BALANCE FUEL DATA, BOILER DATA, AND NOTES

Unit Rating	MWg	425
Boiler Heat Input	MBtu/hr	4,208
Fuel Feed Rate	lb/hr	386,068
SO ₂ Inlet Loading	lb SO ₂ /MBtu	6.32
SO ₂ Removal Efficiency	%	98.5
Excess Air	%	20.0
Air Heater Leakage	%	10.0
Oxygen at FGD Inlet	vol.%, dry	6.95
Site Elevation	ft above MSL	460
Ambient Pressure	in H ₂ O	14.45
Ambient Temperature	°F	-23.1 - 105.4
Coal Analysis		
Coal	--	Performance Fuel
Carbon	wt.%, wet	60.00
Hydrogen	wt.%, wet	4.00
Nitrogen	wt.%, wet	1.30
Oxygen	wt.%, wet	5.90
Sulfur	wt.%, wet	3.45
Chlorine	wt.%, wet	0.35
Fluorine	wt.%, wet	0.02
Ash	wt.%, wet	14.00
Moisture	wt.%, wet	11.00
Higher Heating Value (HHV)	BTU/lb	10,900
Limestone Analysis		
Total CaCO ₃	wt.%, dry	Note 4 94.6
Reactive CaCO ₃	%	91.3
Total MgCO ₃	wt.%, dry	2.4
Reactive MgCO ₃	%	
Inerts	wt.%, dry	3.0
Gypsum Quality (at HC Underflow)		
Free Moisture	wt.%	--
CaSO ₄ -2H ₂ O	wt.%, dry	91.79
CaSO ₃ -1/2H ₂ O	wt.%, dry	0.29
CaCO ₃	wt.%, dry	4.21
Inerts	wt.%, dry	1.81
MgCO ₃	wt.%, dry	1.9
Fly Ash	wt.%, dry	
Maximum Chloride Content	ppmvd	17,250
Total Suspended Solids (TSS)	wt.%	
Total Dissolved Solids (TDS)	mg/L	
Average Particle Diameter	microns	

Notes:

1. For stream references see Process Flow Diagram, document number 502718-103000100.
2. Values provided represent time-averaged values and do not necessarily represent equipment capacity or actual continuous operation.
3. Emergency Quench flow normally 0 gpm.
4. Assumes 96.5% CaCO₃ availability on total CaCO₃.

DOCUMENT NUMBER:



BabcockPower
ENVIRONMENTAL

**MATERIAL BALANCE
WET FLUE GAS DESULFURIZATION**

PROJECT NUMBER	100585
CUSTOMER NAME	Louisville Gas & Electric (LG&E)
PROJECT NAME	Mill Creek Unit 3
LOCATION - CITY, STATE	Louisville, KY
DESCRIPTION	CASE: Design - 8,000 ppm Cl - filtrate return via Clearwell Pond
	LOAD: 100% MCR
	FUEL: High Sulfur Bituminous Coal
	SO ₂ Removal Efficiency: 98.5%
	REAGENT: Limestone
	WATER: Clearwell Pond Water + Service Water for ME Wash

PREPARED	NAME	_____
	DATE	_____
CHECKED	NAME	_____
	DATE	_____
APPROVED	NAME	_____
	DATE	_____

REVISION HISTORY		PREPARED BY	APPROVED BY
1	_____	_____	_____
2	_____	_____	_____
3	_____	_____	_____
4	_____	_____	_____
5	_____	_____	_____
6	_____	_____	_____
7	_____	_____	_____
8	_____	_____	_____
9	_____	_____	_____
10	_____	_____	_____

DISTRIBUTION LIST	
1	6
2	7
3	8
4	9
5	10

This document and the information, design and material contained and/or illustrated therein (hereinafter "proprietary material"), is the property of BABCOCK POWER Inc., P.O. Box 15040, Worcester, MA 01615-0040, and is submitted, lent and furnished to recipient in strict confidence with the express understanding that the recipient shall not reproduce, copy, loan, dispose of, or disclose to anyone outside recipient's organization, directly or indirectly, or use said proprietary material for any purpose other than that for which it is furnished and submitted. Recipient by receiving said proprietary material agrees not to use the same in any way injurious to the interest or BABCOCK POWER Inc., and agrees to return same upon request. Copyright © BABCOCK POWER Inc., 2011.

DOCUMENT NUMBER:

0
0

BABCOCK POWER ENVIRONMENTAL INC.

Mill Creek Unit 3

MATERIAL BALANCE GAS PATH STREAMS

Stream Number		11	13	15	16			
Notes								
Description		FLUE GAS BEFORE ABSORBER	FLUE GAS AFTER ABSORBER	OXIDATION AIR AFTER BLOWER	OXIDATION AIR AFTER HUMIDIFICATION			
Mass Flow	lb/hr, wet	4,942,271	5,298,295	110,824	115,779			
	lb/hr, dry	4,704,921	4,750,980	105,361	107,276			
Volume Flow	acfm, wet	1,652,827	1,357,500	44,249	17,550			
	scfm, wet	1,079,723	1,202,285	25,305	12,781			
	scfm, dry	995,132	1,007,273	23,358	23,358			
Molecular Weight	lb/lb-mole, wet	29.34	28.25	27.96	27.31			
	lb/lb-mole, dry	30.30	30.23	27.97	28.48			
Density	lb/ft ³	0.050	0.065	0.042	0.110			
Temperature	°F	357	131	327	158			
Pressure	iwg	TBD	TBD	--	--			
	psig	--	--	TBD	TBD			
N ₂	lb/hr	3,517,078	3,562,873	93,341	93,341			
O ₂	lb/hr	340,973	348,764	13,907	13,907			
CO ₂	lb/hr	820,682	838,573	28	28			
SO ₂	lb/hr	24,853	373	0	0			
SO ₃	lb/hr	522	261	0	0			
HCl	lb/hr	609	6	0	0			
HF	lb/hr	77	1	0	0			
H ₂ O	lb/hr	237,349	547,180	3,548	7,360			
Entrained Moisture	lb/hr	0	135	0	1,143			
Fly Ash	lb/hr	128	130	0	0			
SO ₂ Concentration	ppmv, dry @ actual O ₂	2,503	37	0	0			
SO ₃ Concentration	ppmv, dry @ actual O ₂	42	21	0	0			
HCl Concentration	ppmv, dry @ actual O ₂	108	1	0	0			
HF Concentration	ppmv, dry @ actual O ₂	25	0	0	0			
Dust Loading	gr/dscf @ actual O ₂	0.015	0.015	0.000	0.000			

Stream Number								
Notes								
Description								
Mass Flow	lb/hr, wet							
	lb/hr, dry							
Volume Flow	acfm, wet							
	scfm, wet							
	scfm, dry							
Molecular Weight	lb/lb-mole, wet							
	lb/lb-mole, dry							
Density	lb/ft ³							
Temperature	°F							
Pressure	iwg							
	psig							
N ₂	lb/hr							
O ₂	lb/hr							
CO ₂	lb/hr							
SO ₂	lb/hr							
SO ₃	lb/hr							
HCl	lb/hr							
HF	lb/hr							
H ₂ O	lb/hr							
Entrained Moisture	lb/hr							
Fly Ash	lb/hr							
SO ₂ Concentration	ppmv, dry @ actual O ₂							
SO ₃ Concentration	ppmv, dry @ actual O ₂							
HCl Concentration	ppmv, dry @ actual O ₂							
HF Concentration	ppmv, dry @ actual O ₂							
Dust Loading	gr/dscf @ actual O ₂							

DOCUMENT NUMBER:

0

BABCOCK POWER ENVIRONMENTAL INC.

0

Mill Creek Unit 3

MATERIAL BALANCE

LIQUID AND SOLID STREAMS

Stream Number		20	23	30	31	32		
Notes								
Description		TOTAL RECYCLE FLOW	LIMESTONE SLURRY TO ABSORBER	BLEED FROM ABSORBER	PRIMARY HC OVERFLOW	PRIMARY HC UNDERFLOW		
Mass Flow	lb/hr	122,166,700	243,545	541,971	405,578	136,392		
Volume Flow	gpm	220,000	431	976	784	192		
Specific Gravity	--	1.109	1.129	1.109	1.034	1.416		
Density	lb/ft3	69.23	70.52	69.22	64.52	88.38		
Temperature	°F	131	94	131	131	131		
Mass Flow Liquid	lb/hr	103,839,217	198,476	460,672	392,476	68,196		
Cl ⁻	lb/hr	830,714	10.9	3,685	3,140	546		
SO ₄ ⁻	lb/hr	1,346,198	18.6	5,972	5,088	897		
SO ₃ ⁻	lb/hr	62,661	0.0	278	237	42		
Ca ⁺⁺	lb/hr	93,342	28.2	414	353	62		
Mg ⁺⁺	lb/hr	572,363	12.8	2,539	2,163	381		
Na ⁺	lb/hr	30,742	11.3	136	116	20		
H ₂ O	lb/hr	100,903,197	198,394	447,647	381,379	66,248		
Mass Flow Solids	lb/hr	18,327,484	45,070	81,307	13,102	68,203		
CaSO ₄ ·2H ₂ O	lb/hr	15,807,707	0.0	70,128	7,012	63,116		
CaCO ₃	lb/hr	1,006,078	40,739	4,463	1,785	2,680		
Inert	lb/hr	1,090,376	1,627	4,837	3,870	968		
CaSO ₃ ·1/2H ₂ O	lb/hr	115,452	0.0	512	407	102		
MgCO ₃	lb/hr	307,871	2,704.2	1,365.8	27.5	1,336.6		
Ca(OH) ₂	lb/hr	0	0.0	0.0	0.0	0.0		
Mg(OH) ₂	lb/hr	0	0.0	0.0	0.0	0.0		
CaO	lb/hr	0	0.0	0.0	0.0	0.0		
MgO	lb/hr	0	0.0	0.0	0.0	0.0		
Total Suspended Solids	wt.%, wet	15.0	18.5	15.0	3.2	50.0		
Cl ⁻ Concentration	ppm	8,000	55	8,000	8,000	8,000		
pH	--	5 to 7	> 7	5 to 7	5 to 7	5 to 7		

Stream Number		35	38	44	45	47		
Notes								
Description		CHLORIDE PURGE	HC OVERFLOW TO ABSORBER	SERVICE WATER WATER TO ME WASH	SERVICE WATER WATER TO OXIDATION	CLEARWELL POND RETURN TO ABSORBER		
Mass Flow	lb/hr	70,617	334,961	77,814	4,955	158,207		
Volume Flow	gpm	136	647	156	10.0	315		
Specific Gravity	--	1.034	1.034	0.995	0.995	1.005		
Density	lb/ft3	64.53	64.53	62.08	62.08	62.72		
Temperature	°F	131	131	95	95	131		
Mass Flow Liquid	lb/hr	68,335.9	324,140.2	78,088	4,955	158,198		
Cl ⁻	lb/hr	546.7	2,593.1	4.3	0.3	490		
SO ₄ ⁻	lb/hr	885.9	4,202.2	7.3	0.5	795		
SO ₃ ⁻	lb/hr	41.2	195.6	0.0	0.0	37		
Ca ⁺⁺	lb/hr	61.4	291.4	11.1	0.7	68		
Mg ⁺⁺	lb/hr	376.7	1,786.7	5.0	0.3	340		
Na ⁺	lb/hr	20.2	96.0	4.5	0.3	24		
H ₂ O	lb/hr	66,403.8	314,975.3	78,055	4,953	156,444		
Mass Flow Solids	lb/hr	2,281.3	10,820.9	1.1	0.1	8.2		
CaSO ₄ ·2H ₂ O	lb/hr	1,221.0	5,791.4	0.0	0.0	6.3		
CaCO ₃	lb/hr	310.7	1,473.8	0.0	0.0	0.3		
Inert	lb/hr	673.9	3,196.5	1.1	0.1	1.4		
CaSO ₃ ·1/2H ₂ O	lb/hr	70.9	336.5	0.0	0.0	0.0		
MgCO ₃	lb/hr	4.8	22.7	0.0	0.0	0.1		
Ca(OH) ₂	lb/hr	0.0	0.0	0.0	0.0	0.0		
Mg(OH) ₂	lb/hr	0.0	0.0	0.0	0.0	0.0		
CaO	lb/hr	0.0	0.0	0.0	0.0	0.0		
MgO	lb/hr	0.0	0.0	0.0	0.0	0.0		
Total Suspended Solids	wt.%, wet	3.2	3.2	0.0	0.0	0.0		
Cl ⁻ Concentration	ppm	8,000	8,000	55	55	3,099		
pH	--	5 to 7	5 to 7	6 to 8	6 to 8	6 to 8		

DOCUMENT NUMBER: 0
0

BABCOCK POWER ENVIRONMENTAL INC.
Mill Creek Unit 3

MATERIAL BALANCE FUEL DATA, BOILER DATA, AND NOTES

Unit Rating	MWg	425
Boiler Heat Input	MBtu/hr	4,208
Fuel Feed Rate	lb/hr	386,068
SO ₂ Inlet Loading	lb SO ₂ /MBtu	6.32
SO ₂ Removal Efficiency	%	98.5
Excess Air	%	20.0
Air Heater Leakage	%	10.0
Oxygen at FGD Inlet	vol.%, dry	6.95
Site Elevation	ft above MSL	460
Ambient Pressure	in H ₂ O	14.45
Ambient Temperature	°F	-23.1 - 105.4
Coal Analysis		
Coal	--	Performance Fuel
Carbon	wt.%, wet	60.00
Hydrogen	wt.%, wet	4.00
Nitrogen	wt.%, wet	1.30
Oxygen	wt.%, wet	5.90
Sulfur	wt.%, wet	3.45
Chlorine	wt.%, wet	0.35
Fluorine	wt.%, wet	0.02
Ash	wt.%, wet	14.00
Moisture	wt.%, wet	11.00
Higher Heating Value (HHV)	BTU/lb	10,900
Limestone Analysis		
Total CaCO ₃	wt.%, dry	Note 4 94.6
Reactive CaCO ₃	%	91.3
Total MgCO ₃	wt.%, dry	2.4
Reactive MgCO ₃	%	
Inerts	wt.%, dry	3.0
Gypsum Quality (at HC Underflow)		
Free Moisture	wt.%	--
CaSO ₄ -2H ₂ O	wt.%, dry	91.79
CaSO ₃ -1/2H ₂ O	wt.%, dry	0.29
CaCO ₃	wt.%, dry	4.21
Inerts	wt.%, dry	1.81
MgCO ₃	wt.%, dry	1.9
Fly Ash	wt.%, dry	
Maximum Chloride Content	ppmvd	17,250
Total Suspended Solids (TSS)	wt.%	
Total Dissolved Solids (TDS)	mg/L	
Average Particle Diameter	microns	

Notes:

1. For stream references see Process Flow Diagram, document number 502718-103000100.
2. Values provided represent time-averaged values and do not necessarily represent equipment capacity or actual continuous operation.
3. Emergency Quench flow normally 0 gpm.
4. Assumes 96.5% CaCO₃ availability on total CaCO₃.

DOCUMENT NUMBER:



BabcockPower
ENVIRONMENTAL

MATERIAL BALANCE WET FLUE GAS DESULFURIZATION

PROJECT NUMBER	100585
CUSTOMER NAME	Louisville Gas & Electric (LG&E)
PROJECT NAME	Mill Creek Unit 3
LOCATION - CITY, STATE	Louisville, KY
DESCRIPTION	CASE: Design - 15,000 ppm Cl and filtrate return via Clearwell Pond
	LOAD: 100% MCR
	FUEL: High Sulfur Bituminous Coal
	SO ₂ Removal Efficiency: 98.5%
	REAGENT: Limestone
	WATER: Clearwell Pond Water and Service Water for ME wash

PREPARED	NAME	_____
	DATE	_____
CHECKED	NAME	_____
	DATE	_____
APPROVED	NAME	_____
	DATE	_____

REVISION HISTORY		PREPARED BY	APPROVED BY
1	_____	_____	_____
2	_____	_____	_____
3	_____	_____	_____
4	_____	_____	_____
5	_____	_____	_____
6	_____	_____	_____
7	_____	_____	_____
8	_____	_____	_____
9	_____	_____	_____
10	_____	_____	_____

DISTRIBUTION LIST	
1	6
2	7
3	8
4	9
5	10

This document and the information, design and material contained and/or illustrated therein (hereinafter "proprietary material"), is the property of BABCOCK POWER Inc., P.O. Box 15040, Worcester, MA 01615-0040, and is submitted, lent and furnished to recipient in strict confidence with the express understanding that the recipient shall not reproduce, copy, loan, dispose of, or disclose to anyone outside recipient's organization, directly or indirectly, or use said proprietary material for any purpose other than that for which it is furnished and submitted. Recipient by receiving said proprietary material agrees not to use the same in any way injurious to the interest of BABCOCK POWER Inc., and agrees to return same upon request. Copyright © BABCOCK POWER Inc., 2011.

DOCUMENT NUMBER:

0
0

BABCOCK POWER ENVIRONMENTAL INC.

Mill Creek Unit 3

MATERIAL BALANCE GAS PATH STREAMS

Stream Number		11	13	15	16			
Notes								
Description		FLUE GAS BEFORE ABSORBER	FLUE GAS AFTER ABSORBER	OXIDATION AIR AFTER BLOWER	OXIDATION AIR AFTER HUMIDIFICATION			
Mass Flow	lb/hr, wet	4,942,271	5,298,376	110,824	115,779			
	lb/hr, dry	4,704,921	4,750,981	105,361	107,276			
Volume Flow	acfm, wet	1,652,827	1,357,532	44,249	17,550			
	scfm, wet	1,079,723	1,202,313	25,305	12,781			
	scfm, dry	995,132	1,007,273	23,358	23,358			
Molecular Weight	lb/lb-mole, wet	29.34	28.25	27.96	27.31			
	lb/lb-mole, dry	30.30	30.23	27.97	28.48			
Density	lb/ft ³	0.050	0.065	0.042	0.110			
Temperature	°F	357	131	327	158			
Pressure	iwg	TBD	TBD	--	--			
	psig	--	--	TBD	TBD			
N ₂	lb/hr	3,517,078	3,562,836	93,341	93,341			
O ₂	lb/hr	340,973	348,775	13,907	13,907			
CO ₂	lb/hr	820,682	838,599	28	28			
SO ₂	lb/hr	24,853	373	0	0			
SO ₃	lb/hr	522	261	0	0			
HCl	lb/hr	609	6	0	0			
HF	lb/hr	77	1	0	0			
H ₂ O	lb/hr	237,349	547,260	3,548	7,360			
Entrained Moisture	lb/hr	0	135	0	1,143			
Fly Ash	lb/hr	128	130	0	0			
SO ₂ Concentration	ppmv, dry @ actual O ₂	2,503	37	0	0			
SO ₃ Concentration	ppmv, dry @ actual O ₂	42	21	0	0			
HCl Concentration	ppmv, dry @ actual O ₂	108	1	0	0			
HF Concentration	ppmv, dry @ actual O ₂	25	0	0	0			
Dust Loading	gr/dscf @ actual O ₂	0.015	0.015	0.000	0.000			

Stream Number								
Notes								
Description								
Mass Flow	lb/hr, wet							
	lb/hr, dry							
Volume Flow	acfm, wet							
	scfm, wet							
	scfm, dry							
Molecular Weight	lb/lb-mole, wet							
	lb/lb-mole, dry							
Density	lb/ft ³							
Temperature	°F							
Pressure	iwg							
	psig							
N ₂	lb/hr							
O ₂	lb/hr							
CO ₂	lb/hr							
SO ₂	lb/hr							
SO ₃	lb/hr							
HCl	lb/hr							
HF	lb/hr							
H ₂ O	lb/hr							
Entrained Moisture	lb/hr							
Fly Ash	lb/hr							
SO ₂ Concentration	ppmv, dry @ actual O ₂							
SO ₃ Concentration	ppmv, dry @ actual O ₂							
HCl Concentration	ppmv, dry @ actual O ₂							
HF Concentration	ppmv, dry @ actual O ₂							
Dust Loading	gr/dscf @ actual O ₂							

DOCUMENT NUMBER:

0

BABCOCK POWER ENVIRONMENTAL INC.

0

Mill Creek Unit 3

MATERIAL BALANCE

LIQUID AND SOLID STREAMS

Stream Number		20	23	30	31	32		
Notes								
Description		TOTAL RECYCLE FLOW	LIMESTONE SLURRY TO ABSORBER	BLEED FROM ABSORBER	PRIMARY HC OVERFLOW	PRIMARY HC UNDERFLOW		
Mass Flow	lb/hr	124,777,477	225,728	559,851	420,960	138,891		
Volume Flow	gpm	220,000	395	987	794	193		
Specific Gravity	--	1.133	1.141	1.133	1.058	1.439		
Density	lb/ft3	70.71	71.26	70.71	66.08	89.79		
Temperature	°F	131	94	131	131	131		
Mass Flow Liquid	lb/hr	106,057,295	180,658	475,849	406,404	69,445		
Cl ⁻	lb/hr	1,590,859	9.9	7,138	6,096	1,042		
SO ₄ ⁻	lb/hr	2,376,118	16.9	10,661	9,105	1,615		
SO ₃ ⁻	lb/hr	109,166	0.0	490	418	74		
Ca ⁺⁺	lb/hr	95,619	25.6	429	366	65		
Mg ⁺⁺	lb/hr	1,094,612	11.7	4,911	4,194	744		
Na ⁺	lb/hr	53,761	10.3	241	206	37		
H ₂ O	lb/hr	100,737,161	180,584	451,979	386,017	65,869		
Mass Flow Solids	lb/hr	18,720,181	45,070	83,994	14,558	69,452		
CaSO ₄ ·2H ₂ O	lb/hr	15,823,880	0.0	70,998	7,101	63,904		
CaCO ₃	lb/hr	1,046,563	40,739	4,696	1,879	2,819		
Inert	lb/hr	1,394,793	1,627	6,258	5,006	1,250		
CaSO ₃ ·1/2H ₂ O	lb/hr	151,649	0.0	680	544	139		
MgCO ₃	lb/hr	303,297	2,704.2	1,360.8	27.7	1,340.3		
Ca(OH) ₂	lb/hr	0	0.0	0.0	0.0	0.0		
Mg(OH) ₂	lb/hr	0	0.0	0.0	0.0	0.0		
CaO	lb/hr	0	0.0	0.0	0.0	0.0		
MgO	lb/hr	0	0.0	0.0	0.0	0.0		
Total Suspended Solids	wt.%, wet	15.0	20.0	15.0	3.5	50.0		
Cl ⁻ Concentration	ppm	15,000	55	15,000	15,000	15,000		
pH	--	5 to 7	> 7	5 to 7	5 to 7	5 to 7		

Stream Number		35	38	44	45	47		
Notes								
Description		CHLORIDE PURGE	HC OVERFLOW TO ABSORBER	SERVICE WATER WATER TO ME WASH	SERVICE WATER WATER TO OXIDATION	RECLAIM WATER RETURN TO ABSORBER		
Mass Flow	lb/hr	33,811	387,149	77,814	4,955	150,557		
Volume Flow	gpm	64	730	156	10.0	297		
Specific Gravity	--	1.058	1.058	0.995	0.995	1.016		
Density	lb/ft3	66.07	66.07	62.08	62.08	63.45		
Temperature	°F	131	131	95	95	131		
Mass Flow Liquid	lb/hr	32,642.0	373,761.6	78,124	4,955	150,549		
Cl ⁻	lb/hr	489.6	5,606.4	4.3	0.3	931		
SO ₄ ⁻	lb/hr	731.3	8,373.8	7.3	0.5	1,391		
SO ₃ ⁻	lb/hr	33.6	384.7	0.0	0.0	64		
Ca ⁺⁺	lb/hr	29.4	337.0	11.1	0.7	68		
Mg ⁺⁺	lb/hr	336.9	3,857.5	5.0	0.3	643		
Na ⁺	lb/hr	16.5	189.5	4.5	0.3	36		
H ₂ O	lb/hr	31,004.6	355,012.7	78,091	4,953	147,416		
Mass Flow Solids	lb/hr	1,169.2	13,388.7	1.2	0.1	8.2		
CaSO ₄ ·2H ₂ O	lb/hr	570.3	6,530.3	0.0	0.0	6.3		
CaCO ₃	lb/hr	150.9	1,728.3	0.0	0.0	0.3		
Inert	lb/hr	402.1	4,603.9	1.2	0.1	1.4		
CaSO ₃ ·1/2H ₂ O	lb/hr	43.7	500.7	0.0	0.0	0.0		
MgCO ₃	lb/hr	2.2	25.4	0.0	0.0	0.1		
Ca(OH) ₂	lb/hr	0.0	0.0	0.0	0.0	0.0		
Mg(OH) ₂	lb/hr	0.0	0.0	0.0	0.0	0.0		
CaO	lb/hr	0.0	0.0	0.0	0.0	0.0		
MgO	lb/hr	0.0	0.0	0.0	0.0	0.0		
Total Suspended Solids	wt.%, wet	3.5	3.5	0.0	0.0	0.0		
Cl ⁻ Concentration	ppm	15,000	15,000	55	55	6,183		
pH	--	5 to 7	5 to 7	6 to 8	6 to 8	6 to 8		

DOCUMENT NUMBER: 0
0

BABCOCK POWER ENVIRONMENTAL INC.
Mill Creek Unit 3

MATERIAL BALANCE FUEL DATA, BOILER DATA, AND NOTES

Unit Rating	MWg	425
Boiler Heat Input	MBtu/hr	4,208
Fuel Feed Rate	lb/hr	386,068
SO ₂ Inlet Loading	lb SO ₂ /MBtu	6.32
SO ₂ Removal Efficiency	%	98.5
Excess Air	%	20.0
Air Heater Leakage	%	10.0
Oxygen at FGD Inlet	vol.%, dry	6.95
Site Elevation	ft above MSL	460
Ambient Pressure	in H ₂ O	14.45
Ambient Temperature	°F	-23.1 - 105.4
Coal Analysis		
Coal	--	Performance Fuel
Carbon	wt.%, wet	60.00
Hydrogen	wt.%, wet	4.00
Nitrogen	wt.%, wet	1.30
Oxygen	wt.%, wet	5.90
Sulfur	wt.%, wet	3.45
Chlorine	wt.%, wet	0.35
Fluorine	wt.%, wet	0.02
Ash	wt.%, wet	14.00
Moisture	wt.%, wet	11.00
Higher Heating Value (HHV)	BTU/lb	10,900
Limestone Analysis		
Total CaCO ₃	wt.%, dry	Note 4 94.6
Reactive CaCO ₃	%	91.3
Total MgCO ₃	wt.%, dry	2.4
Reactive MgCO ₃	%	
Inerts	wt.%, dry	3.0
Gypsum Quality (at HC Underflow)		
Free Moisture	wt.%	--
CaSO ₄ -2H ₂ O	wt.%, dry	91.79
CaSO ₃ -1/2H ₂ O	wt.%, dry	0.29
CaCO ₃	wt.%, dry	4.21
Inerts	wt.%, dry	1.81
MgCO ₃	wt.%, dry	1.9
Fly Ash	wt.%, dry	
Maximum Chloride Content	ppmvd	17,250
Total Suspended Solids (TSS)	wt.%	
Total Dissolved Solids (TDS)	mg/L	
Average Particle Diameter	microns	

Notes:

1. For stream references see Process Flow Diagram, document number 502718-103000100.
2. Values provided represent time-averaged values and do not necessarily represent equipment capacity or actual continuous operation.
3. Emergency Quench flow normally 0 gpm.
4. Assumes 96.5% CaCO₃ availability on total CaCO₃.

DOCUMENT NUMBER:



BabcockPower
ENVIRONMENTAL

MATERIAL BALANCE WET FLUE GAS DESULFURIZATION

PROJECT NUMBER	100585
CUSTOMER NAME	Louisville Gas & Electric (LG&E)
PROJECT NAME	Mill Creek Unit 3
LOCATION - CITY, STATE	Louisville, KY
DESCRIPTION	CASE: Design - 50,000 ppm Cl - filtrate return via Clearwell Pond
	LOAD: 100% MCR
	FUEL: High Sulfur Bituminous Coal
	SO ₂ Removal Efficiency: 98.5%
	REAGENT: Limestone
	WATER: Clearwell Pond Water & Service Water (ME wash)

PREPARED	NAME	_____
	DATE	_____
CHECKED	NAME	_____
	DATE	_____
APPROVED	NAME	_____
	DATE	_____

REVISION HISTORY		PREPARED BY	APPROVED BY
1	_____	_____	_____
2	_____	_____	_____
3	_____	_____	_____
4	_____	_____	_____
5	_____	_____	_____
6	_____	_____	_____
7	_____	_____	_____
8	_____	_____	_____
9	_____	_____	_____
10	_____	_____	_____

DISTRIBUTION LIST	
1	6
2	7
3	8
4	9
5	10

This document and the information, design and material contained and/or illustrated therein (hereinafter "proprietary material"), is the property of BABCOCK POWER Inc., P.O. Box 15040, Worcester, MA 01615-0040, and is submitted, lent and furnished to recipient in strict confidence with the express understanding that the recipient shall not reproduce, copy, loan, dispose of, or disclose to anyone outside recipient's organization, directly or indirectly, or use said proprietary material for any purpose other than that for which it is furnished and submitted. Recipient by receiving said proprietary material agrees not to use the same in any way injurious to the interest or BABCOCK POWER Inc., and agrees to return same upon request. Copyright © BABCOCK POWER Inc., 2011.

DOCUMENT NUMBER:

0
0

BABCOCK POWER ENVIRONMENTAL INC.

Mill Creek Unit 3

MATERIAL BALANCE GAS PATH STREAMS

Stream Number		11	13	15	16			
Notes								
Description		FLUE GAS BEFORE ABSORBER	FLUE GAS AFTER ABSORBER	OXIDATION AIR AFTER BLOWER	OXIDATION AIR AFTER HUMIDIFICATION			
Mass Flow	lb/hr, wet	4,942,271	5,298,824	110,824	115,779			
	lb/hr, dry	4,704,921	4,750,981	105,361	107,276			
Volume Flow	acfm, wet	1,652,827	1,357,712	44,249	17,550			
	scfm, wet	1,079,723	1,202,473	25,305	12,781			
	scfm, dry	995,132	1,007,273	23,358	23,358			
Molecular Weight	lb/lb-mole, wet	29.34	28.25	27.96	27.31			
	lb/lb-mole, dry	30.30	30.23	27.97	28.48			
Density	lb/ft ³	0.050	0.065	0.042	0.110			
Temperature	°F	357	131	327	158			
Pressure	iwg	TBD	TBD	--	--			
	psig	--	--	TBD	TBD			
N ₂	lb/hr	3,517,078	3,562,767	93,341	93,341			
O ₂	lb/hr	340,973	348,795	13,907	13,907			
CO ₂	lb/hr	820,682	838,648	28	28			
SO ₂	lb/hr	24,853	373	0	0			
SO ₃	lb/hr	522	261	0	0			
HCl	lb/hr	609	6	0	0			
HF	lb/hr	77	1	0	0			
H ₂ O	lb/hr	237,349	547,708	3,548	7,360			
Entrained Moisture	lb/hr	0	135	0	1,143			
Fly Ash	lb/hr	128	130	0	0			
SO ₂ Concentration	ppmv, dry @ actual O ₂	2,503	37	0	0			
SO ₃ Concentration	ppmv, dry @ actual O ₂	42	21	0	0			
HCl Concentration	ppmv, dry @ actual O ₂	108	1	0	0			
HF Concentration	ppmv, dry @ actual O ₂	25	0	0	0			
Dust Loading	gr/dscf @ actual O ₂	0.015	0.015	0.000	0.000			

Stream Number								
Notes								
Description								
Mass Flow	lb/hr, wet							
	lb/hr, dry							
Volume Flow	acfm, wet							
	scfm, wet							
	scfm, dry							
Molecular Weight	lb/lb-mole, wet							
	lb/lb-mole, dry							
Density	lb/ft ³							
Temperature	°F							
Pressure	iwg							
	psig							
N ₂	lb/hr							
O ₂	lb/hr							
CO ₂	lb/hr							
SO ₂	lb/hr							
SO ₃	lb/hr							
HCl	lb/hr							
HF	lb/hr							
H ₂ O	lb/hr							
Entrained Moisture	lb/hr							
Fly Ash	lb/hr							
SO ₂ Concentration	ppmv, dry @ actual O ₂							
SO ₃ Concentration	ppmv, dry @ actual O ₂							
HCl Concentration	ppmv, dry @ actual O ₂							
HF Concentration	ppmv, dry @ actual O ₂							
Dust Loading	gr/dscf @ actual O ₂							

DOCUMENT NUMBER:

0

BABCOCK POWER ENVIRONMENTAL INC.

0

Mill Creek Unit 3

MATERIAL BALANCE

LIQUID AND SOLID STREAMS

Stream Number		20	23	30	31	32		
Notes								
Description		TOTAL RECYCLE FLOW	LIMESTONE SLURRY TO ABSORBER	BLEED FROM ABSORBER	PRIMARY HC OVERFLOW	PRIMARY HC UNDERFLOW		
Mass Flow	lb/hr	139,263,429	211,823	577,926	437,101	141,069		
Volume Flow	gpm	220,000	367	913	733	181		
Specific Gravity	--	1.264	1.152	1.264	1.191	1.560		
Density	lb/ft3	78.92	71.92	78.91	74.34	97.43		
Temperature	°F	131	94	131	131	131		
Mass Flow Liquid	lb/hr	118,363,340	166,753	491,194	420,910	70,534		
Cl ⁻	lb/hr	5,915,421	9.2	24,548	21,042	3,526		
SO ₄ ⁻	lb/hr	7,902,605	15.6	32,795	28,086	5,503		
SO ₃ ⁻	lb/hr	414,952	0.0	1,722	1,475	289		
Ca ⁺⁺	lb/hr	156,643	23.7	650	557	109		
Mg ⁺⁺	lb/hr	3,969,002	10.8	16,471	14,110	2,765		
Na ⁺	lb/hr	180,594	9.5	749	642	126		
H ₂ O	lb/hr	99,824,123	166,685	414,258	354,998	58,217		
Mass Flow Solids	lb/hr	20,900,089	45,069	86,733	16,191	70,541		
CaSO ₄ ·2H ₂ O	lb/hr	17,273,923	0.0	71,685	7,168	64,504		
CaCO ₃	lb/hr	1,174,585	40,743	4,874	1,954	2,934		
Inert	lb/hr	1,920,718	1,623	7,971	6,369	1,594		
CaSO ₃ ·1/2H ₂ O	lb/hr	202,731	0.0	841	672	169		
MgCO ₃	lb/hr	328,131	2,704.2	1,361.7	27.5	1,340.2		
Ca(OH) ₂	lb/hr	0	0.0	0.0	0.0	0.0		
Mg(OH) ₂	lb/hr	0	0.0	0.0	0.0	0.0		
CaO	lb/hr	0	0.0	0.0	0.0	0.0		
MgO	lb/hr	0	0.0	0.0	0.0	0.0		
Total Suspended Solids	wt.%, wet	15.0	21.3	15.0	3.7	50.0		
Cl ⁻ Concentration	ppm	49,977	55	49,977	49,992	49,992		
pH	--	5 to 7	> 7	5 to 7	5 to 7	5 to 7		

Stream Number		35	38	44	45	47		
Notes								
Description		CHLORIDE PURGE	HC OVERFLOW TO ABSORBER	SERVICE WATER WATER TO ME WASH	SERVICE WATER WATER TO OXIDATION	CLEARWELL POND RETURN TO ABSORBER		
Mass Flow	lb/hr	4,819	432,282	77,814	4,955	144,689		
Volume Flow	gpm	8	725	156	10.0	272		
Specific Gravity	--	1.191	1.191	0.995	0.995	1.082		
Density	lb/ft3	74.36	74.36	62.08	62.08	67.54		
Temperature	°F	131	131	95	95	131		
Mass Flow Liquid	lb/hr	4,640.3	416,269.7	78,112	4,955	144,681		
Cl ⁻	lb/hr	232.0	20,810.1	4.3	0.3	3,139		
SO ₄ ⁻	lb/hr	309.6	27,776.6	7.3	0.5	4,191		
SO ₃ ⁻	lb/hr	16.3	1,458.5	0.0	0.0	220		
Ca ⁺⁺	lb/hr	6.1	551.3	11.1	0.7	95		
Mg ⁺⁺	lb/hr	155.6	13,954.1	5.0	0.3	2,107		
Na ⁺	lb/hr	7.1	634.9	4.5	0.3	100		
H ₂ O	lb/hr	3,913.6	351,084.2	78,080	4,953	134,829		
Mass Flow Solids	lb/hr	178.6	16,012.4	1.0	0.1	8.2		
CaSO ₄ ·2H ₂ O	lb/hr	79.1	7,088.7	0.0	0.0	6.5		
CaCO ₃	lb/hr	21.6	1,932.7	0.0	0.0	0.3		
Inert	lb/hr	70.3	6,299.3	1.0	0.1	1.3		
CaSO ₃ ·1/2H ₂ O	lb/hr	7.4	664.5	0.0	0.0	0.0		
MgCO ₃	lb/hr	0.3	27.2	0.0	0.0	0.1		
Ca(OH) ₂	lb/hr	0.0	0.0	0.0	0.0	0.0		
Mg(OH) ₂	lb/hr	0.0	0.0	0.0	0.0	0.0		
CaO	lb/hr	0.0	0.0	0.0	0.0	0.0		
MgO	lb/hr	0.0	0.0	0.0	0.0	0.0		
Total Suspended Solids	wt.%, wet	3.7	3.7	0.0	0.0	0.0		
Cl ⁻ Concentration	ppm	49,992	49,992	55	55	21,695		
pH	--	5 to 7	5 to 7	6 to 8	6 to 8	6 to 8		

DOCUMENT NUMBER: 0
0

BABCOCK POWER ENVIRONMENTAL INC.
Mill Creek Unit 3

MATERIAL BALANCE FUEL DATA, BOILER DATA, AND NOTES

Unit Rating	MWg	425
Boiler Heat Input	MBtu/hr	4,208
Fuel Feed Rate	lb/hr	386,068
SO ₂ Inlet Loading	lb SO ₂ /MBtu	6.32
SO ₂ Removal Efficiency	%	98.5
Excess Air	%	20.0
Air Heater Leakage	%	10.0
Oxygen at FGD Inlet	vol.%, dry	6.95
Site Elevation	ft above MSL	460
Ambient Pressure	in H ₂ O	14.45
Ambient Temperature	°F	-23.1 - 105.4
Coal Analysis		
Coal	--	Performance Fuel
Carbon	wt.%, wet	60.00
Hydrogen	wt.%, wet	4.00
Nitrogen	wt.%, wet	1.30
Oxygen	wt.%, wet	5.90
Sulfur	wt.%, wet	3.45
Chlorine	wt.%, wet	0.35
Fluorine	wt.%, wet	0.02
Ash	wt.%, wet	14.00
Moisture	wt.%, wet	11.00
Higher Heating Value (HHV)	BTU/lb	10,900
Limestone Analysis		
Total CaCO ₃	wt.%, dry	Note 4 94.6
Reactive CaCO ₃	%	91.3
Total MgCO ₃	wt.%, dry	2.4
Reactive MgCO ₃	%	
Inerts	wt.%, dry	3.0
Gypsum Quality (at HC Underflow)		
Free Moisture	wt.%	--
CaSO ₄ -2H ₂ O	wt.%, dry	91.79
CaSO ₃ -1/2H ₂ O	wt.%, dry	0.29
CaCO ₃	wt.%, dry	4.21
Inerts	wt.%, dry	1.81
MgCO ₃	wt.%, dry	1.9
Fly Ash	wt.%, dry	
Maximum Chloride Content	ppmvd	17,250
Total Suspended Solids (TSS)	wt.%	
Total Dissolved Solids (TDS)	mg/L	
Average Particle Diameter	microns	

Notes:

1. For stream references see Process Flow Diagram, document number 502718-103000100.
2. Values provided represent time-averaged values and do not necessarily represent equipment capacity or actual continuous operation.
3. Emergency Quench flow normally 0 gpm.
4. Assumes 96.5% CaCO₃ availability on total CaCO₃.

DESIGN BASIS



Project Number:	100585
Revision Number:	Rev. 0
Customer Name:	LG&E Energy
Project Name:	Mill Creek Unit 3
Location, City, State	Kosmodale, KY
Description	WFGD Upgrade
Report Title (shown on printed sheets)	

Email changes to		
Prepared	Name	Suzette Puski
Prepared	Date	11/13/11
Checked	Name	
Checked	Date	
Customer Signed	Name	
Customer Signed	Date	
Remarks:		

This technical data is proprietary technology of BPEI, Inc. P.O. Box 15040, Worcester, MA 01615-0040, and is submitted, lent and furnished to recipient in strict confidence with the express understanding that the recipient shall not reproduce, copy, loan, dispose of or disclose to anyone outside recipient's organization, directly or indirectly, or use said proprietary material for any purpose other than that for which it is furnished and submitted. Recipient by receiving said proprietary material agrees not to use the same in any way injurious to the interest of BPEI, Inc., and agrees to return same upon request.

Copyright BPEI, Inc. 2011.




Mill Creek Unit 3
Rev. 0

FGD Design Basis Spreadsheet

Scope of Supply		
Plant Name:		
Plant Location		
	U3 No Change to Spray Header Location	U3 High Removal
Flue Gas Path		
Equipment for Partical Removal		
Equipment for Draft System		
Inlet Duct Modifications	x	x
Equipment for SO2 Removal		
Install Wall Rings on Spray Levels 2 and 3	8 Wall Rings	8 Wall Rings
Install Up/Down Interior Spray Nozzles	128	336
Install Up/Down Interior Wall Ring Nozzles	160	288
Install Double-Down Interior Spray Nozzles	128	112
Install Double-Down Wall Ring Spray Nozzles	160	96
Replace Recycle Pumps		
Replace Recycle Pump Piping		
Replace Recycle Pump Gear Boxes		8 Pumps
Add Agitators and Air Lances	10	10
Equipment for SO3 Removal		
Equipment for Hg Removal		
Equipment for NOx Removal		
Equipment for Mist Removal		
Replace ME Section w/ DV210		x
other		
Waste Water Treatment		
Utilities		
Reagent		
Equipment for Reagent Unloading		
Equipment for Reagent Storage		
Equipment for Reagent Day Storage		
Equipment for Reagent Slurry Preparation		
Increase Limestone Grind		May be Required
Organic Acid		
Equipment for Organic Acid System		
Add organic feed system to Units 1 and 2		
Byproduct		
Equipment for Byproduct Treatment		
Equipment for Byproduct Storage		
Equipment for Byproduct Loading		
Fly Ash		
Equipment for Flyash Treatment		
Equipment for Flyash Storage		
Equipment for Flyash Loading		
Balance of Plant		
Water Supply		
Service Air Supply		
Instrument Air Supply		
Cooling Water Supply		
Process Control		
Evaluate revising control logic for SO2 removal	x	x
Electrical Equipment		
Structural Steel		
Civil		
Construction		
Process Equipment		
Balance of Plant Equipment		
Process Control incl. Wiring		
Electrical Equipment incl. Wiring		
Structural Steel		
Civil		
Commissioning		Yes
Performance Test		No



Plant Data Sheet	Units	DESIGN
Plant Name:		Mill Creek Unit 3
Plant Location		Kosmodale, KY
Site Conditions		
Seismic Zone		(Av/Aa) 0.09/0.07
Design Ambient Temp	°F	68
Maximum Summer Ambient Temp	°F	105.4
Minimum Winter Ambient Temp	°F	-23.1
Indoor Temperature Design / Range	°F	36-76
Plant Elevation @ Grade	ft	460
Elevation @ Absorber Inlet	ft above TOC	28
Atmospheric Pr. @ Absorber Inlet Elevation	psia	14.44
Absolute Humidity Average	%	60
Average Rainfall	inches/year	44.5
Wind Speed CRM 780 section 1611.0	MPH	90
Snow Load CMR 780 Section 1610.0	lb/sf	15
Earthquake Loads CMR 780 Section 1612.0		
FGD Operation		
Mode	Part/Continuous	Continuous
Months of FGD operation/yr - Design	Mon/yr	12
Months of FGD operation/yr - Future	Mon/yr	12
Number of Boilers served by one Scrubber	#	Unit has a dedicated 4 module absorber system
Bypass Operation required	Yes / No	No Bypass Allowed
Equipment Installation Indoor/Outdoor		Indoor

 BabcockPower ENVIRONMENTAL	FGD Design Basis Spreadsheet	Mill Creek Unit 3 Rev. 0
Boiler Data Sheet	Units	
		Unit 3
LOAD	% MCR	100
Nominal Rating	MW, Gross	410
	MW, Net	386
Boiler Manufacturer	-	Babcock & Wilcox
Fuel Fired	Coal/Gas/Oil	Coal
Firing Method	Dry Bot/Wet Bot/Cyclone	Opposed Wall Fired Boiler (5x4 high) w/ LNB
MCR Steam Flow (Design)	pph	3,144,000
Boiler Type	Balanced Draft/Pressurized	Balanced Draft
Plant Capacity Factor	Percent of Year	74.9 Gross/ 73.6 Net
Hours of operation per year	Hours	in 2000 7447 hrs
Number of Cold Starts per year	Target/Actual	2 actual
Number of Hot Restarts per year	Target / Actual	22 actual
Ignition Fuel Fired	Oil/Gas	Oil
Ignition Fuel Fired	Hours/Year	800,000 gal
Minimum Load for FGD Operation	MWnet	193 MW net
Flue Gas Recirculation	Y/N	N
SCR		
SCR Reactor - Number Installed	-	2
Catalyst Type		Hitachi Plate
NOx inlet / outlet	lbs/Mbtu	0.347 / 0.035
NH3 Slip	ppmdv @ ref O2	< 2.0 @ the End of Life
Air Heater		
Air Heater - Number Installed	-	2
Air Heater Type	Rotary/Tubualr	Ljungstrom Rotary
Air Heater Orientation	V-Shaft or H-S	V-Shaft
Will Air Heater be changed?	Y/N & to what?	N
Air Heater Surface configuration	Model Numbers & Materials	29-VI-54
Air Heater Cleaning Device	-	Steam Soot Blowers
Air Heater Leakage	Percent	8 @ as-found condition Baseline Test
ESP		
ESP's - Number Installed	Number	2
ESP Info - Configuration	Single layer or Stacked	TBD by LG&E
ESP Info - Location	Cold or Hot	Cold
ESP Dust Loading @ ESP Temp	grains/ACF @F	3.375 @ 300 °F
Dust Loading @ Eco. Out Temp	grains/ACF @F	2.294 @ 64 8°F
ESP Info - Outlet Dust Loading	grains/ACF @F	TBD by LG& E
ESP Efficiency	%	TBD by LG&E
WFGD		
WFGD - Original Supplier	Name	American Filter
WFGD - Number Absorbers Operating / Installed	Number	4 / 4
WFGD Info - Type	Single Loop or Double Loop	Single
WFGD Info - Spray Configuration	Co-Current or Counter Current	Counter Current (Co-Current on Level 2)
WFGD Info - Spray Level Configuration	Operating + Spare	4+0 + Tray
WFGD Info - Reagent	Lime or Limestone	Limestone
WFGD Info - Original Design SO2 Loading	lbs/Mbtu	6.3
WFGD Info - SO2 Removal Efficiency	%	Phase 1: 96, Phase 2: 98+
Other		
Ash Reinjection	Yes or No	No
Draft System		
FD Fan, Existing	Number	2 / American Standard (595 rpm @ 110°F)
Design Pressure	IWG	
Fan HP	HP	
ID Fan, Existing	Number	2 / American Standard (834,950 cfm @ 300°F)
Design Pressure	IWG	45
Fan HP	HP	
ID Booster Fan, Existing	Number	N/A
Design Pressure	IWG	N/A
Booster Fan HP	HP	N/A




FGD Design Basis Spreadsheet

LG&E Mill Creek Rev. 0

FGD Load Data Sheet		Units			
Load Name		Unit 4	Unit 3	Unit 3	
Load	MW	525	425	425	
Fuel Flow Rate	lb/hr				
Firing Rate	Gross10 ⁶ BTU/Hr				
Excess Air	%				
In-Leakage	%				
Flue Gas Conditions @ Inlet Scope of Supply			SCR Test	Ratio to U4 Design Basis	
Flow Basis	per Absorber	1	1 of 4	1 of 4	
Flue Gas Flow Rate	lbs/h wet	6,126,411	1,418,869	1,239,869	
Flue Gas Flow Rate	lbs/h dry	5,838,557	1,356,591	1,181,613	
Flue Gas Flow Rate	scfm wet	1,337,090	289,144	270,602	
Flue Gas Flow Rate	scfm dry	1,234,489	268,459	249,837	
Flue Gas Flow Rate	acfm	2,046,801	463,259	414,234	
Flue Gas Temperature	°F	357	313	357.0	
Flue Gas Pressure	I.W.G.	11	14.44	11.0	
Flue Gas O2	% vol, dry	6.9	7.9	6.9	
Flue Gas CO2	% vol, dry	12.1	11.0	12.1	
Flue Gas H2O	% vol wet	7.7	7.1	7.7	
Flue Gas reference O2	% vol dry	6.0	6.0	6.0	
Flue Gas SO2 *)	ppmdv @ act O2 / lbs/MBTu	2,630/6.33	2,395 / 6.3	2,630/6.33	
Flue Gas SO3 *)	ppmdv @ act O2 / lbs/MBTu	44	8	44	
Flue Gas HCl *)	ppmdv @ act O2 / lbs/MBTu	235	44	235	
Flue Gas HF*)	ppmdv @ act O2 / lbs/MBTu	25	9	25	
Flue Gas NOx *)	ppmdv @ act O2 / lbs/MBTu				
Flue Gas NH3 *)	ppmdv @ act O2 / lbs/MBTu				
Flue Gas Dust *)	grains/ dcfm lbs/MBTU	0.015/0.03	0.07 / 0.41	0.015/0.03	
Flue Gas Hg *)	ppmdv @ act O2 / lbs/MBTu				
Flue Gas Cd *)	ppmdv @ act O2 / lbs/MBTu				
Flue Gas Heavy Metals *)	ppmdv @ act O2 / lbs/MBTu				
*) Concentration range is independent of the boiler load					
Flue Gas Conditions @ outlet Scope of Supply expected values					
Flue Gas Flow Rate	lbs/h wet	10,356,857	1,518,574	1,467,221	
Flue Gas Flow Rate	lbs/h dry	8,704,210	1,276,255	1,233,096	
Flue Gas Flow Rate	scfm wet	2,184,799	320,346	309,513	
Flue Gas Flow Rate	scfm dry	1,861,975	273,012	263,780	
Flue Gas Flow Rate	acfm	2,624,304	384,789	371,776	
Flue Gas Temperature	°F	128	128	128	
Flue Gas Pressure	I.W.G.	14.62			
Flue Gas O2	% vol wet	11.1	11.1	11.1	
Flue Gas CO2	% vol wet	8	8	8	
Flue Gas H2O	% vol wet	14.8	14.8	14.8	
Flue Gas SO2 *)	ppmdv @ act O2 / lbs/MBTu	52 / 0.14	47 / 0.13	47 / 0.13	
Flue Gas SO3 *)	ppmdv @ act O2 / lbs/MBTu	8	2	2	
Flue Gas HCl *)	ppmdv @ act O2 / lbs/MBTu	0	0	0	
Flue Gas HF*)	ppmdv @ act O2 / lbs/MBTu	0	0	0	
Flue Gas NOx *)	ppmdv @ act O2 / lbs/MBTu				
Flue Gas Dust *)	grains/ dcfm lbs/MBTU	0.02 / 0.12	0.02 / 0.12	0.02 / 0.12	
Flue Gas Hg *)	ppmdv @ act O2 / lbs/MBTu				
Flue Gas Cd *)	ppmdv @ act O2 / lbs/MBTu				
Flue Gas Heavy Metals *)	ppmdv @ act O2 / lbs/MBTu				
*) Concentration range is independent of the boiler load					



Coal & Reagent Data Sheet	Units	Unit 3	Unit 3	Unit 3		
Design Coal Name	Must be filled in					
Coal Source:	Coal Mine	2009	Original	Revised		
Date Sample Taken:	Date	Average	Design	Design		
Coal Ultimate Analysis	As Received					
Carbon (C)	Wt%	61.61	61.20	60.00		
Hydrogen (H)	Wt%	4.22	4.28	4.00		
Oxygen (O ₂)	Wt%	7.01	6.89	5.90		
Nitrogen (N ₂)	Wt%	1.28	1.27	1.30		
Sulfur (S)	Wt%	3.02	3.36	3.45		
Chlorine (Cl)	Wt%	0.06	0.16	0.35		
Fluorine (F)	Wt%	0.01				
Moisture (Water H ₂ O)	Wt%	11.43	11.00	11.00		
Ash	Wt%	11.36	12.00	14.00		
Total	Wt%	100.00	100.16	100.00		
Wt. % Volatile	Wt%	35.68				
Wt % Fixed Carbon	Wt%	41.54				
Higher Heating Value	Btu/lb, As Recvd	11,115	11,200	10,900		
Reagent Name:						
Reagent Source:						
Date Sample Taken:						
Reagent Analysis						
CaCO ₃	wt. %					
reactive CaCO ₃	wt. %					
CaO	wt. %					
Ca(OH) ₂	wt. %					
Fe ₂ O ₃	wt. %					
Al ₂ O ₃	wt. %					
SiO ₂	wt. %					
MgCO ₃	wt. %					
MgO	wt. %					
Mg(OH) ₂	wt. %					
Chlorine (Cl)	ppm					
Fluorine (F)	ppm					
Moisture	wt%					
Inert	wt%					

	FGD Design Basis Spreadsheet	Mill Creek Unit 3 Rev. 0		
Process Water Data Sheet	Units	Design	Min	Max
Mist Eliminator Wash Water Analysis				
pH				
Conductivity	mS/m			
Total hardness	mg/l			
Carbonate hardness	mg/l	526		
Temperature	°F			
Suspended solids	mg/l			
Calcium as CaCO ₃	mg/l	142		
Magnesium as CaCO ₃	mg/l	64		
Sodium as CaCO ₃	mg/l	57		
Chloride as CaCO ₃	mg/l	55		
Sulphate as CaCO ₃	mg/l	94		
Sulphite as CaCO ₃	mg/l			
Make-Up Water Analysis				
pH				
Conductivity	mS/m			
Total hardness	mg/l			
Carbonate hardness	mg/l	526		
Temperature	°F			
Suspended solids	mg/l			
Calcium as CaCO ₃	mg/l	142		
Magnesium as CaCO ₃	mg/l	64		
Sodium as CaCO ₃	mg/l	57		
Chloride as CaCO ₃	mg/l	55		
Sulphate as CaCO ₃	mg/l	94		
Sulphite as CaCO ₃	mg/l			
Reclaim Water Analysis				
pH				
Conductivity	mS/m			
Total hardness	mg/l			
Carbonate hardness	mg/l	526		
Temperature	°F			
Suspended solids	mg/l			
Calcium as CaCO ₃	mg/l	142		
Magnesium as CaCO ₃	mg/l	64		
Sodium as CaCO ₃	mg/l	57		
Chloride as CaCO ₃	mg/l	55		
Sulphate as CaCO ₃	mg/l	94		
Sulphite as CaCO ₃	mg/l			
Service Water Analysis				
pH		7.70		
Conductivity	mS/m			
Total hardness	mg/l			
Carbonate hardness	mg/l	444		
Temperature	°F			
Suspended solids	mg/l	13		
Calcium as CaCO ₃	mg/l	119		
Magnesium as CaCO ₃	mg/l	55		
Sodium as CaCO ₃	mg/l	48		
Chloride as CaCO ₃	mg/l	48		
Sulphate as CaCO ₃	mg/l	76		
Sulphite as CaCO ₃	mg/l			




Gypsum Slurry Data Sheet	Units	U3 No Change to Spray Header Location	U3 High Removal
Recycle Slurry Analysis			
Mass Flow Rate, per pump	lb/hr	15,000,000	15,000,000
Volume Flow rate, per pump	gpm	27,500	27,500
Estimated TDH			
Spray Level 1	ft, H2O	56.4	59.7
Spray Level 2	ft, H2O	61.2	64.7
Spray Level 3	ft, H2O	64.6	69.7
Spray Level 4	ft, H2O	68.0	74.7
Specific Gravity		1.08-1.11	1.08-1.11
Density	lb/ft ³	66.8-69.3	66.8-69.3
Temperature	°F	125-135	125-135
pH		5 to 6	5 to 6
Chloride as Cl-	mg/l	5,000	5,000
Viscosity	cp	7.00	7.00
Solids Content	wt. %	14-18	14-18
Solids Stream			
Gypsum	wt.% dry	85-95	85-95
Limestone	wt.% dry	1-3	1-3
Inert	wt.% dry	5-15	5-15
Special Notes:		Compressed air is injected in the reaction tank to complete oxidation reaction Pump TDH calculations are preliminary for cost estimate purposes only	




WATER FLOW SCHEMATIC

Schematic of Water Flow – Filtrate Returns to WFGD System



Schematic of Water Flow – Filtrate Does Not Returns to WFGD System



BUDGET ENGINEERING AND PROCUREMENT ESTIMATE



BabcockPower
ENVIRONMENTAL

LG&E-KU Services Company
Contract No. 843037
Mill Creek Unit 4 WFGD Performance Upgrade Analysis

Budget Engineering and Procurement Estimate

December 2, 2011

<u>Description</u>	<u>Labor</u>	<u>Materials</u>	<u>Total</u>
Case 1: Alloy 27-7MO Unit 4 (12,500 ppm chlorides)	\$7,832,901	\$24,688,994	\$32,521,895
Case 2: Alloy C-276 Unit 4 (50,000 ppm chlorides)	\$7,832,901	\$27,369,596	\$35,202,498

Note: The estimate for the Mill Creek Unit 4 WFGD Performance Upgrade Analysis is a ROM (rough order of magnitude) estimate. The accuracy is based on +25% to -10%. The pricing is based on current 2011 dollars with no escalation.

The scope of pricing for the Mill Creek Unit 4 WFGD Performance Upgrade Analysis is limited to the Engineering and Procurement of the retrofit improvements. There are no allowances for BOP work, construction or maintenance upgrades to the WFGD structure.



11/30/2011

LG&E - KU Services Company
Mill Creek Unit 3 gas to Unit 4 WFGD Systems Upgrade
ROM Price Estimate Revision 0
Alloy 27-7MO

Materials / Subcontracts	Labor Hours	Qty's	Units	Total Sell Price
Absorber Recycle Pumps				\$2,584,891
Recycle Pumps		8	pcs	
Recycle Pumps - Special Tools		1	lot	
Recycle Pumps - First Fill Lubricants		8	pcs	
Recycle Pumps - NPSH,Noise, Vibration Test		1	lot	
Recycle Pumps - Performance Test		1	lot	
Recycle Pumps - MFG Field Service		5	days	
Recycle Pumps - Exp.Jt. Non- Matalic @ recycle suction		8	pcs	
Recycle Pumps - Exp.Jt. Non- Matalic @ recycle discharge		8	pcs	
Absorber Vessel				\$6,573,740
Absorber Free Issue Plate - 32,000 sq ft plate (4) units		336,000	lbs	
Absorber Fabrication		336,000	lbs	
Awning - Free Issue Materials		2,100	lbs	
Awning - Fabrication		2,100	lbs	
Imtec Doors		20	pcs	
Absorber Vessel Wall Rings				\$428,081
Wall Rings Support Clips		600	lbs	
Wall Rings		8	pcs	
Wall Rings - freight		1	lot	
Wall Rings Support Clips - freight		1	lot	
Agitators & Sump Tank				\$2,748,186
Absorber Agitators		10	pcs	
Absorber Agitators - Model Study Test		1	lot	
Absorber Agitators - 5% LOC / Surety Guarantee		1	lot	
Absorber Agitators - Mfg Field Service		5	days	
Absorber Agitators - freight		10	pcs	
Agitator Metal Boxes for Mounting - 94 sq ft x 10 pcs = 940 sq ft		10	pcs	
Absorber Sump Pumps		2	pcs	
Absorber Sump Pumps Driver		2	pcs	
Absorber Sump Agitators		1	pcs	
Sump Covers and Bridges		2	ea	
Ox Air Nozzles 10 pca 10"/ea approximately 6' lg per ea.		60	lf	
Supply FRP Nozzles for Roof of Tank 60" x 4 pcs		4	pcs	
Stebbins - Engineering for Agitator Boxes		10	pcs	
Stebbins - Engineering to Evaluate the Tile Lined Tank		1	lot	
Stebbins - Engineering to Design a New Concrete Roof		1	lot	
Stebbins - Material Supply New Concrete Roof - prefab		6400	sqft	
Stebbins - Engineering for Nozzles 12 pcs 10"/ea		12	pcs	
Stebbins - Engineer large roof nozzles 60" times 4 pcs		4	pcs	

11/30/2011

LG&E - KU Services Company
Mill Creek Unit 3 gas to Unit 4 WFGD Systems Upgrade
ROM Price Estimate Revision 0
Alloy 27-7MO

Materials / Subcontracts	Labor Hours	Qty's	Units	Total Sell Price
Internal & External Recycle Pipe				\$5,474,463
Internal Spray Headers - FRP		16	pcs	
Internal Spray Headers - Recycle Spray Nozzles - 4"		832	pcs	
Internal Spray Headers - Flanges 4" - 150#		832	pcs	
Internal Spray Headers - Alloy Trusses		16	pcs	
Internal Spray Headers - Freight		1	lot	
External Recycle Piping		2000	lf	
External Recycle Piping - Stress Analysis		1	lot	
External Recycle Piping - Bolt & Gasket Sets		1	lot	
External Recycle Piping - Anchors, Hangers & Supports		1	lot	
External Recycle Piping - Freight		1	lot	
External Recycle Piping - Temp Strainers		3	pcs	
External Recycle Piping - Exp. Jts		32	pcs	
External Recycle Piping - Freight		1	lot	
Recycle Valves - Suction		8	pcs	
Recycle Valves - Discharge		8	pcs	
Recycle Valves - Mfg Field Service		1	pcs	
Recycle Valves - Hydraulic Unit		1	pcs	
Recycle Valves - Freight		1	lot	
Bleed Pump System				\$106,639
Slurry Bleed Pumps		2	pcs	
Slurry Bleed Pumps Driver		2	pcs	
Slurry Bleed Pump - Expansion Joint		4	pcs	
Structural Steel				\$0
Sump CS Plate		Not Incl.		
Grating - Replacement		Not Incl.		
Cover Plating Steel		Not Incl.		
Railing		Not Incl.		
Ladders		Not Incl.		
Safety Gates		Not Incl.		
Valves & Piping				\$2,277,636
Replace all Manual Valves		1	lot	
Replace all Actuated Valves		1	lot	
Piping Specialties		1	lot	
Large Bore Piping w/Hanger & Supports		1	lot	
Misc. Hangers		1	lot	
Nuts, Bolts & Gaskets CS		1	lot	
Nuts, Bolts & Gaskets Alloy		1	lot	
Oxidation Air Lances		10	pcs	
Oxidation Air Lances - boltups		10	pcs	
Oxidation Air Lances - Structural Steel Supports		10	pcs	
Reactor to Sump FRP Piping		4	pcs	
Sump Overflow FRP Piping		2	pcs	
Sump Vent Piping Connected to the Ductwork		2	pcs	
Bleed Piping		1	lot	
Knife Gate Valves - Hydraulic Piping		1	lot	
Emergency Quench Piping Header (Internal to Duct) Alloy		1	lot	
Emergency Quench - Nozzles		70	pcs	
Emergency Quench - Expansion Joints		6	pcs	

LG&E - KU Services Company
Mill Creek Unit 3 gas to Unit 4 WFGD Systems Upgrade
ROM Price Estimate Revision 0

Alloy 27-7MO

Materials / Subcontracts	Labor Hours	Qty's	Units	Total Sell Price
Instruments & Controls				\$504,560
Analyzer - Sox			1 lot	
Instruments & Controls			1 lot	
Misc Tubing, Fittings & Hangers			1 lot	
Performance Test				\$222,006
Physical Flow Model			1 lot	
Performance Testing			1 lot	
Subcontractors				\$261,184
BOP Electrical Design			1 lot	
BOP Instrument Design			1 lot	
Ductwork & Expansion Joints				\$517,112
Absorber Outlet Expansion Joints			180 lf	
Absorber Outlet Expansion Joints - freight			4 pcs	
Absorber Inlet Expansion Joints			256 lf	
Absorber Inlet Expansion Joints - Freight			2 pcs	
Inlet Duct - Replace plate with Alloy 16' x 16' x 12'			26,112 lbs	
Inlet Duct - Fabrication			26,112 lbs	
Inlet Duct - Stiffeners			39,014 lbs	
Imtec Access Doors Inlet Duct			4 pcs	
Mist Eliminator & Supports				\$953,907
Mist Eliminator - FRP DV 210			4 sets	
Mist Eliminator - Wash System			1 lot	
Mist Eliminator - Installation Supervision			1 lot	
Mist Eliminator - Alloy Supports			1 lot	
Mist Eliminator - Water Wash Tank 40' x 40'			1 pc	
Mist Eliminator - Water Wash Pumps			2 pcs	
Mist Eliminator - Water Wash Pump Drivers			2 pcs	
Oxidation Air System				\$0
Site Work & Foundation Design				\$59,360
Foundation Design			1 lot	
Secondary Hydrocyclone System				\$1,710,109
Primary Hydroclone			2 ea	
Primary Hydroclone Feed Tank 48' x 51'			2 ea	
Primary Hydroclone Pumps Expansion Joints			4 ea	
Primary Hydroclone Underflow Feed Tank Agitator			2 ea	
Primary Hydroclone - Feed Pumps			2 ea	
Primary Hydroclone - Feed Pumps			2 ea	
Cloride Purge Pumps			2 ea	
Underflow Tanks FRP 5' x 5'			2 ea	
Engineering Total	22,604			\$2,824,907
Project Management Total	18,861			\$2,583,247
Field Service Total	2,108			\$361,466
Site Engineer Total	8,431			\$1,590,775
Misc. Items				\$267,120
BPEI Travel Expense				\$472,506
Materials / Subcontracts				\$32,521,895



BabcockPower
ENVIRONMENTAL

11/30/11

LG&E - KU Services Company
Mill Creek Unit 3 gas to Unit 4 WFGD Systems Upgrade
ROM Price Estimate Revision 0
C-276 Materials

Materials / Subcontracts	Labor Hours	Qty's	Units	Total Sell Price
Absorber Recycle Pumps				\$2,584,891
Recycle Pumps			8 pcs	
Recycle Pumps - Special Tools			1 lot	
Recycle Pumps - First Fill Lubricants			8 pcs	
Recycle Pumps - NPSH,Noise, Vibration Test			1 lot	
Recycle Pumps - Performance Test			1 lot	
Recycle Pumps - MFG Field Service			5 days	
Recycle Pumps - Exp.Jt. Non- Matalic @ recycle suction			8 pcs	
Recycle Pumps - Exp.Jt. Non- Matalic @ recycle discharge			8 pcs	
Absorber Vessel				\$9,254,343
Absorber Free Issue Plate - 32,000 sq ft plate (4) units		336,000	lbs	
Absorber Fabrication		336,000	lbs	
Awning - Free Issue Materials		2,100	lbs	
Awning - Fabrication		2,100	lbs	
Imtec Doors		20	pcs	
Absorber Vessel Wall Rings				\$428,081
Wall Rings Support Clips		600	lbs	
Wall Rings		8	pcs	
Wall Rings - freight		1	lot	
Wall Rings Support Clips - freight		1	lot	
Agitators & Sump Tank				\$2,748,186
Absorber Agitators		10	pcs	
Absorber Agitators - Model Study Test		1	lot	
Absorber Agitators - 5% LOC / Surety Guarantee		1	lot	
Absorber Agitators - Mfg Field Service		5	days	
Absorber Agitators - freight		10	pcs	
Agitator Metal Boxes for Mounting - 94 sq ft x 10 pcs = 940 sq ft		10	pcs	
Absorber Sump Pumps		2	pcs	
Absorber Sump Pumps Driver		2	pcs	
Absorber Sump Agitators		1	pcs	
Sump Covers and Bridges		2	ea	
Ox Air Nozzles 10 pca 10"/ea approximately 6' lg per ea.		60	lf	
Supply FRP Nozzles for Roof of Tank 60" x 4 pcs		4	pcs	
Stebbins - Engineering for Agitator Boxes		10	pcs	
Stebbins - Engineering to Evaluate the Tile Lined Tank		1	lot	
Stebbins - Engineering to Design a New Concrete Roof		1	lot	
Stebbins - Material Supply New Concrete Roof - prefab		6400	sqft	
Stebbins - Engineering for Nozzles 12 pcs 10"/ea		12	pcs	
Stebbins - Engineer large roof nozzles 60" times 4 pcs		4	pcs	



LG&E - KU Services Company
Mill Creek Unit 3 gas to Unit 4 WFGD Systems Upgrade
ROM Price Estimate Revision 0
C-276 Materials

Materials / Subcontracts	Labor Hours	Qty's	Units	Total Sell Price
Internal & External Recycle Pipe				\$5,474,463
Internal Spray Headers - FRP			16 pcs	
Internal Spray Headers - Recycle Spray Nozzles - 4"			832 pcs	
Internal Spray Headers - Flanges 4" - 150#			832 pcs	
Internal Spray Headers - Alloy Trusses			16 pcs	
Internal Spray Headers - Freight			1 lot	
External Recycle Piping			2000 lf	
External Recycle Piping - Stress Analysis			1 lot	
External Recycle Piping - Bolt & Gasket Sets			1 lot	
External Recycle Piping - Anchors, Hangers & Supports			1 lot	
External Recycle Piping - Freight			1 lot	
External Recycle Piping - Temp Strainers			3 pcs	
External Recycle Piping - Exp. Jts			32 pcs	
External Recycle Piping - Freight			1 lot	
Recycle Valves - Suction			8 pcs	
Recycle Valves - Discharge			8 pcs	
Recycle Valves - Mfg Field Service			1 pcs	
Recycle Valves - Hydraulic Unit			1 pcs	
Recycle Valves - Freight			1 lot	
Bleed Pump System				\$106,639
Slurry Bleed Pumps			2 pcs	
Slurry Bleed Pumps Driver			2 pcs	
Slurry Bleed Pump - Expansion Joint			4 pcs	
Structural Steel				\$0
Sump CS Plate			Not Incl.	
Grating - Replacement			Not Incl.	
Cover Plating Steel			Not Incl.	
Railing			Not Incl.	
Ladders			Not Incl.	
Safety Gates			Not Incl.	
Valves & Piping				\$2,277,636
Replace all Manual Values			1 lot	
Replace all Actuated Valves			1 lot	
Piping Specialties			1 lot	
Large Bore Piping w/Hanger & Supports			1 lot	
Misc. Hangers			1 lot	
Nuts, Bolts & Gaskets CS			1 lot	
Nuts, Bolts & Gaskets Alloy			1 lot	
Oxidation Air Lances			10 pcs	
Oxidation Air Lances - boltups			10 pcs	
Oxidation Air Lances - Structural Steel Supports			10 pcs	
Reactor to Sump FRP Piping			4 pcs	
Sump Overflow FRP Piping			2 pcs	
Sump Vent Piping Connected to the Ductwork			2 pcs	
Bleed Piping			1 lot	
Knife Gate Valves - Hydraulic Piping			1 lot	
Emergency Quench Piping Header (Internal to Duct) Alloy			1 lot	
Emergency Quench - Nozzles			70 pcs	
Emergency Quench - Expansion Joints			6 pcs	



LG&E - KU Services Company
Mill Creek Unit 3 gas to Unit 4 WFGD Systems Upgrade
ROM Price Estimate Revision 0
C-276 Materials

Materials / Subcontracts	Labor Hours	Qty's	Units	Total Sell Price
Instruments & Controls				\$504,560
Analyzer - Sox			1 lot	
Instruments & Controls			1 lot	
Misc Tubing, Fittings & Hangers			1 lot	
Performance Test				\$222,006
Physical Flow Model			1 lot	
Performance Testing			1 lot	
Subcontractors				\$261,184
BOP Electrical Design			1 lot	
BOP Instrument Design			1 lot	
Ductwork & Expansion Joints				\$517,112
Absorber Outlet Expansion Joints		180 lf		
Absorber Outlet Expansion Joints - freight		4 pcs		
Absorber Inlet Expansion Joints		256 lf		
Absorber Inlet Expansion Joints - Freight		2 pcs		
Inlet Duct - Replace plate with Alloy 16' x 16' x 12'		0 lbs		
Inlet Duct - Fabrication		26,112 lbs		
Inlet Duct - Stiffeners		39,014 lbs		
Imtec Access Doors Inlet Duct		4 pcs		
Mist Eliminator & Supports				\$953,907
Mist Eliminator - FRP DV 210			4 sets	
Mist Eliminator - Wash System			1 lot	
Mist Eliminator - Installation Supervision			1 lot	
Mist Eliminator - Alloy Supports			1 lot	
Mist Eliminator - Water Wash Tank 40' x 40'			1 pc	
Mist Eliminator - Water Wash Pumps			2 pcs	
Mist Eliminator - Water Wash Pump Drivers			2 pcs	
Oxidation Air System				\$0
Site Work & Foundation Design				\$59,360
Foundation Design			1 lot	
Secondary Hydrocyclone System				\$1,710,109
Primary Hydroclone			2 ea	
Primary Hydroclone Feed Tank 48' x 51'			2 ea	
Primary Hydroclone Pumps Expansion Joints			4 ea	
Primary Hydroclone Underflow Feed Tank Agitator			2 ea	
Primary Hydroclone - Feed Pumps			2 ea	
Primary Hydroclone - Feed Pumps			2 ea	
Cloride Purge Pumps			2 ea	
Underflow Tanks FRP 5' x 5'			2 ea	
Engineering Total	22,604		MHS	\$2,824,907
Project Management Total	18,861		MHS	\$2,583,247
Field Service Total	2,108		MHS	\$361,466
Site Engineer Total	8,431		MHS	\$1,590,775
Misc. Items			1 lot	\$267,120
BPEI Travel Expense			1 lot	\$472,506
Materials / Subcontracts	52,004			\$35,202,498



WORK SCOPE

Mill Creek Unit 4 WFGD

Work Scope

11/8/2011

Unit 4 • Year 1 2012 (4wks) 4/16-5/07	<ul style="list-style-type: none">• Sump Walls – (Agitators)• Sump Roof• Oxidation Air (Sump Internals)
Unit 4 • Year 2 2013 (2wks) 5/13 & 11/11	<ul style="list-style-type: none">• Replace All Valves & Instruments• Replace Bleed Pumps• Replace Hydrocyclone• Replace FRP Piping for Bleed/Hydrocyclone• Agitators
Unit 3 • Year 2 2013 (6wks) Fall	<ul style="list-style-type: none">• Install U3 Outlet Duck Blank off Plate
Unit 4 • Year 3 2014 (8wks) Fall 9/29-11/17	<ul style="list-style-type: none">• Replace Absorber vessel with Internals<ul style="list-style-type: none">– Spray Hdrs– Spray Nozzles– Mist Eliminator– Wall Rings– Trusses (if required)• Nox Analyzers• Knife gate Valves suction/discharge• Rework Recycle Pipes to feed Hdrs• Emergency Quench System• Replace Scrubber Outlet Duct• Replace Inlet Duct 4 places• Inlet/Outlet expansion joints
Unit 3 • Year 3 2014 (1wk) Fall	<ul style="list-style-type: none">• Remove U3 Blank off Plate in Ductwork
General Work • 2012	<ul style="list-style-type: none">• Run Oxidation Air Piping• Structural Steel/Walkways (Clean/Paint or Replace)
• 2013	<ul style="list-style-type: none">• Continue Structural Steel/Walkways (Clean/Paint or Replace)• Recycle Pumps & Foundation Replace (1) per month• Run duct work Unit 3 to Unit 4 & Steel Supports• Replace Required Pipe & Tubing for Valve & Instrument Replacement in the outage.
• 2014	<ul style="list-style-type: none">• Continue Structural Steel/Walkways (Clean/Paint or Replace)• Replace Walkways for Recycle Pipe Changes



SCHEDULE (HIGH LEVEL)

Activity ID	Activity Name	Rem Dur	Start	Finish	%	2012												2013												2014												2015															
						Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec				
Mill Creek Unit 4 WFGD Conversion Study						901	02-Jan-12	15-Jun-15																																																	
Major Milestones						901	02-Jan-12	15-Jun-15																																																	
A1168	Construction	901	02-Jan-12*	15-Jun-15	0%																																																				
A1165	Engineering	175	02-Jan-12	31-Aug-12	0%																																																				
A1166	Procurement	214	20-Jan-12*	14-Nov-12	0%																																																				
A1167	Fabrication & Delivery	640	23-Jan-12*	04-Jul-14	0%																																																				
A1169	Outages Unit 4 (2012)	16	16-Apr-12*	07-May-12	0%																																																				
A1170	Outage Unit 4 (2013)	6	13-May-13*	20-May-13	0%																																																				
A1171	Outage Unit 3 (2013) (Approximately)	5	01-Nov-13*	07-Nov-13	0%																																																				
A1172	Outage Unit 4 (2014)	30	29-Sep-14*	07-Nov-14	0%																																																				
A1173	Outage Unit 3 (2014) (Approximately)	11	03-Nov-14*	17-Nov-14	0%																																																				
General Work Performed Between Outages						901	02-Jan-12	15-Jun-15																																																	
A1176	Miscellaneous Work to be Done	901	02-Jan-12*	15-Jun-15	0%																																																				
A1304	Rework Existing Structural Steel	684	01-May-12*	12-Dec-14	0%																																																				
A1175	Run Oxidation Air Piping & Hangers	261	01-Jun-12*	31-May-13	0%																																																				
A1177	Recycle Pumps & Foundations Replace (1) per Month	196	01-Mar-13*	29-Nov-13	0%																																																				
A1179	Replace Random Sec. of Pipe & Tubing on Valves & Instruments	120	01-Mar-13*	15-Aug-13	0%																																																				
A1178	Run New Ductwork Unit 3 Outlet to Unit 4 & Support Steel	77	01-May-13*	15-Aug-13	0%																																																				
A1180	Replace Reworked Platforms for Recycle Pipe Relocation	109	01-Apr-14*	29-Aug-14	0%																																																				
Engineering						175	02-Jan-12	31-Aug-12																																																	
A1183	BPEI Receives Notice to Proceed	1	02-Jan-12	02-Jan-12	0%																																																				
A1184	Design Calculations	20	02-Jan-12	27-Jan-12	0%																																																				
A1185	Conduct Physical Modeling	40	06-Feb-12	30-Mar-12	0%																																																				
A1186	Develop Equipment D&R Sheets	25	12-Mar-12	13-Apr-12	0%																																																				
A1187	Develop Mechanical Drawings	125	12-Mar-12	31-Aug-12	0%																																																				
Procurement						214	20-Jan-12	14-Nov-12																																																	
A1201	Issue P.O. Oxidation Air System	12	20-Jan-12*	06-Feb-12	0%																																																				
A1190	Issue P.O. Recycle Pumps	10	20-Feb-12	02-Mar-12	0%																																																				
A1192	Issue P.O. Wall Rings	10	01-Mar-12	14-Mar-12	0%																																																				
A1193	Issue P.O. Agitators	10	20-Apr-12*	03-May-12	0%																																																				
A1191	Issue P.O. Absorber Vessel	10	01-Jun-12	14-Jun-12	0%																																																				
A1196	Issue P.O. Instruments & Controls	10	20-Jun-12	03-Jul-12	0%																																																				
A1197	Issue P.O. Inlet/ Outlet Expansion Joints	10	20-Jun-12	03-Jul-12	0%																																																				
A1198	Issue P.O. Inlet Duct Sections	10	20-Jun-12	03-Jul-12	0%																																																				
A1199	Issue P.O. Manual & Automatic Valves	10	20-Jun-12	03-Jul-12	0%																																																				
A1200	Issue P.O. Mist Eliminator System	10	20-Jun-12	03-Jul-12	0%																																																				
A1194	Issue P.O. Analyzer SOX	10	02-Jul-12*	13-Jul-12	0%																																																				
A1195	Issue P.O. Bleed Pump System	10	01-Aug-12*	14-Aug-12	0%																																																				
A1202	Issue P.O. Hydrocyclone System	10	01-Oct-12*	12-Oct-12	0%																																																				
A1203	Issue P.O. Recycle Spray Headers	10	01-Oct-12	12-Oct-12	0%																																																				
A1204	Issue P.O. Recycle Spray Nozzles	10	01-Oct-12	12-Oct-12	0%																																																				
A1205	Issue P.O. Recycle External Piping	10	01-Nov-12*	14-Nov-12	0%																																																				
A1206	Issue P.O. Recycle Suction & Discharge Valves	10	01-Nov-12	14-Nov-12	0%																																																				
A1207	Issue P.O. Emergency Quench System	10	01-Nov-12	14-Nov-12	0%																																																				

- Early Bar
- Critical Remaining Work
- Milestone
- Summary

100585 LG&E - KU Mill Creek

WFGD Retrofit Performance Upgrade Study



BabcockPower

Activity ID	Activity Name	Rem Dur	Start	Finish	%	2012												2013												2014												2015															
						Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec				
Fabrication and Delivery						640	23-Jan-12	04-Jul-14																																																	
A1221	Fabricate Oxidation Air System	71	23-Jan-12*	30-Apr-12	0%	[Green bar from Jan 23 to Apr 30, 2012]																																																			
A1239	Deliver Oxidation Air System	8	01-May-12	10-May-12	0%	[Green square at May 1, 2012]																																																			
A1210	Fabricate Recycle Pumps	152	04-May-12*	03-Dec-12	0%	[Green bar from May 4 to Dec 3, 2012]																																																			
A1213	Fabricate Agitators	125	04-May-12	25-Oct-12	0%	[Green bar from May 4 to Oct 25, 2012]																																																			
A1216	Fabricate Instruments & Controls	60	04-Jul-12	25-Sep-12	0%	[Green bar from Jul 4 to Sep 25, 2012]																																																			
A1231	Deliver Agitators	10	26-Oct-12	08-Nov-12	0%	[Green square at Oct 26, 2012]																																																			
A1219	Fabricate Manual & Automatic Valves	87	15-Nov-12*	15-Mar-13	0%	[Green bar from Nov 15 to Mar 15, 2013]																																																			
A1228	Deliver Recycle Pumps	10	04-Dec-12	17-Dec-12	0%	[Green square at Dec 4, 2012]																																																			
A1215	Fabricate Bleed Pump System	84	10-Dec-12*	04-Apr-13	0%	[Green bar from Dec 10 to Apr 4, 2013]																																																			
A1222	Fabricate Hydrocyclone System	157	28-Dec-12*	05-Aug-13	0%	[Green bar from Dec 28 to Aug 5, 2013]																																																			
A1237	Deliver Manual & Automatic Valves	21	18-Mar-13	15-Apr-13	0%	[Green square at Mar 18, 2013]																																																			
A1233	Deliver Bleed Pump System	10	05-Apr-13	18-Apr-13	0%	[Green square at Apr 5, 2013]																																																			
A1234	Deliver Instruments & Controls	55	15-Jul-13*	27-Sep-13	0%	[Green bar from Jul 15 to Sep 27, 2013]																																																			
A1240	Deliver Hydrocyclone System	10	06-Aug-13	19-Aug-13	0%	[Green square at Aug 6, 2013]																																																			
A1226	Fabricate Recycle Suction & Discharge Valves	158	07-Oct-13*	14-May-14	0%	[Green bar from Oct 7 to May 14, 2014]																																																			
A1211	Fabricate Absorber Vessel	140	15-Nov-13	29-May-14	0%	[Green bar from Nov 15 to May 29, 2014]																																																			
A1212	Fabricate Wall Rings	150	15-Nov-13	12-Jun-14	0%	[Green bar from Nov 15 to Jun 12, 2014]																																																			
A1217	Fabricate Inlet/ Outlet Expansion Joints	123	25-Nov-13*	14-May-14	0%	[Green bar from Nov 25 to May 14, 2014]																																																			
A1218	Fabricate Inlet Duct Sections	123	25-Nov-13*	14-May-14	0%	[Green bar from Nov 25 to May 14, 2014]																																																			
A1220	Fabricate Mist Eliminator System	95	25-Nov-13*	04-Apr-14	0%	[Green bar from Nov 25 to Apr 4, 2014]																																																			
A1223	Fabricate Recycle Spray Headers	87	25-Nov-13*	25-Mar-14	0%	[Green bar from Nov 25 to Mar 25, 2014]																																																			
A1224	Fabricate Recycle Spray Nozzles	95	25-Nov-13*	04-Apr-14	0%	[Green bar from Nov 25 to Apr 4, 2014]																																																			
A1225	Fabricate Recycle External Piping	87	25-Nov-13*	25-Mar-14	0%	[Green bar from Nov 25 to Mar 25, 2014]																																																			
A1227	Fabricate Emergency Quench System	71	02-Dec-13*	10-Mar-14	0%	[Green bar from Dec 2 to Mar 10, 2014]																																																			
A1214	Fabricate Analyzer SOX	85	01-Jan-14*	29-Apr-14	0%	[Green bar from Jan 1 to Apr 29, 2014]																																																			
A1245	Deliver Emergency Quench System	10	11-Mar-14	24-Mar-14	0%	[Green square at Mar 11, 2014]																																																			
A1243	Deliver Recycle External Piping	10	26-Mar-14	08-Apr-14	0%	[Green square at Mar 26, 2014]																																																			
A1235	Deliver Inlet/ Outlet Expansion Joints	13	15-May-14	02-Jun-14	0%	[Green square at May 15, 2014]																																																			
A1236	Deliver Inlet Duct Sections	13	15-May-14	02-Jun-14	0%	[Green square at May 15, 2014]																																																			
A1244	Deliver Recycle Suction & Discharge Valves	10	15-May-14	28-May-14	0%	[Green square at May 15, 2014]																																																			
A1232	Deliver Analyzer SOX	8	22-May-14*	02-Jun-14	0%	[Green square at May 22, 2014]																																																			
A1238	Deliver Mist Eliminator System	8	22-May-14*	02-Jun-14	0%	[Green square at May 22, 2014]																																																			
A1242	Deliver Recycle Spray Nozzles	8	22-May-14*	02-Jun-14	0%	[Green square at May 22, 2014]																																																			
A1241	Deliver Recycle Spray Headers	7	23-May-14*	02-Jun-14	0%	[Green square at May 23, 2014]																																																			
A1229	Deliver Absorber Vessel	8	25-Jun-14*	04-Jul-14	0%	[Green square at Jun 25, 2014]																																																			
A1230	Deliver Wall Rings	8	25-Jun-14*	04-Jul-14	0%	[Green square at Jun 25, 2014]																																																			
Construction (General Work Between Outages)						901	02-Jan-12	15-Jun-15		[Green bar from Jan 2 to Jun 15, 2015]																																															
A1249	Mobilize Construction	8	02-Jan-12	11-Jan-12	0%	[Green bar from Jan 2 to Jan 11, 2012]																																																			
A1252	Replace Recycle Pumps & Foundations (1) at a time	457	01-Mar-12*	29-Nov-13	0%	[Green bar from Mar 1 to Nov 29, 2013]																																																			
A1254	Replace Pipe and Tubing for Valves & Instruments	381	01-Mar-12*	15-Aug-13	0%	[Green bar from Mar 1 to Aug 15, 2013]																																																			
A1251	Repair Structural Steel and Walkways	684	01-May-12*	12-Dec-14	0%	[Green bar from May 1 to Dec 12, 2014]																																																			
A1253	Install Duct work Unit 3 to Unit 4 and Steel Supports	338	01-May-12*	15-Aug-13	0%	[Green bar from May 1 to Aug 15, 2013]																																																			

- Early Bar
- Critical Remaining Work
- Milestone
- Summary



Exhibit JNV-2

Zachry New WFGD Estimate
for Mill Creek Unit 3



LG&E Mill Creek Environmental Compliance Project

New Unit 3 WFGD – Scope description and Budget Estimate < September 11, 2012 >

Budget estimates for the following Unit 3 WFGD options are included:

- Option A = Stebbins Absorber Vessel – Base DOR [Absorber internals by EPC / Zachry]
- Option B = Solid C276 Absorber Vessel – Base DOR [Absorber internals by EPC / Zachry]
- Option C = Solid C276 Absorber Vessel – Modified DOR [Absorber Vessel by WFGD / Babcock]

The following information is included:

- Scope Summary – 6 pp.
- Preliminary Schedule [Options A ~ C] – 3 pp.
- Budget Estimate Comparison Summary – 2 pp.
- Budget Estimate Detail [Options A ~ C] – 6 pp.
- Babcock Budget Estimates [Options A ~ C] – 6 pp.

Mill Creek Unit 3 WFGD

Demolition

The major demolition for Unit 3 is the ductwork on the outlet of the existing electrostatic precipitators (ESP). The ductwork from the discharge of the existing ESP will be replaced with new ductwork. The existing Unit 3 WFGD system will be abandoned in place. The existing ID fans will be removed and replaced.

We have also included the cost for a subcontractor to demolish the existing Unit 4 WFGD down to the anchor bolts, and we plan to self perform the demolition of the existing concrete foundation.

Quantity Basis

Please refer to Attachment A for Estimated Quantities.

Civil Site Work

Work will include the design and construction of all surveys, clearing, dewatering, grading, import and export of materials, as required, excavation, filling, trenching, shoring, backfilling, and paving, seeding, or other surfacing.

The EPC Contractor (Contractor) will establish and maintain benchmarks and control points, as required, to provide measurement control and to verify location of completed Work within the site coordinate system.

Contractor will design, furnish, and install temporary and permanent erosion and sediment controls for the Work.

Contractor will design and construct all excavation, trenching, and backfill and also design, furnish, install and maintain dewatering systems and/or shoring systems, as required.

Contractor will design, furnish and install final surfacing, including concrete and/or asphalt pavement, aggregate surfacing, and/or seeding, as required. Grade finished surfaces to drain without ponding.

Structural Work

Contractor will design, furnish, and install all required foundations, including deep foundation elements such as piling or caissons for structures and equipment, including:

- 1 PJFF(2-50%);
- WFGD system
- 2 ID fans located between the PJFF and the WFGD;
- Variable Frequency Drives (VFD) equipment and enclosures for the ID fans;
- PAC storage silos, associated transfer systems and buildings;
- SAMM storage silos, associated transfer systems, and buildings;
- Electrical transformers. These foundations will incorporate permanent construction for containing spills of oil, contaminated fire protection water and rainwater; and
- Any and all additional equipment identified as required during the execution of this Work.
- Contractor will design, furnish, and install all ductwork, associated supports, slide bearing assemblies, ductwork stiffeners (for both new and existing duct being reused), connections to existing ductwork, access doors, access platforms, stairs, ladders, handrails, and lifting lugs including:
- Gas ducts with, sampling, cleanout, instrumentation, and test ports, including turning vanes, as required, and flow straightening devices, as required, by the air flow model study, from the ESP outlet to the inlet of the PJFF;

Mill Creek Unit 3 WFGD

- Gas ducts including duct from the PJFF outlet to the ID fans inlets, and test ports, including turning vanes, as required, and flow straightening devices, as required, by the air flow model study, and dampers;
- Gas ducts from the ID fans outlets to and including the inlet duct to the WFGD, and test ports, including turning vanes, as required, and flow straightening devices, as required, by the air flow model study, and dampers; and
- Gas duct from the WFGD outlet to the existing Unit 4 chimney breeching.
- o Gas ducting includes 0.050 inch stainless steel type 304, 4x1 box rib Alclad conventional screwed system for duct roofs.
- o Contractor assumes existing ESP outlet duct is structurally sound and no stiffening is required.

Contractor will design, furnish, and install all required structural steel for support of equipment and ductwork, including:

- Support of 2 – 50% PJFF structures for Unit 3. The structure will include stairs, platforms and vertical access elements provided by the PJFF supplier;
- Elevated concrete platform with support steel up to the equipment baseline under the PJFF.
- Support of the WFGD equipment building and all associated equipment provided by the WFGD supplier;
- Support of 2 PAC silos and all associated equipment and structures;
- Support of 2 SAMM silos and all associated equipment and structures;
- Support of the complete ash handling system provided by the Contractor;
- Support for new ductwork and re-support of modified existing ductwork;
- Miscellaneous steel structures for support of piping, raceway, and other utilities as may be required; and
- Miscellaneous steel structures and platforms for maintenance access to installed equipment, valves, and instruments;
- o Contractor has assumed modifications to existing pipe racks are not required and that structure capacity is adequate for increased utility loadings;
- o Contractor assumes existing building steel, isobus support steel, and concrete deck can be used to support the new isobus sections and cable bus.

Contractor will design, furnish, and install foundations, including deep foundation elements such as piling, required for the support of buildings and structures, including:

- PJFF support structure;
- WFGD absorber building, and associated equipment (including elevator);
- Electrical equipment building;
- PAC silos and equipment building;
- SAMM silos and equipment building;
- Ash handling equipment and building; and
- Miscellaneous yard structures for pipe, cable tray and other utility supports.

Miscellaneous Work – Installation of Buyer-Furnished Equipment

Contract will include designing of all necessary interfaces, receiving, unloading, inventorying, inspecting, storing, maintaining, removing from storage, protecting, handling, rigging, installing,

Mill Creek Unit 3 WFGD

field adjusting, aligning, commissioning, and testing of all of the following Buyer furnished equipment:

- PJFFs – Two 50% self-supporting PJFF modules furnished for control of particulates including:
 - o Casing, roof, hoppers, tube sheet, and appurtenances from the gas inlet manifolds to the gas outlet manifolds including flanges, access doors, struts;
 - o Structural steel framing up from foundations for support of slide bearing assemblies, all integrated with PJFF Vendor requirements and recommendations.
 - o Structural and miscellaneous steel for all permanent access platforms, both internal and external, including walkways, floor plated areas, stairways, ladders, and handrail (guard rail) from equipment baseline to the top equipment elevation of the PJFF, including access to fly ash removal equipment;
 - o Filter bags and cages;
 - o Filter bag cleaning system;
 - o Compressed air system including compressors, dryers, receivers, building enclosure and air distribution system required for filter bag cleaning and actuation of equipment;
 - o Weather enclosure;
 - o Gas flow distribution vanes and baffles;
 - o Compartment isolation dampers and actuators;
 - o Casing bypass dampers and actuators;
 - o Rain gutters and drains to grade;
 - o Electric hoists and trolleys,
 - o Access doors;
 - o Fly ash hoppers and nozzles including ash level detectors, outlet connections, pounding anvil, hopper vibrators, poke holes, anti-sneak baffles, electric hopper heaters, and insulation panels;
 - o All electrical equipment and motors; and
 - o Instruments, final control elements, and connections necessary to effectively control and monitor all equipment and systems for a complete and operable PJFF.
- PAC injection system for mercury control, including:
 - o Two storage silos including accessories;
 - o Reagent feeders for metering material;
 - o Conditioning equipment;
 - o Conveying equipment; and
 - o Flow monitoring and injection equipment.
- SAMM injection system for sulfuric acid and acid mist control, including:
 - o Two storage silos including accessories;
 - o Reagent feeders for metering material;
 - o Conditioning equipment;
 - o Conveying equipment; and
 - o Flow monitoring and injection equipment.
- Per the information received from Riley, the existing Unit 4 Oxidation Blowers will be reused for the new Unit 3 WFGD. We have included the cost to remove the existing pipe, and then re-pipe the oxidation air over to the new WFGD. It is assumed that the blowers, building, electrical, and controls, will be let untouched therefore not requiring any additional costs.

Miscellaneous Work – Installation of Contractor-Furnished Equipment

Mill Creek Unit 3 WFGD

Contract will include designing all necessary interfaces, receiving, unloading, inventorying, inspecting, storing, maintaining, removing from storage, protecting, handling, rigging, installing, field adjusting, aligning, commissioning, and testing of all of the following below listed Contractor-furnished equipment.

- Expansion joints – furnish and install flue gas ductwork expansion joints at all necessary locations;
- Ductwork;
- Dampers;
- Fly ash conveying and storage system;
- Compressed air system;
- Service water;
- Potable water;
- Fire protection system;
- Wastewater system;
- Lube oil system; and
- ID fans (2X50%).

AQCS Power Supply Systems

Refer to Attachment B – Preliminary One lines for an overview of the electrical system. Contractor will design, furnish, install, and commission new AC power supply systems (120v, 208v, 480v, 4160v, 13.8kV), 125 DC power supply system, and new uninterruptible power supply (UPS) system. All electrical equipment necessary will be included to provide a complete power supply system including isolated phase bus duct, non-segregated bus duct, transformers, cable bus, switchgear, motor control centers, variable frequency drives, panelboards, batteries, battery chargers, UPS systems, cable, raceway, etc. Equipment will include everything needed to tie into the existing plant system at agreed terminal points.

Protective relaying for unit aux transformers, 138kV to 13.8kV , and 13.8kV to 4,160V switchgear will be microprocessor based relays with primary differential protection and backup overcurrent protection. Breakers will be operated from DCS.

Contractor assumes the existing plant Diesel Generator is large enough to accommodate all changes/additions, a new Diesel Generator is not required

Communication

Contractor will extend the existing plant paging communications system to all new and /or replaced plant buildings and process areas as described herein. The scope of supply will include designing, furnishing, and installing all new equipment and system related components and interfacing with the existing plant page/party system. Contractor will design, furnish, and install raceway and space provisions for telephone/LAN equipment

Lighting

Contractor will design, furnish, and install permanent lighting in all new buildings and enclosures as well as outdoor areas as described herein. The lighting system will include convenience receptacles, power receptacles suitable for plant welding equipment, transformers, panelboards, cable, contactors, conduit, etc.

PJFF supplier shall supply lights and receptacles. Contractor will provide raceway, cable, power distribution panels and transformers as needed.

Mill Creek Unit 3 WFGD

Grounding and Lightning Protection

Contractor will design, furnish, and install the grounding and lightning protecting system to tie into the existing plant ground grid and limit surface step potential values to the required level.

Cathodic Protections and Freeze Protection

Contractor will design, furnish and install the cathodic protection system for all underground metallic piping, underground steel tanks, and pad-mounted steel tanks and other critical above or below grade steel items for which corrosion is a significant concern.

Contractor will design, furnish, and install an electrical heat tracing system for freeze protection and process temperature maintenance for size 6-inch and smaller piping. This will include power feeder circuits, self-regulating heat trace devices, dry type distribution transformers, distribution panelboards, contactors, monitor panels, thermostats, raceway systems, and all materials required for powering and monitoring the heat tracing system.

Instrumentation and Control Work

Contractor will provide a complete and functional instrumentation and control system to satisfy the control and monitoring requirements of the Mill Creek AQCS systems.

Contractor shall not provide continuous monitoring systems as required by the specification and meeting the requirements of 40 CFR 75. This equipment was removed from the scope during negotiations. Contractor will provide CEM's building foundation, power, instrument air, umbilical cord, cables to the monitors on the monitoring platform, and installation of the CEMS shelter.

Contractor will obtain the services of the DCS original equipment manufacturer for all AQCS DCS engineering and design work such as DCS configuration and implementation. Contractor will be responsible for furnishing all control logics, control narratives, and system descriptions associated with the AQCS project.

Contractor will develop the master instrument and I/O lists to forward to the Buyer and/or DCS OEM to allow for I/O partitioning and DCS equipment sizing. The I/O list will be approved by the Buyer prior to partitioning.

Contractor will provide vibration Monitoring on all MV driven equipment and will wire vibration equipment provided by OEMs

The new Honeywell Experion PKS system will be integrated into the existing Plant Honeywell DCS . The new system shall incorporate a true distribution of controls by locating I/O equipment in the vicinity of the field equipment. Control System Architecture drawing will provide the DCS layout. DCS will be installed and commissioned per Honeywell's recommendations and best practices.

Control system Performance and sizing will incorporate a design to achieve maximum efficiency, operability, reliability, and availability.

Hardware:

- o Unit 3 Controller Subsystem & Marshaling
- o 20% spare I/O and Record Drawings

Engineering Summary:

Configuration of IO—

Experion HTML Graphics (Static— & Dynamic)

- Static Shape Library
- Pop-ups / faceplates
- System Diagnostic displays

Mill Creek Unit 3 WFGD

Control System Database→

Logic configuration for AQCS upgrade→

Third Party Interfaces→

For the WFGD - use of Existing Unit # 4 DCS→ controller for Unit #3. This includes software configuration, tag name changes and connection to existing unit #3 DCS. It is assumed that no new Honeywell DCS hardware is required to convert U #4 WFGD to U#3 and there are enough spares available in case of any additions.

Factory Acceptance Test→

→ Site Acceptance Test

New Historian Tags to be added to existing→ Experion PKS Historian for Historical data storage & Retrieval

Fiber→ & Ethernet interface to the existing DCS

Other considerations taken;

- **The PJFF has been rotated 90 degrees to facilitate better future access behind Unit 3**
- **We have included the additional cost for the piling and concrete foundation for the PJFF**
- **We have included the additional BOP electrical, piping, and controls that was not originally included**
- **We have utilized the schedules received from Riley for the three separate WFGD options, when looking at this additional cost please remember that the project has to be extended past our original demobilization date**
- **We have included the additional cost to remove the two 1280 D tower cranes at the end of the project, originally this was not required, but now because of the new location of the PJFF and new WFGD, we cannot access these tower cranes for removal, per our original plan**

LG&E Scheduled Outage	Fall 2016 A	Spring 2016 B	Spring 2016 C
BPI			
BPI Base	\$ 43,249,807	\$ 50,647,803	\$ 52,548,520
Other Site Conditions	\$ 1,374,303	\$ 1,178,197	\$ 1,178,197
Bpi Total Number	\$ 44,624,110	\$ 51,826,000	\$ 53,726,717
BPI Pt-Pt Duration	ZII Internals 12 months	ZII Internals 9 months	BPI Internals 7 months 2 months not critical
Remove Internals from ZHI Scope			(21,037)
Assumed average rate for ZHI reduction			\$ 63.60
Resultant price to remove from B case for ZHI number			\$ (1,337,867)
ZHI Number	\$ 67,556,264	\$ 61,497,958	\$ 60,160,091
ZHI Fee on BPI	\$ 1,380,000	\$ 1,603,000	\$ 1,662,000
Total ZHI Number	\$ 68,936,264	\$ 63,100,958	\$ 61,822,091
TOTAL	\$ 113,560,374	\$ 114,926,958	\$ 115,548,808
Incremental Delta	Previous Base	\$ 1,366,584 increase	\$ 621,850 increase
BPI add for internals analysis			\$ 1,900,717
Average rate using BPI delta over ZHI removed DWH's			(90.35)



Description	Quantity	UM	6/25/2012		9/11/2012		6/25/2012		9/11/2012		6/25/2012		9/11/2012		6/25/2012		9/11/2012		6/25/2012		9/11/2012		6/25/2012		9/11/2012									
			LABOR HOURS	Delta	LABOR HOURS	LABOR AMOUNT	Delta	LABOR AMOUNT	MAT AMOUNT	Delta	MAT AMOUNT	CONST EQUIP	Delta	CONST EQUIP	SUB AMOUNT	Delta	SUB AMOUNT	SUP AMOUNT	Delta	SUP AMOUNT	TOTAL AMOUNT	Delta	TOTAL AMOUNT	TOTAL AMOUNT	Delta	TOTAL AMOUNT								
WFGD Pipe	8,390	LF			26,160		26,160			\$876,802		\$876,802			\$743,203		\$743,203											\$1,620,006		\$1,620,006				
WFGD Demolition	1	EA			1,050		1,050			\$31,138		\$31,138								\$4,518		\$4,518	\$321,939		(\$3,390)	\$318,549		\$321,939		\$32,266	\$354,205			
WFGD Site Improvements	600	SY			65		65			\$1,925		\$1,925			\$3,469		\$3,469			\$9,613		\$9,613					\$17,717		\$17,717					
WFGD U/G Utility Excavation/Backfill	2,000	CY			550		550			\$16,180		\$16,180			\$1,000		\$1,000			\$11,390		\$11,390			\$13,571	\$13,571	\$250	\$250	\$42,391	\$42,391				
WFGD Structural Excavation & Backfill	6,215	CY			2,416		(269)	2,147		\$79,013		(\$9,500)	\$69,514		\$13,572		(\$3,367)	\$10,205		\$13		\$30,458	\$33,164		(\$5,341)	\$27,823		\$125,762		\$12,249	\$138,012			
WFGD Piling - Load Bearing	454	EA			1,786		(559)	1,227		\$56,351		(\$17,588)	\$38,763							\$2,959,248		(\$1,942,357)	\$1,016,891				\$3,015,599		(\$1,959,945)	\$1,055,654				
WFGD Structural Concrete	3,960	CY			25,398		(2,616)	22,781		\$802,094		(\$81,695)	\$720,399		\$796,533		(\$86,001)	\$710,532			\$38,462		(\$4,292)	\$34,170		\$49,650	(\$10,248)	\$39,402	\$1,686,738		(\$182,236)	\$1,504,503		
WFGD Structural Steel - UNIT 3 (W/YE	697	TN			24,772		6,759	31,531		\$866,397		\$236,435	\$1,102,832		\$2,934,202		\$716,492	\$3,650,695								\$76,331	(\$5,523)	\$70,808	\$3,876,931		\$947,404	\$4,824,335		
WFGD Buildings	1	SF																		\$3,022,807		(\$466,248)	\$2,556,559				\$3,022,807		(\$466,248)	\$2,556,559				
WFGD U4 Fire Protection & Detection	1	PC																		\$279,028		\$134,618	\$413,646				\$279,028		\$134,618	\$413,646				
WFGD Mechanical Equipment Unit # 3	808	TN			91,566		(12,838)	78,728		\$3,106,923		(\$434,779)	\$2,672,143		\$3,977,235		\$44,267,016	\$48,244,251			\$904,706		\$446,944	\$1,351,650		\$26,250	\$26,250	\$8,015,114		\$44,279,180	\$52,294,294			
WFGD Electrical	1	EA			36,163		36,163			\$1,220,156		\$1,220,156			\$1,388,335		\$1,388,335				\$239,700		\$239,700			\$6,521	\$6,521	\$2,854,711		\$2,854,711				
WFGD Instrumentation	165	EA			2,927		673	3,600		\$108,040		\$23,702	\$131,742		\$1,373,862		(\$803,517)	\$570,345									\$1,481,902		(\$779,816)	\$702,087				
WFGD Other Piping Insulation U3	1	LS																		\$211,050		\$250,400	\$461,450				\$211,050		\$250,400	\$461,450				
WFGD 3 Field Finish Painting	16,774	SF			4,253		4,253			\$136,318		\$136,318			\$12,513		\$12,513										\$148,831		\$148,831					
WFGD Special Coatings	9,648	SF																									\$400,142		\$400,142					
12 - PJFF U/G Utility Excavation/Backfi	1,175	LF			41		41			\$1,237		\$1,237			\$748		\$748											\$1,985		\$1,985				
13 - PJFF Structural Excavation & Back	3,600	CY			1,482		1,482			\$48,640		\$48,640			\$10,205		\$10,205			\$21,282		\$21,282			\$19,982	\$19,982	\$100,109		\$100,109					
18 - PJFF Structural Concrete	1,371	CY			8,704		8,704			\$276,673		\$276,673			\$258,784		\$258,784									\$25,200	\$25,200	\$573,339		\$573,339				
18 - PJFF Piling - Load Bearing	66	EA																								\$1,187,643	\$1,187,643	\$1,187,643		\$1,187,643				
20 - PJFF Structural Steel	490	TN			8,862		8,862			\$299,678		\$299,678			\$1,193,707		\$1,193,707										\$1,493,384		\$1,493,384					
23 - Architectural Demo	1	EA																									(\$239,604)	(\$239,604)	(\$239,604)		(\$239,604)			
26 - PJFF-Mechanical	1	EA			(4,819)		(4,819)			(\$157,765)		(\$157,765)			(\$387,581)		(\$387,581)											(\$545,346)	(\$545,346)	(\$545,346)				
42 - PJFF Electrical	1	EA			31,782		31,782			\$1,065,779		\$1,065,779			\$814,281		\$814,281										\$28,800	\$28,800	\$1,908,860		\$1,908,860			
52 - PJFF Insulation U3	(17,000)	SF																									(\$267,750)	(\$267,750)	(\$267,750)		(\$267,750)			
54 - PJFF Field Finish Painting	11,750	SF			2,441		2,441			\$78,233		\$78,233			\$7,619		\$7,619											\$85,852		\$85,852				
50 - Instrumentation	1	LS			3,640		3,640			\$119,912		\$119,912			\$65,975		\$65,975											\$185,887		\$185,887				
12 - Other U/G Utility Excavation/Backfi	485	LF			16		16			\$495		\$495			\$299		\$299											\$794		\$794				
42 - Other Electrical	1	EA			6,888		6,888			\$222,838		\$222,838			\$697,265		\$697,265										\$7,200	\$7,200	\$927,303		\$927,303			
Craft Start Up Assistance	100	PC			500		500			\$22,252		\$23	\$22,275														\$22,252	\$23	\$22,275					
Sub Total Direct Cost			149,364	118,427	267,791			\$5,041,071	\$3,954,836	\$8,995,906	\$9,095,404	\$48,899,396	\$57,994,800	\$13	\$71,406	\$71,419	\$7,770,404	(\$177,688)	\$7,592,716	\$152,230	\$16,200	\$168,430	\$22,059,122	\$52,764,150	\$74,823,272									
Construction Equipment Owned & 3rd	1	LS			1,628		1,628			\$51,402		\$51,402			\$2,988,816	\$3,366,216	\$6,355,032										\$270,665	\$270,665	\$2,988,816	\$3,688,283	\$6,677,099			
Direct Labor Unallocated Supplies	1	LS																									\$205,247	\$220,633	\$425,880	\$205,247	\$220,633	\$425,880		
Scaffolding Supplies	1	LS																									\$45,750	\$101,250	\$147,000	\$45,750	\$101,250	\$147,000		
Small Tools	1	LS													\$73,439		\$73,439										\$900,608	(\$640,608)	\$260,000	\$900,608	(\$567,170)	\$333,439		
Craft Per Diem	1	LS						\$972,600	\$646,800	\$1,619,400																	\$972,600	\$646,800	\$1,619,400	\$1,945,200	\$1,293,600	\$3,238,800		
Construction Staff & Expenses	1	LS			20,510		108,976	129,486		\$694,609		\$3,776,027	\$4,470,636														\$913,470	\$1,237,219	\$2,150,689	\$1,608,079	\$5,013,246	\$6,621,325		
Sales Tax	1	EA																									\$94,533	\$79,467	\$174,000	\$94,533	\$79,467	\$174,000		
Indirect Sundries	1	LS																									\$34,535	\$34,535	\$34,535		\$34,535			
Home Office Support	1	LS			3,513		3,513			\$108,847		\$108,847															\$170,166	\$170,166	\$279,013		\$279,013			
Engineering Liason & Expenses	1	LS			2,080		2,080			\$174,510		\$174,510															\$48,500	\$48,500	\$223,010		\$223,010			
Engineering	1	LS																									\$2,000,000	\$3,740,866	\$5,740,866	\$2,000,000	\$3,740,866	\$5,740,866		
Enterprise Start Up & Commissioning	1	LS																									\$1,512,100	(\$990,512)	\$521,588	\$230,457	\$230,457	\$1,512,100	(\$760,055)	\$752,045
Builders Risk	1	EA																									\$300,000	\$300,000	\$300,000		\$300,000			
JV 6000 Joint Venture Indirects	1	LS			1,442		1,442			\$243,031		\$243,031															\$38,578	\$894,202	\$932,780	\$38,578	\$1,137,233	\$1,175,811		
Escalation	1	LS								\$30,000		\$30,000			\$87,000		\$87,000										\$535,000	\$3,826,280	\$4,361,280	\$535,000	\$3,943,280	\$4,478,280		
General & Administrative	1	LS																									\$2,644,000	\$2,085,000	\$4,729,000	\$2,644,000	\$2,085,00			



Zachry Industrial Incorporated
 Estimate Detail Option "A" Stebbins Tower
 Estimate: PFAQ12042 A
 Zachry Industrial Inc. Custom Report

Code	Description	Quantity	UM	LABOR WORKHOURS	LABOR AMOUNT	MATERIAL AMOUNT	EQUIPMENT AMOUNT	SUBCONTRT AMOUNT	SUPPLIES AMOUNT	TOTAL AMOUNT
2 New Unit 3 WFGD										
2.1	WFGD Pipe	8,390	EA	26,160	\$876,802	\$743,203				\$1,620,006
2.2	WFGD Demolition	1	EA	1,050	\$31,138		\$4,518	\$318,549		\$354,205
2.3	WFGD Site Improvments	600	SY	65	\$1,925	\$3,469	\$2,710	\$9,613		\$17,717
2.4	WFGD U/G Utility Excavation/Backfill	2,000	CY	550	\$16,180	\$1,000	\$11,390	\$13,571	\$250	\$42,391
2.5	WFGD Structural Excavation & Backfill	5,000	CY	2,147	\$69,514	\$10,205	\$30,471	\$27,823		\$138,012
2.6	WFGD Piling - Load Bearing	281	EA	1,227	\$38,763			\$1,016,891		\$1,055,654
2.7	WFGD Structural Concrete	3,694	CY	22,781	\$720,399	\$710,532		\$34,170	\$39,402	\$1,504,503
2.8	WFGD Structural Steel - UNIT 3 (W/YE	1,426	TN	31,531	\$1,102,832	\$3,650,695			\$70,808	\$4,824,335
2.9	WFGD Buildings	1	SF					\$2,556,559		\$2,556,559
2.10	WFGD U3 Fire Protection & Detection	1	PC					\$413,646		\$413,646
2.11	WFGD Mechanical Equipment Unit # 3	321	TN	78,728	\$2,672,143	\$48,244,251		\$1,351,650	\$26,250	\$52,294,294
2.12	WFGD Electrical	1	EA	36,163	\$1,220,156	\$1,388,335		\$239,700	\$6,521	\$2,854,711
2.13	WFGD Instrumentation	165	EA	3,600	\$131,742	\$570,345				\$702,087
2.14	Other Piping Insulation U3	23,499	SF					\$461,450		\$461,450
2.15	WFGD 3 Field Finish Painting	21,093	SF	4,253	\$136,318	\$12,513				\$148,831
2.16	WFGD Special Coatings	9,648	SF					\$400,142		\$400,142
3 Unit 3 PJFF Modifications										
3.1	12 - PJFF U/G Utility Excavation/Backfi	1,175	LF	41	\$1,237		\$748			\$1,985
3.2	13 - PJFF Structural Excavation & Back	3,600	CY	1,482	\$48,640	\$10,205	\$21,282	\$19,982		\$100,109
3.3	18 - PJFF Structural Concrete	1,371	CY	8,704	\$276,673	\$258,784		\$12,682	\$25,200	\$573,339
3.4	18 - PJFF Piling - Load Bearing	66	EA					\$1,187,643		\$1,187,643
3.5	20 - PJFF Structural Steel	490	TN	8,862	\$299,678	\$1,193,707				\$1,493,384
3.6	23 - Architectural Demo	1	EA					(\$239,604)		(\$239,604)
3.7	26 - PJFF-Mechanical	1	EA	(4,819)	(\$157,765)	(\$387,581)				(\$545,346)
3.8	42 - PJFF Electrical	1	EA	31,782	\$1,065,779	\$814,281		\$28,800		\$1,908,860
3.9	52 - PJFF Insulation U3	(17,000)	SF					(\$267,750)		(\$267,750)
3.10	54 - PJFF Field Finish Painting	11,750	SF	2,441	\$78,233	\$7,619				\$85,852
3.11	50 - Instrumentation	1	EA	3,640	\$119,912	\$65,975				\$185,887
4 Other Common Modifications										
4.1	12 - Other U/G Utility Excavation/Backfi	485	LF	16	\$495		\$299			\$794
4.2	42 - Other Electrical	1	EA	6,888	\$222,838	\$697,265		\$7,200		\$927,303
5 Remainder of Construction										
5.1	Craft Start Up Assistance	100	PC	500	\$22,275					\$22,275
6.1	Craft Inefficiency - Schedule Related	1	LS							
7.1	Craft Inefficiency - Special Conditions	1	LS							
8.1	Construction Equipment Owned & 3rd f	100	LS	1,628	\$51,402		\$6,354,523	\$270,665		\$6,676,590
9.1	Direct Labor Unallocated Supplies	1	LS					\$425,880		\$425,880
10.1	Scaffolding Supplies	1	LS					\$147,000		\$147,000
11.1	Small Tools	1	LS				\$73,439	\$260,000		\$333,439
12.1	Craft Per Diem	1	LS					\$1,619,400		\$1,619,400
17.1	Pre Construction Costs	1	LS							
18.1	Mobilization Cost	1	LS	1,016	\$32,931			\$252,567		\$285,498
18.2	Demobilization Cost	1	LS	100	\$3,289			\$573		\$3,862



Zachry Industrial Incorporated
 Estimate Detail Option "A" Stebbins Tower
 Estimate: PFAQ12042 A
 Zachry Industrial Inc. Custom Report

Code	Description	Quantity	UM	LABOR WORKHOURS	LABOR AMOUNT	MATERIAL AMOUNT	EQUIPMENT AMOUNT	SUBCONTRT AMOUNT	SUPPLIES AMOUNT	TOTAL AMOUNT
20.1	Construction Staff & Expenses	1	LS	94,875	\$4,433,744				\$1,645,050	\$6,078,794
22.1	Support Labor & Indirect Supplies	1	LS	33,495	\$1,000,672		\$10,566		\$1,252,499	\$2,263,737
23.1	Sales Tax	1	Each						\$174,000	\$174,000
24.1	Indirect Sundries	1	LS						\$34,535	\$34,535
25.1	Home Office Support	1	LS	3,513	\$108,847				\$170,166	\$279,013
26.1	Engineering Liason & Expenses	1	LS	2,080	\$174,510				\$48,500	\$223,010
27.1	Cost Based Adjustments	1	LS							
28.1	Engineering	1	LS					\$5,740,866		\$5,740,866
29.1	Enterprise Start Up & Commissioning	1	LS					\$130,930	\$230,457	\$361,387
31.1	Builders Risk	1	EA						\$300,000	\$300,000
32.1	JV 6000 Joint Venture Indirects	1	LS	2,253	\$243,031				\$932,780	\$1,175,811
33.1	Escalation	1	LS		\$30,000		\$87,000		\$4,361,280	\$4,478,280
34.1	Contingency	1	LS							
35.1	General & Administrative	1	LS						\$4,729,000	\$4,729,000
36.1	Fee	1	LS						\$3,407,000	\$3,407,000
Extended Totals by Category				406,750	\$15,074,333	\$57,994,800	\$6,596,947	\$13,464,513	\$20,429,781	\$113,560,374



Zachry Industrial Incorporated
Estimate Details Option "B" Alloy Tower
 Estimate: PFAQ12042 B
 Zachry Industrial Inc. Custom Report

Code	Description	Quantity	UM	LABOR WORKHOURS	LABOR AMOUNT	MATERIAL AMOUNT	EQUIPMENT AMOUNT	SUBCONTRT AMOUNT	SUPPLIES AMOUNT	TOTAL AMOUNT
2 New Unit 3 WFGD										
2.1	WFGD Pipe	8,390	EA	26,160	\$876,802	\$743,203				\$1,620,006
2.2	WFGD Demolition	1	EA	1,050	\$31,138		\$4,518	\$318,549		\$354,205
2.3	WFGD Site Improvments	600	SY	65	\$1,925	\$3,469	\$2,710	\$9,613		\$17,717
2.4	WFGD U/G Utility Excavation/Backfill	2,000	CY	550	\$16,180	\$1,000	\$11,390	\$13,571	\$250	\$42,391
2.5	WFGD Structural Excavation & Backfill	5,000	CY	2,147	\$69,514	\$10,205	\$30,471	\$27,823		\$138,012
2.6	WFGD Piling - Load Bearing	281	EA	1,227	\$38,763			\$1,016,891		\$1,055,654
2.7	WFGD Structural Concrete	3,694	CY	22,781	\$720,399	\$710,532		\$34,170	\$39,402	\$1,504,503
2.8	WFGD Structural Steel - UNIT 3 (W/YE	1,426	TN	31,531	\$1,102,832	\$3,650,695			\$70,808	\$4,824,335
2.9	WFGD Buildings	1	SF					\$2,556,559		\$2,556,559
2.10	WFGD U3 Fire Protection & Detection	1	PC					\$413,646		\$413,646
2.11	WFGD Mechanical Equipment Unit # 3	321	TN	70,187	\$2,378,595	\$55,446,141		\$1,351,650	\$26,250	\$59,202,635
2.12	WFGD Electrical	1	EA	36,163	\$1,220,156	\$1,388,335		\$239,700	\$6,521	\$2,854,711
2.13	WFGD Instrumentation	165	EA	3,600	\$131,742	\$570,345				\$702,087
2.14	Other Piping Insulation U3	23,499	SF					\$461,450		\$461,450
2.15	WFGD 3 Field Finish Painting	21,093	SF	4,253	\$136,318	\$12,513				\$148,831
2.16	WFGD Special Coatings	9,648	SF					\$400,142		\$400,142
3 Unit 3 PJFF Modifications										
3.1	12 - PJFF U/G Utility Excavation/Backfi	1,175	LF	41	\$1,237		\$748			\$1,985
3.2	13 - PJFF Structural Excavation & Back	3,600	CY	1,482	\$48,640	\$10,205	\$21,282	\$19,982		\$100,109
3.3	18 - PJFF Structural Concrete	1,371	CY	8,704	\$276,673	\$258,784		\$12,682	\$25,200	\$573,339
3.4	18 - PJFF Piling - Load Bearing	66	EA					\$1,187,643		\$1,187,643
3.5	20 - PJFF Structural Steel	490	TN	8,862	\$299,678	\$1,193,707				\$1,493,384
3.6	23 - Architectural Demo	1	EA					(\$239,604)		(\$239,604)
3.7	26 - PJFF-Mechanical	1	EA	(4,819)	(\$157,765)	(\$387,581)				(\$545,346)
3.8	42 - PJFF Electrical	1	EA	31,782	\$1,065,779	\$814,281		\$28,800		\$1,908,860
3.9	52 - PJFF Insulation U3	(17,000)	SF					(\$267,750)		(\$267,750)
3.10	54 - PJFF Field Finish Painting	11,750	SF	2,441	\$78,233	\$7,619				\$85,852
3.11	50 - Instrumentation	1	EA	3,640	\$119,912	\$65,975				\$185,887
4 Other Common Modifications										
4.1	12 - Other U/G Utility Excavation/Backfi	485	LF	16	\$495		\$299			\$794
4.2	42 - Other Electrical	1	EA	6,888	\$222,838	\$697,265		\$7,200		\$927,303
5 Remainder of Construction										
5.1	Craft Start Up Assistance	100	PC	500	\$22,275					\$22,275
6.1	Craft Inefficiency - Schedule Related	1	LS							
7.1	Craft Inefficiency - Special Conditions	1	LS							
8.1	Construction Equipment Owned & 3rd f	100	LS	1,138	\$35,838		\$4,736,337		\$200,527	\$4,972,703
9.1	Direct Labor Unallocated Supplies	1	LS						\$404,355	\$404,355
10.1	Scaffolding Supplies	1	LS						\$136,500	\$136,500
11.1	Small Tools	1	LS				\$43,987		\$250,000	\$293,987
12.1	Craft Per Diem	1	LS						\$1,567,700	\$1,567,700
17.1	Pre Construction Costs	1	LS							
18.1	Mobilization Cost	1	LS	1,016	\$32,931				\$236,967	\$269,898
18.2	Demobilization Cost	1	LS	100	\$3,289				\$573	\$3,862



Zachry Industrial Incorporated
 Estimate Details Option "B" Alloy Tower
 Estimate: PFAQ12042 B
 Zachry Industrial Inc. Custom Report

Code	Description	Quantity	UM	LABOR WORKHOURS	LABOR AMOUNT	MATERIAL AMOUNT	EQUIPMENT AMOUNT	SUBCONTRT AMOUNT	SUPPLIES AMOUNT	TOTAL AMOUNT
20.1	Construction Staff & Expenses	1	LS	59,143	\$2,740,101				\$1,047,350	\$3,787,451
22.1	Support Labor & Indirect Supplies	1	LS	34,083	\$1,075,726		\$6,126		\$1,470,247	\$2,552,100
23.1	Sales Tax	1	Each						\$178,980	\$178,980
24.1	Indirect Sundries	1	LS						\$23,592	\$23,592
25.1	Home Office Support	1	LS	2,343	\$76,438				\$167,826	\$244,264
26.1	Engineering Liason & Expenses	1	LS	1,040	\$87,255				\$24,300	\$111,555
27.1	Cost Based Adjustments	1	LS							
28.1	Engineering	1	LS					\$5,380,866		\$5,380,866
29.1	Enterprise Start Up & Commissioning	1	LS					\$130,930	\$230,457	\$361,387
31.1	Builders Risk	1	EA						\$300,000	\$300,000
32.1	JV 6000 Joint Venture Indirects	1	LS	1,387	\$149,616				\$812,480	\$962,096
33.1	Escalation	1	LS		\$15,000		\$59,000		\$3,817,050	\$3,891,050
34.1	Contingency	1	LS							
35.1	General & Administrative	1	LS						\$4,305,000	\$4,305,000
36.1	Fee	1	LS						\$3,448,000	\$3,448,000
Extended Totals by Category				359,499	\$12,918,552	\$65,196,690	\$4,916,870	\$13,104,513	\$18,790,334	\$114,926,958



Zachry Industrial Incorporated
 Estimate Details Option "C" Alloy Tower
 Estimate: PFAQ12042 C
 Zachry Industrial Inc. Custom Report

Code	Description	Quantity	UM	LABOR WORKHOURS	LABOR AMOUNT	MATERIAL AMOUNT	EQUIPMENT AMOUNT	SUBCONTRT AMOUNT	SUPPLIES AMOUNT	TOTAL AMOUNT
2 New Unit 3 WFGD										
2.1	WFGD Pipe	8,390	EA	26,160	\$876,802	\$743,203				\$1,620,006
2.2	WFGD Demolition	1	EA	1,050	\$31,138		\$4,518	\$318,549		\$354,205
2.3	WFGD Site Improvments	600	SY	65	\$1,925	\$3,469	\$2,710	\$9,613		\$17,717
2.4	WFGD U/G Utility Excavation/Backfill	2,000	CY	550	\$16,180	\$1,000	\$11,390	\$13,571	\$250	\$42,391
2.5	WFGD Structural Excavation & Backfill	5,000	CY	2,147	\$69,514	\$10,205	\$30,471	\$27,823		\$138,012
2.6	WFGD Piling - Load Bearing	281	EA	1,227	\$38,763			\$1,016,891		\$1,055,654
2.7	WFGD Structural Concrete	3,694	CY	22,781	\$720,399	\$710,532		\$34,170	\$39,402	\$1,504,503
2.8	WFGD Structural Steel - UNIT 3 (W/YE	1,426	TN	31,531	\$1,102,832	\$3,650,695			\$70,808	\$4,824,335
2.9	WFGD Buildings	1	SF					\$2,556,559		\$2,556,559
2.10	WFGD U3 Fire Protection & Detection	1	PC					\$413,646		\$413,646
2.11	WFGD Mechanical Equipment Unit # 3	321	TN	49,150	\$1,655,606	\$57,346,858		\$1,351,650	\$26,250	\$60,380,364
2.12	WFGD Electrical	1	EA	36,163	\$1,220,156	\$1,388,335		\$239,700	\$6,521	\$2,854,711
2.13	WFGD Instrumentation	165	EA	3,600	\$131,742	\$570,345				\$702,087
2.14	Other Piping Insulation U3	23,499	SF					\$461,450		\$461,450
2.15	WFGD 3 Field Finish Painting	21,093	SF	4,253	\$136,318	\$12,513				\$148,831
2.16	WFGD Special Coatings	9,648	SF					\$400,142		\$400,142
3 Unit 3 PJFF Modifications										
3.1	12 - PJFF U/G Utility Excavation/Backfi	1,175	LF	41	\$1,237		\$748			\$1,985
3.2	13 - PJFF Structural Excavation & Back	3,600	CY	1,482	\$48,640	\$10,205	\$21,282	\$19,982		\$100,109
3.3	18 - PJFF Structural Concrete	1,371	CY	8,704	\$276,673	\$258,784		\$12,682	\$25,200	\$573,339
3.4	18 - PJFF Piling - Load Bearing	66	EA					\$1,187,643		\$1,187,643
3.5	20 - PJFF Structural Steel	490	TN	8,862	\$299,678	\$1,193,707				\$1,493,384
3.6	23 - Architectural Demo	1	EA					(\$239,604)		(\$239,604)
3.7	26 - PJFF-Mechanical	1	EA	(4,819)	(\$157,765)	(\$387,581)				(\$545,346)
3.8	42 - PJFF Electrical	1	EA	31,782	\$1,065,779	\$814,281		\$28,800		\$1,908,860
3.9	52 - PJFF Insulation U3	(17,000)	SF					(\$267,750)		(\$267,750)
3.10	54 - PJFF Field Finish Painting	11,750	SF	2,441	\$78,233	\$7,619				\$85,852
3.11	50 - Instrumentation	1	EA	3,640	\$119,912	\$65,975				\$185,887
4 Other Common Modifications										
4.1	12 - Other U/G Utility Excavation/Backfi	485	LF	16	\$495		\$299			\$794
4.2	42 - Other Electrical	1	EA	6,888	\$222,838	\$697,265		\$7,200		\$927,303
5 Remainder of Construction										
5.1	Craft Start Up Assistance	100	PC	500	\$22,275					\$22,275
6.1	Craft Inefficiency - Schedule Related	1	LS							
7.1	Craft Inefficiency - Special Conditions	1	LS							
8.1	Construction Equipment Owned & 3rd f	100	LS	1,138	\$35,838		\$4,736,337		\$200,527	\$4,972,703
9.1	Direct Labor Unallocated Supplies	1	LS						\$351,330	\$351,330
10.1	Scaffolding Supplies	1	LS						\$126,000	\$126,000
11.1	Small Tools	1	LS				\$43,987		\$230,000	\$273,987
12.1	Craft Per Diem	1	LS						\$1,440,600	\$1,440,600
17.1	Pre Construction Costs	1	LS							
18.1	Mobilization Cost	1	LS	1,016	\$32,931				\$235,267	\$268,198
18.2	Demobilization Cost	1	LS	100	\$3,289				\$573	\$3,862



Zachry Industrial Incorporated
 Estimate Details Option "C" Alloy Tower
 Estimate: PFAQ12042 C
 Zachry Industrial Inc. Custom Report

Code	Description	Quantity	UM	LABOR WORKHOURS	LABOR AMOUNT	MATERIAL AMOUNT	EQUIPMENT AMOUNT	SUBCONTRT AMOUNT	SUPPLIES AMOUNT	TOTAL AMOUNT
20.1	Construction Staff & Expenses	1	LS	59,143	\$2,740,101				\$1,047,350	\$3,787,451
22.1	Support Labor & Indirect Supplies	1	LS	32,157	\$1,011,071		\$6,126		\$1,384,271	\$2,401,469
23.1	Sales Tax	1	Each						\$170,100	\$170,100
24.1	Indirect Sundries	1	LS						\$23,180	\$23,180
25.1	Home Office Support	1	LS	2,343	\$76,438				\$167,826	\$244,264
26.1	Engineering Liason & Expenses	1	LS	1,040	\$87,255				\$24,300	\$111,555
27.1	Cost Based Adjustments	1	LS							
28.1	Engineering	1	LS					\$5,380,866		\$5,380,866
29.1	Enterprise Start Up & Commissioning	1	LS					\$130,930	\$230,457	\$361,387
31.1	Builders Risk	1	EA						\$300,000	\$300,000
32.1	JV 6000 Joint Venture Indirects	1	LS	1,387	\$149,616				\$812,480	\$962,096
33.1	Escalation	1	LS		\$14,000		\$59,000		\$3,709,420	\$3,782,420
34.1	Contingency	1	LS							
35.1	General & Administrative	1	LS						\$4,211,000	\$4,211,000
36.1	Fee	1	LS						\$3,467,000	\$3,467,000
Extended Totals by Category				336,536	\$12,129,908	\$67,097,407	\$4,916,870	\$13,104,513	\$18,300,110	\$115,548,808

Kehm, Charles

From: doleary@babcockpower.com
Sent: Tuesday, September 11, 2012 12:49 PM
To: Wheat, T.W.
Cc: Brumage, Mike; Gappa, Rob (Contract); Gipson, John; Hecker, Thomas; Kehm, Charles; Pryor, Jennifer; Schmidt, Adam; Traphagan, Doug
Subject: RE: LG&E MC AQCS / FW: Mill Creek Unit 3 Budget Price (Riley)

Sorry, my oversight. The Turret will be installed by BPEI's contractor in option B and C.

Thanks Dan.



Dan O'Leary
Project Manager
Riley Power Inc.
5 Neponset Street
Worcester, MA 01606

T: 508-854-3964 F: 508-852-7122

doleary@babcockpower.com
<http://www.babcockpower.com>

From: "Wheat, T.W." <wheattw@zhi.com>
To: "Kehm, Charles" <kehmc@zhi.com>, "Gappa, Rob (Contract)" <GappaR@zhi.com>, "Hecker, Thomas" <heckert@zhi.com>, "Schmidt, Adam" <schmidta@zhi.com>, <doleary@babcockpower.com>
Cc: "Brumage, Mike" <BrumageM@zhi.com>, "Pryor, Jennifer" <pryorj@zhi.com>, "Gipson, John" <gipsonj@zhi.com>, "Traphagan, Doug" <traphagand@zhi.com>, "Wheat, T.W." <wheattw@zhi.com>
Date: 09/11/2012 11:36 AM
Subject: RE: LG&E MC AQCS / FW: Mill Creek Unit 3 Budget Price (Riley)

I was under the assumption that the roof and turret would be installed by BPI for option B & C, the roof and turret are not mentioned in the scope of work for option B, Dan can you clarify this for me?

Thanks,
TW Wheat

The ZACHRY logo, with the word "ZACHRY" in a bold, green, sans-serif font, set against a black rectangular background.

T.W. Wheat
Estimating Executive

Zachry Industrial, Inc.
527 Logwood
San Antonio, Texas 78221
www.zhi.com

wheattw@zhi.com
Office: 210-588-5216
Cell: 210-827-6311
Fax: 210-588-5146

This e-mail may contain confidential and privileged material for the sole use of the intended recipient. Any review, use, distribution or disclosure by others is



**LG&E Air Quality Compliance Program
Mill Creek Unit 3 WFGD System**

**Budget Estimate
September 10, 2012**

A) Base Bid – Stebbins Absorber (No Internals)	
• Base Stebbins Absorber Island Scope	\$43,249,807
• Additional Site Conditions	\$1,374,303
• Schedule – 12 months	
	Total Price <u>\$44,624,110</u>
B) Base Bid – Solid C276 Absorber (No Internals)	
• Base Solid C276 Absorber Island Scope	\$50,647,803
• Additional Site Conditions	\$1,178,197
• Schedule – 9 months (Note)	
	Total Price <u>\$51,826,000</u>
C) Option Bid – Solid C276 Absorber (<u>With</u> Internals)	
• Option Solid C276 Absorber Island Scope	\$52,548,520
• Additional Site Conditions	\$1,178,197
• Schedule – 7 months	
	Total Price <u>\$53,726,717</u>

Note: Zachry has added two months for the installation of internals. BPEI's Construction schedule is seven months.



**LG&E Air Quality Compliance Program
Mill Creek Unit 3 WFGD System**

Scope Description
September 10, 2012

The scope of work included in Item A, Base Bid; Stebbins Absorber with No Internals is as follows:

- Engineering and Project Labor
- Model Study
- Stebbins Absorber
- Oxidation Lances/Trusses/Turret
- Agitators
- Mist Eliminator System
- Recycle Spray Headers
- Spray Nozzles
- Recycle Pumps
- Mist Eliminator Wash System
- Structural Steel
- Piping Systems/ Valves and specialties
- Recycle External Piping
- Quench Water System
- Instruments and Controls
- Hoists and Cranes
- Hydroclone system
- Bleed Pumps

The Additional, site conditions for the Base Bid, Stebbins Absorber is as follows:

- Larger Concrete Pump Truck
- Material Reloading and Unloading Remote to the work area.
- Additional Hydraulic Yard Crane
- Crane Operator
- Additional Support & Supervision
- Additional Small tools & Consumables

The work included in Item B; Base Bid, Solid C276 Absorber with no Internals includes all Item Listed in Item A except as follows:

- Remove Stebbins Absorber
- Replace with Solid C276 Absorber
- Field Construction of Solid C276 Absorber
- Inlet Duct Solid C686



The additional site conditions for the Base Bid, Solid C276 Absorber without Internals is as follows:

- Remote Lay down Labor
- Hydraulic Yard Crane
- Crane Operator
- Additional Support & Supervision
- Additional Small tools and Consumables
- Inefficiency due to two Construction Companies working in the same erection space.

The work included in Item C; Option Bid for the Solid C276 Absorber with the internals installed by BPEI. The work scope is the same as Item B. Plus the following Items:

- Oxidation Air Lances C276
- Oxidation Air Lance Supports C276
- Outlet Duct Seal
- Mist Eliminator and Spray Header Trusses
- Outlet Turret Solid C276
- Agitators
- Mist Eliminator & Wash System (inside vessel)
- Recycle Spray Headers
- Spray Nozzles
- Quench Piping and Nozzles

The additional site conditions are the same as Item B, Solid C276 Absorber without Internals.



**LG&E Air Quality Compliance Program
Mill Creek Unit 3 WFGD System**

**Estimating Assumptions
Stebbins Absorber
September 10, 2012**

1. Oxidation Air Blowers have not been included; the plan is to reuse the existing Atlas Copco Blowers.
2. The underflow tank agitator will be carbon steel rubber lined.
3. All vendors will be the same as unit's ½ & 4 where possible.
4. All Hasleloy Studs will have two nuts, one on either end.
5. Escalation Risk Cap:
 - a. Freight-Stebbins has included 4% per annum through completion of the project, and will place the threshold risk cap at 5% on all truckloads. (2012 basis \$125,000)
 - b. Rebar – Stebbins has allowed 4% per annum to procure late 2014, and will place the threshold risk cap at 5% on 700,000lbs of rebar. (2012 basis value \$0.45/lb)
 - c. Concrete – Stebbins has allowed 4% per annum, and will place the threshold risk cap at 5% on 2500CT, (2012 basis value \$120/CY)
 - d. Resinous Materials – Stebbins has allowed 4% per annum to procure late 2014, and will place the threshold risk cap at 5% (2012 basis value \$130,000).
 - e. Field Labor – Stebbins has allowed 4% per annum, and will place the threshold risk cap at 5% on 42,000 manhours. (2012 basis value \$3,225,000)
6. BPEI is supporting Stebbins by fast tracking engineering, to support Stebbins procurement of major items starting no later than March 2013.
7. BPEI will Purchase all C276 at FNTP. This will lock in the lowest possible price for the Mill Creek Project.
8. FRP material has been escalated at 6% per year.
9. Please note that the C276 price is subject to a ceiling LME spot price for nickel of \$7.83/lb.



**LG&E Air Quality Compliance Program
Mill Creek Unit 3 WFGD System**

**Estimating Assumptions
Solid C276 Absorber
September 10, 2012**

1. Oxidation Air Blowers have not been included; the plan is to reuse the existing Atlas Copco Blowers.
2. The underflow tank agitator will be carbon steel rubber lined.
3. All vendors will be the same as unit's ½ & 4 where possible.
4. All Hasteloy Studs will have two nuts, one on either end.
5. BPEI will purchase all C276 at FNTF.
6. Please note that the C276 price is subject to a ceiling LME spot price for nickel of \$7.83/lb. The unit price for C276 alloy on Units 1, 2 & 4 is \$15.24, Stebbins option. The offer from Special Metals for an Alloy Vessel is \$15.00 per pound. This offer is valid till 1/15/2013 or until Nickel exceeds \$7.83 / LB which ever come first.

Exhibit JNV-3

Update to Mill Creek 3
Retire/Retrofit Decision,
October 2012

Update to Mill Creek 3 Retire/Retrofit Decision



PPL companies

**Generation Planning & Analysis
October 2012**

Table of Contents

1.0 Summary 2

2.0 Updated Assumptions..... 2

 2.1 Capital Costs..... 2

 2.2 Operating Expenses 3

 2.3 In-Service Dates 3

3.0 Updated Analysis 3

4.0 Conclusion..... 5

5.0 Appendix – Annual Revenue Requirements 6

1.0 Summary

On December 15, 2011, the Kentucky Public Service Commission (“KPSC”) approved the unanimous settlement agreement in the 2011 environmental cost recovery (“ECR”) case for LG&E and KU, which included refurbished wet flue gas desulfurization (“WFGD”) equipment, a baghouse, and sulfuric acid mist (“SAM”) mitigation/economizer modifications for Mill Creek 3. The cost assumptions included in the ECR filing for these projects were based on an engineering study completed in March 2011. In December 2011 and July 2012, more detailed engineering studies were prepared with updated estimates for capital and operating costs. Based on these studies, a new WFGD is more economical than a refurbished WFGD for Mill Creek 3. Since building a new WFGD requires a modified Certificate for Public Convenience and Necessity (“Certificate”) and KPSC approval, the Companies updated their 2011 ECR analysis to confirm that retrofitting Mill Creek 3 (versus retiring the unit) is still the most economical option and that the least-cost retrofit option includes a new WFGD.

2.0 Updated Assumptions

2.1 Capital Costs

The 2011 Air Compliance Plan was developed in anticipation of the Companies’ 2011 ECR filing and includes the analysis supporting the decision to retrofit Mill Creek 3. Additional analyses related to Mill Creek 3 were presented in the proceedings to the 2011 ECR case. The capital and operating costs for these analyses were taken from a March 2011 study prepared by Black & Veatch, which included preliminary information from a February 2011 study prepared by Babcock Power Environmental, Inc. (“Babcock”). The WFGD costs in this study (\$74 million) reflected the estimated cost to refurbish the existing WFGD equipment on Mill Creek 4 and connect it to Mill Creek 3, replacing the existing WFGD on Mill Creek 3.

In December 2011, a more detailed engineering study was completed for the Mill Creek 3 projects by Babcock. Based on this study, the capital cost estimate for the Mill Creek 3 WFGD project increased to \$161 million while the capital cost estimate for the baghouse decreased from \$140 million to \$113 million. In addition, the scope of the new baghouse estimate now includes the SAM mitigation/economizer modifications that were previously included as a separate project in the 2011 ECR Plan. In total, the new capital cost estimate for the Mill Creek 3 projects is \$49 million higher than the estimate in the 2011 filing (see Table 1).

Table 1 – Capital Costs with Refurbished WFGD (Nominal \$M)

Equipment	2011 ECR Plan	2012 Update	Difference
WFGD	74	161	86
Baghouse	140	113	-27
SAM Mitigation/Economizer Modifications	10	-	-10
Total	225	274	49

Because of the increase in the Mill Creek 3 WFGD capital costs, the Companies evaluated the cost of building a new WFGD as an alternative to retrofitting the existing Mill Creek 4 WFGD. According to a September 2012 engineering study by Zachry Holdings, Inc., the capital cost for building a new WFGD at

Mill Creek 3 is estimated to be \$132 million. With a new WFGD, the total capital cost of the Mill Creek 3 environmental projects is only \$21 million higher than the estimates in the 2011 ECR filing (see Table 2).

Table 2 – Capital Costs with New WFGD (Nominal \$M)

Equipment	2011 ECR Plan	2012 Update	Change
WFGD	74	132	58
Baghouse	140	113	-27
SAM Mitigation/Economizer Modifications	10	-	-10
Total	225	245	21

2.2 Operating Expenses

Since the 2011 Air Compliance Plan was developed, the estimated operating expenses for the Mill Creek 3 baghouse have decreased (see Table 3; operating expenses for other Mill Creek projects are unchanged). When the 2011 Air Compliance Plan was developed, the Companies had limited operating experience with the Trimble County 2 baghouse. The updated operating expense estimates are based on almost two years of experience operating the Trimble County 2 baghouse.

Table 3 – Baghouse Operating Expenses (2011 \$)

Operating Expenses	2011 ECR Plan	2012 Update	Change
Variable O&M (\$/MWh)	2.76	1.45	-1.31
Fixed O&M (\$M/yr)	1.2	0.6	-0.6

2.3 In-Service Dates

The schedule for completing the ECR projects at Mill Creek 3 has also changed due to the available space to construct the new Unit 3 WFGD requires the demolition of Unit 4's current WFGD to make the available space. This results in demolition of the existing Unit 4 WFGD beginning in the fall of 2014 when the tie-in outage of Unit 4 to its new WFGD and PJFF occur. Table 4 summarizes these changes.

Table 4 – Project In-Service Dates

Equipment	2011 ECR Plan	2012 Update
WFGD	11/2014	4/2016
Baghouse	10/2015	4/2016
SAM Mitigation	4/2013	4/2016

3.0 Updated Analysis

Table 5 summarizes the net present value of revenue requirements ("NPVRR") for two generation portfolios used in the proceedings to the 2011 ECR case to evaluate the decision to retire or retrofit Mill Creek 3. The total NPVRR differences in Table 5 are taken from the 2011 Air Compliance Plan and Supplemental Analysis. In the 'Retrofit Mill Creek 3' portfolio, Mill Creek 3 is retrofitted per the schedule summarized in Table 4. In the 'Retire Mill Creek 3' portfolio, Mill Creek 3 is retired in

December 2015. In the Base and CERA fuel price scenarios, the NPVRR savings associated with retrofitting Mill Creek 3 are \$756 and \$338 million, respectively.

Table 5 – NPVRR from 2011 ECR Filing: Mill Creek 3 Retire/Retrofit Decision (2011 \$M)

Fuel Price Scenario	NPVRR								
	Retrofit Mill Creek 3			Retire Mill Creek 3			Difference		
	Prod Cost	Capital	Total	Prod Cost	Capital	Total	Prod Cost	Capital	Total
Base	26,152	6,634	32,786	26,848	6,693	33,542	696	60	756
CERA	24,276	6,634	30,910	24,562	6,686	31,247	286	52	338

As discussed above, the updated capital and operating cost estimates for the Mill Creek 3 baghouse project have decreased while the capital cost estimate for the Mill Creek 3 WFGD project has increased. In the Base fuel price scenario, increasing the WFGD capital cost from \$74 to \$132 million increases NPVRR by \$43 million, while the reductions in baghouse capital and operating expenses reduce NPVRR by \$107 million. Clearly, the reductions in revenue requirements associated with the lower baghouse capital and operating expenses more than offset the increase in revenue requirements associated with the higher WFGD capital cost.

Table 6 summarizes the NPVRR of the two generating portfolios with updated cost estimates and project in-service dates. The NPVRR values in Table 6 reflect the cost of the new WFGD (\$132 million) since this alternative is less expensive than the updated cost of the refurbished WFGD (\$161 million). All other assumptions from the 2011 ECR filing are unchanged.¹ Based on the updated cost estimates (and despite the increase in the WFGD capital cost), the savings associated with retrofitting Mill Creek 3 are greater than the savings evaluated in the 2011 ECR filing.

Table 6 – Updated Mill Creek 3 Retire/Retrofit Decision (2011 \$M)

Fuel Price Scenario	NPVRR								
	Retrofit Mill Creek 3			Retire Mill Creek 3			Difference		
	Prod Cost	Capital	Total	Prod Cost	Capital	Total	Prod Cost	Capital	Total
Base	26,085	6,637	32,722	26,848	6,693	33,542	763	57	820
CERA	24,209	6,637	30,846	24,562	6,686	31,247	353	49	402

A modified Certificate and KPSC approval are required to proceed with the least-cost plan to construct a new WFGD for Mill Creek 3. However, due to project lead times, KPSC approval must be received on an expedited basis to place the WFGD in-service by the April 2016 compliance deadline for the Mercury and Air Toxics Standard. If KPSC approval is not received as requested, the Companies must either (a) proceed with the original more-costly plan to refurbish the Mill Creek 4 WFGD and connect it to Mill Creek 3 or (b) wait for KPSC approval and plan to place Mill Creek 3 on inactive reserve after April 2016 until the new WFGD can be commissioned.

To identify the least-cost way forward in the event of a delayed KPSC decision, the Companies' compared the revenue requirements of the 'Refurbished WFGD' option to a 'New WFGD – Delayed In-Service Date' option. In the latter option, the in-service date for the new WFGD is delayed by 6 months, during which the Companies enter into a power purchase agreement ("PPA") for capacity and energy to

¹ Please see Appendix A in the 2011 Air Compliance Plan for a summary of these assumptions.

replace Mill Creek 3. The cost of the PPA is assumed to be \$58/kW-year or \$19 million (in 2016 \$).² Based on the results in Table 7 and

Table 8, if the Companies do not receive approval on an expedited basis, the least-cost way forward is to proceed with the plan to refurbish the Mill Creek 4 WFGD and connect it to Mill Creek 3.

Table 7 – NPVRR of ‘Refurbished WFGD’ Option (2011 \$M)

Fuel Price Scenario	NPVRR								
	Retrofit Mill Creek 3			Retire Mill Creek 3			Difference		
	Prod Cost	Capital	Total	Prod Cost	Capital	Total	Prod Cost	Capital	Total
Base	26,085	6,662	32,748	26,848	6,693	33,542	763	31	794
CERA	24,209	6,662	30,872	24,562	6,686	31,247	353	23	376

Table 8 – NPVRR of ‘New WFGD – Delayed In-Service Date’ Option (2011 \$M)

Fuel Price Scenario	NPVRR								
	Retrofit Mill Creek 3			Retire Mill Creek 3			Difference		
	Prod Cost	Capital	Total	Prod Cost	Capital	Total	Prod Cost	Capital	Total
Base	26,122	6,638	32,760	26,848	6,693	33,542	727	55	782
CERA	24,240	6,638	30,878	24,562	6,686	31,247	322	48	370

Annual revenue requirements for all of the options considered in this analysis are included in the Appendix.

4.0 Conclusion

Table 9 summarizes the NPVRR savings for all options considered. Based on updated capital and operating cost estimates, the NPVRR savings associated with retrofitting Mill Creek 3 are greater than the savings presented in the 2011 ECR filing. Provided that the companies receive a modified Certificate on an expedited basis, a new WFGD is more economical for Mill Creek 3 than a refurbished WFGD.

Table 9 – NPVRR Savings Associated with Retrofitting Mill Creek 3 (2011 \$M)

Gas Price	2011 ECR Plan	2012 Update		
		Least-Cost Option	Delay Options	
		New WFGD 4/2016	Refurbished WFGD 4/2016	New WFGD 10/2016 with PPA
Base Case	756	820	794	782
2011 CERA	338	402	376	370

² The cost of the PPA includes the cost of firm gas transportation and 330 MW of simple-cycle combustion turbine (“SCCT”) capacity. Approximately 330 MW is needed to maintain a 16% reserve margin. The cost of SCCT capacity is based on a response to the Companies’ December 2010 RFP for generating capacity and energy.

5.0 Appendix – Annual Revenue Requirements

Appendix Table 1 – 2011 ECR Plan; Base Fuel Price Scenario (\$M)

Year	Retrofit Mill Creek 3			Retire Mill Creek 3			Difference		
	Prod Costs	Capital	Total	Prod Costs	Capital	Total	Prod Costs	Capital	Total
2011	1,142	7	1,148	1,142	7	1,148	0	0	0
2012	1,222	48	1,270	1,222	46	1,269	0	-1	-1
2013	1,264	129	1,393	1,262	125	1,387	-2	-4	-6
2014	1,353	274	1,627	1,349	296	1,645	-4	23	19
2015	1,449	427	1,876	1,442	474	1,915	-8	47	40
2016	1,586	554	2,140	1,608	585	2,193	22	30	53
2017	1,623	582	2,204	1,604	578	2,182	-19	-4	-22
2018	1,682	601	2,283	1,706	563	2,269	23	-37	-14
2019	1,765	597	2,362	1,818	556	2,374	54	-41	12
2020	1,834	584	2,418	1,916	586	2,502	82	2	84
2021	1,938	576	2,513	2,048	618	2,667	111	43	153
2022	2,070	605	2,675	2,125	638	2,763	55	33	88
2023	2,143	639	2,783	2,164	633	2,797	21	-6	14
2024	2,148	662	2,809	2,236	616	2,852	88	-46	43
2025	2,247	662	2,909	2,363	612	2,976	117	-50	66
2026	2,382	651	3,033	2,535	651	3,187	153	1	154
2027	2,389	640	3,029	2,525	694	3,220	137	54	191
2028	2,494	634	3,128	2,595	720	3,316	102	86	188
2029	2,543	683	3,225	2,615	725	3,340	72	42	115
2030	2,683	735	3,419	2,730	715	3,445	47	-20	27
2031	2,657	765	3,422	2,771	700	3,471	115	-65	49
2032	2,715	771	3,486	2,851	699	3,551	136	-71	65
2033	2,829	756	3,584	2,973	730	3,703	144	-25	118
2034	2,887	743	3,630	3,052	765	3,817	165	22	187
2035	2,987	740	3,727	3,079	788	3,867	92	48	140
2036	3,062	735	3,797	3,157	773	3,929	95	38	132
2037	3,116	737	3,854	3,223	752	3,975	107	15	121
2038	3,239	668	3,907	3,357	667	4,024	118	-1	117
2039	3,257	654	3,912	3,393	662	4,054	135	7	143
2040	3,401	631	4,032	3,524	647	4,171	123	15	138
NPVRR	26,152	6,634	32,786	26,848	6,693	33,542	696	60	756

Appendix Table 2 – 2011 ECR Plan; CERA Fuel Price Scenario (\$M)

Year	Retrofit Mill Creek 3			Retire Mill Creek 3			Difference		
	Prod Costs	Capital	Total	Prod Costs	Capital	Total	Prod Costs	Capital	Total
2011	1,142	7	1,148	1,142	7	1,148	0	0	0
2012	1,207	48	1,254	1,207	46	1,253	0	-1	-1
2013	1,251	129	1,381	1,249	125	1,374	-2	-4	-6
2014	1,290	274	1,563	1,286	296	1,582	-4	23	19
2015	1,366	427	1,793	1,359	474	1,833	-8	47	40
2016	1,493	554	2,047	1,504	585	2,089	12	30	42
2017	1,502	582	2,083	1,476	578	2,054	-26	-4	-29
2018	1,590	601	2,190	1,593	563	2,156	3	-37	-34
2019	1,602	597	2,200	1,632	556	2,188	30	-41	-12
2020	1,648	584	2,232	1,695	586	2,281	47	2	50
2021	1,752	576	2,328	1,824	618	2,442	72	43	114
2022	1,868	605	2,473	1,878	638	2,516	10	33	43
2023	1,921	639	2,560	1,901	633	2,534	-20	-6	-26
2024	1,879	662	2,541	1,908	616	2,524	29	-46	-17
2025	1,955	662	2,617	2,001	605	2,607	47	-57	-10
2026	2,051	651	2,702	2,129	602	2,731	78	-49	29
2027	2,118	640	2,758	2,191	615	2,806	73	-25	48
2028	2,159	634	2,793	2,231	663	2,894	72	29	101
2029	2,253	683	2,936	2,324	717	3,041	71	34	105
2030	2,389	735	3,125	2,388	752	3,140	-1	17	16
2031	2,408	765	3,174	2,447	750	3,197	39	-15	23
2032	2,499	771	3,269	2,549	741	3,290	50	-29	21
2033	2,620	756	3,376	2,675	734	3,409	55	-22	33
2034	2,721	743	3,464	2,787	764	3,551	66	21	87
2035	2,832	740	3,571	2,895	799	3,694	63	59	122
2036	2,951	735	3,686	2,970	810	3,780	19	74	94
2037	3,040	737	3,778	3,068	800	3,869	28	63	91
2038	3,180	668	3,848	3,207	705	3,912	27	37	64
2039	3,254	654	3,909	3,299	677	3,977	45	23	68
2040	3,412	631	4,043	3,464	648	4,112	52	17	69
NPVRR	24,276	6,634	30,910	24,562	6,686	31,247	286	52	338

Appendix Table 3 – New WFGD 4/2016; Base Fuel Price Scenario (\$M)

Year	Retrofit Mill Creek 3			Retire Mill Creek 3			Difference		
	Prod Costs	Capital	Total	Prod Costs	Capital	Total	Prod Costs	Capital	Total
2011	1,142	7	1,148	1,142	7	1,148	0	0	0
2012	1,222	47	1,269	1,222	46	1,269	0	-1	-1
2013	1,262	123	1,385	1,262	125	1,387	0	2	2
2014	1,349	265	1,614	1,349	296	1,645	0	32	32
2015	1,442	420	1,862	1,442	474	1,915	0	54	54
2016	1,578	556	2,134	1,608	585	2,193	30	29	59
2017	1,618	585	2,203	1,604	578	2,182	-14	-7	-21
2018	1,677	604	2,281	1,706	563	2,269	28	-41	-12
2019	1,760	600	2,360	1,818	556	2,374	59	-45	14
2020	1,829	587	2,415	1,916	586	2,502	87	-1	86
2021	1,932	578	2,511	2,048	618	2,667	116	40	156
2022	2,065	608	2,672	2,125	638	2,763	61	30	91
2023	2,138	642	2,780	2,164	633	2,797	26	-9	17
2024	2,142	665	2,806	2,236	616	2,852	94	-48	46
2025	2,241	665	2,906	2,363	612	2,976	122	-53	70
2026	2,376	653	3,029	2,535	651	3,187	159	-2	157
2027	2,383	642	3,025	2,525	694	3,220	142	53	195
2028	2,487	636	3,123	2,595	720	3,316	108	85	193
2029	2,536	684	3,220	2,615	725	3,340	78	41	119
2030	2,677	737	3,413	2,730	715	3,445	53	-21	32
2031	2,650	767	3,417	2,771	700	3,471	121	-67	54
2032	2,708	772	3,480	2,851	699	3,551	143	-72	71
2033	2,822	757	3,579	2,973	730	3,703	151	-27	124
2034	2,880	745	3,624	3,052	765	3,817	172	21	193
2035	2,981	741	3,722	3,079	788	3,867	99	47	145
2036	3,054	736	3,791	3,157	773	3,929	102	36	139
2037	3,109	738	3,848	3,223	752	3,975	114	14	127
2038	3,231	669	3,900	3,357	667	4,024	125	-2	124
2039	3,250	656	3,906	3,393	662	4,054	143	6	149
2040	3,393	633	4,026	3,524	647	4,171	131	13	145
NPVRR	26,085	6,637	32,722	26,848	6,693	33,542	763	57	820

Appendix Table 4 – New WFGD 4/2016; CERA Fuel Price Scenario (\$M)

Year	Retrofit Mill Creek 3			Retire Mill Creek 3			Difference		
	Prod Costs	Capital	Total	Prod Costs	Capital	Total	Prod Costs	Capital	Total
2011	1,142	7	1,148	1,142	7	1,148	0	0	0
2012	1,207	47	1,254	1,207	46	1,253	0	-1	-1
2013	1,249	123	1,373	1,249	125	1,374	0	2	2
2014	1,286	265	1,551	1,286	296	1,582	0	32	32
2015	1,359	420	1,779	1,359	474	1,833	0	54	54
2016	1,485	556	2,041	1,504	585	2,089	19	29	48
2017	1,497	585	2,082	1,476	578	2,054	-21	-7	-28
2018	1,585	604	2,189	1,593	563	2,156	8	-41	-32
2019	1,598	600	2,198	1,632	556	2,188	34	-45	-10
2020	1,643	587	2,229	1,695	586	2,281	53	-1	52
2021	1,747	578	2,326	1,824	618	2,442	77	40	117
2022	1,862	608	2,470	1,878	638	2,516	16	30	46
2023	1,915	642	2,558	1,901	633	2,534	-14	-9	-23
2024	1,873	665	2,538	1,908	616	2,524	35	-48	-13
2025	1,949	665	2,614	2,001	605	2,607	53	-60	-7
2026	2,045	653	2,698	2,129	602	2,731	84	-51	33
2027	2,112	642	2,754	2,191	615	2,806	79	-27	52
2028	2,152	636	2,788	2,231	663	2,894	79	27	106
2029	2,247	684	2,931	2,324	717	3,041	77	33	110
2030	2,383	737	3,119	2,388	752	3,140	6	15	21
2031	2,402	767	3,169	2,447	750	3,197	45	-17	29
2032	2,492	772	3,264	2,549	741	3,290	57	-31	26
2033	2,613	757	3,371	2,675	734	3,409	61	-23	38
2034	2,714	745	3,458	2,787	764	3,551	73	20	93
2035	2,825	741	3,566	2,895	799	3,694	69	58	128
2036	2,943	736	3,680	2,970	810	3,780	27	73	100
2037	3,033	738	3,771	3,068	800	3,869	35	62	97
2038	3,172	669	3,841	3,207	705	3,912	35	36	71
2039	3,246	656	3,902	3,299	677	3,977	53	21	74
2040	3,403	633	4,037	3,464	648	4,112	60	15	76
NPVRR	24,209	6,637	30,846	24,562	6,686	31,247	353	49	402

Appendix Table 5 – Refurbished WFGD 4/2016; Base Fuel Price Scenario (\$M)

Year	Retrofit Mill Creek 3			Retire Mill Creek 3			Difference		
	Prod Costs	Capital	Total	Prod Costs	Capital	Total	Prod Costs	Capital	Total
2011	1,142	7	1,148	1,142	7	1,148	0	0	0
2012	1,222	47	1,269	1,222	46	1,269	0	-1	-1
2013	1,262	123	1,385	1,262	125	1,387	0	2	2
2014	1,349	265	1,614	1,349	296	1,645	0	31	31
2015	1,442	422	1,863	1,442	474	1,915	0	52	52
2016	1,578	560	2,138	1,608	585	2,193	30	25	55
2017	1,618	589	2,207	1,604	578	2,182	-14	-11	-25
2018	1,677	607	2,285	1,706	563	2,269	28	-44	-16
2019	1,760	604	2,364	1,818	556	2,374	59	-48	11
2020	1,829	590	2,418	1,916	586	2,502	87	-4	83
2021	1,932	582	2,514	2,048	618	2,667	116	37	153
2022	2,065	611	2,675	2,125	638	2,763	61	27	88
2023	2,138	645	2,783	2,164	633	2,797	26	-12	14
2024	2,142	667	2,809	2,236	616	2,852	94	-51	43
2025	2,241	668	2,908	2,363	612	2,976	122	-55	67
2026	2,376	655	3,031	2,535	651	3,187	159	-4	155
2027	2,383	644	3,027	2,525	694	3,220	142	51	193
2028	2,487	638	3,125	2,595	720	3,316	108	83	191
2029	2,536	686	3,222	2,615	725	3,340	78	39	117
2030	2,677	739	3,415	2,730	715	3,445	53	-23	30
2031	2,650	769	3,419	2,771	700	3,471	121	-69	52
2032	2,708	774	3,482	2,851	699	3,551	143	-74	69
2033	2,822	759	3,581	2,973	730	3,703	151	-28	122
2034	2,880	746	3,626	3,052	765	3,817	172	19	191
2035	2,981	742	3,723	3,079	788	3,867	99	45	144
2036	3,054	738	3,792	3,157	773	3,929	102	35	137
2037	3,109	740	3,849	3,223	752	3,975	114	12	126
2038	3,231	670	3,902	3,357	667	4,024	125	-3	122
2039	3,250	657	3,907	3,393	662	4,054	143	4	147
2040	3,393	635	4,027	3,524	647	4,171	131	12	143
NPVRR	26,085	6,662	32,748	26,848	6,693	33,542	763	31	794

Appendix Table 6 – Refurbished WFGD 4/2016; CERA Fuel Price Scenario (\$M)

Year	Retrofit Mill Creek 3			Retire Mill Creek 3			Difference		
	Prod Costs	Capital	Total	Prod Costs	Capital	Total	Prod Costs	Capital	Total
2011	1,142	7	1,148	1,142	7	1,148	0	0	0
2012	1,207	47	1,254	1,207	46	1,253	0	-1	-1
2013	1,249	123	1,373	1,249	125	1,374	0	2	2
2014	1,286	265	1,551	1,286	296	1,582	0	31	31
2015	1,359	422	1,781	1,359	474	1,833	0	52	52
2016	1,485	560	2,045	1,504	585	2,089	19	25	44
2017	1,497	589	2,086	1,476	578	2,054	-21	-11	-32
2018	1,585	607	2,192	1,593	563	2,156	8	-44	-36
2019	1,598	604	2,201	1,632	556	2,188	34	-48	-14
2020	1,643	590	2,232	1,695	586	2,281	53	-4	49
2021	1,747	582	2,329	1,824	618	2,442	77	37	114
2022	1,862	611	2,473	1,878	638	2,516	16	27	43
2023	1,915	645	2,560	1,901	633	2,534	-14	-12	-26
2024	1,873	667	2,540	1,908	616	2,524	35	-51	-16
2025	1,949	668	2,616	2,001	605	2,607	53	-62	-10
2026	2,045	655	2,700	2,129	602	2,731	84	-53	31
2027	2,112	644	2,756	2,191	615	2,806	79	-29	50
2028	2,152	638	2,790	2,231	663	2,894	79	25	104
2029	2,247	686	2,933	2,324	717	3,041	77	31	108
2030	2,383	739	3,121	2,388	752	3,140	6	14	19
2031	2,402	769	3,170	2,447	750	3,197	45	-19	27
2032	2,492	774	3,266	2,549	741	3,290	57	-32	25
2033	2,613	759	3,372	2,675	734	3,409	61	-25	36
2034	2,714	746	3,460	2,787	764	3,551	73	18	91
2035	2,825	742	3,567	2,895	799	3,694	69	57	126
2036	2,943	738	3,681	2,970	810	3,780	27	72	99
2037	3,033	740	3,773	3,068	800	3,869	35	60	96
2038	3,172	670	3,842	3,207	705	3,912	35	35	70
2039	3,246	657	3,904	3,299	677	3,977	53	20	73
2040	3,403	635	4,038	3,464	648	4,112	60	14	74
NPVRR	24,209	6,662	30,872	24,562	6,686	31,247	353	23	376

Appendix Table 7 – New WFGD 10/2016; Base Fuel Price Scenario (\$M)

Year	Retrofit Mill Creek 3			Retire Mill Creek 3			Difference		
	Prod Costs	Capital	Total	Prod Costs	Capital	Total	Prod Costs	Capital	Total
2011	1,142	7	1,148	1,142	7	1,148	0	0	0
2012	1,222	47	1,269	1,222	46	1,269	0	-1	-1
2013	1,262	123	1,385	1,262	125	1,387	0	2	2
2014	1,349	265	1,614	1,349	296	1,645	0	31	31
2015	1,442	420	1,862	1,442	474	1,915	0	54	54
2016	1,629	554	2,183	1,608	585	2,193	-20	31	10
2017	1,618	586	2,204	1,604	578	2,182	-14	-8	-22
2018	1,677	604	2,281	1,706	563	2,269	28	-41	-13
2019	1,760	601	2,361	1,818	556	2,374	59	-45	14
2020	1,829	587	2,416	1,916	586	2,502	87	-1	86
2021	1,932	579	2,511	2,048	618	2,667	116	39	155
2022	2,065	608	2,673	2,125	638	2,763	61	30	90
2023	2,138	642	2,780	2,164	633	2,797	26	-10	17
2024	2,142	665	2,807	2,236	616	2,852	94	-49	45
2025	2,241	665	2,906	2,363	612	2,976	122	-53	69
2026	2,376	653	3,029	2,535	651	3,187	159	-2	157
2027	2,383	642	3,025	2,525	694	3,220	142	52	194
2028	2,487	636	3,123	2,595	720	3,316	108	84	192
2029	2,536	684	3,221	2,615	725	3,340	78	41	119
2030	2,677	737	3,414	2,730	715	3,445	53	-22	32
2031	2,650	767	3,417	2,771	700	3,471	121	-67	54
2032	2,708	772	3,480	2,851	699	3,551	143	-73	70
2033	2,822	757	3,579	2,973	730	3,703	151	-27	124
2034	2,880	745	3,625	3,052	765	3,817	172	20	193
2035	2,981	741	3,722	3,079	788	3,867	99	47	145
2036	3,054	737	3,791	3,157	773	3,929	102	36	139
2037	3,109	739	3,848	3,223	752	3,975	114	13	127
2038	3,231	669	3,901	3,357	667	4,024	125	-2	124
2039	3,250	656	3,906	3,393	662	4,054	143	5	148
2040	3,393	634	4,026	3,524	647	4,171	131	13	144
NPVRR	26,122	6,638	32,760	26,848	6,693	33,542	727	55	782

Appendix Table 8 – New WFGD 10/2016; CERA Fuel Price Scenario (\$M)

Year	Retrofit Mill Creek 3			Retire Mill Creek 3			Difference		
	Prod Costs	Capital	Total	Prod Costs	Capital	Total	Prod Costs	Capital	Total
2011	1,142	7	1,148	1,142	7	1,148	0	0	0
2012	1,207	47	1,254	1,207	46	1,253	0	-1	-1
2013	1,249	123	1,373	1,249	125	1,374	0	2	2
2014	1,286	265	1,551	1,286	296	1,582	0	31	31
2015	1,359	420	1,779	1,359	474	1,833	0	54	54
2016	1,527	554	2,081	1,504	585	2,089	-23	31	8
2017	1,497	586	2,083	1,476	578	2,054	-21	-8	-29
2018	1,585	604	2,189	1,593	563	2,156	8	-41	-33
2019	1,598	601	2,198	1,632	556	2,188	34	-45	-11
2020	1,643	587	2,230	1,695	586	2,281	53	-1	52
2021	1,747	579	2,326	1,824	618	2,442	77	39	116
2022	1,862	608	2,470	1,878	638	2,516	16	30	46
2023	1,915	642	2,558	1,901	633	2,534	-14	-10	-24
2024	1,873	665	2,538	1,908	616	2,524	35	-49	-14
2025	1,949	665	2,614	2,001	605	2,607	53	-60	-7
2026	2,045	653	2,698	2,129	602	2,731	84	-51	33
2027	2,112	642	2,754	2,191	615	2,806	79	-27	51
2028	2,152	636	2,788	2,231	663	2,894	79	27	106
2029	2,247	684	2,931	2,324	717	3,041	77	32	110
2030	2,383	737	3,120	2,388	752	3,140	6	15	21
2031	2,402	767	3,169	2,447	750	3,197	45	-17	28
2032	2,492	772	3,264	2,549	741	3,290	57	-31	26
2033	2,613	757	3,371	2,675	734	3,409	61	-24	38
2034	2,714	745	3,458	2,787	764	3,551	73	20	93
2035	2,825	741	3,566	2,895	799	3,694	69	58	127
2036	2,943	737	3,680	2,970	810	3,780	27	73	100
2037	3,033	739	3,772	3,068	800	3,869	35	61	97
2038	3,172	669	3,841	3,207	705	3,912	35	36	71
2039	3,246	656	3,903	3,299	677	3,977	53	21	74
2040	3,403	634	4,037	3,464	648	4,112	60	15	75
NPVRR	24,240	6,638	30,878	24,562	6,686	31,247	322	48	370