## **EXHIBIT O** Options

Owner shall have the option, through a Change Order, to have Contractor provide a similar scope (i.e., engineering, procuring, and constructing) to add a PJFF to Unit 1 or Unit 2 or both.

ltems	Costs
Electrostatic Precipitators (ESPs)	
Demolition of Existing ESPs 3-1A and 3-2A and Auxiliary Equipment	
Demolition of Existing ESP 3-1 (at the same time as ESPs 3-1A and 3-2A) and Auxiliary Equipment	
Relocate NFPA Suction between ID Fans and PJFF.	
Remove Scope associated with Sump Pumps, Agitator and Piping (Leave in the Sump and add Trenches in Grade Slab).	
Credit Price to DEDUCT robust mobile platform from base pricing (to access upper poke holes in the PJFF hopper area).	
Option Price to mobilize small receiving crew by 3/10/14 to receive CBPG equipment. Pricing includes indirect equipment and craft costs.	
Add price to supply the cost associated with a CB shop fabricated supply vs. CB loose pipe and fitting supply for Complete Package (CB providing enough quantity for standard waste).	
Add price to supply the cost associated with a CB shop fabricated supply vs. CB loose pipe and fitting supply for the PAC Injection System Only (CB providing enough quantity for standard waste).	
Add price to supply & install 28 ea 4" flanged full port SS ball valves for port isolation and rated 400 degs F w/ peek seats.	
Add price to supply & install 28 ea 4" flanged full port CS ball valves for port isolation and rated 400 degs F w/ peek seats.	