

Contents

<b>Executive Summary</b>	<b>1</b>
ES.1. Purpose and Scope of Project .....	1
ES.2. Hydraulic Model Update and Analysis .....	2
ES.2.1. Population and Demand Projections .....	2
ES.2.2. Treatment Capacity Expansion .....	3
ES.2.3. Pumping and Storage Analysis .....	3
ES.2.4. Recommended Hydraulic Improvements .....	4
ES.3. Asset Management .....	5
ES.3.1. Condition Assessment for Existing Assets .....	6
ES.3.2. Recommended R&R Improvements for Existing Assets .....	7
ES.3.3. Recommendations for Asset Management Program .....	9
ES.3.4. Recommendations for Additional Studies .....	12
ES.4. IT Master Plan .....	13
ES.4.1. Information Systems Assessment .....	13
ES.5. Funding Strategy .....	14
ES.5.1. Development of Strategy .....	14
ES.5.2. Scenarios .....	14
ES.5.3. Summary of Costs .....	16
ES.5.4. Financial Analysis .....	16
ES.5.5. Financial Summary .....	19
<b>1. Hydraulic Model Update and Analyses</b>	<b>1-1</b>
1.1. Introduction .....	1-1
1.2. Existing System Facilities .....	1-1
1.2.1. Distribution System Overview .....	1-1
1.2.1.1. Fort Thomas & Memorial Parkway WTP Service Areas .....	1-3
1.2.1.2. Taylor Mill WTP Service Areas .....	1-3
1.2.1.3. Wholesale Supply .....	1-3
1.2.2. System Pumping .....	1-4
1.2.3. System Storage .....	1-5
1.2.4. SCADA and Controls .....	1-7
1.2.4.1. Data Acquisition .....	1-7
1.2.4.2. Pump Controls .....	1-7
1.3. Water Demand .....	1-8
1.3.1. Introduction .....	1-8
1.3.2. Data Sources .....	1-9
1.3.3. Landuse Assignment .....	1-9
1.3.3.1. Classifications .....	1-9
1.3.3.2. 2020 and 2030 Development .....	1-10
1.3.4. Consumption .....	1-14
1.3.5. Population Projections .....	1-18
1.4. Supply and Storage Requirements .....	1-18
1.4.1. Introduction .....	1-18
1.4.2. Supply Gap Analysis .....	1-19
1.4.3. Storage Gap Analysis .....	1-22
1.5. Model Development and Calibration .....	1-25
1.5.1. Background .....	1-25

1.5.2. Model Demand ..... 1-25

1.5.3. Model Calibration ..... 1-26

1.6. Existing System Performance Analysis ..... 1-27

1.6.1. Average Day Demand Analysis ..... 1-28

1.6.2. Maximum Day Demand Analysis ..... 1-29

1.6.3. Pump Curve Analysis ..... 1-35

1.7. Future System Analysis ..... 1-43

1.7.1. 2020 Analysis ..... 1-43

1.7.2. 2030 Analysis ..... 1-44

1.7.3. Bullock Pen Analysis ..... 1-46

1.8. Recommended Improvements..... 1-47

1.8.1. Existing System..... 1-47

1.8.1.1. Existing System Tanks ..... 1-49

1.8.1.2. Existing System Pipe Improvements..... 1-49

1.8.1.3. Other Existing System Improvements ..... 1-49

1.8.2. 2010 - 2020 Improvements ..... 1-50

1.8.2.1. 2010-2020 System Tanks ..... 1-52

1.8.2.2. 2010-2020 System Pump Stations..... 1-52

1.8.2.3. 2010-2020 System Pipe Improvements ..... 1-53

1.8.3. 2020-2030 Improvements ..... 1-53

1.8.3.1. 2020-2030 System Tanks ..... 1-55

1.8.3.2. 2020-2030 System Pump Stations..... 1-55

1.8.3.3. 2020-2030 System Pipe Improvements ..... 1-55

1.8.4. Other Improvements..... 1-55

1.9. Conclusions..... 1-56

**2. Asset Management Plan 2-1**

2.1. Introduction ..... 2-1

2.2. Above Ground Asset Inventory and Hierarchies..... 2-3

2.2.1. Current AwwaRF and Antero Asset Hierarchy..... 2-4

2.2.2. Asset Hierarchy – Summary Recommendations ..... 2-4

2.2.2.1. Five to Six Level Asset Hierarchy..... 2-5

2.2.2.2. Water Distribution at the Facility Level ..... 2-6

2.2.3. Asset Attribute Data ..... 2-8

2.3. Asset Condition Assessment ..... 2-8

2.3.1. Physical Condition Assessment ..... 2-8

2.3.2. Summary of Results ..... 2-8

2.3.3. Summary of Recommendations ..... 2-11

2.4. Above Ground Asset Criticality ..... 2-13

2.4.1. Criticality Approach ..... 2-13

2.4.2. Summary of Results ..... 2-14

2.4.3. Summary of Recommendations ..... 2-16

2.5. Asset Renewal and Replacement (R&R) Planning ..... 2-16

2.5.1. R&R Evaluation Alternatives ..... 2-16

2.5.1.1. Asset Priority Evaluation Approach – 5 yr CIP ..... 2-17

2.5.1.2. Effective Useful Life ..... 2-17

2.5.2. Summary of Results ..... 2-18

2.5.3. Summary of Recommendations ..... 2-19

2.5.3.1. Effective Useful Life Approach ..... 2-19

2.6. Proposed Performance Measures ..... 2-21

<b>3. Information Systems Assessment and Technology Master Plan</b>	<b>3-1</b>
3.1. Introduction .....	3-1
3.2. Overview .....	3-1
3.3. Approach.....	3-2
3.3.1. Information Systems Assessment.....	3-2
3.3.2. Business Process Inventory.....	3-3
3.3.3. Systems and Data Assessment .....	3-3
3.3.4. IT Projects Planning .....	3-4
3.3.5. IT Governance Recommendations Development .....	3-4
3.4. Summary of Recommendations.....	3-4
3.4.1. Geographic Information Systems Environment.....	3-5
3.4.2. Data Communications Infrastructure Environment .....	3-5
3.4.3. Computerized Maintenance Management Systems Environment.....	3-5
3.4.4. Critical Systems Integration.....	3-5
3.4.5. Asset Data System of Record .....	3-6
3.5. Summary of Recommended Projects .....	3-6
3.5.1. Recommendations for Immediate Action .....	3-6
3.5.2. Project Schedule .....	3-10
3.5.3. Project Budget.....	3-10
3.5.4. Minimum, Moderate & Aggressive Options.....	3-14
3.5.5. IT Governance.....	3-14
3.6. Existing Conditions .....	3-15
3.7. Interview Summary .....	3-18
3.7.1. IT Governance/Management .....	3-18
3.7.2. Customer Information System/Billing System (CIS) .....	3-20
3.7.3. Distribution CMMS (George Butler Associates Master Series - gbaMS)....	3-21
3.7.4. Water Treatment CMMS (AllMax Antero) .....	3-23
3.7.5. Geographic Information System (GIS).....	3-24
3.7.6. Laboratory Information Management System (LIMS) .....	3-24
3.7.7. Supervisory Control and Data Acquisition (SCADA).....	3-26
3.7.8. Financial Information Systems (FIS).....	3-27
3.8. Findings and Recommendations .....	3-28
3.8.1. Overview of Findings.....	3-28
3.8.2. Specific Findings .....	3-29
3.8.3. Recommended Areas of Focus.....	3-31
3.8.3.1. Systems and Data Assessment .....	3-34
3.8.3.2. IT Information Systems Assessment.....	3-36
3.8.3.3. Geographic Information System (ESRI).....	3-39
3.8.3.4. Laboratory Information Management System (Accelerated Technologies).....	3-41
3.8.3.5. CMMS – Water Treatment Plants (AllMax Antero) .....	3-43
3.8.3.6. CMMS – Distribution (George Butler Associates Master Series).....	3-45
3.8.3.7. CIS (Advanced Utility Systems) .....	3-47
3.8.3.8. IT Infrastructure .....	3-49
3.9. IT Projects Overview.....	3-50
3.10. IT Project Details.....	3-53
3.10.1. Foundation Projects .....	3-53
3.10.2. GeoDatabase Conversion.....	3-55
3.10.3. Reconcile Inventory Control Methods .....	3-56
3.10.4. Implement IT Issues Tracking .....	3-57
3.10.5. SCADA Network Data Communications Approach.....	3-58

3.10.6.	Near-Term Projects .....	3-59
3.10.7.	Mid-Term Projects .....	3-64
3.10.8.	Long-Term Projects.....	3-69
3.11.	IT Governance, Management, and Support Plan .....	3-70
3.11.1.	Purpose .....	3-70
3.11.2.	Definitions and Concepts .....	3-71
3.11.3.	Structure .....	3-73
3.11.4.	IT Principles.....	3-75
3.11.5.	IT Architecture .....	3-75
3.11.6.	IT Infrastructure .....	3-79
3.11.7.	Business Application Strategy.....	3-79
3.11.8.	Project Portfolio Management Methodology .....	3-79
3.11.9.	IT Management and Support .....	3-80
3.12.	Implementation Recommendations .....	3-81
3.13.	IT Skill Development and Staffing.....	3-82

**4. Identified Needs and Improvements 4-1**

4.1.	Large Capital Projects in 5-Yr CIP .....	4-1
4.1.1.	Raw Water Supply Evaluation .....	4-1
4.1.1.1.	Ohio River Pump Station No. 2 .....	4-1
4.1.1.2.	Licking River Pump Station .....	4-4
4.1.2.	Water Treatment Plant Evaluation .....	4-6
4.1.2.1.	Memorial Parkway WTP.....	4-6
4.1.2.2.	Fort Thomas WTP .....	4-9
4.1.2.3.	Taylor Mill WTP .....	4-12
4.1.3.	Pumping Station Evaluation .....	4-14
4.1.4.	Storage Tank Evaluation .....	4-17
4.1.5.	Other.....	4-17
4.1.5.1.	Laboratory Equipment .....	4-17
4.1.6.	Project Recommendations .....	4-19
4.2.	Annual General Facility R&R (WQ&P).....	4-42
4.2.1.	Raw Water Pump Stations .....	4-42
4.2.1.1.	Ohio River Pump Station No. 1 .....	4-42
4.2.1.2.	Licking River Pump Station .....	4-42
4.2.2.	Water Treatment Plant Evaluation .....	4-43
4.2.2.1.	Memorial Parkway Treatment Plant .....	4-43
4.2.2.2.	Fort Thomas Treatment Plant .....	4-44
4.2.2.3.	Taylor Mill Treatment Plant .....	4-47
4.2.3.	Pumping Station Evaluation .....	4-50
4.2.4.	Storage Tank Evaluation .....	4-52
4.2.5.	Annual General Facility R&R Projects .....	4-57
4.3.	Evaluation of Programs.....	4-69
4.3.1.	Above Ground Assets .....	4-69
4.3.1.1.	Antero CMMS Overview .....	4-69
4.3.1.2.	Work Order Management Overview.....	4-72
4.3.1.3.	Antero Evaluation .....	4-77
4.3.2.	Below Ground Assets.....	4-82
4.3.2.1.	Water Distribution System Reliability Evaluation .....	4-82
4.3.2.2.	System Inventory.....	4-83
4.3.2.3.	Water Main Replacement Program .....	4-97
4.3.2.4.	Water Distribution O&M Programs .....	4-102
4.3.3.	Summary of Recommendations for Additional Studies.....	4-106

4.3.3.1.	ORPS1 Surge Analysis .....	4-106
4.3.3.2.	Plant Capacity Analysis .....	4-107
4.3.3.3.	Corrosion Control Soil Testing .....	4-107
4.3.3.4.	Structural Analysis of ORPS 2 .....	4-107
4.3.3.5.	Evaluation of Electrical Systems .....	4-107

**5. Funding Strategy** **5-1**

5.1.	Development of Strategy .....	5-1
5.1.1.	Scenarios .....	5-1
5.1.2.	Summary of Costs .....	5-3
5.2.	Financial Analysis .....	5-4
5.2.1.	Assumptions .....	5-5
5.2.2.	Capital Financing .....	5-6
5.2.3.	Revenue Adjustments .....	5-7
5.3.	Operating and Capital Flow of Funds .....	5-7
5.4.	Summary .....	5-9

**Tables**

Table 1-1.	Summary of Pump Station Capacities .....	1-4
Table 1-2.	Current Available Storage .....	1-6
Table 1-3.	Summary of Pump Station Controls .....	1-8
Table 1-4.	Landuse and Corresponding Comprehensive Plan Categories .....	1-10
Table 1-5.	Unit Values for Consumption .....	1-14
Table 1-6.	New Account Projections: Present through 2020 .....	1-15
Table 1-7.	New Account Projections: 2021 through 2030 .....	1-15
Table 1-8.	NKWD Future Demand Projections .....	1-17
Table 1-9.	Historical and Projected Population by County .....	1-18
Table 1-10.	Existing Pumping Capacity Analysis .....	1-20
Table 1-11.	2020 Pumping Capacity Analysis .....	1-20
Table 1-12.	2030 Pumping Capacity Analysis .....	1-21
Table 1-13.	Existing Storage Analysis .....	1-23
Table 1-14.	2020 Storage Analysis .....	1-23
Table 1-15.	2030 Storage Analysis .....	1-24
Table 1-16.	Summary of System Performance Criteria for Maximum Day Demand .....	1-28
Table 1-17.	Pump Starts Analysis .....	1-42
Table 1-18.	2020 Demands by Pressure Zone .....	1-43
Table 1-19.	2020 Demands by WTP Service Area .....	1-44
Table 1-20.	2030 Demands by Pressure Zone .....	1-45
Table 1-21.	2030 Demands by Pressure Zone .....	1-45
Table 1-22.	Recommended System Improvements and Costs .....	1-57
Table 2-1.	Asset Physical Condition Summary of Worst Scores ( 4 or higher) .....	2-9
Table 2-2.	Asset Criticality - Final Criteria and Weights .....	2-14
Table 2-3.	Pump Station Criticality - Current Scores Compared to AwwaRF Ratings .....	2-16
Table 2-4.	Asset R&R Planning and CIP Groups .....	2-17
Table 2-5.	Asset R&R Planning - Effective Useful Life Estimates .....	2-18
Table 2-6.	Examples AWWA QualServe Benchmarks .....	2-24
Table 3-1.	Foundation Projects .....	3-7
Table 3-2.	Near Term IT Projects .....	3-8
Table 3-3.	Mid Term IT Projects .....	3-9

Table 3-4. Long Term IT Projects.....	3-9
Table 3-5. Total Projected External Costs.....	3-11
Table 3-6. Total Projected Internal Labor Hours.....	3-13
Table 3-7. IT Projects Costs and Schedule for the Moderate Approach Option.....	3-14
Table 3-8. Asset Data System of Record.....	3-35
Table 3-9. IT Information Systems Assessment.....	3-39
Table 3-10. Stakeholders and Roles.....	3-74
Table 3-11. Elements of System Architecture.....	3-77
Table 4-1. Probable Costs for Alternative A.....	4-2
Table 4-2. Probable Costs for Alternative B.....	4-3
Table 4-3. Probable Costs for Alternative C.....	4-4
Table 4-4. Design Criteria for GAC Contractors MPTP.....	4-7
Table 4-5. Opinion of Probable Project Costs-MPTP.....	4-7
Table 4-6. Design Criteria for GAC Contactors-FTTP.....	4-10
Table 4-7. Opinion of Probable Project Costs-FTTP.....	4-10
Table 4-8. Design Criteria for GAC Contactors-TMTP.....	4-12
Table 4-9. Opinion of Probable Project Costs-TMTP.....	4-13
Table 4-10. Laboratory Equipment Replacement Schedule.....	4-18
Table 4-11. 5-Year CIP Project Description.....	4-20
Table 4-12. Master List of 5-Year CIP Projects 2009-2030.....	4-35
Table 4-13. NKWD Tank Inspection and Maintenance Schedule.....	4-55
Table 4-14. Tank Summary.....	4-57
Table 4-15. Annual General R&R 2011 through 2030.....	4-58
Table 4-16. Increases to 2008 O&M Budget - 2009 through 2030.....	4-63
Table 4-17. Antero CMMS Physical/Performance Attributes.....	4-70
Table 4-18. Antero CMMS Financial Attributes.....	4-71
Table 4-19. Antero CMMS Asset Management Attributes.....	4-72
Table 4-20. Antero CMMS Work Order Types.....	4-73
Table 4-21. Antero CMMS Work Order Cost Data.....	4-73
Table 4-22. Antero CMMS Work Order Tracking.....	4-73
Table 4-23. Key Performance Indicators.....	4-76
Table 4-24. NKWD Number of Water Main Breaks and Leaks.....	4-86
Table 4-25. NKWD Number of Breaks Only.....	4-86
Table 4-26. Distribution System Reliability by Pipe Class.....	4-92
Table 4-27. Distribution System Replacement Costs vs. Reliability Targets.....	4-100
Table 4-31. Water Main Break/Leak Repair Data Collection Efficiency.....	4-103
Table 5-1. Yearly Costs for Projects and O&M.....	5-4
Table 5-2. Growth Projections.....	5-6

## Figures

Figure 1-1: System Overview.....	1-2
Figure 1-2: 2020 Development Areas.....	1-12
Figure 1-3: 2030 Development Areas.....	1-13
Figure 1-4: Existing System – Average Demand Day Maximum Pipe Velocity Results.....	1-30
Figure 1-5: Existing System – Average Demand Day Minimum Pressure Results.....	1-31
Figure 1-6: Existing System – Maximum Demand Day Maximum Pipe Velocity Results.....	1-33
Figure 1-7: Existing System – Maximum Demand Day Minimum Pressure Results.....	1-34
Figure 1-8: Bristow Pump Station.....	1-36
Figure 1-9: Bromley Pump Station.....	1-36
Figure 1-10: Carothers Pump Station.....	1-37
Figure 1-11: Dudley 1040 Pump Station.....	1-37

Figure 1-12: Dudley 1080 Pump Station ..... 1-38  
 Figure 1-13: Hands Pike Pump Station ..... 1-38  
 Figure 1-14: Latonia Pump Station..... 1-39  
 Figure 1-15: Richardson Road Pump Station..... 1-39  
 Figure 1-16: Ripple Creek Pump Station..... 1-40  
 Figure 1-17: Taylor Mill Pump Station ..... 1-40  
 Figure 1-18: US 27 Pump Station..... 1-41  
 Figure 1-19: West Covington Pump Station ..... 1-41  
 Figure 1-20: Existing System Improvements..... 1-48  
 Figure 1-21: 2010 – 2020 System Improvements ..... 1-51  
 Figure 1-22: 2020 – 2030 System Improvements ..... 1-54  
 Figure 2-1: NKWD Water Plants - Asset Condition - All Assets..... 2-9  
 Figure 2-2: NKWD Water Plants - Asset Condition - Mechanical Assets..... 2-10  
 Figure 2-3: NKWD Pump Stations & Storage Tanks - Asset Condition - All Assets by Class.. 2-11  
 Figure 2-4: Examples of Typical Asset Performance Condition Criteria and Scoring ..... 2-12  
 Figure 2-5: Memorial Parkway WTP - Example Treatment Process Criticality ..... 2-15  
 Figure 2-6: NKWD Water Plants, Pump Stations and Tanks - Asset R&R ..... 2-19  
 Figure 3-1: NKWD Wide Area Network ..... 3-17  
 Figure 3-2: Current Relationship between Systems..... 3-29  
 Figure 3-3: Relationship between IT Systems and Development of Capital Projects..... 3-32  
 Figure 3-4: High Level Data Integration Diagram ..... 3-52  
 Figure 3-5: Virtualized Service Oriented Architecture to Support Business Intelligence ..... 3-77  
 Figure 4-1: 2009-2030 System Improvements ..... 4-41  
 Figure 4-2: Available Antero Reports ..... 4-75  
 Figure 4-3: Above Ground Asset R&R Planning ..... 4-79  
 Figure 4-4: NKWD Major Pipe Classes ..... 4-85  
 Figure 4-5: Average Monthly Water Main Breaks and Leaks..... 4-87  
 Figure 4-6: Average Monthly Water Main Breaks and Leaks (2007) ..... 4-87  
 Figure 4-7: Annual Number of Water Main Breaks and Leaks..... 4-88  
 Figure 4-8: Distribution Pipe Breaks by Pipe Class..... 4-89  
 Figure 4-9: Water System Distribution Reliability ..... 4-94  
 Figure 4-10: Pipe Breakage Percent by Pipe Class ..... 4-95

Appendices

A. Large User Demand Patterns 6  
 B. Model Calibration Results 32  
 C. Pump Manufacturer's Curves 30  
 D. Asset Physical Condition Assessment 26  
 E. Asset Criticality Assessment 80  
 F. 2009-2030 System Improvements (Min, Mod, Aggres.) 8  
 G. Antero CMMS Work Order Tasks & Equipment 5  
 H. Pipe Material Data 16  
 I. GBA Master Series Documentation 82

183

