# LAUREL COUNTY WATER DISTRICT NO. 2 SOUTH LAUREL WATER SYSTEM IMPROVEMENTS CONTRACT NO. 2 - HOPEWELL WATER STORAGE TANK LAUREL COUNTY, KENTUCKY

# TABLE OF CONTENTS

COVER

GENERAL NOTES GN-1

500,000 GALLON WATER STORAGE TANK

CONSTRUCTION DETAILS

EXISTING SITE PLAN

PROPOSED SITE PLAN

3 - 4

OAK RIDGE TANK CONTROL VALVE VAULT ADDITION 5

STANDARD DETAIL DRAWINGS SD-1

PROJECT FUNDED BY:

USDA RURAL DEVELOPMENT


# **BOARD OF COMMISSIONERS**

ROY WAYNE JENKINS, CHAIRMAIN RONNIE BALL, SECRETARY KENNETH FINLEY, TREASURER DAVID MOORE LISA BAKER

> MANAGER KENNETH FISHER

> OCTOBER 2019

# LOCATION MAP



Monarch Engineering, Inc.

556 CARLTON DRIVE LAWRENCEBURG, KY 40342

### LOCATION AND SCOPE OF PROJECT

THE PROJECT LOCATION IS GENERALLY DEFINED AS THE EXISTING TANK SITE BOUNDARY OWNED BY THE LAUREL COUNTY WATER DISTRICT NO. 2, ON KY HIGHWAY 1223 IN SOUTHERN LAUREL COUNTY, KENTUCKY. THE WORK TO BE DONE UNDER THIS CONTRACT INCLUDES FURNISHING ALL MATERIALS, EQUIPMENT, AND LABOR NECESSARY TO CONSTRUCT THE HOPEWELL WATER STORAGE TANK IN ACCORDANCE WITH THE PLANS, SPECIFICATIONS AND CONTRACT DOCUMENTS.

### **GENERAL NOTES**

- 1. IT IS THE INTENTION OF THESE PLANS TO CONSTRUCT ALL WORK IN ACCORDANCE WITH ALL APPLICABLE REQUIREMENTS OF THE LAUREL COUNTY WATER DISTRICT NO. 2, LAUREL COUNTY. THE KENTUCKY DEPARTMENT FOR ENVIRONMENTAL PROTECTION, AND THE U.S. ARMY CORPS OF ENGINEERS. WHERE THERE IS A CONFLICT BETWEEN THE CONTRACT DOCUMENTS, PLANS, AND SPECIFICATIONS AND THE PERMIT REQUIREMENTS OF THE AGENCY CONTROLLING THE UTILITY OR RESPECTIVE RIGHTS-OF-WAY, THE MORE RESTRICTIVE SHALL GOVERN.
- 2. THE CONTRACTOR AND ANY APPLICABLE SUBCONTRACTORS SHALL ATTEND A PRE-CONSTRUCTION MEETING AT A TIME AND PLACE ARRANGED BY THE ENGINEER, IN WHICH ALL AFFECTED PARTIES WILL BE PRESENT. ALSO, A PRE-DISTRUBANCE WALK THROUGH WILL NEED TO BE ATTENDED BY THE CONTRACTOR
- 3. FOLLOWING THE PRE-CONSTRUCTION MEETING, THE CONTRACTOR SHALL NOTIFY THE ENGINEER A MINIMUM OF THREE (3) WORKING DAYS PRIOR TO THE START OF CONSTRUCTION FOR INSPECTION COORDINATION. NO WORK CAN COMMENCE UNTIL ALL PERMITS HAVE BEEN OBTAINED AND THE CONTRACTOR HAS BEEN GIVEN THE AUTHORITY TO PROCEED.
- 4. THE CONTRACTOR SHALL NOTIFY KENTUCKY 811 AT LEAST 72 HOURS IN ADVANCE OF CONSTRUCTION. FOR LOCATION AND MARKING OF ALL EXISTING UTILITIES.
- 5. LOCATIONS AND ELEVATIONS OF EXISTING UNDERGROUND UTILITIES AS SHOWN ON THE PLANS ARE APPROXIMATE. NO GUARANTEE IS EITHER EXPRESSED OR IMPLIED AS TO THE COMPLETENESS OR ACCURACY THEREOF. THE CONTRACTOR SHALL BE EXCLUSIVELY RESPONSIBLE FOR DETERMINING AND VERIFYING THE LOCATION, DEPTH, AND ELEVATION OF THE EXISTING UTILITIES WITHIN THE CONSTRUCTION AREA PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IF ANY CONFLICTS ARE APPARENT OR IF LOCATIONS AND DEPTHS DIFFER SIGNIFICANTLY FROM THE PLANS
- 6. ALL ELEVATIONS REFER TO THE CURRENT NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD '88).
- 7. THE ENGINEER HAS NOT PERFORMED PROPERTY OR RIGHT-OF-WAY SURVEYS FOR ANY OF THE AREAS INCLUDED IN THIS PROJECT. RIGHT-OF-WAY OR PROPERTY LINES SHOWN ON THE PLANS ARE APPROXIMATE AND ARE SHOWN FOR GENERAL ORIENTATION ONLY. PROPERTY CORNERS OR OTHER SURVEY MARKERS HAVE NOT BEEN LOCATED, UNLESS SPECIFICALLY CALLED OUT ON THE PLANS.
- 8. ALL PROPERTIES OR FACILITIES IN THE SURROUNDING AREAS, PUBLIC OR PRIVATE, DESTROYED OR OTHERWISE DAMAGED BY THE CONTRACTORS OPERATIONS SHALL BE REPLACED OR REPAIRED BY THE CONTRACTOR AT THEIR OWN EXPENSE TO THE SATISFACTION OF THE AUTHORITY HAVING JURISDICTION OVER THE IMPACTED PROPERTY OR FACILITY.
- 9. IF, IN THE OPINION OF THE ENGINEER, WORK HAS NOT PROGRESSED IN A REASONABLE AND TIMELY MANNER, THE ENGINEER SHALL HAVE THE RIGHT, WITH THE APPROVAL OF THE OWNER, TO DIRECT THE CONTRACTOR TO PROCEED WITH THE WORK OR ANY PORTION THEREOF IMMEDIATELY. IN THE EVENT THAT THE CONTRACTOR DOES NOT PROCEED WITH THE WORK IMMEDIATELY, AS DIRECTED BY THE ENGINEER, THE ENGINEER, UNDER THE DIRECTION OF THE OWNER, MAY ORDER ANY OR ALL OTHER OPERATIONS OF THE CONTRACTOR, UNDER THIS CONTRACT, TO CEASE UNTIL THE REQUESTED WORK IS PROCEEDING IN AN ACCEPTABLE MANNER. SHOULD THE CONTRACTOR FAIL TO COMPLY WITH THESE PROVISIONS, THE OWNER MAY, WITH OR WITHOUT NOTICE, CAUSE THE REQUIRED WORK TO BE DONE BY THE OWNER OR OTHERS AND WILL DEDUCT THE COST OF SAID WORK FROM ANY FUNDS DUE OR TO BECOME DUE THE CONTRACTOR UNDER THIS CONTRACT. THE PERFORMANCE OF SUCH WORK BY THE OWNER OR OTHERS SHALL SERVE IN NO WAY TO RELEASE THE CONTRACTOR FROM HIS GENERAL OF PARTICULAR LIABILITY FOR THE SAFETY OF THE PUBLIC OR COMPLETION OF THE WORK.
- 10. ACTIONS MUST BE TAKEN TO MINIMIZE THE TRACKING OF MUD AND SOIL FROM CONSTRUCTION AREAS ONTO PUBLIC ROADWAYS. ANY SOIL TRACKED ONTO A PUBLIC ROADWAY SHALL BE REMOVED DAILY.
- 11. ALL WORK SHALL BE INCORPORATED IN TO THOSE UNIT PRICES LISTED IN THE CONTRACT DOCUMENTS. ANY ITEMS NOT SPECIFICALLY LISTED IN THE UNIT PRICES SHALL BE CONSIDERED INCIDENTAL TO THE WORK AND SHALL NOT BE ELIGIBLE FOR SEPARATE PAYMENT OR COMPENSATION.

## **EROSION AND SEDIMENTATION CONTROL NOTES**

- 1. THE CONTRACTOR SHALL COMPLY WITH ALL EROSION AND SEDIMENTATION CONTROL REQUIREMENTS OF THE BOTH THE STATE OF KENTUCKY AND THE U.S. ARMY CORPS OF ENGINEERS FOR ALL DISTRUSTED AREAS INCLUDED IN THE PROJECT.
- 2. THE CONTRACTOR SHALL CONDUCT CONSTRUCTION OPERATIONS IN A MANNER THAT WILL REDUCE ACCELERATED EROSION TO THE PRACTICAL MINIMUM AND PREVENT DAMAGING SILTATION TO EXISTING SEWERS AND WATER COURSES LEADING FROM THE PROJECT AREA.
- 3. THE CONTRACTOR SHALL CONDUCT WORK IN SUCH A MANNER AS TO PREVENT THE ENTRY OF FUELS, OILS, BITUMINOUS MATERIALS, CHEMICALS, SEWERAGE, OR OTHER HARMFUL MATERIALS INTO NEARBY LAKES AND STREAMS.
- 4. WASTE DISPOSAL AREAS SHALL BE SELECTED BY THE CONTRACTOR WITH FULL CONSIDERATION OF EROSION AND SEDIMENT CONTROL, SELECTION OF DISPOSAL SITE(S), AND CONTROL OF OPERATIONS, AND THE RESTORATION OF SAID AREAS SHALL BE SUBJECT TO APPROVAL OF THE ENGINEER.
- 5. EXCAVATIONS FROM THE PROJECT AREA INCLUDING THOSE IN CHANNELS AND WATERCOURSES SHALL NOT BE DEPOSITED IN OR NEAR RIVERS, STREAMS, OR PONDS WHERE IT MAY ENTER THE WATERWAY.
- 6. AT THE COMPLETION OF EACH DAYS CONSTRUCTION, CARE SHOULD BE TAKEN TO ENSURE THAT MINIMAL EROSION WILL OCCUR IN TRENCHES AND TO STOCKPILED MATERIALS UNTIL RESUMPTION OF
- 7. THE CONTRACTOR SHALL CONFINE CONSTRUCTION OPERATIONS TO THE MINIMUM AMOUNT OF WORKING SPACE PRACTICAL TO AID IN THE MINIMIZATION OF SOIL EROSION.
- 8. THE PROJECT WILL BE CONTINUALLY OBSERVED BY VARIOUS STATE & LOCAL REGULATORY AGENCIES FOR EROSION CONTROL COMPLIANCE. DEFICIENCIES WILL BE CORRECTED BY THE CONTRACTOR IMMEDIATELY UPON NOTICE OF SUCH DEFICIENCIES. FAILURE TO CORRECT THE DEFICIENCIES MAY RESULT IN THE ISSUANCE OF A STOP WORK ORDER AND THERE WILL BE NO CONTRACT TIME EXTENSION GRANTED FOR THIS TYPE OF STOPPAGE.
- 9. TEMPORARY SOIL EROSION CONTROL MEASURES CONSISTING OF SILT FENCE, MULCHING, AND TARPING SHALL BE IMPLEMENTED THROUGHOUT THE ENTIRE CONSTRUCTION AREA OF THE PROJECT, AND SHALL BE REMOVED BY THE CONTRACTOR AFTER THE PERMANENT SOIL EROSION MEASURES HAVE BEEN
- 10. PERMANENT SOIL EROSION MEASURES CONSISTING OF AN APPROVED SEED MIXTURE AND MULCH BLANKET SHALL BE COMPLETED WITHIN FIVE (5) CALENDAR DAYS OF FINAL GRADING. IN THE EVENT IT IS NOT POSSIBLE TO PERMANENTLY STABILIZE THE AREA DUE TO SITE CONDITIONS OR SEASONAL LIMITATIONS, THE TEMPORARY MEASURES SHALL REMAIN IN FORCE AND SHALL BE MAINTAINED BY THE CONTRACTOR UNTIL SUCH TIME IT IS PRACTICAL TO COMPLETE THE PERMANENT SOIL EROSION CONTROL
- 11. THE ENGINEER SHALL HAVE FULL AUTHORITY TO TEMPORARILY SUSPEND WORK IN THE EVENT THAT ANY OF THE ABOVE REQUIREMENTS ARE NOT BEING MET BY THE CONTRACTOR, OR IF CONDITIONS INDICATE THAT ADDITIONAL TEMPORARY MEASURES ARE WARRANTED, IN THE OPINION OF THE ENGINEER OR REGULATORY AGENCIES.
- 12. PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL INSTALL INLET FILTERS AT ALL STORM SEWER INLETS WHICH MAY BE PRESENT IN THE CONSTRUCTION AREA.
- 13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF ANY REQUIRED ACCESS ROAD SURFACES AND SOIL EROSION CONTROL MEASURES WITHIN THE CONSTRUCTION AREA UNTIL THE FULL COMPLETION OF THE PROJECT.
- 14. ALL NON-PAVED DISTURBED AREAS SHALL BE RESTORED AS INDICATED ON THE PLANS. IF NOT SPECIFICALLY STATED ON THE PLANS, RESTORATION SHALL CONSIST OF 4-INCHES OF TOPSOIL, FERTILIZER, SEED AND MULCH. UNLESS OTHERWISE STATED, ALL DISTURBED AREAS SHALL BE SEEDED WITH A SEED MIX APPROVED BY THE ENGINEER.

### **WORK LIMITS**

IF INDICATED ON THE PLANS, THE CONTRACTOR SHALL KEEP ALL OPERATIONS WITHIN THE WORK LIMITS SHOWN. OTHERWISE, THE CONTRACTOR SHALL ESTABLISH CONSTRUCTION LIMITS WITHIN THE EXISTING AND/OR PROPOSED RIGHTS-OF-WAY AND EASEMENTS AS DIRECTED BY THE ENGINEER. THIS REQUIREMENT SHALL INCLUDE MATERIAL STOCKPILING AND EQUIPMENT STORAGE. THE CONTRACTOR MAY NOT EXIT THE ESTABLISHED PROJECT WORK LIMITS WITHOUT EXPLICIT PERMISSION FROM THE OWNER AND THE ENGINEER.

### **UTILITIES**

FOR PROTECTION OF UNDERGROUND UTILITIES AND IN CONFORMANCE WITH KENTUCKY LAW. THE CONTRACTOR SHALL SHALL DAIL KENTUCKY 811 A MINIMUM OF THREE (3) FULL WORKING DAYS. EXCULDING SATURDAYS, SUNDAYS, AND HOLIDAYS, PRIOR TO BEGINNING WORK IN EACH CONSTRUCTION AREA WHERE PUBLIC UTILITIES HAVE NOT BEEN PREVIOUSLY LOCATED. MEMBERS WILL THUS BE ROUTINELY NOTIFIED. THIS DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY OF NOTIFYING UTILITY OWNERS WHO MAY NOT BE PART OF THE 'KY 811" ALERT SYSTEM. UTILITY LOCATIONS SHOWN ON THE PLANS ARE ONLY APPROXIMATE AND SHOULD BE LOCATED IN THE FIELD PRIOR TO ANY EXCAVATION.

### WORK WITHIN STREAMS, CREEKS & WATERWAYS

ANY AND ALL WORK TO BE COMPLETED WITHIN STREAMS, CREEKS & WATERWAYS SHALL BE COMPLETED ONLY DURING TIMES OF LOW FLOW AS DETERMINED BY THE ENGINEER. THE CONTRACTOR SHALL STRICTLY LIMIT THE USE OF HEAVY EQUIPMENT WITHIN THE WATERCOURSE AT ALL TIMES. STREAM FLOW SHALL NOT BE RESTRICTED OR IMPEDED AT ANY TIME DURING THE COURSE OF CONSTRUCTION.

### **BENCHMARKS**

BENCHMARK NO. 1: IRON PIN WITH CAP STAMPED "OWEN PLS 2681" ELEV XXXX.XX BENCHMARK ALSO SERVES AS SOUTHWESTERN CORNER OF TANK SITE (LOCATION IS DEPICTED ON PLAN SHEET 2)

### **DISRUPTION OF SERVICE**


THE CONTRACTOR SHALL COORDINATE ALL DISRUPTIONS OF SERVICE WITH THE OWNER AND ENGINEER. PRIOR TO ANY DISRUPTION, THE CONTRACTOR SHALL INFORM BOTH PARTIES OF HIS INTENTIONS, METHODS AND PROJECTED DURATION OF DISTURBANCE AND RECEIVE THEIR APPROVAL PRIOR TO INITIATING THE SPECIFIC WORK.

### WORK WITHIN PUBLIC ROAD RIGHT-OF-WAYS

WHEN PERFORMING WORK ALONG OR ACROSS ANY PUBLIC ROADWAY. THE CONTRACTOR SHALL POST WARNING SIGNS PAINTED ORANGE AND THEY SHALL BE FOUR FEET BY FOUR FEET MOUNTED ON POSTS IN ACCORDANCE WITH THE KENTUCKY TRANSPORTATION DEPARTMENT'S MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES. THE SIGNS SHALL BE AS FOLLOWS:

- 1) CAUTION PIPELINE CONSTRUCTION 1500 FEET
- 2) CAUTION PIPELINE CONSTRUCTION 1000 FEET 3) CAUTION PIPELINE CONSTRUCTION 500 FEET
- ALL SIGNS, BARRICADES, LIGHTS, AND TRAFFIC CONTROL SHALL BE INSTALLED IN ACCORDANCE WITH THE KENTUCKY TRANSPORTATION DEPARTMENT'S MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
- THE CONTRACTOR SHALL MAINTAIN TWO FLAG MEN AT ALL TIMES WHERE MACHINERY IS IN OPERATION WHERE THE FLOW OF TRAFFIC WILL BE DISTURBED. THERE IS NO EXCEPTION TO THIS REQUIREMENT. THE USE OF RADIOS WILL BE REQUIRED WHEN VISUAL CONTACT BETWEEN THE FLAGMEN DOES NOT EXIST.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING ENTIRE ROADWAY FREE AND CLEAR AT THE END OF EACH WORKING DAY. NO EQUIPMENT SHALL BE LEFT ON OR PARKED ALONG THE ROAD RIGHT OF WAY. AT THE COMPLETION OF EACH WORK DAY, THE CONTRACTOR SHALL BACKFILL ALL OPEN TRENCHES AND INSTALL ALL TRAFFIC CONTROL SIGNS, BARRICADES, AND LIGHTS IN ACCORDANCE WITH THE KENTUCKY TRANSPORTATION DEPARTMENT'S MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

### PROJECT LOCATION MAP



 $\vdash$  m

 $\bigcirc$ 

KENTUC 0

2

HOPE

PROJECT NO. 1813 DATE: OCT 2019 DRAWN BY: CHECKED BY: DSB

CHECKED BY: DMB

SCALE: AS NOTED

SHEET:

NOTE

ENERAL

**5** 5


0


ONTRACT

TOR


WATER

GN-1





EXISTING SITE PLAN SCALE: 1"=20'



PROPERTY & EASMENT MAP SCALE: 1"=40'

AGE SITE 40342

, X X X

556 CARLTON AWRENCEBURG

 $\mathcal{C}\mathcal{V}$ 


DISTRICT TY WAT EXISTING HOPEWELL WATER EL COUNTY LAUREL CO

PROJECT NO. 1813 DATE: OCT 2019


DRAWN BY: JLMCHECKED BY: DSB CHECKED BY: DMB

SCALE: AS NOTED


SHEET:




PROPOSED SITE PLAN



SITE ENTRANCE DETAIL SCALE: 1"=10'



SITE ELECTRICAL PLAN SCALE: 1"=20'



TANK ORIENTATION LAYOUT NOT TO SCALE

40342

556 CARLTON AWRENCEBURC

 $\mathcal{C}\mathcal{V}$ 

WAT

COUNT


CO


AGE SITE STOR PROPOSED ELL WATER HOPEWELL


PROJECT NO. 1813 DATE: OCT 2019 DRAWN BY: CHECKED BY: DSB


CHECKED BY: DMB AS NOTED

SHEET:









TANK SITE -LAT: 36°59'38.41" N LONG: 84°04'58.36" W

# LOCATION MAPS

THE TANK AND CONCRETE SUPPORT PEDESTAL SHALL BE DESIGNED AND CONSTRUCTED IN ACCORDANCE WITH AWWA D100-11, AND PROJECT SPECIFICATIONS.

### LOADING CRITERIA:

DESIGN WIND VELOCITY: 100 PSF MSE SPECTRAL RESPONSE ACCELERATION - 0.2-SEC PERIOD (Ss): PER AWWA D100-11 MSE SPECTRAL RESPONSE ACCELERATION - 1.0-SEC PERIOD (S1): PER AWWA D100-11

THE CONTRACTOR SHALL GROUT BENEATH BASE PLATES UPON COMPLETION OF ERECTION.


STEEL PLATE: ASTM A283 GR.C/A36 STRUCTURAL STEEL SHAPES: ASTM A36 BRACE & STAY RODS: ASTM A36 LADDER RUNGS: ASTM A706

### <u>GENERAL:</u>

- ACCESSORIES SHOWN ON ELEVATION DRAWINGS ARE ROTATED FOR CLARITY.
- ALL HANDRAILS, PLATFORM LANDINGS, WALKWAYS, LADDERS AND SAFETY CLIMB DEVICES SHALL CONFORM WITH CURRENT OSHA STANDARDS.
- SEE PROJECT SPECIFICATIONS FOR SHOP AND FIELD PAINT REQUIREMENTS FOR THE STEEL TANK.

- STERILIZE TANK IN ACCORDANCE WITH AWWA C652-02 AND PROJECT SPECIFICATIONS.

- TOWER LADDER SHALL HAVE 3' X 3' REST PLATFORM AT TOWER LADDER MIDPOINT




ORIENTATION DETAIL

SHEET:

CONSTRUCTION

WATER




403 以 、 、 、 、 、 、 、


> DISTRICT KENTUCKY 国 ry wat count COUNTY AUREL CC

HOPEWELL


PROJECT NO. 1813 DATE: OCT 2019 DRAWN BY: JLM CHECKED BY: DSB

CHECKED BY: DMB SCALE: N.T.S.






PLAN VIEW




SECTION VIEW


# CONTROL VALVE VAULT DETAILS

SCALE: N.T.S.





LOCATION MAPS



SITE PLAN SCALE: 1"=20'

DRIVE 3, KY

40342

556 CARLTON -AWRENCEBURG

PLAN RAGE ry wat count PROPOSED OAK RIDGI EXISTING

SITE E STO


PROJECT NO. 1813 DATE: OCT 2019 DRAWN BY: CHECKED BY: DSB

CHECKED BY: DMB

AS NOTED

SHEET:





FENCE #2

PLACE THE END POST OF OF FENCE #2 INSIDE THE END POST OF FENCE #1.

ROTATE BOTH POSTS AT LEAST 180 DEGREES IN


A CLOCKWISE DIRECTION

TO CREATE A TIGHT SEAL WITH THE FABRIC MATERIAL.


DRIVE BOTH POSTS ABOUT 10" INTO THE GROUND

AND BURY FLAP.

SCALE: N.T.S.



SCALE: N.T.S.



NOTE: THE CONTRACTOR SHALL DO ALL WORK AND TAKE ALL MEASURES NECESSARY TO CONTROL SOIL EROSION RESULTING FROM CONSTRUCTION OPERATIONS. THE FLOW OF SEDIMENT AND ALL OTHER CONSTRUCTION MATERIALS INCLUDING EXCAVATION AND BACKFILL SHALL BE CONTAINED TO THE CONSTRUCTION SITE SO TO PROTECT ADJACENT WATERCOURSE AND WETLANDS. CONTRACTOR SHALL USE ANY APPROVED METHOD REQUIRED TO ACHIEVE THIS, AND AT A MINIMUM THOSE MEASURES DEPICTED HEREIN. THIS REQUIREMENT APPLIES TO ANY AND ALL DISTURBED AREAS WITHIN PROJECT AREA. THE COST OF EROSION CONTROL MEASURES SHALL BE INCIDENTAL TO THE COST OF CONSTRUCTING OTHER PROJECT COMPONENTS.

DETAIL ONTROL NO PROTECTI EROSION

WAT]

.TY CO

IL COUNT


URE PROJECT NO. 1813 DATE: OCT 2019


DRAWN BY: CHECKED BY: DSB CHECKED BY: DMB

AS NOTED

SHEET:

EC-1





THRUST BLOCK DETAILS

VALVE. TRACER WIRE ACCESS BOXES SHALL BE SPACED NO FURTHER THAN 1000' APART, A MINIMUM OF 3 FEET OF TRACER WIRE SHOULD BE COILED UP INSIDE OF EACH ACCESS BOX. TRACER WIRE DETAILS

ACCESS BOXES SHALL BE INSTALLED AT EACH VALVE, HYDRANT AND AIR RELEASE

TRACER WIRE —

TRACER WIRE ACCESS BOX

TIE TRACER WIRES TIGHTLY -TOGETHER USING SQUARE

FOR OPEN CUT INSTALLATION, TRACER WIRE IS TO BE #12 AWG SOLID COPPER

TRACER WIRE SHALL BE INSTALLED WITH THE PIPE AT THE TRENCH BOTTOM.

WITH 30 MIL BLUE HMWPE INSULATION, FOR TRENCHLESS INSTALLATION, TRACER WIRE IS TO BE #12 AWG SOLID COPPER CLAD STEEL CORE WITH 45 MIL BLUE

KNOT TO PREVENT PULLOUT

─\_INTEGRAL TWIST-ON

TRACER WIRE CONNECTION

HDPE INSULATION.

CONNECTOR WITH STRAIN

RELIEF LID AND SEALANT

WATER OR

SEWER FORCE MAIN

(TYP.)

TRACER WIRE —

∕-GRADE LINE

\_MAGNETIZED HEAVY DUTY TRACER WIRE ACCESS

(COPPERHEAD SNAKE PIT

OR APPROVED EQUAL)

TRACER WIRE (TYP.)

TRACER WIRE

CONNECTOR DETAIL

STRIP %" INSULATION — FROM ENDS OF TRACER WIRE AND TWIST TOGETHER

DIRECT BURY WIRE

CONNECTOR PRE-FILLED

-SILICONE AND EQUIPPED


WITH INTEGRAL STRAIN

RELIEF (DRYCONN DBSR OR APPROVED EQUAL)


DIELECTRIC

# - RIGHT-OF-WAY RIGHT-OF-WAY -ACCESS ROAD 12' WIDTH MIN. COMPACTED NO. 4 SURFACE COURSE (4" MIN.) CROSS SLOPE = $\frac{1}{2}$ " TO $\frac{3}{4}$ " PER FOOT OF LANE WIDTH COMPACTED NO. 2 SUBBASE GRAVEL — (8" MIN.) COMPACTED GRAVEL SUBBASE SHALL BE UNDERLINED WITH GEOTEXTILE SEPARATOR FABRIC

TYPICAL ACCESS ROAD SECTION DETAIL



GATE VALVE DETAIL



**BACKFILLING** 

П 4 URI,  $\vdash$   $\bowtie$ ARL 

03

 $\mathcal{C}$ 

DISTRICT KENTUCKY

ER

2 STANDARD

TY WAT L COUNTY AUREL CC LAUREL

PROJECT NO. 1813 DATE: OCT 2019 DRAWN BY: CHECKED BY: DSB

CHECKED BY: DMB

SCALE: N.T.S.

SHEET:

SD-1

