



STA. 0+00  
 CONNECT NEW 6-INCH WATER LINE TO  
 EXISTING 6-INCH WATER LINE WITH  
 6-INCH 6-INCH TAPPING SLEEVE AND VALVE.  
 LAT: 38° 58' 35.39" N  
 LONG: 84° 36' 48.06" W

C & C KOGER FAMILY  
 FARMS LTD PARTNERSHIP  
 c/o CECIL KOGER

CONTRACTOR SHALL DISCONNECT/SHUT  
 OFF CORP STOP AT EACH EXISTING  
 METER SETTING (TYP.-4)

EMERSON K.  
 HAMPTON  
 c/o MRS.  
 EMERSON K.  
 HAMPTON

CONTRACTOR SHALL REMOVE EXISTING METER  
 SETTING AND RECONNECT NEW METER TO  
 EXISTING CUSTOMER SERVICE LINE (TYP.)

ALPHA & OMEGA LLC

ROGER & PAULA  
 DURHAM

DAVID WADE  
 BALDWIN &  
 JASON  
 GRANVILLE  
 BALDWIN  
 c/o JASON G.  
 BALDWIN

DAVID K.  
 MARTIN

GREGORY S.  
 ARBOGAST

MICHAEL M.  
 MOEGENBERG  
 LIVING TRUST  
 c/o MICHAEL  
 MOEGENBERG

MENSHOUSE  
 FAMILY TRUST  
 DTD

INSTALL 3/4-INCH PE  
 SERVICE TUBING (TYP.)

INSTALL NEW METER  
 SETTING (TYP.)

INSTALL 6-INCH PVC SDR 17  
 WATER LINE

STA. 7+50  
 INSTALL 2-WAY FLUSH  
 HYDRANT ASSEMBLY

INSTALL 6-INCH WATER LINE ALONG  
 AND IN THE LEFT-HAND SIDE OF THE  
 COUNTY ROAD. INSTALL 700 LF OF  
 FULL WIDTH PAVEMENT REPLACEMENT.

NOTE:  
 1. CONTRACTOR SHALL EXPOSE EXISTING WATER  
 LINE AT 100 FOOT INTERVALS. NEW WATER  
 LINE TO BE PLACED PARALLEL TO AND  
 WITHIN 6 FEET OF EXISTING WATER LINE.

2022 WATER SYSTEM IMPROVEMENTS & REPLACEMENTS  
 BRONSTON WATER ASSOCIATION  
 PULASKI & WAYNE COUNTIES, KENTUCKY  
 ISLAND VIEW DRIVE WATER LINE REPLACEMENT



**Monarch Engineering, Inc.**  
 556 CARLTON DRIVE  
 LAWRENCEBURG, KY 40342

|                 |                  |         |       |
|-----------------|------------------|---------|-------|
| DRAWN BY: JRC   | DATE: JULY 2022  | REVISED | SHEET |
| CHECKED BY: JLM | SCALE: 1" = 100' |         | 4     |
| CHECKED BY: DSB | PROJECT: 2235    |         |       |





CONNECT NEW 3-INCH WATER LINE TO EXISTING 3-INCH WATER LINE WITH 3-INCHx3-INCH TAPPING SLEEVE AND VALVE.  
 STA. 0+00  
 LAT: 36° 05' 46.81" N  
 LONG: 84° 41' 22.03" W

CUT & CAP EXISTING 3-INCH WATER LINE

HENRY, JR. & CYNTHIA DELPHENE DECKER

SASHA CHAPLIN

WTR ENTERPRISES INC. JUSTIN HANCOCK

WILMA D. TURPIN

INSTALL 3-INCH GATE VALVE

JIM & TAMMY CHAPLIN

DONNIE GREGORY

INSTALL 3-INCH PVC SDR 17 WATER LINE

JOSHUA CATRON

HAROLD DUNAGAN

GAYLA B. LONGWORTH

INSTALL 40 LF OF BORE & CASE FOR 3-INCH WATER LINE

HAROLD & IRENE DUNAGAN

RECONNECT EXISTING METER TO NEW WATER LINE WITH NEW 3/4-INCH HDPE SERVICE LINE AND FITTINGS (TYP.)

EXISTING 3-INCH WATER LINE TO BE ABANDONED

INSTALL 3-INCH WATER LINE ON PRIVATE EASEMENT AS DIRECTED BY ENGINEER

LISA DARLENE & ANDREW S. BRUMMETT AND NICOLE RAE GIBSON

EXISTING 3-INCH WATER LINE TO BE ABANDONED

INSTALL 3-INCH PVC SDR 17 WATER LINE

RECONNECT 2-INCH METER TO NEW 3-INCH WATER LINE WITH NEW 2-INCH HDPE SERVICE LINE AND FITTINGS

EDWARD CASADA

EXISTING 2-INCH WATER LINE TO BE ABANDONED

MATCH LINE SHEET 6

NOTES:  
 1. CONTRACTOR SHALL FURNISH AND INSTALL TEMPORARY CONSTRUCTION FENCING (SAFETY FENCE, ORANGE) AT EACH PRIVATE PROPERTY EASEMENT DURING CONSTRUCTION OF WATER LINE. FENCING SHALL BE INSTALLED ALONG THE ENTIRE LENGTH OF THE PROPERTY OWNER, OR AS DIRECTED BY THE ENGINEER. SEE PLAN SHEET TF-1 FOR DETAILS.  
 2. TEMPORARY CONSTRUCTION FENCING SHALL REMAIN IN PLACE DURING ALL EXCAVATION AND INSTALLATION OF WATER LINE ALONG EACH PRIVATE PROPERTY EASEMENT. TEMPORARY CONSTRUCTION FENCING SHALL REMAIN IN PLACE FOR THE ENTIRETY OF THE PROJECT OR AS DIRECTED BY THE ENGINEER.

NOTE:  
 1. CONTRACTOR SHALL EXPOSE EXISTING WATER LINE AT 100 FOOT INTERVALS. NEW WATER LINE TO BE PLACED PARALLEL TO AND WITHIN 6 FEET OF EXISTING WATER LINE.

2022 WATER SYSTEM IMPROVEMENTS & REPLACEMENTS  
 BRONSTON WATER ASSOCIATION  
 PULASKI & WAYNE COUNTIES, KENTUCKY  
 SUGAR HOLLAR ROAD WATER LINE REPLACEMENT



**Monarch Engineering, Inc.**  
 556 CARLTON DRIVE  
 LAWRENCEBURG, KY 40342

|                 |                  |         |       |
|-----------------|------------------|---------|-------|
| DRAWN BY: JRC   | DATE: JULY 2022  | REVISED | SHEET |
| CHECKED BY: JLM | SCALE: 1" = 100' |         | 5     |
| CHECKED BY: DSB | PROJECT: 2235    |         |       |





NOTES:  
 1. CONTRACTOR SHALL FURNISH AND INSTALL TEMPORARY CONSTRUCTION FENCING (SAFETY FENCE, ORANGE) AT EACH PRIVATE PROPERTY EASEMENT DURING CONSTRUCTION OF WATER LINE. FENCING SHALL BE INSTALLED ALONG THE ENTIRE LENGTH OF THE PROPERTY OWNER, OR AS DIRECTED BY THE ENGINEER. SEE PLAN SHEET TP-1 FOR DETAILS.  
 2. TEMPORARY CONSTRUCTION FENCING SHALL REMAIN IN PLACE DURING ALL EXCAVATION AND INSTALLATION OF WATER LINE ALONG EACH PRIVATE PROPERTY EASEMENT. TEMPORARY CONSTRUCTION FENCING SHALL REMAIN IN PLACE FOR THE ENTIRETY OF THE PROJECT OR AS DIRECTED BY THE ENGINEER.

NOTE:  
 1. CONTRACTOR SHALL EXPOSE EXISTING WATER LINE AT 100 FOOT INTERVALS. NEW WATER LINE TO BE PLACED PARALLEL TO AND WITHIN 6 FEET OF EXISTING WATER LINE.

2022 WATER SYSTEM IMPROVEMENTS & REPLACEMENTS  
 BRONSTON WATER ASSOCIATION  
 PULASKI & WAYNE COUNTIES, KENTUCKY  
 SUGAR HOLLAR ROAD WATER LINE REPLACEMENT



**Monarch Engineering, Inc.**  
 556 CARLTON DRIVE  
 LAWRENCEBURG, KY 40342

|                 |                  |         |       |
|-----------------|------------------|---------|-------|
| DRAWN BY: JRC   | DATE: JULY 2022  | REVISED | SHEET |
| CHECKED BY: JLM | SCALE: 1" = 100' |         | 6     |
| CHECKED BY: DSB | PROJECT: 2235    |         |       |