Case No. 2024-00253

Request No. 1:

Submit a copy of the leases or purchase agreements, including options, separate agreements, or

deeds which Clover Creek Solar has entered into in connection with the proposed solar facility,

including the agreements for each of the parcels of the project.

Response No. 1:

Please find the Project's redacted agreements filed separately due to file size limits and stamped

as Resp. to 1 RFI 01, Pages 001-497.1

Responding Witness: Jesse Eick

¹ The unredacted documents have been provided under seal with a concurrently-filed Petition for Confidential Treatment.

Request No. 2:

Detail any contracts by which Clover Creek Solar has paid, has negotiated to pay, or any

compensation paid to non-participating landowners, whether cash or otherwise, near the project.

Include the terms of the agreements and which properties are involved, in terms of distance, to the

project boundaries.

Response No. 2:

There are no agreements with non-participating landowners.

Case No. 2024-00253

Request No. 3:

Explain why Clover Creek Solar has chosen a site with so many non-contiguous parcels.

Response No. 3:

The overall site location was chosen for its proximity to the New Hardinsburg substation because

this substation allows interconnection at the preferred voltage of 138 kV, and allows the project to

utilize the existing transmission line owned and operated by Big Rivers Electric Corporation

(BREC). See Application, para. 21. Clover Creek Solar Project LLC d/b/a New Frontiers Solar

Park ("New Frontiers") then worked with the nearby landowners who expressed interest in

participating in the project and entered land use agreements for the relevant parcels accordingly to

create a contiguous site.

Case No. 2024-00253

Request No. 4:

Explain how a non-contiguous Project site can be developed and function as single integrated

Project.

Response No. 4:

Parcels which are not immediately adjacent can still be developed effectively to produce electricity.

Clover Creek will utilize medium voltage collection lines to connect the applicant's generation

infrastructure throughout the site. These collection lines and the easements through which they run

effectively create one contiguous/integrated electrical generation facility (the "Project"). See

Application Exhibit B, Site Layout Map and Parcel Map.

Request No. 5:

Explain how power generated within the non-contiguous portions of the Project site will be

delivered to the substation.

Response No. 5:

As described in the Response to Request No. 4, the site is contiguous. Power produced at any

location within the Project will be delivered to the substation through medium voltage collection

lines.

Request No. 6:

Explain whether the construction and operational entrances will be locked outside of normal

working hours.

Response No. 6:

It is anticipated that construction and operational entrances for the site will be secured and/or

locked as necessary outside of those hours identified in the Response to Request No. 8.

Request No. 7:

Provide a schedule for the project, starting from the receipt of the proposed certificate for construction to the completion of the project, including the length of each construction phase.

Include when the peak construction would occur within the timeline.

Response No. 7:

A preliminary Project schedule is shown below. These estimated dates are subject to change based on actual ongoing industry-wide supply chain constraints, feasible delivery timeframes of equipment, procurement items, execution of labor contracts, and inclement weather conditions. Peak construction is anticipated to occur between Q3 2025 and Q3 2026.

Milestone	Timeframe (est.)
State Siting Board Construction Certificate	Q2 2025
State Permitting: Floodplain, Stormwater, and other Environmental Permits	Q2 2025
Federal Permitting: USACE Jurisdictional Determination	Q2 2025
EPC Mobilization	Q2 2025
Grading: Access roads and entrances begin	Q2 2025
Peak Construction (grading/pile install)	Q4 2025
Substantial Completion	Q3 2026

Case No. 2024-00253

Request No. 8:

Provide what time of day construction, operation and maintenance activities will begin and end

each day.

Response No. 8:

Construction activities will occur Monday through Saturday between 7:00 a.m. and 7:00 p.m.

Construction will not be conducted on Sundays unless necessary to make up for delays or to meet

deadlines. Non-construction activities will occur Monday through Sunday from dawn until dusk,

and may take place prior to 7:00 a.m.

Request No. 9:

Provide a narrative description of the location of each laydown area to be used during construction.

Response No. 9:

Please see the narrative table below for descriptions of laydown areas.

Name	Acres	Parcel ID	Main Road	Length
Laydown Area 1	0.8	44-12	Hwy 60	301 Feet Northeast of main road
Laydown Area 2	2.27	44-26	Hwy 60	785.3 Feet Northeast of main road
Laydown Area 3	1.5	58-12	Hwy 60	5,223.9 Feet Northeast of main road
Laydown Area 4	1.12	58-13A	Hwy 60	4,000 Feet Northeast of main road
Laydown Area 5	0.4	58-13A	Hwy 60	4,400 Feet Northeast of main road
Laydown Area 6	2.53	58-12	Hwy 60	3,016 Feet East of main road
Laydown Area 7	1.32	58-13A	Hwy 60	3,688.5 Feet East of main road
Laydown Area 8	2.06	44-26	Hwy 60	360 Feet Northeast of main road
Laydown Area 9	0.93	44-27A	Hwy 60	309 Feet Southwest of main road
Laydown Area 10	0.62	44-32	Skillman Monarch Ln	150 Feet North of main road
Laydown Area 11	0.68	44-23	Skillman Monarch Ln	1,284 Feet South of main road
Laydown Area 12	1.37	44-23	Skillman Monarch Ln	5,230 Feet Southeast of main road
Laydown Area 13	0.32	59-11C	Hwy 259	2,317 Feet Southwest of main road
Laydown Area 14	0.68	59-11C	Hwy 259	2,871.7 Feet Southwest of main road
Laydown Area 15	2.41	44-23	Skillman Monarch Ln	3,291.3 Feet South of main road
Laydown Area 16	0.36	59-4E	Hwy 60	1,442.8 Feet West of main road
Laydown Area 17	0.54	59-4E	Hwy 60	4,531.3 Feet West of main road
Laydown Area 18	1.32	45-9	Skillman Monarch Ln	6,542.3 Feet South of main road
Laydown Area 19	1.1	45-9	Skillman Monarch Ln	8,201.8 Feet South of main road
Laydown Area 20	0.99	60-6	Hwy 261	6,515.8 Feet West of main road
Laydown Area 21	0.76	74-1	Hwy 261	2,180.8 Feet West of main road
Laydown Area 22	1.45	60-6	Hwy 261	5,386 Feet West of main road
Laydown Area 23	0.45	74-1	Hwy 261	150 Feet West of main road
Laydown Area 24	0.61	74-1	Hwy 261	739.8 Feet Southeast of main road
Laydown Area 25	2.21	60-6	Frank Farm Ln	253.9 Feet South of main road
Laydown Area 26	0.4	60-7	Miller Ln	551.3 Feet North of main road
Laydown Area 27	0.81	60-10	Bens Hole Branch Rd	1,592.6 Feet South of main road
Laydown Area 28	0.68	60-10	Bens Hole Branch Rd	2,981.4 Feet South of main road

Responding Witness: Chad Martin

Request No. 10:

Provide a narrative description of the location to each of the following site features:

- a. Each construction entrance.
- b. Each entrance to be used in operations.
- c. Operation & Maintenance (O&M) area.
- d. Each laydown area.

Response No. 10:

- a. Narratives for the Project's 11 proposed construction entrances are as follows:
 - i. <u>Construction Entrance 1</u>: Located in the northern part of the Project, off of the east side of Highway 60 by Parcel 44-12. This proposed construction entrance will be utilized during construction for potential laydown yard 1, and the proposed array on that parcel.
 - ii. <u>Construction Entrance 2</u>: Located in the northern part of the Project, off of the east side of Highway 60 by parcel 44-26. This proposed construction entrance will be utilized during construction for potential laydown yard 2, and the proposed solar array on that parcel.
 - iii. <u>Construction Entrance 3</u>: Located in the northern part of the Project, off of the east side of Highway 60 by parcel 58-12. This proposed construction entrance will be utilized during construction for potential laydown yards 3, 4, 5, 6, 7, and 8, and the proposed solar array on parcels 58-12 and 58-13A.
 - iv. <u>Construction Entrance 4</u>: Located in the northern part of the Project, off of the west side of Highway 60 by parcel 44-27A. This proposed

construction entrance will be utilized during construction for potential laydown yards 9, 10, 11, 12, 15, 18, and 19 and the proposed solar array

on parcels 44-27A, 44-32, 44-23, and 45-9.

- v. <u>Construction Entrance 5</u>: Located in the northeastern part of the Project, off of the south side of KY 259 by parcel 59-15. This proposed construction entrance will be utilized during construction for potential laydown yards 13 and 14 and the proposed solar array on parcel 59-11C.
- vi. <u>Construction Entrance 6</u>: Located in the central part of the Project, off of the west side of Highway 60 by parcel 59-4E. This proposed construction entrance will be utilized during construction for potential laydown yards 16 and 17 and the proposed solar array on parcel 59-4E.
- vii. <u>Construction Entrance 7</u>: Located in the southern part of the Project, off of the north side of KY 261 by parcel 74-1. This proposed construction entrance will be utilized during construction for potential laydown yards 20, 21, 22, and 23, and the proposed solar array on parcels 74-1 and 60-6.
- viii. <u>Construction Entrance 8</u>: Located in the southern part of the Project, off of the south side of KY 261 by parcel 74-1. This proposed construction entrance will be utilized during construction for potential laydown yard 24 and the proposed solar array on parcel 74-1.
- ix. <u>Construction Entrance 9</u>: Located in the southern part of the Project, off of the south side of Frank Farm Lane by parcel 60-6. This proposed construction entrance will be utilized during construction for potential laydown yard 25 and the proposed solar array on parcels 60-6 and 60-7.

- x. <u>Construction Entrance 10</u>: Located in the southern part of the Project, off of the north side of Miller Lane by parcel 60-7. This proposed construction entrance will be utilized during construction for potential laydown yard 26 and the proposed solar array on parcel 60-7.
- xi. <u>Construction Entrance 11</u>: Located in the southern part of the Project, off of the south side of Miller Lane by parcel 60-10. This proposed construction entrance will be utilized during construction for potential laydown yard 27 and 28 and the proposed solar array on parcels 60-10.
- b. Clover Creek Solar intends to use the 11 proposed construction entrances described in Response No. 10(a) above as entrances during the Project's operations phase.
- c. The proposed O&M Area is located in the northern part of the project, on the east side of Highway 60 by Construction Entrance 2. The O&M area is proposed to be placed on parcel 44-26, which will allow for easy ingress and egress for the operations and management teams.
- d. See Response to Request No. 9 above.

Request No. 11:

Provide a detailed table listing all residential structures located within 2,000 feet of the Project boundary line. For each structure, provide:

- a. The distance to the boundary line.
- b. The distance to the closest solar panel.
- c. The distance to the nearest inverter.
- d. The distance to the substation.

Response No. 11:

- a. Please refer to Table A.1 of the Sound Study, SAR Attachment D, for a table containing all residential structures within 2,000 feet of the Project boundary line.
- b. See Response to Request No. 11(a) above.
- c. See Response to Request No. 11(a) above.
- d. See Response to Request No. 11(a) above.

Responding Witness: Chad Martin

Case No. 2024-00253

Request No. 12:

Provide a detailed table listing all non-residential structures located within 2,000 feet of the Project

boundary line. For each structure, provide:

A description of any structure (barn, commercial building, warehouse, church, etc.). a.

The distance to the boundary line. b.

The distance to the closest solar panel. c.

d. The distance to the nearest inverter.

The distance to the substation. e.

Response No. 12:

a. Please see the attached Non-Residential Structure Table ("Table") for the

description of any structure located within 2,000 feet of the Project boundary line,

including the distance of each to the boundary line, to the closest solar panel, to the nearest

inverter, and to the substation.

b. Please see Table.

c. Please see Table.

d. Please see Table.

Responding Witness: Chad Martin

#	Structure Type	Feet to Nearest Fenceline	Feet to Nearest Panel	Feet to Nearest Inverter	Feet to Nearest Substation
1	Auto Shop	519.6	788.8	1638.7	15816.0
3	Whitworth Tool Inc	1624.5	2026.1	2717.2	1412.7
4	Barn	1344.6	1875.4	2451.6	965.4
5	Breck County Ready Mix Company	1499.4	2099.5	2525.6	386.9
6	Trailersaver Company	753.1	1356.3	1826.4	1086.7
7	Atlas Machine and Supply Company	1069.9	1399.4	2150.6	1656.6
8	Substation	2237.9	2826.3	3264.3	0.0
9	Texas Gas Transmission	1364.5	1487.6	2192.8	3900.3
10	Barn	433.0	566.3	1311.8	3126.9
11 12	Barn	1845.7 1886.7	1914.0 2154.4	1914.8 2994.7	17119.8
13	Barn Barn	460.4	502.2	1145.2	16922.3 16186.5
14	Barn	727.6	764.5	1621.3	15182.2
15	Barn	521.9	559.4	1403.3	15351.9
16	Barn	477.3	506.0	1355.4	15009.2
17	Shop	555.7	678.1	1557.0	15649.6
18	Barn	493.1	534.6	1046.5	14367.0
19	Barn	291.0	316.3	942.6	14446.8
20	Shop	457.7	519.0	824.6	12899.4
22	Barn	225.1	264.0	1065.1	12735.1
23	Shop	827.6	1343.3	1544.8	13850.5
24	Barn	1816.2	1931.2	3135.0	12500.3
25	Barn	2030.2	2144.5	2347.4	14787.5
26	Barn	1581.4	1624.5	2306.3	13924.5
27	Barn	1647.0	1703.1	1699.2	13736.1
28	Barn	1309.4	1346.6	2361.1	9836.4
29	Barn	1830.5	1859.4	2958.0	9531.3
30	Shop	1023.0	1054.5	2051.3	9895.6
31	Barn	1437.5	1473.3	2500.3	9898.5
32	Barn	1262.5	1288.8	2423.5	9174.0
33	Barn	1500.7	1532.5	2636.5	9543.5
34	Barn	1733.0	1777.4	2827.8	9553.0
35	Barn	1529.1	1650.6	2049.0	8650.9
36	Barn	1906.0	1935.8	2720.4	9220.8
37	Barn	1478.1	1589.8	1930.1	8243.0
38	Barn	1897.8	2010.1	2323.0	8225.7
39	Barn	1173.1	1226.2	1895.2	8014.4
40	Barn	1400.2	1441.0	2102.6	8252.9
41	Barn	1150.3	1183.4	1836.9	8017.4
42	Barn	1050.6	1040.2	1713.9	7944.4
43	Barn	631.7	662.2	1300.1	7452.7
44	Barn	600.5	659.2	1362.8	7601.2
45	Barn	524.0	606.0	1129.4	7312.2 7112.0
46	Barn	422.7	635.2	1096.1	
47	Barn	735.6	1057.9	1461.0	7379.0 6787.0
48	Barn	686.5 847.7	796.2 952.0	1534.3 1656.1	6/8/.0
49 50	Barn Barn	847.7 943.8	952.0 1015.2	1687.7	7136.0
51	Barn	1634.4	1773.6	2498.9	7705.5
52	Barn	862.9	975.2	1752.3	6655.2
53	Barn	1633.7	1731.4	2374.6	7701.5
54	Barn	1763.5	1875.5	2634.6	7525.9
55	Barn	1903.2	2022.8	2725.3	7780.6
56	Texas Gas Transmission	1174.5	1254.9	2137.7	3378.8
57	Barn	1920.9	2029.5	2894.0	3034.8
58	Barn	613.3	747.6	1625.0	2702.0
59	Barn	544.2	658.5	1544.0	2617.6
60	Barn	1914.3	2002.0	2873.3	2874.4
61	Greenhouse	1458.7	1600.7	2016.1	4369.3
62	Substation	3181.6	3603.5	3850.3	0.0
63	Barn	1691.1	1799.1	2589.0	6017.1
64	Barn	922.0	1022.9	2150.0	10307.3
65	Barn	1433.4	1494.6	2319.9	10413.9
66	Agricultual buildings	400.8	427.8	1007.4	8857.9
67	Barn	296.1	384.7	745.0	8904.7
68	Agricultual buildings	383.8	423.1	1173.6	8549.8
	-				
69	Barn	369.5	281.0	1155.0	10200.0

71	Barn	535.0	812.6	1544.5	7119.0
71	Barn	610.0	831.0	1538.8	6803.0
72	Barn	135.3	156.8	940.9	8827.3
73	Barn	160.0	216.3	1038.0	8800.0
74	Barn	2221.7	2224.0	2668.5	2649.0
75	Barn	2811.0	2817.6	3214.4	1995.7
76	Barn	2805.0	2820.3	3214.4	1999.3
78	Barn	2383.5	2441.4	2962.7	2630.7
79	Garage/Barn	1286.2	1615.7	2097.2	3658.4
80	Barn	1361.5	1656.9	2172.9	3952.1
81	Barn	1543.0	1767.2	2290.2	3927.8
82	Barn	1637.0	1889.3	2373.1	3616.6
83	Shop	2016.0	2215.2	2730.4	3662.2
84	Shop	1976.0			
85	Shop	2001.0	2199.3 2233.7	2744.0 2772.4	4052.3 3754.8
86	Barn	1869.0	2050.0	2662.3	6599.3
87					6586.2
	Barn	1871.2	2052.2	2667.4	
88	Barn	142.4	182.8	961.5	7733.7
89	Barn	209.7	227.9	874.5	7729.9
90 91	Barn Dilanidated Barn	496.2	568.6 131.4	819.9 425.9	10997.3
	Dilapidated Barn	111.4			10818.8
92	Barn	140.0	286.2	247.7	10851.0
93	Barn	843.5	850.6	861.5	10241.4 10321.6
94	Barn	871.6 420.1	956.6 497.6	917.7	9744.8
95 96	Shop Shop	420.1 578.0	497.6 716.6	708.6 881.2	9744.8 9953.9
			1887.8		
97	Shop	1820.9		2254.8	13421.9
98	No structure	1365.3 1026.0	1541.2	2285.5	11992.0
99	Barn		1201.8	1939.6	11939.4
100	Shop	852.7	985.1	1791.6	11619.1
101	Shop	799.8	928.5	1748.0	11092.7
102	Shop	822.3	946.2	1753.8	11622.8
103	Barn	662.8	795.8	1616.7	11221.7
104	Barn	580.5	686.2	1520.4	11056.6
105 107	Barn	536.1 414.4	611.3	1404.0	10799.0 10384.9
107	Shop No structure, in middle of panels	141.0	511.7 0.0	1694.0 715.0	9093.1
109	No structure, in middle of panels Barn	1241.3	1301.1	2228.9	10359.7
110	Barn	1482.9	1538.5	2421.5	10648.6
111	Barn	1661.2	1703.1	2638.1	10714.3
112	Dilapidated Structure	186.3	234.6	785.7	9169.7
113	Barn	431.3	549.4	1093.7	9473.0
114	Shop	1575.3	1643.4	2038.9	11606.3
115	Shop	1955.3	2072.2	2562.5	11543.6
116	Barn	184.0	238.6	914.1	9251.0
117	Barn	147.0	204.4	893.6	8253.6
117	Shop	633.6	700.3	1275.9	7752.1
119	Shop	1098.1	1134.4	1657.2	8531.4
120	County Coop Building	1111.9	1168.2	1754.2	8266.8
121	Recycle Center	1352.2	1414.9	2347.2	9399.3
122	Business	1981.3	2021.9	2654.1	8614.5
123	Business	1741.9	1829.1	2443.9	8099.8
123	Business	1741.9	1846.0	2547.3	7974.4
125	Business	1872.1	1954.3	2563.2	8089.2
126	Shop	822.0	861.4	477.9	6045.8
127	Barn	1623.2	1789.4	2218.3	4733.3
128	Barn	1631.0	1789.4	2224.5	4743.0
129	Barn	959.0	962.2	1551.6	11252.1
130	Barn	935.1	971.9	1580.8	11269.3
131	Barn	511.0	517.3	1151.0	10891.1
131	Shop	324.5	399.2	669.7	10222.7
133	Shop	1124.8	1175.7	1741.8	11830.1
134	Barn	1135.3	1175.7	1741.6	11812.3
135	Shop	1009.1	1131.4	2458.6	10335.4
136	Shop	826.2	941.3	2224.6	11703.6
130	onop	020.2	341.0	2224.0	
127	Shon	1015.2	1126.2	2201.2	112155
137 138	Shop Shop	1015.2 1793.5	1126.2 1831.9	2201.2 2326.7	11815.5 12220.0

Request No. 13:

Refer to the Application, Record of Environmental Violations at 12. Provide the entities with a

direct ownership interest in Clover Creek Solar. Also provide the corporate structure of those


entities.

Response No. 13:

Please see the attached organizational chart for entities with a direct ownership interest in Clover

Creek Solar and the corporate structure of those entities.

CLOVER CREEK SOLAR PROJECT LLC Ownership Chart



Case No. 2024-00253

Request No. 14:

Provide a list of permits that will be required from any other local, state, or federal agencies for

the project. Include in the response the status of those permits.

Response No. 14:

All necessary air, water, and waste permits and authorizations will be obtained before construction

and operation of the Project. The Project's final site design will determine which permits will be

required. Please see the attached list of potential permit authorizations that may be required for

Project development.

Additionally, Breckenridge County currently has an ordinance that references three types of solar

energy systems (SES) with correlating requirements for each type. However, this ordinance does

not define the types of SES or give guidance as to what constitutes an SES, and it further does not

contain any processes or procedures for preparing or filing an application for an SES. As such,

Breckenridge County does not have a local permitting process that applies to the Clover Creek

Solar Project at this time. Notably, the Project meets or exceeds the setbacks described in the

ordinance. Breckenridge County does not have a comprehensive plan or a Planning Commission.

Clover Creek Solar Project Permit Matrix				
Permit	Agency	Status	Notes	
Federal				
Clean Water Section 401/404 Permit(s)	U.S. Army Corps of Engineers	Start: December 2024 (if applicable) End: March 2025 (target)		
Endangered Species Act (ESA) Section 7 Consultation	U.S. Fish & Wildlife Service	Start: Summer 2024 (coordination in progress) End: March 2025 (target)	Submitted contribution to imperiled bat fund mitigation; commenced coordination with Kentucky Department of Fish and Wildlife Resources.	
Migratory Bird Treaty Act (MBTA)	U.S. Fish & Wildlife Service	No permit anticipated, general USFWS coordination in progress.		
Bald and Golden Eagle Protection Act (BGEPA)	U.S. Fish & Wildlife Service	No permit anticipated, general USFWS coordination in progress.		
State				
Construction Certificate	Kentucky State Board on Electric Generation and Transmission Siting	Start: November 4th, 2024 End: May 3rd, 2025	Certificates will be for generation facility and nonregulated electric transmission line.	
KPDES KYR10 Stormwater Construction General Permit	Kentucky Energy and Environment Cabinet, Division of Water	Not yet submitted; anticipated submittal 90 days prior to construction.	Includes submittal of Storm Water Pollution Prevention Plan.	
Floodplain Construction Permit	Kentucky Energy and Environment Cabinet, Division of Water	Not yet submitted.		
National Historic Preservation Act - Section 106 Consultation	Kentucky Heritage Council - State Historic Preservation Office	Not yet submitted; no permit anticipated.		
Threatened & Endangered Species Consultation	Kentucky Department of Fish and Wildlife Resources	Start: November 2024 End: January/February 2025	No permit anticipated, coordination in progress.	
Road Encroachment Permit(s)	Kentucky Transportation Cabinet	Not yet submitted.		
Utility Crossing Permit(s)	Kentucky Transportation Cabinet	Not yet submitted.		
Overweight/Over-Dimensional Permit	Kentucky Transportation Cabinet	Not yet submitted.		
Building Permit	Kentucky Dept. of Housing, Building and Construction	Not yet submitted.	For O&M building.	
Local				
Road Use Agreement	Breckinridge County Fiscal Court	Not yet submitted.	Applicant anticipates Breckinridge County to require road repair language in the form of MOU or Resolution that is executed. Contractor to support repairs as required.	
Decommissioning Agreement	Breckinridge County Fiscal Court	Not yet submitted.	Plan to have resolution signed by county that states that we are in compliance with 2022 ordinance, which outlines decommissioning requirements	

Case No. 2024-00253

Request No. 15:

Refer to the Site Assessment Report (SAR), Attachment A, Preliminary Site Layout. The map that


is provided is not legible. Provide an updated site plan for the proposed project that is of sufficient


quality. Separate the site plan into discrete project areas and file the documents separately so each


one can be accessed and enlarged.

Response No. 15:

Please see the attached updated SAR Attachment A.









Request No. 16:

Refer to the SAR, Attachment A, Preliminary Site Layout. Provide a one page site map that


contains the locations water features, including rivers, streams, lakes, and ponds. Also include any

known or suspected karst features.

Response No. 16:

Please see the attached site map showing water and karst features.

Responding Witness: Chad Martin



Request No. 17:

Explain whether the perimeter security will be installed according to National Electrical Safety

Code (NESC) standards. Include in the response whether the fencing will be installed before any

electrical work begins.

Response No. 17:

The perimeter security fence will be installed in accordance with the applicable NESC standards

prior to commencing any electrical work.

Request No. 18:

Explain whether the substation have its own separate fencing and will it comply with NESC standards.

Response No. 18:

The Project substation will have its own separate fencing compliant with the applicable NESC standards.

Request No. 19:

Provide the total length of cabling to be used in the projects' collection system.

Response No. 19:

It is anticipated that 75,100 Linear feet of collection cabling will be dispersed throughout the Project area.

Request No. 20:

List all churches or other religious facilities within a two-mile radius of the project. Provide the corresponding distances from the facility to the closest site boundary.

Response No. 20:

Please see the below table of churches within two miles of the project including corresponding distances. Also refer to the map included in Application Exhibit B, Sensitive Resources within Two Miles of the Project.

Name	Address	GPS	Distance (miles)	Direction from Project area
Hardinsburg Baptist Church	515 US Highway 60 Byp, Hardinsburg, KY 40143	37.761673°- 86.470590°,	0.01	E; Immediately adjacent to central portion of Project
New Bethel Church	504 Highway 2779, Hardinsburg, KY 40143	37.830358°, -86.503524°	0.83	N
St. Romuald Catholic Church	N Main St, Hardinsburg, Ky 40143	37.786660°, -86.461633°	0.5	Е
Hardinsburg United Methodist	123 S Main St, Hardinsburg, KY 40143	37.781549°, -86.460962°	0.58	Е
Talbert Chapel Methodist Church	312 E 2nd St, Hardinsburg, KY 40143	37.782033°, -86.456181°	0.86	E
Restorations Church	419 3rd St Hardinsburg, KY 40143	37.781970°, -86.453008°	1.39	Е
First Baptist Church	142 Docile Dr Hardinsburg, KY 40143	37.783400°, -86.452567°	1.93	Е
Kingdom Mission Church	221 Ball Park Rd Hardinsburg, KY 40143	37.764369°, -86.444513°	0.89	Е

Responding Witness: Chad Martin

Request No. 21:

Provide any communication with any churches or other religious facilities regarding the project.

Provide any concerns that were raised.

Response No. 21:

Project representatives spoke with Pastor Tod Brown from the Hardinsburg Baptist Church to

address various concerns and questions received from church congregants. To the best of project

representatives' knowledge, there have been no follow up conversations or similar requests.

Request No. 22:

Explain if an Engineering, Procurement, and Construction (EPC) firm has been selected for the

project. Provide the request for proposal (RFP) for the EPC contractor.

Response No. 22:

Please see the attached RFP. At this time, two EPC firms will work on the Project. PCL Industrial

Construction Company will perform photovoltaic and medium voltage work, and M.J. Electric

will perform any high voltage work.



CONFIDENTIAL AND INTENDED FOR ADDRESSES ONLY

Request for Proposal

EDP Renewables North America, LLC

Clover Creek Solar Park LLC

Date: July 8, 2022



Table of Contents:

1.		Introduction
2.		Acknowledgement of Receipt5
3.		Project Overview6
4.		Proposal Guidance
5.		Bidder Questions
6.		Submission of Proposal
i		Exhibit Tracker7
i	i.	Pricing7
i	ii.	Bidder Questions
İ	v.	Modifications/Clarifications8
١	/ .	Addendum to the RFP Documents8
١	/i.	Governing Contract
7.		Assignment9
8.		Confidentiality9
9.		Proposal Submittal Format and Table of Contents9
10.		Evaluation of Proposals
11.		Enclosures
i		Attachment 1, Exhibit Tracker
i	i.	Attachment 2, Modifications Document, Design Guidelines and Requirements
i	ii.	Pricing Sheet



1. Introduction

EDP Renewables North America, LLC "EDPR NA" and or "Company" is pleased to invite you to submit a competitive proposal for the scope(s) of work listed in Section 2 herein (the "Acknowledgment of Receipt") and as more fully described in the exhibits referenced herein. This Request For Proposal ("RFP") shall be open to those parties directly contacted by the Company (each a "RFP Participant"). Those eligible parties responding to this RFP (each a "RFP Respondent" or "Bidder") are requested to provide the proposal(s) (each a "Proposal" or "RFP Proposal") for the scope(s) of work requested (the "Services"). In preparing the Proposal, it is essential that all requirements of the enclosed RFP are adhered to.

All Proposals must be received by the RFP Manager (as defined below) by the deadline set forth in the Acknowledgment of Receipt and will be reviewed after that time. Late or incomplete Proposals will not be considered. Proposals, including proposed prices shall be extended and remain FIRM and binding on the RFP Respondent(s) through the earlier of: (i) the date of the completion of negotiations of the EPC Agreement (the "Contract") or (ii) one hundred eighty (180) days. Such period may be extended by mutual agreement of the RFP Respondent and Company.

A duly authorized officer of the RFP Respondent must sign the Proposal. All materials and Proposals received by the Company from the RFP Respondents in response to this RFP will not be returned to the RFP Respondents. All materials and Proposals submitted by the RFP Respondents will become the property of the Company and may be used by the Company for the purpose of evaluating the Proposals, executing any Contracts, and administering any resulting definitive agreements.

The Company reserves the right to revise, suspend, or terminate this RFP and any schedule related thereto, in its sole discretion, without liability to the RFP Participants and/or RFP Respondents. The Company reserves at all times the right to invite additional parties to participate in this RFP and change the technical and other requirements of the Project.

The Company, in its sole discretion, shall evaluate and select Proposals that, if any, provide the most value to the Company. The Company shall determine in its sole discretion the value of the Proposals. The Company shall evaluate the Proposals in terms of price and non-price attributes.

Without limiting any other provision of this RFP, the Company reserves the right, without qualification and in its sole discretion:

- To reject any or all Proposals or any portion of any Proposal received for failure to meet any criteria set forth in this RFP or otherwise
- To decline to enter into an arrangement with any Participant, terminate negotiations with any Participant, or to abandon the RFP process in its entirety at any time and without notice to RFP Participants thereof
- To make an award on a basis other than lowest priced Proposal
- To waive any failure of any Proposal to comply with the requirements of this RFP or to decline to disqualify a non-compliant Proposal
- To re-issue a request for proposals for all or any part of the scope of work that is the subject of this RFP, with or without any additional scope, at a later time
- To decline to enter into an arrangement with any Participant, terminate negotiations with any Participant, or to abandon the RFP process in its entirety any time and without notice to Participants



 To make an award to any one or multiple Participants of the RFP process for all or any part of the scope of work.

Those RFP Respondents who submit Proposals agree to do so without any legal recourse against the Company, its affiliates or subsidiaries, and their directors, officers, employees and agents; for rejection of their Proposal(s) or for failure to execute an agreement for any reason. The Company shall not be liable to any RFP Respondent or party in law or equity for any reason whatsoever for any acts or omissions arising out of or in connection with this RFP. By submitting its Proposal, each RFP Respondent waives any right to challenge any valuation by the Company of any Proposal, of any RFP Respondent, any other decision of the Company contemplated by this RFP, or any resulting commercial relationship related to a selected Proposal. Each RFP Respondent, in submitting its Proposal, irrevocably agrees and acknowledges that it is making its Proposal subject to and in agreement with the terms of this RFP and agrees that the Company shall be entitled to specific performance of their rights hereunder and injunctive relief.

Each RFP Participant and RFP Respondent shall solely bear all costs incurred to compile, prepare, submit, or negotiate its Proposal, the Contract, or for any other activity related thereto (such as phone calls, meetings, negotiations, etc.). All Proposals are submitted at the RFP Participant's own free will. RFP Participants and RFP Respondents will not be reimbursed for any cost associated with this RFP.

Each Bidder is requested to sign and return a completed Acknowledgement of Receipt (Section 2) via email, along with the first 5 pages of this RFP, in a single pdf, addressed to the RFP Manager; such submittal shall be referred to as the "Intent to Bid".

Regards,
Amy Zaczek

RFP Manager EDP Renewables North America LLC 346-445-4207 Amy.Zaczek@edp.com



2. Acknowledgement of Receipt

RECEIPT ACKNOWLEDGED:

Acknowledgement of Receipt for Services includes acceptance of the terms and conditions described in this RFP with intent to submit a technical and commercial Proposal as shown in the RFP Milestones below.

Project Name	Solar Capacity	Scope	Location
Clover Creek Solar Park LLC	100MWac	Solar PV/MV	Breckenridge, Kentucky

RFP Milestones	Date
RFP RELEASE Date	July 8, 2022
Intent to Bid Due Date (5:00PM CST)	July 14, 2022
Submission of all Clarifications / Questions	July 29, 2022
Proposal Due Date	August 19, 2022
The below is an approximate timeline for review and short List fo lack of adherence to the criteria set forth in this RFP and / or delay the exhibits included in this RFP, may delay short list and / or the 0	of review and acceptance of
Company Technical & Commercial Review	August 2022
Short List	September 2022
Contract Execution Date	November 2022

Please Sign: _______ Date: ______ Company: ______ Name: _____ Title: _____ SHAREFILE ACCESS: Please confirm the names and email addresses to be given Sharefile access where the RFP documents may be found. Name: ______ Email: ______



3. Project Overview

EDP Renewables North America, LLC ("EDPR NA" or "Company") and its subsidiaries (each a "Company") develop, construct, own, and operate wind farms and solar parks throughout North America. Headquartered in Houston, Texas, with more than 7,300 megawatts (MW) and operates more than 7,000 MW of renewable energy projects. With approximately 700 employees, Company's highly qualified team has a proven capacity to execute projects across the continent.

RFP Respondents will be asked to provide a Proposal in accordance with Company's RFP requirements as requested herein. RFP Respondent shall provide competitive pricing as a fixed fee Proposal for the Services that Bidder is capable in performing in accordance with the Contract and all applicable exhibits.

Project Name	Solar Capacity	Scope	Location
Clover Creek Solar Park LLC	100MWac	Solar PV/MV	Breckenridge, Kentucky

4. Proposal Guidance

EDPR NA is providing bidders with multiple technical exhibits to support the bid process. The bidders shall consider all technical exhibits and information to support their Proposal. It is the intent of EDPR NA to have the bidders provide a layout optimized to the minimum P50 provided in Exhibit D6 as a part of the Submission (Section 6). The layout should be based on, but not limited to, the site information Exhibit H, the constraints map in Exhibit H2 and Design Requirements.

As guidance, EDPR NA has provided parameters in Exhibit D6 used to generate the P50. The bidders have the freedom to optimize these parameters as long as the minimum P50 is obtained. The bidder may use the EDPR provided parameters as the basis of their bid if they choose not to optimize. However, additional time will not be provided later in the bid process to further optimize the layout. A longer time period has been provided in the first round to allow bidders to give the lowest cost of project while still hitting the minimum P50. For the energy analysis, the bidders shall use the EDPR provided PVSYST inputs, which includes requirements on weather files, losses, module performance and other items (Attachment 1 to Exhibit D6).

The Proposal shall include equipment from the approved vendor list as defined in Exhibit I-1. The base bid should assume only these vendors and if savings are available using other vendors, a value add option should be provided or if others are requested then Bidder shall bear the risk prior to the approval designation by EDPR post execution. The bidders should take note of the early milestones required for the design and construction of the switchyard access road and pad. EDPR needs to understand the start time required to support this to ensure the feasibility of supporting this.

5. Bidder Questions

All requests, questions, and communications regarding the commercial and technical aspects of this RFP shall ONLY be directed to the email designed herein, addressed to the RFP Manager and must be submitted by RFP Milestone dates set forth in Section 2 (Acknowledgment of Receipt). Responses to Bidder questions will be provided to all Bidders by Company.



6. Submission of Proposal

The goal of releasing this RFP is to award and execute a Contract for the Services by the Contract Execution date shown in Section 2. Bidder's Proposal for this RFP shall be submitted/uploaded to the Sharefile link provided by the RFP Manager by the Proposal Due Date in Section 2. All of the documents/exhibits in this RFP package will be shared by Company to Bidder(s) use Sharefile. A link to this Sharefile folder will be shared by the RFP Manager via email once the Intent to Bid has been signed and returned. Any additional documentation to the RFP will be shared via a formal Addendum in an email. Any additional team members Bidder wants to access the RFP package in Sharefile, should be included in the signed Intent to Bid. Any individuals added to the Sharefile site should receive an email within twenty four (24) hours with instructions on how to access the RFP documentation. If you do not receive this email in your inbox, please check your spam.

All Proposals must be received by the RFP Manager via Sharefile **NO LATER THAN** the Proposal Due Date set forth in Section 2. Late or incomplete Proposals will not be considered.

- 6.1 "Exhibit Tracker" in Attachment 1 has been provided to Bidders in an excel document to be used as a checklist for all documentation that the Company has released to Bidder at the time of the RFP. Due to the nature of the type of Service and/or the timing of release, some items may be marked as 'Not Provided'. Bidder shall produce all documents that show "Contractor" as the owner of the Exhibit in the table. Any items that have been 'Provided' to Bidder from EDPR, should receive a response status from Bidder, for example "In Process, see Redline" or "Accepted as Final". Please note that all line items should be used as a comprehensive action items list (checklist) to complete prior to the Proposal submission to Company. Bidder shall provide their status and any applicable notes to each line item before sending back to Company.
- **6.2 Pricing:** Pricing shall be submitted on the Pricing Sheet and Exhibit F-1 Milestone Payment Schedule, also referred to as the "**Schedule of Values**", which have been provided in this RFP release package. The base price should include all scope as defined in Exhibit A. If the bidders want to propose cost savings options by deviating from the SOW or engineering guidelines they should communicate this through attachment 2 Modification Documents, as further described in Section 5.4 below. For sake of clarity, scope removal is not value engineering option. Please note that Company reserves the right to reject any Proposals that do not include all relevant prices requested in the Pricing Sheet. Contract price, as submitted from the Bidder, shall include, among other things, all materials, supervision, labor, services, equipment, tools, consumables, supplies, testing, warehousing, temporary facilities, utilities, insurance, contractor permits, overhead, and profit in accordance with all of the documents / requirements included in this RFP.

Contract price shall also include any and all sales and use taxes, with the exception of any sales and use tax imposed on Services eligible for exemption and addressed in the draft Contract. The Contract price shall remain FIRM and binding on the Bidder(s) through the earlier of: (i) the date of the completion of negotiations of the [EPC Agreement/BOP Agreement/Construction Agreement] (the "Contract") or (ii) one hundred eighty (180) days from Proposal Due Date in Section 2. The price shall include any anticipated price adjustments for each year (due to escalation or de-escalation) which may occur throughout the completion of the Services.



EDPR's expectation from the Bidder(s) for the pricing is to target 0.62 - 0.64 \$/Wdc for the Azalea Springs project. Bidder shall be able to let EDPR know if they can meet this target pricing range by the Intent to Bid date in Section 2.

- **6.3 Bidder Questions:** All questions and information requests must be submitted prior to the date set forth in the RFP Milestone table in Section 2 (Acknowledgment of Receipt), and should be provided in a list format via email to the RFP Manager.
- **6.4 Modifications/Clarifications**: The Completed Modifications Document in Attachment 2 should be used for ANY project specific proposed modifications to the RFP package (except for Exhibit D6, SOW, and Milestone Schedule that we are asking to be made in track changes).

Any modifications, clarifications, exclusions or limitations that are being proposed by Bidder(s) that are not included in Attachment 2 as described above, shall not be made a part of this RFP.

- 6.5 Addendum to the RFP Documents: If new or revised documents are made available after the RFP documents have been sent to Bidders, Company may announce the introduction of the documents by an addendum. This addendum email will include the new or revised documents, an updated Exhibit Tracker, and will specify whether or not the Bidders will receive an extension to revise the Proposal. The extension timeframe shall be reviewed on a case by case basis, as it will be dependent on the revisions provided to the Bidders. If an approved extension is granted, it will include an announcement of an updated RFP Milestone schedule in Section 2. Oral instructions or information concerning the RFP documents provided to Bidders by employees or agents of EDPR NA shall not bind EDPR NA. All communications regarding the commercial and technical aspects of this RFP shall ONLY be directed to the RFP Manager designated herein.
- 6.6 Governing Contract: As part of this RFP, a draft Contract for the Bidder to review and comment will be provided. If not provided at release, it shall be provided during the shortlisting stage which will be communicated to the Bidder by Company. For each Proposal, Company expects the Bidders to provide a detailed redline (if any) of the Contract in Microsoft Word using track changes. However, specifically for the Design Guidelines and Requirements documents, all modifications, assumptions, clarifications, exclusions, and limitations revisions or clarifications should only be documented on the table in Attachment 2 Modifications Document.

Company will carefully review the requested changes to the draft Contract and will consider the degree and nature of the requested changes equally with the other aspects of each Proposal. Company will not negotiate or discuss modifications to the Contract suggested by the Bidder(s) that are not specifically included in the detailed redline via track changes in the Contract. Company reserves the right to make additional revisions and changes to the draft Contract. The redline from the Bidders shall be specific and comprehensive, and comments such as "need to discuss" will not be accepted. Company reserves the right to reject any Proposals that do not include a redlined Contract.

The Bidder explicitly agrees that participation in the RFP process does not create any



contractual relationship between Company or affiliated parties and the Bidder. Bidder may, without prejudice to itself, modify or withdraw a Proposal by written request to Company, provided that the Proposal and any request is received by the applicable Company prior to the Proposal Due.

7. Assignment

Company reserves the right to assign to all and or portions of the Proposals received without the prior written or verbal consent of the RFP Respondent. Company receiving such assignment however shall provide written notice to the RFP Respondent. This notice shall be deemed received when any of the following conditions are met (i) notice personally delivered to the RFP Respondent; (ii) notice delivered within five (5) days after deposit in the United States mail, first class, postage prepaid, and certified; or (iii) notice sent the next business day if sent by reputable overnight courier, provided receipt is obtained and charges prepaid by the Company.

8. Confidentiality

Company will take reasonable precautions and use reasonable efforts to protect any claimed proprietary and confidential information contained in a Proposal, provided that such information is clearly identified on the page by the RFP Respondent as "Proprietary and Confidential". Such information may, however, be made available under applicable state or federal law or other governmental agencies having an interest or jurisdiction in these matters.

Company also reserves the right to release such information to its affiliates and any of their agents or contractors for the purpose of evaluating the RFP Respondent's Proposal, but such agents or contractors will be required to observe the same reasonable efforts and care with respect to such propriety and confidential information as Company. Under no circumstances will Company, any of its affiliates or their respective directors, officers, employees, agents or contractors, be liable for any damages resulting from any disclosure of RFP Respondent's claimed confidential information during or after the solicitation process.

9. Proposal Submittal Format and Table of Contents

Company will review the Proposal(s) from the Bidder(s) in two (2) parallel efforts by having the Bidder(s) divide each submission into a technical and commercial folder. Company will carefully review the technical and commercial proposals from each Bidder to assure all RFP requirements are properly fulfilled. Please use the following as a checklist for proposal submission:

9.1 Technical Proposal Folder: DO NOT INCLUDE DOLLAR AMOUNTS WITHIN THIS FOLDER

- 1. Attachment 1, Exhibit Tracker with status to each exhibit.
- 2. Attachment 2, Modifications Documents. This should include ALL clarifications and assumptions.
- 3. Bidder Technical Proposal
- 4. Exhibit Documents as listed in Attachment 1. Please include native file.
- 5. Value add engineering options
- 6. Contractor's Project Layout (in CAD & PDF)
 - a. Optimized layout to minimum required Project P50;
 - b. EA model to Follow guidelines and requirements of Attachment 1 of Exhibit D6
 - c. PVsyst

9.2 Commercial Proposal Folder:

- 1. Completed Price Sheet including tax
- 2. Contract "red-lined" to the Draft Contract, if applicable (in word)
- 3. Certificate of Insurance, In Alignment with Exhibit W-1
- 4. Any material litigation or arbitration over the past five years



- 5. Audited Financials (past 3 years) Only if not previously qualified by EDPR NA
- 6. Applicable State License. Copy of license for our records with number included.

10. Evaluation of Proposals

The Company will evaluate each Proposal received based on several criteria, to include, but not be limited to the following:

- Implementation plan
- Lump sum price and unit costs
- General qualifications and experience
- Comments/Redlines to the Contract
- Scope exceptions in Attachment 2
- Design Criteria Parameters
- Value engineering propositions
- Overall quality of Proposal based on Company requirements

11. Enclosures:

- 11.1 Exhibit Tracker, Attachment 1
- 11.2 Modifications Document, Attachment 2
- 11.3 Pricing Sheet
- 11.4 Clarifications Document



CLOVER CREEK (PVMV) EXTERNAL FULL-WRAP (PV/MV, HV, BESS) RFP EXHIBIT DETAILS & OWNERSHIP

Commercial Items	CONTRACTOR DELIVERABLE CHECK LIST	CONTRACTOR NOTES (If "Not Provided", add notes here)
Completed Price Sheet including tax		
Draft Contract accepted as is or "red-lined" using track changed in Word		
Certificate of Insurance, in Alignment with Exhibit W-1		
Any material litigation or arbitration over the past five years		
 Audited Financials (past 3 years) – Only if not previously qualified by Company 		
 Applicable State License. Copy of license for our records with number included. 		

Can be filtered

				Can be filtered	
EXHIBIT	ACTIONS FOR CONTRACTOR	CONTRACTOR RFP RESPONSE	OWNER	EDPR SHAREFILE EXHIBIT STATUS	BIDDER NOTES
A Scope Of Work					
A1 EPC Scope of Work	Please confirm review/acceptance in "Contractor RFP Response" column. Any modifications should be redlined in the document.				
A2 Engineering SOW					
(A2.4) PV+ MV (TCSP-NA/TSE&C-PV-00001)	Please confirm review/acceptance in "Contractor RFP Response" column. Any modifications should be redlined in the document.				
(A2.5) PV SCADA	Please confirm review/acceptance in "Contractor RFP Response" column. Any modifications should be redlined in the document.				
A3 Environmental Scope of Work	Please confirm review/acceptance in "Contractor RFP Response" column. Any modifications should be redlined in the document.				
A4 Scope of Work Detailed Task Identification	Please confirm review/acceptance in "Contractor RFP Response" column. Any modifications should be redlined in the document.				
B Contractor Deliverables Table and Job Books					
B1 Contractor Deliverables Table					
(B1.1) PV + MV Deliverable List	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2				
(B1.5) Construction Deliverable List	Modifications/Clarifications. Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.				
B2 Format and Contents of Job Books	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.				
C Permits					
C1 List of Certain Permits	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.				
C2 Road Agreement(s)	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.				
D Technical Specifications					
D2 Engineering General Dsg Guideline (GDG-001)	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.				
D2 PV + MV (TCSP-GLB/TSE&C-PV-00009-03)	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.				
D4 Drawing Templates	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.				
D6 PV + MV Design Criteria Document	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.				
D14 O&M Building Guideline and Specification	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2				
E Project Schedule					
E1 Milestone Schedule	Please confirm acceptance. Substantial completion date must remain intact however EDPR will review <u>redlines</u> to interim milestones. Please also provide gantt style schedule aligned with milestones chedule.				
E2 Delay Liquidated Damages	milestone schedule. Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2 Modifications/Clarifications				
E3 SCADA Milestone Schedule	Modifications/Clarifications. Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.				
F Contract Price					
F1 Milestone Payment Schedule	Please allocate your lump sum price into the format provided. If				
F2 Options Price List	provided, add note in "Bidder Notes" This is to be populated by EDPR if applicable				
G Progress Reports					
G1 Form of Monthly Progress Report	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.				
G2 Form of Daily Progress Report	Please confirm review/acceptance in "Contractor RFP Response" column". If provided, add note in "Bidder Notes"				
H Site					
H1 Geotechnical Report	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.				
H2 Site Layout (pdf and CAD files) and Constraint Map	Please confirm acceptance, any clarifications to be <u>redlined</u> in A1 SOW.				
H4 Phase I ESA	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2 Modifications/Clarifications. Please confirm review/acceptance in "Contractor RFP Response"				
H5 ALTA Survey	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2 Modifications/Clarifications. Please confirm review/acceptance in "Contractor RFP Response"				
H9 Wildlife Assessment	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.				
I Subcontractors					

M. Annound Vondon Unb			
I1 Approved Vendor List	Please confirm review/acceptance in "Contractor RFP Response"		
12 Subcontractor Request Form	Please populate subcontractor table provided by EDPR Form to be included in EPC contract for any subcontractors that		
I3 Form of Approved Subcontractor Conditions Cert.	will be used from AVL with special conditions. Please let us know		
J Tests			
J1 Commissioning Requirement	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2		
J2 Acceptance Tests	Modifications/Clarifications.		
(J2.a) Performance Acceptance Tests (including Capacity	Please confirm review/acceptance in "Contractor RFP Response"		
Tests & Operational Tests	column. Any clarifications to be made on Attachment 2 Modifications/Clarifications. Please confirm review/acceptance in "Contractor RFP Response"		
J3 Performance Ratio Test	column. Any clarifications to be made on Attachment 2		
K Key Personnel	Modifications/Clarifications.		
K1 Personnel Work Chart (Including resumes)	Need organizational chart on hierarchy of governance for project		
L Unit Rate Sheet	execution and any applicable resumes.		
L1 Unit Rate Sheet	Please complete form as provided by EDPR		
M Form of Change in Work Form	Please confirm acceptance, any clarifications to be made on		
M1 Change Order Form	Attachment 2 Modifications/Clarifications.		
N Form of Contractor Performance Security			
N1 Form of Performance Assurance (100% Performance Bond)	Per RFP, provide performance bond price and bond issuer name. EDPR will inform you of specific requirements. Please assume		
O Key Equipment Minimum Warranty Requirements	100% performance bond		
	Please confirm review/acceptance in "Contractor RFP Response"		
O1 Key Equipment Minimum Warranty Requirements	column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.	 	
P Quality Plan			
P1 Quality Plan	Template of quality plan and confirm your intention to provide site specific plan prior to commencement of work		
Q Project Document Requirements	provide commencement of work		·
Q2 Redacted Interconnection Agreement	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2		
	Modifications/Clarifications. Please confirm review/acceptance in "Contractor RFP Response"		
Q4 Landowner Provisions (if applicable)	column. Any clarifications to be made on Attachment 2		
Q5 OSE Supplier Agreement Requirements:	Diogo confirm voltan/c		
(Q5.1) PV Modules	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2		
R Lien Waiver and Release Requirements	Modifications/Clarifications.		
S Completion Certificates (NUMBERING TO BE UPDATED)	Please confirm review/acceptance in "Contractor RFP Response"		
S1 Form of 100% Engineering Completion Certificate	column. Any clarifications to be made on Attachment 2		
S2 Form of Initial Circuit Mechanical Completion Certificate	Modifications/Clarifications. Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2		
	Modifications/Clarifications. Please confirm review/acceptance in "Contractor RFP Response"		
S3 Form of Circuit Mechanical Completion Certificate	column. Any clarifications to be made on Attachment 2		
S4 Form of Initial Circuit Energization Completion Certificate	Modifications/Clarifications. Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2		
341 om of main circuit Energiation completion certificate	Modifications/Clarifications. Please confirm review/acceptance in "Contractor RFP Response"		
S8 Form of Turnover Certificate	column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.		
S9 Form of Substantial Completion Certificate	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2		
55 Torm or substantial completion certained.	Modifications/Clarifications. Please confirm review/acceptance in "Contractor RFP Response"		
S10 Form of Final Completion Certificate	column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.		
T Safety	wountations/Clarifications.		
T1 Project Safety Requirements	Please confirm acceptance, any clarifications to be made on		
	Attachment 2 Modifications/Clarifications. Contractor to provide template of safety plan and confirm your		
T2 Safety Plan	intention to provide site specific plan prior to commencement of work . If provided, add note to "Bidder Notes"		
U Operating Personnel Training Program	NOW. II provided, and note to bidder notes		
	Place provide template training		
U1 Operating Personnel Training Program	Please provide template training program		
V Parent Guarantee (If Applicable)	Please provide Parent Guarantee template for our review and		
V1 Parent Guarantee	any applicable cost implications.		
W Insurance Requirements			
W1 Insurance Requirements	Please confirm review/acceptance in "Contractor RFP Response" column. Any modifications to be redlined with the Draft Contract.		
X Labor Requirements			
Y Confirming Line Documentation			
	Contractor to provide for EDPR review. If provided, please add		
Y1 Bank Verification Letter	note to "Bidder Notes" Contractor to provide for EDPR review. If provided, please add		
Y2 Secretary's Certificate	note to "Bidder Notes"	 	
Z Owner Supplied Equipment	Please confirm review/acceptance in "Contractor RFP Response"		
Z1 Delivery Schedule	column. Any clarifications to be made on Attachment 2		
73 Decease for Material - December - Lands	Modifications/Clarifications. Please confirm review/acceptance in "Contractor RFP Response"		
Z2 Process for Materials Receiving Instruction	column. Any clarifications to be made on Attachment 2 Modifications/Clarifications. Please confirm review/accentance in "Contractor REP Response"		
Z3 Form of Material Receiving Report	Please confirm review/acceptance in "Contractor RFP Response" column. Any clarifications to be made on Attachment 2		
AA Form of Attestation	Modifications/Clarifications.		<u></u>
	Please confirm review/acceptance in "Contractor RFP Response"		
AA1 Form of Attestation	column. Any clarifications to be made on Attachment 2 Modifications/Clarifications.	 <u></u>	
Additional Project Info- Not a part of the contract:			

	Please confirm review/acceptance in "Contractor RFP Response"			
Aerial (includes Topo)	column. Any clarifications to be made on Attachment 2			
	Modifications/Clarifications.			
	Please confirm review/acceptance in "Contractor RFP Response"			
H&H Study	column. Any clarifications to be made on Attachment 2			
	Modifications/Clarifications.			
	Please confirm review/acceptance in "Contractor RFP Response"			
Basemap	column. Any clarifications to be made on Attachment 2			
	Modifications/Clarifications.			
	Please confirm review/acceptance in "Contractor RFP Response"			
Tax Docs	column. Any clarifications to be made on Attachment 2			
	Modifications/Clarifications.			
	<u> </u>	·	 <u> </u>	·
Contractor Deliverables				
Contractor Deliverables				

Please provide standard plan of action to stay within constraints

Out of Bounds

Kachlah Document Number Andread Radio EDJPR, Approver Nates Commont Number Andread Andread <th>=</th> <th> For any ocietors we will be underlining the specific verbiage in the specific document. For all insertions we will be underlining the specific verbiage in the specific document. </th> <th>come terromage an une absentie accomment</th> <th></th> <th></th> <th></th>	=	 For any ocietors we will be underlining the specific verbiage in the specific document. For all insertions we will be underlining the specific verbiage in the specific document. 	come terromage an une absentie accomment			
		t Document Number		Document Section & Page Number		Notes
	1 1					
	1					
	1					
	ıl					
	1					
	1	+				
	1					
	1					
	1					
	1					
	1					
	1					
	1					
	- 1		1			
	- 1					
	1					
	1					
	ı					
	1					
	ıl					
	ı					
	1					
	- 1					

|--|

EDP Renewables Solar and/or Storage

		Exhibit A RFP BOQ and Price Sheet Category Summary	et		TOTAL	\$/Wp		
	Subtotak	Or Collection System Or Collection System Or Collection System General Construction Engineering Engineer			0.0000000000000000000000000000000000000		1	
WBS Code		Description Quantity	ty Unit of Mea	asure Unit Price	S Total Cost	s s/wp	Notes/Clarifications	Definition
CBCCO3A CSBCCO3A CSBCCO3A CSBCCO3A CSBCCO3A CSBCCO3B CSBC	Chil	Half Control Annual Control Co	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2		0.00.00.00.00.00.00	<i></i>	266600000000	Maint backs and tempers sammones, undersons activate consistence and tempers of the consisten
WBS Code (Internal) CSBEL01A CSBEL01B CSBEC01G CSBEL02A	DC Collection	Description Descri	ty Unit of Mea	sture.	Total Cost	S S S S	Note (Cartados	Defined to SHAY, A values shary, for conditions shary, for conditions supply, and the conditions supply for conditions shary, and the state of the supply of conditions supply for conditions supply for conditions supply and the supply
BS Code (Internal)		Lescriber Cuantity	ty Unit of me	asure	TOTAL COST	dwk	Notes/Clarifications	Accounting to suppoy Accountings suppoy
CSBESO1C CSBESO4L CSBESO3A CSBESO3A CSBESO3A CSBESO3A	MV Collection	Caling MacCaling & Commissioning MacCaling & Commissioning MacCaling MacCali	ล ล ล ล ล ล ล ล ล ล ล ล ล ล ล ล ล ล ล				A A A A A A A A A A A A A A A A A A A	ACOMONIO NSIMPLY, AC GOLD MODES SUPPLY CONTROL WE ARREST TO THE STATION AND SENCENCE, SCIEN ARE SOUR AND TESTING, SCIENCE SCIENCES SCIENCE
WBS Code (Internal) FII02A		Surety Bonds (Performance Bond, etc.) 1	ty United may	asure	Total cost	dw/s	Notes/Claritications B	Definition Definition CONTRACT PRICE PERFORMANCE BOND
CFIDSA CSFIDGA CSFIDGA CSCOAAA CSCOAAAZ CSCOOQAA CSCOOQAA CSCOOQAA CSCOOQBA	General Construction		2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2		90 90 90 90 90 90 90 90			WHEARTH, AS FRE THE COME OF CONTRACT IS FRET HE FORM OF CONTRACT, BY WISSIANCE REQUERABILITYS THE CONTRACT HAS THE ASSET OF CONTRACT, BY WISSIANCE REQUERABILITYS THE CONTRACT HAS THE ASSET OF CONTRACT, BY WISSIANCE STILL BEACH OF CONTRACT HAS AN EXPENSE AS THE PROPERTY HAS AND
EEE17A		Site Ovil Solar Design 1	SI			\$	NOTES/ CALIFICATIONS	GEOTECH, PULL TEST, CIVIL ENGINEERING
DEEE13A DEEE18A DEEE12A WBS Code (Internal)	Engineering	Ace Flank Studies 1 DC/AC Collection is System Design 1 SCADA Communication for beign 1 SCADA Communication To be sign 1 Description Quantity	LS LS LS	ans.	S	w w	A A	ELCTRACK Sociales ELCTRACK EDWIRENCE MALCONED INSTITUTE delign. & protection scheme design Definition
CSBMM03A		tem Supply	L			s	8	PACKING SUPPLY, PACKING SHIPPING, PACKING SUPPLIER ENGINEE RING, PACKING PROTESS ON AL SERVICES
CSBMM03B CSBMM03I CSBMM03J	Racking System	Pile Supply Contractor Management/Install - Radding System 1 Testing & Commissioning	2 22		 s ss	v v v		MONOMERS HEL NOT LIVOUR. HELDOSTER, HELDOSTE
WBS Code (Internal)		Description Quantity	ty Unit of Mea	asure	Total Cost	\$/Wp	Notes/Clarifications	Definition
CSBECOIA CSBECOIB	Inverters	Ontracezi warugeneni,rinsaii "irvertes 1 Inverter 1 Foundation 1	3 2 2		\$ \$, , , v v		ALICIA PO DESTITUCION NA SEULON PO DESTITUCION NA SEULON POR PROPERTICION
WBS Code (Internal) CSBMM06A CSMPP04A	Solar Panels	Description Quantity Panel Install 1 Testing & Commissioning 1	ty Unit of Mea	asure	Total Cost	s sywp	Notes/Cartications	POTATION NOTICE CONTINUE MODULE, LOCATICS MODULES MODILE SELF-CONTINUENCY VY TESTING MODILE CONVENIES
WBS Code (Internal)		Description Quantity	y Unit of Mea	sure	Total Cost	\$/Wp	Notes/Clarifications	Definition
CSBMM03H CSBMM03H CSBMM03H CSBMM03H CSBMM03H	Misc/Other	1 West/Other 1 We	2 2 2 2 2					
		TOTAL				\$		

i. Any quantities and descriptions listed herein are explicitly limited to Winef's use for scope lealathon and evaluation purposes and will have no bearing on final confract. Final design quantities are the sole responsibility of the Contractor and the scope is the Work including its Requirements as described within the Contract.

Notes					
Charge to Exhibit/Document					
Status					
Bidde r Response					
EDPR Response					
EDPR Reviewer Name					
Bidde r Question					
Document name, Section Reference & Page Number					
Category of Chriftication/Assumption					
Clarification Round					
FROM:					
SEND TO:	dders dders Name	 		 	



Request No. 23:

Explain whether a historical survey of the project has been conducted. If yes, provide a copy. If

no, explain when that will occur.

Response No. 23:

Please see the archaeological records review completed for the Project in 2021, filed separately

and stamped as Resp. to 1 RFI 23, pages 1-41.

Case No. 2024-00253

Request No. 24:

Refer to SAR, Attachment G, Landscape Plan. In narrative form identify the seven historic

structures in the landscape plan.

Response No. 24:

Please note that the Project's Landscape Plan, SAR Attachment G, did not identify historic

structures. However, the information related to historical structures contained in paragraph 40 of

the SAR narrative is incorrect and is remnant language from a prior report. The Project's Visual

Resources Assessment (VRA), submitted as SAR Attachment E, and the Archaeological Records

Review prepared by Cultural Resource Analysis, Inc. and provided in Response to Request No.

23, do not show any National Register of Historic Plance (NRHP) records within or near the

Project boundary.

Case No. 2024-00253

Request No. 25:

Provide any communication that has occurred with any schools within a two mile radius of the

project. Provide any communication and any concerns that were raised.

Response No. 25:

Project representatives met with the Breckinridge County High School Future Farmers of America

(FFA) class to provide information about the project and educate about the solar industry. Project

representatives answered student questions during the meeting. A copy of email communications

setting up meeting times with the FFA class instructor is attached.

Please reply during your own working hours and consider the environment before printing.

From: JESSE EICK < JESSE.EICK@EDP.COM>

Sent: Wednesday, November 13, 2024 11:28 AM

To

"h@breck.kyschools.us>; CHASE GLOTFELTY < CHASE.GLOTFELTY@EDP.COM>

Cc: JULIA MCPHERSON < JULIA.MCPHERSON@EDP.COM>

Subject: Re: Breckinridge County FFA

Good morning, Derek -

Thank you for reaching out, we are happy to help!

Couple of questions for you:

- Would it be possible to meet prior to the Fiscal Court meeting? We can be at the school or anywhere in Hardinsburg by 8am. If not, no problem, we'll plan to meet after the Fiscal Court adjourns.

- How many students do you expect will be there? We have some information packets that we can bring and leave with you.

In addition, Breckinridge County is contemplating a Moratorium on new solar projects to be presented to the County. This will not affect our project but wanted to note for you here in case you were unaware. The concern of the Fiscal Court stems from the number of projects being contemplated in the area. We're happy to dive into this a bit during our discussion.

This sounds like a great contest, and we are happy to help in any way that we can.

Thank you!



Jesse Eick

EDPR

Pd - Southeast, Il Solar & M&A

1501 McKinney Street, Suite 1300, Houston, TX 77010, United States T +1(832)819-9040







Please reply during your own working hours and consider the environment before printing.

From:

th@breck.kyschools.us>

Sent: Tuesday, November 12, 2024 8:06 PM

To: JESSE EICK <JESSE.EICK@EDP.COM>; CHASE GLOTFELTY <CHASE.GLOTFELTY@EDP.COM>

Subject: Breckinridge County FFA

Hey guys I'm an Ag Teacher in Breckinridge County Kentucky and we are putting together an Ag Issues team this year to compete at our state convention in June. For this contest we have to provide both sides to an issue currently facing Agriculture. This year we are going to do solar farms. We would like to sit down and meet with someone from the Solar Industry to give us some insight on how we need to write our presentation. The team cannot have a bias or push the judges one way or another, they just have to provide both sides of the issue.

We are going to take the kids to the Fiscal Court meeting on Monday November 18th and if anyone would be free to talk with them after that meeting I would appreciate it! If that date or time doesn't work we would be open to meeting someone whenever we can!

Thanks,

Case No. 2024-00253

Request No. 26:

The proposed Project site sits in a karst prone region with high groundwater sensitivity levels.

Provide any mitigation measures Clover Creek Solar will implement during construction and

operations in response.

Response No. 26:

Clover Creek Solar has taken steps to ensure that karst features are avoided and any potential

impacts are mitigated throughout the Project area. Consultant THG prepared an initial Phase 3

Karst Assessment in March of 2023, and is currently performing an additional assessment of the

Project area to determine if any amendment is necessary. Applicant anticipates completion of the

updated Phase 3 Karst assessment by February 2025. The preliminary site layout requires a strict

50 foot setback from all karst and potential karst features identified on site, which the Project has

communicated with the EPC.

Request No. 27:

Provide the security measures for the O&M areas and substation within the project's boundaries.

Response No. 27:

The Project's O&M and substation areas will be fenced, gated, and locked. Security fencing is

comprised of a 7-foot tall chain-link fence with 12-inch barbed wire. The Project will install gated

entrances locked with a combination padlock or keyed padlock.

Case No. 2024-00253

Request No. 28:

Explain how Clover Creek Solar will coordinate with local law enforcement and fire services

regarding security and emergency protocols during construction and operations.

Response No. 28:

The Applicant will work closely with EPC contractors and local first responders to develop and

maintain comprehensive emergency response plans. Before the Project begins commercial

operations, Clover Creek Solar will collaborate with local fire departments and first responders to

establish safe and effective fire containment and extinguishing procedures. Project representatives

will meet with Breckinridge County Fire and EMS, City Police and the Breckinridge County

Sheriff to discuss actions and coordination required for local emergency services for the project

site. A direct line of communication, 911 address, and emergency contact line will be established

at the project substation and construction office prior to the EPC mobilization.

Req	uest	No.	29:

Explain whether any existing structures on the project site will be demolished during construction.

Response No. 29:

The Project does not anticipate demolishing any existing structures located on site.

Request No. 30:

Describe any utilities that will be required during construction or operations and what utility will

provide the service.

Response No. 30:

The Project anticipates electrical services to be provided by Meade County RECC, and water

service to be provided by the City of Hardinsburg Water.

Request No. 31:

Refer to SAR, Attachment A. Explain whether there will be vegetation clearing for construction.

Provide in the response the number of acres that will be cleared and any permits that will be

required.

Response No. 31:

At this time, the Project anticipates clearing approximately 10.5 acres of forested area. The Project

has engaged the U.S. Fish & Wildlife Service and the Kentucky Department of Fish and Wildlife

Resources to determine whether a permit is required for planned clearing activities.

Request No. 32:

Refer to SAR, Attachment A, Preliminary Site Layout. It appears not all proposed solar arrays have

populated on the site plan. Provide an updated site plan showing all proposed solar arrays and any

other updates.

Response No. 32:

See site layout provided in Response to Request No. 15.

Case No. 2024-00253

Request No. 33:

Refer to SAR, Exhibit A, Preliminary Site Layout Plan. Explain if the medium voltage collection

system will be underground, aboveground, or both. If the MV collection system will be

underground and above ground, provide a map that shows which segments are underground and

which segments are above ground.

Response No. 33:

Clover Creek Solar Project plans to use a combination of underground and overhead collection

throughout the Project area. The medium voltage collection line routes will abide by specific

requirements outlined in respective leases and collection easement agreements with participating

Project landowners.

Request No. 34:

Provide copies of any documents submitted to other agencies, other than what in the application.

Response No. 34:

No additional documents have been submitted to agencies at this time other than those in the application.

Request No. 35:

Explain how the project has been designed to minimize the amount of tree clearing required.

Response No. 35:

The Project is situated on parcels primarily consisting of agriculture and other non-forested

landcover. The Project team is working to minimize tree clearing. Priority is given to avoiding the

placement of contiguous infrastructure, such as panel blocks, in woodlots, intact wooded areas,

and riparian zones, except where necessary.

Case No. 2024-00253

Request No. 36:

Describe and provide information regarding what federal and state agencies that Clover Creek

Solar is coordinating with in regard to the tree clearing strategy for protected bats.

Response No. 36:

Clover Creek is working with the U.S. Fish & Wildlife Service (USFWS) and the Kentucky

Department of Fish and Wildlife Resources (KDFWR) regarding the tree clearing strategy for

protected bats, with the most recent meeting between the Project and both agencies occurring on

November 7, 2024. Mitigation strategies for tree clearing considerations related to protected bats,

including support of the Imperiled Bat Conservation Fund (IBCF), have been discussed with

USFWS.

Request No. 37:

Provide a wetland delineation report for the project. If one does not exist, provide when one will be produced.

Response No. 37:

Please see the Wetland Delineation Report, filed separately and stamped Resp. to 1 RFI 37, pages 1-34 and appendices.

Responding Witness: Chad Martin

Request No. 38:

Explain whether the Site Layout Plan will be modified after the Wetland Delineations are

completed.

Response No. 38:

The preliminary Site Layout Plan (as submitted to the Siting Board) was created after completion

of the Wetland Delineation Report. Although the Project does not anticipate significant changes to

the plan, minor changes may occur but should not have any negative impact to wetlands onsite.

Request No. 39:

Explain whether Light Detection and Ranging (LiDAR) been utilized during research and evaluation of the project.

Response No. 39:

LiDAR was utilized to evaluate the existing ground elevations for the Project.

Explain in detail all cemetery facilities that may be affected by the project.

Response No. 40:

No impacts to cemetery facilities are anticipated.

Request No. 41:

Provide a one-page directional map showing highlighted anticipated delivery routes for the project.

Include on the map: access roads, access points, existing roads, bridges, electric generation


components, and all structures within two miles of the project. Differentiate between roads and

bridges that will and will not be used for deliveries.

Response No. 41:

Please see attached. Please also see the Table attached to Response No. 12.

New Frontiers Solar - Preliminary Delivery Map




Request No. 42:

Provide a map highlighting all construction entrances to the Project site and all roads proposed to be used.


Response No. 42:

Please see the attached map showing proposed construction entrances and roads.



Disclaimer. This document has been prepared based on information provided by others as cited in the Notes section. Stantec has not verified the accuracy and/or completeness of this information and shall not be responsible for any errors or omissions which may be incorporated herein as a result. Stantec assumes no responsibility for data supplied in electronic format, and the recipient accepts full responsibility for verifying the accuracy and completeness of the data.


Title Construction Road Entrances














Legend

- Fenceline
- Laydown Areas
 - Access Roads
- Public Roads

Stantec


(At original document size of 8.5x11) 1:12,000

Prepared by CRH on 2024-10-23

Client: EDP Renewables Project: New Frontiers Solar Park

Title Construction Road Entrances






Legend

- Fenceline
- Access Roads

Notes
1. Coordinate System: NAD 1983 StatePlane
Kentucky FIPS 1600 Feet
2. Data Sources: New Frontiers/Clover Creek Layout
Rev 2
3. Background: KyFromAbove Orthoimagery (2021)



Public Roads




1,000 (At original document size of 8.5x11) 1:12,000




Prepared by CRH on 2024-10-23 Client: EDP Renewables Project: New Frontiers Solar Park Report: SAR

Construction Road Entrances

Page 6 of 8





Case No. 2024-00253

Request No. 43:

Identify all bridges along all roads proposed to be used during the delivery/construction phase of

the project. Identify the width and weight capacity of each bridge and any upgrades or repairs that

will need to be made prior to the commencement of construction.

Response No. 43:


Please see attached map identifying the bridges along proposed delivery/construction routes. The


identified bridges have been rated for full access and thus there are no width or weight limits were

identified for these bridges per the Kentucky Department of Transportation. Although

improvements to accommodate heavy loads on existing state roads are not anticipated,

improvements may be required for county roads used for deliveries during Project construction.





Notes
1. Coordinate System: NAD 1983 StatePlane
Kentucky FIPS 1800 Feet
2. Data Sources: New Frontiers/Clover Creek Layout
Rev 2.
3. Background: KyFromAbove Orthoimagery (2021)

Legend

Bridge

Box Culvert

Project Area

Project Fenceline

Access Roads

Arrays







Project Location Hardinsburg Breckenridge County, Kentucky	Present to IC IP 2004 O 24
Client/Project	235300918
Client: EDP Renewables Project: New Frontiers Solar Park Report: SAR	
Exhibit 1	
Title Bridge Map	

Case No. 2024-00253

Request No. 44:

Explain the plan for repairing Project-related damage to any roadways or bridges.

Response No. 44:

A survey will be performed prior to construction to identify the current conditions of roadways

and bridges. The EPC contractor will then create a plan to address damage sustained during the

construction phase of the Project and to restore any roads or bridges their pre-construction

condition. The Project will work with local and state authorities as necessary to facilitate these

repairs.

Request No. 45:

Provide if Industrial Park Lane will be utilized during the delivery of the project substation.

Response No. 45:


At this time, the Project does not plan to utilize Industrial Park Lane for delivery of the Project substation.

Req	uest	No.	46:

Provide any sketches of the proposed transmission line support structure.

Response No. 46:

Please see the attached sketch showing the proposed support structure.



Request No. 47:

Explain how the proposed transmission route was determined.

Response No. 47:

Clover Creek determined the shortest and least impactful transmission route to interconnect the Project is the BREC Hardinsburg substation.

Case No. 2024-00253

Request No. 48:

Multiple transmission lines, owned by Big Rivers Electric Corporation (BREC) and Kentucky

Utilities Company (KU), transect the project. Provide any communication with the two utilities

regarding the project and any concerns that were raised.

Response No. 48:

Project representatives have communicated with representatives from both BREC and KU

regarding the Project, and these communications have included discussions about potential

encroachment agreements. Both BREC and KU have provided design parameters related to the

areas where transmission lines transect the Project, and the Project will be designed accordingly.

Specific communications with utilities have been preliminary, with conversations focusing on


location of potential crossings, crossing requirements, and potential encroachment agreements.


Req	uest	No.	49:

Provide the rights-of-way for all transmission lines that transect any portion of the project site.

Response No. 49:

Please see the attached map showing rights-of-way for the Project site.





Case No. 2024-00253

Request No. 50:

Detail any communication with the residences closest to the proposed substation location.

Response No. 50:

Project representatives contacted the landowners near the Project substation, mainly by telephone,

to discuss the construction process and initiate communications to address any questions or

concerns. In addition, a packet outlining the Project information and an invitation to confer with

Project representatives was dropped off in mailboxes belonging to these landowners. Project

representatives did not receive any responses to these communication efforts.

Request No. 51:

Explain whether vegetative clearing be required to accommodate the proposed 460 ft long

transmission line. If yes, provide the anticipated acreage of vegetative clearing and any permits

that will be required.

Response No. 51:

It is not anticipated that any vegetative clearing will be necessary to accommodate the proposed

transmission line.

Case No. 2024-00253

Request No. 52:

Refer to the Kentucky Geological Survey Oil and Gas Wells Search (KY Geode: KGS Oil and Gas

Wells Search (uky.edu)).

a. Provide a map with all active and inactive oil or gas wells on the proposed site.

Also include any gas- gathering pipelines associated with the wells.

Determine and confirm whether any of these wells are currently permitted and b.

active.

c. Confirm whether the existence of oil and gas wells and pipelines will require

adjustments to the proposed location of solar panels.


Response No. 52:


a. Please see attached maps showing the wells and pipelines on the proposed site.

No wells on the proposed site are active. b.


All wells and pipelines were considered when designing the Project, thus no c.

adjustments to the proposed location of solar panels are needed.












Area Shown



0 0.25 0.5 Miles

Request No. 53:


The proposed project site is transected by multiple pipelines, including: A Texas Gas 26" natural gas main pipeline, a Texas Gas 16" natural gas pipeline, and an Owensboro, Catlettsburg Crude 24" crude oil pipeline. Provide:

- a. Any communication with the owners of these pipelines and any concerns that were raised.
- b. The appropriate setbacks from each pipeline.
- c. A map showing the location of all pipelines and their corresponding setbacks from all project components. Include on the map all electric generation components.
- d. Provide how Clover Creek Solar manages to avoid all pipelines, especially with components such as the AC Collection system.

Response No. 53:

- a. Project representatives communicated with pipeline owners regarding proposed encroachment agreements and setbacks for the Project, including representatives of Marathon Pipe Line LLC and Boardwalk (Texas Gas) Pipelines. Communications included details regarding pipeline locations and possible terms for encroachment agreements. Communications with the pipelines are currently being reviewed for confidentiality under federal and state laws and will be produced at a later date.
- b. Each pipeline in the Project area has been set back 100 feet on either side of the pipeline's center line.
- c. Please see the attached map showing pipeline locations and related setbacks.

d. Although complete avoidance of pre-existing pipelines is not possible, the Project is designed to minimize impacts to pipelines by avoiding placement of infrastructure in ROWs except where boring techniques will be utilized to cross underneath the pipelines.



Request No. 54	Rec	uest	No.	54:
----------------	-----	------	-----	-----

Provide a narrative description of where the solar meteorological stations will be located.

Response No. 54:

The Project has not finalized locations for its meteorological stations at this time.

Case No. 2024-00253

Request No. 55:

Explain whether Clover Creek Solar will pursue an Industrial Revenue Bond and Payment In Lieu

of Taxes agreement with Breckinridge County. If yes, explain how that might change the

cumulative tax revenues of the Project.

Response No. 55:

Although the Project has communicated with the Breckinridge County Fiscal Court and County

Judge/Executive regarding a potential Industrial Revenue Bond and Payment In Lieu of Taxes

agreement, no decision to pursue such an agreement has been reached at this time.

Case No. 2024-00253

Request No. 56:

Explain whether Clover Creek Solar intends to hire as many local workers for the construction and

operations phases of the project as possible, all other qualifications for the positions being equal.

If confirmed, explain how Clover Creek Solar will ensure this occurs.

Response No. 56:

The Project and its EPC contractor hope to hire as many local workers as possible, as long as these

individuals are qualified for the open positions to be filled. To help facilitate this goal, the Project

plans to partner with a third party labor agency to hold job fairs and otherwise market the Project

to local communities.

Request No. 57:

Refer to the Application, SAR, Attachment D, Noise Study. Provide a map that displays and labels each noise receptor listed in the report.

Response No. 57:

A map displaying and labeling each noise receptor is included in SAR Attachment D (Sound Study), Figure 3.

Responding Witness: Chad Martin

Case No. 2024-00253

Request No. 58:

Refer to SAR, Attachment D, Appendix A. Provide a table in the format of Table A.1. for the

Construction Sound Model results. Include the results for pile driving in the table.

Response No. 58:

Noise from pile driving would vary depending on multiple factors including the location of pile

driving activity within the Project site, the number of pile drivers being used within a given area,

humidity, wind, and other variables. Because noise levels from pile driving would vary based on

these factors, the Project's Sound Study modeled noise results from up to three pile drivers working

simultaneously within the same solar panel block. Results of this study were compiled in the noise

contour map provided with SAR Attachment D, which showed a 55 dBa contour approximately

1,000 feet from collective noise-producing sources, or in this case, the edge of the Project's racking

systems.

Case No. 2024-00253

Request No. 59:

Regarding construction noise, provide all mitigation measures considered for noise dampening

during the construction phase.

Response No. 59:

Mitigation measures considered for noise during the construction phase are as follows. Noise from

pile driving will be mitigated by Project setbacks from residential and other noise sensitive

receptors, limitation of construction hours, use of existing topography, and sequencing of pile

driver use to avoid creating sustained noise in any one area.

Case No. 2024-00253

Request No. 60:

Explain whether construction activities will occur sequentially, or concurrently across the Project

site.

Response No. 60:

Construction activities may occur both sequentially and concurrently, depending on the activity

and phase of construction. Construction activities will include activities such as pile driving,

grading and site preparation, and installation of generation infrastructure. Certain activities will

move sequentially across the site as needed, but multiple activities may occur simultaneously

within a single location for a short time.

Case No. 2024-00253

Request No. 61:

Detail any communications with members of the public, including neighboring landowners,

regarding construction noise.

Response No. 61:

Project representatives have communicated extensively with members of the public regarding

information such as construction noise. Specifically, Project representatives have presented Project

information at local fiscal court meetings, meetings with nonparticipating landowners in the county

and otherwise adjacent to the Project, and also by meeting with participating landowners. Specific

information regarding construction noise and the construction process and timeframe were

discussed in these meetings. Project representatives have made themselves available to the public

at fiscal court meetings in an effort to hear the concerns and proposed solutions of the constituents

in the county.

Request No. 62:

Provide a copy of the stormwater management plan for the project.

Response No. 62:

A copy of the Project's stormwater management plan is not currently available. The Project anticipates creating this plan by mid-March 2025.

Request No. 63:

Confirm whether the site will be irrigated to promote vegetation.

Response No. 63:

A decision whether to implement irrigation to promote vegetation has not been finalized at this

time. Implementation of irrigation is dependent on multiple factors, including time of year for

planting.

Request No. 64:

Provide any geotechnical reports for the project.

Response No. 64:

A final geotechnical report is anticipated to be completed by February 2025 and will be submitted to the Siting Board upon completion.

Request No. 65:

Provide any historic or archeologic studies that have been planned or completed for the project site.

Response No. 65:

Please see the archaeological records review provided in Response to Request No. 23.

Provide the Construction Dust Control Plan for the project.

Response No. 66:

Please see the attached Dust Control Plan.



Dust Control Plan

New Frontiers Solar

November 2024

Rev. 0

SOLAR



Table of Contents

1. 2. 3. 4.	Purpose and Scope	. 3
4.1	General Dust Control Strategies	3
4.2	Specific Dust Control during Construction Activities	∠
4.3	Excavation & Trenching	4
4.4	Ongoing Monitoring and Adjustment	4
5.	Employee and Public Safety Measures	. 5
6.	Emergency Response Plan	. 5
7.	Conclusion	. 5

Rev. 00 - Nov 2024 2 0F 6



1. Purpose and Scope

This Dust Control Plan (DCP) is designed to outline the measures to be implemented during the construction of the New Frontiers Solar Farm to minimize and control airborne dust emissions. The goal is to ensure compliance with environmental regulations, safeguard the health and safety of construction workers, and reduce any negative impact on neighboring communities, agricultural lands, and sensitive ecosystems.

2. Regulatory Requirements

<u>Local Regulations</u>: Ensure compliance with local air quality standards and construction dust regulations.

<u>Federal Regulations:</u> Adherence to the Clean Air Act (CAA), EPA National Ambient Air Quality Standards (NAAQS), and state-level air quality standards.

<u>Permits</u>: If required, obtain necessary air quality permits and provide documentation for dust suppression measures to local authorities.

3. Site Assessment and Identification of Dust Sources

Dust can be generated from various sources during the construction process, including:

- a. Site Preparation: Land clearing, grading, and excavation.
- b. Vehicle Traffic: Dust from heavy trucks and construction vehicles moving across dirt or gravel roads
- c. Material Handling: Dust generated from stockpiling, transferring, and moving materials such as sand, gravel, or soil.
- d. Demolition: Dust from removal of any existing structures or debris on-site.
- e. Operation of Heavy Equipment: Dust from bulldozers, excavators, and other construction machinery.

4. Dust Control Measures

4.1 General Dust Control Strategies

a. Watering: Apply water to exposed surfaces, roads, and stockpiles to minimize dust by use of water truck. Frequency of watering will depend on weather conditions and construction activities.

Rev. 00 - Nov 2024 3 OF 6



- b. Dust Suppressant Chemicals: When water alone is insufficient, non-toxic dust suppressant chemicals (such as lignosulfonates or synthetic polymers) may be applied to stabilize soil surfaces.
- c. Speed Limits: Establish and enforce speed limits (e.g., 15 mph or lower) for all construction vehicles within the project site to reduce dust generation.
- d. Gravel or Paved Roads: If feasible, provide gravel or temporary paving on frequently used roads to minimize dust.
- e. Enclosed Material Handling: Use covered trucks or tarps when transporting materials that are prone to creating dust.
- f. Dust Barriers: Erect temporary dust barriers (e.g., silt fences or windbreaks) around construction areas or material storage yards.

4.2 Specific Dust Control during Construction Activities

Site Preparation & Grading:

- a. Limit the amount of disturbed land at any one time to reduce overall dust exposure.
- b. Apply dust control measures (water or suppressant) as soon as practicable after grading activities.

4.3 Excavation & Trenching

- a. Wetting down soil before excavation and placing a cover or tarp over exposed excavated areas to reduce wind-blown dust.
- b. Use water sprays on trenching equipment if needed to minimize airborne dust.
- c. Store material piles in low-traffic areas with sufficient watering or dust control treatments.
- d. Use tarps or covers on stockpiles during high-wind conditions.
- e. Use wet demolition methods to minimize dust generation (if applicable)
- f. Use vacuum systems or dust capture devices for cutting and grinding (if applicable)

4.4 Ongoing Monitoring and Adjustment

Visual Inspection: Daily site inspections by the site manager or environmental officer to assess the effectiveness of dust control measures.

Corrective Actions: If dust levels exceed acceptable limits or if visible dust is noted, additional control measures (e.g., increased watering, use of dust suppressant, temporary covering of stockpiles) will be implemented.

Rev. 00 - Nov 2024 4 0F 6



5. Employee and Public Safety Measures

Personal Protective Equipment (PPE): Ensure all workers have access to appropriate PPE, including dust masks (N95 or higher) when working in high-dust areas.

Health and Safety Training: Provide dust exposure awareness training for all workers and enforce use of PPE when required.

Public Notifications: In areas where the project is near residential or agricultural zones, notify local communities of the construction schedule and potential dust impacts. Provide contact information for dust-related complaints.

6. Emergency Response Plan

In case of a dust-related emergency (e.g., dust storm or high levels of dust impacting local air quality), the following measures will be enacted:

- a. Cease Operations: Temporarily halt activities that are contributing to the dust (e.g., grading, excavation, etc.).
- b. Increased Dust Suppression: Increase watering or apply additional dust suppressants immediately.
- c. Evacuate High-Risk Areas: For particularly sensitive individuals, such as workers with respiratory conditions, evacuate from areas with high dust exposure.
- d. Notify Authorities: Report the dust event to local environmental agencies if air quality thresholds are exceeded.

7. Conclusion

The goal of this Dust Control Plan is to ensure that dust emissions during the construction of the New Frontiers Solar Farm are minimized, and the health and safety of workers and the surrounding community are protected. Continuous monitoring, quick action in response to dust issues, and compliance with regulatory requirements will ensure a smooth construction process and adherence to environmental standards.

Rev. 00 - Nov 2024 5 OF 6



Revision History

Rev. #	Description of Changes	Revised By	Reviewed By	Approved By	Date
0	NEW FRONTIERS SOLAR DUST CONTROL PLAN	K. Gomez Diaz		K. Gomez Diaz	12/16/24

Rev. 00 - Nov 2024

Request No. 67:	Rec	uest	No.	67:
-----------------	-----	------	-----	-----

Provide a copy of the Groundwater Protection Plan.

Response No. 67:

A Groundwater Protection Plan for the Project has not been prepared at this time.

Case No. 2024-00253

Request No. 68:

Provide any communication with local emergency services on security and emergency protocols

during construction and operations. If contact has not been made, explain when that contact will

occur.

Response No. 68:

No communications with local emergency services have been initiated at this time. Project

representatives will connect with local fire and other necessary emergency officials in early 2025

to discuss the Project, and EPC contractor PCL will begin working with local emergency services

regarding security and emergency protocols for the Project prior to commencing construction.

Please also see Response to Request No. 28.

Request No. 69:

Provide who will control access to the site during construction and operations.

Response No. 69:

During construction, the EPC team will control access to the site. During operation, the Project's site operations manager will manage site access.

Request No. 70:

Refer to the SAR, Attachment D and H, Noise and Traffic Study.

- a. Provide the weight limits of each local roadway to be used for construction traffic.
- b. Provide the number of worker vehicles traveling to the site each day during construction.
- c. Provide the number and approximate weight classes of the heavy and light duty trucks anticipated on site per day during the construction phase.
- d. Provide the estimated weight of the project's required substation transformer and the truck class necessary for its delivery.

Response No. 70:

- a. Weight limits for anticipated roadways are as follows:
 - i. Highway 60: Class AAA, 80,000 pounds;
 - ii. Skillman Monarch Lane: Class A, 44,000 pounds;
 - iii. KY 259: Class AA, 62,000 pounds;
 - iv. KY 992: Class AA, 62,000 pounds;
 - v. KY 261: Class AA, 62,000 pounds; and
 - vi. Bens Hole Branch Road: Class A, 44,000 pounds.
- b. The Project anticipates up to 240 worker vehicles traveling daily during construction.
- c. The number and approximate weight classes of heavy and light duty trucks onsite per day during Project construction are as follows:
 - i. Approximately 200 passenger cars or pickup trucks, ranging between 2,500 and 6,000 pounds in weight;

- ii. Approximately 20 delivery trucks and associated trailers, ranging between6,000 and 10,000 pounds in weight; and
- iii. Approximately five semi-trucks and associated trailers, ranging between24,000 and 80,000 pounds in weight.
- d. The substation transformer is anticipated to weigh between 40,000 and 60,000 pounds. The class of truck anticipated for delivery of the substation will be a semi-truck with drop axles and a flatbed trailer capable of hauling up to 105,000 pounds.

Case No. 2024-00253

Request No. 71:

Identify specific roadways used by heavy trucks, including for delivery of the transformer.

Response No. 71:

Although the specific route for oversized loads will be finalized in coordination with state and

local officials prior to commencing construction, the Project anticipates heavy trucks will likely

use Highway 60, KY 261, and KY 992 and as main haul routes. Use of local roads are anticipated

but finalized routes will depend on the terminal delivery point for the Project substation. At this

time, potential delivery routes on local roads may include Frank Farm Road, Bens Hole Branch

Road, and Skillman Monarch Lane.

Case No. 2024-00253

Request No. 72:

Explain whether any traffic stoppages will be necessary to accommodate large truck deliveries. If

yes, provide the expected locations, frequency, and length of those stoppages.

Response No. 72:

Clover Creek Solar Project anticipates potential traffic stoppages, mainly related to the delivery of

the Project substation. The Project substation will be installed on parcel 59-21, which adjoins the

existing utility substation owned and operated by BREC. The Project intends to utilize Highway

60 and KY 992 as its main delivery route. The location, frequency and length of stoppages will

depend on the route selected and the specific date and time of the delivery. Clover Creek anticipates

brief and infrequent and singular traffic stoppages for delivery of the transformer.

Case No. 2024-00253

Request No. 73:

Provide any communications with Breckinridge County Road Department regarding permits or

agreements necessary for the project. If no communication has been initiated, explain when that

contact will occur.

Response No. 73:

Project representatives have contacted the Breckinridge County Road Department to discuss

construction and operation of the Project. Discussions focused on county permitting requirements.

Road officials conveyed to Project representatives that county driveway permits will not be

required for the Project. The EPC team will meet with county road officials in the first quarter of

2025 for pre-construction preparation.



Provide the number of miles between the Clover Creek Solar project and the project in Case No. 2020-00387.

Response No. 74:

The projects are approximately 10 miles apart as measured from each site's closest point.

Responding Witness: Chad Martin

Request No. 75:

Provide any overlaps in the projected construction schedules of the projects in Breckinridge

County.

Response No. 75:

Green River Solar's projected construction schedule is unknown, and thus Project representatives

do not know whether the projected construction schedules overlap.

Case No. 2024-00253

Request No. 76:

Describe the cumulative effects on noise from the construction activities of the two projects, any

steps to minimize these effects.

Response No. 76:

Cumulative effects on noise from construction activities from the two projects have not been

reviewed. However, noise studies provided with the SAR indicate that construction noise would

dissipate to a point below ambient day and nighttime levels within 1,000 feet of the project area.

See SAR Attachment D. The Green River Solar project is over 10 miles away from Clover Creek

and therefore, there would be no cumulative effects related to noise associated with the Clover

Creek project in the event that construction schedules overlap.

Case No. 2024-00253

Request No. 77:

Describe the potential for cumulative effects on traffic and roadways from construction activities

of the two projects, and any steps planned to minimize these effects.

Response No. 77:

As discussed in the Response to Request No. 75, Green River Solar's construction schedule is

unknown. However, because of the distance between the projects along with each project's relative

location in Breckinridge County, it is unlikely that there would be any cumulative impact on traffic

or roadways. Green River Solar's project site straddles Breckinridge and Meade Counties, near the

city of Irvington; whereas Clover Creek Solar's site is located west of the city of Hardinsburg and

is approximately 10 miles away from the Green River Solar site. Clover Creek Solar's traffic study

analyzed US 60, KY 992, and KY 261 as road segments potentially to be utilized during

construction. The study concluded that the Project would not result in significant adverse traffic

impacts.

Case No. 2024-00253

Request No. 78:

Describe the potential cumulative effects on property values and land uses from the construction

and operation of the two projects.

Response No. 78:

Cumulative effects on property values and land uses were not specifically reviewed. However, as

discussed above, because of the distance between the two projects and each site's relative location

in Breckinridge County, it is highly unlikely that any one property would be impacted by both

projects.

Case No. 2024-00253

Request No. 79:

Provide any communication with the Kentucky Transportation Cabinet District Engineer regarding

permits or agreements necessary for the project. If no communication has been initiated, explain

when that contact will occur.

Response No. 79:

Project representatives have been in contact with traffic and permitting officials at the Kentucky

Transportation Cabinet and are coordinating with the same to obtain necessary encroachment

permits for appropriate Project access points.

Request No. 80:

Provide information on the specifications, model number, and cutsheets of the photovoltaic (PV) cell/solar panels to be used.

Response No. 80:

Please see the attached informational sheets from Canadian Solar and QCells.





TOPBiHiKu7

N-type Bifacial TOPCon Technology 690 W ~ 720 W CS7N-690|695|700|705|710|715|720TB-AG



MORE POWER



Module power up to 720 W Module efficiency up to 23.2 %



Up to 85% Power Bifaciality, more power from the back side



Excellent anti-LeTID & anti-PID performance. Low power degradation, high energy yield



Lower temperature coefficient (Pmax): -0.29%/°C, increases energy yield in hot climate



Lower LCOE & system cost

MORE RELIABLE



Minimizes micro-crack impacts



Heavy snow load up to 5400 Pa, wind load up to 2400 Pa*

* For detailed information, please refer to the Installation Manual.



Enhanced Product Warranty on Materials and Workmanship*



Linear Power Performance Warranty*

1st year power degradation no more than 1% Subsequent annual power degradation no more than 0.4%

*According to the applicable Canadian Solar Limited Warranty Statement.

MANAGEMENT SYSTEM CERTIFICATES*

ISO 9001: 2015 / Quality management system ISO 14001: 2015 / Standards for environmental management system

ISO 45001: 2018 / International standards for occupational health & safety IEC 62941: 2019 / Photovoltaic module manufacturing quality system

PRODUCT CERTIFICATES*

IEC 61215 / IEC 61730 / CE / INMETRO / MCS / UKCA / CGC CEC listed (US California) / FSEC (US Florida) UL 61730 / IEC 61701 / IEC 62716 / IEC 60068-2-68 UNI 9177 Reaction to Fire: Class 1 / Take-e-way






in which the products will be used.












CSI Solar Co., Ltd. is committed to providing high quality solar photovoltaic modules, solar energy and battery storage solutions to customers. The company was recognized as the No. 1 module supplier for quality and performance/price ratio in the IHS Module Customer Insight Survey. Over the past 22 years, it has successfully delivered over 110 GW of premium-quality solar modules across the world.

ENGINEERING DRAWING (mm)

Rear View

Frame Cross Section A-A



ELECTRICAL DATA | STC*

		Nominal Max. Power (Pmax)	Opt. Operating Voltage (Vmp)	Opt. Ope- rating Current (Imp)	Circuit	Short Circuit Current (Isc)	Module Efficiency
CS7N-690	ΓB-AG	690 W	39.6 V	17.43 A	47.5 V	18.39 A	22.2%
D:6 : 1	5%	725 W	39.6 V	18.30 A	47.5 V	19.31 A	23.3%
Bifacial Gain**	10%	759 W	39.6 V	19.17 A	47.5 V	20.23 A	24.4%
	20%	828 W	39.6 V	20.92 A	47.5 V	22.07 A	26.7%
CS7N-695	ΓB-AG	695 W	39.8 V	17.47 A	47.7 V	18.44 A	22.4%
D:6:-I	5%	730 W	39.8 V	18.34 A	47.7 V	19.36 A	23.5%
Bifacial Gain**	10%	765 W	39.8 V	19.22 A	47.7 V	20.28 A	24.6%
	20%	834 W	39.8 V	20.96 A	47.7 V	22.13 A	26.8%
CS7N-700	ΓB-AG	700 W	40.0 V	17.51 A	47.9 V	18.49 A	22.5%
D:6 : 1	5%	735 W	40.0 V	18.39 A	47.9 V	19.41 A	23.7%
Bifacial Gain**	10%	770 W	40.0 V	19.26 A	47.9 V	20.34 A	24.8%
	20%	840 W	40.0 V	21.01 A	47.9 V	22.19 A	27.0%
CS7N-705	ΓB-AG	705 W	40.2 V	17.55 A	48.1 V	18.54 A	22.7%
Bifacial Gain**	5%	740 W	40.2 V	18.43 A	48.1 V	19.47 A	23.8%
	10%	776 W	40.2 V	19.31 A	48.1 V	20.39 A	25.0%
	20%	846 W	40.2 V	21.06 A	48.1 V	22.25 A	27.2%
CS7N-710	ΓB-AG	710 W	40.4 V	17.59 A	48.3 V	18.59 A	22.9%
Diferial	5%	746 W	40.4 V	18.47 A	48.3 V	19.52 A	24.0%
Bifacial Gain**	10%	781 W	40.4 V	19.35 A	48.3 V	20.45 A	25.1%
Guiii	20%	852 W	40.4 V	21.11 A	48.3 V	22.31 A	27.4%
CS7N-715	ΓB-AG	715 W	40.6 V	17.63 A	48.5 V	18.64 A	23.0%
Diferial	5%	751 W	40.6 V	18.51 A	48.5 V	19.57 A	24.2%
Bifacial Gain**	10%	787 W	40.6 V	19.39 A	48.5 V	20.50 A	25.3%
Guiii	20%	858 W	40.6 V	21.16 A	48.5 V	22.37 A	27.6%
CS7N-720	ΓB-AG	720 W	40.8 V	17.67 A	48.7 V	18.69 A	23.2%
Difosial	5%	756 W	40.8 V	18.55 A	48.7 V	19.62 A	24.3%
Bifacial Gain**	10%	792 W	40.8 V	19.44 A	48.7 V	20.56 A	25.5%
	20%	864 W	40.8 V	21.20 A	48.7 V	22.43 A	27.8%

^{*} Under Standard Test Conditions (STC) of irradiance of 1000 W/m², spectrum AM 1.5 and cell temperature of 25°C.


ELECTRICAL DATA

Operating Temperature	-40°C ~ +85°C
Max. System Voltage	1500 V (IEC/UL) or 1000 V (IEC/UL)
Module Fire Performance	TYPE 29 (UL 61730) or CLASS C (IEC61730)
Max. Series Fuse Rating	35 A
Protection Class	Class II
Power Tolerance	0 ~ + 10 W
Power Bifaciality*	80 %

^{*} Power Bifaciality = $Pmax_{rear}$ / $Pmax_{front}$ both $Pmax_{rear}$ and $Pmax_{front}$ are tested under STC, Bifaciality Tolerance: \pm 5 %

Please be kindly advised that PV modules should be handled and installed by qualified people who have professional skills and please carefully read the safety and installation instructions before using our PV modules.

CS7N-695TB-AG / I-V CURVES



ELECTRICAL DATA | NMOT*

ELECTRICAL DATA TUMOT									
	Nominal	Opt.	Opt.	Open	Short				
	Max.		Operating	Circuit	Circuit				
	Power (Pmax)	Voltage (Vmp)	Current (Imp)	Voltage (Voc)	Current (Isc)				
CS7N-690TB-AG	522 W	37.4 V	13.94 A	45.0 V	14.83 A				
CS7N-695TB-AG	526 W	37.6 V	13.97 A	45.2 V	14.87 A				
CS7N-700TB-AG	529 W	37.8 V	14.00 A	45.4 V	14.91 A				
CS7N-705TB-AG	533 W	38.0 V	14.03 A	45.5 V	14.95 A				
CS7N-710TB-AG	537 W	38.2 V	14.06 A	45.7 V	14.99 A				
CS7N-715TB-AG	541 W	38.4 V	14.09 A	45.9 V	15.03 A				
CS7N-720TB-AG	544 W	38.6 V	14.12 A	46.1 V	15.07 A				
* Under Naminal Mod	lula Operatio	a Temperature	(NIMOT) irradi	ance of 800	\M/m2.				

^{*} Under Nominal Module Operating Temperature (NMOT), irradiance of 800 W/m² spectrum AM 1.5, ambient temperature 20°C, wind speed 1 m/s.

MECHANICAL DATA

Specification	Data
Cell Type	TOPCon cells
Cell Arrangement	132 [2 x (11 x 6)]
Dimensions	2384 × 1303 × 35 mm (93.9 × 51.3 × 1.38 in)
Weight	37.9 kg (83.6 lbs)
Front Glass	2.0 mm heat strengthened glass with anti- reflective coating
Back Glass	2.0 mm heat strengthened glass
Frame	Anodized aluminium alloy
J-Box	IP68, 3 bypass diodes
Cable	6.0 mm ² (IEC), 10 AWG (UL)
Cable Length (Including Connector)	360 mm (14.2 in) (+) / 200 mm (7.9 in) (-) or 2000 mm (78.7 in) (+) / 1400 mm (55.1 in) (-)
Connector	T6 or MC4 series
Per Pallet	31 pieces
Per Container (40' HQ	558 pieces or 496 pieces (only for US & Canada)

TEMPERATURE CHARACTERISTICS

Specification	Data
Temperature Coefficient (Pmax)	-0.29 % / °C
Temperature Coefficient (Voc)	-0.25 % / °C
Temperature Coefficient (Isc)	0.05 % / °C
Nominal Module Operating Temperature	41 ± 3°C

PARTNER SECTION

^{**} Bifacial Gain: The additional gain from the back side compared to the power of the front side at the standard test condition. It depends on mounting (structure, height, tilt angle etc.) and albedo of the ground.

^{*} The specifications and key features contained in this datasheet may deviate slightly from our actual products due to the on-going innovation and product enhancement. CSI Solar Co., Ltd. reserves the right to make necessary adjustment to the information described herein at any time without further notice.

Q.PEAK DUO ML-G12S SERIES



675 - 695 Wp | 132 Cells 22.4% Maximum Module Efficiency

MODEL

Q.PEAK DUO ML-G12S.3/BFG Q.PEAK DUO ML-G12S.d/BFG





Highest Power Class Module

With the new G12, Qcells heralds the next generation of solar modules' enabling more power generation than ever before.



Bifacial energy yield gain of up to 21%

Bifacial Q.ANTUM solar cells make efficient use of light shining on the module rear-side for radically improved LCOE.



Low electricity generation costs

Q.ANTUM DUO technology with optimized module layout to boost module power and improve LCOE.



A reliable investment

Double glass module design enables extended lifetime with 12-year product warranty and improved 30-year performance warranty¹.



Enduring high performance

Long-term yield security with Anti LID and Anti PID Technology², Hot-Spot Protect.



Frame for versatile mounting options

High-tech aluminum alloy frame protects from damage, enables use of a wide range of mounting structures and is certified regarding IEC for high snow (5400 Pa) and wind loads (2400 Pa)³.



Innovative all-weather technology

Optimal yields, whatever the weather with excellent low-light and temperature behavior.

 $^{^2}$ APT test conditions according to IEC/TS 62804-1:2015 method B (–1500 V, 168 h) including post treatment according to IEC 61215-1-1 Ed. 2.0 (CD)














¹ See data sheet on rear for further information.

■ Mechanical Specification

Format	93.8 in × 51.3 in × 1.38 in (including frame) (2384 mm × 1303 mm × 35 mm)
Weight	84.2 lbs (38.2kg)
Front Cover	0.08 in (2.0 mm) thermally pre-stressed glass with anti-reflection technology
Back Cover	0.08 in (2.0 mm) semi-tempered glass
Frame	Anodised aluminium
Cell	6 × 22 monocrystalline Q.ANTUM solar half cells
Junction box	2.09-3.98 \times 1.26-2.36 \times 0.59-0.71 in (53-101 mm \times 32-60 mm \times 15-18 mm), Protection class IP67, with bypass diodes
Cable	4 mm² Solar cable; (+) ≥31.5 in (800 mm), (-) ≥13.8 in (350 mm)
Connector	Stäubli MC4; Stäubli MC4-Evo2; - IP68



■ Electrical Characteristics

PC	WER CLASS			675		680		685		690		695	
MIN	MINIMUM PERFORMANCE AT STANDARD TEST CONDITIONS, STC1 (POWER TOLERANCE +5 W/-0 W)												
					BSTC*								
	Power at MPP ¹	P_{MPP}	[W]	675	738.4	680	743.8	685	749.3	690	754.8	695	760.2
_	Short Circuit Current ¹	I _{sc}	[A]	18.45	20.20	18.48	20.23	18.51	20.26	18.54	20.30	18.58	20.33
m.	Open Circuit Voltage ¹	V _{oc}	[V]	45.74	45.90	45.76	45.92	45.78	45.94	45.80	45.97	45.82	45.99
Minin	Current at MPP	I _{MPP}	[A]	17.56	19.22	17.62	19.28	17.68	19.34	17.74	19.40	17.79	19.47
	Voltage at MPP	V_{MPP}	[V]	38.43	38.42	38.59	38.58	38.75	38.74	38.90	38.90	39.06	39.05
	Efficiency ¹	η	[%]	≥21.7		≥21.9		≥22.1		≥22.2		≥22.4	

Bifaciality of P_{MPP} and I_{SC} 70 % \pm 5% \bullet Bifaciality given for rear side irradiation on top of STC (front side) \bullet According to IEC 60904-1-2


 $^{1}\text{Measurement tolerances P}_{\text{MPP}}\pm3\,\%; I_{\text{SC}}, V_{\text{OC}}\pm5\,\% \text{ at STC: } 1000\,\text{W/m}^{2}; \\ ^{*}\text{at BSTC: } 1000\,\text{W/m}^{2}+\phi \times 135\,\text{W/m}^{2}, \\ \phi = 70\,\%, 25\pm2\,^{\circ}\text{C}, \text{AM 1.5 according to IEC 60904-300}; \\ ^{*}\text{AM 1.5 acco$

MINIMUM PERFORMANCE AT NORMAL OPERATING CONDITIONS, NMOT²

	Power at MPP	P_{MPP}	[W]	508.2	512.0	515.7	519.5	523.3	
Ę	Short Circuit Current	I _{sc}	[A]	14.86	14.89	14.91	14.94	14.96	
Minim	Open Circuit Voltage	V _{oc}	[V]	43.26	43.28	43.30	43.32	43.34	
	Current at MPP	I _{MPP}	[A]	13.83	13.88	13.93	13.98	14.03	
	Voltage at MPP	V _{MPP}	[V]	36.75	36.89	37.03	37.16	37.29	

 $^{1}\text{Measurement tolerances P}_{\text{MPP}}\pm3\%; \\ \text{I}_{\text{SC}}; \\ \text{V}_{\text{OC}}\pm5\% \text{ at STC}: \\ 1000 \\ \text{W/m}^{2}, \\ 25\pm2\text{°C}, \\ \text{AM 1.5 according to IEC 60904-3} \\ \bullet \text{^2800 W/m}^{2}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^2800 W/m}^{2}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^2800 W/m}^{2}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^2800 W/m}^{2}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^2800 W/m}^{2}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^2800 W/m}^{2}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^2800 W/m}^{2}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^2800 W/m}^{2}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^2800 W/m}^{2}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^2800 W/m}^{2}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^2800 W/m}^{2}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^{2800 W/m}^{2}}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^{2800 W/m}^{2}}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^{2800 W/m}^{2}}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^{2800 W/m}^{2}}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^{2800 W/m}^{2}}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^{2800 W/m}^{2}}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^{2800 W/m}^{2}}, \\ \text{NMOT, spectrum AM 1.5 according to IEC 60904-3} \\ \bullet \text{^{2800 W/m}^{2}}, \\ \text{^{$


Qcells PERFORMANCE WARRANTY



At least 98% of nominal power during first year. Thereafter max. 0.45% degradation per year. At least 93.95% of nominal power up to 10 years. At least 84.95% of nominal power up to 30 years.

All data within measurement tolerances. Full warranties in accordance with the warranty terms of the Qcells sales organisation of your respective country.





*Standard terms of guarantee for the 5 PV companies with the highest production capacity in 2021 (February 2021)

Typical module performance under low irradiance conditions in comparison to STC conditions (25 $^{\circ}$ C, 1000 W/m²).

TEMPERATURE COEFFICIENTS							
Temperature Coefficient of I _{sc}	α	[%/K]	+0.04	Temperature Coefficient of V_{oc}	β	[%/K]	-0.27
Temperature Coefficient of P _{MPP}	γ	[%/K]	-0.34	Nominal Module Operating Temperature	NMOT	[°F]	108±5.4 (42±3°C)

■ Properties for System Design

Maximum System Voltage	V_{SYS}	[V]	1500	PV
Maximum Series Fuse Rating		[A DC]	35	Fire
Max. Push Load ³ , Test/Design		[lbs/ft ²]	113 (5400 Pa)/75 (3600 Pa)	Per
Max. Pull Load³, Test/Design		[lbs/ft²]	50 (2400 Pa)/33 (1600 Pa)	on (

³ See Installation Manual for instructions

С	PV module classification	Class II
5	Fire Rating based on ANSI/UL 61730	TYPE 29 ⁴
a) a)	Permitted Module Temperature on Continuous Duty	-40°F up to +185°F (-40°C up to +85°C)

⁴ New Type is similar to Type 3 but with metallic frame

Qualifications and Certificates

UL 61730, CE-compliant, IEC 61215:2016, IEC 61730:2016, U.S. Patent No. 9,893,215 (solar cells)









ocells



Request No. 81:

Confirm whether the project will have a battery storage system. If a battery storage system is going

to be utilized, provide the following:

a. Safety data sheets for the energy storage system.

b. The environmental impact of the batter[y] storage system.

c. Expected life of the batteries.

d. Method to dispose of batteries at the end of the useful life.

e. How the battery storage system installation will comply with National Fire

Protection Association Standard 855.

Response No. 81:

a. The Project will not include a battery storage system.

b. See Response No. 81(a).

c. See Response No. 81(a).

d. See Response No. 81(a).

e. See Response No. 81(a).

Case No. 2024-00253

Request No. 82:

Provide information on any fiber optic or communication network installed as a part of the project

and any excavation that may be required for the installation.

Response No. 82:

Communication networks will be installed throughout Project site and to the substation to establish

plant monitoring and communications. Communication lines will be trenched in tandem with the

Project's medium voltage cabling to minimize trenching activities and to keep communication and

electric cabling parallel in the same trench.

Request No. 83:

Provide the planned time for construction to begin and end each day. Explain how Clover Creek

Solar plans to mitigate arrivals and departures to minimize disruption to the area.

Response No. 83:

See Response Nos. 8 and 59.

Case No. 2024-00253

Request No. 84:

Provide any communication representatives of Clover Creek Solar have had with any of the

property owners surrounding the project. Explain whether any changes have been made to the

project based upon those concerns.

Response No. 84:

Project representatives have communicated with multiple adjoining property owners regarding the

Project, mainly conducted in-person or via phone. Responsive neighbors expressed concern over

panel placement. Project representatives addressed neighbors' concerns by providing information

regarding the Project's setbacks and vegetative screening plans. In certain portions of the project,

based on neighbor feedback, setbacks were enlarged and additional vegetative screening was

added. See also the Response to Request No. 50.