

**COMMONWEALTH OF KENTUCKY
BEFORE THE PUBLIC SERVICE COMMISSION**

In the Matter of:

Electronic Application Of Kentucky Power)
Company For A Certificate Of Public Convenience)
And Necessity To Replace and Upgrade Portions of)
the Bellefonte Station In Boyd County, Kentucky)
(Bellefonte Station Upgrade Project))

Case No. 2024-00343

**ERRATA DIRECT TESTIMONY OF
NICOLAS C. KOEHLER
ON BEHALF OF KENTUCKY POWER COMPANY**

**ERRATA DIRECT TESTIMONY OF
NICOLAS C. KOEHLER ON BEHALF OF
KENTUCKY POWER COMPANY
BEFORE THE PUBLIC SERVICE COMMISSION OF KENTUCKY**

CASE NO. 2024-00343

TESTIMONY INDEX

<u>SECTION</u>	<u>PAGE</u>
I. INTRODUCTION	1
II. BACKGROUND	1
III. PURPOSE OF TESTIMONY	2
IV. PROJECT NEED AND SOLUTION.....	2
V. ALTERNATIVES TO THE PROJECT.....	6

**ERRATA DIRECT TESTIMONY OF
NICOLAS C. KOEHLER ON BEHALF OF
KENTUCKY POWER COMPANY
BEFORE THE PUBLIC SERVICE COMMISSION OF KENTUCKY**

CASE NO. 2024-00343

I. INTRODUCTION

1 **Q. PLEASE STATE YOUR NAME, POSITION AND BUSINESS ADDRESS.**

2 A. My name is Nicolas C. Koehler. My position is Director of East Transmission Planning for
3 American Electric Power Service Corporation (“AEPSC”). AEPSC supplies engineering,
4 financing, accounting, planning, advisory, and other services to the subsidiaries of the
5 American Electric Power (“AEP”) system, one of which is Kentucky Power Company (the
6 “Company”). My business address is 1 Riverside Plaza, Columbus, Ohio 43215.

II. BACKGROUND

7 **Q. PLEASE SUMMARIZE YOUR EDUCATIONAL BACKGROUND AND**
8 **BUSINESS EXPERIENCE.**

9 A. I received a Bachelor of Science – Electrical Engineering degree from Ohio Northern
10 University in Ada, Ohio. In 2008, I joined AEP as a Planning Engineer where I advanced
11 through increasing levels of responsibility. I received my Professional Engineer license in
12 the state of Ohio in 2012 (license number 76967). In May 2019, I assumed my current
13 position.

14 **Q. WHAT ARE YOUR RESPONSIBILITIES AS DIRECTOR OF EAST**
15 **TRANSMISSION PLANNING?**

16 A. My responsibilities include organizing and managing all activities related to assessing the
17 adequacy of AEP's transmission network to meet the needs of its customers in a reliable,

1 safe, cost effective, and environmentally compatible manner. I participate in planning
2 activities with Kentucky Power to address overall system performance.

3 **Q. HAVE YOU PREVIOUSLY SUBMITTED TESTIMONY BEFORE THE**
4 **KENTUCKY PUBLIC SERVICE COMMISSION?**

5 A. Yes. I previously submitted testimony in support of three of Kentucky Power’s previous
6 transmission Certificate of Public Convenience and Necessity (“CPCN”) cases, Case No.
7 2020-00062, Case No. 2021-00346, and Case No. 2023-00040.

III. PURPOSE OF TESTIMONY

8 **Q. WHAT IS THE PURPOSE OF YOUR TESTIMONY?**

9 A. I am testifying in support of Kentucky Power’s application for a CPCN authorizing
10 Kentucky Power to construct the Bellefonte Station Upgrade Project (the “Project”) located
11 in Boyd County just northwest of Ashland. I will provide information related to the need
12 for the Project.

IV. PROJECT NEED AND SOLUTION

13 **Q. PLEASE DESCRIBE THE NEED FOR THE PROPOSED PROJECT.**

14 A. This Project is driven by baseline thermal and short circuit violations at the Bellefonte
15 Station identified by AEP and PJM during the 2026 Regional Transmission Expansion Plan
16 (“RTEP”), as well as supplemental asset renewal needs identified by AEP within the
17 Station. During the 2026 RTEP planning process, an N-1-1 violation was identified on the
18 station conductors (“risers”) between 138/69 kV Transformer #3 and the 69kV causing a
19 thermal overload due to loss of the 138/69kV transformer and associated buses at Kenova
20 Station. and the Bellefonte 138/69kV Transformer #2. These risers will need to be
21 upgraded. Also during the 2026 RTEP, six 69 kV breakers, C, G, I, Z, AB, and JJ, were

1 identified as overdutied. Addressing this baseline violation has the additional benefit of
2 upgrading these 1970's vintage oil-filled breakers, which are increasingly difficult and
3 expensive to maintain. After these upgrades are complete, some minor remote end
4 upgrades must also be completed at associated stations, Pleasant Street Station and Coalton
5 Station, to adjust for the upgrades.

6 For supplemental needs, the 138/69 kV Transformer #2 is 1970's vintage and has
7 nitrogen and oil leaks, along with failed fans, and it lacks high-side protection. The oil
8 filled 69kV circuit breakers H and T are 1960's vintage and are increasingly difficult and
9 expensive to maintain and will be upgraded as part of the Project. The 69kV capacitor bank
10 KK is installed on the Raceland 69kV line instead of the 69kV bus. The Company is also
11 using this opportunity to electrically reterminate the Raceland 69kV line from bus #2 to
12 bus #1 and the capacitor bank from the Raceland 69kV line to bus #1. After these upgrades
13 are complete, some minor remote end upgrades must also be completed at an associated
14 station, Raceland Station, to adjust for the upgrades.

15 The 34.5 kV yard is obsolete and no longer serves any customers and will be retired.
16 The two 138/34.5 kV Transformers, #1 and #5, are 1950's and 1960's vintage respectively
17 and have asset health concerns such as oil and nitrogen leaks and also will be retired. The
18 34.5kV circuit breakers E, K, M, and F are 1950's-1970's vintage and have asset health
19 concerns such as being oil filled without oil containment, and will also be retired.

20 **Q. PLEASE DESCRIBE HOW THE PROJECT ADDRESSES THE NEEDS YOU**
21 **IDENTIFIED ABOVE.**

22 A. The baseline needs will be addressed on this Project by replacing the overloaded and
23 overdutied equipment. The risers on 138/69kV Transformer #3 are overloaded to 101%.

1 This Project will increase the rating of the risers. The 69kV circuit breakers C, G, I, Z, AB,
2 and JJ are overdutied to 115%. This Project will replace these circuit breakers with 40 kA
3 circuit breakers.

4 The remaining supplemental equipment condition needs will be addressed by
5 replacing 69kV circuit breakers H and T. The 138/69kV Transformer #2 will be replaced
6 and a 138kV circuit switcher will be installed. The 69kV line to Raceland will be relocated
7 from 69kV bus #2 to 69kV bus #1 and the 69kV capacitor bank KK will be moved from
8 the Raceland line to 69kV bus #1. The 34.5 kV yard and equipment will be retired since it
9 no longer serves any customers. This includes 138/34.5kV Transformer #5 and #1, and
10 34.5kV circuit breakers E, K, M, and F.

11 **Q. HOW MANY CUSTOMERS ARE SERVED BY THIS STATION IN THE AREA?**

12 A. Bellefonte Station currently serves two industrial customers and 3,570 distribution
13 customers. The industrial customers served from transmission have a peak load of
14 approximately 26.9 MW. The distribution customers served from Bellefonte Station have
15 a peak load of approximately 17.5 MW.

16 **Q. ARE THERE FUTURE PROJECTS ANTICIPATED FOR THIS STATION?**

17 A. If the CPCN requested in this Application is granted, the Company does not anticipate
18 further projects at the Bellefonte Station this time.

19 **Q. IS THE DESIGNATION OF A PROJECT AS “BASELINE” OR**
20 **“SUPPLEMENTAL” INDICATIVE OF WHETHER THE PROJECT IS**
21 **NECESSARY OR HOW NECESSARY IT IS?**

22 A. No, it is not. The designation of a project as a Baseline or Supplemental is not indicative
23 of the level of, or absence of, need for the project. Instead, the designations simply reflect

1 that the project addresses different system reliability and resilience needs.

2 The criteria for designation as a Supplemental or Baseline Project are not mutually
3 exclusive, and a single project can be needed under either or both. Under the existing PJM
4 RTO framework, Transmission Owners retain planning responsibility for managing the
5 maintenance and replacement of their transmission assets and planning of their local
6 transmission systems.

7 PJM planning criteria addresses the expansion and enhancement of transmission
8 facilities required to meet national and regional planning criteria. Supplemental Projects
9 improve or preserve a PJM Transmission Owner's ability to provide reliable service to its
10 customers, consistent with its obligation to serve, and are grounded in Good Utility
11 Practice.

12 **Q. DO ANY OF THE COMPONENTS OF THE PROJECT RESULT IN WASTEFUL**
13 **DUPLICATION?**

14 A. No. All components, whether baseline or supplemental, of the proposed Project are
15 required to fully address the needs described above. By performing the work inside the
16 existing station location to better take advantage of space and available outages, the
17 Company is proposing to move forward with the most cost-effective solution to address
18 the needs. The baseline components are required to address planning criteria violations at
19 the Station to avoid the risk of damaging equipment and/or not being able to serve load
20 (load drop) as a means to address thermal and short circuit issues as identified in the 2026
21 RTEP analysis. The supplemental components are needed to address deteriorating
22 infrastructure concerns that could potentially lead to failures and extended outages in the
23 future if not addressed. By performing all this work together, the Company is better able

1 to utilize available resources to complete the work instead of using a piecemeal approach
2 to replacement.

V. **ALTERNATIVES TO THE PROJECT**

3 **Q. WHAT ELECTRICAL ALTERNATIVES WERE EVALUATED BY THE**
4 **COMPANY?**

5 A. The Project Alternative would consist of rebuilding and relocating the existing Bellefonte
6 69kV Station facilities and seven transmission lines, plus two transformer feeds to the
7 existing Bellefonte Station 34kV yard located to the north-west of the existing 69kV yard
8 (see Exhibit 6). Instead the Proposed Project will upgrade the existing Bellefonte 69kV
9 Station facilities generally in place. Both the Proposed Project and the project alternative
10 require completing the proposed supplemental work at the existing Bellefonte 138kV
11 Station yard and retiring the obsolete 34kV equipment. The Project Alternative was
12 dismissed early since (i) it is significantly more work and cost; (ii) it would result in
13 wasteful duplication; and (iii) it does not provide additional benefits to justify the additional
14 cost. The cost of the alternative is \$46.5 million as compared to the Proposed Project
15 estimate of \$26.3 million. Please see the Direct Testimony of Company Witness Wolfram
16 for a breakdown of the estimated cost of the Proposed Project.

17 **Q. FROM AN ELECTRICAL PERSPECTIVE, IS THE ALTERNATIVE**
18 **PREFERABLE TO THE PROPOSED PROJECT?**

19 A. While there might be slight electrical benefits to constructing specifically the ring bus
20 configuration from the alternative, the alternative configuration would not address any
21 current needs beyond those addressed by the Proposed Project and is therefore not presently
22 justified given the significant cost difference. As such, the Project represents the least-

1 cost, most reasonable option to address the baseline and supplemental needs identified
2 above.

3 **Q. DOES THIS CONCLUDE YOUR TESTIMONY?**

4 A. Yes, it does.

Certificate Of Completion

Envelope Id: F5365327-F4C4-4C49-A548-B3C7B40FD343
 Subject: Complete with Docusign: Koehler Verification Form.doc
 Source Envelope:
 Document Pages: 1 Signatures: 2
 Certificate Pages: 5 Initials: 0
 AutoNav: Enabled
 Envelopeld Stamping: Disabled
 Time Zone: (UTC-08:00) Pacific Time (US & Canada)

Status: Completed
 Envelope Originator:
 Michelle Caldwell
 mmcaldwell@aep.com
 IP Address: 167.239.221.107


Record Tracking

Status: Original
 12/17/2024 5:00:25 PM
 Holder: Michelle Caldwell
 mmcaldwell@aep.com
 Location: DocuSign

Signer Events

Nicolas C Koehler
 nckoehler@aep.com
 Security Level: Notarized Signing (Notary: Michelle Caldwell)

Signature

Signed by:

 5701CC311F0D49D...

Signature Adoption: Pre-selected Style
 Using IP Address: 167.239.221.104

Timestamp

Sent: 12/17/2024 5:02:22 PM
 Viewed: 12/18/2024 10:01:17 AM
 Signed: 12/18/2024 10:01:35 AM

Electronic Record and Signature Disclosure:

Accepted: 12/18/2024 10:01:17 AM
 ID: 46835097-7a0f-4699-ab39-d0343015956e

In Person Signer Events

Signature

Timestamp

Editor Delivery Events

Status

Timestamp

Agent Delivery Events

Status

Timestamp

Intermediary Delivery Events

Status

Timestamp

Certified Delivery Events

Status

Timestamp

Carbon Copy Events

Status

Timestamp

Witness Events

Signature

Timestamp

Notary Events

Signature

Timestamp

Michelle Caldwell
 mmcaldwell@aep.com
 Regulatory Case Coordinator
 AEP Kentucky Power

MARILYN MICHELLE CALDWELL
 ONLINE NOTARY PUBLIC
 COMMONWEALTH OF KENTUCKY
 Commission #KYNP71841
 My Commission Expires 5/5/2027

Sent: 12/17/2024 5:02:23 PM
 Viewed: 12/18/2024 10:01:11 AM
 Signed: 12/18/2024 10:02:15 AM

Notary for Nicolas C Koehler (nckoehler@aep.com) Using IP Address: 167.239.221.107

Security Level: Email, Account Authentication (Required), Digital Certificate

Signature Provider Location:
<https://ssasign.docusign.net/sca/1940>

Signature Provider Details:

Signature Type: DS Authority IDV (Client ID: c171dfd7-d7e5-4793-b1bf-4d660787eaa0)

Signature Issuer: DocuSign Cloud Signing CA-Identity

Electronic Record and Signature Disclosure:

Not Offered via DocuSign

Envelope Summary Events

Status

Timestamps

Envelope Summary Events	Status	Timestamps
Envelope Sent	Hashed/Encrypted	12/17/2024 5:02:23 PM
Certified Delivered	Security Checked	12/18/2024 10:01:17 AM
Signing Complete	Security Checked	12/18/2024 10:01:35 AM
Completed	Security Checked	12/18/2024 10:02:15 AM

Payment Events	Status	Timestamps
-----------------------	---------------	-------------------

Electronic Record and Signature Disclosure
