RECEIVED

APR 01 2020

PUBLIC SERVICE COMMISSION



Electric Distribution Utility Annual Reliability Report For 2019

March 2020

KENTUCKY PUBLIC SERVICE COMMISSION

Electric Distribution Utility Annual Reliability Report

SECTION 1: CONTACT INFORMATION

UTILITY NAME REPORT PREPARED BY E-MAIL ADDRESS OF PREPARER PHONE NUMBER OF PREPARER Blue Grass Energy

Kyle Lancaster

kylel@bgenergy.com

(859) 885-2103

SECTION 2: REPORTING YEAR

CALENDAR YEAR OF REPORT

2019

SECTION 3: MAJOR EVENT DAYS (MED)

FIRST DATE USED TO DETERMINE T_{MED} LAST DATE USED TO DETERMINE T_{MED} NUMBER OF MED IN REPORT YEAR

11.38

January 1 2014

December 31 2018

NOTE: Per IEEE 1366 T_{MED} should be calculated using the daily SAIDI values for the five prior years. If five years of data are not available, then utilities should use what is available until five years are accumulated.

SECTION 4: SYSTEM RELIABILITY INFORMATION AND RESULTS

System-wide Information

TOTAL CUSTOMERS 57854

TOTAL CIRCUITS 136

Excluding MED

| 5 YEAR AVERAGE | | | REPORTING YEAR | |
|----------------|--------|-------|-----------------------|--|
| SAIDI | 126.93 | SAIDI | 130.19 | |
| SAIFI | 1.0921 | SAIFI | 1.1387 | |

Including MED

| | 5 YEAR AVERAGE | | REPORTING YEAR |
|-------|----------------|-------|----------------|
| SAIDI | 214.46 | SAIDI | 169.64 |
| SAIFI | 1.3048 | SAIFI | 1.3050 |

Notes:

- 1) All duration indices (SAIDI) are to be reported in units of minutes.
- 2) Reports are due on the first business day of May of each year
- 3) Reports cover the calendar year ending in the December before the reports are due.
- 4) IEEE 1366 (latest version) is used to define SAIDI, SAIFI, and T_{MED}

KENTUCKY PUBLIC SERVICE COMMISSION

SECTION 5: CIRCUIT REPORTING

(CIRCUITS WITH SAIDI AND/OR SAIFI EXCEEDING 5 YEAR AVERAGE)

(CIRCUIT NUMBERS SHOULD BE REPORTED EXCLUDING MED)

CIRCUIT #1:

- 1. SUBSTATION NAME AND NUMBER
- 2. SUBSTATION LOCATION (COUNTY-ROAD-TOWN)
- 3. CIRCUIT NAME AND NUMBER
- 4. CIRCUIT LOCATION (TOWN-ROAD-GENERAL AREA)
- 5. TOTAL CIRCUIT LENGTH (MILES)
- 6. CUSTOMER COUNT FOR THIS CIRCUIT
- 7.. DATE OF LAST CIRCUIT TRIM (VM)
- 8. LIST OUTAGE CAUSES FOR CIRCUIT ALONG WITH PERCENTAGE OF TOTAL OUTAGE NU NUMBERS REPRESENTED BY EACH CAUSE
- 9. CIRCUIT 5 YEAR AVERAGE (SAIDI)
- 10. REPORTING YEAR (SAIDI)
- 11. CIRCUIT 5 YEAR AVERAGE (SAIFI)
- 12. REPORTING YEAR (SAIFI)
- 13. CORRECTIVE ACTION PLAN

REPEAT INFORMATION FOR EACH CIRCUIT EXCEEDING ITS 5 YEAR AVERAGE FOR SAIDI AND/OR SAIFI

KENTUCKY PUBLIC SERVICE COMMISSION

SECTION 6: VEGETATION MANAGEMENT PLAN REVIEW

INCLUDE CURRENT VEGETATION MANAGEMENT PLAN

Additional page may be attached as needed.

| Vegetation Manag | gement Plan Attached in Word Document. | |
|------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| : | | |
| | | |
| | | |
| | The state of the s | |
| | | |
| | OPENION TO LITTLE OF COMMENTS | |
| | SECTION 7: UTILITY COMMENTS | |
| | SECTION 7: UTILITY COMMENTS | |
| | SECTION 7: UTILITY COMMENTS | |
| | SECTION 7: UTILITY COMMENTS | |
| | SECTION 7: UTILITY COMMENTS | |
| | SECTION 7: UTILITY COMMENTS | |
| | SECTION 7: UTILITY COMMENTS | |
| | SECTION 7: UTILITY COMMENTS | |
| | SECTION 7: UTILITY COMMENTS | |
| | SECTION 7: UTILITY COMMENTS | |

Substation Name and Number 3M 37 Hwy 982, Cynthiana, KY 41031 Substation Location Circuit Name and Number 3M 114 Circuit Location 3M Plant 0.4 Total Circuit Length (Miles) 2019 Member Count 1 1 5 Year Average Member Count Date of Last Trim December-14 2023 Date of Next Trim

| | 5 Year | 5 Year Average | |)19 |
|-------------------------|---------|----------------|---------|---------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 58.2 | 0.4 | 106 | 1 |
| Total Minutes/Frequency | 291.00 | 2.0000 | 106.00 | 1.0000 |
| Equipment Fault | 100.00% | 100.00% | 100.00% | 100.00% |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% |
| Small Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 0.00% | 0.00% | 0.00% | 0.00% |
| Deterioration | 0.00% | 0.00% | 0.00% | 0.00% |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 0.00% | 0.00% | 0.00% | 0.00% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 0.00% | 0.00% | 0.00% | 0.00% |
| Lightning | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - Non ROW | 0.00% | 0.00% | 0.00% | 0.00% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number 3M #2 41 Hwy 982, Cynthiana, KY 41031 **Substation Location** Circuit Name and Number 3M #2 104 Webbers Circuit Location Total Circuit Length (Miles) 42.1 704 2019 Member Count 685 5 Year Average Member Count Date of Last Trim December-18 Date of Next Trim 2024

| | 5 Year | 5 Year Average | | 019 |
|-------------------------|------------|----------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 131.998773 | 1.676514141 | 321.6079545 | 3.323863636 |
| Total Minutes/Frequency | 452091.00 | 5742.0000 | 226412.00 | 2340.0000 |
| Equipment Fault | 21.91% | 26.40% | 34.61% | 50.94% |
| Wind | 3.25% | 4.09% | 6.43% | 9.96% |
| Small Animal | 6.69% | 7.07% | 0.11% | 0.21% |
| Squirrel | 0.25% | 0.35% | 0.00% | 0.00% |
| Unknown Cause | 1.46% | 1.72% | 0.00% | 0.00% |
| Deterioration | 0.11% | 0.19% | 0.00% | 0.00% |
| Scheduled | 0.37% | 0.35% | 0.09% | 0.13% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.09% | 0.10% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 1.83% | 3.03% | 0.00% | 0.00% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.33% | 0.38% | 0.00% | 0.00% |
| Tree - ROW | 32.35% | 18.01% | 51.44% | 29.74% |
| Lightning | 23.94% | 32.22% | 3.80% | 6.54% |
| Tree - Non ROW | 6.10% | 4.35% | 3.52% | 2.48% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 1.31% | 1.72% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number 41 3M #2 Hwy 982, Cynthiana, KY 41031 Substation Location 3M #2 Circuit Name and Number 144 Hospital Circuit Location 1.7 Total Circuit Length (Miles) 2019 Member Count 5 5 5 Year Average Member Count November-15 Date of Last Trim 2021 Date of Next Trim

| | 5 Year | 5 Year Average | |)19 |
|-------------------------|-------------|----------------|---------|---------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 12.16853789 | 0.205549626 | 14 | 0.4 |
| Total Minutes/Frequency | 296.00 | 5.0000 | 70.00 | 2.0000 |
| Equipment Fault | 0.00% | 0.00% | 0.00% | 0.00% |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% |
| Small Animal | 20.27% | 20.00% | 0.00% | 0.00% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 0.00% | 0.00% | 0.00% | 0.00% |
| Deterioration | 0.00% | 0.00% | 0.00% | 0.00% |
| Scheduled | 56.08% | 40.00% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 23.65% | 40.00% | 100.00% | 100.00% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 0.00% | 0.00% | 0.00% | 0.00% |
| Lightning | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - Non ROW | 0.00% | 0.00% | 0.00% | 0.00% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Public Accident caused outages. No corrections necessary at this time.

Substation Name and Number
Substation Location
Circuit Name and Number
Circuit Location
Total Circuit Length (Miles)
2019 Member Count
5 Year Average Member Count
Date of Last Trim
Date of Next Trim

ALCAN 1 10
306 Mayde Road, Berea, KY 40403
ALCAN 1 124
Mayde Rd/MENASHA KI USA
3.7
40
43
January-18
2022

| | 5 Year | 5 Year Average | | 019 |
|-------------------------|-------------|----------------|---------|---------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 50.81814159 | 0.813053097 | 38.325 | 1.1 |
| Total Minutes/Frequency | 10938.00 | 175.0000 | 1533.00 | 44.0000 |
| Equipment Fault | 4.68% | 2.29% | 27.79% | 6.82% |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% |
| Small Animal | 27.11% | 39.43% | 72.21% | 93.18% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 0.00% | 0.00% | 0.00% | 0.00% |
| Deterioration | 37.12% | 16.00% | 0.00% | 0.00% |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 18.10% | 25.71% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 0.00% | 0.00% | 0.00% | 0.00% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Γree - ROW | 0.00% | 0.00% | 0.00% | 0.00% |
| Lightning | 12.99% | 16.57% | 0.00% | 0.00% |
| Γree - Non ROW | 0.00% | 0.00% | 0.00% | 0.00% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

No corrections necessary at this time.

Substation Name and Number BRACKEN COUNTY 31 61 New Zion Rd, Foster, KY 41043 **Substation Location** BRACKEN_COUNTY Circuit Name and Number 114 Lenoxburg Circuit Location 85.9 Total Circuit Length (Miles) 2019 Member Count 660 657 5 Year Average Member Count December-13 Date of Last Trim Date of Next Trim 2020

| | 5 Year | 5 Year Average | | 019 |
|-------------------------|-------------|----------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 101.0477063 | 0.70336595 | 111.7348485 | 0.937878788 |
| Total Minutes/Frequency | 332149.00 | 2312.0000 | 73745.00 | 619.0000 |
| Equipment Fault | 13.06% | 9.95% | 2.80% | 2.58% |
| Wind | 8.44% | 4.41% | 20.61% | 8.08% |
| Small Animal | 2.79% | 4.33% | 3.01% | 4.68% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 5.12% | 9.13% | 7.00% | 10.34% |
| Deterioration | 4.42% | 4.71% | 15.65% | 11.95% |
| Scheduled | 0.93% | 2.03% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 6.58% | 11.46% | 6.59% | 14.38% |
| Ice/Snow | 0.95% | 0.91% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 3.68% | 8.65% | 16.57% | 32.31% |
| Tree - ROW | 3.13% | 2.81% | 13.77% | 10.02% |
| Lightning | 6.58% | 5.84% | 0.15% | 0.16% |
| Tree - Non ROW | 43.30% | 34.17% | 13.84% | 5.49% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 1.04% | 1.60% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number

Substation Location

Circuit Name and Number

Circuit Location

Total Circuit Length (Miles)

2019 Member Count

5 Year Average Member Count

Date of Last Trim

Date of Next Trim

BRIDGEPORT #2

42

218 Taylor Branch Rd., Frankfort, KY 40601

BRIDGEPORT #2

244

Coolbrook

37.3

1084

1066

August-18

2024

| | 5 Year | Average | 2 | 019 |
|-------------------------|-------------|------------|------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 187.4741795 | 1.68439634 | 194.699262 | 1.583948339 |
| Total Minutes/Frequency | 999596.60 | 8981.0600 | 211054.00 | 1717.0000 |
| Equipment Fault | 16.93% | 17.88% | 46.24% | 45.89% |
| Wind | 10.91% | 12.60% | 4.32% | 2.56% |
| Small Animal | 3.95% | 7.00% | 1.48% | 3.32% |
| Squirrel | 0.30% | 0.56% | 0.00% | 0.00% |
| Unknown Cause | 0.84% | 1.41% | 2.72% | 4.72% |
| Deterioration | 0.51% | 0.66% | 0.05% | 0.12% |
| Scheduled | 1.16% | 2.04% | 0.58% | 0.52% |
| Power Supplier | 6.23% | 11.56% | 0.00% | 0.00% |
| Bird | 0.03% | 0.06% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 1.09% | 2.05% | 0.00% | 0.00% |
| Ice/Snow | 4.23% | 1.51% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 5.30% | 3.21% | 0.06% | 0.12% |
| Lightning | 25.32% | 19.12% | 27.22% | 30.34% |
| Tree - Non ROW | 22.58% | 18.46% | 17.32% | 12.41% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| | | | | |

0.63%

0.00%

100%

1.88%

0.00%

100%

0.00%

0.00%

100%

0.00%

0.00%

100%

Corrections to be made:

Contractor

Flash Flood

Substation Name and Number CLAY_LICK 26 **Substation Location** 5627 Louisville, Rd., Salvisa, KY 40372 Circuit Name and Number CLAY_LICK 124 Circuit Location Mccouns Ferry Total Circuit Length (Miles) 72.8 629 2019 Member Count 5 Year Average Member Count 616 December-14 Date of Last Trim Date of Next Trim 2021

| | 5 Year | 5 Year Average | | 019 |
|-------------------------|-------------|----------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 127.9053009 | 0.946105141 | 332.2988871 | 2.103338633 |
| Total Minutes/Frequency | 394083.00 | 2915.0000 | 209016.00 | 1323.0000 |
| Equipment Fault | 2.31% | 3.95% | 0.33% | 0.45% |
| Wind | 17.58% | 10.94% | 23.56% | 15.42% |
| Small Animal | 5.42% | 10.46% | 3.51% | 8.77% |
| Squirrel | 0.77% | 0.75% | 0.00% | 0.08% |
| Unknown Cause | 1.40% | 2.92% | 0.42% | 0.60% |
| Deterioration | 0.45% | 1.03% | 0.00% | 0.00% |
| Scheduled | 0.03% | 0.10% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.27% | 0.58% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 0.22% | 0.45% | 0.16% | 0.60% |
| Ice/Snow | 2.97% | 0.86% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 5.36% | 8.92% | 2.90% | 4.76% |
| Lightning | 38.91% | 34.03% | 54.68% | 48.68% |
| Tree - Non ROW | 24.27% | 24.97% | 14.45% | 20.63% |
| Large Animal | 0.03% | 0.03% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number
Substation Location
Circuit Name and Number
Circuit Location
Total Circuit Length (Miles)
2019 Member Count
5 Year Average Member Count

Date of Last Trim Date of Next Trim COLEMANSVILLE

32

Corner of HWY 1032 & 1054, Berry, KY 41003

COLEMANSVILLE

104

Morgan Marcus

111.8 784 772

June-19

2025

| | 5 Year | 5 Year Average | | 019 |
|-------------------------|-------------|----------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 273.4884032 | 1.910428955 | 575.3673469 | 3.415816327 |
| Total Minutes/Frequency | 1055056.00 | 7370.0000 | 451088.00 | 2678.0000 |
| Equipment Fault | 21.11% | 14.40% | 44.42% | 32.82% |
| Wind | 4.89% | 3.65% | 7.98% | 3.55% |
| Small Animal | 1.25% | 1.87% | 0.49% | 0.82% |
| Squirrel | 0.07% | 0.11% | 0.00% | 0.00% |
| Unknown Cause | 3.83% | 14.33% | 4.66% | 7.77% |
| Deterioration | 3.41% | 1.66% | 7.61% | 3.96% |
| Scheduled | 9.84% | 12.42% | 20.37% | 24.68% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 1.99% | 2.39% | 0.02% | 0.04% |
| Ice/Snow | 0.22% | 0.08% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 3.57% | 1.79% | 0.00% | 0.00% |
| Lightning | 23.39% | 19.93% | 0.85% | 4.33% |
| Tree - Non ROW | 20.44% | 15.70% | 10.47% | 18.11% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 6.00% | 11.68% | 3.13% | 3.92% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number
Substation Location
Circuit Name and Number
Circuit Location
Total Circuit Length (Miles)
2019 Member Count
5 Year Average Member Count
Date of Last Trim
Date of Next Trim

COLEMANSVILLE

32

Corner of HWY 1032 & 1054, Berry, KY 41005

COLEMANSVILLE

124

Robinson 72.1 580 571

December-18

2024

| | 5 Year | Average | 20 | 019 |
|-------------------------|-------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 186.1165577 | 1.438350188 | 216.9775862 | 1.494827586 |
| Total Minutes/Frequency | 531170.00 | 4105.0000 | 125847.00 | 867.0000 |
| Equipment Fault | 30.73% | 19.32% | 30.09% | 26.30% |
| Wind | 10.79% | 12.74% | 29.86% | 32.06% |
| Small Animal | 4.45% | 7.82% | 0.94% | 2.08% |
| Squirrel | 0.02% | 0.07% | 0.00% | 0.00% |
| Unknown Cause | 5.44% | 9.18% | 0.00% | 0.00% |
| Deterioration | 4.05% | 3.39% | 0.64% | 1.38% |
| Scheduled | 0.54% | 0.61% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.04% | 0.07% | 0.00% | 0.00% |
| Overload | 0.01% | 0.02% | 0.00% | 0.00% |
| Public Accident | 6.94% | 5.94% | 0.12% | 0.23% |
| Ice/Snow | 0.10% | 0.17% | 0.00% | 0.00% |
| Fire | 0.42% | 0.27% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 3.93% | 1.80% | 0.00% | 0.00% |
| Lightning | 28.20% | 32.81% | 22.00% | 18.11% |
| Tree - Non ROW | 3.88% | 4.26% | 14.38% | 12.69% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.47% | 1.51% | 1.97% | 7.15% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

13 Substation Name and Number CROOKSVILLE 765 Crooksville Rd., Richmond, KY 40475 **Substation Location** Circuit Name and Number CROOKSVILLE 114 Speedwell Circuit Location 69.1 Total Circuit Length (Miles) 2019 Member Count 641 633 5 Year Average Member Count November-14 Date of Last Trim 2021 Date of Next Trim

| | 5 Year Average | | 2019 | |
|-------------------------|----------------|-------------|-------------|------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 65.20559711 | 0.598036884 | 62.84087363 | 0.68798752 |
| Total Minutes/Frequency | 206508.00 | 1894.0000 | 40281.00 | 441.0000 |
| Equipment Fault | 5.68% | 7.55% | 6.92% | 7.26% |
| Wind | 1.30% | 1.85% | 0.00% | 0.00% |
| Small Animal | 21.60% | 28.83% | 46.43% | 46.49% |
| Squirrel | 0.89% | 1.58% | 0.00% | 0.00% |
| Unknown Cause | 7.44% | 11.77% | 19.81% | 26.08% |
| Deterioration | 2.74% | 4.75% | 0.16% | 0.23% |
| Scheduled | 0.42% | 0.95% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 12.02% | 10.03% | 0.00% | 0.00% |
| Ice/Snow | 8.77% | 3.12% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 11.50% | 8.45% | 6.31% | 6.35% |
| Lightning | 6.54% | 7.81% | 0.34% | 0.68% |
| Tree - Non ROW | 19.69% | 11.62% | 20.04% | 12.93% |
| Large Animal | 1.42% | 1.69% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

No corrections necessary at this time.

Substation Name and Number
Substation Location
Circuit Name and Number
Circuit Location
Total Circuit Length (Miles)
2019 Member Count
5 Year Average Member Count
Date of Last Trim
Date of Next Trim

CROOKSVILLE 13
765 Crooksville Rd., Richmond, KY 40475
CROOKSVILLE 124
Ogg Lane
53.7
700
692
February-15
2021

| | 5 Year Average | | 2019 | |
|-------------------------|----------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 50.1007114 | 0.401037003 | 97.65285714 | 0.782857143 |
| Total Minutes/Frequency | 173275.00 | 1387.0000 | 68357.00 | 548.0000 |
| Equipment Fault | 3.80% | 2.88% | 0.36% | 0.55% |
| Wind | 9.69% | 5.98% | 15.96% | 9.67% |
| Small Animal | 18.44% | 19.03% | 3.93% | 10.04% |
| Squirrel | 0.75% | 1.87% | 0.29% | 0.55% |
| Unknown Cause | 5.70% | 8.58% | 3.57% | 6.75% |
| Deterioration | 0.09% | 0.29% | 0.02% | 0.18% |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 0.03% | 0.14% | 0.00% | 0.00% |
| Ice/Snow | 8.28% | 12.18% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 5.85% | 13.19% | 11.11% | 26.28% |
| Lightning | 1.69% | 2.96% | 0.77% | 0.55% |
| Tree - Non ROW | 45.56% | 32.44% | 63.97% | 45.44% |
| Large Animal | 0.11% | 0.43% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number **DAVIS** 4 3876 Delong Rd., Lexington, KY 40515 **Substation Location** Circuit Name and Number **DAVIS** 124 Delong Rd Circuit Location 15.7 Total Circuit Length (Miles) 160 2019 Member Count 5 Year Average Member Count 166 December-19 Date of Last Trim Date of Next Trim 2023

| | 5 Year Average | | 2019 | |
|-------------------------|----------------|------------|----------|----------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 113.6699468 | 2.05123413 | 141.9 | 3.93125 |
| Total Minutes/Frequency | 94317.00 | 1702.0000 | 22704.00 | 629.0000 |
| Equipment Fault | 8.49% | 19.80% | 1.55% | 0.79% |
| Wind | 16.09% | 5.17% | 0.00% | 0.00% |
| Small Animal | 22.99% | 19.45% | 5.66% | 2.38% |
| Squirrel | 4.95% | 5.17% | 0.00% | 0.00% |
| Unknown Cause | 5.77% | 5.17% | 12.98% | 7.00% |
| Deterioration | 1.30% | 0.24% | 0.00% | 0.00% |
| Scheduled | 0.16% | 0.24% | 0.56% | 0.16% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.14% | 0.12% | 0.26% | 0.16% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 8.98% | 28.44% | 28.92% | 74.56% |
| Ice/Snow | 8.70% | 2.82% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 16.72% | 8.11% | 50.06% | 14.94% |
| Lightning | 5.73% | 5.29% | 0.00% | 0.00% |
| Tree - Non ROW | 0.00% | 0.00% | 0.00% | 0.00% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Circuit Trimmed at end of 2019. No corrections necessary at this time.

Substation Name and Number **DAVIS** 3876 Delong Rd., Lexington, KY 40515 **Substation Location** Circuit Name and Number **DAVIS** 144 Tates Creek Estates Circuit Location Total Circuit Length (Miles) 5.0 297 2019 Member Count 308 5 Year Average Member Count December-15 Date of Last Trim 2020 Date of Next Trim

| | 5 Year | 5 Year Average | | 2019 | |
|-------------------------|-------------|----------------|-------------|-------------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 94.52134137 | 1.099847869 | 118.7239057 | 1.414141414 | |
| Total Minutes/Frequency | 145583.00 | 1694.0000 | 35261.00 | 420.0000 | |
| Equipment Fault | 33.24% | 25.09% | 86.55% | 70.71% | |
| Wind | 4.06% | 3.84% | 0.00% | 0.00% | |
| Small Animal | 20.76% | 34.30% | 3.88% | 8.81% | |
| Squirrel | 0.10% | 0.12% | 0.00% | 0.00% | |
| Unknown Cause | 2.63% | 3.42% | 0.00% | 0.00% | |
| Deterioration | 2.53% | 2.24% | 0.00% | 0.00% | |
| Scheduled | 2.07% | 3.13% | 0.00% | 0.00% | |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% | |
| Bird | 0.17% | 0.30% | 0.48% | 0.71% | |
| Overload | 0.38% | 0.24% | 0.00% | 0.00% | |
| Public Accident | 1.68% | 1.18% | 0.00% | 0.00% | |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% | |
| Fire | 0.29% | 0.41% | 0.00% | 0.00% | |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - ROW | 28.86% | 19.95% | 4.04% | 10.95% | |
| Lightning | 1.53% | 2.77% | 0.00% | 0.00% | |
| Tree - Non ROW | 1.70% | 3.01% | 5.04% | 8.81% | |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% | |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:

Substation Name and Number
Substation Location
Circuit Name and Number
Circuit Location
Total Circuit Length (Miles)
2019 Member Count
5 Year Average Member Count
Date of Last Trim
Date of Next Trim

FAYETTE1 5 2442 Armstrong Mill, Lexington, KY 40515 FAYETTE1 104

Squires Rd-Right 14.4 692 685 March-18 2022

| | 5 Year | 5 Year Average | | 2019 | |
|-------------------------|-------------|----------------|------------|------------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 35.20454051 | 0.266853681 | 53.1517341 | 0.24132948 | |
| Total Minutes/Frequency | 120579.00 | 914.0000 | 36781.00 | 167.0000 | |
| Equipment Fault | 41.49% | 32.49% | 38.71% | 14.37% | |
| Wind | 11.57% | 4.60% | 37.52% | 22.16% | |
| Small Animal | 11.27% | 24.07% | 4.23% | 23.95% | |
| Squirrel | 4.61% | 7.00% | 0.00% | 0.00% | |
| Unknown Cause | 0.00% | 0.00% | 0.00% | 0.00% | |
| Deterioration | 9.59% | 6.78% | 0.93% | 1.80% | |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% | |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% | |
| Bird | 0.03% | 0.33% | 0.09% | 1.80% | |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% | |
| Public Accident | 0.45% | 0.22% | 1.49% | 1.20% | |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% | |
| Fire | 6.78% | 5.03% | 0.00% | 0.00% | |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - ROW | 5.35% | 6.78% | 17.03% | 34.73% | |
| Lightning | 4.86% | 6.35% | 0.00% | 0.00% | |
| Tree - Non ROW | 3.99% | 6.35% | 0.00% | 0.00% | |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% | |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:

Substation Name and Number
Substation Location
Circuit Name and Number
Circuit Location
Total Circuit Length (Miles)
2019 Member Count
5 Year Average Member Count

2019 Member Count
5 Year Average Member Count
Date of Last Trim
Date of Next Trim

| | 5 Year Average | | 2019 | |
|--------------------------|-------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 28.80576833 | 0.229521129 | 65.03308824 | 0.446078431 |
| Total Minutes/Fun manage | 116342.00 | 927.0000 | 53067.00 | 364.0000 |
| Total Minutes/Frequency | 59.78% | 46.82% | 92.92% | 90.38% |
| Equipment Fault | 3641275 201313135 | The state of the s | 7 mile mile . | |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% |
| Small Animal | 35.64% | 47.25% | 0.41% | 1.10% |
| Squirrel | 0.48% | 1.19% | 0.37% | 0.82% |
| Unknown Cause | 0.00% | 0.00% | 0.00% | 0.00% |
| Deterioration | 0.24% | 0.11% | 0.00% | 0.00% |
| Scheduled | 1.61% | 1.40% | 3.53% | 3.57% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 0.70% | 0.97% | 1.54% | 2.47% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 0.46% | 0.76% | 0.00% | 0.00% |
| Lightning | 0.21% | 0.43% | 0.00% | 0.00% |
| Tree - Non ROW | 0.90% | 1.08% | 1.23% | 1.65% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

FAYETTE1

FAYETTE1

2442 Armstrong Mill, Lexington, KY 40515

Armstrong Mill

7.0

816 808

March-18

2022

5

Corrections to be made:

Substation Name and Number FAYETTE1 5 Substation Location 2442 Armstrong Mill, Lexington, KY 40515 Circuit Name and Number FAYETTE1 Squire Rd-Left Circuit Location Total Circuit Length (Miles) 7.2 554 2019 Member Count 548 5 Year Average Member Count Date of Last Trim April-18 2022 Date of Next Trim

| | 5 Year | 5 Year Average | | 2019 | |
|-------------------------|-------------|----------------|------------|-------------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 87.01711742 | 0.734120087 | 138.734657 | 0.752707581 | |
| Total Minutes/Frequency | 238606.00 | 2013.0000 | 76859.00 | 417.0000 | |
| Equipment Fault | 56.91% | 54.15% | 88.47% | 82.25% | |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% | |
| Small Animal | 3.47% | 6.46% | 1.58% | 3.60% | |
| Squirrel | 0.86% | 1.64% | 0.00% | 0.00% | |
| Unknown Cause | 0.00% | 0.00% | 0.00% | 0.00% | |
| Deterioration | 0.19% | 0.40% | 0.00% | 0.00% | |
| Scheduled | 0.35% | 2.43% | 0.00% | 0.00% | |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% | |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% | |
| Overload | 0.16% | 0.15% | 0.00% | 0.00% | |
| Public Accident | 0.00% | 0.00% | 0.00% | 0.00% | |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% | |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% | |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - ROW | 20.26% | 21.81% | 9.67% | 13.43% | |
| Lightning | 7.01% | 6.46% | 0.00% | 0.00% | |
| Tree - Non ROW | 10.78% | 6.51% | 0.28% | 0.72% | |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% | |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:

Substation Name and Number
Substation Location
Circuit Name and Number
Circuit Location
Total Circuit Length (Miles)
2019 Member Count
5 Year Average Member Count
Date of Last Trim
Date of Next Trim

FAYETTE2 6
2442 Armstrong Mill, Lexington, KY 40515
FAYETTE2 114
Hartland

10.8 692 692 December-16 2020

| | 5 Year | 5 Year Average | | 2019 | |
|-------------------------|-------------|----------------|-------------|-------------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 34.33313408 | 0.898792826 | 37.41618497 | 1.047687861 | |
| Total Minutes/Frequency | 118723.00 | 3108.0000 | 25892.00 | 725.0000 | |
| Equipment Fault | 21.25% | 5.05% | 16.13% | 3.72% | |
| Wind | 17.67% | 22.20% | 0.00% | 0.00% | |
| Small Animal | 9.63% | 24.29% | 0.22% | 0.28% | |
| Squirrel | 0.11% | 0.06% | 0.00% | 0.00% | |
| Unknown Cause | 0.00% | 0.00% | 0.00% | 0.00% | |
| Deterioration | 0.42% | 0.10% | 0.00% | 0.00% | |
| Scheduled | 32.67% | 25.90% | 0.00% | 0.00% | |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% | |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% | |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% | |
| Public Accident | 0.78% | 0.16% | 3.59% | 0.69% | |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% | |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% | |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - ROW | 0.00% | 0.00% | 0.00% | 0.00% | |
| Lightning | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - Non ROW | 17.46% | 22.23% | 80.06% | 95.31% | |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% | |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:

No corrections necessary at this time.

Substation Name and Number

Substation Location

Circuit Name and Number

Circuit Location

Total Circuit Length (Miles)

2019 Member Count

5 Year Average Member Count

Date of Last Trim

Date of Next Trim

FAYETTE2

6

2442 Armstrong Mill, Lexington, KY 40515

FAYETTE2

124

Armstrong Mill

6.4

1064

1063

December-16

2020

| | 5 Year Average | | 2019 | |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|----------------------|----------------------|-----------------------|
| | SAIDI 103.6906774 | SAIFI 0.926106853 | SAIDI 191.6907895 | SAIFI 1.14943609 |
| Total Minutes/Frequency | 551311.00 | 4924.0000 | 203959.00 | 1223.0000 |
| Equipment Fault | 42.25% | 24.90% | 5.14% | 12.10% |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% |
| Small Animal | 35.12% | 21.99% | 94.42% | 87.00% |
| Squirrel | 0.02% | 0.06% | 0.00% | 0.00% |
| Resolving Control of the Control of | 270220 | (U.S. 1204)2-04 | | 1920 123 124 24 24 24 |

| Equipment Fault | 42.25% | 24.90% | 5.14% | 12.10% |
|-----------------|--------|--------|--------|--------|
| Wind | 0.00% | 0.00% | 0.00% | 0.00% |
| Small Animal | 35.12% | 21.99% | 94.42% | 87.00% |
| Squirrel | 0.02% | 0.06% | 0.00% | 0.00% |
| Unknown Cause | 0.50% | 1.08% | 0.38% | 0.82% |
| Deterioration | 2.27% | 4.45% | 0.00% | 0.00% |
| Scheduled | 0.57% | 4.57% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 19.28% | 42.95% | 0.06% | 0.08% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 0.00% | 0.00% | 0.00% | 0.00% |
| Lightning | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - Non ROW | 0.00% | 0.00% | 0.00% | 0.00% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |

100%

100%

100%

100%

Corrections to be made:

No corrections necessary at this time.

Substation Name and Number **Substation Location**

Circuit Name and Number

Circuit Location

Total Circuit Length (Miles)

2019 Member Count

5 Year Average Member Count

Date of Last Trim

Date of Next Trim

FOUR_OAKS

33

4255 Hwy. 27 South, Falmouth, KY 41040

FOUR OAKS

104

Broadford

40.5

216

212

November-17

2023

5 Year Average

2019

SAIDI 108.3396038

SAIFI 0.733742942 96.96759259

SAIDI

SAIFI 0.861111111

| | | | I CHARLESTON CONTRACTOR | AN ASSAULT OF THE PARTY OF THE |
|-------------------------|-----------|----------|-------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Total Minutes/Frequency | 114579.00 | 776.0000 | 20945.00 | 186.0000 |
| Equipment Fault | 19.75% | 25.52% | 4.70% | 20.43% |
| Wind | 15.66% | 7.47% | 0.00% | 0.00% |
| Small Animal | 3.79% | 6.31% | 1.42% | 1.08% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 4.13% | 4.51% | 16.26% | 10.22% |
| Deterioration | 13.99% | 8.38% | 0.00% | 0.00% |
| Scheduled | 0.06% | 0.13% | 0.31% | 0.54% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 1.17% | 2.19% | 0.00% | 0.00% |
| Ice/Snow | 0.11% | 0.52% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 6.23% | 4.77% | 34.09% | 19.89% |
| Tree - ROW | 8.48% | 11.47% | 32.64% | 28.49% |
| Lightning | 9.08% | 15.85% | 0.88% | 0.54% |
| Tree - Non ROW | 17.56% | 12.89% | 9.69% | 18.82% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number FOUR_OAKS 33 4255 Hwy. 27 South, Falmouth, KY 41040 Substation Location Circuit Name and Number FOUR OAKS Morgan Circuit Location 85.7 Total Circuit Length (Miles) 2019 Member Count 974 954 5 Year Average Member Count October-16 Date of Last Trim Date of Next Trim 2022

| | 5 Year | 5 Year Average | | 2019 | |
|-------------------------|-------------|----------------|-------------|-------------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 186.1155072 | 1.479779911 | 310.5770021 | 1.784394251 | |
| Total Minutes/Frequency | 887576.00 | 7057.0000 | 302502.00 | 1738.0000 | |
| Equipment Fault | 7.17% | 9.58% | 5.30% | 6.73% | |
| Wind | 2.21% | 3.36% | 0.35% | 1.04% | |
| Small Animal | 2.06% | 3.83% | 1.94% | 3.62% | |
| Squirrel | 0.02% | 0.06% | 0.00% | 0.00% | |
| Unknown Cause | 1.44% | 3.13% | 0.30% | 0.58% | |
| Deterioration | 31.98% | 19.57% | 75.56% | 58.06% | |
| Scheduled | 2.44% | 4.69% | 1.84% | 5.12% | |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% | |
| Bird | 0.56% | 0.44% | 0.00% | 0.00% | |
| Overload | 1.44% | 2.17% | 1.55% | 4.89% | |
| Public Accident | 8.68% | 6.43% | 2.17% | 2.82% | |
| Ice/Snow | 0.66% | 0.50% | 0.00% | 0.00% | |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% | |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - ROW | 0.02% | 0.03% | 0.00% | 0.00% | |
| Lightning | 7.73% | 10.05% | 9.06% | 15.82% | |
| Tree - Non ROW | 33.50% | 35.92% | 1.92% | 1.32% | |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.09% | 0.26% | 0.00% | 0.00% | |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:

Substation Name and Number
Substation Location
Circuit Name and Number
Circuit Location
Total Circuit Length (Miles)
2019 Member Count
5 Year Average Member Count
Date of Last Trim

Date of Next Trim

FOUR_OAKS 33 4255 Hwy. 27 South, Falmouth, KY 41040 FOUR_OAKS 124

> Sunrise 137.1 766 750 November-17 2023

| | 5 Year | Average | 20 | 019 |
|-------------------------|-------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 99.77866132 | 0.672971306 | 122.7088773 | 0.852480418 |
| Total Minutes/Frequency | 374223.00 | 2524.0000 | 93995.00 | 653.0000 |
| Equipment Fault | 3.81% | 4.71% | 0.39% | 0.31% |
| Wind | 2.79% | 4.52% | 6.86% | 12.86% |
| Small Animal | 6.87% | 15.10% | 1.37% | 6.74% |
| Squirrel | 0.03% | 0.12% | 0.00% | 0.00% |
| Unknown Cause | 2.28% | 3.53% | 0.03% | 0.15% |
| Deterioration | 22.05% | 16.92% | 30.50% | 17.15% |
| Scheduled | 2.79% | 4.36% | 10.81% | 15.16% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 11.12% | 9.47% | 4.38% | 3.37% |
| Ice/Snow | 6.30% | 3.41% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 2.99% | 3.76% | 0.00% | 0.00% |
| Lightning | 8.25% | 9.35% | 7.50% | 6.74% |
| Tree - Non ROW | 30.71% | 24.76% | 38.15% | 37.52% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

FOUR_OAKS Substation Name and Number 33 4255 Hwy. 27 South, Falmouth, KY 41040 Substation Location Circuit Name and Number FOUR_OAKS Circuit Location Hammer Total Circuit Length (Miles) 4.0 20 2019 Member Count 20 5 Year Average Member Count Date of Last Trim August-16 Date of Next Trim 2022

| | 5 Year | Average | 2019 | |
|-------------------------|-------------|-------------|---------|---------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 56.25728165 | 0.980341085 | 123.9 | 2.5 |
| Total Minutes/Frequency | 5509.00 | 96.0000 | 2478.00 | 50.0000 |
| Equipment Fault | 35.72% | 42.71% | 79.42% | 82.00% |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% |
| Small Animal | 12.63% | 15.63% | 6.78% | 12.00% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 0.00% | 0.00% | 0.00% | 0.00% |
| Deterioration | 0.00% | 0.00% | 0.00% | 0.00% |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 23.45% | 19.79% | 0.00% | 0.00% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 0.00% | 0.00% | 0.00% | 0.00% |
| Lightning | 20.57% | 14.58% | 13.80% | 6.00% |
| Free - Non ROW | 7.62% | 7.29% | 0.00% | 0.00% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number **HEADQUARTERS** 36 2195 Saltwell Hedquarters, Rd., Carlisle, KY 40311 **Substation Location** Circuit Name and Number 104 **HEADQUARTERS** V3-1 US 68 Circuit Location 9.7 Total Circuit Length (Miles) 2019 Member Count 71 5 Year Average Member Count 70 Date of Last Trim June-16 Date of Next Trim 2022

| | 5 Year | 5 Year Average | | 2019 | |
|-------------------------|-------------|----------------|-------------|-------------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 42.38135306 | 0.621000644 | 51.28169014 | 0.492957746 | |
| Total Minutes/Frequency | 14929.57 | 218.7583 | 3641.00 | 35.0000 | |
| Equipment Fault | 1.15% | 0.46% | 0.00% | 0.00% | |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% | |
| Small Animal | 18.04% | 15.09% | 5.05% | 5.71% | |
| Squirrel | 8.14% | 6.86% | 0.00% | 0.00% | |
| Unknown Cause | 15.02% | 14.17% | 0.00% | 0.00% | |
| Deterioration | 0.00% | 0.00% | 0.00% | 0.00% | |
| Scheduled | 0.26% | 1.37% | 0.00% | 0.00% | |
| Power Supplier | 9.80% | 34.17% | 0.00% | 0.00% | |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% | |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% | |
| Public Accident | 0.00% | 0.00% | 0.00% | 0.00% | |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% | |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% | |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - ROW | 1.13% | 2.29% | 4.64% | 14.29% | |
| Lightning | 46.46% | 25.60% | 90.30% | 80.00% | |
| Tree - Non ROW | 0.00% | 0.00% | 0.00% | 0.00% | |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% | |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:

Substation Name and Number **Substation Location** Circuit Name and Number Circuit Location Total Circuit Length (Miles) 2019 Member Count 5 Year Average Member Count Date of Last Trim Date of Next Trim

HEADQUARTERS 2195 Saltwell Hedquarters, Rd., Carlisle, KY 40311 **HEADQUARTERS** Arthur Road

114

36

29.2 159 158 July-17 2023

| | 5 Year Average | | 2019 | |
|-------------------------|----------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 266.5863719 | 1.298549097 | 537.3144654 | 1.635220126 |
| Total Minutes/Frequency | 210304.81 | 1024.4001 | 85433.00 | 260.0000 |
| Equipment Fault | 21.66% | 22.65% | 23.49% | 46.92% |
| Wind | 28.31% | 10.45% | 69.45% | 39.62% |
| Small Animal | 0.70% | 2.64% | 0.17% | 0.77% |
| Squirrel | 0.03% | 0.20% | 0.00% | 0.00% |
| Unknown Cause | 0.94% | 2.64% | 0.00% | 0.00% |
| Deterioration | 4.96% | 8.30% | 0.00% | 0.00% |
| Scheduled | 0.19% | 0.49% | 0.00% | 0.00% |
| Power Supplier | 3.06% | 14.97% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 4.49% | 5.95% | 0.00% | 0.00% |
| Public Accident | 1.59% | 1.85% | 0.00% | 0.00% |
| Ice/Snow . | 0.16% | 0.10% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.17% | 0.39% | 0.00% | 0.00% |
| Tree - ROW | 0.78% | 1.37% | 0.00% | 0.00% |
| Lightning | 27.67% | 22.26% | 6.89% | 12.69% |
| Tree - Non ROW | 5.29% | 5.76% | 0.00% | 0.00% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |

100%

100%

100%

100%

Corrections to be made:

Substation Name and Number

Substation Location

Circuit Name and Number

Circuit Location

Total Circuit Length (Miles)

2019 Member Count

5 Year Average Member Count

Date of Last Trim

Date of Next Trim

HEADQUARTERS

36

2195 Saltwell Hedquarters, Rd., Carlisle, KY 40311

HEADQUARTERS

144

Kentontown

121.0

718

712

December-19

2025

5 Year Average

2019

SAIDI

SAIFI 288.3899815 1.939994275 679.4721448 4.540389972

SAIDI

SAIFI

| Total Minutes/Frequency | 1027350.75 | 6910.9702 | 487861.00 | 3260.0000 |
|-------------------------|------------|-----------|-----------|-----------|
| Equipment Fault | 42.29% | 41.92% | 27.22% | 52.39% |
| Wind | 1.69% | 1.82% | 0.00% | 0.00% |
| Small Animal | 4.72% | 7.60% | 0.20% | 0.74% |
| Squirrel | 0.34% | 0.42% | 0.00% | 0.00% |
| Unknown Cause | 0.24% | 0.49% | 0.00% | 0.00% |
| Deterioration | 0.43% | 0.78% | 0.00% | 0.00% |
| Scheduled | 0.42% | 1.71% | 0.22% | 1.01% |
| Power Supplier | 2.73% | 9.67% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 7.64% | 7.94% | 11.28% | 10.31% |
| Ice/Snow | 1.21% | 1.30% | 0.00% | 0.00% |
| Fire | 0.01% | 0.01% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 2.15% | 2.91% | 0.00% | 0.00% |
| Lightning | 5.05% | 4.04% | 1.29% | 0.89% |
| Free - Non ROW | 31.09% | 19.39% | 59.79% | 34.66% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

No corrections necessary at this time.

Substation Name and Number HICKORY PLAINS 9 1075 Old US 25, Berea, KY 40403 **Substation Location** Circuit Name and Number HICKORY PLAINS Circuit Location Old US 25 Total Circuit Length (Miles) 18.7 2019 Member Count 305 5 Year Average Member Count 294 Date of Last Trim May-18 Date of Next Trim 2024

| | 5 Year | Average | 20 | 2019 | |
|-------------------------|-------------|-------------|-------------|-------------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 25.25359655 | 0.387377218 | 36.43278689 | 0.485245902 | |
| Total Minutes/Frequency | 37159.00 | 570.0000 | 11112.00 | 148.0000 | |
| Equipment Fault | 4.72% | 3.51% | 11.34% | 6.08% | |
| Wind | 0.06% | 0.18% | 0.20% | 0.68% | |
| Small Animal | 16.73% | 19.82% | 11.09% | 20.95% | |
| Squirrel | 0.14% | 0.18% | 0.00% | 0.00% | |
| Unknown Cause | 5.62% | 5.44% | 14.65% | 13.51% | |
| Deterioration | 44.56% | 46.32% | 0.00% | 0.00% | |
| Scheduled . | 0.00% | 0.00% | 0.00% | 0.00% | |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% | |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% | |
| Overload | 1.11% | 0.70% | 0.00% | 0.00% | |
| Public Accident | 5.67% | 10.18% | 18.97% | 39.19% | |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% | |
| Fire | 1.11% | 0.53% | 0.00% | 0.00% | |
| Sag/Clearance | 2.10% | 1.93% | 0.00% | 0.00% | |
| Γree - ROW | 0.44% | 0.35% | 1.48% | 1.35% | |
| Lightning | 3.69% | 4.04% | 0.00% | 0.00% | |
| Γree - Non ROW | 14.03% | 6.84% | 42.28% | 18.24% | |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% | |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:

No corrections necessary at this time.

Substation Name and Number

Substation Location

Circuit Name and Number

Circuit Location

Total Circuit Length (Miles)

2019 Member Count

5 Year Average Member Count

Date of Last Trim

Date of Next Trim

HICKORY PLAINS

1075 Old US 25, Berea, KY 40403

HICKORY PLAINS

Silver Creek/Rainbow Sub

24.2

728

702

December-14

2020

5 Year Average

2019

SAIDI 84.61213315

SAIFI 0.949277693 158.4711538 1.767857143

SAIDI

SAIFI

| Total Minutes/Frequency | 297170.00 | 3334.0000 | 115367.00 | 1287.0000 |
|-------------------------|-----------|-----------|-----------|-----------|
| Equipment Fault | 7.88% | 6.93% | 1.97% | 1.79% |
| Wind | 11.63% | 6.39% | 29.38% | 15.31% |
| Small Animal | 9.30% | 15.99% | 4.59% | 9.01% |
| Squirrel | 0.11% | 0.15% | 0.00% | 0.00% |
| Unknown Cause | 0.31% | 0.45% | 0.00% | 0.00% |
| Deterioration | 1.96% | 2.76% | 4.91% | 6.99% |
| Scheduled | 1.81% | 2.22% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.01% | 0.03% | 0.00% | 0.00% |
| Public Accident | 18.08% | 21.18% | 0.00% | 0.00% |
| Ice/Snow | 11.74% | 6.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 7.51% | 8.04% | 6.20% | 9.40% |
| Lightning | 2.86% | 2.31% | 2.80% | 1.32% |
| Tree - Non ROW | 26.79% | 27.56% | 50.14% | 56.18% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number

Substation Location

Circuit Name and Number

HICK

Circuit Location

Total Circuit Length (Miles)

2019 Member Count

5 Year Average Member Count

Date of Last Trim

Date of Next Trim

HICKORY PLAINS 9
1075 Old US 25, Berea, KY 40403
HICKORY PLAINS 154
North-City of Berea

12.8 454 438 May-18 2024

| | 5 Year Average | | 2019 | |
|-------------------------|----------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 78.04167472 | 0.869300942 | 132,9251101 | 1.405286344 |
| Total Minutes/Frequency | 170932.00 | 1904.0000 | 60348.00 | 638.0000 |
| Equipment Fault | 2.85% | 2.26% | 0.53% | 0.47% |
| Wind | 26.18% | 29.36% | 69.11% | 76.65% |
| Small Animal | 6.58% | 11.08% | 0.13% | 0.63% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 4.40% | 5.62% | 0.63% | 0.78% |
| Deterioration | 1.80% | 1.89% | 0.00% | 0.00% |
| Scheduled | 1.77% | 2.00% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.18% | 1.58% | 0.50% | 4.70% |
| Public Accident | 6.06% | 3.62% | 17.15% | 10.82% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 12.11% | 9.09% | 10.96% | 5.49% |
| Lightning | 26.94% | 23.58% | 0.00% | 0.00% |
| Tree - Non ROW | 10.61% | 8.09% | 0.99% | 0.47% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.53% | 1.84% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number

Substation Location

Circuit Name and Number

Circuit Location

Total Circuit Length (Miles)

2019 Member Count

5 Year Average Member Count

Date of Last Trim

Date of Next Trim

HOLLOWAY

2

6447 Harrodsburg Rd., Nicholasville, KY 40356

HOLLOWAY

124

Clear Creek/Murphy's Lane

37.9

351

344

March-17

2023

| | 5 Year | Average | 20 | 019 |
|-------------------------|-------------|-------------|------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 74.47472046 | 0.719343215 | 30.2962963 | 1.284900285 |
| Total Minutes/Frequency | 127965.00 | 1236.0000 | 10634.00 | 451.0000 |
| Equipment Fault | 2.61% | 2.99% | 9.57% | 2.88% |
| Wind | 0.05% | 0.08% | 0.00% | 0.00% |
| Small Animal | 3.32% | 5.50% | 6.31% | 2.00% |
| Squirrel | 0.14% | 0.16% | 0.00% | 0.00% |
| Unknown Cause | 0.54% | 0.73% | 6.44% | 2.00% |
| Deterioration | 0.44% | 0.49% | 1.27% | 0.22% |
| Scheduled | 2.85% | 10.19% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 3.33% | 3.40% | 0.00% | 0.00% |
| Public Accident | 4.26% | 32.52% | 50.82% | 88.91% |
| Ice/Snow | 0.19% | 0.08% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 4.23% | 2.02% | 2.26% | 0.44% |
| Lightning | 15.50% | 9.47% | 3.19% | 0.67% |
| Tree - Non ROW | 62.52% | 32.20% | 20.14% | 2.88% |
| Large Animal | 0.03% | 0.16% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Public Accident caused outages. No corrections necessary at this time.

Substation Name and Number **JACKSONVILLE** 39 1386 Russell Cave Rd., Cynthiana, KY 41031 Substation Location Circuit Name and Number **JACKSONVILLE** Broadwell Circuit Location Total Circuit Length (Miles) 25.1 154 2019 Member Count 5 Year Average Member Count 156 April-14 Date of Last Trim Date of Next Trim 2021

| | 5 Year Average | | 2019 | |
|-------------------------|----------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 83.07655959 | 0.768752073 | 110.5844156 | 0.798701299 |
| Total Minutes/Frequency | 64732.00 | 599.0000 | 17030.00 | 123.0000 |
| Equipment Fault | 14.39% | 13.86% | 0.00% | 0.00% |
| Wind | 1.21% | 1.00% | 4.62% | 4.88% |
| Small Animal | 2.58% | 4.51% | 0.12% | 0.81% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 0.34% | 0.67% | 0.00% | 0.00% |
| Deterioration | 0.17% | 0.67% | 0.00% | 0.00% |
| Scheduled | 1.56% | 5.84% | 0.00% | 0.00% |
| Power Supplier | 1.58% | 6.34% | 0.00% | 0.00% |
| Bird | 0.18% | 0.33% | 0.00% | 0.00% |
| Overload | 0.10% | 0.17% | 0.37% | 0.81% |
| Public Accident | 19.02% | 21.20% | 29.91% | 39.02% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Γree - ROW | 13.60% | 7.85% | 50.80% | 37.40% |
| Lightning | 20.38% | 23.87% | 14.18% | 17.07% |
| Free - Non ROW | 24.57% | 13.02% | 0.00% | 0.00% |
| Large Animal | 0.32% | 0.67% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number

Substation Location

Circuit Name and Number

Circuit Location

Total Circuit Length (Miles)

2019 Member Count

5 Year Average Member Count

Date of Last Trim

Date of Next Trim

JACKSONVILLE

39

1386 Russell Cave Rd., Cynthiana, KY 41031

JACKSONVILLE

114

Bourbon Acres

91.8

646

654

August-13

2020

| | 5 Year | Average | 2019 | |
|-------------------------|-------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 60.88427257 | 0.525312791 | 66.87616099 | 0.569659443 |
| Total Minutes/Frequency | 199002.00 | 1717.0000 | 43202.00 | 368.0000 |
| Equipment Fault | 26.20% | 25.74% | 5.58% | 4.89% |
| Wind | 2.36% | 2.68% | 3.70% | 4.62% |
| Small Animal | 4.54% | 8.68% | 0.94% | 2.99% |
| Squirrel | 0.73% | 0.99% | 0.00% | 0.00% |
| Unknown Cause | 20.30% | 16.54% | 17.33% | 14.13% |
| Deterioration | 0.74% | 2.39% | 0.83% | 2.17% |
| Scheduled | 2.90% | 6.81% | 9.06% | 18.75% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.80% | 0.87% | 0.00% | 0.00% |
| Overload | 0.07% | 0.12% | 0.00% | 0.00% |
| Public Accident | 1.49% | 3.55% | 1.45% | 1.36% |
| Ice/Snow | 0.11% | 0.35% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 1.23% | 1.63% | 0.00% | 0.00% |
| Tree - ROW | 22.09% | 15.43% | 12.32% | 14.13% |
| Lightning | 4.74% | 6.70% | 9.50% | 15.49% |
| Tree - Non ROW | 11.38% | 6.93% | 39.28% | 21.47% |
| Large Animal | 0.32% | 0.58% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

No corrections necessary at this time.

Substation Name and Number **JACKSONVILLE** 39 **Substation Location** 1386 Russell Cave Rd., Cynthiana, KY 41031 Circuit Name and Number **JACKSONVILLE** Silas Circuit Location Total Circuit Length (Miles) 26.7 206 2019 Member Count 208 5 Year Average Member Count Date of Last Trim November-19 2025 Date of Next Trim

| | 5 Year | Average | 2019 | |
|-------------------------|-------------|------------|------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 85.86988193 | 0.83854121 | 156.407767 | 1.791262136 |
| Total Minutes/Frequency | 89501.00 | 874.0000 | 32220.00 | 369.0000 |
| Equipment Fault | 28.04% | 34.44% | 56.88% | 59.08% |
| Wind | 13.86% | 13.27% | 27.03% | 17.62% |
| Small Animal | 8.23% | 10.18% | 1.17% | 3.52% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 7.10% | 10.64% | 0.00% | 0.00% |
| Deterioration | 14.22% | 9.61% | 2.07% | 1.36% |
| Scheduled | 0.79% | 1.72% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 0.00% | 0.00% | 0.00% | 0.00% |
| Ice/Snow | 0.36% | 0.23% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 0.96% | 0.57% | 0.84% | 0.81% |
| Lightning | 8.10% | 8.58% | 10.20% | 12.20% |
| Tree - Non ROW | 17.69% | 8.47% | 0.00% | 0.00% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.65% | 2.29% | 1.80% | 5.42% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number LEES LICK 34 HWY 1842, Cynthiana, KY 41031 Substation Location Circuit Name and Number LEES_LICK White Oak Circuit Location 62.0 Total Circuit Length (Miles) 2019 Member Count 452 466 5 Year Average Member Count Date of Last Trim November-16 2022 Date of Next Trim

| | 5 Year | Average | 2019 | |
|-------------------------|-------------|-------------|-------------|------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 115.5989812 | 1.132701927 | 307.5154867 | 1.89380531 |
| Total Minutes/Frequency | 269296.82 | 2638.7173 | 138997.00 | 856.0000 |
| Equipment Fault | 38.84% | 18.23% | 72.52% | 52.57% |
| Wind | 13.67% | 12.47% | 0.00% | 0.00% |
| Small Animal | 5.48% | 7.12% | 0.72% | 1.99% |
| Squirrel | 1.47% | 1.52% | 0.00% | 0.00% |
| Unknown Cause | 2.77% | 3.75% | 1.87% | 4.91% |
| Deterioration | 0.24% | 0.34% | 0.00% | 0.00% |
| Scheduled | 0.40% | 0.42% | 0.15% | 0.23% |
| Power Supplier | 13.14% | 32.62% | 0.00% | 0.00% |
| Bird | 0.57% | 0.72% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 1.27% | 1.74% | 0.00% | 0.00% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.03% | 0.04% | 0.00% | 0.00% |
| Tree - ROW | 1.32% | 1.74% | 0.00% | 0.00% |
| Lightning | 3.57% | 4.81% | 0.49% | 0.82% |
| Tree - Non ROW | 17.24% | 14.48% | 24.25% | 39.49% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

MERCER_CO 25
754 Industrial Park Drive, Harrodsburg, KY 40330
MERCER_CO 104

Mercer Co. Schools
2.1
20
20
January-16
2021

| | 5 Year | 5 Year Average | | 2019 | |
|-------------------------|-------------|----------------|---------|---------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 41.97362319 | 0.60557971 | 108.9 | 1.85 | |
| Total Minutes/Frequency | 4228.00 | 61.0000 | 2178.00 | 37.0000 | |
| Equipment Fault | 0.00% | 0.00% | 0.00% | 0.00% | |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% | |
| Small Animal | 41.49% | 52.46% | 38.43% | 51.35% | |
| Squirrel | 6.43% | 13.11% | 0.00% | 0.00% | |
| Unknown Cause | 0.00% | 0.00% | 0.00% | 0.00% | |
| Deterioration | 0.00% | 0.00% | 0.00% | 0.00% | |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% | |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% | |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% | |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% | |
| Public Accident | 11.49% | 3.28% | 0.00% | 0.00% | |
| Ice/Snow | 8.87% | 1.64% | 0.00% | 0.00% | |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% | |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - ROW | 0.00% | 0.00% | 0.00% | 0.00% | |
| Lightning | 31.72% | 29.51% | 61.57% | 48.65% | |
| Tree - Non ROW | 0.00% | 0.00% | 0.00% | 0.00% | |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% | |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:

Storm related outages. No corrections necessary at this time.

MILLERSBURG 38 1024 Miller Station Rd., Carlisle, KY 40311 MILLERSBURG 114

Little Rock 88.6 475 470 March-14 2021

| | 5 Year | Average | 2019 | |
|-------------------------|-------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 169.7020275 | 1.289801559 | 256.7410526 | 1.458947368 |
| Total Minutes/Frequency | 398700.86 | 3030,2820 | 121952.00 | 693.0000 |
| Equipment Fault | 6.61% | 6.83% | 0.10% | 0.14% |
| Wind | 6.70% | 4.85% | 17.34% | 13.56% |
| Small Animal | 3.51% | 4.22% | 0.45% | 0.87% |
| Squirrel | 0.03% | 0.07% | 0.00% | 0.00% |
| Unknown Cause | 4.09% | 6.77% | 5.27% | 11.40% |
| Deterioration | 6.17% | 4.92% | 9.95% | 11.69% |
| Scheduled | 0.14% | 2.05% | 0.00% | 0.00% |
| Power Supplier | 11.02% | 30.20% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 7.15% | 5.94% | 10.76% | 7.94% |
| Ice/Snow | 15.62% | 7.16% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.59% | 1.25% | 0.00% | 0.00% |
| Tree - ROW | 8.74% | 6.50% | 10.74% | 11.83% |
| Lightning | 16.54% | 11.72% | 28.04% | 23.38% |
| Tree - Non ROW | 13.07% | 7.52% | 17.35% | 19.19% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Storm related outages. No corrections necessary at this time.

Substation Name and Number **NEWBY** 247 Maple Grove Rd., Richmond, KY 40475 Substation Location Circuit Name and Number **NEWBY** Circuit Location Shallow Ford Total Circuit Length (Miles) 14.7 149 2019 Member Count 5 Year Average Member Count 145 Date of Last Trim July-18 2024 Date of Next Trim

| | 5 Year | Average | 20 | 019 |
|-------------------------|-------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 151.9115971 | 1.322088786 | 218.4228188 | 1.241610738 |
| Total Minutes/Frequency | 109847.00 | 956.0000 | 32545.00 | 185.0000 |
| Equipment Fault | 42.30% | 32.11% | 95.43% | 82.70% |
| Wind | 1.10% | 0.31% | 0.00% | 0.00% |
| Small Animal | 3.85% | 7.53% | 3.71% | 16.22% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 0.12% | 0.21% | 0.00% | 0.00% |
| Deterioration | 0.33% | 0.21% | 0.00% | 0.00% |
| Scheduled | 0.07% | 0.21% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.04% | 0.10% | 0.00% | 0.00% |
| Public Accident | 6.59% | 10.15% | 0.00% | 0.00% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.11% | 0.10% | 0.00% | 0.00% |
| Tree - ROW | 4.17% | 6.59% | 0.00% | 0.00% |
| Lightning | 8.89% | 9.62% | 0.00% | 0.00% |
| Tree - Non ROW | 32.36% | 32.74% | 0.86% | 1.08% |
| Large Animal | 0.06% | 0.10% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number

Substation Location

Circuit Name and Number

Circuit Location

Total Circuit Length (Miles)

2019 Member Count

5 Year Average Member Count

Date of Last Trim

Date of Next Trim

NEWBY

7

247 Maple Grove Rd., Richmond, KY 40475

NEWBY

34

Tates Creek Rd

21.7

388

377

November-15

2021

| | 5 Year | 5 Year Average | | 019 |
|-------------------------|-------------|----------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 53.79860377 | 0.612331469 | 191.8221649 | 2.237113402 |
| Total Minutes/Frequency | 101301.00 | 1153.0000 | 74427.00 | 868.0000 |
| Equipment Fault | 2.61% | 2.60% | 1.45% | 0.81% |
| Wind | 2.97% | 2.86% | 1.37% | 1.84% |
| Small Animal | 8.47% | 11.54% | 1.29% | 2.19% |
| Squirrel | 1.24% | 1.47% | 0.00% | 0.00% |
| Unknown Cause | 1.27% | 1.73% | 0.00% | 0.00% |
| Deterioration | 2.14% | 1.91% | 0.72% | 0.58% |
| Scheduled | 0.03% | 0.09% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 0.11% | 0.09% | 0.00% | 0.00% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 7.84% | 5.90% | 8.27% | 5.88% |
| Lightning | 3.27% | 2.43% | 0.00% | 0.00% |
| Tree - Non ROW | 70.03% | 69.38% | 86.90% | 88.71% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |

0.00%

100%

0.00%

100%

0.00%

100%

0.00%

100%

Corrections to be made:

Flash Flood

Substation Name and Number

Substation Location

Circuit Name and Number

Circuit Location

Total Circuit Length (Miles)

2019 Member Count

5 Year Average Member Count

Date of Last Trim

Date of Next Trim

NEWBY

7

247 Maple Grove Rd., Richmond, KY 40475

NEWBY

144

Bears Den/Mule Shed Rd

57.7

619

601

September-18

2024

5 Year Average

2019

| S I car . | Average | 20 | 119 |
|-------------|-------------|-------------|-------------|
| SAIDI | SAIFI | SAIDI | SAIFI |
| 62.80134871 | 0.428427062 | 44.72213247 | 0.432956381 |

| Total Minutes/Frequency | 188656.00 | 1287.0000 | 27683.00 | 268.0000 |
|-------------------------|-----------|-----------|----------|----------|
| Equipment Fault | 7.28% | 9.48% | 32.70% | 31.72% |
| Wind | 0.42% | 0.62% | 0.00% | 0.00% |
| Small Animal | 12.40% | 20.82% | 45.54% | 40.67% |
| Squirrel | 0.03% | 0.47% | 0.00% | 0.00% |
| Unknown Cause | 3.02% | 5.21% | 7.01% | 7.46% |
| Deterioration | 2.04% | 1.40% | 0.00% | 0.00% |
| Scheduled | 0.52% | 2.10% | 2.28% | 9.33% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 1.11% | 2.18% | 0.00% | 0.00% |
| Public Accident | 1.09% | 2.10% | 2.23% | 4.10% |
| Ice/Snow | 0.04% | 0.08% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 4.02% | 4.66% | 0.00% | 0.00% |
| Lightning | 9.65% | 13.52% | 0.00% | 0.00% |
| Tree - Non ROW | 8.80% | 9.63% | 10.25% | 6.72% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.02% | 0.08% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 49.57% | 27.66% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number **NEWBY** 247 Maple Grove Rd., Richmond, KY 40475 **Substation Location** Circuit Name and Number **NEWBY** 154 Circuit Location Jiggwate 30.0 Total Circuit Length (Miles) 217 2019 Member Count 211 5 Year Average Member Count October-15 Date of Last Trim 2021 Date of Next Trim

| | 5 Year | 5 Year Average | | 2019 | |
|-------------------------|-------------|----------------|-------------|-------------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 127.9580775 | 0.598232238 | 329.3456221 | 1.050691244 | |
| Total Minutes/Frequency | 134753.00 | 630.0000 | 71468.00 | 228.0000 | |
| Equipment Fault | 47.18% | 25.40% | 87.35% | 64.91% | |
| Wind | 4.73% | 3.17% | 0.03% | 1.75% | |
| Small Animal | 10.88% | 24.76% | 4.33% | 10.53% | |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% | |
| Unknown Cause | 6.46% | 15.71% | 4.16% | 11.84% | |
| Deterioration | 0.16% | 0.16% | 0.00% | 0.00% | |
| Scheduled | 0.13% | 0.16% | 0.00% | 0.00% | |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% | |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% | |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% | |
| Public Accident | 19.77% | 9.68% | 0.00% | 0.00% | |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% | |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% | |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - ROW | 2.82% | 5.08% | 4.13% | 10.96% | |
| Lightning | 6.17% | 12.86% | 0.00% | 0.00% | |
| Tree - Non ROW | 1.42% | 2.38% | 0.00% | 0.00% | |
| Large Animal | 0.19% | 0.48% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.07% | 0.16% | 0.00% | 0.00% | |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:

Date of Last Trim Date of Next Trim NICHOLASVILLE

1049 Bethany Rd., Nicholasville, KY 40356

NICHOLASVILLE

14

Mackey Pike/McLane

20.2

233 217

January-18

2024

| | 5 Year | Average | 20 |)19 |
|-------------------------|-------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 65.40608382 | 1.067387104 | 61.88841202 | 1.394849785 |
| Total Minutes/Frequency | 70836.00 | 1156.0000 | 14420.00 | 325.0000 |
| Equipment Fault | 8.99% | 4.24% | 0.00% | 0.00% |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% |
| Small Animal | 42.09% | 67.65% | 66.62% | 74.46% |
| Squirrel | 1.04% | 1.73% | 5.13% | 6.15% |
| Unknown Cause | 1.84% | 2.77% | 3.05% | 6.15% |
| Deterioration | 0.46% | 0.26% | 1.56% | 0.31% |
| Scheduled | 0.08% | 0.26% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.21% | 0.35% | 0.61% | 0.62% |
| Overload | 0.27% | 0.35% | 0.00% | 0.00% |
| Public Accident | 0.85% | 0.35% | 4.17% | 1.23% |
| Ice/Snow | 1.12% | 0.69% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 8.14% | 3.89% | 7.10% | 4.00% |
| Lightning | 7.72% | 5.54% | 0.00% | 0.00% |
| Tree - Non ROW | 26.60% | 11.59% | 11.76% | 7.08% |
| Large Animal | 0.58% | 0.35% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number
Substation Location
Circuit Name and Number
Circuit Location

Total Circuit Length (Miles) 2019 Member Count

5 Year Average Member Count

Date of Last Trim Date of Next Trim **NICHOLASVILLE**

1

1049 Bethany Rd., Nicholasville, KY 40356

NICHOLASVILLE

134

Bethany/US 27

11.3

144

134

February-19

2025

| | 5 Year | Average | 20 | 019 |
|-------------------------|-------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 32.88645418 | 0.394422311 | 51.01388889 | 0.569444444 |
| Total Minutes/Frequency | 22012.00 | 264.0000 | 7346.00 | 82.0000 |
| Equipment Fault | 6.32% | 4.17% | 0.87% | 2.44% |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% |
| Small Animal | 15.27% | 14.02% | 29.50% | 13.41% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 17.17% | 19.32% | 51.46% | 62.20% |
| Deterioration | 1.53% | 0.76% | 0.00% | 0.00% |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 1.37% | 2.65% | 4.10% | 8.54% |
| Overload | 3.16% | 4.55% | 0.00% | 0.00% |
| Public Accident | 0.00% | 0.00% | 0.00% | 0.00% |
| Ice/Snow | 0.78% | 0.38% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 35.01% | 37.12% | 14.08% | 13.41% |
| Lightning | 17.51% | 14.77% | 0.00% | 0.00% |
| Tree - Non ROW | 1.88% | 2.27% | 0.00% | 0.00% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

NICHOLASVILLE 1049 Bethany Rd., Nicholasville, KY 40356 NICHOLASVILLE 144

Country
4.4
24
22
November-14
2020

| | 5 Year | 5 Year Average | | 2019 | |
|-------------------------|-------------|----------------|-------------|---------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 106.0368526 | 0.690239044 | 393.7083333 | 1.125 | |
| Total Minutes/Frequency | 11829.00 | 77.0000 | 9449.00 | 27.0000 | |
| Equipment Fault | 0.63% | 3.90% | 0.79% | 11.11% | |
| Wind | 1.24% | 3.90% | 0.00% | 0.00% | |
| Small Animal | 9.05% | 42.86% | 0.00% | 0.00% | |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% | |
| Unknown Cause | 0.96% | 1.30% | 0.00% | 0.00% | |
| Deterioration | 2.97% | 3.90% | 0.00% | 0.00% | |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% | |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% | |
| Bird | 0.54% | 1.30% | 0.00% | 0.00% | |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% | |
| Public Accident | 0.00% | 0.00% | 0.00% | 0.00% | |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% | |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% | |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - ROW | 79.68% | 32.47% | 99.21% | 88.89% | |
| Lightning | 4.93% | 10.39% | 0.00% | 0.00% | |
| Tree - Non ROW | 0.00% | 0.00% | 0.00% | 0.00% | |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% | |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:

Circuit to be trimmed in 2020.

Total Minutes/Frequency

Equipment Fault

Small Animal Squirrel

Sag/Clearance
Tree - ROW
Lightning
Tree - Non ROW
Large Animal
Vandalism
Contractor

Flash Flood

Unknown Cause
Deterioration
Scheduled
Power Supplier

Wind

Bird
Overload
Public Accident
Ice/Snow
Fire

NORTH MADISON

15

2064 Jacks Creek Pike, Richmond KY 40475

NORTH MADISON

104

Shiloh Point 12.1 200 195 August-15

2021

| 5 Year | Average | 20 | 19 |
|-------------|-------------|----------|---------|
| SAIDI | SAIFI | SAIDI | SAIFI |
| 26.39132702 | 0.144489287 | 61.465 | 0.27 |
| 25754.00 | 141.0000 | 12293.00 | 54.0000 |
| 47.05% | 54.61% | 35.53% | 44.44% |
| 29.41% | 17.73% | 61.62% | 46.30% |
| 0.15% | 0.71% | 0.00% | 0.00% |
| 0.00% | 0.00% | 0.00% | 0.00% |
| 0.35% | 0.71% | 0.00% | 0.00% |
| 19.08% | 19.15% | 0.00% | 0.00% |
| 0.00% | 0.00% | 0.00% | 0.00% |
| 0.00% | 0.00% | 0.00% | 0.00% |
| 0.00% | 0.00% | 0.00% | 0.00% |
| 0.00% | 0.00% | 0.00% | 0.00% |
| 0.00% | 0.00% | 0.00% | 0.00% |
| 0.00% | 0.00% | 0.00% | 0.00% |
| 0.00% | 0.00% | 0.00% | 0.00% |
| 0.00% | 0.00% | 0.00% | 0.00% |
| 0.00% | 0.00% | 0.00% | 0.00% |
| 2.61% | 3.55% | 0.00% | 0.00% |
| 1.36% | 3.55% | 2.85% | 9.26% |
| 0.00% | 0.00% | 0.00% | 0.00% |
| 0.00% | 0.00% | 0.00% | 0.00% |

0.00%

0.00%

100%

0.00%

0.00%

100%

0.00%

0.00%

100%

0.00%

0.00%

100%

Corrections to be made:

Storm related outages. No corrections necessary at this time.

NORTH MADISON

15

2064 Jacks Creek Pike, Richmond KY 40475

NORTH MADISON

134

Stringtown 31.1 252 246

November-16

2022

| | 5 Year | 5 Year Average | | 019 |
|-------------------------|------------|----------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 82.4685255 | 0.466829061 | 110.6706349 | 0.638888889 |
| Total Minutes/Frequency | 101401.00 | 574.0000 | 27889.00 | 161.0000 |
| Equipment Fault | 2.11% | 2.96% | 2.67% | 3.11% |
| Wind | 0.34% | 0.35% | 0.82% | 0.62% |
| Small Animal | 5.25% | 10.10% | 0.00% | 0.00% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 4.72% | 5.75% | 14.79% | 15.53% |
| Deterioration | 3.20% | 4.70% | 0.00% | 0.00% |
| Scheduled | 0.44% | 2.09% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 0.18% | 0.35% | 0.00% | 0.00% |
| Ice/Snow | 1.18% | 0.70% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 4.73% | 6.27% | 0.90% | 1.86% |
| Lightning | 0.14% | 1.39% | 0.00% | 0.00% |
| Tree - Non ROW | 22.63% | 22.47% | 80.81% | 78.88% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 55.07% | 42.86% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number **OXFORD** 40 3466 Cynthiana Rd., Georgetown, KY 40324 Substation Location Circuit Name and Number **OXFORD** Circuit Location Carrick 39.5 Total Circuit Length (Miles) 357 2019 Member Count 307 5 Year Average Member Count December-19 Date of Last Trim 2025 Date of Next Trim

| | 5 Year | Average | 2019 | |
|-------------------------|-------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 306.2523263 | 2.141234415 | 309.2829132 | 2.557422969 |
| Total Minutes/Frequency | 470810.69 | 3291.7825 | 110414.00 | 913.0000 |
| Equipment Fault | 41.61% | 30.68% | 10.88% | 10.84% |
| Wind | 0.04% | 0.03% | 0.00% | 0.00% |
| Small Animal | 0.69% | 1.09% | 1.89% | 2.30% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 0.54% | 0.94% | 0.00% | 0.00% |
| Deterioration | 1.21% | 1.76% | 0.00% | 0.00% |
| Scheduled | 0.59% | 3.77% | 0.46% | 7.23% |
| Power Supplier | 20.80% | 30.19% | 33.89% | 38.66% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 0.12% | 0.36% | 0.00% | 0.00% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 2.51% | 3.04% | 0.00% | 0.00% |
| Lightning | 17.73% | 17.77% | 52.73% | 40.85% |
| Tree - Non ROW | 14.16% | 10.36% | 0.14% | 0.11% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number **OXFORD** 40 3466 Cynthiana Rd., Georgetown, KY 40324 **Substation Location** Circuit Name and Number **OXFORD** Finnell Circuit Location Total Circuit Length (Miles) 20.7 2019 Member Count 180 5 Year Average Member Count 155 Date of Last Trim December-19 Date of Next Trim 2025

| | 5 Year Average | | 2019 | |
|-------------------------|----------------|-------------|----------|----------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 127.0602631 | 1.207986693 | 166.1 | 1.6 |
| Total Minutes/Frequency | 98487.46 | 936.3395 | 29898.00 | 288.0000 |
| Equipment Fault | 9.98% | 10.57% | 11.33% | 18.06% |
| Wind | 4.33% | 0.96% | 14.18% | 2.78% |
| Small Animal | 6.91% | 12.60% | 4.32% | 11.11% |
| Squirrel | 0.56% | 1.07% | 0.00% | 0.00% |
| Unknown Cause | 0.99% | 1,92% | 0.00% | 0.00% |
| Deterioration | 0.00% | 0.00% | 0.00% | 0.00% |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% |
| Power Supplier | 51.91% | 55.14% | 65.26% | 62.15% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.07% | 0.11% | 0.00% | 0.00% |
| Public Accident | 0.04% | 0.11% | 0.00% | 0.00% |
| Ice/Snow | 1.29% | 2.56% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Гree - ROW | 0.12% | 0.21% | 0.25% | 0.35% |
| Lightning | 4.92% | 3.95% | 0.76% | 0.69% |
| Tree - Non ROW | 18.89% | 10.79% | 3.90% | 4.86% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

| Substation Name and Number | OXFORD | 40 |
|------------------------------|---------------------------|------------------|
| Substation Location | 3466 Cynthiana Rd., Georg | getown, KY 40324 |
| Circuit Name and Number | OXFORD | 134 |
| Circuit Location | BCTC | |
| Total Circuit Length (Miles) | 31.8 | |
| 2019 Member Count | 307 | |
| 5 Year Average Member Count | 264 | |
| Date of Last Trim | August-1 | 6 |
| Date of Next Trim | 2022 | |

| | 5 Year | 5 Year Average | | 019 |
|-------------------------|------------|----------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 138.259179 | 1.149758192 | 355.7687296 | 2.654723127 |
| Total Minutes/Frequency | 182781.00 | 1520.0000 | 109221.00 | 815.0000 |
| Equipment Fault | 0.25% | 0.26% | 0.15% | 0.12% |
| Wind | 40.79% | 37.11% | 50.93% | 49.82% |
| Small Animal | 4.13% | 8.42% | 0.95% | 2.33% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 0.52% | 0.72% | 0.87% | 1.35% |
| Deterioration | 0.00% | 0.00% | 0.00% | 0.00% |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% |
| Power Supplier | 35.76% | 38.95% | 29.29% | 36.69% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 0.00% | 0.00% | 0.00% | 0.00% |
| Ice/Snow | 0.20% | 0.13% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 4.24% | 4.93% | 3.35% | 3.80% |
| Lightning | 1.21% | 0.72% | 0.00% | 0.00% |
| Tree - Non ROW | 12.90% | 8.75% | 14.46% | 5.89% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

<u>Corrections to be made:</u> Storm related outages. No corrections necessary at this time.

POWELL TAYLOR 28 1024 Powell Taylor Rd., Lawrenceburg, KY 40342 POWELL TAYLOR 114

> Birdie Rd 57.8 384 376 November-17 2023

| | 5 Year | Average | 20 | 019 |
|-------------------------|-------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 263.8106292 | 1.671173502 | 374.3828125 | 1.768229167 |
| Total Minutes/Frequency | 495521.00 | 3139.0000 | 143763.00 | 679.0000 |
| Equipment Fault | 2.57% | 2.99% | 3.09% | 5.74% |
| Wind | 18.50% | 14.59% | 0.14% | 0.15% |
| Small Animal | 1.68% | 2.87% | 0.53% | 5.30% |
| Squirrel | 0.08% | 0.19% | 0.00% | 0.00% |
| Unknown Cause | 0.86% | 1.27% | 2.52% | 3.98% |
| Deterioration | 0.04% | 0.16% | 0.02% | 0.29% |
| Scheduled | 0.48% | 2.36% | 0.22% | 1.03% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 0.39% | 0.86% | 0.00% | 0.00% |
| Ice/Snow | 10.09% | 4.49% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 3.57% | 7.65% | 2.48% | 3.98% |
| Lightning | 6.33% | 11.98% | 0.41% | 0.44% |
| Tree - Non ROW | 54.27% | 46.80% | 90.59% | 79.09% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 1.14% | 3.79% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number POWELL TAYLOR 28 Substation Location 1024 Powell Taylor Rd., Lawrenceburg, KY 40342 Circuit Name and Number POWELL TAYLOR Puckett Rd Circuit Location 34.1 Total Circuit Length (Miles) 341 2019 Member Count 334 5 Year Average Member Count Date of Last Trim March-18 Date of Next Trim 2024

| | 5 Year | Average | 2019 | |
|-------------------------|-------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| € | 102.6470197 | 0.874106993 | 91.18181818 | 1.134897361 |
| Total Minutes/Frequency | 171214.00 | 1458.0000 | 31093.00 | 387.0000 |
| Equipment Fault | 30.46% | 35.80% | 16.20% | 20.67% |
| Wind | 8.03% | 13.24% | 18.43% | 24.03% |
| Small Animal | 6.22% | 5.56% | 1.05% | 3.36% |
| Squirrel | 2.14% | 2.74% | 11.30% | 9.56% |
| Unknown Cause | 0.59% | 1.30% | 0.00% | 0.00% |
| Deterioration | 0.73% | 3.70% | 2.13% | 10.08% |
| Scheduled | 0.24% | 2.19% | 0.78% | 7.75% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.05% | 0.21% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 0.64% | 0.89% | 0.00% | 0.00% |
| Ice/Snow | 3.60% | 4.18% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 0.10% | 0.27% | 0.40% | 0.78% |
| Lightning | 8.17% | 7.27% | 1.12% | 0.52% |
| Tree - Non ROW | 39.03% | 22.63% | 48.59% | 23.26% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

SINAI 23 Hwy 62, Lawrenceburg, KY 40342 SINAI 114 Buntain School Rd/Birdie 27.8

27.8 209 204 June-17 2023

| | 5 Year | Average | 2019 | |
|-------------------------|-------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 81.50743055 | 1.278921289 | 72.44976077 | 1.296650718 |
| Total Minutes/Frequency | 83016.11 | 1302.5937 | 15142.00 | 271.0000 |
| Equipment Fault | 0.75% | 0.54% | 2.80% | 1.11% |
| Wind | 1.47% | 1.92% | 6.97% | 8.86% |
| Small Animal | 17.61% | 18.42% | 67.80% | 54.24% |
| Squirrel | 3.36% | 6.76% | 18.06% | 32.10% |
| Unknown Cause | 3.13% | 3.61% | 0.00% | 0.00% |
| Deterioration | 0.35% | 0.46% | 1.40% | 1.48% |
| Scheduled | 1.19% | 1.00% | 0.00% | 0.00% |
| Power Supplier | 62.07% | 61.46% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 0.00% | 0.00% | 0.00% | 0.00% |
| Ice/Snow | 1.02% | 0.46% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 3.00% | 0.92% | 0.00% | 0.00% |
| Lightning | 3.16% | 2.00% | 2.48% | 1.48% |
| Tree - Non ROW | 2.74% | 2.15% | 0.49% | 0.74% |
| Large Animal | 0.12% | 0.23% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.04% | 0.08% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

| Substation Name and Number | SINAI 23 |
|------------------------------|--------------------------------|
| Substation Location | Hwy 62, Lawrenceburg, KY 40342 |
| Circuit Name and Number | SINAI 154 |
| Circuit Location | Glensboro |
| Total Circuit Length (Miles) | 57.3 |
| 2019 Member Count | 382 |
| 5 Year Average Member Count | 372 |
| Date of Last Trim | June-19 |
| Date of Next Trim | 2025 |

| | 5 Year | Average | 2019 | |
|-------------------------|------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 181.389188 | 1.848014158 | 195.8376963 | 1.748691099 |
| Total Minutes/Frequency | 337670.91 | 3440.2305 | 74810.00 | 668.0000 |
| Equipment Fault | 5.61% | 3.87% | 0.08% | 0.15% |
| Wind | 9.67% | 4.04% | 0.11% | 0.15% |
| Small Animal | 3.83% | 4.21% | 11.03% | 11.68% |
| Squirrel | 0.13% | 0.20% | 0.00% | 0.00% |
| Unknown Cause | 1.63% | 2.01% | 0.00% | 0.00% |
| Deterioration | 0.27% | 0.44% | 0.10% | 0.15% |
| Scheduled | 9.66% | 8.20% | 40.66% | 26.80% |
| Power Supplier | 27.28% | 42.13% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.02% | 0.06% | 0.00% | 0.00% |
| Public Accident | 3.49% | 4.53% | 2.97% | 4.49% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 0.16% | 0.15% | 0.00% | 0.00% |
| Lightning | 1.57% | 0.70% | 0.18% | 0.15% |
| Tree - Non ROW | 36.69% | 29.47% | 44.87% | 56.44% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

<u>Corrections to be made:</u> No corrections necessary at this time.

Substation Name and Number

Substation Location

Circuit Name and Number

Circuit Location

Total Circuit Length (Miles)

2019 Member Count

5 Year Average Member Count

Date of Last Trim

Date of Next Trim

SOUTH ELKHORN

12

3251 Keene Rd., Nicholasville, KY 40356

SOUTH ELKHORN

104

Firebrook/Dogwood Trace

21.3

1080

1068

October-19

2023

| | 5 Year | Average | 2019 | |
|-------------------------|-------------|-------------|-------------|------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 44.90120326 | 0.780464125 | 50.59166667 | 1.09537037 |
| Total Minutes/Frequency | 239807.72 | 4168.2919 | 54639.00 | 1183.0000 |
| Equipment Fault | 14.38% | 27.23% | 7.69% | 3.30% |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% |
| Small Animal | 4.60% | 3.67% | 4.88% | 3.13% |
| Squirrel | 0.58% | 0.67% | 0.18% | 0.25% |
| Unknown Cause | 0.00% | 0.00% | 0.00% | 0.00% |
| Deterioration | 0.25% | 0.22% | 0.00% | 0.00% |
| Scheduled | 0.23% | 0.36% | 0.00% | 0.00% |
| Power Supplier | 21.06% | 25.77% | 0.00% | 0.00% |
| Bird | 0.41% | 0.43% | 0.00% | 0.00% |
| Overload | 0.38% | 0.12% | 0.00% | 0.00% |
| Public Accident | 25.29% | 10.63% | 0.00% | 0.00% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 11.36% | 4.27% | 4.17% | 1.94% |
| Lightning | 2.54% | 0.70% | 0.00% | 0.00% |
| Tree - Non ROW | 18.93% | 25.93% | 83.09% | 91.38% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number SOUTH ELKHORN 3251 Keene Rd., Nicholasville, KY 40356 **Substation Location** Circuit Name and Number SOUTH ELKHORN Champions Circuit Location 29.9 Total Circuit Length (Miles) 419 2019 Member Count 5 Year Average Member Count 414 December-15 Date of Last Trim 2021 Date of Next Trim

12

124

| | 5 Year Average | | 2019 | |
|-------------------------|----------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 41.84984133 | 0.491121551 | 54.21718377 | 0.568019093 |
| Total Minutes/Frequency | 86714.01 | 1017.6172 | 22717.00 | 238.0000 |
| Equipment Fault | 27.21% | 22.01% | 84.63% | 78.57% |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% |
| Small Animal | 5.55% | 8.94% | 5.36% | 8.40% |
| Squirrel | 1.93% | 3.14% | 0.00% | 0.00% |
| Unknown Cause | 4.37% | 5.11% | 0.20% | 1.26% |
| Deterioration | 2.53% | 1.28% | 0.00% | 0.00% |
| Scheduled | 0.60% | 0.49% | 0.00% | 0.00% |
| Power Supplier | 21.71% | 39.37% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 1.33% | 1.28% | 0.00% | 0.00% |
| Public Accident | 1.01% | 0.59% | 0.00% | 0.00% |
| Ice/Snow | 2.11% | 0.39% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 9.29% | 9.34% | 9.67% | 10.92% |
| Lightning | 6.38% | 2.95% | 0.14% | 0.84% |
| Tree - Non ROW | 15.97% | 5.11% | 0.00% | 0.00% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

SOUTH JESSAMINE

14

1307 Chrisman Mill Rd., Nicholasville, KY 40356

SOUTH JESSAMINE

104

John Watts Drive

4.3

24

23

December-16

2022

| | 5 Year | Average | 2019 | |
|-------------------------|------------|------------|-------------|--------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 7.76751003 | 0.05242414 | 26,20833333 | 0.125 |
| Total Minutes/Frequency | 889.00 | 6.0000 | 629.00 | 3.0000 |
| Equipment Fault | 0.00% | 0.00% | 0.00% | 0.00% |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% |
| Small Animal | 11.47% | 16.67% | 0.00% | 0.00% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 0.00% | 0.00% | 0.00% | 0.00% |
| Deterioration | 0.00% | 0.00% | 0.00% | 0.00% |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird · | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 7.31% | 16.67% | 0.00% | 0.00% |
| Public Accident | 0.00% | 0.00% | 0.00% | 0.00% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 6.41% | 16.67% | 9.06% | 33.33% |
| Lightning | 64.34% | 33.33% | 90.94% | 66.67% |
| Tree - Non ROW | 10.46% | 16.67% | 0.00% | 0.00% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Storm related outages. No corrections necessary at this time.

Substation Name and Number

Substation Location

Circuit Name and Number

Circuit Location

Total Circuit Length (Miles)

2019 Member Count

5 Year Average Member Count

Date of Last Trim

Date of Next Trim

SOUTH JESSAMINE

14

1307 Chrisman Mill Rd., Nicholasville, KY 40356

SOUTH JESSAMINE

114

Southbrook

24.9

897

856

August-16

2022

5 Year Average

2019

SAIDI 88.66424028 **SAIFI**

SAIDI

SAIFI 0.997753526 169.6176143 1.824972129

| Total Minutes/Frequency | 379271.00 | 4268.0000 | 152147.00 | 1637.0000 |
|-------------------------|-----------|-----------|-----------|-----------|
| Equipment Fault | 20.13% | 19.35% | 45.74% | 42.82% |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% |
| Small Animal | 5.67% | 7.05% | 0.14% | 0.24% |
| Squirrel | 4.91% | 5.04% | 0.00% | 0.00% |
| Unknown Cause | 0.12% | 0.73% | 0.28% | 1.83% |
| Deterioration | 0.43% | 0.61% | 0.00% | 0.00% |
| Scheduled | 0.07% | 0.21% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.01% | 0.02% | 0.02% | 0.06% |
| Overload | 0.10% | 0.14% | 0.00% | 0.00% |
| Public Accident | 17.53% | 23.69% | 0.00% | 0.00% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 0.33% | 0.66% | 0.07% | 0.67% |
| Lightning | 1.37% | 1.29% | 0.06% | 0.12% |
| Tree - Non ROW | 21.54% | 20.81% | 53.70% | 54.25% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 27.79% | 20.41% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

SOUTH JESSAMINE

14

1307 Chrisman Mill Rd., Nicholasville, KY 40356

SOUTH JESSAMINE

124

Sulpher Well

60.2

609

581

June-17

2023

| | 5 Year | 5 Year Average | |)19 |
|-------------------------|-------------|----------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 180.1617109 | 1.704085828 | 507.1789819 | 6.093596059 |
| | | | | |
| Total Minutes/Frequency | 523225.00 | 4949.0000 | 308872.00 | 3711.0000 |
| Equipment Fault | 10.18% | 5.50% | 0.03% | 0.03% |
| Wind | 14.47% | 3.82% | 0.00% | 0.00% |
| Small Animal | 19.72% | 23.60% | 32.25% | 29.88% |
| Squirrel | 0.56% | 1.05% | 0.00% | 0.00% |
| Unknown Cause | 0.83% | 1.01% | 1.27% | 1.24% |
| Deterioration | 1.30% | 1.05% | 0.00% | 0.00% |
| Scheduled | 0.90% | 1.11% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 10.63% | 17.30% | 17.99% | 23.04% |
| Overload | 0.04% | 0.08% | 0.00% | 0.00% |
| Public Accident | 13.40% | 15.54% | 16.44% | 16.44% |
| Ice/Snow | 0.38% | 0.22% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 12.01% | 9.74% | 19.44% | 12.02% |
| Lightning | 11.82% | 17.68% | 11.94% | 16.36% |
| Tree - Non ROW | 3.69% | 2.26% | 0.65% | 1.00% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.06% | 0.04% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number SOUTH JESSAMINE **Substation Location** 1307 Chrisman Mill Rd., Nicholasville, KY 40356 Circuit Name and Number SOUTH JESSAMINE Circuit Location **Industrial Park** Total Circuit Length (Miles) 4.5 29 2019 Member Count 5 Year Average Member Count 28 Date of Last Trim December-16 Date of Next Trim 2022

144

| | 5 Year Average | | 2 | 2019 | |
|-------------------------|----------------|-------------|---------|-------------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 19.05346318 | 0.282005717 | 67 | 1.034482759 | |
| Total Minutes/Frequency | 2635.00 | 39.0000 | 1943.00 | 30,0000 | |
| Equipment Fault | 4.14% | 2.56% | 0.00% | 0.00% | |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% | |
| Small Animal | 4.67% | 5.13% | 6.33% | 6.67% | |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% | |
| Unknown Cause | 3.30% | 5.13% | 0.00% | 0.00% | |
| Deterioration | 0.00% | 0.00% | 0.00% | 0.00% | |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% | |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% | |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% | |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% | |
| Public Accident | 14.46% | 10.26% | 0.00% | 0.00% | |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% | |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% | |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - ROW | 1.86% | 2.56% | 0.00% | 0.00% | |
| Lightning | 2.50% | 2.56% | 0.00% | 0.00% | |
| Tree - Non ROW | 69.07% | 71.79% | 93.67% | 93.33% | |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% | |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:

Substation Name and Number Substation Location Circuit Name and Number Circuit Location

Total Circuit Length (Miles) 2019 Member Count

5 Year Average Member Count

Date of Last Trim Date of Next Trim VAN_ARSDELL

24

104 Bardstown Rd., Harrodsburg, KY 40330

VAN_ARSDELL

114

Shakertown/Mcafee Ln

127.4

936

916

December-14

2020

| | 5 Year | Average | 20 | 2019 | |
|-------------------------|-----------|-------------|-------------|-------------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 73,105543 | 0.779196123 | 67.54487179 | 0.870726496 | |
| Total Minutes/Frequency | 334756.00 | 3568.0000 | 63222.00 | 815.0000 | |
| Equipment Fault | 4.47% | 4.62% | 2.33% | 2.21% | |
| Wind | 25.50% | 6.92% | 4.30% | 3.80% | |
| Small Animal | 11.57% | 13.14% | 15.71% | 12.02% | |
| Squirrel | 4.73% | 3.25% | 4.83% | 5.77% | |
| Unknown Cause | 1.45% | 1.49% | 0.78% | 0.49% | |
| Deterioration | 1.16% | 1.60% | 0.00% | 0.00% | |
| Scheduled | 3.05% | 25.48% | 0.00% | 0.00% | |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% | |
| Bird | 0.31% | 0.50% | 0.23% | 0.12% | |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% | |
| Public Accident | 4.32% | 4.23% | 9.47% | 4.29% | |
| Ice/Snow | 0.77% | 0.20% | 0.00% | 0.00% | |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% | |
| Sag/Clearance | 0.17% | 0.17% | 0.00% | 0.00% | |
| Tree - ROW | 7.50% | 10.03% | 27.83% | 31.17% | |
| Lightning | 10.30% | 12.61% | 22.88% | 28.71% | |
| Tree - Non ROW | 23.81% | 14.27% | 10.81% | 9.45% | |
| Large Animal | 0.32% | 0.36% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.39% | 0.67% | 0.00% | 0.00% | |
| Flash Flood | 0.16% | 0.45% | 0.84% | 1.96% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:

Circuit to be trimmed in 2020.

VAN_ARSDELL 24 104 Bardstown Rd., Harrodsburg, KY 40330 VAN_ARSDELL 144

Kirkwood 88.7 628 614 March-15 2021

| | 5 Year | Average | 20 | 019 |
|-------------------------|-------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 133.2121413 | 0.879149486 | 145.5907643 | 0.910828025 |
| Total Minutes/Frequency | 409266.00 | 2701.0000 | 91431.00 | 572.0000 |
| Equipment Fault | 37.76% | 31.73% | 71.64% | 61.01% |
| Wind | 22.19% | 21.29% | 12.75% | 8.22% |
| Small Animal | 1.75% | 5.26% | 3.29% | 11.54% |
| Squirrel | 0.03% | 0.11% | 0.00% | 0.00% |
| Unknown Cause | 2.26% | 4.07% | 1.40% | 3.15% |
| Deterioration | 2.40% | 2.89% | 9.42% | 9.27% |
| Scheduled | 0.03% | 0.04% | 0.00% | 0.00% |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.01% | 0.04% | 0.00% | 0.00% |
| Public Accident | 4.05% | 6.37% | 0.00% | 0.00% |
| Ice/Snow | 4.18% | 1.85% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.45% | 1.22% | 0.00% | 0.00% |
| Tree - ROW | 1.92% | 4.96% | 0.80% | 2.97% |
| Lightning | 13.27% | 9.44% | 0.61% | 2.62% |
| Free - Non ROW | 9.68% | 10.70% | 0.09% | 1.22% |
| Large Animal | 0.01% | 0.04% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Date of Next Trim

WEST BEREA 8
5350 Walnutmeadow Rd., Berea, KY 40403
WEST BEREA 114

Days Inn/Berea Sewer
4.4
139
137
December-16
2022

| | 5 Year A | Average | 20 | 2019 | |
|-------------------------|-------------|-----------|-------------|-------------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 28.32010426 | 0.3777771 | 106.5035971 | 1.381294964 | |
| Total Minutes/Frequency | 19341.00 | 258.0000 | 14804.00 | 192.0000 | |
| Equipment Fault | 78.52% | 75.97% | 100.00% | 100.00% | |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% | |
| Small Animal | 21.48% | 24.03% | 0.00% | 0.00% | |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% | |
| Unknown Cause | 0.00% | 0.00% | 0.00% | 0.00% | |
| Deterioration | 0.00% | 0.00% | 0.00% | 0.00% | |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% | |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% | |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% | |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% | |
| Public Accident | 0.00% | 0.00% | 0.00% | 0.00% | |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% | |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% | |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - ROW | 0.00% | 0.00% | 0.00% | 0.00% | |
| Lightning | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - Non ROW | 0.00% | 0.00% | 0.00% | 0.00% | |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% | |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:

WEST BEREA 8
5350 Walnutmeadow Rd., Berea, KY 40403
WEST BEREA 144

Walnut Meadow 46.0 235 231 September-15 2021

| | 5 Year | Average | 20 | 2019 | |
|-------------------------|-------------|------------|-------------|-------------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 116.9645444 | 0.69113956 | 347.6893617 | 1.604255319 | |
| Total Minutes/Frequency | 135049.00 | 798.0000 | 81707.00 | 377.0000 | |
| Equipment Fault | 44.74% | 43.36% | 34.08% | 25.73% | |
| Wind | 2.23% | 2.76% | 0.35% | 0.27% | |
| Small Animal | 4.44% | 9.27% | 2.03% | 5.04% | |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% | |
| Unknown Cause | 1.37% | 2.26% | 2.27% | 4.77% | |
| Deterioration | 2.08% | 3.01% | 0.00% | 0.00% | |
| Scheduled | 0.07% | 0.13% | 0.00% | 0.00% | |
| Power Supplier | 0.00% | 0.00% | 0.00% | 0.00% | |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% | |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% | |
| Public Accident | 36.72% | 29.20% | 60.55% | 61.54% | |
| Ice/Snow | 1.50% | 0.88% | 0.00% | 0.00% | |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% | |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - ROW | 2.13% | 2.51% | 0.00% | 0.00% | |
| Lightning | 2.88% | 4.64% | 0.72% | 2.65% | |
| Tree - Non ROW | 1.83% | 2.01% | 0.00% | 0.00% | |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% | |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:

Public Accident caused outages. No corrections necessary at this time.

Substation Name and Number WEST NICHOLASVILLE **Substation Location** 398 Bass Pond Glen Dr., Nicholasville, KY 40356 Circuit Name and Number WEST NICHOLASVILLE 124 Circuit Location Shun Pike Total Circuit Length (Miles) 48.5 433 2019 Member Count 427 5 Year Average Member Count April-15 Date of Last Trim Date of Next Trim 2021

| | 5 Year | 5 Year Average | | 2019 | |
|-------------------------|-------------|----------------|-------------|-------------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 183.9772171 | 1.511340599 | 378.0300231 | 3.233256351 | |
| Total Minutes/Frequency | 392709.82 | 3226.0424 | 163687.00 | 1400.0000 | |
| Equipment Fault | 23.93% | 15.68% | 56.08% | 34.50% | |
| Wind | 0.12% | 0.34% | 0.00% | 0.00% | |
| Small Animal | 7.32% | 19.50% | 2.30% | 8.14% | |
| Squirrel | 0.32% | 0.71% | 0.02% | 0.14% | |
| Unknown Cause | 0.27% | 0.81% | 0.26% | 1.07% | |
| Deterioration | 0.04% | 0.09% | 0.00% | 0.00% | |
| Scheduled | 0.27% | 0.50% | 0.00% | 0.00% | |
| Power Supplier | 8.68% | 13.21% | 20.82% | 30.43% | |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% | |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% | |
| Public Accident | 10.37% | 12.12% | 6.10% | 11.71% | |
| Ice/Snow | 3.00% | 2.94% | 0.00% | 0.00% | |
| Fire | 0.09% | 0.09% | 0.00% | 0.00% | |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - ROW | 7.90% | 6.14% | 5.06% | 5.57% | |
| Lightning | 1.65% | 1.95% | 0.08% | 0.14% | |
| Tree - Non ROW | 36.04% | 25.91% | 9.28% | 8.29% | |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% | |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:

Date of Next Trim

WEST NICHOLASVILLE

3

398 Bass Pond Glen Dr., Nicholasville, KY 40356

WEST NICHOLASVILLE

134

Lone Oak/Clear Creek

46.8

1015

1001

May-17

2023

| | 5 Year | Average | 20 | 019 |
|-------------------------|-------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 84.93231092 | 1.271574951 | 246.0256158 | 4.113300493 |
| Total Minutes/Frequency | 424970.52 | 6362,5005 | 249716.00 | 4175.0000 |
| Equipment Fault | 33.64% | 25.89% | 25.41% | 24.57% |
| Wind | 0.14% | 0.06% | 0.00% | 0.00% |
| Small Animal | 12.57% | 18.48% | 1.31% | 1.34% |
| Squirrel | 0.45% | 0.57% | 0.00% | 0.00% |
| Unknown Cause | 0.82% | 1.02% | 0.53% | 0.62% |
| Deterioration | 0.16% | 0.08% | 0.00% | 0.00% |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% |
| Power Supplier | 42.28% | 47.51% | 71.95% | 72.41% |
| Bird | 0.02% | 0.03% | 0.00% | 0.00% |
| Overload | 1.27% | 1.57% | 0.00% | 0.00% |
| Public Accident | 0.20% | 0.19% | 0.11% | 0.05% |
| Ice/Snow | 0.16% | 0.03% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 1.88% | 0.97% | 0.00% | 0.00% |
| Lightning | 1.10% | 0.60% | 0.00% | 0.00% |
| Tree - Non ROW | 5.30% | 3.00% | 0.69% | 1.01% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

WEST NICHOLASVILLE

3

398 Bass Pond Glen Dr., Nicholasville, KY 40356

WEST NICHOLASVILLE

154

North Main St

8.6

691

681

November-16

2022

| | 5 Year | Average | 20 |)19 |
|-------------------------|-------------|-------------|-------------|-------------|
| | SAIDI | SAIFI | SAIDI | SAIFI |
| | 29.63798701 | 0.491871573 | 81.01013025 | 1.018813314 |
| Total Minutes/Frequency | 100959.36 | 1675.5199 | 55978.00 | 704.0000 |
| Equipment Fault | 1.83% | 1.49% | 0.28% | 0.28% |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% |
| Small Animal | 33.71% | 47.90% | 0.24% | 0.43% |
| Squirrel | 0.00% | 0.00% | 0.00% | 0.00% |
| Unknown Cause | 0.01% | 0.06% | 0.02% | 0.14% |
| Deterioration | 0.46% | 0.36% | 0.00% | 0.00% |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% |
| Power Supplier | 55.15% | 41.54% | 99.47% | 98.86% |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% |
| Public Accident | 0.24% | 0.06% | 0.00% | 0.00% |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% |
| Tree - ROW | 6.32% | 6.80% | 0.00% | 0.28% |
| Lightning | 2.28% | 1.79% | 0.00% | 0.00% |
| Tree - Non ROW | 0.00% | 0.00% | 0.00% | 0.00% |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% |
| | 100% | 100% | 100% | 100% |

Corrections to be made:

Substation Name and Number WEST NICHOLASVILLE 3 Substation Location 398 Bass Pond Glen Dr., Nicholasville, KY 40356 Circuit Name and Number WEST NICHOLASVILLE 164 Squire Lake Circuit Location Total Circuit Length (Miles) 6.3 2019 Member Count 457 5 Year Average Member Count 451 Date of Last Trim January-19 Date of Next Trim 2025

| | 5 Year | Average | 20 | 2019 | |
|-------------------------|-------------|-------------|-------------|-------------|--|
| | SAIDI | SAIFI | SAIDI | SAIFI | |
| | 42.90972769 | 0.630142257 | 79.54923414 | 0.991247265 | |
| Total Minutes/Frequency | 96670.01 | 1419.6282 | 36354.00 | 453.0000 | |
| Equipment Fault | 35.23% | 29.44% | 0.97% | 0.66% | |
| Wind | 0.00% | 0.00% | 0.00% | 0.00% | |
| Small Animal | 24.77% | 37.59% | 0.00% | 0.00% | |
| Squirrel | 0.12% | 0.21% | 0.00% | 0.00% | |
| Unknown Cause | 0.00% | 0.00% | 0.00% | 0.00% | |
| Deterioration | 0.00% | 0.00% | 0.00% | 0.00% | |
| Scheduled | 0.00% | 0.00% | 0.00% | 0.00% | |
| Power Supplier | 37.24% | 31.70% | 99.03% | 99.34% | |
| Bird | 0.00% | 0.00% | 0.00% | 0.00% | |
| Overload | 0.00% | 0.00% | 0.00% | 0.00% | |
| Public Accident | 0.00% | 0.00% | 0.00% | 0.00% | |
| Ice/Snow | 0.00% | 0.00% | 0.00% | 0.00% | |
| Fire | 0.00% | 0.00% | 0.00% | 0.00% | |
| Sag/Clearance | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - ROW | 0.00% | 0.00% | 0.00% | 0.00% | |
| Lightning | 0.00% | 0.00% | 0.00% | 0.00% | |
| Tree - Non ROW | 2.64% | 1.06% | 0.00% | 0.00% | |
| Large Animal | 0.00% | 0.00% | 0.00% | 0.00% | |
| Vandalism | 0.00% | 0.00% | 0.00% | 0.00% | |
| Contractor | 0.00% | 0.00% | 0.00% | 0.00% | |
| Flash Flood | 0.00% | 0.00% | 0.00% | 0.00% | |
| | 100% | 100% | 100% | 100% | |

Corrections to be made:



DISTRIBUTION RIGHT-OF-WAY VEGETATION MANAGEMENT 2020 PLAN/ 2019 PLAN REVIEW

March 2020

Blue Grass Energy Vegetation Management Plan

2019 Review of Plan Implementation

Blue Grass Energy developed a formal plan to manage the maintenance of vegetation on distribution rights-of-way (ROW) in 2007/2008. The plans goals were established to provide excellent member service, maintain current tree related reliability, and look for opportunities to increase production and reduce program cost. These plans were continued and improved into 2019.

As stated in the previously submitted Vegetation Management Plan, the plan may be modified from time-to-time based on performance as measured by tree-related service reliability and evaluations of member satisfaction with service reliability. Specific reliability metrics may include Tree SAIFI, trends in customer minutes interrupted by tree-related causes and tree-caused primary interruptions per 100 line miles as internal benchmarks of program performance over time. A Tree-Caused Outage Report summarizes these reliability criteria and is regularly reviewed and monitored daily. Upon reporting of tree related outages, a field investigation is conducted to determine the root cause.

2017-2020 Vegetation Management Strategy

SCHEDULED MAINTENANCE AND CLEARANCE

Blue Grass Energy provides electric service to over 57,000 members through a network of over 4,700 miles of distribution line. Blue Grass Energy uses a cyclic approach to preventive vegetation management of its electric distribution ROW. Different circuits or portions of circuits may be scheduled on different cycles based on site conditions, sensitivity of the line to interruptions caused by trees or criticality of the line. The maintenance cycle for tree removal, tree pruning or brush control may be the same or different for a given scheduling unit. Following pruning and clearance operations, herbicide application is conducted after one full growing season.

As illustrated in Table 1, Blue Grass Energy completed 17 out of 18 distribution circuits scheduled in 2019 for a total of 684 miles of distribution line completed. In 2020, there are 17 distribution circuits, for a total of 676 miles scheduled for completion. The varying site conditions determine the cost and cause completed miles to vary by year.

Table 1. Blue Grass Energy R/W Miles Scheduled vs. Completed - Trimming

| Maintenance Year | 2017 | 2018 | 2019 | 2020 |
|------------------|------|------|------|------|
| Scheduled | 736 | 658 | 756 | 676 |
| Completed | 736 | 658 | 684 | TBD |

Of the 2017 & 2018 maintenance year mileage, 21 circuits consisting of 697 miles were identified for selective herbicide application and completed in 2019. Herbicide application consisting of 979 miles from the 2018 & 2019 maintenance years are scheduled to be completed in 2020.

Table 2. Blue Grass Energy R/W Miles Scheduled vs. Completed - Herbicide

| Maintenance Year - Herbicide | 2017 | 2018 | 2019 | 2020 |
|------------------------------|------|------|------|------|
| Scheduled | 816 | 731 | 697 | 979 |
| Completed | 816 | 731 | 697 | TBD |

RELIABILITY

In 2008, Blue Grass Energy developed and implemented an outage investigation process to better understand the cause of tree failures. The data was again used in 2019 to identify species failure rates and help plan future scheduled and non-scheduled work to eliminate potential outages. The investigation of all tree related outages will continue through 2019 to collect data on major outage categories.

Historical Blue Grass Energy tree caused outages within the right of way are illustrated in Table 3.

Table 3. Number of Tree-Caused Outages within the ROW on the Blue Grass Energy System†

| Year | 2015 | 2016 | 2017 | 2018 | 2019 |
|--------|------|------|------|------|------|
| TOTALS | 77 | 86 | 110 | 142 | 150 |

†Outages on primary conductor excluding major event days

2019 VEGETATION MANAGEMENT PLAN REVIEW

No Changes were implemented in 2019 to the ROW management plan. The "Distribution Right-Of-Way Vegetation Management Plan" Dated April 2019 reiterated in detail the processes that were built into the plan.

In 2019, 684 trim miles out of 756 trim miles were completed 2019 calendar year. 72 trim miles were not completed due to weather delays. These miles were assigned to 2020 work and started in January. All 2019 herbicide miles were completed in 2019.

Listed below are some of the processes used in 2019:

- Continuation of Formal Contractor Evaluation Program. Each contractor will be rated on nine qualitative categories such as customer complaints, quarterly mileage goals, exceptions/ omissions, quality/standards, tools/equipment, unscheduled interruptions/OSHA LWD, contractor cooperation & communication, crew professionalism, and data accuracy.
- 2. Yearly Revision of formal program policies and procedures and assurance of consistent implementation throughout the system to include additional detailed requirements.
- 3. Continued yearly revision of a 5-6 year maintenance cycle for the system based on collected field data. In areas where standard clearances cannot be consistently achieved (e.g., subdivisions), mid cycle assessments will be conducted, and cycles adjusted based on those findings. Recommended cycle lengths are guidelines.

- 4. ISA Certified Arborist Utility Specialist supervisory personnel have adequate utility vegetation management technical expertise and a qualified ISA Certified Assistant Arborist is on staff.
- 5. Selective use of herbicides to control resprouting from the stumps of removed deciduous trees.
- 6. Continuation of formal herbicide spray program to control woody species following maintenance pruning.
- 7. Written notification of property owners of the intent to prune trees and requirement of written permission for "yard" tree removals. We always strive to not allow property owners to influence pruning clearances.
- 8. The crew labor and equipment complements were adjusted throughout the year to maximize cost effectiveness.
- 9. Revised and improved the formal work monitoring and completion process. Each circuit is 100 percent audited by ROW supervisory personnel to ensure specifications for clearance and quality are achieved.
- 10. Records were maintained of key aspects of the ROW vegetation management program to document program performance. This data provides information necessary for ongoing program management and circuit scheduling.
- 11. Meet requirements for Arbor Day Foundation Tree Line USA certification.

2020 VEGETATION MANAGEMENT PLAN

In addition to continuing the Distribution Right-Of-Way Vegetation Management Plans outlined for 2019 we intend to utilize the following key objectives in the upcoming year:

- > Continue Formal Crew Field Audit Evaluation process, at the 100 percent level
- > Continue to Uphold National Arbor Day Tree Line USA standards
- > Continue to uphold ANSI A300 pruning and Z133 safety standards
- > Utilization of vegetation management Best Management Practices as defined by the International Society of Arboriculture.
- Continue to evaluate and increase production and quality with established work force.
- > Further inspection and reduction of unnecessary reactive maintenance
- > Utilize multiple ROW vegetation maintenance contractors
- > Continue with formal herbicide spray program to control woody species following maintenance pruning.
- > Evaluate effectiveness of pilot program for using tree growth regulators (TGR) in urban area yard trees and continue use of TGR's in 2020.

Appendix

ROW VEGETATION MAINTENANCE CLEARANCE CYCLE SCHEDULING STRATEGY

The following table summarizes the Blue Grass Energy ROW vegetation maintenance scheduling strategy. Individual circuits may be accelerated or deferred based on assessment of field conditions and operating performance.

| Circuit Description | Primary Cycle Length (Years) | Mid-cycle Inspection/selective Tree Maintenance (Years) |
|--------------------------------|---------------------------------|---------------------------------------------------------------|
| Feeder Multi-phase | 5-6 | 2 to 3 |
| Feeder Laterals (single-phase) | 5-6 | |
| Industrial Circuits | 4-5 | Annual inspection and selective maintenance |