

SOUTH KENTUCKY R.E.C.C.
SOMERSET, KY.

APPENDIX A OF P.S.C. KY. NO. 4
Subdivision - 30 Lots

Underground Cost per foot	\$3.09
Overhead Cost per foot	<u>\$1.19</u>
Average Cost differential	<u>\$1.90</u>

UNDERGROUND

<u>Units</u>	<u>No. of Units</u>	<u>Unit Prices</u>			<u>Extended Price</u>		
		<u>Labor</u>	<u>Material</u>	<u>Labor & Mat.</u>	<u>Labor</u>	<u>Material</u>	<u>Lab. & Mat.</u>
1/OAI.15KV	3400'	\$0.365/ft.	\$0.40/ft.	\$0.765/ft.	\$1241.00	\$1360.00	\$2601.00
4/OTPX 600V	3000'	0.73/ft.	0.36/ft.	1.09	2190.00	1080.00	3270.00
25KVA Transf.	8	292.00	406.86	698.86	2336.00	3254.88	5590.88
Terminators	16	73.00	21.00	94.00	1168.00	336.00	1504.00
Parking Bush.	8	4.50	13.00	17.50	36.00	104.00	140.00
Conduit(PVC)	110'	0.65/ft.	1.60/ft.	2.25	71.50	176.00	247.50
Trench	6400'	1.00/ft.	---	1.00/ft.	6400.00	---	6400.00
TOTAL					<u>\$13,442.50</u>	<u>\$6,310.88</u>	<u>\$19,753.38</u>

\$3.09 per ft.

OVERHEAD

<u>Units</u>	<u>No. of Units</u>						
40-4	14	\$40.00	\$52.00	\$92.00	\$560.00	\$728.00	\$1288.00
A5	4	6.50	13.50	20.00	26.00	54.00	80.00
A1	12	3.00	6.00	9.00	36.00	72.00	108.00
E1-2	8	10.50	8.00	18.50	84.00	64.00	148.00
F1-2	8	13.00	7.50	20.50	104.00	60.00	164.00
15KVA	14	35.00	233.00	268.00	490.00	3262.00	3752.00
#2ACSR	6000'	57./m'	38./m'	95./m'	342.00	228.00	570.00
M2-2	14	7.75	5.75	13.50	108.50	80.50	189.00
K11	30	2.75	2.25	5.00	82.50	67.50	150.00
#2TPX	3000'	34./m'	200./m'	234./m'	102.00	600.00	702.00
TOTAL					<u>\$1,935.00</u>	<u>\$5,216.00</u>	<u>\$7,151.00</u>

\$1.19 per ft.

4-76

TYPICAL ROCK CLAUSE

An additional \$10 per linear trench foot shall be charged when rocky conditions are encountered, such conditions being defined as limestone or other hard stratified material in a continuous volume of at least one cubic yard or more which cannot be removed using ordinary excavation equipment.

CHECKED

PUBLIC SERVICE COMMISSION

JUN 27 1973

by *[Signature]*

DATE OF ISSUE June 1, 1973

DATE EFFECTIVE June 7, 1973

ISSUED BY Sam J. Hord Manager

P.O. Box 910 Somerset, Ky.

Sam J. Hord