So Ky RECC

Somerset, Kentucky 42501

APPENDIX A OF E.R.C. KENTUCKY NO. 5

A Sub-division of which 113 Lots are served Underground.
The line designed at 7.2 KV. Primary voltage, using loop feed.

Underground Cost per Foot	$6.15
Overhead Cost per Foot	-1.85
Average Cost Differential	$4.30

	FOOTAGE	MATERIAL	ESTIMATED: TRENCH, SAND, BACKFILL, BACKHOE	INITIAL LABOR & OVERHEAD	TOTAL COST
Job Totals	33,518	$69,035.81	$50,880.32	$86,476.44	$206,392.57
Cost per Foot		2.82	1.52	0.85 1.73 2.58	6.15

The Overhead Cost per Foot used here ($1.85 per Foot) was determined by taking an Average Cost of actual lines built into subdivisions typical of this, during the year 1979.

CHECKED
Energy Regulatory Commission
FEB 29 1980
by B Redmond
RATES AND TARIFFS

TYPICAL ROCK CLAUSE

An additional $35.00 per linear trench foot shall be charged where extreme rock conditions are encountered, such conditions being defined as limestone or other hard stratified material in a continous volume of at least one cubic yard or more which cannot be removed using ordinary excavation equipment.

C6-41

DATE ISSUED February 15, 1980 (Month Day Year) DATE EFFECTIVE February 1, 1980 (Month Day Year)

ISSUED BY [signature] (Name) Manager (Title) P.O. Box 910 Somerset, KY 42501 (Address)