

McCreary County Water District

For: All of McCreary County

CANCELLED

March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

P.S.C. Ky. No. 2

1st Revised Sheet No. 3

Cancelling P.S.C. Ky. No. 1

Original Sheet No. 3

RULES AND REGULATIONS

This schedule of Rules and Regulations governs the furnishing of water service by McCreary County Water District hereinafter referred to as the DISTRICT and applies to all service received from the DISTRICT. No employee or individual Commissioner of the DISTRICT is permitted to make an exception to Rates, Rules or Regulations. All Rules and Regulations are to be in effect so long as they are not in conflict with Public Service Commission Rules and Regulations. The DISTRICT is further subject to all Rules and Regulations of the Public Service Commission even though not contained herein.

1. Scope

This Schedule of Rules and Regulations is a part of all contracts for receiving water service from the DISTRICT, and applies to all service received from the DISTRICT whether the service is based upon contract, agreement, signed application, or otherwise. A copy of this schedule, together with a copy of the DISTRICT'S Schedule of Rates and Charges, shall be kept open to inspection at the office of the DISTRICT. The rules are promulgated under direction and authority granted pursuant to Chapter 13 of Kentucky Revised Statutes and Administrative Regulations 807 KAR 5 established via authority of Executive Order 81-126 dated March 4, 1981. The aforesaid rules and regulations are hereby adopted and included the same or herein written now or as may be legally changed from time to time.


2. Revisions

These Rules and Regulations may be revised, amended, supplemented, or otherwise changed from time to time by either of the two (2) following methods:

Date of Issue: September 10, 1987


Date of Issue: PUBLIC SERVICE COMMISSION, 1987
OF KENTUCKY

ISSUED BY: McCreary County Water District, P.O. Box 488, Whitley City, Kentucky 42653


R.D. Bryant, Chairman

APR 01 1987

PURSUANT TO 807 KAR 5:011,
SECTION 9 (1)

BY: 
PUBLIC SERVICE COMMISSION MANAGER

CANCELLED

March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

P.S.C. Ky. No. 2

Original Sheet No. 4

Cancelling P.S.C. Ky. No.

Sheet No.

RULES AND REGULATIONS

- A. By order of the Public Service Commission upon formal application by the DISTRICT, and after hearing as provided by commission regulation set forth in 807 KAR 5:011.
- B. By issuing and filing on at least thirty (30) days notice to the commission and the public all proposed changes in the Rules and Regulations, as provided by commission regulations set forth in 807 KAR 5:011.

3. Conflict

In case of conflict between any provisions of any rate schedule and the schedule of Rules and Regulations, the rate schedule shall apply. Also, should the rules contained herein conflict with the present rules in effect under 807 KAR 5 as of this date, same shall take precedence over those contained herein.


4. Application for Service

Any person, firm, agency or governmental entity within the current boundary of the DISTRICT may request service. Said request must be in writing on a form approved by the DISTRICT.

No service for a request shall be granted unless the property of said requestor has public access within a reasonable distance from an existing distribution main of the DISTRICT consistent with the topography of the area. Should the requestor desire to have the existing distribution system extended to serve them, same shall be accomplished as stipulated, hereafter.

Date of Issue: September 10, 1987 Date Effective: ~~September 10, 1987~~ **PUBLIC SERVICE COMMISSION**, 1987

ISSUED BY: McCreary County Water District, P.O. Box 488,
Whitley City, Kentucky 42653


R.D. Bryant, Chairman

APR 01 1987

PURSUANT TO 807 KAR 5:011,
SECTION 9 (1)

BY: 
PUBLIC SERVICE COMMISSION MANAGER

McCreary County Water District

For: All of McCreary County

CANCELLED

March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

P.S.C. Ky. No. 2

Original Sheet No. 5

Cancelling P.S.C. Ky. No.

Sheet No.

RULES AND REGULATIONS

Should DISTRICT determine that service to requestor is available, each prospective customer desiring water service shall be required to execute and sign the DISTRICT'S standard application for water service before service is supplied by the DISTRICT. A 5/8" X 3/4" meter shall be "the standard customer service meter and should be installed at all points of service unless the customer provides sufficient justification for the installation of a larger meter."

The DISTRICT shall provide for a standard connection (i.e., 5/8" x 3/4" meter) from the DISTRICT'S existing distribution main. An estension of fifty (50) feet or less shall be made by the DISTRICT to its existing utility main without change for a prospective customer who applies for and contracts to use the service for one (1) year or more with the appropriate guarantee.


5. Non-Standard Service

Each prospective customer requiring a non-standard service (i.e., other than a 5/8" X 3/4" meter) shall present to the DISTRICT sufficient justification for same. Insofar as prospective customer requirement may meet those non-standard service presently in effect by DISTRICT same may be applied. An extension of fifty (50) feet or less shall be made by the DISTRICT to its existing utility main without change for a prospective customer who applies for and contracts to use the service for one (1) year or more with the appropriate guarantee.

Date of Issue: September 10, 1987


Date Effective: April 1, 1987

ISSUED BY: McCreary County Water District, P.O. Box 488
Whitley City, Kentucky 42653 PUBLIC SERVICE COMMISSION
OF KENTUCKY


R.D. Bryant, Chairman

APR 01 1987

PURSUANT TO 807 KAR 5:011,
SECTION 9(1)

BY: 
PUBLIC SERVICE COMMISSION MANAGER

CANCELLED

March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

P.S.C. Ky. No. 2

Original Sheet No. 6

Cancelling P.S.C. Ky. No.

Sheet No.

RULES AND REGULATIONS

In addition, the prospective customer shall pay the cost of any special installation necessary to meet his particular requirements, as a contribution in aid of construction.

6. Point of Delivery

The point of delivery is the point where the meter or vault is located on the customer's premises. All water lines, plumbing, and equipment beyond the meter shall be installed and maintained by the customer. The DISTRICT reserves the right to determine the location of point of delivery with full regard to those wishes of the prospective customer, however the DISTRICT will in no event set a meter at a point that does not deliver 30 psig at the meter.

7. Customer's Service Line

All service lines beyond the metering point should be installed of material consisting of copper, galvanized, PVC pipe, or PE pipe with rating of not less than 200 psi. The size of service line beyond the point of delivery should not be less than 3/4".

Should a prospective customer desire a higher pressure due to his location or need, he may make provision, at his expense, for an individual pressure booster system. The manner of connection, location cross-connection protection and type is subject to approval by DISTRICT. The DISTRICT reserves the right to require discontinuance and disconnection should the private booster system have a detrimental effect on DISTRICT'S system.

PUBLIC SERVICE COMMISSION

Date of Issue: April 1, 1987 Date Effective: ~~KENTUCKY~~ APR 11 1, 1987
EFFECTIVE

ISSUED BY: McCreary County Water District, P.O. Box 488,
Whitley City, Kentucky 42653 APR 01 1987

R.D. Bryant
R.D. Bryant, Chairman

PURSUANT TO 807 KAR 5:011,
SECTION 9 (1)
BY: *George L. Lister*
PUBLIC SERVICE COMMISSION MANAGER

CANCELLED

P.S.C. Ky. No. 2

March 22, 2023

Original Sheet No. 7

Cancelling P.S.C. Ky. No.

Sheet No.

**KENTUCKY PUBLIC
SERVICE COMMISSION**

RULES AND REGULATIONS

8. Ownership of Mains, Services & Appurtenances

All mains, fire hydrants, valves, crossings and other appurtenances are and shall remain the property of the DISTRICT, whether installed directly by them or received through actions of a customer or extendor.

All service lines from main to meter with appurtenances shall be and remain the property of DISTRICT, whether installed directly by them or received through actions of a customer or extendor.

The customer shall install, own and maintain his service line from meter and/or point of delivery as defined here before.

9. Discontinuance of Service by DISTRICT

Water service may be discontinued by the DISTRICT for any violation of any rule, regulation, or condition, and especially for any of the following reasons.

- A. Misrepresentation in the application or contract as to the property or fixtures to be supplied or additional use to be made of water.
- B. Failure to report to the DISTRICT additions to the property or fixtures to be supplied or additional use to be made of water.
- C. Resale of water.

Date of Issue: September 10, 1987

Date Effective: **PUBLIC SERVICE COMMISSION
OF KENTUCKY** April 1, 1987
EFFECTIVE

ISSUED BY: McCreary County Water District, P.O. Box 488,
Whitley City, Kentucky 42653

APR 01 1987


R.D. Bryant Chairman

PURSUANT TO 807 KAR 5:011,
SECTION 9 (1)

BY: 
PUBLIC SERVICE COMMISSION MANAGER

AREA McCreary County, Kentucky

PSC KY NO. 1

4th Revised SHEET NO. 8

McCreary County Water District

CANCELLING PSC KY NO. 1

3rd Revised SHEET NO. 8

RULES AND REGULATIONS

D. Waste or misuse of water due to improper or imperfect service pipes and/or failure to keep such pipes in a suitable state of repair.

E. Tampering with meter, meter seal, service, or valves, or permitting such tampering by others.

F. Connection, cross-connection, or permitting the same, of any separate water supply to premises which receive water from the District.

G. Non-payment of bills for water service. (T)

H. The presence or existence of a dangerous condition on the customer's or applicant's premises that results from or is exacerbated by continued water service, provided the District immediately notifies the customer or applicant of the reasons for the discontinuance or refusal and the corrective action that applicant or customer must take before service can be restored. (T) (T)

I. Non-payment of bills for sewer service if the District is providing both water and sewer service at the customer's location. (N)

J. Failure to comply with the District's rules and regulation regarding water service. (N)

K. Failure to comply with the District's rules and regulations regarding sewer service if the District is providing both water and sewer service at the customer's location. (N)

CANCELLED

March 22, 2023

KENTUCKY PUBLIC SERVICE COMMISSION

DATE OF ISSUE August 9, 2019
MONTH / DATE / YEAR

DATE EFFECTIVE August 29, 2019
MONTH / DATE / YEAR

ISSUED BY /s/Randy Kidd
SIGNATURE OF OFFICER

TITLE Chairman

BY AUTHORITY OF ORDER OF THE PUBLIC SERVICE COMMISSION
IN CASE NO. _____ DATED _____

KENTUCKY PUBLIC SERVICE COMMISSION

Gwen R. Pinson
Executive Director
Gwen R. Pinson

EFFECTIVE
8/29/2019
PURSUANT TO 807 KAR 5:011 SECTION 9 (1)

FOR ALL TERRITORY SERVED

PSC KY NO. 3

SHEET NO. 9

McCREARY COUNTY WATER DISTRICT
(NAME OF UTILITY)

CANCELLING PSC KY NO. 2

SHEET NO. 9

RULES & REGULATIONS

10. Billing

Bills and notices relating to the conduct of business of the District will be mailed to the customer at the address listed on the user's agreement unless a change of address has been filed in writing with the District; and the District shall not otherwise be responsible for delivery of any bill or notice nor will the customer be excused from payment of any bill or any performance required in said notice.

Bills for the water services are due and payable at the office of the District, or to any designated agent, on the date of issue. For nonpayment of charges incurred for utility services. The utility may terminate service only after five (5) days written notice of termination is provided, and after twenty (20) days have elapsed since the mailing date of the original unpaid bill. However, if, prior to discontinuance of service, there is delivered to the District or its employee empowered to discontinue service, a written certificate signed by a physician, a registered nurse, or a public health officer that, in the opinion of the certifier, discontinuance of service will aggravate an existing illness or infirmity of the affected premises, service shall not be discontinued until the affected resident can make other living arrangements or until thirty (30) days elapse from the time of the District's receipt of said certification, whichever occurs first.

11. Discontinuance of service by customer

Any customer having fulfilled their contract terms and desiring to discontinue the water service to his premises

CANCELLED
March 22, 2023
**KENTUCKY PUBLIC
SERVICE COMMISSION**

DATE OF ISSUE _____

MONTH/DATE/YEAR

DATE EFFECTIVE _____

11 / 1 / 11

MONTH/DATE/YEAR

ISSUED BY _____

Raymond Jackson
SIGNATURE OF OFFICER

TITLE _____

Chairman

BY AUTHORITY OF ORDER OF THE PUBLIC SERVICE COMMISSION

IN CASE NO. _____

DATED _____

**KENTUCKY
PUBLIC SERVICE COMMISSION**
**JEFF R. DEROUEN
EXECUTIVE DIRECTOR**
TARIFF BRANCH
Brent Kirtley
EFFECTIVE
11/1/2011
PURSUANT TO 807 KAR 5:011 SECTION 9 (1)

AREA McCreary County, Kentucky

PSC KY NO. 1

2nd Revised SHEET NO. 10

McCreary County Water District

CANCELLING PSC KY NO. 1

First Revised SHEET NO. 10

RULES AND REGULATIONS

for any reason must give notice of discontinuance in writing at the business office of the DISTRICT at least three (3) days prior to the date on which the customer desires to disconnect service. If such notice in writing is not given, a customer shall remain liable for all water used and service rendered to such premises by the DISTRICT until such notice is received by the DISTRICT.

12. Reconnection Fee

Where the water supply has been turned off because of customer request or has been discontinued for non-payment of delinquent bills, a charge of \$12.50 will be made for reconnection of water service, but the reconnection will not be made until all delinquent bills and other charges, if any, owed by the customer to the district have been paid. (R)



DATE OF ISSUE August 2, 2022
MONTH / DATE / YEAR
DATE EFFECTIVE July 27, 2022
MONTH / DATE / YEAR
ISSUED BY /s/Randy Kidd
SIGNATURE OF OFFICER
TITLE Chairman

BY AUTHORITY OF ORDER OF THE PUBLIC SERVICE COMMISSION IN CASE NO. 2021-00301 DATED July 27, 2022



CANCELLED

March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

P.S.C. Ky. No. 2

Original Sheet No. 11

Cancelling P.S.C. Ky. No.

Sheet No.

RULES AND REGULATIONS

14. Adjustment Relative to Erroneous Meter

If a meter is inaccurate in excess of +2%, whether upon periodic testing or upon requested testing, additional tests shall be made at once to determine the average error of the meter, and the adjustments shall be made in the customer's water bills as follows:


A. If the result of such tests shows an average error greater than 2% fast, the customer's bill for the period during which the meter error is known to have existed, shall be recomputed and the account adjusted on the basis of the test. If the period during which the meter error existed cannot be determined, then the customer's bill shall be recomputed for one-half (1/2) of the elapsed time since the last previous test, but in no event to exceed 12 months; provided, however, that if time for the periodic test has overrun to the extent that 1/2 of the time elapsed since the last previous test exceeds 12 months, the refund shall be for the 12 months specified above, plus those months exceeding the periodic test period, provided, further, that such refund may be limited to the 12 month period if failure to make the periodic test was due to causes beyond the control of the DISTRICT.


B. If the result of such tests shows an average error greater than 2% slow, the customer's bill for the period during which the meter error is known to have existed, shall be recomputed and the account adjusted on the basis of the test. If the period during which

Date of Issue: September 10, 1987

PUBLIC SERVICE COMMISSION
BY KENTUCKY
EFFECTIVE
APR 01 1987

ISSUED BY: McCreary County Water District, P.O. Box 488,
Whitley City, Kentucky 42653


R.D. Bryant, Chairman

PURSUANT TO 807 KAR 5:011,
SECTION 9 (1)
BY: 
PUBLIC SERVICE COMMISSION MANAGER

CANCELLED

March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

RULES AND REGULATIONS

the meter error existed cannot be determined, then the customer's bill shall be recomputed for one-half (1/2) of the elapsed time since the last previous test, but in no event to exceed 12 months.

- C. If the result of such tests necessitates making a refund or back billing a customer, the customer shall be notified in writing of the percentage of error, fast or slow, the date(s) of testing, and the amount of charge or credit to be shown on the next bill of the customer.

15. Meters

All meters shall be installed, renewed, and maintained at the expense of the DISTRICT, and the DISTRICT reserves the right to approve the size and type of meter used.

It shall be the policy of the DISTRICT to test each water meter pursuant to Public Service Commission Regulation 807 KAR 5:066. Section 15. In addition, upon written request of any customer, the meter servicing such customer shall be tested by the DISTRICT, pursuant to Public Service Commission Regulation 807 KAR 5:006, Section 20.

16. Failure of Water Meter


Where a meter is found to be in error, the customer's bill will be adjusted in accordance with Public Service Commission Regulation 807 KAR 5:006, Section 9. Where a meter has ceased to register, the District will estimate


Date of Issue: September 10, 1987

PUBLIC SERVICE COMMISSION
OF KENTUCKY
Date Effective: April 1, 1987
EFFECTIVE

ISSUED BY: McCreary County Water District, P.O. Box 488,
Whitley City, Kentucky 42653

APR 01 1987


R.D. Bryant, Chairman

PURSUANT TO 807 KAR 5:011,
SECTION 9(1)
BY: 
PUBLIC SERVICE COMMISSION MANAGER



RULES AND REGULATIONS

the monthly bill of the customer for the month that the meter is replaced. The estimated bill will be based upon the previous six months' usage.

17. Right of Access

The customer must agree to permit the DISTRICT to lay, maintain, repair, or remove such water lines which is the property of the DISTRICT located on the customer's property with the right of ingress-and egress over customer's property. The DISTRICT'S duly authorized representative and/or other duly authorized employee of the State Health Department bearing proper credentials and identification shall be permitted to enter upon all properties for the purpose of inspection, observation, measurement, sampling, and testing, in accordance with the provisions of these Rules and Regulations.

18. Interruption of Service

The DISTRICT will use reasonable diligence in supplying water service, but shall not be liable for breach of contract in the event of, or for loss, injury, or damage to persons or property resulting from interruptions in service, excessive or inadequate water pressure, or otherwise unsatisfactory service, whether or not caused by negligence. The DISTRICT does hereby explicitly state that its system is one for rural domestic consumption and that its allowance of connections to its system for fire protection whether by design or implication is only for such benefit as said customer may be able to derive from such connection.


PUBLIC SERVICE COMMISSION
OF KENTUCKY
APR 11 1987


Date of Issue: September 10, 1987

Date Effective: ~~Effective~~, 1987

ISSUED BY: McCreary County Water District, P.O. Box 488,
Whitley City, Kentucky 42653

APR 01 1987


R.D. Bryant, Chairman

PURSUANT TO 807 KAR 5:011,
SECTION 9 (1)
BY: 
PUBLIC SERVICE COMMISSION MANAGER

CANCELLED

March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

P.S.C. Ky. No. 2

Original Sheet No. 14

Cancelling P.S.C. Ky. No.

Sheet No.

RULES AND REGULATIONS

The DISTRICT'S system is not designed nor intended for use for fire protection in any manner whatsoever. Any customer using same for fire protection does so at their own full and sole responsibility.

The DISTRICT shall in no event be held responsible for any claim made against it by reason of the breaking of any mains or service pipes or by reason of any other interruption of the supply of water caused by the failure of machinery or stoppage for necessary repairs. No person shall be entitled to damages nor for any portion of a payment refunded for any interruption of service which in the opinion of the DISTRICT may be deemed necessary.

The DISTRICT shall made all reasonable efforts to eliminate interruption of service and when such interruption occur will endeavor to reestablish service with the shortest possible delay. When the service is interrupted all consumers affected by such interruption will be notified in advance whenever it is possible to do so.


19. Boilers and/or Pressure Vessels

Customers having boilers and/or pressure vessels receiving a supply of water from the DISTRICT must have a check valve on the water supply line and a vacuum valve on the stream line to prevent collapse in case the water supply from the DISTRICT is discontinued or interrupted for any reason, with or without notice. It is the


PUBLIC SERVICE COMMISSION

Date of Issue: September 10, 1987 Date Effective: **APR 1, 1987**

ISSUED BY: McCreary County Water District, P.O. Box 488,
Whitley City, Kentucky 42653


R.D. Bryant, Chairman

PURSUANT TO 207 KAR 5:011,
SECTION 9(1)

BY: 
PUBLIC SERVICE COMMISSION MANAGER

CANCELLED

March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

P.S.C. Ky. No. 2

Original Sheet No. 15

Cancelling P.S.C. Ky. No.

Sheet No.

RULES AND REGULATIONS

responsibility of the customer to make provisions for protection of his equipment in case of interrupted or intermittent service.

20. Backflow Preventors

Special services and fire connection shall have backflow preventors of a type approved by the DISTRICT, installed at the cost of prospective customer.

21. Cross-Connection

Kentucky Department of Health, Kentucky Public Service Commission and these rules and regulations do hereby explicitly state that cross-connection of the DISTRICT'S system with any other source is hereby prohibited.

22. Relocation of Water Facility

The DISTRICT may, at the request of a customer or other person relocate, change or modify existing DISTRICT owned equipment, mains or appurtenances. Same shall reimburse DISTRICT for such changes at actual cost including appropriate legal, administrative, engineering and overhead cost.

23. Damage to DISTRICT'S Water System

No person shall maliciously, willfully, or negligently break, damage, destroy, uncover, deface, or tamper with any structure appurtenance, or equipment which is a part of the DISTRICT'S water works. Any person violating this

Date of Issue: September 10, 1987 Date Effective: April 1, 1987
PUBLIC SERVICE COMMISSION OF KENTUCKY

ISSUED BY: McCreary County Water District, P.O. Box 488,
Whitley City, Kentucky 42653 APR 01 1987

R.D. Bryant
R.D. Bryant, Chairman

PURSUANT TO KAR 5:011,
SECTION 9(1)
BY: *Steve Keller*
PUBLIC SERVICE COMMISSION MANAGER

CANCELLED

March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

P.S.C. Ky. No. 2

Original Sheet No. 16

Cancelling P.S.C. Ky. No.

Sheet No.

RULES AND REGULATIONS

provision shall be subject to immediate arrest and/or discontinuation of water service and shall pay the cost of repairing or replacing the pipe or appurtenance.

Any person, firm or organization working around or near DISTRICT'S distribution mains or appurtenances may request the DISTRICT to indicate location of same. However, indication by DISTRICT of same does not relieve such person of complete responsibility and liability for any and all damages, liability and loss resulting from any act of such person or his assigns and/or agent.

24. Additional Load

The service connection supplied by the DISTRICT for each customer has a definite capacity, and no addition to the equipment or load connected thereto will be allowed except by consent of the DISTRICT. Failure to give notice of additions or changes in load, and to obtain the DISTRICT'S consent for same, shall render the customer liable for any damage to any of the DISTRICT'S lines or equipment caused by the additional or changed installation.


25. Notice of Trouble


The customer shall notify the DISTRICT immediately should the service be unsatisfactory for any reason, or should there be any defects, trouble or accidents affecting the supply of water.

Date of Issue: September 10, 1987 Date Effective: **PUBLIC SERVICE COMMISSION OF KENTUCKY** APR 01 1987
EFFECTIVE

ISSUED BY: McCreary County Water District, P.O. Box 488,
Whitley City, Kentucky 42653

APR 01 1987


R.D. Bryant, Chairman

PURSUANT TO 197 KAR 5:011,
SECTION 9(1),
BY: 
PUBLIC SERVICE COMMISSION MANAGER

CANCELLED

March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

FOR ALL TERRITORY SERVED

PSC KY NO. 3

SHEET NO. 17

McCREARY COUNTY WATER DISTRICT
(NAME OF UTILITY)

CANCELLING PSC KY NO. 2

SHEET NO. 17

RULES & REGULATIONS

26. Distribution Extensions

Any person desiring an extension to DISTRICT'S system shall request in writing, in a form approved by DISTRICT, for such extension. Any requested extension may be provided under one of the following options.

OPTION I - DISTRICT shall construct such extension under authority and procedure as stipulated in Public Service Commission Regulation 807 KAR 5:066, Section 11. Any extension made under this option shall be subject to refund as outlined in said regulation.

OPTION II - Applicant may construct and donate to DISTRICT, the extension, as a contribution in aid of construction, meeting all DISTRICT'S specifications and approval. DISTRICT reserves right to stipulate applicable engineering, legal and administrative factors. Applicant shall pay all cost of DISTRICT as a contribution in aid of construction. Any extension made under this option shall not be eligible for refund.

The applicant or group of applicants shall have the right to elect the option by which said extension shall be made. In either case applicant must execute a contract and agreement for line extension of form approved by DISTRICT.

Extendor applicant is hereby notified that regardless of option selected all other rules, rates and schedules of fees applicable to size and type of service requested shall be paid in addition to cost of extension.

DATE OF ISSUE _____ MONTH / DATE / YEAR
DATE EFFECTIVE 11/1/11 MONTH / DATE / YEAR
ISSUED BY Raymond Jorgensen SIGNATURE OF OFFICER
TITLE Chairman
BY AUTHORITY OF ORDER OF THE PUBLIC SERVICE COMMISSION
IN CASE NO. _____ DATED _____

**KENTUCKY
PUBLIC SERVICE COMMISSION**
**JEFF R. DEROUEN
EXECUTIVE DIRECTOR**
TARIFF BRANCH
Brent Kirtley
EFFECTIVE
11/1/2011
PURSUANT TO 807 KAR 5:011 SECTION 9 (1)

CANCELLED

March 22, 2023

RULES AND REGULATIONS

KENTUCKY PUBLIC SERVICE COMMISSION

OPTION III-

THE DISTRICTS SHALL DETERMINE THE TOTAL COST OF THE PROPOSED WATER MAIN EXTENSION (EXCLUSIVE OF THE METER CONNECTIONS) AND THE TOTAL LENGTH OF THE EXTENSION. THE DISTRICTS SHALL PAY THE PORTION OF THE COST OF THE WATER MAIN EXTENSION EQUAL TO 50 FEET FOR EACH APPLICANT FOR SERVICE. THAT PART OF THE COST NOT COVERED BY THE DISTRICT'S PORTION SHALL BE CONTRIBUTED EQUALLY BY THOSE APPLICANTS DESIRING SERVICE ON THE MAIN EXTENSION. EACH APPLICANT WILL ALSO BE REQUIRED TO PAY THE DISTRICT'S APPROVED "TAP-ON-FEE" FOR A METER CONNECTION TO THE MAIN EXTENSION.

FOR A PERIOD OF FIVE YEARS AFTER THE ORIGINAL CONSTRUCTION OF THE MAIN EXTENSION EACH ADDITIONAL CUSTOMER DIRECTLY CONNECTED TO EACH PARTICULAR EXTENSION WILL BE REQUIRED TO CONTRIBUTE TO THE COST OF THAT WATER MAIN EXTENSION BASED ON A RECOMPUTATION OF BOTH THE DISTRICT'S PORTION OF THE TOTAL COST AND EACH CUSTOMER'S CONTRIBUTION AS SET OUT ABOVE. THE DISTRICT MUST REFUND TO THOSE CUSTOMERS THAT HAVE PREVIOUSLY CONTRIBUTED TO THE COST OF EACH MAIN EXTENSION ITSELF THAT AMOUNT NECESSARY TO REDUCE THEIR CONTRIBUTION TO THE CURRENTLY CALCULATED AMOUNT FOR EACH CUSTOMER CONNECTED TO THAT EXTENSION. ALL CUSTOMER DIRECTLY CONNECTED TO EACH MAIN EXTENSION FOR A FIVE-YEAR PERIOD AFTER IT IS PLACED IN SERVICE ARE TO CONTRIBUTE EQUALLY TO COST OF CONSTRUCTION OF THE WATER MAIN EXTENSION ITSELF. IN ADDITION EACH CUSTOMER MUST PAY THE APPROVED "TAP-ON-FEE" APPLICABLE AT THE TIME OF THEIR APPLICATION FOR THE METER CONNECTION. THE "TAP-ON-FEE" IS NOT PART OF THE REFUNDABLE COST OF THE EXTENSION AND MAY BE CHANGED DURING THE REFUND PERIOD. AFTER THE FIVE-YEAR REFUND PERIOD EXPIRES, ANY ADDITIONAL CUSTOMER APPLYING FOR SERVICE ON EACH MAIN EXTENSION MUST BE CONNECTED FOR THE AMOUNT OF THE APPROVED "TAP-ON-FEE" ONLY. ALSO, AFTER THE FIVE-YEAR REFUND PERIOD EXPIRES, THE DISTRICT WILL BE REQUIRED TO MAKE REFUNDS FOR AN ADDITIONAL FIVE-YEAR PERIOD IN ACCORDANCE WITH 807 KAR 5:066 SECTION 12(b).

Date Issued: August 28, 1991

Date Effective: Sept 28, 1991

ISSUED BY: McCreary County Water District, P.O. Box 228, Whitley City, Kentucky 42653

PUBLIC SERVICE COMMISSION OF KENTUCKY EFFECTIVE

Raymond Taylor
Raymond Taylor, Chairman

SEP 28 1991

PURSUANT TO 807 KAR 5:011, SECTION 9 (1)

BY: Chapman
PUBLIC SERVICE COMMISSION MANAGER

AREA McCreary County, Kentucky

PSC KY NO. 1

1st Revised SHEET NO. 18

McCreary County Water District

CANCELLING PSC KY NO. 1

Original SHEET NO. 18

RULES AND REGULATIONS

27. Complaints

Complaints may be made to the operator of the system whose decision may be appealed to the District Commissioners. Such appeal shall be in writing within ten (10) days of date of decision by operator, stating the nature of the complaint and supporting evidence. Decisions by the District's Commissioners or operation may be brought before the Public Service Commission in accordance to current PSC Rules & Regulations.

28. Sale of water

Water furnished by the District may be used for domestic consumption by the customer's household or business, subject to special service agreements. The customer shall not sell, donate, give or allow use of such water to any authorized or unauthorized party.

29. Special charges

- A. A charge of \$8.50 will be made for each check returned to the District by the bank. (R)
- B. A charge of \$12.50 will be made to reread a meter at the customer's request unless such reread reveals that the initial reading was erroneous. No charge shall be made if the initial reading was erroneous. (R)



DATE OF ISSUE August 2, 2022

MONTH / DATE / YEAR

DATE EFFECTIVE July 27, 2022

MONTH / DATE / YEAR

ISSUED BY /s/Randy Kidd

SIGNATURE OF OFFICER

TITLE Chairman

BY AUTHORITY OF ORDER OF THE PUBLIC SERVICE COMMISSION IN CASE NO. 2021-00301 DATED July 27, 2022



AREA McCreary County, Kentucky

PSC KY NO. 1

1st Revised SHEET NO. 19

McCreary County Water District

CANCELLING PSC KY NO. 1

Original SHEET NO. 19

RULES AND REGULATIONS

C. A charge of \$12.50 will be made for a meter retest when such test is made at the customer's request unless the meter is found to be faulty. No charge shall be made for a faulty meter, but appropriate adjustments shall be made in accordance with Section 14 of these rules and regulations. (R)

30. Special User Agreements for Nonstandard Service

Each prospective customer requesting a nonstandard service shall execute to the DISTRICT an agreement for special service. The standard forms for Agreement for Special Services are as follows:

Agreement for Special Service, Nonstandard Size Meter

Agreement for Multi-Family Development, Master Meter

Agreement for Multi-Family Development, Units with Individual Meters

Agreement for Mobile Home Park Service, Master Meter

Agreement for Mobile Home Park Service, Sites with Individual Meters

Agreement for Special Service, Sprinkler System and Fire Service Connection



DATE OF ISSUE August 2, 2022

MONTH / DATE / YEAR

DATE EFFECTIVE July 27, 2022

MONTH / DATE / YEAR

ISSUED BY /s/Randy Kidd

SIGNATURE OF OFFICER

TITLE Chairman

BY AUTHORITY OF ORDER OF THE PUBLIC SERVICE COMMISSION IN CASE NO. 2021-00301 DATED July 27, 2022



McCreary County Water District

For: All of McCreary County

P.S.C. Ky. No. 2

Original Sheet No. 20

Cancelling P.S.C. Ky. No.

Sheet No.

RULES AND REGULATIONS

For special service not applicable to above categories the DISTRICT may, upon consent of Applicant and DISTRICT, formulate and execute a contractual agreement specifically applicable to said special service need.

CANCELLED


March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

Date of Issue: April 1, 1987

Date Effective: ~~April 1, 1987~~ **APR 01 1987**

ISSUED BY: McCreary County Water District, P.O. Box 488,
Whitley City, Kentucky 42653


R.D. Bryant, Chairman

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

PURSUANT TO KRS 5:011,
SECTION 9 (1)
BY: 
PUBLIC SERVICE COMMISSION MANAGER

CANCELLED

March 22, 2023

McCreary County Water District

KENTUCKY PUBLIC SERVICE COMMISSION

AREA McCreary County, Kentucky

PSC KY NO. 1

Original SHEET NO. 21

CANCELLING PSC KY NO. _____

_____ SHEET NO. _____

RULES AND REGULATIONS

CROSS-CONNECTIONS

For purposes of this section

“Auxiliary Water Supply” means any water supply on or available to the premises other than the Water District’s public water supply. These auxiliary waters may include water from any natural source such as a well, spring, river, stream, or body of water or any water or other substance of unknown or questionable quality that may present a health or system hazard to the potable public water supply.

“Backflow” means the reversal of the normal flow of water caused by either back pressure or back siphonage.

“Backflow Prevention Assembly” means an assembly or means designed to prevent backflow. A listing of acceptable backflow prevention assemblies and degree of hazard is available in the Kentucky State Plumbing Law, Regulations and Code.

“Contamination” means an impairment of the quality of the potable water supply by any waste product, fluid, substance, compound or other material to a degree which creates an actual or potential hazard to the public health through poisoning or through the spread of disease.

“Cross Connection” means any physical connection or arrangement of piping or fixtures between two otherwise separate piping systems one of which contains potable water and the other non-potable water or substance of questionable quality, through which, or because of which, backflow may occur into the potable water system.

“Non-residential building” means any building not used for habitation.

“Residential Building” means any building used for habitation.

“Thermal Expansion Tank” means a device installed on the cold water supply line near a water heater to compensate for the expansion of water within a water system when such water is heated.

↑
(N)
↓

DATE OF ISSUE August 9, 2019
MONTH / DATE / YEAR

DATE EFFECTIVE August 29, 2019
MONTH / DATE / YEAR


ISSUED BY /s/Randy Kidd
SIGNATURE OF OFFICER

TITLE Chairman

BY AUTHORITY OF ORDER OF THE PUBLIC SERVICE COMMISSION IN CASE NO. _____ DATED _____

KENTUCKY PUBLIC SERVICE COMMISSION

Gwen R. Pinson
Executive Director



EFFECTIVE
8/29/2019
PURSUANT TO 807 KAR 5:011 SECTION 9 (1)

CANCELLED

March 22, 2023

McCreary County / Water District

**KENTUCKY PUBLIC
SERVICE COMMISSION**

AREA McCreary County, Kentucky

PSC KY NO. 1

Original SHEET NO. 22

CANCELLING PSC KY NO. _____


_____ SHEET NO. _____

RULES AND REGULATIONS

No water service connection shall be made or installed to any residential building unless such service connection is protected by a backflow prevention assembly. Residential service connections shall be considered as low hazard applications and all such connections shall have at a minimum a dual check valve backflow preventer installed between the water meter and the residence. The District may require additional or alternate backflow prevention assemblies if the degree of hazard constitutes a higher level of protection for the public water system.

No water service or supply connection shall be installed or permitted to be installed to any non-residential facility unless the water service connection is protected by a backflow prevention assembly. The type of protection device required shall be determined at the time of installation of the service and shall be commensurate with the degree of hazard at the point of such service connection. At a minimum, the service connection shall be installed with a dual check valve backflow preventer. In the event the purpose or use of a non-residential facility changes and the new purpose or change creates a higher degree of hazard, then customer receiving service at the non-residential facility shall replace the backflow prevention with an assembly that provides acceptable protection.

All water service connections that are in existence as of the effective date of this regulation and lack the minimum backflow prevention assemblies required by this regulation shall become compliant with this regulation's requirements within a reasonable period after the property owner has received notice of the service connection's non-compliance. If the Water District determines that a hazard to health exists, then a backflow prevention assembly meeting the requirements of this regulation may be installed on an existing service connection. Backflow prevention assemblies shall not be installed on existing service connections until after the property owner has been informed of the actual and potential hazards that may be created as a result of such backflow assembly installation. Notices provided to such property owners shall include the following: "When cross connection control devices are properly installed, they create a closed water system. A properly sized thermal expansion tank shall be installed in the cold water supply located as near the water heater as possible."



DATE OF ISSUE August 9, 2019
MONTH / DATE / YEAR

DATE EFFECTIVE August 29, 2019
MONTH / DATE / YEAR


ISSUED BY /s/Randy Kidd
SIGNATURE OF OFFICER

TITLE Chairman

BY AUTHORITY OF ORDER OF THE PUBLIC SERVICE
COMMISSION IN CASE NO. _____ DATED _____

**KENTUCKY
PUBLIC SERVICE COMMISSION**

Gwen R. Pinson
Executive Director



EFFECTIVE
8/29/2019
PURSUANT TO 807 KAR 5:011 SECTION 9 (1)

AREA McCreary County, Kentucky

PSC KY NO. 1

Original SHEET NO. 23

McCreary County Water District

CANCELLING PSC KY NO. _____

_____ SHEET NO. _____

RULES AND REGULATIONS

A customer shall make its water system open for inspection at all reasonable times to authorized representatives of the Water District to determine whether cross connections or other structural or sanitary hazards, including violation of this rule, exist. If the Water District discovers or learns of such condition, it may deny or immediately discontinue service to the facility by providing a physical break in the service line until the customer has corrected the condition in conformance with state and local laws and regulations. Water service to any facility shall be discontinued if the backflow prevention assembly required by this regulation has been removed, bypassed, or if any unprotected cross connection exists on the premises and will not be restored until such conditions or defects are corrected.

The cross-connection of the Water District's system with any auxiliary water supply is prohibited.

↑
N
↓
T

CANCELLED

March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

DATE OF ISSUE August 9, 2019
MONTH / DATE / YEAR
DATE EFFECTIVE August 29, 2019
MONTH / DATE / YEAR
ISSUED BY /s/Randy Kidd
SIGNATURE OF OFFICER
TITLE Chairman
BY AUTHORITY OF ORDER OF THE PUBLIC SERVICE
COMMISSION IN CASE NO. _____ DATED _____

**KENTUCKY
PUBLIC SERVICE COMMISSION**

Gwen R. Pinson
Executive Director
Gwen R. Pinson

EFFECTIVE
8/29/2019
PURSUANT TO 807 KAR 5:011 SECTION 9 (1)

McCreary County Water District

For: ALL OF MCCREARY COUNTY

P.S.C. Ky. No. 2

Original Sheet No. _____

Cancelling P.S.C. Ky. _____

CANCELLED

March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

RULES AND REGULATIONS

MONITORING OF CUSTOMER USAGE

AT LEAST ONCE ANNUALLY THE COMPANY WILL MONITOR THE USAGE OF EACH CUSTOMER ACCORDING TO THE FOLLOWING PROCEDURE:

1. THE CUSTOMER'S ANNUAL USAGE FOR THE MOST RECENT 12-MONTH PERIOD WILL BE COMPARED WITH THE ANNUAL USAGE FOR THE 12 MONTHS IMMEDIATELY PRECEDING THAT PERIOD.
2. IF THE ANNUAL USAGE FOR THE TWO PERIODS ARE SUBSTANTIALLY THE SAME OR IF ANY DIFFERENCE IS KNOWN TO BE ATTRIBUTED TO UNIQUE CIRCUMSTANCES, SUCH AS UNUSUAL WEATHER CONDITIONS, COMMON TO ALL CUSTOMER, NO FURTHER REVIEW WILL BE DONE.
3. IF THE ANNUAL USAGES DIFFER BY 100 PERCENT OR MORE AND 10,000 GALS AND CANNOT BE ATTRIBUTED TO A READILY IDENTIFIED COMMON CAUSE, THE COMPANY WILL COMPARE THE CUSTOMER'S MONTHLY USAGE RECORDS FOR THE 12-MONTH PERIOD WITH THE MONTHLY FOR THE SAME MONTHS OF THE PRECEDING YEAR.
4. IF THE CAUSE FOR THE USAGE DEVIATION CANNOT BE DETERMINED FROM ANALYSIS OF THE CUSTOMER'S METER READING AND BILLING RECORDS, THE COMPANY WILL CONTACT THE CUSTOMER BY TELEPHONE OR IN WRITING TO DETERMINE WHETHER THERE HAVE BEEN CHANGES SUCH AS DIFFERENT NUMBER OF HOUSEHOLD MEMBERS OR WORK STAFF, ADDITIONAL OR DIFFERENT APPLIANCES, CHANGES IN BUSINESS VOLUME, OR KNOWN LEAKS IN THE CUSTOMER'S SERVICE LINE.
5. WHERE THE DEVIATION IS NOT OTHERWISE EXPLAINED, THE COMPANY WILL TEST THE CUSTOMER'S METER TO DETERMINE WHETHER IT SHOWS AN AVERAGE ERROR GREATER THAN 2 PERCENT FAST OR SLOW.

Date Issued: June 10, 1992

Date Effective: July 1, 1992

ISSUED BY: McCreary County Water District, P.O. Box 188,
Whitley City, Kentucky 42653

Raymond Taylor
Raymond Taylor, Chairman

PUBLIC SERVICE COMMISSION
OF KENTUCKY

AUG 1 1992

PURSUANT TO 807 KAR 5.011.
SECTION 9 (1)

BY: *Sharon Deller*
PUBLIC SERVICE COMMISSION MANAGER

McCreary County Water District

For: ALL OF MCCREARY COUNTY

P.S.C. Ky. No. 2

Original Sheet No. _____

Cancelling P.S.C. Ky. _____

RULES AND REGULATIONS

- 6. THE COMPANY WILL NOTIFY THE CUSTOMERS OF THE INVESTIGATION, ITS FINDINGS, AND ANY REFUNDS OR BACKBILLING IN ACCORDANCE WITH 807 KAR 5:006, SECTION 10(4) AND (5).

IN ADDITION TO THE ANNUAL MONITORING THE COMPANY WILL IMMEDIATELY INVESTIGATION USAGE DEVIATIONS BROUGHT TO ITS ATTENTION AS A RESULT OF ITS ON-GOING METER READING OR BILLING PROCESSES OR CUSTOMER INQUIRY.

CANCELLED

March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

Date Issued: June 10, 1992

PUBLIC SERVICE COMMISSION
Date Effective: July 10, 1992
EFFECTIVE

ISSUED BY: McCreary County Water District, P.O. Box 488,
Whitley City, Kentucky 42653

AUG 1 1992

Raymond Taylor
Raymond Taylor, Chairman

PURSUANT TO 807 KAR 5:011,
SECTION 9 (1)

BY: Cheryl Sallee
PUBLIC SERVICE COMMISSION MANAGER

FOR All Territory Served
Community, Town or City

P.S.C. KY. NO. _____

SHEET NO. 21

McCreary County Water District
(Name of Utility)

CANCELLING P.S.C. KY. NO. _____

SHEET NO. _____

RULES & REGULATIONS

Leak Adjustments. A customer may make a request for a bill adjustment in the event of a leak under the following conditions:

1. The customer must request a leak adjustment in writing to the utility.
2. The customer's bill will be based on two components. The first step will be to calculate the customer's average monthly usage over a 12-month period. The second step will be to deduct the customer's average monthly usage (as calculated in the above) from the total amount of water that passed through the meter. The usage calculated in step one will be billed at the utility's regular rates, while the remaining usage will be charged at 50% discount from the regular rates. All water passing through the meter must be accounted and paid for by the customer. So the customer will owe the amount of his/her average bill plus 1/2 the amount they would normally be billed for that remaining water that passed through the meter.
3. If meter readings are not available for an entire 12-month period, the water bill will be estimated by the utility, subject to an upward or downward adjustment once a 12-month average of actual meter readings can be calculated.
4. Only one (1) leak adjustment will be made for a specific service location during any given 12-month period.
5. Leak adjustments will not be given for wholesale customers.

CANCELLED

March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

DATE OF ISSUE October 24, 2008
Month / Date / Year

DATE EFFECTIVE December 7, 2008
Month / Date / Year

ISSUED BY Raymond A. Taylor
(Signature of Officer)

TITLE Chairman

BY AUTHORITY OF ORDER OF THE PUBLIC SERVICE COMMISSION

IN CASE NO. _____ DATED _____

**PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE
12/7/2008
PURSUANT TO 807 KAR 5:011
SECTION 9 (1)**

By Stephanie Dumb
Executive Director

FOR All Territory Served

PSC KY NO. _____

SHEET NO. 22

McCreary County Water District
(NAME OF UTILITY)

CANCELLING PSC KY NO. _____

SHEET NO. _____

RULES & REGULATIONS

FIRE DEPARTMENTS:

Any city, county, urban-county, charter county, fire protection district, or volunteer fire protection district ("User") may withdraw water from the utility's water distribution system for the purpose of fighting fires or training firefighters at no charge on the condition that it maintains estimates of the amount of water used for fire protection and training during the calendar month and reports the amount of this water usage to the utility no later than the 15th day of the following calendar month.

Any city, county, urban-county, charter county, fire protection district, or volunteer fire protection district that withdraws water from the utility's water distribution system for fire protection or training purposes and fails to submit the required report on water usage in a timely manner shall be assessed the cost of this water.

A non-reporting user's usage shall be presumed to 0.3 percent of the utility's total water sales for the calendar month. A non-reporting user may present evidence of its actual usage to rebut the presumed usage. The utility shall consider this evidence and may adjust the presumed usage amount accordingly.

The non-reporting user shall be billed for this usage at the lowest usage block rate regardless of customer classification that the utility charges.

A non-reporting user shall also be assessed a penalty of \$ 10.00 for each failure to submit a report in a timely manner.

CANCELLED

March 22, 2023

KENTUCKY PUBLIC SERVICE COMMISSION

DATE OF ISSUE _____ MONTH / DATE / YEAR

DATE EFFECTIVE 11/1/11 MONTH / DATE / YEAR

ISSUED BY Raymond Taylor SIGNATURE OF OFFICER

TITLE Chairman

BY AUTHORITY OF ORDER OF THE PUBLIC SERVICE COMMISSION

IN CASE NO. _____ DATED _____

KENTUCKY PUBLIC SERVICE COMMISSION
JEFF R. DEROUEN
EXECUTIVE DIRECTOR

TARIFF BRANCH
Brent Kirtley
EFFECTIVE
11/1/2011
PURSUANT TO 807 KAR 5:011 SECTION 9 (1)

FOR All Territory Served
Community, Town or City

P.S.C. KY. NO. _____

SHEET NO. 23

CANCELLING P.S.C. KY. NO. _____

SHEET NO. _____

McCreary County Water District
(Name of Utility)

CONTENTS



McCREARY COUNTY WATER DISTRICT
P.O. Box 488
Whitby City, KY 42683

MESSAGES

CANCELLED

March 22, 2023

**KENTUCKY PUBLIC
SERVICE COMMISSION**

OFFICE HOURS
MONDAY-FRIDAY
9:00 A.M.-4:30 P.M.
PHONE
(606) 376-2540
CLOSED SATURDAY, SUNDAY AND HOLIDAYS
NIGHT DEPOSITORY BOX LOCATED AT OFFICE

SERVICE TO		TO		ACCOUNT NUMBER	
PREVIOUS READINGS	CURRENT READINGS	CONTRIBUTION	DATE	AMOUNT	
<i>Raymond Taylor</i>					KEEP THIS PORTION OF THE BILL FOR YOUR RECORDS IF YOU ARE MOVING, PLEASE CALL US AT (606) 376-2540 ADDITIONAL INFORMATION IS LISTED ON THE BACK OF THIS BILL
DUE DATE		PAY AFTER DUE DATE		UNPAID BALANCE	

PLEASE MAIL YOUR PAYMENT IN THE ENVELOPE PROVIDED
MAKE CHECKS PAYABLE TO:
McCREARY COUNTY WATER DISTRICT
P.O. Box 488
Whitby City, KY 42683

ACCOUNT ENCLOSED
\$

ACCOUNT NUMBER	DUE DATE	PAY AFTER DUE DATE	UNPAID BALANCE
DO NOT WRITE BELOW THIS LINE UNLESS THE COMPANY WILL PAY THE BILL ENCLOSED			

DO NOT WRITE IN THE AREA BELOW

DATE OF ISSUE _____

DATE EFFECTIVE 11/1/11
MONTH / DATE / YEAR

ISSUED BY Raymond Taylor
SIGNATURE OF OFFICER

TITLE Chairman

BY AUTHORITY OF ORDER OF THE PUBLIC SERVICE COMMISSION

IN CASE NO. _____ DATED _____

**KENTUCKY
PUBLIC SERVICE COMMISSION**

**JEFF R. DEROUEN
EXECUTIVE DIRECTOR**

TARIFF BRANCH

Brent Kirtley

EFFECTIVE
11/1/2011
PURSUANT TO 807 KAR 5:011 SECTION 9 (1)