

SOUTH KENTUCKY RECC
SOMERSET, KENTUCKY 42501

APPENDIX A OF P.S.C. KENTUCKY NO. 5

A Subdivision of which 113 lots are served Underground.

The line designed at 7.2 KV Primary voltage, using loop feed.

Underground Cost per Foot	\$8.38
Overhead Cost per Foot	<u>2.50</u>
Average Cost Differential	<u><u>\$5.88</u></u>

Underground Cost Computation

	<u>Footage</u>	<u>Material</u>	<u>Estimated: Trench, Sand Backfill, Backhoe</u>	<u>Initial Labor & Overhead</u>	<u>Total Cost</u>
Job Totals	33,518	\$94,021.24	\$69,294.93	\$117,773.99	\$281,090.16
Cost Per Foot		\$ 2.80	\$ 2.07	\$ 3.51	\$ 8.38

TYPICAL ROCK CLAUSE: An additional \$47.67 per linear trench foot shall be charged where extreme rock conditions are encountered, such conditions being defined as limestone or other hard stratified material in a continuous volume of at least one cubic yard or more which cannot be removed using ordinary excavation equipment.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

FEB 1 1984

PURSUANT TO 307 KAR 5:011,
SECTION 9 (1)

BY: *Jordan Chel*

DATE OF ISSUE JANUARY 30 1984 DATE EFFECTIVE FEBRUARY 1 1984
Month Day Year Month Day Year

ISSUED BY *J. Keith Sloan* Manager, P.O. Box 901 Somerset, KY 42501
Name of Officer Title Address

C5-85